

JOB # 3

CITY OF GRAND FORKS
NORTH DAKOTA

TEU-6-986(113)117
City Project #7077

Grand Forks County
Granitoid Pavement Preservation
Cottonwood St from 2nd to 3rd Ave S


3rd Ave S from 250' West of Cottonwood St to Cottonwood St
2nd Ave S from the Alley East of Cottonwood St to Chestnut St
8in Concrete Repair-Full Depth Doweled, Random PCC Crack Cleaning & Sealing

STATE	PROJECT NO.	PCN	SECTION NO.	SHEET NO.
ND	TEU-6-986(113)117	20389	1	1

GOVERNING SPECIFICATIONS:

2014 Standard Specifications adopted by the North Dakota Department of Transportation and the Supplemental Specifications effective on the date the project is advertised.

PROJECT NUMBER \ DESCRIPTION	NET MILES	GROSS MILES
TEU-6-986(113)117 Granitoid Pavement Preservation	0.22	0.30




 City of Grand Forks
 Engineering Department

DESIGNERS
David Kuharenko

I hereby certify that the attached plans were prepared by me or under my direct supervision and that I am a duly registered professional engineer under the laws of the state of ND.

APPROVED DATE 08/01/2014

David J. Kuharenko
Sr. Civil Engineer, City of Grand Forks, ND

This document was originally issued and sealed by David J. Kuharenko Registration Number PE-8411 on 08/01/2014. The original document is stored at the City of Grand Forks Engineering Department.

STATE	PROJECT NO.	PCN	SECTION NO.	SHEET NO.
ND	TEU-6-986(113)117	20389	2	1

TABLE OF CONTENTS


<u>Section No.</u>	<u>Sheet No.</u>	<u>Description</u>
1	1	Title Sheet
2	1	Table of Contents
4	1	Scope of Work
6	1-2	Notes
8	1	Quantities
20	1-2	General Details
75	1	Erosion Control
80	1-2	Repair Locations
100	1-2	Work Zone Traffic Control

LIST OF STANDARD DRAWINGS

<u>Standard No.</u>	<u>Description</u>
D-20-1,2,3	NDDOT Approved Abberviations
D-20-10	NDDOT Utility Co Approved Abbreviations
D-20-20,21	Linestyles
D-20-30,31,32	Symbols
D-704-7,8	Breakaway Systems for Construction Zone Signing
D-704-9,10,11	Construction Sign Detail
D-704-13	Barricade Details and Channelizing Devices
D-704-14	Construction Sign Punching and Mounting Details
D-704-23	Short Term Urban Detour and Lane Closures on a Divided Highway Layout

This document was originally issued and sealed by David J. Kuharenko Registration Number PE-8411 on 08/01/2014. The original document is stored at the City of Grand Forks Engineering Department.

STATE	PROJECT NO.	PCN	SECTION NO.	SHEET NO.
ND	TEU-6-986(113)117	20389	4	1



START PROJECT
TEU-6-986(113)117
STA 2+49

END PROJECT
TEU-6-986(113)117
STA 15+60



This document was originally issued and sealed by David J. Kuharenko Registration Number PE-8411 on 08/01/2014. The original document is stored at the City of Grand Forks Engineering Department.

Scope of Work

NOTES

STATE	PROJECT NO.	PCN	SECTION NO.	SHEET NO.
ND	TEU-6-986(113)117	20389	6	1

100-P01 Noise Restrictions: The contractor shall be required to comply with the City of Grand Forks noise ordinance. The contractor shall schedule his or her operations between the hours of 6:30 AM and 10:00 PM, Monday through Saturday. No work on Sundays & Holidays.

100-P02 Plan Scale: Plan sheets indicate a specific scale. Be aware that during reproduction operations, the plan sheets may have been distorted (reduced or increased) and may no longer scale properly at the indicated scale.

100-P03 Existing Utility Locations: Contractor shall call North Dakota One Call (1-800-795-0555) for utility locates prior to beginning work. The approximate location of known existing utilities is shown on the plans; however there may be other utilities within the project limits that are not shown in the plans. Contractor shall be responsible for coordinating with all utility companies for the location of buried utilities prior to any excavation. Equipment shall work around utility poles, bases and pedestals within the construction area that are not to be disturbed. Contractor shall contact all residents living adjacent to the construction site and inquire about the existence of any private utilities/sprinkler systems in the construction area. All private utilities, if disturbed, shall be restored to preconstruction condition at the contractor's expense.

105-110 Pavement Sweeping: The contractor shall sweep streets before opening to traffic and for final acceptance. For this sweeping, the contractor shall furnish and utilize a vacuum type sweeper to control the dust. All costs connected with this work shall be included in the price bid for other items. Contractor shall sweep existing paved roadway surfaces due to construction equipment tracking as determined by Engineer. All costs shall be included in the price for other bid items.

107-P01 Haul Road Restriction: The Contractor shall contact the appropriate State, County, Township, or City officials to determine if there are any "No Haul Routes" prior to preparing a bid for this project.

202-P01 Removals: All removal limits shall be marked by the engineer. Full depth sawing is required at all concrete and asphalt removal limits. Removals will be incidental to "8-Inch Concrete Pavement Repair – Full Depth Doweled".

202-P02 Inert Waste Disposal: Disposal of inert waste materials shall conform to Section 107.10 of the Specifications. All costs for disposal shall be borne by the Contractor and no separate measurement or payment will be made for disposal of inert waste materials.

203-P01 Excavation and Disposal of Contaminated Soil: If contaminated material is encountered, the contractor shall notify the City Engineer, the Project Engineer, and the North Dakota Department of Health, Division of Waste Management (701-328- 5166) at least 5 days in advance of the removal of the contaminated soil. The engineer shall determine the excavation limits of the contaminated soil to be removed. The contractor shall clear with the NDDH an "Application to Land Treat Petroleum Contaminated Soil" before any excavation of the contaminated soil. All costs for labor, materials, and equipment to excavate, haul and treat the material shall be paid for as specified in Section 104.03 D of the NDDOT Standard Specifications. Disposal of contaminated soil at the City of Grand Forks Landfill may be allowed. Soil cannot be in a liquid state. The contractor shall contact the City of Grand Forks Engineering Department prior to any disposal at the landfill. No contaminated material is expected on this project.

570-P01 Concrete Pavement Repair: An additional 20% has been added to the quantities for "8-Inch Concrete Pavement Repair – Full Depth Doweled", and "Random PCC Crack Cleaning & Sealing" to be used as directed by the Engineer.

570-P02 8-Inch Concrete Pavement Repair – Full Depth Doweled: The 8-Inch Concrete Pavement Repair – Full Depth Doweled shall be constructed as shown on the detail sheet in the plans. The repair areas will be measured by the square yard (SY). Sawing shall create a clean vertical, full-depth cut along the entire length required to facilitate material removed. Contractor will drill and epoxy deformed bar as shown in the details. Contractor will stamp concrete to match existing Granitoid Pavement jointing pattern. Concrete saw cutting, drilling and epoxying dowels, as well as stamping concrete will be incidental to 8-Inch Concrete Pavement Repair – Full Depth Doweled. All costs for labor, materials, and equipment to complete this work shall be paid at the unit price bid for " 8-Inch Concrete Pavement Repair – Full Depth Doweled".

570-P03 Random PCC Crack Cleaning & Sealing: Cracks identified by the plans that are less than 3/8" in width will be routed to 3/8". Cost for routing cracks shall be incidental to Random PCC Crack Cleaning & Sealing. Contractor will fill all cracks from the bottom up with a self-leveling silicone recessed so it is flush with the bottom of the stamp in the Granitoid pavement. Contractor will immediately clean up any crack sealant that spills on the surface of the pavement. At the Contractor's option, after the cracks have been sandblasted and cleaned with compressed air, cracks may be filled and leveled with clean sand at a depth to accommodate a minimum of 1" of crack sealant. Sand fill shall be tamped as needed to reduce any large air voids in the sand. Cost for sand fill shall be incidental to Random PCC Crack Cleaning & Sealing. Crack sealant will be gray in color and comply with ASTM D5893. All costs for labor, materials, and equipment to complete this work shall be paid at the unit price for "Random PCC Crack Cleaning & Sealing".

This document was originally issued and sealed by David J. Kuharenko Registration Number PE-8411 on 08/01/2014. The original document is stored at the City of Grand Forks Engineering Department.

ENVIRONMENTAL COMMITMENTS

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	TEU-6-986(113)117	6	2

ENVIRONMENTAL COMMITMENTS (EC): The City of Grand Forks, The North Dakota Department of Transportation and the Federal Highway Administration *has* made environmental commitments to secure approval of this project. The environmental commitments are as follows:

EC-1: Based on the NEPA documentation, no additional permits or environmental commitments have been identified beyond what is covered by the NDDOT's Standard Specification of Road and Bridge Construction.

Wetland Number	Cowardin Classification	Wetland Type	Wetland Size (acres)	Wetland Feature	USACE Jurisdictional Wetlands	Impacts to Wetlands	
						Temp.	Perm.
NO WETLANDS PRESENT							
TOTALS:			0.00			0.00	0.00

EC-2: The North Dakota State Historic Preservation Officer (SHPO) has determined that this project will have No Adverse Effect provided original curb and gutter is not removed.

ACTION REQUIRED /TAKEN: The contractor shall not remove any original curb and gutter within the project limits.

EC-3: The City of Grand Forks has a noise ordinance, which will be in effect for this project unless a variance is authorized by the City of Grand Forks.

ACTION REQUIRED /TAKEN: The Contractor shall be required to have mufflers on equipment with an internal combustion engine. Said mufflers must be in good working condition.

EC-4: The North Dakota Department of Health has stated that necessary measures must be taken to minimize fugitive dust emissions created during construction activities.

ACTION REQUIRED /TAKEN: If dust from construction becomes a hazard to traffic or a nuisance to the public, the Contractor shall be required to apply water for dust palliative purposes, water shall be incidental to the project. Prior to opening any section of roadway to traffic, the Contractor is required to vacuum sweep the street.

EC-5: Water Quality

ACTION REQUIRED /TAKEN: Construction activities will include erosion and sediment control to minimize impacts.

PERMITS REQUIRED

- ND Dept of Health Stormwater Permit
- City of Grand Forks Storm Water Pollution Prevention Permit


QUANTITIES

STATE	PROJECT NO.	PCN	SECTION NO.	SHEET NO.
ND	TEU-6-986(113)117	20389	8	1

SPEC NO.	CODE NO.	ITEM DESCRIPTION	QTY	UNIT
103	100	CONTRACT BOND	1	LS
570	713	8IN CONCRETE PAVEMENT REPAIR – FULL DEPTH DOWELED	220	SY
570	966	RANDOM PCC CRACK CLEANING & SEALING	7,700	LF
702	100	MOBILIZATION	1	L SUM
704	1000	TRAFFIC CONTROL SIGNS	761	UNIT
704	1050	TYPE I BARRICADE	47	EA
704	1052	TYPE III BARRICADE	23	EA
708	1540	INLET PROTECTION SPECIAL	16	EA

This document was originally issued and sealed by David J. Kuharenko Registration Number PE-8411 on 08/01/2014. The original document is stored at the City of Grand Forks Engineering Department.

STATE	PROJECT NO.	PCN	SECTION NO.	SHEET NO.
ND	TEU-6-986(113)117	20389	20	1



NOTES:


CONTRACTOR WILL SAW CUT CONCRETE AROUND THE PERIMETER OF THE REPAIR AS MARKED BY THE ENGINEER. SAW CUTTING WILL BE INCIDENTAL TO 8IN CONCRETE PAVEMENT REPAIR - FULL DEPTH DOWELED.

ALL FOUR SIDES OF THE REPAIR WILL BE TIED TO EXISTING CONCRETE. IF THE SIDE IS 3' TO 4' IN LENGTH USE TWO BARS EVENLY SPACED. IF LONGER THAN 4', SPACE 24" CENTER TO CENTER. DRILLING AND EPOXYING 18" #5 DEFORMED BAR WILL BE INCIDENTAL TO 8IN CONCRETE PAVEMENT REPAIR - FULL DEPTH DOWELED.

CONCRETE PAVEMENT REPAIR WILL BE STAMPED TO MATCH SURROUNDING GRANITOID PAVEMENT. STAMPING WILL BE INCIDENTAL TO 8IN CONCRETE PAVEMENT REPAIR - FULL DEPTH DOWELED.

1/8" WIDE STANDARD FILLED JOINTS AROUND CONCRETE PAVEMENT REPAIRS INCLUDING OVERCUTS WILL BE INCIDENTAL TO THE 8IN CONCRETE PAVEMENT REPAIR - FULL DEPTH DOWELED.

8IN CONCRETE PAVEMENT REPAIR - FULL DEPTH DOWELED



NOTES:

1/8" WIDE STANDARD FILLED JOINT TO BE USED ON ALL CONCRETE CONSTRUCTION AND CONTRACTION JOINTS UNLESS OTHERWISE NOTED

DURING CONCRETE PAVEMENT REPAIRS OR REHABILITATIONS, JOINT WIDTH AND SEALANT TYPE TO MATCH EXISTING JOINTS UNLESS OTHERWISE NOTED.

"D" IS DEPTH OF PAVEMENT


JOINT WIDTH TOLERANCE IS + 1/16" TO - 1/32"

THE JOINT FACES SHALL BE CLEANED BY SANDBLASTING AND DRIED BY AIR BLASTING

STANDARD FILLED JOINT

This document was originally issued and sealed by David J. Kuharenko Registration Number PE-8411 on 08/01/2014. The original document is stored at the City of Grand Forks Engineering Department.


STATE	PROJECT NO.	PCN	SECTION NO.	SHEET NO.
ND	TEU-6-986(113)117	20389	20	2



FILTER BAG INSERT
(CAN BE INSTALLED IN ANY INLET TYPE WITH OR WITHOUT A CURB BOX)

NOTES:

1. ALL GEOTEXTILE MATERIAL USED FOR INLET PROTECTION SHALL BE MONOFILAMENT IN BOTH DIRECTIONS.
2. FINISHED SIZE, INCLUDING POCKETS WHERE REQUIRED SHALL EXTEND A MINIMUM OF 10 INCHES AROUND THE PERIMETER TO FACILITATE MAINTENANCE OR REMOVAL.
3. INSTALLATION NOTES:
DO NOT INSTALL FILTER BAG INSERT IN INLETS SHALLOWER THAN 30 INCHES, MEASURED FROM THE BOTTOM OF THE INLET TO THE TOP OF THE GRATE. THE INSTALLED BAG SHALL HAVE A MINIMUM SIDE CLEARANCE OF 3 INCHES BETWEEN THE INLET WALLS AND THE BAG, MEASURED AT THE BOTTOM OF THE OVERFLOW HOLES. WHERE NECESSARY THE CONTRACTOR SHALL CLINCH THE BAG, USING PLASTIC ZIP TIES, TO ACHIEVE THE 3 INCH SIDE CLEARANCE.
4. FLAP POCKETS SHALL BE LARGE ENOUGH TO ACCEPT WOOD 2 INCH X 4 INCH OR USE A ROCK SOCK OR STRAW WATTLE IN PLACE OF THE FLAP POCKETS.



NOTES:

CONTRACTOR WILL CONDUCT A SITE VISIT TO FAMILIARIZE THEMSELVES WITH THE CRACKS PRIOR TO BIDDING.

THE CRACK FACES SHALL BE CLEANED BY SANDBLASTING AND DRIED BY AIR BLASTING.

IDENTIFIED CRACKS THAT ARE LESS THAN 3/8" IN WIDTH WILL BE ROUTED TO 3/8" WIDE AND TO THE DEPTH SPECIFIED BY THE MANUFACTURER. COST FOR ROUTING CRACKS SHALL BE INCIDENTAL TO RANDOM PCC CRACK CLEANING & SEALING.

FILL ALL CRACKS WITH SELF LEVELING SILICONE, RECESSED SO IT IS FLUSH WITH THE BOTTOM OF THE STAMPED GRANITOID.

AT THE CONTRACTOR'S OPTION, AFTER THE CRACKS HAVE BEEN SANDBLASTED AND CLEANED WITH COMPRESSED AIR, CRACKS MAY BE FILLED AND LEVELED WITH CLEAN SAND AT A DEPTH TO ACCOMMODATE A MINIMUM OF 1" OF CRACK SEALANT. SAND FILL SHALL BE TAMPED AS NEEDED TO REDUCE ANY LARGE VOIDS IN THE SAND.



Random PCC Crack Cleaning & Sealing

This document was originally issued and sealed by David J. Kuharenko Registration Number PE-8411 on 08/01/2014. The original document is stored at the City of Grand Forks Engineering Department.

STATE	PROJECT NO.	PCN	SECTION NO.	SHEET NO.
ND	TEU-6-986(113)117	20389	75	1



Inlet Protection Special	EA
0+39	2 EA
4+30	2 EA
4+70	2 EA
9+44	2 EA
11+73	2 EA
12+12	2 EA
15+55	2 EA



This document was originally issued and sealed by David J. Kuharenko Registration Number PE-8411 on 08/01/2014. The original document is stored at the City of Grand Forks Engineering Department.

Erosion Control

2nd Ave S

STATE	PROJECT NO.	PCN	SECTION NO.	SHEET NO.
ND	TEU-6-986(113)117	20389	80	1

8in Conc Pvmt Repair-Full Depth Doweled	89 SY
3rd Ave S	19 SY
Cottonwood St	70 SY
Random PCC Crack Cleaning & Sealing	3,425 LF
3rd Ave S	1,150 LF
Cottonwood St	2,275 LF

LEGEND


 Random PCC Crack Cleaning & Sealing

 8in Conc Pvmt Repair-Full Depth Doweled




This document was originally issued and sealed by David J. Kuharenko Registration Number PE-8411 on 08/01/2014. The original document is stored at the City of Grand Forks Engineering Department.

Repair Locations
STA 2+49 to 9+50



STATE	PROJECT NO.	PCN	SECTION NO.	SHEET NO.
ND	TEU-6-986(113)117	20389	80	2



8in Conc Pvmt Repair-Full Depth Doweled	94 SY
2nd Ave S	94 SY
Random PCC Crack Cleaning & Sealing	3,032 LF
2nd Ave S	3,032 LF


- LEGEND
-  Random PCC Crack Cleaning & Sealing
 -  8in Conc Pvmt Repair-Full Depth Doweled



This document was originally issued and sealed by David J. Kuharenko Registration Number PE-8411 on 08/01/2014. The original document is stored at the City of Grand Forks Engineering Department.

Repair Locations
STA 10+00 to 15+60

STATE	PROJECT NO.	PCN	SECTION NO.	SHEET NO.
ND	TEU-6-986(113)117	20389	100	2



This document was originally issued and sealed by David J. Kuharenko Registration Number PE-8411 on 08/01/2014. The original document is stored at the City of Grand Forks Engineering Department.



Traffic Control

NDDOT ABBREVIATIONS

? This is a special text character used in the labeling of existing features. It indicates a feature that has an unknown characteristic, potentially based on: lack of description, location accuracy or purpose.

Abn abandoned
 Abut abutment
 Ac acres
 Adj adjusted
 Aggr aggregate
 Ahd ahead
 ARV air release valve
 Align alignment
 Al alley
 Alt alternate
 Alum aluminum
 ADA Americans with Disabilities Act
 A ampere
 & and
 Appr approach
 Approx approximate
 ACP asbestos cement pipe
 Asph asphalt
 AC asphalt cement
 Assmd assumed
 @ at
 Atten attenuation
 ATR automatic traffic recorder
 Ave Avenue
 Avg average
 ADT average daily traffic
 Az azimuth
 Bk back
 BF back face
 Bs backsight
 Balc balcony
 B Wire barbed wire
 Barr barricade
 Btry battery
 Brg bearing
 BI beehive inlet
 Beg begin
 BM bench mark
 Bkwy bikeway
 Bit bituminous
 Blk block
 Bd Ft board feet
 BH bore hole
 BS both sides
 Bot bottom
 Blvd Boulevard
 Bndry boundary
 BC brass cap
 Brkwy breakaway
 Br bridge
 Bldg building

BV butterfly valve
 Byp bypass
 C Gdrl cable guardrail
 Calc calculate
 Cd candela
 CIP cast iron pipe
 CB catch basin
 CRS cationic rapid setting
 C Gd cattle guard
 C To C center to center
 Cl or C centerline
 Cm centimeter
 Ch chain
 Chnlk chain-link
 Ch Blk channel block
 Ch Ch channel change
 Chk check
 Chsld chiseled
 Cir circle
 Cl class
 Cl clay
 Cl F clay fill
 Cl Hvy clay heavy
 Cl Lm clay loam
 Clnt clean-out
 Clr clear
 Cl&gr clearing & grubbing
 Co S coal slack
 Comb. combination
 Coml commercial
 Compr compression
 CADD computer aided drafting & design
 Conc concrete
 Cond conductor
 Const construction
 Cont continuous
 CSB continuous split barrel sample
 Contr contraction
 Contr contractor
 CP control point
 Coord coordinate
 Cor corner
 Corr corrected
 CAES corrugated aluminum end section
 CAP corrugated aluminum pipe
 CMES corrugated metal end section
 CMP corrugated metal pipe
 CPVCP corrugated poly-vinyl chloride pipe
 CSES corrugated steel end section
 CSP corrugated steel pipe
 C coulomb
 Co County
 Crse course
 C Gr course gravel
 CS course sand

Ct Court
 Xarm cross arm
 Xbuck cross buck
 Xsec cross sections
 Xing crossing
 Xrd Crossroad
 Crn crown
 CF cubic feet
 M3 cubic meter
 M3/s cubic meters per second
 CY cubic yard
 Cy/mi cubic yards per mile
 Culv culvert
 C&G curb & gutter
 CI curb inlet
 CR curb ramp
 CS curve to spiral
 C cut
 Dd Ld dead load
 Defl deflection
 Defm deformed
 Deg or D degree
 DInt delineate
 DIntr delineator
 Depr depression
 Desc description
 Det detail
 DWP detectable warning panel
 Dtr detour
 Dia diameter
 Dir direction
 Dist distance
 DM disturbed material
 DB ditch block
 DG ditch grade
 Dbl double
 Dn down
 Dwg drawing
 Dr drive
 Drwy driveway
 DI drop inlet
 D dry density
 Ea each
 Esmt easement
 E East
 EB Eastbound
 Elast elastomeric
 EL electric locker
 E Mtr electric meter
 Elec electric/al
 EDM electronic distance meter
 Elev or El elevation
 Ellipt elliptical
 Emb embankment
 Emuls emulsion/emulsified

ES end section
 Engr engineer
 ESS environmental sensor station
 Eq equal
 Eq equation
 Evgr evergreen
 Exc excavation
 Exst existing
 Exp expansion
 Expy Expressway
 E external of curve
 Extru extruded
 FOS factor of safety
 F Fahrenheit
 FS far side
 F farad
 Fed Federal
 FP feed point
 Ft feet/foot
 Fn fence
 Fn P fence post
 FO fiber optic
 FB field book
 FD field drive
 F fill
 FAA fine aggregate angularity
 FS fine sand
 FH fire hydrant
 Fl flange
 Flrd flared
 FES flared end section
 F Bcn flashing beacon
 FA flight auger sample
 FL flow line
 Ftg footing
 FM force main
 Fs foresight
 Fnd found
 Fdn foundation
 Frac fractional
 Frwy freeway
 Frt front
 FF front face
 F Disp fuel dispenser

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
06-15-10	
REVISIONS	
DATE	CHANGE
04-20-11	Added Items
03-15-13	Added Items
11-01-13	Added Items
03-25-14	Added Items

This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930 , on 03/25/14 and the original document is stored at the North Dakota Department of Transportation

NDDOT ABBREVIATIONS

FFP	fuel filler pipes	IP	iron Pipe	M	mega	Ped	pedestrian
FLS	fuel leak sensor	Jt	joint	Mer	meridian	PPP	pedestrian pushbutton post
Furn	furnish/ed	J	joule	M	meter	Pen.	penetration
Gal	gallon	Jct	junction	M/s	meters per second	Perf	perforated
Galv	galvanized	K	kelvin	M	mid ordinate of curve	Per.	perimeter
Gar	garage	Kn	kilo newton	Mi	mile	PL	pipeline
Gs L	gas line	Kpa	kilo pascal	MM	mile marker	PI	place
G Reg	gas line regulator	Kg	kilogram	MP	mile post	P&P	plan & profile
GMV	gas main valve	Kg/m3	kilogram per cubic meter	MI	milliliter	PL	plastic limit
G Mtr	gas meter	Km	kilometer	Mm	millimeter	PI	plate
GSV	gas service valve	K	Kip(s)	Mm/hr	millimeters per hour	Pt	point
GVP	gas vent pipe	LS	Land Surveyor (licensed)	Min	minimum	PCC	point of compound curve
GV	gate valve	LSIT	Land Surveyor In Training	Misc	miscellaneous	PC	point of curve
Ga	gauge	Ln	lane	Mon	monument	PI	point of intersection
Geod	geodetic	Lg	large	Mnd	mound	PRC	point of reverse curvature
GIS	Geographical Information System	Lat	latitude	Mtbl	mountable	PT	point of tangent
G	giga	Lt	left	Mtd	mounted	POC	point on curve
GPS	Global Positioning System	L	length of curve	Mtg	mounting	POT	point on tangent
Gov	government	Lens	lenses	Mk	muck	PE	polyethylene
Grd	graded/grade	Lvl	level	Mun	municipal	PVC	polyvinyl chloride
Gr	gravel	LB	level book	N	nano	PCC	Portland Cement concrete
Grnd	ground	LvIng	leveling	NGS	National Geodetic Survey	Lb or #	pounds
GWM	ground water monitor	Lht	light	NS	near side	PP	power pole
Gdrl	guardrail	LP	light pole	Neop	neoprene	Preempt	preemption
Gtr	gutter	Ltg	lighting	Ntwk	network	Prefab	prefabricated
H Plg	H piling	Lig Co	lignite coal	N	newton	Prfmd	performed
Hdwl	headwall	Lig Sl	lignite slack	N	North	Prep	preparation
Ha	hectare	LF	linear foot	NE	North East	Press.	pressure
Ht	height	Liq	liquid	NW	North West	PRV	pressure relief valve
HI	height of instrument	LL	liquid limit	NB	Northbound	Prestr	prestressed
Hel	helical	L	litre	No. or #	number	Pvt	private
H	henry	Lm	loam	Obsc	obscure(d)	PD	private drive
HZ	hertz	Loc	location	Obsn	observation	Prod.	production/produce
HDPE	high density polyethylene	LC	long chord	Ocpd	occupied	Prog	programmed
HM	high mast	Long.	longitude	Ocpy	occupy	Prop.	property
HP	high pressure	Lp	loop	Off Loc	office location	Prop Ln	property line
HPS	high pressure sodium	LD	loop detector	O/s	offset	Ppsd	proposed
Hwy	highway	Lm	lumen	OC	on center	PB	pull box
Hor	horizontal	Lum	luminaire	C	one dimensional consolidation		
HBP	hot bituminous pavement	L Sum	lump sum	OC	organic content		
Hr	hour(s)	Lx	lux	Orig	original		
Hyd	hydrant	ML	main line	O To O	out to out		
Ph	hydrogen ion content	M Hr	man hour	OD	outside diameter		
Id	identification	MH	manhole	OH	overhead		
In or "	inch	Mkd	marked	PMT	pad mounted transformer		
Incl	inclinometer tube	Mkr	marker	Pg	pages		
IMH	inlet manhole	Mkg	marking	Pntd	painted		
ID	inside diameter	MA	mast arm	Pr	pair		
Inst	instrument	Matl	material	Pnl	panel		
Intchg	interchange	Max	maximum	Pk	park		
Intmdt	intermediate	MC	meander corner	PK	Parker-Kalon nail		
Intscn	intersection	Meas	measure	Pa	pascal		
Inv	invert	Mdn	median	PSD	passing sight distance		
IM	iron monument	MD	median drain	Pvmt	pavement		
IPn	Iron Pin	MC	medium curing	Ped	pedestal		

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
06-15-10	
REVISIONS	
DATE	CHANGE
04-20-11	Added Items
03-15-13	Added Items
11-01-13	Added Items
03-25-14	Added Items

This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930 , on 03/25/14 and the original document is stored at the North Dakota Department of Transportation

NDDOT ABBREVIATIONS

D-20-3

Qty	quantity	Sig	signal	TS	tangent to spiral	WB	Westbound
Qtr	quarter	Si Cl	silt clay	Tel	telephone	Wrng	wiring
Rad or R	radius	Si Cl Lm	silty clay loam	Tel B	Telephone Booth	W/	with
RR	railroad	Si Lm	silty loam	Tel P	telephone pole	W/o	without
Rlwy	railway	Sgl	single	Temp	temperature	WC	witness corner
Rsd	raised	SC	slow curing	Temp	temporary	WGS	World Geodetic System
RTP	random traverse point	SS	slow setting	TBM	temporary bench mark	Z	zenith
Rge or R	range	Sm	small	T	tesla		
RC	rapid curing	S	South	T	thinwall tube sample		
Rec	record	SE	South East	T/mi	tons per mile		
Rcy	recycle	SW	South West	Ts	topsoil		
RPCC	recycled Portland cement concrete	SB	Southbound	Twp or T	township		
Ref	reference	Sp	spaces	Traf	traffic		
R Mkr	reference marker	Spcl	special	TSCB	traffic signal control box		
RM	reference monument	SA	special assembly	Tr	trail		
Refl	reflectorized	SP	special provisions	Transf	transformer		
RCB	reinforced concrete box	G	specific gravity	TB	transit book		
RCES	reinforced concrete end section	Spk	spike	Trans	transition		
RCP	reinforced concrete pipe	SC	spiral to curve	TT	transmission tower		
RCPS	reinforced concrete pipe sewer	ST	spiral to tangent	Trans	transverse		
Reinf	reinforcement	SB	split barrel sample	Trav	traverse		
Res	reservation	SH	sprinkler head	TP	traverse point		
Ret	retaining	SV	sprinkler valve	Trtd	treated		
Rev	reverse	Sq	square	Trmt	treatment		
Rt	right	SF	square feet	Qc	triaxial compression		
R/W	right of way	Km2	square kilometer	TERO	tribal employment rights ordinance		
Riv	river	M2	square meter	Tpl	triple		
Rd	road	SY	square yard	TP	turning point		
Rdbd	road bed	Stk	stake	Typ	typical		
Rdwy	roadway	Std	standard	Qu	unconfined compressive strength		
RWIS	Roadway Weather Information System	N	standard penetration test	Ugrnd	underground		
Rk	rock	Std Specs	Standard Specifications	USC&G	US Coast & Geodetic Survey		
Rt	route	Sta	station	USGS	US Geologic Survey		
Salv	salvage(d)	Sta Yd	station yards	Util	utility		
Sd	sand	Stm L	steam line	VG	valley gutter		
Sdy Cl	sandy clay	SEC	steel encased concrete	Vap	vapor		
Sdy Cl Lm	sandy clay loam	SSD	stopping sight distance	Vert	vertical		
Sdy Fl	sandy fill	SD	storm drain	VC	vertical curve		
Sdy Lm	sandy loam	St	street	VCP	vitrified clay pipe		
San	sanitary sewer line	SPP	structural plate pipe	V	volt		
Sc	scoria	SPPA	structural plate pipe arch	Vol	volume		
Sec	seconds	Str	structure	Wkwy	walkway		
Sec	section	Subd	subdivision	W	water content		
SL	section line	Sub	subgrade	WGV	water gate valve		
Sep	separation	Sub Prep	subgrade preparation	WL	water line		
Seq	sequence	Ss	subsoil	WM	water main		
Serv	service	SE	superelevation	WMV	water main valve		
Sh	shale	SS	supplement specification	W Mtr	water meter		
Sht	sheet	Supp	supplemental	WSV	water service valve		
Shtng	sheeting	Surf	surfacing	WW	water well		
Shldr	shoulder	Surv	survey	W	watt		
Sw	sidewalk	Sym	symmetrical	Wrng	wearing		
S	siemens	SI	Systems International	Wb	weber		
SD	sight distance	Tan	tangent	WIM	Weigh In Motion		
SN	sign number	T	tangent (semi)	W	West		

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
06-15-10	
REVISIONS	
DATE	CHANGE
04-20-11	Added Items
03-15-13	Added Items
11-01-13	Added Items
03-25-14	Added Items

This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930 , on 03/25/14 and the original document is stored at the North Dakota Department of Transportation

NDDOT UTILITY COMPANY AND ORGANIZATION ABBREVIATIONS

D-20-10

702COM 702 Communications
 ACCENT Accent Communications
 AGASSIZ WU Agassiz Water Users Incorporated
 AGC Associated General Contractors of America
 All PI Alliance Pipeline
 ALL SEAS WU All Seasons Water Users Association
 AMOCO PI Amoco Pipeline Company
 AMRDA HESS Amerada Hess Corporation
 AT&T AT&T Corporation
 B PAW Bear Paw Energy Incorporated
 BAKER ELEC Baker Electric
 BASIN ELEC Basin Electric Cooperative Incorporated
 BEK TEL Bek Communications Cooperative
 BELLE PL Belle Fourche Pipeline Company
 BLM Bureau of Land Management
 BNSF Burlington Northern Santa Fe Railway
 BOEING Boeing
 BRNS RWD Barnes Rural Water District
 BURK-DIV ELEC Burke-Divide Electric Cooperative
 BURL WU Burleigh Water Users
 Cable One Cable One
 CABLE SERV Cable Services
 CAP ELEC Capital Electric Cooperative Incorporat
 CASS CO ELEC Cass County Electric Cooperative
 CASS RWU Cass Rural Water Users Incorporated
 CAV ELEC Cavalier Rural Electric Cooperative
 CBLCOM Cablecom Of Fargo
 CENEX PL Cenex Pipeline
 CENT PL WATER DIST Central Pipe Line Water District
 CENT PWR ELEC Central Power Electric Cooperative
 COE Corps of Engineers
 CONS TEL Consolidated Telephone
 CONT RES Continental Resource Inc
 CPR Canadian Pacific Railway
 D O E Department Of Energy
 DAK CARR Dakota Carrier Network
 DAK CENT TEL Dakota Central Telephone
 DAK RWD Dakota Rural Water District
 DGC Dakota Gasification Company
 DICKEY R NET Dickey Rural Networks
 DICKEY RWU Dickey Rural Water Users Association
 DICKEY TEL Dickey Telephone
 DNRR Dakota Northern Railroad
 DOME PL Dome Pipeline Company
 DVELEC Dakota Valley Electric Cooperative
 DVMW Dakota, Missouri Valley & Western
 ENBRDG Enbridge Pipelines Incorporated
 ENVENTIS Enventis Telephone
 FALK MNG Falkirk Mining Company
 FHWA Federal Highway Administration
 G FKS-TRL WD Grand Forks-trail Water District
 GETTY TRD & TRAN Getty Trading & Transportation
 GLDN W ELEC Golden West Electric Cooperative
 GRGS CO TEL Griggs County Telephone

GT PLNS NAT GAS Great Plains Natural Gas Company
 HALS TEL Halstad Telephone Company
 IDEA1 Idea1
 INT-COMM TEL Inter-Community Telephone Company
 KANEB PL Kaneb Pipeline Company
 KEM ELEC Kem Electric Cooperative Incorporated
 KOCH GATH SYS Koch Gathering Systems Incorporated
 LKHD PL Lakehead Pipeline Company
 LNGDN RWU Langdon Rural Water Users Incorporated
 LWR YELL R ELEC Lower Yellowstone Rural Electric
 MCKNZ CON McKenzie Consolidated Telcom
 MCKENZ ELEC McKenzie Electric Cooperative
 MCKNZ WRD McKenzie County Water Resource District
 MCLEOD McLeod USA
 MCLN ELEC McLean Electric Cooperative
 MCLN-SHRDN R WAT McLean-Sheridan Rural Water
 MDU Montana-dakota Utilities
 MID-CONT CABLE Mid-Continent Cable
 MIDSTATE TEL Midstate Telephone Company
 MINOT CABLE Minot Cable Television
 MINOT TEL Minot Telephone Company
 MISS W W S Missouri West Water System
 MNKOTA PWR Minnkota Power
 MOR-GRAN-SOU ELEC Mor-gran-sou Electric Cooperative
 MOUNT-WILLI ELEC Mountrail-williams Electric Cooperative
 MRE LBTY TEL Moore & Liberty Telephone
 MUNICIPAL City Water And Sewer
 MUNICIPAL City Of '.....'
 N CENT ELEC North Central Electric Cooperative
 N VALL W DIST North Valley Water District
 ND PKS & REC North Dakota Parks And Recreation
 ND TEL North Dakota Telephone Company
 NDDOT North Dakota Department of Transportation
 NDSU SOIL SCI DEPT NDSU Soil Science Department
 NEMONT TEL Nemont Telephone
 NODAK R ELEC Nodak Rural Electric Cooperative
 NOON FRMS TEL Noonan Farmers Telephone Company
 NPR Northern Plains Railroad
 NSP Northern States Power
 NTH PRAIR RW Northern Prairie Rural Water Association
 NTHN BRDR PL Northern Border Pipeline
 NTHN PLNS ELEC Northern Plains Electric Cooperative Incorporated
 NTHWSTRN REF Northwestern Refinery Company
 NW COMM Northwest Communication Cooperation
 ONEOK Oneok gas
 OSHA Occupational Safety and Health Administration
 OTTR TL PWR Otter Tail Power Company
 P L E M Prairielands Energy Marketing
 POLAR COM Polar Communications
 PVT ELEC Private Electric
 QWEST Qwest Communications
 R & T W SUPPLY R & T Water Supply Association
 RAMSEY R SEW Ramsey Rural Sewer Association
 RAMSEY RW Ramsey Rural Water Association
 RAMSEY UTIL Ramsey County Rural Utilities

RED RIV TEL Red River Rural Telephone
 RESVTN TEL Reservation Telephone
 ROBRTS TEL Roberts Company Telephone
 R-RIDER ELEC Roughrider Electric Coop
 RRVW Red River Valley & Western Railroad
 RSR ELEC R.S.R. Electric Cooperative
 S E W U South East Water Users Incorporated
 SCOTT CABLE Scott Cable Television Dickinson
 SHERDN ELEC Sheridan Electric Cooperative
 SHEYN VLY ELEC Sheyenne Valley Electric Cooperative
 SKYTECH Skyland Technologies Incorporated
 SLOPE ELEC Slope Electric Cooperative Incorporated
 SOURIS RIV TELCOM Souris River Telecommunications
 ST WAT COMM State Water Commission
 STATE LN WATER State Line Water Cooperative
 STER ENG Sterling Energy
 STUT RWU Stutsman Rural Water Users
 SW PL PRJ Southwest Pipeline Project
 T M C Turtle Mountain Communications
 TCI TCI of North Dakota
 TESORO GH PLNS PL Tesoro High Plains Pipeline
 TRI-CNTY WU Tri-County Water Users Incorporated
 TRL CO RWU Traill County Rural Water Users
 UNTD TEL United Telephone
 UPPR SOUR WUA Upper Souris Water Users Association
 US SPRINT U.S. Sprint
 USAF MSL CABLE U.S.A.F. Missile Cable
 USFWS US Fish and Wildlife Service
 USW COMM U.S. West Communications
 VRNDRY ELEC Verendrye Electric Cooperative
 W RIV TEL West River Telephone Incorporated
 WEB W. E. B. Water Development Association
 WILLI RWA Williams Rural Water Association
 WILSTN BAS PL Williston Basin Interstate Pipeline Company
 WLSH RWD Walsh Water Rural Water District
 WOLVRTN TEL Wolverton Telephone
 XLENER Xcel Energy
 YSVR Yellowstone Valley Railroad

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
6-15-10	
REVISIONS	
DATE	CHANGE
04-20-11	Added Items
03-15-13	Added Items
11-01-13	Added Items, Changed Standard Name to Include Organizations

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 11/01/13 and the original document is stored at the North Dakota Department of Transportation









Line Styles

.....	Limits of Const Transition Line	—— s —— s ——	Floating Silt Curtain	—— ——— ———	Existing Aggregate (Cross Section View)	- - - - -	Existing Centerline
.....	Bale Check	—— ——— T ——	Existing Telephone Line	—— ——— ———	Existing Curb and Gutter (Cross Section View)	- - - - -	Supplemental Contour
.....	Rock Check	—— ——— TV ——	Existing TV Line	—— ——— ———	Existing Riprap	—— - - - - -	Right of Way
.....	Sight Distance Triangle Line	Void — void — void — v	Existing Assumed Ground (Not Surveyed)	—— ——— ———	Existing Underground Vault or Lift Station	—— - - - - -	Existing Right of Way
- - - - -	Small Hidden Object	Void — void — void — v	Tentative Ground Line	—— ——— ———	Tangent Line	—— - - - - -	Existing Right of Way Railroad
- - - - -	Dimension Leader	—— ——— w ——	Existing Water or Steam Line	- - - - -	Hidden Object	- - - - -	Failure Line
- - - - -	Existing Ground	=====	Existing Under Drain	—— ——— ———	Existing Dirt Surface	- - - - -	Existing Conditions
- - - - -	Existing Topsoil (Cross Section View)	=====	Under Drain	—— ——— ———	Existing Conduit	- - - - -	Existing Ground (Details)
—— ——— ———	Large Hidden Object	=====	Wall	—— ——— ———	Topsoil Profile	—— - - - - -	Existing Sixteenth Section Line
—— ——— ———	Edge Drain	=====	Existing Slotted Drain	- - - - -	Existing Conductor	- - - - -	Existing Right of Way Not State Owned
—— D —— D ——	Geotextile Fabric Type D	—— + —— + ——	Existing Cemetary Boundary	- - - - -	Conductor	- - - - -	Phantom Object
—— ——— E ——	Existing Electrical	—— ——— ———	Centerline Pavement Marking	- - - - -	Fiber Optic	- - - - -	Centerline Main
—— ——— FO ——	Existing Fiber Optic Line	=====	Barrier with Centerline Pavement Marking	- - - - -	Existing Loop Detector	-	Existing Guardrail Cable
—— ——— FO ——	Existing TV Fiber Optic	=====	Barrier Pavement Marking	- - - - -	Subgrade, Subcut or Ditch Grade	— • — • — • — •	Existing Guardrail Metal
—— ——— G ——	Existing Gas Pipe	- - - - -	Stripe 4 IN Dotted Extension White	—— ——— ———	Existing Asphalt Surface	—— . ——— . ——— . ——— .	Existing Edge of Water
—— Geo —— Geo ——	Geogrid	- - - - -	Stripe 8 IN Dotted Extension White	—— ——— ———	Existing Asphalt (Cross Section View)	- - - - -	Excavation Limits
—— ——— OH ——	Existing Overhead Utility Line	- - - - -	Stripe 8 IN Lane Drop	—— ——— ———	Existing Reinforcement Rebar	——	Existing Government Lot Line
—— ——— P ——	Existing Power	—— v v v v ——	Wetland Mitigation	—— ——— ———	Existing Tie Point Line	Existing Adjacent Block Lines
—— ——— PL ——	Existing Fuel Pipeline	- - - - -	Existing Box Culvert Bridge	—— ——— ———	Existing State or International Line	Existing Adjacent Lot Lines
—— ——— PL ——	Existing Undefined Above Ground Pipe Line	- - - - -	Existing Concrete Surface	—— ——— ———	Existing Quarter Section Line	Existing Adjacent Property Line
—— ——— R —— R ——	Geotextile Fabric Type R	- - - - -	Existing Drainage Structure	—— ——— ———	Existing County	Existing Adjacent Subdivision Lines
—— ——— R —— R ——	Geotextile Fabric Type R1	- - - - -	Easement	—— ——— ———	Existing Section Line	
—— REMOVE —— REMOVE ——	Remove Line	- - - - -	Existing Concrete	—— ——— ———	Existing Township	
—— RR —— RR ——	Geotextile Fabric Type RR	- - - - -	Existing Easement	—— ——— ———	Existing Railroad Centerline	
—— S —— S ——	Geotextile Fabric Type S	—— ——— ———	Existing Gravel Surface	—— - - - - -	Centerline	

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
4-20-11	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 4/20/11 and the original document is stored at the North Dakota Department of Transportation

Line Styles

	Subgrade Reinforcement		Existing Railroad Switch		Sheet Piling
	Existing Down Guy Wire Down Guy		Overhead Sign Structure Cantilever		W-Beam w Posts
	Existing Fence		24 Inch Pipe		Existing W-Beam Guardrail with Posts
	Existing Railroad		Reinforced Concrete Pipe		Exst Wet Area-Vegetation Break
	Existing Sanitary Sewer		Signal Head with Mast Arm		Existing Wetland Delineated
	Existing Sanitary Force Main		Existing Signal Head with Mast Arm		
	Existing Storm Drain		Tie Bar at Random Spacing		
	Existing Storm Drain Force Main		3-Cable w Posts		
	Fence		Existing 3-Cable w Posts		
	Silt Fence		Site Boundary		
	Existing Field Line		Fiber Rolls		
	Exst Flow		Doweled Joint		
	Flow		Tie Bar 30 Inch 4 Foot Center to Center		
	Existing Culvert		Tie Bar 18 Inch 3 Foot Center to Center		
	Existing Curb		Existing Berm, Dike, Pit, or Earth Dam		
	Existing Valley Gutter		Existing Ditch Block		
	Existing Driveway Gutter		Depression Contours		
	Existing Curb and Gutter		Existing City Corporate Limits or Reservation Boundary		
	Existing Mountable Curb and Gutter		Gravel Pit - Borrow Area		
	Existing Double Micro Loop Detector		Existing Tree Boundary		
	Micro Loop Detector Double		Tree Row		
	Existing Overhead Sign Structure		Existing Brush or Shrub Boundary		
	Existing Micro Loop Detector		Existing Retaining Wall		
	Micro Loop Detector		Existing Planter or Wall		
	Existing Overhead Sign Structure Cantilever		Retaining Wall (Plan View)		

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
4-20-11	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 4/20/11 and the original document is stored at the North Dakota Department of Transportation

Symbols

	North Arrow (Half Scale)		Attenuation Device		Existing Railroad Battery Box		Existing Delineator Type E
	Truck Mounted Attenuator		Diamond Grade Delineator Type A		Existing Bush or Shrub		Existing EFB Misc
	Type I Barricade		Diamond Grade Delineator Type B		Existing Gas Cap or Stub		Existing Flashing Beacon
	Type II Barricade		Diamond Grade Delineator Type C		Existing Sanitary Cap or Stub		Existing Pipe Mounted Flasher
	Type III Barricade		Diamond Grade Delineator Type D		Existing Storm Drain Cap or Stub		Existing Pad Mounted Feed Point
	Catch Basin		Diamond Grade Delineator Type E		Existing Water Cap or Stub		Existing Pipe Mounted Feed Point with Pad
	Cairn or Stone Circle		Flexible Delineator		Existing Sanitary Cleanout		Existing Pole Mounted Feed Point
	Video Detection Camera		Flexible Delineator Type A		Existing Concrete Foundation		Existing Railroad Frog
	Storm Drain Cap or Stub		Flexible Delineator Type B		Existing Traffic Signal Controller		Existing Snow Gate 18
	Corrugated Metal End Section 18 Inch		Flexible Delineator Type C		Existing Pad Mounted Signal Controller		Existing Snow Gate 28
	Corrugated Metal End Section 24 Inch		Flexible Delineator Type D		Existing Sixteenth Section Corner		Existing Snow Gate 40
	Corrugated Metal End Section 30 Inch		Flexible Delineator Type E		Existing Quarter Section Corner		Existing Headwall
	Corrugated Metal End Section 36 Inch		Delineator Type A		Existing Section Corner		Existing Pedestrian Head with Number
	Corrugated Metal End Section 42 Inch		Delineator Type A Reset		Existing Railroad Crossbuck		Existing Signal Head
	Corrugated Metal End Section 48 Inch		Delineator Type B		Existing Satellite Dish		Existing Sprinkler Head
	Concrete Foundation		Delineator Type B Reset		Existing Fuel Dispensers		Existing Fire Hydrant
	Ground Connection Conductor		Delineator Type C		Existing Flexible Delineator Type A		Existing Catch Basin Drop Inlet
	Neutral Connection Conductor		Delineator Type D		Existing Flexible Delineator Type B		Existing Curb Inlet
	Phase 1 Connection Conductor		Delineator Type E		Existing Flexible Delineator Type C		Existing Manhole Inlet
	Phase 2 Connection Conductor		Delineator Drums		Existing Flexible Delineator Type D		Existing Junction Box
	Traffic Cone		Spot Elevation		Existing Flexible Delineator Type E		
	Signal Controller		Existing Access Control Arrow		Existing Delineator Type A		
	Pad Mounted Signal Controller		Existing Artifact		Existing Delineator Type B		
	Alignment Data Point		Existing Flashing Beacon		Existing Delineator Type C		
	Emergency Vehicle Detector		Existing Benchmark		Existing Delineator Type D		

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
4-20-11	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 4/20/11 and the original document is stored at the North Dakota Department of Transportation

Symbols

D-20-31

 Existing Light Standard	 Existing Manhole with Valve Water	 Existing Telephone Pole	 Existing Undefined Manhole
 Existing High Mast Light Standard 10 Luminaire	 Existing Water Manhole	 Existing Wood Pole	 Existing Undefined Pull Box
 Existing High Mast Light Standard 3 Luminaire	 Existing Mile Post Type A	 Existing Post	 Existing Undefined Pedestal
 Existing High Mast Light Standard 4 Luminaire	 Existing Mile Post Type B	 Existing Pedestrian Push Button Post	 Existing Undefined Valve
 Existing High Mast Light Standard 5 Luminaire	 Existing Mile Post Type C	 Existing Control Point CP	 Existing Undefined Pipe Vent
 Existing High Mast Light Standard 6 Luminaire	 Existing Reference Marker	 Existing Control Point GPS-RTK	 Existing Gas Valve
 Existing High Mast Light Standard 7 Luminaire	 Existing RW Marker	 Existing Control Point TRI	 Existing Water Valve
 Existing High Mast Light Standard 8 Luminaire	 Existing Utility Marker	 Existing Reference Marker Point NGS	 Existing Fuel Pipe Vent
 Existing High Mast Light Standard 9 Luminaire	 Existing Monument Found	 Existing Pull Box	 Existing Gas Pipe Vent
 Existing Overhead Sign Structure Load Center	 Existing Monument set	 Existing Intelligent Transportation Pull Box	 Existing Sanitary Pipe Vent
 Existing Luminaire	 Existing RW Property Monument Found	 Existing Water Pump	 Existing Storm Drain Pipe Vent
 Existing Light Standard Luminaire	 Existing RW Property Monument set	 Existing Slotted Reinforced Concrete Pipe	 Existing Water Pipe Vent
 Existing Federal Mailbox	 Existing Object Marker Type I	 Existing RR Profile Spot	 Existing Weather Station
 Existing Private Mailbox	 Existing Object Marker Type II	 Existing Fuel Leak Sensors	 Existing Ground Water Well Bore Hole
 Existing Meander Section Corner	 Existing Object Marker Type III	 Existing Highway Sign	 Existing Windmill or Tower
 Existing Meter	 Existing Electrical Pedestal	 Existing Miscellaneous Spot	 Existing Witness Corner
 Existing Electrical Manhole	 Existing Telephone Pedestal	 Existing Lighting Standard Pole	 Flashing Beacon
 Existing Gas Manhole	 Existing Fiber Optic Telephone Pedestal	 Existing Traffic Signal Standard	 Flagger
 Existing Sanitary Manhole	 Existing TV Pedestal	 Existing Transformer	 Pipe Mounted Flasher
 Existing Sanitary Force Main Manhole	 Existing Fiber Optic TV Pedestal	 Existing Large Evergreen Tree	 Sanitary Force Main with Valve
 Existing Sanitary Manhole with Valve	 Existing Fuel Filler Pipes	 Existing Small Evergreen Tree	
 Existing Storm Drain Manhole	 Existing Traverse PI Aerial Panel	 Existing Large Tree	
 Existing Force Main Storm Drain Manhole	 Existing Pole	 Existing Small Tree	
 Existing Force Main Storm Drain Manhole with Valve	 Existing Power Pole	 Existing Tree Trunk	
 Existing Telephone Manhole	 Existing Power Pole with Transformer	 Existing Pad Mounted Traffic Signal Control Box	

NORTH DAKOTA	
DEPARTMENT OF TRANSPORTATION	
4-20-11	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by
 Roger Weigel,
 Registration Number PE-2930,
 on 4/20/11 and the original document is stored at the North Dakota Department of Transportation

Symbols

 Pad Mounted Feed Point  Pipe Mounted Feed Point with Pad  Pole Mounted Feed Point  Headwall  Double Headwall with Vegetation Barrier  Single Headwall with Vegetation Barrier  Pole Mounted Head  Sprinkler Head  Fire Hydrant  Inlet Type 1  Inlet Type 2  Double Inlet Type 2  Inlet Gate Type 2  Junction Box  High Mast Light Standard 10 Luminaire  High Mast Light Standard 3 Luminaire  High Mast Light Standard 4 Luminaire  High Mast Light Standard 5 Luminaire  High Mast Light Standard 6 Luminaire  High Mast Light Standard 7 Luminaire  High Mast Light Standard 8 Luminaire  High Mast Light Standard 9 Luminaire  Relocate Light Standard  Overhead Sign Structure Load Center  Light Standard 100 Watt High Pressure Sodium Vapor Luminaire	 Light Standard 1000 Watt High Pressure Sodium Vapor Luminaire  Light Standard 150 Watt High Pressure Sodium Vapor Luminaire  Light Standard 175 Watt High Pressure Sodium Vapor Luminaire  Light Standard 200 Watt High Pressure Sodium Vapor Luminaire  Light Standard 250 Watt High Pressure Sodium Vapor Luminaire  Light Standard 310 Watt High Pressure Sodium Vapor Luminaire  Light Standard 35 Watt High Pressure Sodium Vapor Luminaire  Light Standard 400 Watt High Pressure Sodium Vapor Luminaire  Light Standard 50 Watt High Pressure Sodium Vapor Luminaire  Light Standard 70 Watt High Pressure Sodium Vapor Luminaire  Light Standard 700 Watt High Pressure Sodium Vapor Luminaire  Manhole  Manhole 48 Inch  Sanitary Force Main Manhole  Sanitary Sewer Manhole  Storm Drain Manhole  Storm Drain Manhole with Inlet  Reset Mile Post  Mile Post Type A  Mile Post Type B  Mile Post Type C  Right of Way Marker  Tubular Marker  Concrete Monument to Be Set  RW Property Monument to Be Set	 Object Marker Type I  Object Marker Type II  Object Marker Type III  Caution Mode Arrow Panel  Back to Back Vertical Panel Sign  Double Direction Arrow Panel  Left Directional Arrow Panel  Right Directional Arrow Panel  Sequencing Arrow Panel  Truck Mounted Arrow Panel  Power Pole  Wood Pole  Pedestrian Push Button Post  Property Corner  Pull Box  Intelligent Transportation Pull Box  Sanitary Pump  Storm Drain Pump  Reinforced Pavement  Reinforced Concrete End Section 15 Inch  Reinforced Concrete End Section 18 Inch  Reinforced Concrete End Section 24 Inch  Reinforced Concrete End Section 30 Inch  Reinforced Concrete End Section 36 Inch  Reinforced Concrete End Section 42 Inch	 Reinforced Concrete End Section 48 Inch  Reinforced Concrete End Section 54 Inch  Reset Right of Way Marker  Reset USGS Marker  Right of Way Markers  Riser 30 Inch  Continuous Split Barrel Sample  Flight Auger Sample  Split Barrel Sample  Thinwall Tube Sample  Highway Sign  SNOW GATE 18 FT  SNOW GATE 28 FT  SNOW GATE 40 FT  Standard Penetration Test  Transformer  Inclinometer Tube  Underdrain Cleanout  Excavation Unit  Water Valve
---	--	---	--


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
4-20-11	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by
Roger Weigel,
 Registration Number
PE-2930,
 on 4/20/11 and the original document is stored at the
 North Dakota Department
 of Transportation




Multi-Directional Slip Base Assembly

Perforated Tube



Top Post Receiver
Plate - ASTM A572 grade 50
Angle Receiver - 2 1/2"x2 1/2"x3/8" ASTM A36 structural angle



Bottom Soil Stub
Tube - 3"x3"x7 gauge ASTM A500 grade B tube
Stabilizing Wing - 7 gauge H.R.P.O. ASTM A1011
Plate - ASTM A572 grade 50


Notes:

1. Slip base bolts shall be torqued as specified by the manufacturer.
2. Anchor shall have a yield strength of 43.9 KSI and tensile strength of 59.3 KSI.
3. The 4" vertical clearance is required for the anchor or breakaway base. The 4"x60" measurement shall be made above and below post location and also back and ahead of the post.
4. When used in concrete sidewalk, anchor shall be same except without the wings.
5. Four post signs shall have over 7' between the first and the fourth posts.


Telescoping Perforated Tube						
Number of Posts	Post Size in.	Wall Thickness Gauge	Sleeve Size in.	Wall Thickness Gauge	Slip Base	Anchor Size without Slip Base in.
1	2	12			No	2 1/4
1	2 1/4	12			No	2 1/2
1	2 1/2	12			(A)	3
1	2 1/2	10			Yes	
1	2 1/4	12	2	12	Yes	
1	2 1/2	12	2 1/4	12	Yes	
2	2	12			No	2 1/4
2	2 1/4	12			No	2 1/2
2	2 1/2	12			Yes	
2	2 1/2	12			Yes	
2	2 1/4	10	2	12	Yes	
2	2 1/2	12	2 1/4	12	Yes	
3 & 4	2 1/2	12			Yes	
3 & 4	2 1/2	10			Yes	
3 & 4	2 1/2	12	2 1/4	12	Yes	
3 & 4	2 1/4	12	2	12	Yes	
3 & 4	2 1/2	10	2 3/16	10	Yes	

Properties of Telescoping Perforated Tube						
Tube Size in.	Wall Thickness in.	U.S. Standard Gauge	Weight per Foot lbs.	Moment of Inertia in. ⁴	Cross Sec. Area in. ²	Section Modulus in. ³
1 1/2 x 1 1/2	0.105	12	1.702	0.129	0.380	0.172
2 x 2	0.105	12	2.416	0.372	0.590	0.372
2 1/4 x 2 1/4	0.105	12	2.773	0.561	0.695	0.499
2 3/16 x 2 3/16	0.135	10	3.432	0.605	0.841	0.590
2 1/2 x 2 1/2	0.105	12	3.141	0.804	0.803	0.643
2 1/2 x 2 1/2	0.135	10	4.006	0.979	1.010	0.785


Top Post Receiver Data Table						
Square Post Sizes (B)	A	B	C	D	E	F
2 3/16"x10 ga.	1 9/64"	2 1/2"	3 1/32"	2 5/32"	1 33/64"	1 1/8"
2 1/2"x10 ga.	1 9/32"	2 1/2"	3 5/16"	5/8"	1 21/32"	1 3/4"



Anchor Unit and Post Assembly



Multi-Directional Slip Base Anchor Unit and Post Sleeve Assembly





Bolt Retainer for Base Connection
Bolt Retainer - 1/32" Reprocessed Teflon

- (A) The breakaway base is required when the support is placed in weak soils. The Engineer shall determine if the soils are weak.
(B) The 2 3/16"x10 ga. may be inserted into 2 1/2"x10 ga. for additional wind load.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
2-28-14	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 2/28/14 and the original document is stored at the North Dakota Department of Transportation

U-Channel Post




Breakaway U-Channel Detail Alternate A

A maximum of 2 posts shall be installed within 7'.




Retainer Strap Detail



Breakaway U-Channel Splice Detail Alternate B (2.5 and 3 lb/ft)

A maximum of 3 posts shall be installed within 7'.



Breakaway U-Channel Splice Detail Alternate C (2.5 and 3 lb/ft)

A maximum of 3 posts shall be installed within 7'.

Alternate A Steps of Installation:












1. a) Drive anchor unit to within 12" of ground level.
b) Proper assembly established by lining up the bottom hole of retainer strap with the 6th hole from the top of the anchor unit.
c) Assemble strap to back of anchor unit using 5/16"x2" bolt, lock washer and nut.
d) Rotate strap 90° to left.
2. a) Drive anchor unit to 4" above ground.
b) Rotate strap to vertical position.
3. a) Place 5/16"x2" bolt, lock washer and nut in bottom of sign post to facilitate alignment of sign post with proper hole in anchor unit.
b) Alternately tighten two connector bolts.
4. Complete assembly by tightening 5/16"x2" bolt (this fastens sign post to retainer strap).
5. The base post, strap and sign post shall be properly nested. Proper nesting occurs when all flat surfaces of the base post, strap, and sign post at the bolts have full contact across the entire width.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
2-28-14	
REVISIONS	
DATE	CHANGE




This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 2/28/14 and the original document is stored at the North Dakota Department of Transportation

CONSTRUCTION SIGN DETAILS
 TERMINAL AND GUIDE SIGNS

D-704-9



ARROW DETAILS



NOTES:


(A) Arrow may be right or left of the legend to indicate construction to the right or left.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-13-13	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by
 Roger Weigel,
 Registration Number
 PE- 2930,
 on 8/13/13 and the original document is stored at the
 North Dakota Department
 of Transportation

CONSTRUCTION SIGN DETAILS
REGULATORY SIGNS


D-704-10




R1-50-24
Legend: black (non-refl)
Background: white



R11-3c-60
Legend: black (non-refl)
Background: white



R2-1a-24
Legend: black (non-refl)
Background: white



R11-4a-60
Legend: black (non-refl)
Background: white



R11-2a-48
Legend: black (non-refl)
Background: white


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-13-13	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 8/13/13 and the original document is stored at the North Dakota Department of Transportation


CONSTRUCTION SIGN DETAILS
WARNING SIGNS

WORD	LETTER SPACING
AHEAD	Standard
200 FT	Standard
350 FT	Standard
500 FT	Standard
1000 FT	Reduce 40%
1500 FT	Reduce 40%
½ MILE	Reduce 50%
1 MILE	Standard


* DISTANCE MESSAGES




W5-8-48
Legend: black (non-refl)
Background: orange




W8-54-48
Legend: black (non-refl)
Background: orange




W20-51-48
Legend: black (non-refl)
Background: orange




W21-51-48
Legend: black (non-refl)
Background: orange




W5-9-48
Legend: black (non-refl)
Background: orange




W8-55-48
Legend: black (non-refl)
Background: orange




W20-52-54
Legend: black (non-refl)
Background: orange




W22-8-48
Legend: black (non-refl)
Background: orange




W5-9-48
ARROW DETAILS



W8-53-48
Legend: black (non-refl)
Background: orange



W8-56-48
Legend: black (non-refl)
Background: orange




W21-50-48
Legend: black (non-refl)
Background: orange

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-13-13	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 8/13/13 and the original document is stored at the North Dakota Department of Transportation

BARRICADE AND CHANNELIZING DEVICE DETAILS




DELINEATOR DRUM

VERTICAL PANEL


The markings on drums shall be horizontal, circumferential, alternating orange and white retroreflective stripes 4" to 6" wide. Each drum shall have a minimum of two orange and two white stripes with the top stripe being orange. Any nonretroreflectORIZED spaces between the horizontal orange and white stripes shall not exceed 3" wide. Stripes shall not be placed on ribs or indentations in the drum. Drums shall have closed tops that will not allow collection of construction debris or other debris. Ballast shall not be placed on the top of a drum.

Markings for vertical panels shall be alternating orange and white retroreflective stripes, sloping downward in the direction vehicular traffic is to pass. Retroreflective sheeting shall be placed on both sides of panel and shall have a minimum of 270 square inches of retroreflective area facing vehicular traffic. Where the height of the retroreflective material on the vertical panel is 36 inches or more, a stripe width of 6 inches shall be used.




TRAFFIC CONE

RetroreflectORIZATION of cones more than 36" in height shall be provided by alternating orange and white retroreflective stripes. Each cone shall have a minimum of two orange and two white stripes with the top stripe being orange. Any nonretroreflectORIZED space between the orange and white stripes shall not exceed 3" wide.



TUBULAR MARKER


RetroreflectORIZATION of tubular markers more than 42" in height shall be provided by alternating four 4" to 6" wide orange and white stripes with the top stripe being orange.



FLEXIBLE DELINEATOR

INSTALLATION NOTES:

1. Drill installation holes to diameter and depth as required by manufacturer's specifications.
2. For removal, remove anchors and fill installation hole with an epoxy designed to bond to pavement surface.
3. In lieu of bolted down base, the contractor may use an 8" x 8" butyl pad or hot melt butyl. Butyl shall be removed as close as possible to pavement surface.




BARRICADE BLADE DETAIL

ELEVATION VIEW

BARRICADE ASSEMBLY DETAIL (Aluminum Barricade Rails)

NOTE: This is the only type of rail acceptable for use with this barricade assembly.




ELEVATION VIEW


BARRICADE ASSEMBLY DETAIL (Wood or Plastic Rails)

SIDE VIEW

NOTE: Markings for barricades shall be alternating orange and white retroreflective stripes, sloping downward in the direction traffic is to pass. Retroreflective sheeting shall be placed on both sides of the rails and shall have a minimum of 270 square inches of visible retroreflective area facing vehicular traffic. When the barricade length is less than 36", the rail stripe width shall be 4".




TYPE I BARRICADE




TYPE II BARRICADE

BARRICADE RAIL DETAILS



TYPE III BARRICADE



REFLECTOR DETAIL

DELINEATORS

MINIMUM BALLAST (For each side of barricade support)

Without Sign	4 - 25 lb sandbags
With Sign	6 - 25 lb sandbags


Note: The number of sandbags are based on a wind speed of 55 MPH. The sandbags are assumed to be placed at or near the ends of the skids.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-3-13	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 10/3/13 and the original document is stored at the North Dakota Department of Transportation

CONSTRUCTION SIGN PUNCHING AND MOUNTING DETAILS


Note: Signs placed in sections with curb shall have a minimum horizontal clearance of 2' from the face of the curb to the near edge of the sign.




TYPICAL SECTION
(48" x 48" diamond warning sign shown)




24" x 24" ROUTE MARKER ASSEMBLY




36" x 36" ROUTE MARKER ASSEMBLY




18" x 18" DIAMOND SIGN




48" x 48" DIAMOND SIGN
(with 30" x 30" secondary sign)




48" x 48" DIAMOND SIGN
(with 30" x 24" secondary sign)




R1-2-60 - YIELD SIGN




W14-3-64 - PENNANT SIGN




R1-1-48 - STOP SIGN
(with R6-1-54 sign as required)




R1-1-48 - STOP SIGN
(with R1-50-24 sign as required)




48" x 48" SIGN
(with R6-1-54 sign as required)




48" x 48" SIGN
(with R2-1a-24 sign as required)




24" x 36" SIGN




30" x 24" SIGN




108" x 48" SIGN




96" x 48" SIGN




72" x 36" SIGN




72" x 24" SIGN




60" x 24" SIGN



48" x 24" SIGN



PORTABLE SIGN SUPPORT
LOW-MOUNTING HEIGHT



PORTABLE SIGN SUPPORT
HIGH-MOUNTING HEIGHT

NOTES:

- Sign Supports:** Supports shall be galvanized or painted. Minimum post sizes are 2.5 lb/ft u-channel or 2" x 2" x 12 gauge steel perforated tube, except where noted. When installing signs on u-channel, the minimum post size for assemblies containing a secondary sign is 3.0 lb/ft. Post sizes are based on a wind speed of 55 MPH.

Signs over 50 square feet should be installed on 2 1/2" x 2 1/2" perforated tube supports as a minimum.

Guy wires shall not be attached to sign supports. Wind beams may be attached to u-posts behind the sign panels.
- Sign Panels:** Provide sign panels made of 0.100" aluminum, 1/2" plywood, or other approved material, except where noted. All holes to be punched round for 3/8" bolts.
- Alternate Messages:** The signs that have alternate messages may have these alternate messages placed on a reflectorized plate (without a border) and installed and removed as required. (i.e. "Left" and "Right" message on a lane closure sign)
- Route Marker Auxiliary Signs:** Provide route marker auxiliary signs, such as the cardinal direction and directional arrows, with a background and legend that match the route marker they are used with:

Interstate - white legend on blue background
Interstate Business Loop - white legend on green background
US and State - black legend on white background
County - yellow legend on blue background
- Vertical Clearance:** Install signs with a vertical clearance of 5'-0" (see TYPICAL SECTION.) In areas where parking or pedestrian movements are likely or the view of the sign may be obstructed, install signs with a vertical clearance of 7'-0" from the top of the curb or from the near edge of the driving lane in absence of a curb.

The vertical clearance to secondary signs is 1'-0" less than the vertical clearance as stated above.

Large signs having an area exceeding 50 square feet shall have a minimum clearance of 7'-0" from the ground at the post.
- Portable Signs:** Provide portable signs that meet the vertical clearance as stated above. Use portable signs when it is necessary to place signs within the pavement surface.

When portable signs are used for 5 days or less, low-mounting height (minimum 12" vertical clearance) sign supports may be used as long as the view of the sign is not obstructed. Time delays caused by unforeseen circumstances, such as equipment breakdown, rain, subgrade failures, etc., will not accrue towards the 5 day period. The R9-8 through R9-11a series, W1-5 through W1-8 series, M4-10, and E5-1 may be used for longer than 5 days.

Signs mounted to the portable sign supports shown in the LOW-MOUNTING HEIGHT and HIGH-MOUNTING HEIGHT Details shall have a maximum surface area of 16 square feet.

MINIMUM BALLAST
(For each side of sign support base)

Sign Panel Mounting Height (ft)	Number of 25 lb sandbags for 4' x 4' sign panel
1'	6
5'	8
7'	10


Note: The number of sandbags are based on a wind speed of 55 MPH. The sandbags are assumed to be placed at or near the ends of the skids.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-4-13	
REVISIONS	
DATE	CHANGE
11-14-13	Revised Note 6.


This document was originally issued and sealed by
Roger Weigel,
Registration Number
PE-2930,
on 11/14/13 and the original document is stored at the North Dakota Department of Transportation

SHORT TERM URBAN DETOUR AND LANE CLOSURE ON A DIVIDED HIGHWAY LAYOUTS

D-704-23



TYPE Q
DETOUR FOR A CLOSED STREET
 Where city streets are used for detouring traffic.
 Urban projects do not require the G20-55-96 and R2-1a-24 signs.



TYPE P
STATIONARY LANE CLOSURE ON A DIVIDED HIGHWAY
 4 lane divided roadway where 1/2 of roadway is closed.
 Short-term (more than 1 hour within a single daylight period.)

- Notes
- Variables
 - S = Numerical value of speed limit or 85th percentile.
 - W = The width of taper
 - L = Minimum length of taper, or $S \times W$ for freeways, expressways, and all other roads with speeds of 45 mph or greater, or $W \times S^2 / 60$ for urban, residential, and other streets with speeds of 40 mph or less.
 - Barricades placed on roadway shall be on a moveable assembly. Signs placed on the roadway shall be placed on skid mounted assemblies.
 - Delinicator drums used for tapering traffic shall be spaced at dimension "S". Delinicator drums or tubular markers used for tangents shall be spaced at 2 times "S".
 - Sequencing Arrow Panels
 - Panels should normally be placed at the beginning of the taper. Where shoulder width does not provide sufficient room the panel should be moved closer to the work area so that it can be placed on the roadway surface.
 - Type A shall be used on roadways with slow moving traffic speeds and low volume (25 mph or less and 750 ADT or less).
 - Type B shall be used on roadways with moderate traffic speeds and volumes (40 mph or less and 5000 ADT or less).
 - Type C shall be used on roadways with high traffic speeds and volumes (over 40 mph or over 5000 ADT).
 - The speed limit shall be re-established. The exact speed limit shall be determined in the field, dependent on location and conditions.
 - The reduced speed limit shall be determined dependent on the in place speed limit before construction. The speed limit reduction should not exceed 10 mph below the existing speed limit, unless the design speed of the work zone feature has been reduced below the 10 mph. In this case, the speed limit reduction shall not exceed 30 MPH. Where speed limits are to be reduced more than 30 MPH, a second speed limit sign shall be installed with the desired speed reduction but shall not exceed 30 MPH. The second speed limit sign shall be placed at 1/2 B.
 - When warning signs are used in urban areas and the signs are not portable, flags shall be installed. The flags shall be 24 inches square, mounted perpendicular to the edges of the diamond sign, and at such a distance above the edge so that when the flag is limp it will not touch the sign. Rural areas will not require flags.
 - Existing speed limit signs within a reduced speed zone shall be covered.
 - Obliterated or covered pavement marking shall be paid for as Obliteration of Pavement Marking. The covering shall be approved by the engineer.
 - Intersection control for Type Q may have to be changed on detour. The Engineer in the field shall determine what control is necessary.
 - Where necessary, safe speed to be determined by the Engineer. When parking is present, signs shall be placed so they are entirely visible above parked vehicles or placed at the edge of the parking area so they are visible to oncoming traffic. These signs may be skid mounted when placed on the roadway surface.
 - The contractor has the option of using portable sign supports in lieu of post mounted signs in accordance with the NDDOT Standard Specifications.

Longitudinal Buffer Space	
Speed (mph)	Length Min (feet)
20	115
25	155
30	200
35	250
40	305
45	360
50	425
55	495
60	570
65	645
70	730
75	820

Road Type	Distance Between Signs Min. (ft)		
	A	B	C
Urban - Low Speed (30 mph or less)	150	150	150
Urban - Low Speed (over 30 to 40 mph)	280	280	280
Urban - High Speed (over 40 mph to 50 mph)	360	360	360
Rural - High Speed (over 50 mph to 65 mph)	720	720	720
Urban Expressway and Freeway (55 mph to 60 mph)	850	1350	2200
Rural Expressway and Freeway (70 mph to 75 mph)	1000	1500	2640
Interstate/4-Lane Divided (Maintenance and Surveying)	750	1000	1500

KEY

	Type III barricade		Work area
	Sign		Sequencing arrow panel
	Delineator Drum		Tubular Markers

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-27-13	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by
 Roger Weigel
 Registration Number
 PE-2930,
 on 09/27/13 and the original document is stored at the
 North Dakota Department
 of Transportation