

DESIGN DATA			
Traffic	Average Daily		
Current 2013	Pass: 3,255	Trucks: 2,095	Total: 5,350
Forecast 2033	Pass: 5,340	Trucks: 3,645	Total: 8,985
Clear Zone Distance: 34		Design Speed: 65	
Minimum Sight Dist. for Stopping: 645		Bridges: N/A	
Sight Dist. for No Passing Zone: 1100			
Pavement Design Life 20 (years)			
Design Accumulated One-way ESALs:			

STATE	PROJECT NO.	PCN	SECTION NO.	SHEET NO.
ND	H-7-085(097)124	20571	1	1

**JOB # 47**  
**NORTH DAKOTA**  
**DEPARTMENT OF TRANSPORTATION**

H-7-085(097)124



McKenzie County  
 2 Miles South Of Long X Bridge

Drainage Improvements  
 Erosion Repair/Soil Stabilization

**GOVERNING SPECIFICATIONS:**

2014 Standard Specifications adopted by the North Dakota Department of Transportation and the Supplemental Specifications effective on the date the project is advertised.

PROJECT NUMBER \ DESCRIPTION	NET MILES	GROSS MILES
H-7-085(097)124 Drainage Improvements & Erosion Repair	0.2	1.5



**STATE COUNTY MAP**

**DESIGNERS**  
 Leon Eckroth /s/

APPROVED DATE 8/27/2014  
 Roger Weigel /s/  
 OFFICE OF PROJECT DEVELOPMENT  
 ND DEPARTMENT OF TRANSPORTATION

I hereby certify that the attached plans were prepared by me or under my direct supervision and that I am a duly registered professional engineer under the laws of the state of ND.  
 APPROVED DATE 8/27/2014  
 James Douglas Rath /s/  
 NDDOT Design Division

This document was originally issued and sealed by James Douglas Rath Registration Number PE- 4288, on 08/27/2014 and the original document is stored at the North Dakota Department of Transportation

**TABLE OF CONTENTS**

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	H-7-085(097)124	2	1

**INDEX OF DRAWINGS**

**LIST OF STANDARD DRAWINGS**

**SECTION**   **SHEET**   **DESCRIPTION**

**STANDARD NO.**   **DESCRIPTION**

<b>1</b>	<b>1</b>	Title Sheet
<b>2</b>	<b>1</b>	Table of Contents
<b>4</b>	<b>1</b>	Scope of Work
<b>6</b>	<b>1 - 2</b>	Notes
	<b>3</b>	Environmental Commitments
<b>8</b>	<b>1</b>	Quantities
<b>20</b>	<b>1 - 3</b>	General Details
<b>40</b>	<b>1 - 2</b>	Removals
<b>51</b>	<b>1</b>	Allowable Pipe List
<b>55</b>	<b>1</b>	Drainage Layouts
<b>60</b>	<b>1 - 3</b>	Plan & Profile
<b>76</b>	<b>1-2</b>	Temporary Erosion Control
<b>77</b>	<b>1-2</b>	Permanent Erosion Control
<b>100</b>	<b>1</b>	Work Zone Traffic Control
<b>200</b>	<b>1 - 6</b>	Cross Sections

D-101-1, 2, 3	NDDOT Abbreviations
D-101-10	NDDOT Utility Company Abbreviations
D-101-20,21	Linestyles
D-101-30, 31, 32	Symbols
D-255-2	Erosion And Siltation Control - Erosion Control Blanket Installation
D-256-1	Erosion And Siltation Controls
D-260-1	Erosion And Siltation Controls - Silt Fence
D-261-1	Erosion Control Fiber Roll Placement Details
D-704-5	Contractor Sign Detail
D-704-7	Breakaway Systems For Construction Zone Signs - Perforated Tube
D-704-8	Breakaway Systems For Construction Zone Signs - U-Channel Post
D-704-9	Construction Sign Details - Terminal And Guide Signs
D-704-10	Construction Sign Detail - Regulatory Signs
D-704-11	Construction Sign Detail - Warning Signs
D-704-12	Shoulder Closure Tapers
D-704-13	Barricade And Channelizing Device Details
D-704-14	Construction Sign Punching And Mounting Details
D-704-19	Road Closure And Lane Closure On A Two Way Road Layouts
D-704-22	Construction Truck And Temporary Detour Layouts
D-704-26	Miscellaneous Sign Layouts
D-704-50	Portable Sign Support Assembly
D-708-6	Erosion And Siltation Controls - Median Or Ditch Inlet Protection
D-714-1	Reinforced Concrete Pipe Culvert And End Section
D-714-22	Concrete Pipe Or Precast Concrete Box Culvert Ties
D-714-27	Pipe Excavation And Installation Detail For Longitudinal Mainline Pipe Or Pipe Not Under The Roadway
D-722-1A	Inlet - Catch Basin
D-752-1	Standard Barbed Wire Fence

**Special Provisions**

03(14) Temporary Erosion And Sediment BMP



**NOTES**

**GENERAL NOTES**

- 100-P01 SUPPLEMENTAL DESIGN DATA: Supplemental design data consisting of electronic survey files or models used for GPS controlled equipment are not available and will not be created for this project.
- 203-P01 HAUL: No average haul has been computed for this project.
- 203-P02 COMMON EXCAVATION-TYPE C: If water is present at either location on the inlet side, it will be the contractor's responsibility to dewater. Approximately 4050 CY of material is to be removed from the inlet side of both culverts at locations 1 and 2. This material may be wet or saturated. This material may be used as embankment material at Location 1 if it is deemed suitable by the engineer. Any excess material removed and not needed as embankment at Location 2 will become the property of the contractor and be disposed of off the right of way. The contractor will be responsible to obtain any additional material for embankment from outside the right of way, if needed. All work to dewater, excavate material from the inlet side, place embankment material, or haul in extra material from another location will be paid for by the unit price bid for "Common Excavation-Type C".
- 251-P01 TEMPORARY COVER CROP: The following temporary seed mixture shall be used for all newly and previously disturbed embankment areas, except for areas with TRM Type 1. All temporary seeding shall be drilled in and covered with straw mulch for the winter.
- |                            |                  |
|----------------------------|------------------|
| Barley                     | 50.0 PLS lbs/ac  |
| Annual Rye grass (Italian) | 10.0 PLS lbs/ac. |
| Turnip (Pasja)             | 1.0 PLS lbs/ac   |
| Forage Radish              | 2.0 PLS lbs/ac   |
| Annual clover (Persian)    | 1.0 PLS lbs/ac   |
- Fertilize cover crop with 80 lbs/ac of 28-29-0 to promote root development. Fertilizer to be placed with the cover crop seed (not spread on surface)
- Cover crop seeded immediately after shaping and prior to straw mulch placement.

251-P02 SEEDING CLASS III: The following seed mixture shall be used for all newly and previously disturbed embankment areas. It shall be drilled in and either covered with TRM Type 1 or the Hydraulic Mulch. Except for the areas covered by TRM Type 1, all permanent seeding will be done between May 1 – June 15, 2015. Seed sources will probably need to come from multiple vendors. ½ Seed to be drilled and ½ applied in conjunction with flexible growth medium.

Species*	Variety	PLS Lbs./ac in mixture
Blue Grama	Bad River	1.00
Green Needlegrass	Lordom	1.20
Sideoats Grama	Killdeer or Pierre	1.8
Western Wheatgrass	Rodan or Rosana	4.00
Slender Wheatgrass	Pryor or Revenue	5.0
Prairie Junegrass	Common	0.15
Little Bluestem	Badlands	0.80
Fourwing Saltbush, Dewinged	Wytana	0.60
Inland Saltgrass		1.4
Rubber Rabbitbush		0.10
Alkali sacaton		0.5
Canada Wildrye	Mandan	3.3
	Total	19.85

This document was originally issued and sealed by Brian J. Rosin, Registration Number PE-2928, on 8/27/2014 and the original document is stored at the North Dakota Department of Transportation.

**NOTES**

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	H-7-085(097)124	6	2

704-P01 TRAFFIC CONTROL: The traffic control for the construction of this project shall consist of shoulder work and flagging. Traffic control devices shall comply with the following Standard Drawings.

D-704-7, 8, 9, 10, 11, 13, and 14 as applicable.

D-704-19, Type F: For temporary lane closures.

D-704-22, Layouts Type K and L: For construction trucks hauling materials.

D-704-24, Layouts Type R: For shoulder preparation, seeding and mulching. Tubular Markers will be used in-place of the cones as shown on the Standard Drawing.

D-704-50: Portable Sign Support Assembly.

752-P01 TEMPORARY FENCE: All temporary fence shall be three strands of barb wire and steel posts. The pay item "Temporary Fence" shall include all costs to provide, place, maintain, and remove the temporary fence.

This document was originally issued and sealed by Brian J. Rosin, Registration Number PE-2928, on 8/27/2014 and the original document is stored at the North Dakota Department of Transportation.

## ENVIRONMENTAL COMMITMENTS

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	H-7-085(097)124	6	3

**ENVIRONMENTAL COMMITMENTS:** The North Dakota Department of Transportation and the Federal Highway Administration have made several environmental commitments to various agencies and the public to secure approval of this project. The environmental commitments are as follows:

Based on the NEPA documentation, no additional permits or environmental commitments have been identified beyond what is covered by the NDDOT's Standard Specification of Road and Bridge Construction.

Wetland Number	Cowardin Classification	Wetland Type	Wetland Size (acres)	Wetland Feature	USACE Jurisdictional Wetlands	Impacts to Wetlands	
						Temp.	Perm.
<b>**NO WETLANDS PRESENT**</b>							
<b>TOTALS:</b>			<b>0.00</b>		<b>0.00</b>	<b>0.00</b>	


\*A wetland Jurisdictional Determination was issued by the USACE on 01/23/2014; NWO-2013-2541-BIS.

# ESTIMATE OF QUANTITIES

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
<b>ND</b>	H-7-085(097)124	<b>8</b>	<b>1</b>

SPEC CODE	ITEM DESCRIPTION	UNIT	MAINLINE	TOTAL
-----	-----	-----	-----	-----
103	0100 CONTRACT BOND	L SUM	0.25	0.25
201	0330 CLEARING & GRUBBING	L SUM	0.25	0.25
202	0170 REMOVAL OF CULVERTS-ALL TYPES & SIZES	LF	16	16
203	0103 COMMON EXCAVATION-TYPE C	CY	4,050	4,050
216	0100 WATER	M GAL	100	100
230	0110 RESHAPING INSLOPE	MILE	0.5	0.5
251	0300 SEEDING CLASS III	ACRE	9.5	9.5
251	2000 TEMPORARY COVER CROP	ACRE	9.5	9.5
251	3000 FERTILIZER	ACRE	9.5	9.5
253	0101 STRAW MULCH	ACRE	15	15
253	0201 HYDRAULIC MULCH	ACRE	9.2	9.2
255	0201 TRM TYPE 1	SY	4,750	4,750
256	0200 RIPRAP GRADE II	CY	105	105
260	0200 SILT FENCE SUPPORTED	LF	2,160	2,160
260	0201 REMOVE SILT FENCE SUPPORTED	LF	2,160	2,160
261	0112 FIBER ROLLS 12IN	LF	3,740	3,740
261	0113 REMOVE FIBER ROLLS 12IN	LF	1,870	1,870
702	0100 MOBILIZATION	L SUM	0.25	0.25
704	0100 FLAGGING	MHR	300	300
704	1000 TRAFFIC CONTROL SIGNS	UNIT	1,402	1,402
704	1060 DELINEATOR DRUMS	EA	16	16
704	1067 TUBULAR MARKERS	EA	37	37
709	0155 GEOSYNTHETIC MATERIAL TYPE RR	SY	210	210
714	0820 PIPE CONC REINF 30IN CL III	LF	7	7
714	1105 PIPE CONC REINF 48IN CL III	LF	16	16
714	9660 REMOVE & RELAY END SECTION-ALL TYPE & SIZES	EA	3	3
722	3480 CASTING CATCH BASIN 9IN BEEHIVE	EA	2	2
752	0905 TEMPORARY FENCE	LF	200	200
752	0922 FENCE REMOVE & RESET	LF	200	200

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	H-7-085(097)124	20	1





This document was originally issued and sealed by  
 Brian J. Rosin  
 Registration Number  
 PE- 2928,  
 on 8/27/2014 and the original document is stored at the  
 North Dakota Department  
 of Transportation

Culvert Inlet Detail

Drainage Improvements/Erosion Repairs

2 Mi South of Long-X Bridge RP 124-125.5



Culvert Diameter Inches	RR Fabric SY	Riprap CY
48"	100	50
60"	110	55

Culvert Diameter Inches	L Feet	W1 Feet	W2 Feet	Riprap Depth, D Inches	Riprap Grade
48"	16	12	23	36	II
60"	20	15	29	24	II

This document was originally issued and sealed by  
 Brian J. Rosin  
 Registration Number  
 PE- 2928,  
 on 8/27/2014 and the original document is stored at the  
 North Dakota Department  
 of Transportation

RipRap Detail

Drainage Improvements/Erosion Repairs



2 Mi South of Long-X Bridge RP 124-125.5

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	H-7-085(097)124	20	3

INLET / MANHOLE T-SECTION

Catch Basins  
(D-722-1A)

Beehive  
(6" OR 9")



T-Section Detail

Notes:

All costs for the labor, equipment and material necessary to construct the T-Section shall be included in the cost of "Pipe Conc. Reinf 48in CI III".

This document was originally issued and sealed by  
 Brian J. Rosin  
 Registration Number  
 PE- 2928,  
 on 8/27/2014 and the original document is stored at the  
 North Dakota Department  
 of Transportation



T-Section Detail

Drainage Improvements/ Erosion Repairs  
 2 Mi South of Long-X Bridge RP 124-125.5

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	H-7-085(097)124	40	1

Location 1

Approximately 325 CY of Silt to be Removed  
at the Inlet Side of Location 1




This document was originally issued and sealed by  
Brian J. Rosin  
Registration Number  
PE- 2928,  
on 8/27/2014 and the original document is stored at the  
North Dakota Department  
of Transportation

Removals  
Location 1  
  
Drainage Improvements/Erosion Repairs  
2 Mi South of Long-X Bridge RP 124-125.5

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	H-7-085(097)124	40	2

Location 2

Approximately 3725 CY of Silt to be Removed at the Inlet Side of Location 2





This document was originally issued and sealed by  
 Brian J. Rosin  
 Registration Number  
 PE- 2928,  
 on 8/27/2014 and the original document is stored at the  
 North Dakota Department  
 of Transportation

Removals  
 Location 2  
 Drainage Improvements/Erosion Repairs  
 2 Mi South of Long-X Bridge RP 124-125.5

STATE	PROJECT NUMBER	SECTION NO.	SHEET NO.
ND	H-7-085(097)124	55	1

**Manhole Data**


Manhole No.	4 - 72 In.		
Sta.	6609+69.25 - 170.97' Rt. (Prop CL - Hwy 85)		
Top of Riser Elev.	2053.34		
Base Elev.	2041.23		
Invert Elev.	2042.5		
Riser	12.12 ft		
-----			
48 In. RCP	W	2047.5	
48 In Conduit	E	2042.5	
-----			
Manhole No.	5 - 72 In.		
Sta.	6610+21.48 - 264.63' Rt. (Prop CL - Hwy 85)		
Top of Riser Elev.	2029.5		
Base Elev.	2011.9		
Invert Elev.	2012		
Riser	17.6 ft		
-----			
48 In. RCP	W	2022.0	
60 In CSP	NE	2012.0	





This document was originally issued and sealed by  
 Randall Sandvig  
 Registration Number  
 PE-8783,  
 on 05/15/2014 and the original document is stored at the  
 North Dakota Department  
 of Transportation

**Centerline Pipe**  
**Existing Manhole and Pipe Details**  
 STA 6609+72  
 US 85





STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	H-7-085(097)124	60	1





This document was originally issued and sealed by  
 Brian J. Rosin  
 Registration Number  
 PE- 2928,  
 on 8/27/2014 and the original document is stored at the  
 North Dakota Department  
 of Transportation

Plan & Profile  
 Location 1  
 Drainage Improvements/Erosion Repairs  
 2 Mi South of Long-X Bridge RP 124-125.5

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	H-7-085(097)124	60	2

Removal of Culverts - All Types & Sizes	
6549+67 Lt	8 LF
Remove & Relay End Section - All Types & Sizes	
6549+67 Rt & Lt	2 EA
Casting Catch Basin 9IN Beehive	
6549+67 Lt	1 EA




This document was originally issued and sealed by  
 Brian J. Rosin  
 Registration Number  
 PE- 2928,  
 on 8/27/2014 and the original document is stored at the  
 North Dakota Department  
 of Transportation

Plan & Profile  
 Location 1  
 Drainage Improvements/Erosion Repairs  
 2 Mi South of Long-X Bridge RP 124-125.5



STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	H-7-085(097)124	76	1

Silt Fence Supported	
6550+00 Lt	600 LF
6550+00 Rt	760 LF
Fiber Rolls 12 IN - Temporary	
6550+00 Lt	360 LF
6550+00 Rt	800 LF
Remove Silt Fence Supported	
6550+00 Lt	600 LF
6550+00 Rt	760 LF
Remove Fiber Rolls 12 IN	
6550+00 Lt	360 LF
6550+00 Rt	800 LF




- x- - - Silt Fence
  - |—|—|— Fiber Rolls
  - [Hatched Box] Temporary Seeding
- Sec 13  
T-147-N  
R-99-W

This document was originally issued and sealed by  
 Brian J. Rosin  
 Registration Number  
 PE- 2928,  
 on 8/27/2014 and the original document is stored at the  
 North Dakota Department  
 of Transportation

Temporary Erosion Control  
 Location 1  
 Drainage Improvements/Erosion Repairs  
 2 Mi South of Long-X Bridge RP 124-125.5

Silt Fence Supported	
6550+00 Lt	400 LF
6550+00 Rt	400 LF
Fiber Rolls 12 IN - Temporary	
6550+00 Lt	260 LF
6550+00 Rt	450 LF
Remove Silt Fence Supported	
6610+00 Lt	400 LF
6610+00 Rt	400 LF
Remove Fiber Rolls 12 IN	
6610+00 Lt	260 LF
6610+00 Rt	450 LF



- x- - - - Silt Fence
- — — — Fiber Rolls
- ▨ Temporary Seeding

This document was originally issued and sealed by  
 Brian J. Rosin  
 Registration Number  
 PE- 2928,  
 on 8/27/2014 and the original document is stored at the  
 North Dakota Department  
 of Transportation

Temporary Erosion Control  
 Location 2  
 Drainage Improvements/Erosion Repairs  
 2 Mi South of Long-X Bridge RP 124-125.5


STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	H-7-085(097)124	77	1

TRM Type 1	
6550+00 Rt	3750 SY
RipRap Grade II	
6550+00 Rt	50 CY
Geosynthetic Material Type RR	
6550+00 Rt	100 SY
Fiber Rolls 12 IN - Permanent	
6550+00 Lt	360 LF
6550+00 Rt	800 LF
Seeding Class III	
Sta. 6550+00 Lt	4.7 AC
Sta. 6550+00 Rt	2.4 AC
Hydraulic Mulch	
Sta. 6550+00 Lt	4.7 AC
Sta. 6550+00 Rt	2.4 AC


- x- Silt Fence
- Fiber Rolls
- Permanent Seeding
- TRM Area

This document was originally issued and sealed by  
 Brian J. Rosin  
 Registration Number  
 PE- 2928,  
 on 8/27/2014 and the original document is stored at the  
 North Dakota Department  
 of Transportation

Permanent Erosion Control  
 Location 1  
 Drainage Improvements/Erosion Repairs  
 2 Mi South of Long-X Bridge RP 124-125.5



STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	H-7-085(097)124	77	2



RipRap Grade II	
6550+00 Rt	55 CY
Geosynthetic Material Type RR	
6550+00 Rt	110 SY
Fiber Rolls 12 IN - Permanent	
6610+00 Lt	260 LF
6610+00 Rt	450 LF
Seeding Class III	
6610+00 Lt	1.7 AC
6610+00 Rt	0.7 AC
Hydraulic Mulch	
6610+00 Lt	1.7 AC
6610+00 Rt	0.7 AC

- x- Silt Fence
- Fiber Rolls
- Permanent Seeding


This document was originally issued and sealed by Brian J. Rosin, Registration Number PE- 2928, on 8/27/2014 and the original document is stored at the North Dakota Department of Transportation.

Permanent Erosion Control  
 Location 2  
 Drainage Improvements/Erosion Repairs  
 2 Mi South of Long-X Bridge RP 124-125.5




Location 1  
Cross Sections

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	H-7-085(097)124	200	1




Location 1  
Cross Sections

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	H-7-085(097)124	200	2




Location 1  
Cross Sections

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	H-7-085(097)124	200	3




Location 2  
Cross Sections

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	H-7-085(097)124	200	4




Location 2  
Cross Sections

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	H-7-085(097)124	200	5



Location 2  
Cross Sections

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	H-7-085(097)124	200	6



NDDOT ABBREVIATIONS

? This is a special text character used in the labeling of existing features. It indicates a feature that has an unknown characteristic, potentially based on: lack of description, location accuracy or purpose.

Abn abandoned  
 Abut abutment  
 Ac acres  
 Adj adjusted  
 Aggr aggregate  
 Ahd ahead  
 ARV air release valve  
 Align alignment  
 Al alley  
 Alt alternate  
 Alum aluminum  
 ADA Americans with Disabilities Act  
 A ampere  
 & and  
 Appr approach  
 Approx approximate  
 ACP asbestos cement pipe  
 Asph asphalt  
 AC asphalt cement  
 Assmd assumed  
 @ at  
 Atten attenuation  
 ATR automatic traffic recorder  
 Ave Avenue  
 Avg average  
 ADT average daily traffic  
 Az azimuth  
 Bk back  
 BF back face  
 Bs backsight  
 Balc balcony  
 B Wire barbed wire  
 Barr barricade  
 Btry battery  
 Brg bearing  
 BI beehive inlet  
 Beg begin  
 BM bench mark  
 Bkwy bikeway  
 Bit bituminous  
 Blk block  
 Bd Ft board feet  
 BH bore hole  
 BS both sides  
 Bot bottom  
 Blvd Boulevard  
 Bndry boundary  
 BC brass cap  
 Brkwy breakaway  
 Br bridge  
 Bldg building

BV butterfly valve  
 Byp bypass  
 C Gdrl cable guardrail  
 Calc calculate  
 Cd candela  
 CIP cast iron pipe  
 CB catch basin  
 CRS cationic rapid setting  
 C Gd cattle guard  
 C To C center to center  
 Cl or C centerline  
 Cm centimeter  
 Ch chain  
 Chnlk chain-link  
 Ch Blk channel block  
 Ch Ch channel change  
 Chk check  
 Chsld chiseled  
 Cir circle  
 Cl class  
 Cl clay  
 Cl F clay fill  
 Cl Hvy clay heavy  
 Cl Lm clay loam  
 Clnt clean-out  
 Clr clear  
 Cl&gr clearing & grubbing  
 Co S coal slack  
 Comb. combination  
 Coml commercial  
 Compr compression  
 CADD computer aided drafting & design  
 Conc concrete  
 Cond conductor  
 Const construction  
 Cont continuous  
 CSB continuous split barrel sample  
 Contr contraction  
 Contr contractor  
 CP control point  
 Coord coordinate  
 Cor corner  
 Corr corrected  
 CAES corrugated aluminum end section  
 CAP corrugated aluminum pipe  
 CMES corrugated metal end section  
 CMP corrugated metal pipe  
 CPVCP corrugated poly-vinyl chloride pipe  
 CSES corrugated steel end section  
 CSP corrugated steel pipe  
 C coulomb  
 Co County  
 Crse course  
 C Gr course gravel  
 CS course sand

Ct Court  
 Xarm cross arm  
 Xbuck cross buck  
 Xsec cross sections  
 Xing crossing  
 Xrd Crossroad  
 Crn crown  
 CF cubic feet  
 M3 cubic meter  
 M3/s cubic meters per second  
 CY cubic yard  
 Cy/mi cubic yards per mile  
 Culv culvert  
 C&G curb & gutter  
 CI curb inlet  
 CR curb ramp  
 CS curve to spiral  
 C cut  
 Dd Ld dead load  
 Defl deflection  
 Defm deformed  
 Deg or D degree  
 DInt delineate  
 DIntr delineator  
 Depr depression  
 Desc description  
 Det detail  
 DWP detectable warning panel  
 Dtr detour  
 Dia diameter  
 Dir direction  
 Dist distance  
 DM disturbed material  
 DB ditch block  
 DG ditch grade  
 Dbl double  
 Dn down  
 Dwg drawing  
 Dr drive  
 Drwy driveway  
 DI drop inlet  
 D dry density  
 Ea each  
 Esmt easement  
 E East  
 EB Eastbound  
 Elast elastomeric  
 EL electric locker  
 E Mtr electric meter  
 Elec electric/al  
 EDM electronic distance meter  
 Elev or El elevation  
 Ellipt elliptical  
 Emb embankment  
 Emuls emulsion/emulsified

ES end section  
 Engr engineer  
 ESS environmental sensor station  
 Eq equal  
 Eq equation  
 Evgr evergreen  
 Exc excavation  
 Exst existing  
 Exp expansion  
 Expy Expressway  
 E external of curve  
 Extru extruded  
 FOS factor of safety  
 F Fahrenheit  
 FS far side  
 F farad  
 Fed Federal  
 FP feed point  
 Ft feet/foot  
 Fn fence  
 Fn P fence post  
 FO fiber optic  
 FB field book  
 FD field drive  
 F fill  
 FAA fine aggregate angularity  
 FS fine sand  
 FH fire hydrant  
 Fl flange  
 Flrd flared  
 FES flared end section  
 F Bcn flashing beacon  
 FA flight auger sample  
 FL flow line  
 Ftg footing  
 FM force main  
 Fs foresight  
 Fnd found  
 Fdn foundation  
 Frac fractional  
 Frwy freeway  
 Frt front  
 FF front face  
 F Disp fuel dispenser

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 07/01/14 and the original document is stored at the North Dakota Department of Transportation

NDDOT ABBREVIATIONS

FFP	fuel filler pipes	IP	iron Pipe	M	mega	Ped	pedestrian
FLS	fuel leak sensor	Jt	joint	Mer	meridian	PPP	pedestrian pushbutton post
Furn	furnish/ed	J	joule	M	meter	Pen.	penetration
Gal	gallon	Jct	junction	M/s	meters per second	Perf	perforated
Galv	galvanized	K	kelvin	M	mid ordinate of curve	Per.	perimeter
Gar	garage	Kn	kilo newton	Mi	mile	PL	pipeline
Gs L	gas line	Kpa	kilo pascal	MM	mile marker	PI	place
G Reg	gas line regulator	Kg	kilogram	MP	mile post	P&P	plan & profile
GMV	gas main valve	Kg/m3	kilogram per cubic meter	MI	milliliter	PL	plastic limit
G Mtr	gas meter	Km	kilometer	Mm	millimeter	PI	plate
GSV	gas service valve	K	Kip(s)	Mm/hr	millimeters per hour	Pt	point
GVP	gas vent pipe	LS	Land Surveyor (licensed)	Min	minimum	PCC	point of compound curve
GV	gate valve	LSIT	Land Surveyor In Training	Misc	miscellaneous	PC	point of curve
Ga	gauge	Ln	lane	Mon	monument	PI	point of intersection
Geod	geodetic	Lg	large	Mnd	mound	PRC	point of reverse curvature
GIS	Geographical Information System	Lat	latitude	Mtbl	mountable	PT	point of tangent
G	giga	Lt	left	Mtd	mounted	POC	point on curve
GPS	Global Positioning System	L	length of curve	Mtg	mounting	POT	point on tangent
Gov	government	Lens	lenses	Mk	muck	PE	polyethylene
Grd	graded/grade	Lvl	level	Mun	municipal	PVC	polyvinyl chloride
Gr	gravel	LB	level book	N	nano	PCC	Portland Cement concrete
Grnd	ground	LvIng	leveling	NGS	National Geodetic Survey	Lb or #	pounds
GWM	ground water monitor	Lht	light	NS	near side	PP	power pole
Gdrl	guardrail	LP	light pole	Neop	neoprene	Preempt	preemption
Gtr	gutter	Ltg	lighting	Ntwk	network	Prefab	prefabricated
H Plg	H piling	Lig Co	lignite coal	N	newton	Prfmd	performed
Hdwl	headwall	Lig Sl	lignite slack	N	North	Prep	preparation
Ha	hectare	LF	linear foot	NE	North East	Press.	pressure
Ht	height	Liq	liquid	NW	North West	PRV	pressure relief valve
HI	height of instrument	LL	liquid limit	NB	Northbound	Prestr	prestressed
Hel	helical	L	litre	No. or #	number	Pvt	private
H	henry	Lm	loam	Obsc	obscure(d)	PD	private drive
HZ	hertz	Loc	location	Obsn	observation	Prod.	production/produce
HDPE	high density polyethylene	LC	long chord	Ocpd	occupied	Prog	programmed
HM	high mast	Long.	longitude	Ocpy	occupy	Prop.	property
HP	high pressure	Lp	loop	Off Loc	office location	Prop Ln	property line
HPS	high pressure sodium	LD	loop detector	O/s	offset	Ppsd	proposed
Hwy	highway	Lm	lumen	OC	on center	PB	pull box
Hor	horizontal	Lum	luminaire	C	one dimensional consolidation		
HBP	hot bituminous pavement	L Sum	lump sum	OC	organic content		
Hr	hour(s)	Lx	lux	Orig	original		
Hyd	hydrant	ML	main line	O To O	out to out		
Ph	hydrogen ion content	M Hr	man hour	OD	outside diameter		
Id	identification	MH	manhole	OH	overhead		
In or "	inch	Mkd	marked	PMT	pad mounted transformer		
Incl	inclinometer tube	Mkr	marker	Pg	pages		
IMH	inlet manhole	Mkg	marking	Pntd	painted		
ID	inside diameter	MA	mast arm	Pr	pair		
Inst	instrument	Matl	material	Pnl	panel		
Intchg	interchange	Max	maximum	Pk	park		
Intmdt	intermediate	MC	meander corner	PK	Parker-Kalon nail		
Intscn	intersection	Meas	measure	Pa	pascal		
Inv	invert	Mdn	median	PSD	passing sight distance		
IM	iron monument	MD	median drain	Pvmt	pavement		
IPn	Iron Pin	MC	medium curing	Ped	pedestal		

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 07/01/14 and the original document is stored at the North Dakota Department of Transportation

NDDOT ABBREVIATIONS

D-101-3

Qty	quantity	Sig	signal	TS	tangent to spiral	WB	Westbound
Qtr	quarter	Si Cl	silt clay	Tel	telephone	Wrng	wiring
Rad or R	radius	Si Cl Lm	silty clay loam	Tel B	Telephone Booth	W/	with
RR	railroad	Si Lm	silty loam	Tel P	telephone pole	W/o	without
Rlwy	railway	Sgl	single	Tv	television	WC	witness corner
Rsd	raised	SC	slow curing	Temp	temperature	WGS	World Geodetic System
RTP	random traverse point	SS	slow setting	Temp	temporary	Z	zenith
Rge or R	range	Sm	small	TBM	temporary bench mark		
RC	rapid curing	S	South	T	tesla		
Rec	record	SE	South East	T	thinwall tube sample		
Rcy	recycle	SW	South West	T/mi	tons per mile		
RPCC	recycled Portland cement concrete	SB	Southbound	Ts	topsoil		
Ref	reference	Sp	spaces	Twp or T	township		
R Mkr	reference marker	Spcl	special	Traf	traffic		
RM	reference monument	SA	special assembly	TSCB	traffic signal control box		
Refl	reflectorized	SP	special provisions	Tr	trail		
RCB	reinforced concrete box	G	specific gravity	Transf	transformer		
RCES	reinforced concrete end section	Spk	spike	TB	transit book		
RCP	reinforced concrete pipe	SC	spiral to curve	Trans	transition		
RCPS	reinforced concrete pipe sewer	ST	spiral to tangent	TT	transmission tower		
Reinf	reinforcement	SB	split barrel sample	Trans	transverse		
Res	reservation	SH	sprinkler head	Trav	traverse		
Ret	retaining	SV	sprinkler valve	TP	traverse point		
Rev	reverse	Sq	square	Trtd	treated		
Rt	right	SF	square feet	Trmt	treatment		
R/W	right of way	Km2	square kilometer	Qc	triaxial compression		
Riv	river	M2	square meter	TERO	tribal employment rights ordinance		
Rd	road	SY	square yard	Tpl	triple		
Rdbd	road bed	Stk	stake	TP	turning point		
Rdwy	roadway	Std	standard	Typ	typical		
RWIS	Roadway Weather Information System	N	standard penetration test	Qu	unconfined compressive strength		
Rk	rock	Std Specs	Standard Specifications	Ugrnd	underground		
Rt	route	Sta	station	USC&G	US Coast & Geodetic Survey		
Salv	salvage(d)	Sta Yd	station yards	USGS	US Geologic Survey		
Sd	sand	Stm L	steam line	Util	utility		
Sdy Cl	sandy clay	SEC	steel encased concrete	VG	valley gutter		
Sdy Cl Lm	sandy clay loam	SSD	stopping sight distance	Vap	vapor		
Sdy Fl	sandy fill	SD	storm drain	Vert	vertical		
Sdy Lm	sandy loam	St	street	VC	vertical curve		
San	sanitary sewer line	SPP	structural plate pipe	VCP	vitrified clay pipe		
Sc	scoria	SPPA	structural plate pipe arch	V	volt		
Sec	seconds	Str	structure	Vol	volume		
Sec	section	Subd	subdivision	Wkwy	walkway		
SL	section line	Sub	subgrade	W	water content		
Sep	separation	Sub Prep	subgrade preparation	WGV	water gate valve		
Seq	sequence	Ss	subsoil	WL	water line		
Serv	service	SE	superelevation	WM	water main		
Sh	shale	SS	supplement specification	WMV	water main valve		
Sht	sheet	Supp	supplemental	W Mtr	water meter		
Shtng	sheeting	Surf	surfacing	WSV	water service valve		
Shldr	shoulder	Surv	survey	WW	water well		
Sw	sidewalk	Sym	symmetrical	W	watt		
S	siemens	SI	Systems International	Wrng	wearing		
SD	sight distance	Tan	tangent	Wb	weber		
SN	sign number	T	tangent (semi)	WIM	Weigh In Motion		
				W	West		

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 07/01/14 and the original document is stored at the North Dakota Department of Transportation

NDDOT UTILITY COMPANY AND ORGANIZATION ABBREVIATIONS

D-101-10

702COM 702 Communications  
 ACCENT Accent Communications  
 AGASSIZ WU Agassiz Water Users Incorporated  
 AGC Associated General Contractors of America  
 All PI Alliance Pipeline  
 ALL SEAS WU All Seasons Water Users Association  
 AMOCO PI Amoco Pipeline Company  
 AMRDA HESS Amerada Hess Corporation  
 AT&T AT&T Corporation  
 B PAW Bear Paw Energy Incorporated  
 BAKER ELEC Baker Electric  
 BASIN ELEC Basin Electric Cooperative Incorporated  
 BEK TEL Bek Communications Cooperative  
 BELLE PL Belle Fourche Pipeline Company  
 BLM Bureau of Land Management  
 BNSF Burlington Northern Santa Fe Railway  
 BOEING Boeing  
 BRNS RWD Barnes Rural Water District  
 BURK-DIV ELEC Burke-Divide Electric Cooperative  
 BURL WU Burleigh Water Users  
 Cable One Cable One  
 CABLE SERV Cable Services  
 CAP ELEC Capital Electric Cooperative Incorporat  
 CASS CO ELEC Cass County Electric Cooperative  
 CASS RWU Cass Rural Water Users Incorporated  
 CAV ELEC Cavalier Rural Electric Cooperative  
 CBLCOM Cablecom Of Fargo  
 CENEX PL Cenex Pipeline  
 CENT PL WATER DIST Central Pipe Line Water District  
 CENT PWR ELEC Central Power Electric Cooperative  
 COE Corps of Engineers  
 CONS TEL Consolidated Telephone  
 CONT RES Continental Resource Inc  
 CPR Canadian Pacific Railway  
 D O E Department Of Energy  
 DAK CARR Dakota Carrier Network  
 DAK CENT TEL Dakota Central Telephone  
 DAK RWD Dakota Rural Water District  
 DGC Dakota Gasification Company  
 DICKEY R NET Dickey Rural Networks  
 DICKEY RWU Dickey Rural Water Users Association  
 DICKEY TEL Dickey Telephone  
 DNRR Dakota Northern Railroad  
 DOME PL Dome Pipeline Company  
 DVELEC Dakota Valley Electric Cooperative  
 DVMW Dakota, Missouri Valley & Western  
 ENBRDG Enbridge Pipelines Incorporated  
 ENVENTIS Enventis Telephone  
 FALK MNG Falkirk Mining Company  
 FHWA Federal Highway Administration  
 G FKS-TRL WD Grand Forks-traill Water District  
 GETTY TRD & TRAN Getty Trading & Transportation  
 GLDN W ELEC Golden West Electric Cooperative  
 GRGS CO TEL Griggs County Telephone

GT PLNS NAT GAS Great Plains Natural Gas Company  
 HALS TEL Halstad Telephone Company  
 IDEA1 Idea1  
 INT-COMM TEL Inter-Community Telephone Company  
 KANEB PL Kaneb Pipeline Company  
 KEM ELEC Kem Electric Cooperative Incorporated  
 KOCH GATH SYS Koch Gathering Systems Incorporated  
 LKHD PL Lakehead Pipeline Company  
 LNGDN RWU Langdon Rural Water Users Incorporated  
 LWR YELL R ELEC Lower Yellowstone Rural Electric  
 MCKNZ CON McKenzie Consolidated Telcom  
 MCKENZIE ELEC McKenzie Electric Cooperative  
 MCKNZ WRD McKenzie County Water Resource District  
 MCLEOD McLeod USA  
 MCLN ELEC McLean Electric Cooperative  
 MCLN-SHRDN R WAT McLean-Sheridan Rural Water  
 MDU Montana-dakota Utilities  
 MID-CONT CABLE Mid-Continent Cable  
 MIDSTATE TEL Midstate Telephone Company  
 MINOT CABLE Minot Cable Television  
 MINOT TEL Minot Telephone Company  
 MISS W W S Missouri West Water System  
 MNKOTA PWR Minnkota Power  
 MOR-GRAN-SOU ELEC Mor-gran-sou Electric Cooperative  
 MOUNT-WILLI ELEC Mountrail-williams Electric Cooperative  
 MRE LBTY TEL Moore & Liberty Telephone  
 MUNICIPAL City Water And Sewer  
 MUNICIPAL City Of '.....'  
 N CENT ELEC North Central Electric Cooperative  
 N VALL W DIST North Valley Water District  
 ND PKS & REC North Dakota Parks And Recreation  
 ND TEL North Dakota Telephone Company  
 NDDOT North Dakota Department of Transportation  
 NDSU SOIL SCI DEPT NDSU Soil Science Department  
 NEMONT TEL Nemont Telephone  
 NODAK R ELEC Nodak Rural Electric Cooperative  
 NOON FRMS TEL Noonan Farmers Telephone Company  
 NPR Northern Plains Railroad  
 NSP Northern States Power  
 NTH PRAIR RW Northern Prairie Rural Water Association  
 NTHN BRDR PL Northern Border Pipeline  
 NTHN PLNS ELEC Northern Plains Electric Cooperative Incorporated  
 NTHWSTRN REF Northwestern Refinery Company  
 NW COMM Northwest Communication Cooperation  
 ONEOK Oneok gas  
 OSHA Occupational Safety and Health Administration  
 OTTR TL PWR Otter Tail Power Company  
 P L E M Prairielands Energy Marketing  
 POLAR COM Polar Communications  
 PVT ELEC Private Electric  
 QWEST Qwest Communications  
 R & T W SUPPLY R & T Water Supply Association  
 RAMSEY R SEW Ramsey Rural Sewer Association  
 RAMSEY RW Ramsey Rural Water Association  
 RAMSEY UTIL Ramsey County Rural Utilities

RED RIV TEL Red River Rural Telephone  
 RESVTN TEL Reservation Telephone  
 ROBRTS TEL Roberts Company Telephone  
 R-RIDER ELEC Roughrider Electric Coop  
 RRVW Red River Valley & Western Railroad  
 RSR ELEC R.S.R. Electric Cooperative  
 S E W U South East Water Users Incorporated  
 SCOTT CABLE Scott Cable Television Dickinson  
 SHERDN ELEC Sheridan Electric Cooperative  
 SHEYN VLY ELEC Sheyenne Valley Electric Cooperative  
 SKYTECH Skyland Technologies Incorporated  
 SLOPE ELEC Slope Electric Cooperative Incorporated  
 SOURIS RIV TELCOM Souris River Telecommunications  
 ST WAT COMM State Water Commission  
 STATE LN WATER State Line Water Cooperative  
 STER ENG Sterling Energy  
 STUT RWU Stutsman Rural Water Users  
 SW PL PRJ Southwest Pipeline Project  
 T M C Turtle Mountain Communications  
 TCI TCI of North Dakota  
 TESORO GHG PLNS PL Tesoro High Plains Pipeline  
 TRI-CNTY WU Tri-County Water Users Incorporated  
 TRL CO RWU Traill County Rural Water Users  
 UNTD TEL United Telephone  
 UPPR SOUR WUA Upper Souris Water Users Association  
 US SPRINT U.S. Sprint  
 USAF MSL CABLE U.S.A.F. Missile Cable  
 USFWS US Fish and Wildlife Service  
 USW COMM U.S. West Communications  
 VRNDRY ELEC Verendrye Electric Cooperative  
 W RIV TEL West River Telephone Incorporated  
 WEB W. E. B. Water Development Association  
 WILLI RWA Williams Rural Water Association  
 WILSTN BAS PL Williston Basin Interstate Pipeline Company  
 WLSH RWD Walsh Water Rural Water District  
 WOLVRTN TEL Wolverton Telephone  
 XLENER Xcel Energy  
 YSVR Yellowstone Valley Railroad

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 07/01/14 and the original document is stored at the North Dakota Department of Transportation






Line Styles

.....	Limits of Const Transition Line	—— s —— s ——	Floating Silt Curtain	—— ——— ———	Existing Aggregate (Cross Section View)	- - - - -	Existing Centerline
.....	Bale Check	—— ——— T ——	Existing Telephone Line	—— ——— ———	Existing Curb and Gutter (Cross Section View)	- - - - -	Supplemental Contour
.....	Rock Check	—— ——— TV ——	Existing TV Line	—— ——— ———	Existing Riprap	—— - - - - -	Right of Way
.....	Sight Distance Triangle Line	Void — void — void — v	Existing Assumed Ground (Not Surveyed)	—— ——— ———	Existing Underground Vault or Lift Station	—— - - - - -	Existing Right of Way
- - - - -	Small Hidden Object	Void — void — void — v	Tentative Ground Line	—— ——— ———	Tangent Line	—— - - - - -	Existing Right of Way Railroad
- - - - -	Dimension Leader	—— ——— w ——	Existing Water or Steam Line	- - - - -	Hidden Object	- - - - -	Failure Line
- - - - -	Existing Ground	=====	Existing Under Drain	—— ——— ———	Existing Dirt Surface	- - - - -	Existing Conditions
- - - - -	Existing Topsoil (Cross Section View)	=====	Under Drain	—— ——— ———	Existing Conduit	- - - - -	Existing Ground (Details)
—— ——— ———	Large Hidden Object	=====	Wall	—— ——— ———	Topsoil Profile	—— - - - - -	Existing Sixteenth Section Line
—— ——— ———	Edge Drain	=====	Existing Slotted Drain	- - - - -	Existing Conductor	- - - - -	Existing Right of Way Not State Owned
—— D —— D ——	Geotextile Fabric Type D	—— + —— + ——	Existing Cemetary Boundary	- - - - -	Conductor	- - - - -	Phantom Object
—— ——— E ——	Existing Electrical	—— ——— ———	Centerline Pavement Marking	- - - - -	Fiber Optic	- - - - -	Centerline Main
—— ——— FO ——	Existing Fiber Optic Line	=====	Barrier with Centerline Pavement Marking	- - - - -	Existing Loop Detector	- ····· -	Existing Guardrail Cable
—— ——— FO ——	Existing TV Fiber Optic	=====	Barrier Pavement Marking	- - - - -	Subgrade, Subcut or Ditch Grade	· - · - · - · -	Existing Guardrail Metal
—— ——— G ——	Existing Gas Pipe	- - - - -	Stripe 4 IN Dotted Extension White	—— ——— ———	Existing Asphalt Surface	—— · - - - -	Existing Edge of Water
—— <b>Geo</b> —— <b>Geo</b> ——	Geogrid	- - - - -	Stripe 8 IN Dotted Extension White	—— ——— ———	Existing Asphalt (Cross Section View)	- - - - -	Excavation Limits
—— ——— OH ——	Existing Overhead Utility Line	- - - - -	Stripe 8 IN Lane Drop	—— ——— ———	Existing Reinforcement Rebar	—— ····· -	Existing Government Lot Line
—— ——— P ——	Existing Power	—— v v v v ——	Wetland Mitigation	—— ——— ———	Existing Tie Point Line	·····	Existing Adjacent Block Lines
—— ——— PL ——	Existing Fuel Pipeline	- - - - -	Existing Box Culvert Bridge	—— ——— ———	Existing State or International Line	·····	Existing Adjacent Lot Lines
—— ——— <b>PL</b> ——	Existing Undefined Above Ground Pipe Line	- - - - -	Existing Concrete Surface	—— ——— ———	Existing Quarter Section Line	·····	Existing Adjacent Property Line
—— ——— R —— R ——	Geotextile Fabric Type R	- - - - -	Existing Drainage Structure	—— ——— ———	Existing County	·····	Existing Adjacent Subdivision Lines
—— ——— R —— R ——	Geotextile Fabric Type R1	- - - - -	Easement	—— ——— ———	Existing Section Line		
—— REMOVE —— REMOVE ——	Remove Line	- - - - -	Existing Concrete	—— ——— ———	Existing Township		
—— RR —— RR ——	Geotextile Fabric Type RR	- - - - -	Existing Easement	—— ——— ———	Existing Railroad Centerline		
—— S —— S ——	Geotextile Fabric Type S	—— ——— ———	Existing Gravel Surface	—— - - - - -	Centerline		

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 07/01/14 and the original document is stored at the North Dakota Department of Transportation

Line Styles

	Subgrade Reinforcement		Existing Railroad Switch		Sheet Piling
	Existing Down Guy Wire Down Guy		Overhead Sign Structure Cantilever		W-Beam w Posts
	Existing Fence		24 Inch Pipe		Existing W-Beam Guardrail with Posts
	Existing Railroad		Reinforced Concrete Pipe		Exst Wet Area-Vegetation Break
	Existing Sanitary Sewer		Signal Head with Mast Arm		Existing Wetland Delineated
	Existing Sanitary Force Main		Existing Signal Head with Mast Arm		
	Existing Storm Drain		Tie Bar at Random Spacing		
	Existing Storm Drain Force Main		3-Cable w Posts		
	Fence		Existing 3-Cable w Posts		
	Silt Fence		Site Boundary		
	Existing Field Line		Fiber Rolls		
	Exst Flow		Doweled Joint		
	Flow		Tie Bar 30 Inch 4 Foot Center to Center		
	Existing Culvert		Tie Bar 18 Inch 3 Foot Center to Center		
	Existing Curb		Existing Berm, Dike, Pit, or Earth Dam		
	Existing Valley Gutter		Existing Ditch Block		
	Existing Driveway Gutter		Depression Contours		
	Existing Curb and Gutter		Existing City Corporate Limits or Reservation Boundary		
	Existing Mountable Curb and Gutter		Gravel Pit - Borrow Area		
	Existing Double Micro Loop Detector		Existing Tree Boundary		
	Micro Loop Detector Double		Tree Row		
	Existing Overhead Sign Structure		Existing Brush or Shrub Boundary		
	Existing Micro Loop Detector		Existing Retaining Wall		
	Micro Loop Detector		Existing Planter or Wall		
	Existing Overhead Sign Structure Cantilever		Retaining Wall (Plan View)		

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 07/01/14 and the original document is stored at the North Dakota Department of Transportation

Symbols

	North Arrow (Half Scale)		Attenuation Device		Existing Railroad Battery Box		Existing Delineator Type E
	Truck Mounted Attenuator		Diamond Grade Delineator Type A		Existing Bush or Shrub		Existing EFB Misc
	Type I Barricade		Diamond Grade Delineator Type B		Existing Gas Cap or Stub		Existing Flashing Beacon
	Type II Barricade		Diamond Grade Delineator Type C		Existing Sanitary Cap or Stub		Existing Pipe Mounted Flasher
	Type III Barricade		Diamond Grade Delineator Type D		Existing Storm Drain Cap or Stub		Existing Pad Mounted Feed Point
	Catch Basin		Diamond Grade Delineator Type E		Existing Water Cap or Stub		Existing Pipe Mounted Feed Point with Pad
	Cairn or Stone Circle		Flexible Delineator		Existing Sanitary Cleanout		Existing Pole Mounted Feed Point
	Video Detection Camera		Flexible Delineator Type A		Existing Concrete Foundation		Existing Railroad Frog
	Storm Drain Cap or Stub		Flexible Delineator Type B		Existing Traffic Signal Controller		Existing Snow Gate 18
	Corrugated Metal End Section 18 Inch		Flexible Delineator Type C		Existing Pad Mounted Signal Controller		Existing Snow Gate 28
	Corrugated Metal End Section 24 Inch		Flexible Delineator Type D		Existing Sixteenth Section Corner		Existing Snow Gate 40
	Corrugated Metal End Section 30 Inch		Flexible Delineator Type E		Existing Quarter Section Corner		Existing Headwall
	Corrugated Metal End Section 36 Inch		Delineator Type A		Existing Section Corner		Existing Pedestrian Head with Number
	Corrugated Metal End Section 42 Inch		Delineator Type A Reset		Existing Railroad Crossbuck		Existing Signal Head
	Corrugated Metal End Section 48 Inch		Delineator Type B		Existing Satellite Dish		Existing Sprinkler Head
	Concrete Foundation		Delineator Type B Reset		Existing Fuel Dispensers		Existing Fire Hydrant
	Ground Connection Conductor		Delineator Type C		Existing Flexible Delineator Type A		Existing Catch Basin Drop Inlet
	Neutral Connection Conductor		Delineator Type D		Existing Flexible Delineator Type B		Existing Curb Inlet
	Phase 1 Connection Conductor		Delineator Type E		Existing Flexible Delineator Type C		Existing Manhole Inlet
	Phase 2 Connection Conductor		Delineator Drums		Existing Flexible Delineator Type D		Existing Junction Box
	Traffic Cone		Spot Elevation		Existing Flexible Delineator Type E		
	Signal Controller		Existing Access Control Arrow		Existing Delineator Type A		
	Pad Mounted Signal Controller		Existing Artifact		Existing Delineator Type B		
	Alignment Data Point		Existing Flashing Beacon		Existing Delineator Type C		
	Emergency Vehicle Detector		Existing Benchmark		Existing Delineator Type D		

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 07/01/14 and the original document is stored at the North Dakota Department of Transportation

Symbols

	Existing Light Standard		Existing Manhole with Valve Water		Existing Telephone Pole		Existing Undefined Manhole
	Existing High Mast Light Standard 10 Luminaire		Existing Water Manhole		Existing Wood Pole		Existing Undefined Pull Box
	Existing High Mast Light Standard 3 Luminaire		Existing Mile Post Type A		Existing Post		Existing Undefined Pedestal
	Existing High Mast Light Standard 4 Luminaire		Existing Mile Post Type B		Existing Pedestrian Push Button Post		Existing Undefined Valve
	Existing High Mast Light Standard 5 Luminaire		Existing Mile Post Type C		Existing Control Point CP		Existing Undefined Pipe Vent
	Existing High Mast Light Standard 6 Luminaire		Existing Reference Marker		Existing Control Point GPS-RTK		Existing Gas Valve
	Existing High Mast Light Standard 7 Luminaire		Existing RW Marker		Existing Control Point TRI		Existing Water Valve
	Existing High Mast Light Standard 8 Luminaire		Existing Utility Marker		Existing Reference Marker Point NGS		Existing Fuel Pipe Vent
	Existing High Mast Light Standard 9 Luminaire		Iron Monument Found		Existing Pull Box		Existing Gas Pipe Vent
	Existing Overhead Sign Structure Load Center		Iron Pin R/W Monument		Existing Intelligent Transportation Pull Box		Existing Sanitary Pipe Vent
	Existing Luminaire		Existing Object Marker Type I		Existing Water Pump		Existing Storm Drain Pipe Vent
	Existing Light Standard Luminaire		Existing Object Marker Type II		Existing Slotted Reinforced Concrete Pipe		Existing Water Pipe Vent
	Existing Federal Mailbox		Existing Object Marker Type III		Existing RR Profile Spot		Existing Weather Station
	Existing Private Mailbox		Existing Electrical Pedestal		Existing Fuel Leak Sensors		Existing Ground Water Well Bore Hole
	Existing Meander Section Corner		Existing Telephone Pedestal		Existing Highway Sign		Existing Windmill or Tower
	Existing Meter		Existing Fiber Optic Telephone Pedestal		Existing Miscellaneous Spot		Existing Witness Corner
	Existing Electrical Manhole		Existing TV Pedestal		Existing Lighting Standard Pole		Flashing Beacon
	Existing Gas Manhole		Existing Fiber Optic TV Pedestal		Existing Traffic Signal Standard		Flagger
	Existing Sanitary Manhole		Existing Fuel Filler Pipes		Existing Transformer		Pipe Mounted Flasher
	Existing Sanitary Force Main Manhole		Existing Traverse PI Aerial Panel		Existing Large Evergreen Tree		Sanitary Force Main with Valve
	Existing Sanitary Manhole with Valve		Existing Pole		Existing Small Evergreen Tree		
	Existing Storm Drain Manhole		Existing Power Pole		Existing Large Tree		
	Existing Force Main Storm Drain Manhole		Existing Power Pole with Transformer		Existing Small Tree		
	Existing Force Main Storm Drain Manhole with Valve				Existing Tree Trunk		
	Existing Telephone Manhole				Existing Pad Mounted Traffic Signal Control Box		

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 07/01/14 and the original document is stored at the North Dakota Department of Transportation

# Symbols






D-101-32

 Pad Mounted Feed Point  Pipe Mounted Feed Point with Pad  Pole Mounted Feed Point  Headwall  Double Headwall with Vegetation Barrier  Single Headwall with Vegetation Barrier  Pole Mounted Head  Sprinkler Head  Fire Hydrant  Inlet Type 1  Inlet Type 2  Double Inlet Type 2  Inlet Grate Type 2  Junction Box  High Mast Light Standard 10 Luminaire  High Mast Light Standard 3 Luminaire  High Mast Light Standard 4 Luminaire  High Mast Light Standard 5 Luminaire  High Mast Light Standard 6 Luminaire  High Mast Light Standard 7 Luminaire  High Mast Light Standard 8 Luminaire  High Mast Light Standard 9 Luminaire  Relocate Light Standard  Overhead Sign Structure Load Center  Light Standard 100 Watt High Pressure Sodium Vapor Luminaire	 Light Standard 1000 Watt High Pressure Sodium Vapor Luminaire  Light Standard 150 Watt High Pressure Sodium Vapor Luminaire  Light Standard 175 Watt High Pressure Sodium Vapor Luminaire  Light Standard 200 Watt High Pressure Sodium Vapor Luminaire  Light Standard 250 Watt High Pressure Sodium Vapor Luminaire  Light Standard 310 Watt High Pressure Sodium Vapor Luminaire  Light Standard 35 Watt High Pressure Sodium Vapor Luminaire  Light Standard 400 Watt High Pressure Sodium Vapor Luminaire  Light Standard 50 Watt High Pressure Sodium Vapor Luminaire  Light Standard 70 Watt High Pressure Sodium Vapor Luminaire  Light Standard 700 Watt High Pressure Sodium Vapor Luminaire  Manhole  Manhole 48 Inch  Sanitary Force Main Manhole  Sanitary Sewer Manhole  Storm Drain Manhole  Storm Drain Manhole with Inlet  Reset Mile Post  Mile Post Type A  Mile Post Type B  Mile Post Type C  Right of Way Marker  Tubular Marker  Alignment Monument  Iron Pin Reference Monument	 Object Marker Type I  Object Marker Type II  Object Marker Type III  Caution Mode Arrow Panel  Back to Back Vertical Panel Sign  Double Direction Arrow Panel  Left Directional Arrow Panel  Right Directional Arrow Panel  Sequencing Arrow Panel  Truck Mounted Arrow Panel  Power Pole  Wood Pole  Pedestrian Push Button Post  Property Corner  Pull Box  Intelligent Transportation Pull Box  Sanitary Pump  Storm Drain Pump  Reinforced Pavement  Reinforced Concrete End Section 15 Inch  Reinforced Concrete End Section 18 Inch  Reinforced Concrete End Section 24 Inch  Reinforced Concrete End Section 30 Inch  Reinforced Concrete End Section 36 Inch  Reinforced Concrete End Section 42 Inch	 Reinforced Concrete End Section 48 Inch  Reinforced Concrete End Section 54 Inch  Reset Right of Way Marker  Reset USGS Marker  Right of Way Markers  Riser 30 Inch  Continuous Split Barrel Sample  Flight Auger Sample  Split Barrel Sample  Thinwall Tube Sample  Highway Sign  SNOW GATE 18 FT  SNOW GATE 28 FT  SNOW GATE 40 FT  Standard Penetration Test  Transformer  Inclinometer Tube  Underdrain Cleanout  Excavation Unit  Water Valve
--	--	---	--

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by  
 Roger Weigel,  
 Registration Number PE-2930,  
 on 07/01/14 and the original document is stored at the North Dakota Department of Transportation

EROSION AND SILTATION CONTROL  
EROSION CONTROL BLANKET INSTALLATION



\* This tie may be placed ahead or back.



DETAILS  
CHANNEL OR SLOPE INSTALLATION



Notes:  
Beginning and ending of erosion control blanket areas shall be installed as shown in "DETAIL C".


Erosion control blanket ends shall be entrenched and stapled to eliminate undermining on side slopes.

BLANKET LAYOUT  
CHANNEL OR SLOPE INSTALLATION



INSTALLATION AT PIPE ENDS

3.8 staples per square yard using 8-inch 11 gauge wire "u" staples.









NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-03-13	
REVISIONS	
DATE	CHANGE
06-26-14	Changed standard drawing number from D-708-5 to D-255-2.

This document was originally issued and sealed by  
Roger Weigel  
Registration Number  
PE-2930,  
on 06/26/14 and the original document is stored at the North Dakota Department of Transportation


EROSION AND SILTATION CONTROLS

D-256-1




NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-03-13	
REVISIONS	
DATE	CHANGE
06-26-14	Changed standard drawing number from D-708-2 to D-256-1. Deleted silt fence details.

This document was originally issued and sealed by Roger Weigel Registration Number PE-2930, on 06/26/14 and the original document is stored at the North Dakota Department of Transportation



SILT FENCE SUPPORTED AND UNSUPPORTED




SILT FENCE CROSS SECTION

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-03-13	
REVISIONS	
DATE	CHANGE
06-26-14	Standard drawing resulted from splitting standard D-708-2.


This document was originally issued and sealed by  
 Roger Weigel  
 Registration Number  
 PE-2930,  
 on 06/26/14 and the original document is stored at the North Dakota Department of Transportation

EROSION CONTROL  
FIBER ROLL PLACEMENT DETAILS




\*Optional Weir. Use in flat areas, such as the Red River Valley, where there is potential for water to back up on adjacent property. Lower fiber roll enough to prevent water from backing up on adjacent property. Do not use 20-inch fiber rolls in flat areas where there is potential for water to back up on adjacent property.


12 OR 20 INCH FIBER ROLL - DITCH BOTTOM




PLAN VIEW FOR SLOPE APPLICATION



PLAN VIEW FOR DITCH APPLICATION



Detail A  
Fiber Roll Overlapping Staking Detail



Detail B  
Fiber Roll Staking Detail

FIBER ROLL DIAMETER	NOMINAL STAKE SIZE	MINIMUM STAKE LENGTH	MINIMUM TRENCH DEPTH	MAXIMUM TRENCH DEPTH
6"	2" x 2"	18"	2"	2"
12"	2" x 2"	24"	2"	3"
20"	2" x 2"	36"	3"	5"

NOTE: Runoff must not be allowed to run under or around roll.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
11-18-10	
REVISIONS	
DATE	CHANGE
06-10-13	Added plan view for ditch and slope application, Added table with values for stake and trench dimensions.
10-04-13	Revised fiber roll overlap detail.
06-26-14	Changed standard drawing number from D-708-7 to D-261-1

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 06/26/14 and the original document is stored at the North Dakota Department of Transportation

CONSTRUCTION SIGN DETAIL

D-704-5

<b>SIGN NUMBER</b>	G20-10-108	<b>STATION(S):</b>	<b>AREA:</b> 36.0 Sq.Ft.
<b>WIDTH x HEIGHT</b>	9'-0" x 4'-0"		
<b>BORDER WIDTH</b>	1.25" (inset 0.75")		
<b>CORNER RADIUS</b>	3"		
<b>MOUNTING</b>	Ground		
<b>BACKGROUND</b>	TYPE: IV Reflective COLOR: Fluorescent Orange		
<b>LEGEND/BORDER</b>	TYPE: Non-Refl COLOR: Black		

SYMBOL	X	Y	WID	HT	ANGLE
	42.1	6.2	24	4	0

Dimensions are in inches.tenths      Letter locations are panel edge to lower left corner

LETTER POSITION (X)															LENGTH	SIZE	SERIES		
C	O	N	S	T	R	U	C	T	E	D	B	Y			69.7	6	D 2000		
19.2	24.5	30	35.1	39.7	44.3	49.4	54.8	59.7	64.3	69	73.1	79.1	83.7						
Y	O	U	R		C	O	M	P	A	N	Y		N	A	M	E	91.5	6	D 2000
8.3	14.2	19.8	25.3	29.4	35.4	40.7	46.2	52.4	56.8	62.8	67.8	72.9	78.9	83.9	89.9	96			
Y	O	U	R		T	O	W	N				N	D				64.6	6	D 2000
21.7	27.6	33.2	38.7	42.8	48.8	53.3	58.4	64.6	69.6	70.7	76.7	82.2							


Notes:

1. Sign shall be placed a distance of 1/2A following the End Road Work (G20-2a-48) sign. There shall be a maximum of 2 signs per project.
2. Sign shall be post mounted.
3. Sign required on rural projects with a 30 day or longer duration and it is not required on seal coat projects or other short duration projects.
4. Sign shall not be placed in urban areas or within city limits.

Advance Warning Sign Spacing (A)			
Road Type	Distance between signs min. (ft)		
	A	B	C
Urban - Low Speed (30 mph or less)	150	150	150
Urban - Low Speed (over 30 to 40 mph)	280	280	280
Urban - High Speed (over 40 mph to 50 mph)	360	360	360
Rural - High Speed (over 50 mph to 65 mph)	720	720	720
Urban Expressway and Freeway (55 mph to 60 mph)	850	1350	2200
Rural Expressway and Freeway (70 mph to 75 mph)	1000	1500	2640
Interstate/4-Lane Divided (Maintenance and Surveying)	750	1000	1500


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-22-12	
REVISIONS	
DATE	CHANGE
7-18-14	Revise sheeting to type IV

This document was originally issued and sealed by Roger Weigel Registration Number PE- 2930, on 7/18/14 and the original document is stored at the North Dakota Department of Transportation




Multi-Directional Slip Base Assembly

Perforated Tube



Top Post Receiver  
Plate - ASTM A572 grade 50  
Angle Receiver - 2 1/2"x2 1/2"x3/8" ASTM A36 structural angle



Bottom Soil Stub  
Tube - 3"x3"x7 gauge ASTM A500 grade B tube  
Stabilizing Wing - 7 gauge H.R.P.O. ASTM A1011  
Plate - ASTM A572 grade 50


Notes:

- Slip base bolts shall be torqued as specified by the manufacturer.
- Anchor shall have a yield strength of 43.9 KSI and tensile strength of 59.3 KSI.
- The 4" vertical clearance is required for the anchor or breakaway base. The 4"x60" measurement shall be made above and below post location and also back and ahead of the post.
- When used in concrete sidewalk, anchor shall be same except without the wings.
- Four post signs shall have over 7' between the first and the fourth posts.


Telescoping Perforated Tube						
Number of Posts	Post Size in.	Wall Thickness Gauge	Sleeve Size in.	Wall Thickness Gauge	Slip Base	Anchor Size without Slip Base in.
1	2	12			No	2 1/4
1	2 1/4	12			No	2 1/2
1	2 1/2	12			(A)	3
1	2 1/2	10			Yes	
1	2 1/4	12	2	12	Yes	
1	2 1/2	12	2 1/4	12	Yes	
2	2	12			No	2 1/4
2	2 1/4	12			No	2 1/2
2	2 1/2	12			Yes	
2	2 1/2	12			Yes	
2	2 1/4	10	2	12	Yes	
2	2 1/2	12	2 1/4	12	Yes	
3 & 4	2 1/2	12			Yes	
3 & 4	2 1/2	10			Yes	
3 & 4	2 1/2	12	2 1/4	12	Yes	
3 & 4	2 1/4	12	2	12	Yes	
3 & 4	2 1/2	10	2 3/16	10	Yes	

Properties of Telescoping Perforated Tube						
Tube Size in.	Wall Thickness in.	U.S. Standard Gauge	Weight per Foot lbs.	Moment of Inertia in. <sup>4</sup>	Cross Sec. Area in. <sup>2</sup>	Section Modulus in. <sup>3</sup>
1 1/2 x 1 1/2	0.105	12	1.702	0.129	0.380	0.172
2 x 2	0.105	12	2.416	0.372	0.590	0.372
2 1/4 x 2 1/4	0.105	12	2.773	0.561	0.695	0.499
2 3/16 x 2 3/16	0.135	10	3.432	0.605	0.841	0.590
2 1/2 x 2 1/2	0.105	12	3.141	0.804	0.803	0.643
2 1/2 x 2 1/2	0.135	10	4.006	0.979	1.010	0.785


Top Post Receiver Data Table						
Square Post Sizes (B)	A	B	C	D	E	F
2 3/16"x10 ga.	1 9/64"	2 1/2"	3 1/32"	2 5/32"	1 33/64"	1 1/8"
2 1/2"x10 ga.	1 9/32"	2 1/2"	3 5/16"	5/8"	1 21/32"	1 3/4"




Anchor Unit and Post Assembly



Multi-Directional Slip Base Anchor Unit and Post Sleeve Assembly



Bolt Retainer for Base Connection  
Bolt Retainer - 1/32" Reprocessed Teflon




Anchor plate shall be a minimum 10 gauge (two post installation)

- (A) The breakaway base is required when the support is placed in weak soils. The Engineer shall determine if the soils are weak.  
 (B) The 2 3/16"x10 ga. may be inserted into 2 1/2"x10 ga. for additional wind load.


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
2-28-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 2/28/14 and the original document is stored at the North Dakota Department of Transportation

U-Channel Post



Detail A




Front View

Side View


Back View

Breakaway U-Channel Detail Alternate A

A maximum of 2 posts shall be installed within 7'.




Retainer Strap Detail



Breakaway U-Channel Splice Detail Alternate B (2.5 and 3 lb/ft)

A maximum of 3 posts shall be installed within 7'.



Breakaway U-Channel Splice Detail Alternate C (2.5 and 3 lb/ft)

A maximum of 3 posts shall be installed within 7'.

Alternate A Steps of Installation:











1. a) Drive anchor unit to within 12" of ground level.  
b) Proper assembly established by lining up the bottom hole of retainer strap with the 6th hole from the top of the anchor unit.  
c) Assemble strap to back of anchor unit using 5/16"x2" bolt, lock washer and nut.  
d) Rotate strap 90° to left.
2. a) Drive anchor unit to 4" above ground.  
b) Rotate strap to vertical position.
3. a) Place 5/16"x2" bolt, lock washer and nut in bottom of sign post to facilitate alignment of sign post with proper hole in anchor unit.  
b) Alternately tighten two connector bolts.
4. Complete assembly by tightening 5/16"x2" bolt (this fastens sign post to retainer strap).
5. The base post, strap and sign post shall be properly nested. Proper nesting occurs when all flat surfaces of the base post, strap, and sign post at the bolts have full contact across the entire width.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
2-28-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 2/28/14 and the original document is stored at the North Dakota Department of Transportation

CONSTRUCTION SIGN DETAILS  
 TERMINAL AND GUIDE SIGNS

D-704-9





ARROW DETAILS

NOTES:

(A) Arrow may be right or left of the legend to indicate construction to the right or left.


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-13-13	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 8/13/13 and the original document is stored at the North Dakota Department of Transportation




CONSTRUCTION SIGN DETAILS  
REGULATORY SIGNS


D-704-10




R1-50-24  
Legend: black (non-refl)  
Background: white



R11-3c-60  
Legend: black (non-refl)  
Background: white



R2-1a-24  
Legend: black (non-refl)  
Background: white



R11-4a-60  
Legend: black (non-refl)  
Background: white



R11-2a-48  
Legend: black (non-refl)  
Background: white


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-13-13	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 8/13/13 and the original document is stored at the North Dakota Department of Transportation


CONSTRUCTION SIGN DETAILS  
WARNING SIGNS

WORD	LETTER SPACING
AHEAD	Standard
200 FT	Standard
350 FT	Standard
500 FT	Standard
1000 FT	Reduce 40%
1500 FT	Reduce 40%
½ MILE	Reduce 50%
1 MILE	Standard


\* DISTANCE MESSAGES




W5-8-48  
Legend: black (non-refl)  
Background: orange




W8-54-48  
Legend: black (non-refl)  
Background: orange




W20-51-48  
Legend: black (non-refl)  
Background: orange




W21-51-48  
Legend: black (non-refl)  
Background: orange




W5-9-48  
Legend: black (non-refl)  
Background: orange




W8-55-48  
Legend: black (non-refl)  
Background: orange




W20-52-54  
Legend: black (non-refl)  
Background: orange




W22-8-48  
Legend: black (non-refl)  
Background: orange




W5-9-48  
ARROW DETAILS



W8-53-48  
Legend: black (non-refl)  
Background: orange



W8-56-48  
Legend: black (non-refl)  
Background: orange




W21-50-48  
Legend: black (non-refl)  
Background: orange

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-13-13	
REVISIONS	
DATE	CHANGE




This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 8/13/13 and the original document is stored at the North Dakota Department of Transportation

# SHOULDER CLOSURE TAPERS

D-704-12



SHOULDER CLOSURE WITH LANE CLOSURE  
(when shoulder is 8' or wider)



SHOULDER CLOSURE USED WITH LANE CLOSURE  
(when shoulder is less than 8' wide)

PORTABLE TRAFFIC SIGNAL OR CHANGEABLE MESSAGE SIGN ON SHOULDER

KEY	
● Delineator Drum	∞ Sequencing Arrow Panel
• Message Display	↳ Portable Traffic Signal


Notes:

- S = Posted Speed Limit in mph  
W = Width of offset in feet  
L = Taper length in feet  
L = WS<sup>2</sup>/60 (40mph or less)  
L = WS (45mph or more)
- If a shoulder taper is used, it should have a length of approximately 1/3 L. If a shoulder is used as a travel lane, a normal merging or shifting taper should be used.
- When paved shoulders of 8 foot width or more are closed, channelizing devices shall be used to close the shoulder in advance to delineate the beginning of the work space and direct vehicular traffic to remain within the traveled way.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-3-13	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel Registration Number PE-2930, on 10/3/13 and the original document is stored at the North Dakota Department of Transportation

BARRICADE AND CHANNELIZING DEVICE DETAILS



The markings on drums shall be horizontal, circumferential, alternating orange and white retroreflective stripes 4" to 6" wide. Each drum shall have a minimum of two orange and two white stripes with the top stripe being orange. Any nonretroreflectORIZED spaces between the horizontal orange and white stripes shall not exceed 3" wide. Stripes shall not be placed on ribs or indentations in the drum. Drums shall have closed tops that will not allow collection of construction debris or other debris. Ballast shall not be placed on the top of a drum.


Markings for vertical panels shall be alternating orange and white retroreflective stripes, sloping downward in the direction vehicular traffic is to pass. Retroreflective sheeting shall be placed on both sides of panel and shall have a minimum of 270 square inches of retroreflective area facing vehicular traffic. Where the height of the retroreflective material on the vertical panel is 36 inches or more, a stripe width of 6 inches shall be used.

RetroreflectORIZATION of cones more than 36" in height shall be provided by alternating orange and white retroreflective stripes. Each cone shall have a minimum of two orange and two white stripes with the top stripe being orange. Any nonretroreflectORIZED space between the orange and white stripes shall not exceed 3" wide.

RetroreflectORIZATION of tubular markers more than 42" in height shall be provided by alternating four 4" to 6" wide orange and white stripes with the top stripe being orange.

INSTALLATION NOTES:

1. Drill installation holes to diameter and depth as required by manufacturer's specifications.
2. For removal, remove anchors and fill installation hole with an epoxy designed to bond to pavement surface.
3. In lieu of bolted down base, the contractor may use an 8" x 8" butyl pad or hot melt butyl. Butyl shall be removed as close as possible to pavement surface.




BARRICADE BLADE DETAIL

BARRICADE ASSEMBLY DETAIL (Aluminum Barricade Rails)

BARRICADE ASSEMBLY DETAIL (Wood or Plastic Rails)


NOTE: Markings for barricades shall be alternating orange and white retroreflective stripes, sloping downward in the direction traffic is to pass. Retroreflective sheeting shall be placed on both sides of the rails and shall have a minimum of 270 square inches of visible retroreflective area facing vehicular traffic. When the barricade length is less than 36", the rail stripe width shall be 4".



TYPE I BARRICADE

TYPE II BARRICADE BARRICADE RAIL DETAILS

TYPE III BARRICADE



MINIMUM BALLAST (For each side of barricade support)

Without Sign	4 - 25 lb sandbags
With Sign	6 - 25 lb sandbags


Note: The number of sandbags are based on a wind speed of 55 MPH. The sandbags are assumed to be placed at or near the ends of the skids.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-3-13	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 10/3/13 and the original document is stored at the North Dakota Department of Transportation

CONSTRUCTION SIGN PUNCHING AND MOUNTING DETAILS


Note: Signs placed in sections with curb shall have a minimum horizontal clearance of 2' from the face of the curb to the near edge of the sign.




TYPICAL SECTION  
(48" x 48" diamond warning sign shown)




24" x 24" ROUTE MARKER ASSEMBLY




36" x 36" ROUTE MARKER ASSEMBLY




18" x 18" DIAMOND SIGN




48" x 48" DIAMOND SIGN  
(with 30" x 30" secondary sign)




48" x 48" DIAMOND SIGN  
(with 30" x 24" secondary sign)




R1-2-60 - YIELD SIGN




W14-3-64 - PENNANT SIGN




R1-1-48 - STOP SIGN  
(with R6-1-54 sign as required)




R1-1-48 - STOP SIGN  
(with R1-50-24 sign as required)




48" x 48" SIGN  
(with R6-1-54 sign as required)




48" x 48" SIGN  
(with R2-1a-24 sign as required)




24" x 36" SIGN




30" x 24" SIGN




108" x 48" SIGN




96" x 48" SIGN




72" x 36" SIGN




72" x 24" SIGN




60" x 24" SIGN



48" x 24" SIGN



PORTABLE SIGN SUPPORT  
LOW-MOUNTING HEIGHT



PORTABLE SIGN SUPPORT  
HIGH-MOUNTING HEIGHT

NOTES:

1. Sign Supports: Supports shall be galvanized or painted. Minimum post sizes are 2.5 lb/ft u-channel or 2" x 2" x 12 gauge steel perforated tube, except where noted. When installing signs on u-channel, the minimum post size for assemblies containing a secondary sign is 3.0 lb/ft. Post sizes are based on a wind speed of 55 MPH.

Signs over 50 square feet should be installed on 2 1/2" x 2 1/2" perforated tube supports as a minimum.

Guy wires shall not be attached to sign supports. Wind beams may be attached to u-posts behind the sign panels.

2. Sign Panels: Provide sign panels made of 0.100" aluminum, 1/2" plywood, or other approved material, except where noted. All holes to be punched round for 3/8" bolts.

3. Alternate Messages: The signs that have alternate messages may have these alternate messages placed on a reflectorized plate (without a border) and installed and removed as required. (i.e. "Left" and "Right" message on a lane closure sign)

4. Route Marker Auxiliary Signs: Provide route marker auxiliary signs, such as the cardinal direction and directional arrows, with a background and legend that match the route marker they are used with:

Interstate - white legend on blue background  
Interstate Business Loop - white legend on green background  
US and State - black legend on white background  
County - yellow legend on blue background

5. Vertical Clearance: Install signs with a vertical clearance of 5'-0" (see TYPICAL SECTION.) In areas where parking or pedestrian movements are likely or the view of the sign may be obstructed, install signs with a vertical clearance of 7'-0" from the top of the curb or from the near edge of the driving lane in absence of a curb.

The vertical clearance to secondary signs is 1'-0" less than the vertical clearance as stated above.

Large signs having an area exceeding 50 square feet shall have a minimum clearance of 7'-0" from the ground at the post.

6. Portable Signs: Provide portable signs that meet the vertical clearance as stated above. Use portable signs when it is necessary to place signs within the pavement surface.

When portable signs are used for 5 days or less, low-mounting height (minimum 12" vertical clearance) sign supports may be used as long as the view of the sign is not obstructed. Time delays caused by unforeseen circumstances, such as equipment breakdown, rain, subgrade failures, etc., will not accrue towards the 5 day period. The R9-8 through R9-11a series, W1-5 through W1-8 series, M4-10, and E5-1 may be used for longer than 5 days.

Signs mounted to the portable sign supports shown in the LOW-MOUNTING HEIGHT and HIGH-MOUNTING HEIGHT Details shall have a maximum surface area of 16 square feet.

MINIMUM BALLAST  
(For each side of sign support base)

Sign Panel Mounting Height (ft)	Number of 25 lb sandbags for 4' x 4' sign panel
1'	6
5'	8
7'	10

Note: The number of sandbags are based on a wind speed of 55 MPH. The sandbags are assumed to be placed at or near the ends of the skids.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-4-13	
REVISIONS	
DATE	CHANGE
11-14-13	Revised Note 6.


This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 11/14/13 and the original document is stored at the North Dakota Department of Transportation

# ROAD CLOSURE AND LANE CLOSURE ON A TWO WAY ROAD LAYOUTS

D-704-19

**Notes**


- Variables  
 S = Numerical value of speed limit or 85th percentile.  
 W = The width of taper  
 L = Minimum length of taper, or S x W for freeways, expressways, and all other roads with speeds of 45 mph or greater, or W x S<sup>2</sup>/60 for urban, residential, and other streets with speeds of 40 mph or less.
- Barricades placed on roadway shall be on a moveable assembly. Signs placed on the roadway shall be placed on skid mounted assemblies.
- Delineator drums used for tapering traffic shall be placed at 3 equal spaces. Delineator drums for tangents shall be spaced at 2 times dimension "S".
- The speed limit shall be re-established. The exact speed limit shall be determined in the field, dependent on location and conditions.
- The reduced speed limit shall be determined dependent on the in place speed limit before construction. The speed limit reduction should not exceed 10 mph below the existing speed limit, unless the design speed of the work zone feature has been reduced below the 10 mph. In this case, the speed limit reduction shall not exceed 30 MPH. Where speed limits are to be reduced more than 30 MPH, a second speed limit sign shall be installed with the desired speed reduction but shall not exceed 30 MPH. The second speed limit sign shall be placed at 1/2 B.
- When warning signs are used in urban areas and the signs are not portable, flags shall be installed. The flags shall be 24 inches square, mounted perpendicular to the edges of the diamond sign, and at such a distance above the edge so that when the flag is limp it will not touch the sign. Rural areas will not require flags.
- Existing speed limit signs within a reduced speed zone shall be covered.
- Where necessary, safe speed to be determined by the Engineer.
- The contractor has the option of using portable sign supports in lieu of post mounted signs in accordance with the NDDOT Standard Specifications.
- G20-55-96 or R2-1a-24 sign are not required when a pilot car operation is used, if this standard is part of other traffic control layouts, or the work is less than 15 days.
- When highway-rail grade crossings exist either within or in the vicinity of the roadway work activities:
  - Extra care shall be taken to minimize the probability of conditions being created, either by lane restrictions, flagging or other operations, where vehicles might be stopped within the highway-rail grade crossing (considered as being 15 feet on either side of the closest and farthest rail.)
  - A "Do Not Stop on Tracks" sign (R8-8-24) should be placed near the cross buck in each direction while the lane closure is in the vicinity of the tracks.
  - A buffer space between the work zone and the lane closure transition should be extended upstream of the highway-rail grade crossing so a queue created by the flagging operation will not extend across the highway-rail grade crossing.
  - If the queuing of vehicles across active rail tracks cannot be avoided, a flagger shall be provided at the highway-rail grade crossing to prevent vehicles from stopping within the highway-rail grade crossing, even if automatic warning devices are in place.



**TYPE E  
ROAD CLOSURE WITH OFF-SITE DETOUR**

Used where a road is closed beyond a detour point. Signing shown for one direction only. Sign not shown on detour shall be shown in plans and installed and maintained by the contractor.

Road Type	ADVANCE WARNING SIGN SPACING		
	Distance Between Signs Min. (ft)		
	A	B	C
Urban - Low Speed (30 mph or less)	150	150	150
Urban - Low Speed (over 30 to 40mph)	280	280	280
Urban - High Speed (over 40 mph to 50 mph)	360	360	360
Rural - High Speed (over 50 mph to 65 mph)	720	720	720
Urban Expressway and Freeway (55 mph to 60 mph)	850	1350	2200
Rural Expressway and Freeway (70 mph to 75 mph)	1000	1500	2640
Interstate/4-Lane Divided (Maintenance and Surveying)	750	1000	1500



**TYPE F  
LANE CLOSURE ON A TWO WAY ROAD USING FLAGGERS**

Two lane highway with one lane closed. Flagger is at a point where it is visible to approaching traffic.

**KEY**


- Delineator Drum
- ▬ Sign
- ▬ Type III Barricade
- ▨ Work/Hazard Area
- ☞ Flagger

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-27-13	
REVISIONS	
DATE	CHANGE
3-13-14	Revised Sign Cell "ROAD WORK XXX FT"

This document was originally issued and sealed by  
**Roger Weigel**  
 Registration Number  
 PE-2930,  
 on 03/13/14 and the original document is stored at the  
 North Dakota Department  
 of Transportation

# CONSTRUCTION TRUCK AND TEMPORARY DETOUR LAYOUTS

D-704-22



- Notes
1. Barricades placed on roadway shall be on a moveable assembly. Signs placed on the roadway shall be placed on skid mounted assemblies. Where necessary, safe speed to be determined by the Engineer.
  2. The reduced speed limit shall be determined dependent on the in place speed limit before construction. The speed limit reduction should not exceed 10 mph below the existing speed limit, unless the design speed of the work zone feature has been reduced below the 10 mph. In this case, the speed limit reduction shall not exceed 30 MPH. Where speed limits are to be reduced more than 30 MPH, a second speed limit sign shall be installed with the desired speed reduction but shall not exceed 30 MPH. The second speed limit sign shall be placed at 1/2 B.
  3. When warning signs are used in urban areas and the signs are not portable, flags shall be installed. The flags shall be 24 inches square, mounted perpendicular to the edges of the diamond sign, and at such a distance above the edge so that when the flag is limp it will not touch the sign. Rural areas will not require flags.
  4. Existing speed limit signs within a reduced speed zone shall be covered. Obliterated or covered pavement marking shall be paid for as Obliteration of Pavement Marking. The covering shall be approved by the engineer.
  5. The contractor has the option of using portable sign supports in lieu of post mounted signs in accordance with the NDDOT Standard Specifications.
  6. The contractor shall install the G20-1b-60 sign when work is suspended for winter.
  7. If existing stop sign is in place, a 48" stop sign is not required.
  8. G20-55-96 sign is not required if this standard is part of other traffic control layouts with this sign or the work is less than 15 days.

KEY

- Type III barricade
- Work area
- Sign
- Flagger

ADVANCE WARNING SIGN SPACING

Road Type	Distance Between Signs Min. (ft)		
	A	B	C
Urban - Low Speed (30 mph or less)	150	150	150
Urban - Low Speed (over 30 to 40mph)	280	280	280
Urban - High Speed (over 40 mph to 50 mph)	360	360	360
Rural - High Speed (over 50 mph to 65 mph)	720	720	720
Urban Expressway and Freeway (55 mph to 60 mph)	850	1350	2200
Rural Expressway and Freeway (70 mph to 75 mph)	1000	1500	2640
Interstate/4-Lane Divided (Maintenance and Surveying)	750	1000	1500

NORTH DAKOTA  
DEPARTMENT OF TRANSPORTATION  
9-27-13

REVISIONS


DATE	CHANGE

This document was originally issued and sealed by  
Roger Weigel  
Registration Number  
PE- 2930,  
on 09/27/13 and the original document is stored at the  
North Dakota Department  
of Transportation



PORTABLE SIGN SUPPORT ASSEMBLY

D-704-50




Notes:

- ① The maximum weight of the assembly is 250 pounds.
- ② Use a 14" wheel and tire.
- ③ Automotive and equipment axle assemblies may not be used for trailer-mounted sign supports.
- ④ Other NCHRP 350 crash tested assemblies are acceptable.


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
11-23-10	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 11/23/10 and the original document is stored at the North Dakota Department of Transportation.


EROSION AND SILTATION CONTROLS  
MEDIAN OR DITCH INLET PROTECTION




FIBER ROLL PROTECTION (MEDIAN OR DITCH INLET)




FIBER ROLL PROTECTION (INLET OF CULVERT)




SILT FENCE PROTECTION (MEDIAN OR DITCH INLET)



GRAVEL INLET PROTECTION (MEDIAN OR DITCH INLET)



SANDBAG PROTECTION (LOW POINT)




SANDBAG PROTECTION (ON SLOPE)

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-03-13	
REVISIONS	
DATE	CHANGE
06-26-14	Updated reference to standard drawing number for fiber roll staking details.


This document was originally issued and sealed by  
 Roger Weigel  
 Registration Number  
 PE-2930,  
 on 06/26/14 and the original document is stored at the North Dakota Department of Transportation

REINFORCED CONCRETE PIPE CULVERTS AND END SECTIONS  
(Round Pipe)



REINFORCED CONCRETE PIPE - FLARED END SECTION  
Reinforcement to be equivalent to Class III RCP


TRAVERSABLE END SECTION							
DIA	B	C	D	E	F	R	S
15"	4"	9"	4'-9"	1'-7 1/2"	2 1/2"	3"	6"
18"	5'-9"	9"	6'-6"	1'-11"	2 1/2"	3"	6"
24"	6"	1'	7"	2'-6"	3"	3"	4"
30"	7'-6"	1'	8'-6"	3'-1"	3 1/2"	3 1/2"	4"
36"	7'-3"	15"	8'-6"	3'-8"	4"	3"	4"




NOTES (Traversable End Section):

1. Manufactured in accordance with applicable portions of ASTM C76/AASHTO M170.
2. Reinforcement per Class III RCP with double reinforcement in the upper 120° of the full barrel portion.


REINFORCED CONCRETE PIPE - TRAVERSABLE END SECTION  
Reinforcement to be equivalent to Class III RCP



END VIEW  
CIRCULAR PIPE




TONGUE & GROOVE JOINT



BELL & SPIGOT JOINT

JOINTS FOR REINFORCED CONCRETE PIPE



CONCRETE PIPE PLUG

FLARED END SECTION						
TERMINAL DIMENSIONS						
DIA	A	B	C	D	E	U
12	0'-4"	2'-0"	4'-0 7/8"	6'-0 7/8"	2'-0"	2"
15	0'-6"	2'-3"	3'-10"	6'-1"	2'-6"	2 1/4"
18	0'-9"	2'-3"	3'-10"	6'-1"	3'-0"	2 1/2"
21	0'-9"	3'-0"	3'-1"	6'-1"	3'-6"	2 3/4"
24	0'-9 1/2"	3'-7 1/2"	2'-6"	6'-1 1/2"	4'-0"	3"
27	0'-10 1/2"	4'-0"	2'-1 1/2"	6'-1 1/2"	4'-6"	3 1/4"
30	1'-0"	4'-6"	1'-7 3/4"	6'-1 3/4"	5'-0"	3 1/2"
36	1'-3"	5'-3"	2'-9"	8'-0"	6'-0"	4"
42	1'-9"	5'-3"	2'-9"	8'-0"	6'-6"	4 1/2"
48	2'-0"	6'-0"	2'-0"	8'-0"	7'-0"	5"
54	2'-3"	5'-5"	2'-9 1/4"	8'-2 1/4"	7'-6"	5 1/2"
60	2'-11"	5'-0"	3'-3"	8'-3"	8'-0"	5"
66	2'-6"	6'-0"	2'-3"	8'-3"	8'-6"	5 1/2"
72	3'-0"	6'-6"	1'-9"	8'-3"	9'-0"	6"
78	3'-0"	7'-6"	1'-9"	9'-3"	9'-6"	6 1/2"
84	3'-0"	7'-6 1/2"	1'-9"	9'-3 1/2"	10'-0"	6 1/2"
90	3'-5"	7'-3 1/2"	2'-0"	9'-3 1/2"	11'-0"	6 1/2"

All Classifications of Round Concrete Pipe

Internal Dia. of Pipe (in. Inches)	Cross-Sectional Water Area (Sq. ft.)	Weight per Lin. Foot of Pipe (Lbs.)	Joint Groove Min./Max. (in.)	Joint Tongue Min./Max. (in.)	Minimum Wall Thickness (in.)
12	0.79	92	1 1/8-2 3/8	3/4	2
15	1.23	127	1 1/4-2 3/4	7/8	2 1/4
18	1.77	168	1 1/2-2 7/8	1	2 1/2
21	2.40	214	1 7/8-3 1/4	1 1/8	2 3/4
24	3.14	265	2 1/4-3 3/4	1 1/2	3
27	3.98	322	2 3/4-4	1 3/4	3 1/4
30	4.91	384	3 1/4-4 1/4	1 3/4	3 1/2
33	5.94	452	3 1/4-4 1/4	1 1/2	3 3/4
36	7.07	524	3 3/4-4 1/4	1 1/2	4
42	9.62	685	3 3/4-4 1/4	1 3/4	4 1/2
48	12.57	885	3 3/4-4 1/4	1 3/8	5
54	15.90	1070	4 1/2-5 1/2	2	5 1/2
60	19.63	1296	4 1/2-5 1/2	2 1/4	6
66	23.76	1542	5-6	2 3/8	6 1/2
72	28.27	1810	5 1/2-6 3/4	2 3/4	7
78	33.18	2098	6 1/4-7 1/4	2 3/8	7 1/2
84	38.48	2410	5 3/4-7 3/4	3 3/8	8
90	44.18	2793	6 3/4-8 1/2	3 3/4	8 1/2
96	50.27	3092	7-8 1/4	3 1/2	9
102	56.75	3466	7-8 1/4	3 1/2	9 1/2
108	63.62	3864	7 1/4-8 1/2	3 3/4	10

SEE STANDARD DRAWING D-714-22 FOR DETAILS OF CONCRETE PIPE TIES (TIE BOLTS).




NOTES:

1. All reinforcing steel shall meet AASHTO M170 requirements.
2. All circular, longitudinal, and elliptical reinforcement shall be assembled and securely fastened in cage fashion so as to maintain reinforcement in exact shape and correct positions within the forms.
3. Laying length of pipe: 12" to 66" (incl.) = not less than 4 feet  
66" to 108" (incl.) = not less than 6 feet
4. Joints shall be sealed with rubber gaskets or with sealer approved by the engineer whenever pipe are specified for storm drain or sanitary sewers.
5. For Class IV and Class V reinforced concrete pipe and end sections, shop drawings and design calculations shall be sealed by a Professional Engineer and submitted for Engineer's review.




NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
05-12-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Terrence R. Udland, Registration Number PE-2674, on 05/12/14 and the original document is stored at the North Dakota Department of Transportation




# CONCRETE PIPE OR PRECAST CONCRETE BOX CULVERT TIES





SECTION A-A



DETAIL A



DETAIL B



REQUIRED SIZE OF TIE BOLTS		
Pipe Size	Thread $\phi$	XXS Pipe Sleeve Inner $\phi$
18" - 24"	$\frac{5}{8}$ " See note 2	$\frac{3}{4}$ "
30" - 66"	$\frac{3}{4}$ "	1"
72" - 78"	1"	1 $\frac{1}{4}$ "
RCB		

NOTES:


- The pipe size listed is the inside diameter of round pipe or the equivalent diameter of pipe arch.
- Nuts and washers are not required on Jacked and Bored pipes or pipes with a 24" diameter or less. Where nuts and washers are not used, the tie bars shall be inserted and grouted into place.
- Ties are only for holding pipe or RCB sections together, not for pulling sections tight.
- Tie bolt assembly shall be hot dip galvanized in accordance with AASHTO M232.
- Holes in pipes to accommodate tie bolts can be precast or drilled. Tapered holes are permitted when precast. Holes shall have a diameter  $\frac{1}{4}$ " larger than the diameter of the thread. Holes in precast RCB's shall contain cast-in bolt sleeves with an inside diameter of  $\frac{1}{4}$ ".
- The contractor has the option of selecting the type of tie bolt used from those shown.
- The cost of precasting or drilling the required holes and furnishing and installing the tie bolts shall be included in the price bid for the appropriate conduit or RCB pay item.
- All concrete culvert and storm sewer joints, including the end section joints, shall be tied unless otherwise specified.
- When joint wrap is specified in the plans, place wrap beneath ties. Overlap the joint by 12" in both directions.
- Tie bolts shall conform to ASTM A 36. Nuts shall be heavy hex and conform to ASTM A 563. Washers shall conform to ASTM F 436, Type 1. Welded pipe sleeves and cast-in bolt sleeves shall conform to ASTM A 53, Grade B.
- Cattle Pass and Jacked and Bored pipes shall have pipe ties inserted from the inside of the pipes and grouted into place. Jacked and bored pipes with a diameter of 24" or less do not require pipe ties.
- RCB tie locations shall be as shown on the plans.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
3-18-14	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by Terrence R. Udland, Registration Number PE-2674, on 3/18/2014 and the original document is stored at the North Dakota Department of Transportation

PIPE EXCAVATION AND INSTALLATION DETAIL FOR LONGITUDINAL MAINLINE PIPE  
OR PIPE NOT UNDER THE ROADWAY

D-714-27



EXCAVATION DETAIL A



EXCAVATION DETAIL B

Pay Items

- 1) Pipe\*
- 2) Removal of Pipe (if required)

\*Included in Pipe Pay Item

- 1) Pipe
- 2) Trench excavation
- 3) Aggregate base course CI 3 or CI 5
- 4) Common Excavation - Type A
- 5) Common Excavation - Type B


NOTES:

- 1) This drawing does not apply to pipes in approaches.
- 2) It is the contractor's option to select Detail A or B.

Bedding and Haunch (A)
Pipes Not Under Roadway = 0.5 O.D. + 4 Inches
Pipes Under the Roadway = 0.5 O.D. + 2 Feet

Backfill Cover (B)
Concrete Pipe = 0.5 O.D.
Metal Pipe = 0.5 O.D. + 1 Foot
PVC/HDPE = 0.5 O.D. + 1 Foot

Backfill Material (C)
Top of Pipe 4 Feet or Less Below the Top of Proposed Subgrade = Aggregate Base Course CI 3 or CI 5
Top of Pipe Greater than 4 Feet Below the Top of Proposed Subgrade = Common Excavation - Type A
Pipe Not Under Roadway = Common Excavation - Type B




BACKFILL DETAIL A

BACKFILL DETAIL B


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
7-26-13	
REVISIONS	
DATE	CHANGE
10-15-13	Label Formatting

This document was originally issued and sealed by  
Ron Horner,  
Registration Number  
PE-2087,  
on 10/15/13 and the original document is stored at the  
North Dakota Department  
of Transportation


STANDARD BARBED WIRE FENCE



VEHICLE GATE




HORIZONTAL BRACE DETAIL




LINE POST DETAIL

NOTES


1. No deduction in measured pay length of cable fence will be made for gates, corner assemblies, double brace assemblies, fence terminals, or depression fencing. Abutment fencing shall be included in the price bid for fencing bid items.
2. Double brace assemblies shall be installed at locations shown on the plans or established by the Engineer. The distance between adjacent fence terminals, corner assemblies, or double brace assemblies shall not exceed 1,320 feet.
3. Cost of furnishing and installing inserts and eyebolts shall be included in the unit price bid for fencing bid items. Eyebolts shall be galvanized according to AASHTO designation M-30; inserts of corrosion resistant material need not be galvanized. Concrete inserts shall be of such design that, when installed in the concrete, will be capable of developing the full strength of the 5/8" diameter threaded eyebolt.
4. The type of posts to be used, either wood or steel, shall be determined by the contractor unless otherwise specified in the plans.




FENCE TERMINAL




DETAIL FOR TYING FENCE TO WINGS OF ABUTMENTS



SHORT SPAN DETAIL (FENCE LINE 100' OR LESS)




FASTENING TO POSTS




WRAP-AROUND DETAIL


USE OF POST	TREATED WOOD		STEEL	
	Post dia.	Post length	Post length	Post wt. Lbs/Ft. Anchor wt. Lbs.
Line post	3 1/2"	6'-6"	6'-6"	1.33 (0.67)
Corner post	8"	8'	7'	4.10 (Conc.)
End post	5"	8'		
Brace post	5"	3 1/2"	8'	3.19 (Conc.)
Gate post	5"	8'		
Horizontal brace	3 1/2"	Var.	As approved by the Engineer	




DOUBLE BRACE ASSEMBLY




CORNER ASSEMBLY



CORNER AND DOUBLE BRACE ASSEMBLY STEEL POSTS




FENCE TERMINAL STEEL POSTS




FENCING FOR WIDE DEPRESSIONS

Same installation as shown shall be used on opposite side of depression



BREAK-AWAY FENCE FOR NARROW DEPRESSIONS SUBJECT TO FLOODING



DETAIL FOR ANCHORING FENCES IN DEPRESSIONS\*


\*Locations shall be determined in the field and included in price bid for fencing. Other methods of anchoring the fence may be used if approved by the Engineer.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
2-2-10	
REVISIONS	
DATE	CHANGE
10-02-12	Notes, steel assemblies/posts
11-25-13	Revised Vehicle Gate

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 11/25/2013 and the original document is stored at the North Dakota Department of Transportation

INLET - CATCH BASIN

D-722-1A



NOTES:

1. Other castings, similar in dimension, may be used if the casting conforms to the riser section and has a grate style as specified in the plans which meets or exceeds the waterway area listed. If modifications to the inlet are required to facilitate similar castings the contractor must receive written approval from the Engineer.
2. Castings shall be manufactured in accordance with AASHTO M306-09. Metal used in the manufacture of castings shall conform to AASHTO M105 Class 35B.
3. The contractor shall have the option of using precast or cast-in-place bases. Class of concrete shall be AE. The aggregate size shall be approved by the engineer in the field. Construction shall be in accordance with the NDDOT Standard Specifications.
4. Precast concrete risers shall be constructed in accordance with AASHTO M199.
5. On projects with P.C.C. pavement all inlet risers shall be constructed 4 to 5 inches below final elevation and adjusted to final grade after paving. Adjustment may be done with adjusting rings, masonry or cast-in-place concrete. All costs for this adjustment shall be included in the price bid for the inlet.
6. All reinforcing steel shall be Grade 60 steel.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
05-14-13	
REVISIONS	
DATE	CHANGE
6-24-14	Revised Note 3

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 6-24-14 and the original document is stored at the North Dakota Department of Transportation

