

DESIGN DATA			
Traffic	Average Daily		
Current 2015 W; E	Pass: 1,325; 1,335	Trucks: 345; 355	Total: 1,670; 1,690
Forecast 2035 W; E	Pass: 1,975; 1,990	Trucks: 515; 530	Total: 2,490; 2,520
Clear Zone Distance: Outside 28 ft, Median 32 ft		Design Speed: 70	
Minimum Sight Dist. for Stopping: 730 ft		Bridges: NA	
Limited Access Control			
Pavement Design Life 20 (years)			
Design Accumulated One-way Flexible ESALs: 2,616,219			

STATE	PROJECT NO.	PCN	SECTION NO.	SHEET NO.
ND	NH-3-002(145)254	20782	1	1



JOB # 22
NORTH DAKOTA
DEPARTMENT OF TRANSPORTATION

NH-3-002(145)254

Ramsey County
 RP 254.481 to RP 254.941 EB/WB
 Widening and HMA Overlay

GOVERNING SPECIFICATIONS:
 2014 Standard Specifications adopted by the North Dakota
 Department of Transportation and the Supplemental Specifications
 effective on the date the project is advertised.

PROJECT NUMBER \ DESCRIPTION	NET MILES	GROSS MILES
NH-3-002(145)254	.460	.460



STATE COUNTY MAP

DESIGNERS
 Kristen Weninger /s/

APPROVED DATE 1/27/2016
 Roger Weigel /s/
 for OFFICE OF PROJECT DEVELOPMENT
 ND DEPARTMENT OF TRANSPORTATION

I hereby certify that the attached plans were prepared by me or under my direct supervision and that I am a duly registered professional engineer under the laws of the state of ND.
 APPROVED DATE 1/27/16
 James Douglas Rath /s/
 NDDOT DESIGN DIVISION

This document was originally issued and sealed by James Douglas Rath, Registration Number PE- 4288, on 1/27/16 and the original document is stored at the North Dakota Department of Transportation

TABLE OF CONTENTS

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	NH-3-002(145)254	2	1

PLAN SECTIONS

Section	Page(s)	Description
1	1	Title Sheet
2	1	Table of Contents
4	1	Scope of Work
6	1	Notes
6	2 - 3	Environmental Commitments
8	1 - 2	Quantities
10	1	Basis of Estimate
11	1	Data Tables
20	1 - 5	General Details
30	1 - 3	Typical Sections
51	1	Allowable Pipe List
60	1 - 3	Plan & Profile
75	1	Wetland Impacts
76	1	Temporary Erosion Control
77	1	Permanent Erosion Control
81	1	Survey Coordinate and Curve Data
100	1	Work Zone Traffic Control
110	1 - 2	Signing
200	1 - 40	Cross Sections

SPECIAL PROVISIONS

Number	Description
SP 0003(14)	Temporary Erosion and Sediment Best Management Practices


LIST OF STANDARD DRAWINGS

Number	Description
D-101-1, 2,3	NDDOT Abbreviations
D-101-10	NDDOT Utility Company and Organization Abbreviations
D-101-20, 21	Line Styles
D-101-30, 31,32	Symbols
D-203-8	Standard Rural Approaches
D-260-1	Erosion and Siltation Controls - Silt Fence
D-261-1	Erosion Control - Fiber Roll Placement Details
D-704-2	Traffic Control For Coring of Hot Bituminous Pavement
D-704-5	Construction Sign Detail
D-704-7	Breakaway Systems for Construction Zone Signs - Perforated Tube
D-704-8	Breakaway Systems for Construction Zone Signs - U-Channel Post
D-704-9	Construction Sign Details - Terminal and Guide Signs
D-704-10	Construction Sign Details - Regulatory Signs
D-704-11	Construction Sign Details - Warning Signs
D-704-12	Shoulder Closure Tapers
D-704-13	Barricade and Channelizing Device Details
D-704-14	Construction Sign Punching and Mounting Details
D-704-15	Road Closure Layouts
D-704-20	Terminal and Seal Coat Sign Layouts
D-704-22	Construction Truck and Temporary Detour Layouts
D-704-24	Shoulder Closures and Bridge Painting Layouts
D-704-26	Miscellaneous Sign Layouts
D-704-27	Traffic Control Plan for Moving Operations
D-704-34	Sign Layout for One Lane Closure
D-704-56	Mobile Operation - Grinding Shoulder Rumble Strips
D-706-1	Bituminous Laboratory
D-714-1	Reinforced Concrete Pipe Culverts and End Sections (Round Pipe)
D-714-4	Round Corrugated Steel Pipe Culverts and End Sections
D-714-22	Concrete Pipe or Precast Concrete Box Culvert Ties
D-714-27	Pipe Installation Detail for Longitudinal Mainline Pipe or Pipe Not Under the Roadway
D-754-9	Letter and Arrow Details for Variable Length Signs
D-754-23	Perforated Tube Assembly Details
D-754-77, 78	Sign Punching, Stringer and Support Location Details - Divided Highway Control Signs
D-760-2	Rumble Strips Divided Highways (Non-Interstate)
D-762-4	Pavement Marking
D-762-6	Short-Term Pavement Marking

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	NH-3-002(145)254	4	1



-  Widening
-  3" HMA Overlay
-  4" HMA Overlay



This document was originally issued and sealed by
 Brian J. Rosin
 Registration Number
 PE- 2928,
 on 2/1/16 and the original document is stored at the
 North Dakota Department
 of Transportation

Scope of Work

Widening and HMA Overlay
 RP 254.481 to RP 254.941 EB/WB

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	NH-3-002(145)254	6	1

NOTES

107-P01 HAUL ROADS: The Engineer will not designate paved roads off the state system as haul roads. If choosing to use a paved road off the state system for this project, obtain written permission from the applicable local entity and bear all costs of the inspection, maintenance, restoration, and release of the haul road. Use Class 13 aggregate for haul road restoration.

Consider the entire haul cycle, loaded and empty, for haul routes. Before submitting a proposal, contact the appropriate State, County, Township, or City officials to determine if there are any roadways that will be designated as "no haul routes".

202-P01 REMOVAL OF BITUMINOUS SURFACING: Include the cost of the full depth vertical saw cuts adjacent to pavement removal areas, specified in Section 202.04 A "General", in the contract unit price for "Removal of Bituminous Surfacing."

203-010 SHRINKAGE: 25 percent additional volume is included for shrinkage in earth embankment.

260-P01 SILT FENCE: Do not embed silt fence installed in standing water.

261-P01 PERMANENT FIBER ROLLS: If fiber rolls are to remain on the project, use fiber rolls that are composed of plastic or natural fiber photodegradable netting that has a life expectancy between 12 to 24 months. If the photodegradable netting is plastic, use either clear or green colored netting. Black plastic netting will not be allowed.

430-P01 CONTRATOR CORING: Before placing bituminous material into core holes, apply a tack coat on all sides of the core holes as specified in Section 401.

704-P01 TRAFFIC CONTROL FOR BITUMINOUS PAVEMENT: Provide traffic control consisting of a temporary lane closure and flagging.

Traffic control device quantities are based on two half-mile lane closures and the list below. The Department will pay for delineator drums used for approach access within the lane closures at the contract unit price. Provide additional devices at no cost to the Department.

1. Standard D-704-20, layout G. Signing will be required at junction: 70th Ave NE;
2. Standard D-704-22, layouts K and L;
3. Standard D-704-24, layouts HH and S;
4. Standard D-704-26, layouts CC, EE, and GG;
5. Standard D-704-34; quantities include 20 delineator drums for approaches.

If the lane closure is removed and uneven lanes exist, provide traffic control as specified in Section 704.04 O, "Traffic Control for Uneven Pavement".

704-P02 TRAFFIC CONTROL – EDGE DROP-OFF: When there is an edge drop-off greater than two inches at the end of the day, construct a temporary wedge with a foreslope of 4:1 or flatter and install stackable vertical panels along the edge of the driving lane adjacent to the drop-off to replace the one-lane closure until work resumes.

The Engineer will not measure material used to construct the wedge. Include cost for the wedge required in this operation in the price bid for aggregate pay items.

706-P01 LABORATORY: Provide laboratories wired for DSL Broadband internet with Wi-Fi and having the capability to allow for hard wiring the computer.

Include the cost of the installation and monthly fee in the contract unit price of the laboratory.

714-P01 REDUCER: Use a 21" to 24" Class III RCP eccentric reducer section at the centerline pipe median connection. Include all costs for providing and installing the eccentric reducer in the unit price bid "Pipe Conc. Reinf. 24IN CI III."

990-P01 APPROACH PIPE CLEANOUT: The location of the approach pipes at 13447+59 – 131' LT, 13447+62 – Median, and 13449+78 – 155' RT were not located within the survey and the locations shown are assumed locations based on the set of plans when they were installed. These approach pipes are assumed to be buried with an approximate 2' grade raise that was constructed in 2013.

Locate the ends of the approach pipes, remove dirt/debris from the ends of the approach pipes, and from inside the pipes. Dispose of the dirt/debris removed. Include all costs for locating and removing dirt/debris from the approach pipes in the unit price bid for "Pipe Cleanout."

This document was originally issued and sealed by Brian J. Rosin, Registration Number PE-2928, on 3/17/16 and the original document is stored at the North Dakota Department of Transportation.

ENVIRONMENTAL COMMITMENTS

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	NH-3-002(145)245	6	2

ENVIRONMENTAL COMMITMENTS (EC): The North Dakota Department of Transportation and the Federal Highway Administration have made environmental commitments to secure approval of this project. The environmental commitments are as follows:

EC-1: Unavoidable permanent impacts will be mitigated onsite, adjacent to the project, or at a NDDOT approved mitigation site or bank in accordance with the mitigation guidance^{2,3}.

ACTION REQUIRED /TAKEN: 1.77 acres of permanent impacts to EO11990 wetlands will require mitigation. The NDDOT will mitigate EO 11990 impacts at Vollrath 16/17 in the Red River Basin Regional Service Area. 0.82 acres of temporary impacts will result from construction. Temporary impact areas will be graded to preconstruction contours.

Wetland Impact Table																			
Wetland Number	Location	Cowardin Class.	Wetland Type	Wetland Size (acres)	Wetland Feature	USACE Jurisdictional Wetlands ¹	Wetland Impacts (acres)		USFWS Easement Impacts (acres)		Wetland Mitigation								
							Temp.	Perm.	Temp.	Perm.	Mitigation Required			Bank		Onsite			
											EO 11990	USACE	USFWS	Location	acres	Mitigation Location; Ratio	acres	Constructed Site #	Constructed size (acres)
1a	Sec.22, T155N, R66W	PEMC	Basin	3.29	Natural	No	0.32	0.28	0.00	0.00	Y	N	N	Vollrath 16/17	0.28				
1b	Sec.22, T155N, R66W	PEMC	Basin	1.02	Natural	No	0.00	0.73	0.00	0.00	Y	N	N	Vollrath 16/17	0.73				
1c	Sec.22, T155N, R66W	PEMC	Basin	2.32	Natural	No	0.20	0.27	0.00	0.00	Y	N	N	Vollrath 16/17	0.27				
1d	Sec.23, T155N, R66W	PEMC	Basin	0.40	Natural	No	0.07	0.04	0.00	0.00	Y	N	N	Vollrath 16/17	0.04				
1e	Sec.23, T155N, R66W	PEMCx	Ditch	1.95	Artificial	No	0.05	0.01	0.00	0.00	N	N	N		0.00				
2a	Sec.23, T155N, R66W	PEMC	Basin	1.37	Natural	No	0.12	0.18	0.00	0.00	Y	N	N	Vollrath 16/17	0.18				
2b	Sec.23, T155N, R66W	PEMCx	Ditch	0.44	Artificial	No	0.06	0.06	0.00	0.00	N	N	N		0.00				
3a	Sec.23, T155N, R66W	PEMC	Basin	0.32	Natural	No	0.00	0.27	0.00	0.00	Y	N	N	Vollrath 16/17	0.27				
Totals				11.11			0.82	1.84	0.00	0.00					1.77		0.00		0.00

¹ A wetland Jurisdictional Determination was issued by the USACE on 9/15/2015; NWO-2015-1467-BIS.

² All impacts to natural wetlands (natural/jurisdictional and natural/non-jurisdictional), regardless of size, as well as impacts greater than 0.10 acre to artificial/jurisdictional wetlands require mitigation.

³ All artificial/non-jurisdictional, deep water (impacts greater than 6.6 feet), Other Waters less than 300 linear feet (determined by the USACE on a case by case), and temporary impacts do not require mitigation.

ENVIRONMENTAL COMMITMENTS

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	NH-3-002(145)245	6	3

Summary Impact Table			
Total Permanent Impact Summary		Temporary Impacts and additional information	
Wetland Type	Total (Acres)	Wetland Type	Total (Acres/Lf)
Natural/JD	0.00	Temporary JD	0.00
Natural/Non-JD	1.77	Non-JD Temporary	0.82
Artificial/JD	0.00	Permanent JD > 0.10	0.00
Artificial /Non-JD	0.07	Permanent OW	0.00
Total	1.84	Temporary OW	0.00

ESTIMATE OF QUANTITIES

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	NH-3-002(145)254	8	1

SPEC CODE	ITEM DESCRIPTION	UNIT	MAINLINE	TOTAL
-----	-----	-----	-----	-----
103	0100 CONTRACT BOND	L SUM	0.4	0.4
202	0132 REMOVAL OF BITUMINOUS SURFACING	SY	668	668
202	0169 REMOVAL OF END SECTION-ALL TYPES & SIZES	EA	1	1
202	0170 REMOVAL OF CULVERTS-ALL TYPES & SIZES	LF	75	75
203	0101 COMMON EXCAVATION-TYPE A	CY	752	752
203	0119 TOPSOIL-IMPORTED	CY	4,051	4,051
203	0140 BORROW-EXCAVATION	CY	14,550	14,550
216	0100 WATER	M GAL	211	211
251	0200 SEEDING CLASS II	ACRE	5.32	5.32
251	1000 WETLAND SEED	ACRE	0.73	0.73
251	2000 TEMPORARY COVER CROP	ACRE	5.32	5.32
253	0101 STRAW MULCH	ACRE	10.64	10.64
255	0104 ECB TYPE 4	SY	4,002	4,002
260	0100 SILT FENCE UNSUPPORTED	LF	3,165	3,165
260	0101 REMOVE SILT FENCE UNSUPPORTED	LF	3,165	3,165
261	0112 FIBER ROLLS 12IN	LF	1,458	1,458
261	0113 REMOVE FIBER ROLLS 12IN	LF	585	585
302	0120 AGGREGATE BASE COURSE CL 5	TON	2,578.6	2,578.6
401	0050 TACK COAT	GAL	1,375	1,375
411	0105 MILLING PAVEMENT SURFACE	SY	600	600
411	0110 MILLING PCC PAVEMENT	SY	450	450
430	0045 SUPERPAVE FAA 45	TON	2,976.5	2,976.5
430	1000 CORED SAMPLE	EA	18	18
430	6428 PG 64-28 ASPHALT CEMENT	TON	178.6	178.6
702	0100 MOBILIZATION	L SUM	0.4	0.4
704	0100 FLAGGING	MHR	300	300
704	1000 TRAFFIC CONTROL SIGNS	UNIT	3,254	3,254
704	1052 TYPE III BARRICADE	EA	6	6
704	1060 DELINEATOR DRUMS	EA	86	86
704	1067 TUBULAR MARKERS	EA	56	56
704	1080 STACKABLE VERTICAL PANELS	EA	30	30
704	1087 SEQUENCING ARROW PANEL-TYPE C	EA	2	2
704	1185 PILOT CAR	HR	100	100

ESTIMATE OF QUANTITIES

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	NH-3-002(145)254	8	2

SPEC CODE	ITEM DESCRIPTION	UNIT	MAINLINE	TOTAL
-----	-----	-----	-----	-----
706 0500	AGGREGATE LABORATORY	EA	0.4	0.4
706 0550	BITUMINOUS LABORATORY	EA	0.4	0.4
706 0600	CONTRACTOR'S LABORATORY	EA	0.4	0.4
714 0310	PIPE CONC REINF 18IN CL III	LF	14	14
714 0400	PIPE CONC REINF 21IN CL III	LF	16	16
714 0615	PIPE CONC REINF 24IN CL III	LF	45	45
714 3013	END SECT-TRAVERSABLE REINF. CONC.18IN	EA	1	1
714 3015	END SECT-CONC REINF 21IN	EA	1	1
714 4106	PIPE CONDUIT 24IN-APPROACH	LF	118	118
714 5015	PIPE CORR STEEL .064IN 18IN	LF	40	40
714 5035	PIPE CORR STEEL .064IN 24IN	LF	8	8
714 5810	END SECT CORR STEEL .064IN 18IN	EA	2	2
714 5820	END SECT CORR STEEL .064IN 24IN	EA	2	2
714 9660	REMOVE & RELAY END SECTION-ALL TYPE & SIZES	EA	1	1
754 0592	RESET SIGN PANEL	EA	6	6
754 0593	RESET SIGN SUPPORT	EA	11	11
760 0005	RUMBLE STRIPS - ASPHALT SHOULDER	MILE	1.365	1.365
762 0430	SHORT TERM 4IN LINE-TYPE NR	LF	1,800	1,800
762 1104	PVMT MK PAINTED 4IN LINE	LF	8,108	8,108
762 1124	PVMT MK PAINTED 24IN LINE	LF	85	85
990 0400	PIPE CLEANOUT	EA	2	2

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	NH-3-002(145)254	10	1

Material	Unit	Mainline EB Sta 13438+98 to Sta 13454+00		Mainline WB Sta 13438+98 to Sta 13454+00		Median Approach	North Approach	South Approach
		Width (ft)	Qty per Sta	Width (ft)	Qty per Sta			
Removal of Bituminous Surfacing	SY	-	22.22	-	22.22	0.00	0.00	0.00
CL 5 Aggregate Base @ 1.5 Ton/CY + 25%	TON	-	45.94	-	37.29	412.14	409.73	506.55
Tack Coat @ 0.05 Gal/SY (1st Lift)	GAL	29.19	16.22	38.43	21.35	30.38	25.05	32.86
Tack Coat @ 0.05 Gal/SY (2nd Lift)	GAL	28.10	15.61	37.22	20.68	26.87	21.52	24.42
Superpave FAA 45 @ 2 Ton/CY	TON	29.19	52.02	38.43	105.68	194.13	160.04	209.93
PG 64 -28 Asphalt Cement @ 6.0%	TON	-	3.12	-	6.34	11.65	9.60	12.60

Short Term 4IN Line - Type NR		
Location - Type	Basis	Quantity
EB		
Centerline - Top of 1st Lift	Centerline Skips - 1,320 LF/Mile	450 LF
Centerline - Top of Final Lift	Centerline Skips - 1,320 LF/Mile	450 LF
WB		
Centerline - Top of 1st Lift	Centerline Skips - 1,320 LF/Mile	450 LF
Centerline - Top of Final Lift	Centerline Skips - 1,320 LF/Mile	450 LF

Permanent Pavement Marking		
Location - Type	Basis	Quantity
EB		
Centerline - Pvmt MK Painted 4IN Line	Centerline Skips - 1,320 LF/Mile	450 LF
Edge Line - Pvmt MK Painted 4IN Line	Edge Line - 10,560 LF/Mile	3,604 LF
WB		
Centerline - Pvmt MK Painted 4IN Line	Centerline Skips - 1,320 LF/Mile	450 LF
Edge Line - Pvmt MK Painted 4IN Line	Edge Line - 10,560 LF/Mile	3,604 LF

Water

25 Mgal/Mile for Dust Palliative
20 Gal/Ton for Aggregates
10 Gal/CY for Embankment

HMA Cored Samples							
Specification Section	A	B	C	D	Quantity (D*2)	Quantity (1 per mile)	Unit
	Lanes	Lifts	Distance (Feet)	Sublots (A*B*C)/2000			
430.04 I.2.b(1), "General"	EB Driving 1st Lift	1	1502	1	2	N/A	EA
	EB Passing 1st Lift	1	1502	1	2	N/A	EA
	EB Driving 2nd Lift	1	1502	1	2	N/A	EA
	EB Passing 2nd Lift	1	1502	1	2	N/A	EA
	WB Driving 1st Lift	1	1502	1	2	N/A	EA
	WB Passing 1st Lift	1	1502	1	2	N/A	EA
	WB Driving 2nd Lift	1	1502	1	2	N/A	EA
	WB Passing 2nd Lift	1	1502	1	2	N/A	EA
430.04 I.2.b(2), "Pavement Thickness Determination Cores"					N/A	2	EA
Total					16	2	EA

This document was originally issued and sealed by
Brian J. Rosin
Registration Number
PE- 2928,
on 3/15/16 and the original document is stored at the
North Dakota Department
of Transportation

Basis of Estimate

Widening and HMA Overlay
RP 254.481 to RP 254.941 EB/WB

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	NH-3-002(145)254	11	1

Station	End Areas (SF)		Volume (CY)		Mass Ordinate
	Excavation	Fill	Excavation	Fill	
13436+00.00	6	0	0	0	0
13436+50.00	2	13	7	15	-8
13437+00.00	2	25	3	43	-49
13437+50.00	1	30	3	63	-109
13438+00.00	2	37	3	78	-184
13438+50.00	1	44	3	94	-275
13439+00.00	13	138	13	210	-472
13439+50.00	11	150	22	333	-784
13440+00.00	10	157	19	356	-1121
13440+50.00	9	164	18	372	-1474
13441+00.00	9	186	17	405	-1862
13441+50.00	8	191	16	437	-2283
13442+00.00	9	170	16	418	-2685
13442+50.00	9	191	16	418	-3087
13443+00.00	8	200	16	453	-3524
13443+50.00	8	240	15	509	-4018
13444+00.00	8	233	15	547	-4550
13444+50.00	8	249	14	558	-5094
13445+00.00	7	248	14	575	-5654
13445+50.00	7	302	14	636	-6277
13446+00.00	7	313	13	712	-6976
13446+50.00	7	353	13	771	-7734
13447+00.00	8	342	14	804	-8525
13447+06.51	8	345	2	103	-8626
13447+50.00	31	362	31	712	-9307
13448+00.00	21	307	48	774	-10033
13448+50.00	40	176	56	559	-10536
13449+00.00	31	341	65	599	-11070
13449+50.00	76	199	99	625	-11596
13450+00.00	19	206	87	468	-11976
13450+50.00	9	167	25	431	-12382
13451+00.00	9	121	16	333	-12699
13451+50.00	11	105	18	261	-12942
13452+00.00	8	116	17	256	-13181
13452+50.00	6	121	13	275	-13443
13453+00.00	8	122	13	281	-13711
13453+50.00	10	104	17	262	-13956
13454+00.00	1	18	11	142	-14086
13454+50.00	1	18	2	41	-14125
13455+00.00	1	14	2	37	-14160
13455+50.00	1	12	2	31	-14188
13456+00.00	1	16	3	33	-14218
13456+50.00	1	14	3	35	-14250
13457+00.00	1	13	3	31	-14279
13457+50.00	2	12	3	29	-14306
13458+00.00	2	12	3	28	-14331
13458+50.00	2	14	3	30	-14358
13459+00.00	2	17	3	35	-14390
13459+50.00	2	19	3	41	-14428
13460+00.00	2	19	3	43	-14469
			Volume (CY)		
			Excavation	Fill	Mass Ordinate
Totals			835	15302	

Excavation (CY)	835
Removal of Pavement (CY)	83
Total Common Excavation (CY)	752


Fill (CY)	15302
Common Excavation (CY)	752
Total Borrow Excavation (CY)	14550

This document was originally issued and sealed by
 Brian J. Rosin
 Registration Number
 PE- 2928,
 on 2/1/16 and the original document is stored at the
 North Dakota Department
 of Transportation

Earthwork


 Widening and HMA Overlay
 RP 254.481 to RP 254.941 EB/WB

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	NH-3-002(145)254	20	1




Removal Section

Cross Section View



Removal Detail

Side View



Removal Section


Cross Section View

- Pay Items**
- 1) Pipe*
 - 2) Remove & Relay Pipe - All Types & Sizes (when required)
 - 3) Remove & Reset End Section or new End Section
 - 4) Borrow Excavation (Compaction Control Type A) or Common Excavation-Type A
 - 5) Topsoil
 - 6) Seeding
 - 7) Mulching

- *Included in Pipe Pay Item**
- 1) Pipe
 - 2) Trench excavation
 - 3) Aggregate Base Course Class 3 or Class 5


- Pay Items**
- 1) Pipe*
 - 2) Remove & Reset End Section or Remove End Section and Place New End Section

- *Included in Pipe Pay Item**
- 1) Pipe
 - 2) Trench excavation
 - 3) Aggregate Base Course Class 3 or Class 5
 - 4) Embankment (Compaction Control Type A)
 - 5) Topsoil, Seeding, and Mulch




Proposed Section

Cross Section View




Backfill Detail

Side View (Topsoil not shown)



Proposed Section

Cross Section View




Proposed Section

Plan View

Pipe Materials	Dim (A) ≤ 4 Feet	Dim (A) > 4 Feet
Concrete	Material (B)	Material (B)
Metal	Embank or Aggr	Embank or Aggr

- NOTES:**
1. Embankment may be either Borrow Excavation (Compaction Control - Type A) or Common Excavation - Type A.
 2. Aggregate may be either Class 3 or Class 5 Aggregate Base Course.



Proposed Section

Plan View

This document was originally issued and sealed by
 Brian J. Rosin
 Registration Number
 PE- 2928,
 on 2/1/16 and the original document is stored at the
 North Dakota Department
 of Transportation

Mainline \varnothing Pipe Extension Detail

Widening and HMA Overlay
 RP 254.481 to RP 254.941 EB/WB

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	NH-3-002(145)254	20	2



NOTES:

Tie all pipe extension joints through the median.

Place fill to provide drainage into the pipe end sections.


If unable to fit the median pipe extension tightly together using the bell and spigot only, the contractor may use either, the exterior metal connection band method shown below, a poured in-place manhole, or other method approved by the engineer. Include all costs for grouting, connecting band method, or manhole and grouting in the unit price bid for "Pipe Conc Reinf 24IN CL III."

Use a butyl joint material to seal the pipes to the band, when using an exterior metal connection band.




** Refer to Standard D-714-1 for culvert details and Standard D-714-2 for arch culvert details.

Exterior Galvanized Steel Band Detail



Section A-A

*Gap should be no more than 1" greater than the RCP tongue length.






Median Pipe Connection
Exterior Galvanized Steel Band Detail
Section B-B


This document was originally issued and sealed by Brian J. Rosin Registration Number PE-2928, on 2/1/16 and the original document is stored at the North Dakota Department of Transportation

Centerline Pipe Median Connections (One-Way Drain)

Widening and HMA Overlay
RP 254.481 to RP 254.941 EB/WB



Milling Transitions									
Begin Transition					End Transition				
X (feet)	Begin Station	Y (inches)	End Station	YY (inches)	YY (inches)	Begin Station	Y (inches)	End Station	X (feet)
75	13437+48	1.5	13438+23	0	0	13455+50	1.5	13454+75	75






Paving Transitions							
X (feet)	Begin (Y)	Y (inches)	YY Station	XX (feet)	YY (inches)	End YYY	YYY (inches)
75	13437+48	1.5	13438+23	75	1.5	13438+98	3
75	13455+50	1.5	13454+75	75	1.5	13454+00	3


This document was originally issued and sealed by Brian J. Rosin, Registration Number PE- 2928, on 2/1/16 and the original document is stored at the North Dakota Department of Transportation

EB Milling & Paving Transitions Detail

Widening and HMA Overlay
RP 254.481 to RP 254.941 EB/WB



Milling Transitions									
Begin Transition					End Transition				
X (feet)	Begin Station	Y (inches)	End Station	YY (inches)	YY (inches)	Begin Station	Y (inches)	End Station	X (feet)
75	13437+48	1.5	13438+23	0	0	13455+50	1.5	13454+75	75






Paving Transitions							
X (feet)	Begin (Y)	Y (inches)	YY Station	XX (feet)	YY (inches)	End YYY	YYY (inches)
75	13437+48	1.5	13438+23	75	1.5	13438+98	3
75	13455+50	1.5	13454+75	75	1.5	13454+00	3

This document was originally issued and sealed by Brian J. Rosin, Registration Number PE- 2928, on 2/1/16 and the original document is stored at the North Dakota Department of Transportation

WB Milling & Paving Transitions Detail

Widening and HMA Overlay
RP 254.481 to RP 254.941 EB/WB

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	NH-3-002(145)254	20	5





This document was originally issued and sealed by
 Brian J. Rosin
 Registration Number
 PE- 2928,
 on 2/1/16 and the original document is stored at the
 North Dakota Department
 of Transportation

BASIS OF ESTIMATE		Gravel	Median
ITEM	UNIT	Section Line	Approach
Number of Locations	#	2	1
Aggregate Base Course CI 5	TON	916	412
Tack Coat	GAL	104	57
Superpave FAA 45	TON	370	194
PG 64-28 Asphalt Cement	TON	22	12

Approach Paving Details
Widening and HMA Overlay
RP 254.481 to RP 254.941 EB/WB

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	NH-3-002(145)254	30	1





This document was originally issued and sealed by
 Brian J. Rosin
 Registration Number
 PE- 2928,
 on 2/1/16 and the original document is stored at the
 North Dakota Department
 of Transportation

Existing Typical Sections

Widening and HMA Overlay

RP 254.481 to RP 254.941 EB/WB

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	NH-3-002(145)254	30	2



This document was originally issued and sealed by
 Brian J. Rosin
 Registration Number
 PE- 2928,
 on 3/16/16 and the original document is stored at the
 North Dakota Department
 of Transportation



Removal Typical Sections

Widening and HMA Overlay

RP 254.481 to RP 254.941 EB/WB

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	NH-3-002(145)254	30	3

* Water elevation at 1455.7' on 1/14/2015



This document was originally issued and sealed by
 Brian J. Rosin
 Registration Number
 PE- 2928,
 on 3/16/16 and the original document is stored at the
 North Dakota Department
 of Transportation

Proposed Typical Sections
 Widening and HMA Overlay
 RP 254.481 to RP 254.941 EB/WB

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	NH-3-002(145)254	51	1

Begin Station / Location	Begin Offset	End Station / Location	End Offset	Pipe Installation (Pay Item)		Allowable Material	Required Diameter	Steel Pipe Coatings	Steel Pipe Corrugations or Spiral Ribs	Steel Pipe Minimum Thickness	R1 Fabric (Pay Item)	(*) End Sections		Applicable Backfill Detail
				In	LF							Begin EA	End EA	
13447+06	16' Rt	13447+07	15' Lt	24	Pipe Conc. Reinf. CL III (Extension)	31'	Reinforced Concrete Pipe - Class III (barrel length = 31 LF)	24				Remove		Section 20 Sheet 1
13447+06	0'	13447+27	0'	18	Pipe Conc. Reinf. CL III (Extension)	14'	Reinforced Concrete Pipe - Class III (barrel length = 14 LF)	18					TES	Section 20 Sheet 1
13447+06	91' RT	13447+06	111' Rt	24	Pipe Conc. Reinf. CL III (Extension)	14'	Reinforced Concrete Pipe - Class III (barrel length = 14 LF)	24				Remove and Relay		Section 20 Sheet 1
13447+07	84' Lt	13447+07	106' Lt	21	Pipe Conc. Reinf. CL III (Extension)	16'	Reinforced Concrete Pipe - Class III (barrel length = 16 LF)	21					FES	Section 20 Sheet 1
13448+00	0'	13449+25	0'	24	Pipe Conduit - Approach	118'	Reinforced Concrete Pipe - Class III (barrel length = 113 LF)	18				FES	FES	Section 203.04 E.3
							Corrugated Steel Pipe	18	Z, A, P	2	0.064			
							Spiral Rib Steel Pipe	18	Z, A, P	3/4, 1	0.064			
							High-Density Polyethylene	18						
13447+14	131' Lt	13447+35	131' Lt	18	Pipe Corr. Steel (Extension)	18'	Corrugated Steel Pipe	18	Z, A, P	2	0.064	FES		Section 203.04 E.3
13447+83	131' Lt	13448+08	131' Lt	18	Pipe Corr. Steel (Extension)	22'	Corrugated Steel Pipe	18	Z, A, P	2	0.064		FES	Section 203.04 E.3
13449+28	155' Rt	13449+40	155' Rt	24	Pipe Corr. Steel (Extension)	8'	Corrugated Steel Pipe	24	Z, A, P	2	0.064	FES	FES	Section 203.04 E.3

Coatings: Z = Zinc
A = Aluminum
P = Polymeric (over Zinc or Aluminum)

Corrugations: 2 = 2-2/3"x1/2"
3 = 3"x1"
5 = 5"x1"

Spiral Ribs: 3/4 = 3/4"x3/4"@7-1/2"
1 = 3/4"x1"@11-1/2"

(*) The price bid for "Pipe Conduit" bid items includes end sections. Pipe Extensions shall pay for end sections separately.
FES = Flared End Section
TES = Traversable End Section


This document was originally issued and sealed by Brian J. Rosin, Registration Number PE- 2928, on 2/1/16 and the original document is stored at the North Dakota Department of Transportation

Allowable Pipe List

Widening and HMA Overlay

RP 254.481 to RP 254.941 EB/WB

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	NH-3-002(145)254	60	2



SPEC CODE	BID ITEM	UNIT	QUANTITY
202 169	REMOVAL OF END SECTION-ALL TYPES & SIZES Sta. 13447+06 - 16' RT	EA	1
202 170	REMOVAL OF CULVERTS-ALL TYPES & SIZES Sta. 13448+62 - Median	LF	75
714 310	PIPE CONC REINF 18IN CL III Sta. 13447+06 - Median	LF	14
714 400	PIPE CONC REINF 21IN CL III Sta. 13447+07 - 84' LT	LF	16
714 615	PIPE CONC REINF 24IN CL III Sta. 13447+06 - 16' RT to 15' LT	LF	31
	Sta. 13447+06 - 91' RT to 111' RT	LF	14
714 3013	END SECT-TRAVERSABLE REINF. CONC. 18IN Sta. 13447+27 - Median	EA	1
714 3015	END SECT-CONC REINF 21IN 13447+07 - 106' LT	EA	1
714 4106	PIPE CONDUIT 24IN-APPROACH Sta. 13448+62 - Median	LF	118
714 5015	PIPE CORR STEEL .064IN 18IN Sta. 13447+59 - 131' LT	LF	40
714 5035	PIPE CORR STEEL .064IN 24IN Sta. 13449+78 - 155' RT	LF	8
714 5810	END SECT CORR STEEL .064IN 18IN Sta. 13447+59 - 131' LT	EA	2
714 5820	END SECT CORR STEEL .064IN 24IN Sta. 13449+78 - 155' RT	EA	2
714 9660	REMOVE & RELAY END SECTION - ALL TYPES & SIZES Sta. 13447+06 - 91' RT	EA	1


1475		Sta. 13447+06 - Median Install 18" x 14' Pipe Conc Reinf 18" CL III Install 18" TES. Sta. 13447+27. In 1456.20 Sta. 13447+06 Out 1452.70		Sta. 13447+59 - 131' LT Install 18" x 22' Pipe Corr Steel Install 18" ES In @ Sta. 13447+35 Out @ Sta. 13447+14		Sta. 13447+59 - 131' LT Install 18" x 22' Pipe Corr Steel Install 18" ES In @ Sta. 13448+08 Out @ Sta. 13447+83		Sta. 13449+78 - 155' RT Install 24" x 8' Pipe Corr Steel Install 2- 24" ES In @ Sta. 13449+40 Out @ Sta. 13449+28		Sta. 13448+62 - Median Install 24" x 113' Pipe Conduit - Approach Install 2- 24" ES Sta. 13448+00 Out 1456.40 Sta. 13449+25 In 1456.50	1475
1470											1470
1465											1465
1460											1460
1455											1455
1450											1450
1445											1445
1440											1440
	1,454.80 1,457.19	1,454.82 1,456.98	1,453.51 1,456.76	1,452.94 1,456.55	1,452.84 1,456.38	1,453.69 1,457.85	1,454.45 1,456.68	1,456.04 1,456.88	1,455.59 1,457.07	1,455.58 1,457.27	1,456.02 1,457.47
	13444+00	13445+00	13446+00	13447+00	13448+00	13449+00	13450+00	13451+00	13452+00	13453+00	13454+00

2/16/2016 10:01:59 AM kwninger R:\project\30002254.145\design\060PP_002_Plan and Profile.dgn

This document was originally issued and sealed by
 Brian J. Rosin
 Registration Number
 PE- 2928,
 on 2/1/16 and the original document is stored at the
 North Dakota Department
 of Transportation

Plan and Profile
 Widening and HMA Overlay
 RP 254.481 to RP 254.941 EB/WB

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	NH-3-002(145)254	75	1



 Wetland Impacts Permanent
 Wetland Impacts Temporary

This document was originally issued and sealed by
 Brian J. Rosin
 Registration Number
 PE- 2928,
 on 2/1/16 and the original document is stored at the
 North Dakota Department
 of Transportation


Wetland Impacts

Widening and HMA Overlay

RP 254.481 to RP 254.941 EB/WB

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	NH-3-002(145)254	76	1

SPEC	CODE	BID ITEM	UNIT	QUANTITY
251	2000	TEMPORARY COVER CROP		
		RP 254.481 to 254.941	ACRE	5.32
253	101	STRAW MULCH		
		RP 254.481 to 254.941	ACRE	5.32
260	100	SILT FENCE UNSUPPORTED		
		RP 254.481 to 254.941	LF	3165
260	101	REMOVE SILT FENCE UNSUPPORTED		
		RP 254.481 to 254.941	LF	3165
261	112	FIBER ROLLS 12IN		
		RP 254.481 to 254.941	LF	585
261	113	REMOVE FIBER ROLLS 12IN		
		RP 254.481 to 254.941	LF	585



-  Temporary Cover Crop and Straw Mulch
-  Fiber Roll
-  Silt Fence

This document was originally issued and sealed by
 Brian J. Rosin
 Registration Number
 PE- 2928,
 on 2/1/16 and the original document is stored at the
 North Dakota Department
 of Transportation


Temporary Erosion & Sediment Control

Widening and HMA Overlay

RP 254.481 to RP 254.941 EB/WB

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	NH-3-002(145)254	77	1

SPEC	CODE	BID ITEM	UNIT	QUANTITY
251	200	SEEDING CLASS II		
		RP 254.481 to 254.941	ACRE	5.32
251	1000	WETLAND SEED		
		RP 254.481 to 254.941	ACRE	0.73
253	101	STRAW MULCH		
		RP 254.481 to 254.941	ACRE	5.32
255	104	ECB TYPE 4		
		RP 254.481 to 254.941	SY	4002
261	112	FIBER ROLLS 12IN		
		RP 254.481 to 254.941	LF	873



-  Seeding Area CI II and Straw Mulch
-  Wetland Seed
-  ECB Type 4
-  Fiber Rolls

This document was originally issued and sealed by
 Brian J. Rosin
 Registration Number
 PE- 2928,
 on 2/1/16 and the original document is stored at the
 North Dakota Department
 of Transportation

Permanent Erosion & Sediment Control

Widening and HMA Overlay

RP 254.481 to RP 254.941 EB/WB

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
N.D.	NH-3-002(145)254	110	1

Sta/RP	Sign No.	Assembly No.	Flat Sheet For Signs		Sign Support Length				Support Size	Max Post Len LF	Sleeve Length				Sleeve Size	Anchor EA	Anchor LF	Anchor Size	Reset Sign Panel EA	Reset Sign Support EA	Break-Away EA	Comments
			IV SF	XI SF	1st LF	2nd LF	3rd LF	4th LF			1st LF	2nd LF	3rd LF	4th LF								
US Hwy 2																						
																			1	3		
																			1	1		
																			1	2		
																			1	2		
																			1	1		
																			1	2		
Sub Total			0.0	0.0	Total 0.0														6	11	0	
Grand Total			0.0	0.0	Total 0.0														6	11	0	


Basis of Estimate
Sign Support Lengths

The sign support lengths have been calculated using the following vertical clearances:

- Areas where parking and/or pedestrian movement will occur - 84"
- Urban/rural expressway and freeway - 84" (Offset - 60")
- Rural Roadway - 60"
- Bike route - 60"

<p>This document was originally issued and sealed by Douglas A. Schumaker, Registration Number PE - 5047, on 2/1/2016 and the original document is stored at the North Dakota Department of Transportation</p>	<p>Sign Summary Perforated Tube</p> <p>US Hwy 2 RP 254.481 to RP 254.941 EB/WB Ramsey County</p>
--	--

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	NH-3-002(145)254	110	2



PVMT MK PAINTED 24IN LINE
24" white stop bar 85 LF

Remove object marker and support

- Sta 13440+57 rt
- Sta 13441+49 lt
- Sta 13441+89 rt
- Sta 13442+54 lt
- Sta 13443+15 rt
- Sta 13443+90 rt
- Sta 13444+02 lt
- Sta 13445+12 lt
- Sta 13445+63 rt
- Sta 13446+55 lt
- Sta 13446+85 rt
- Sta 13447+62 lt
- Sta 13448+08 rt
- Sta 13449+12 lt
- Sta 13450+18 lt
- Sta 13450+76 rt
- Sta 13451+50 lt
- Sta 13452+08 rt
- Sta 13452+75 lt

Total 19

This document was originally issued and sealed by Douglas A. Schumaker, Registration Number PE- 5047, on 2/1/16 and the original document is stored at the North Dakota Department of Transportation

Signing and Pavement Marking Layout
US Hwy 2
RP 254.481 to RP 254.941 EB/WB
Ramsey County

NDDOT ABBREVIATIONS

? This is a special text character used in the labeling of existing features. It indicates a feature that has an unknown characteristic, potentially based on: lack of description, location accuracy or purpose.

Abn abandoned
 Abut abutment
 Ac acres
 Adj adjusted
 Aggr aggregate
 Ahd ahead
 ARV air release valve
 Align alignment
 Al alley
 Alt alternate
 Alum aluminum
 ADA Americans with Disabilities Act
 A ampere
 & and
 Appr approach
 Approx approximate
 ACP asbestos cement pipe
 Asph asphalt
 AC asphalt cement
 Assmd assumed
 @ at
 Atten attenuation
 ATR automatic traffic recorder
 Ave Avenue
 Avg average
 ADT average daily traffic
 Az azimuth
 Bk back
 BF back face
 Bs backsight
 Balc balcony
 B Wire barbed wire
 Barr barricade
 Btry battery
 Brg bearing
 BI beehive inlet
 Beg begin
 BM bench mark
 Bkwy bikeway
 Bit bituminous
 Blk block
 Bd Ft board feet
 BH bore hole
 BS both sides
 Bot bottom
 Blvd Boulevard
 Bndry boundary
 BC brass cap
 Brkwy breakaway
 Br bridge
 Bldg building

BV butterfly valve
 Byp bypass
 C Gdrl cable guardrail
 Calc calculate
 Cd candela
 CIP cast iron pipe
 CB catch basin
 CRS cationic rapid setting
 C Gd cattle guard
 C To C center to center
 Cl or C centerline
 Cm centimeter
 Ch chain
 Chnlk chain-link
 Ch Blk channel block
 Ch Ch channel change
 Chk check
 Chsld chiseled
 Cir circle
 Cl class
 Cl clay
 Cl F clay fill
 Cl Hvy clay heavy
 Cl Lm clay loam
 Clnt clean-out
 Clr clear
 Cl&gr clearing & grubbing
 Co S coal slack
 Comb. combination
 Coml commercial
 Compr compression
 CADD computer aided drafting & design
 Conc concrete
 Cond conductor
 Const construction
 Cont continuous
 CSB continuous split barrel sample
 Contr contraction
 Contr contractor
 CP control point
 Coord coordinate
 Cor corner
 Corr corrected
 CAES corrugated aluminum end section
 CAP corrugated aluminum pipe
 CMES corrugated metal end section
 CMP corrugated metal pipe
 CPVCP corrugated poly-vinyl chloride pipe
 CSES corrugated steel end section
 CSP corrugated steel pipe
 C coulomb
 Co County
 Crse course
 C Gr course gravel
 CS course sand

Ct Court
 Xarm cross arm
 Xbuck cross buck
 Xsec cross sections
 Xing crossing
 Xrd Crossroad
 Crn crown
 CF cubic feet
 M3 cubic meter
 M3/s cubic meters per second
 CY cubic yard
 Cy/mi cubic yards per mile
 Culv culvert
 C&G curb & gutter
 CI curb inlet
 CR curb ramp
 CS curve to spiral
 C cut
 Dd Ld dead load
 Defl deflection
 Defm deformed
 Deg or D degree
 DInt delineate
 DIntr delineator
 Depr depression
 Desc description
 Det detail
 DWP detectable warning panel
 Dtr detour
 Dia diameter
 Dir direction
 Dist distance
 DM disturbed material
 DB ditch block
 DG ditch grade
 Dbl double
 Dn down
 Dwg drawing
 Dr drive
 Drwy driveway
 DI drop inlet
 D dry density
 Ea each
 Esmt easement
 E East
 EB Eastbound
 Elast elastomeric
 EL electric locker
 E Mtr electric meter
 Elec electric/al
 EDM electronic distance meter
 Elev or El elevation
 Ellipt elliptical
 Emb embankment
 Emuls emulsion/emulsified

ES end section
 Engr engineer
 ESS environmental sensor station
 Eq equal
 Eq equation
 Evgr evergreen
 Exc excavation
 Exst existing
 Exp expansion
 Expy Expressway
 E external of curve
 Extru extruded
 FOS factor of safety
 F Fahrenheit
 FS far side
 F farad
 Fed Federal
 FP feed point
 Ft feet/foot
 Fn fence
 Fn P fence post
 FO fiber optic
 FB field book
 FD field drive
 F fill
 FAA fine aggregate angularity
 FS fine sand
 FH fire hydrant
 Fl flange
 Flrd flared
 FES flared end section
 F Bcn flashing beacon
 FA flight auger sample
 FL flow line
 Ftg footing
 FM force main
 Fs foresight
 Fnd found
 Fdn foundation
 Frac fractional
 Frwy freeway
 Frt front
 FF front face
 F Disp fuel dispenser

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 07/01/14 and the original document is stored at the North Dakota Department of Transportation

NDDOT ABBREVIATIONS

D-101-2

FFP	fuel filler pipes	IPn	Iron Pin	MC	medium curing	Ped	pedestal
FLS	fuel leak sensor	IP	iron Pipe	M	mega	Ped	pedestrian
Furn	furnish/ed	Jt	joint	Mer	meridian	PPP	pedestrian pushbutton post
Gal	gallon	J	joule	M	meter	Pen.	penetration
Galv	galvanized	Jct	junction	M/s	meters per second	Perf	perforated
Gar	garage	K	kelvin	M	mid ordinate of curve	Per.	perimeter
Gs L	gas line	Kn	kilo newton	Mi	mile	PL	pipeline
G Reg	gas line regulator	Kpa	kilo pascal	MM	mile marker	PI	place
GMV	gas main valve	Kg	kilogram	MP	mile post	P&P	plan & profile
G Mtr	gas meter	Kg/m3	kilogram per cubic meter	MI	milliliter	PL	plastic limit
GSV	gas service valve	Km	kilometer	Mm	millimeter	PI	plate
GVP	gas vent pipe	K	Kip(s)	Mm/hr	millimeters per hour	Pt	point
GV	gate valve	LS	Land Surveyor (licensed)	Min	minimum	PCC	point of compound curve
Ga	gauge	LSIT	Land Surveyor In Training	Misc	miscellaneous	PC	point of curve
Geod	geodetic	Ln	lane	Mon	monument	PI	point of intersection
GIS	Geographical Information System	Lg	large	Mnd	mound	PRC	point of reverse curvature
G	giga	Lat	latitude	Mtbl	mountable	PT	point of tangent
GPS	Global Positioning System	Lt	left	Mtd	mounted	POC	point on curve
Gov	government	L	length of curve	Mtg	mounting	POT	point on tangent
Grd	graded/grade	Lens	lenses	Mk	muck	PE	polyethylene
Gr	gravel	Lvl	level	Mun	municipal	PVC	polyvinyl chloride
Grnd	ground	LB	level book	N	nano	PCC	Portland Cement concrete
GWM	ground water monitor	Lvng	leveling	NGS	National Geodetic Survey	Lb or #	pounds
Gdrl	guardrail	Lht	light	NS	near side	PP	power pole
Gtr	gutter	LP	light pole	Neop	neoprene	Preempt	preemption
H Plg	H piling	Ltg	lighting	Ntwk	network	Prefab	prefabricated
Hdwl	headwall	Lig Co	lignite coal	N	newton	Prfmd	performed
Ha	hectare	Lig Sl	lignite slack	N	North	Prep	preparation
Ht	height	LF	linear foot	NE	North East	Press.	pressure
HI	height of instrument	Liq	liquid	NW	North West	PRV	pressure relief valve
Hel	helical	LL	liquid limit	NB	Northbound	Prestr	prestressed
H	henry	L	litre	No. or #	number	Pvt	private
HZ	hertz	Lm	loam	Obsc	obscure(d)	PD	private drive
HDPE	high density polyethylene	Loc	location	Obsn	observation	Prod.	production/produce
HM	high mast	LC	long chord	Ocpd	occupied	Prog	programmed
HP	high pressure	Long.	longitude	Ocpy	occupy	Prop.	property
HPS	high pressure sodium	Lp	loop	Off Loc	office location	Prop Ln	property line
Hwy	highway	LD	loop detector	O/s	offset	Ppsd	proposed
Hor	horizontal	Lm	lumen	OC	on center	PB	pull box
HBP	hot bituminous pavement	Lum	luminaire	C	one dimensional consolidation		
HMA	hot mix asphalt	L Sum	lump sum	OC	organic content		
Hr	hour(s)	Lx	lux	Orig	original		
Hyd	hydrant	ML	main line	O To O	out to out		
Ph	hydrogen ion content	M Hr	man hour	OD	outside diameter		
Id	identification	MH	manhole	OH	overhead		
In or "	inch	Mkd	marked	PMT	pad mounted transformer		
Incl	inclinometer tube	Mkr	marker	Pg	pages		
IMH	inlet manhole	Mkg	marking	Pntd	painted		
ID	inside diameter	MA	mast arm	Pr	pair		
Inst	instrument	Matl	material	Pnl	panel		
Intchg	interchange	Max	maximum	Pk	park		
Intmdt	intermediate	MC	meander corner	PK	Parker-Kalon nail		
Intscn	intersection	Meas	measure	Pa	pascal		
Inv	invert	Mdn	median	PSD	passing sight distance		
IM	iron monument	MD	median drain	Pvmt	pavement		

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
08-03-15	General Revisions

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 08/03/15 and the original document is stored at the North Dakota Department of Transportation

NDDOT ABBREVIATIONS

D-101-3

Qty	quantity	SN	sign number	Tan	tangent	Wb	weber
Qtr	quarter	Sig	signal	T	tangent (semi)	WIM	weigh in motion
Rad or R	radius	Si Cl	silt clay	TS	tangent to spiral	W	west
RR	railroad	Si Cl Lm	silty clay loam	Tel	telephone	WB	westbound
Rlwy	railway	Si Lm	silty loam	Tel B	Telephone Booth	Wrng	wiring
Rsd	raised	Sgl	single	Tel P	telephone pole	W/	with
RTP	random traverse point	SC	slow curing	Tv	television	W/o	without
Rge or R	range	SS	slow setting	Temp	temperature	WC	witness corner
RC	rapid curing	Sm	small	Temp	temporary	WGS	world geodetic system
Rec	record	S	South	TBM	temporary bench mark	Z	zenith
Rcy	recycle	SE	South East	T	tesla		
RAP	recycled asphalt pavement	SW	South West	T	thinwall tube sample		
RPCC	recycled portland cement concrete	SB	Southbound	T/mi	tons per mile		
Ref	reference	Sp	spaces	Ts	topsoil		
R Mkr	reference marker	Spcl	special	Twp or T	township		
RM	reference monument	SA	special assembly	Traf	traffic		
Refl	reflectorized	SP	special provisions	TSCB	traffic signal control box		
RCB	reinforced concrete box	G	specific gravity	Tr	trail		
RCES	reinforced concrete end section	Spk	spike	Transf	transformer		
RCP	reinforced concrete pipe	SC	spiral to curve	TB	transit book		
RCPS	reinforced concrete pipe sewer	ST	spiral to tangent	Trans	transition		
Reinf	reinforcement	SB	split barrel sample	TT	transmission tower		
Res	reservation	SH	sprinkler head	Trans	transverse		
Ret	retaining	SV	sprinkler valve	Trav	traverse		
Rev	reverse	Sq	square	TP	traverse point		
Rt	right	SF	square feet	Trtd	treated		
R/W	right of way	Km2	square kilometer	Trmt	treatment		
Riv	river	M2	square meter	Qc	triaxial compression		
Rd	road	SY	square yard	TERO	tribal employment rights ordinance		
Rdbd	road bed	Stk	stake	Tpl	triple		
Rdwy	roadway	Std	standard	TP	turning point		
RWIS	roadway weather information system	N	standard penetration test	Typ	typical		
Rk	rock	Std Specs	standard specifications	Qu	unconfined compressive strength		
Rt	route	Sta	station	Ugrnd	underground		
Salv	salvage(d)	Sta Yd	station yards	USC&G	US Coast & Geodetic Survey		
Sd	sand	Stm L	steam line	USGS	US Geologic Survey		
Sdy Cl	sandy clay	SEC	steel encased concrete	Util	utility		
Sdy Cl Lm	sandy clay loam	SMA	stone matrix asphalt	VG	valley gutter		
Sdy Fl	sandy fill	SSD	stopping sight distance	Vap	vapor		
Sdy Lm	sandy loam	SD	storm drain	Vert	vertical		
San	sanitary sewer line	St	street	VC	vertical curve		
Sc	scoria	SPP	structural plate pipe	VCP	vitrified clay pipe		
Sec	seconds	SPPA	structural plate pipe arch	V	volt		
Sec	section	Str	structure	Vol	volume		
SL	section line	Subd	subdivision	Wkwy	walkway		
Sep	separation	Sub	subgrade	W	water content		
Seq	sequence	Sub Prep	subgrade preperation	WGV	water gate valve		
Serv	service	Ss	subsoil	WL	water line		
Sh	shale	SE	superelevation	WM	water main		
Sht	sheet	SS	supplement specification	WMV	water main valve		
Shtng	sheeting	Supp	supplemental	W Mtr	water meter		
Shldr	shoulder	Surf	surfacing	WSV	water service valve		
Sw	sidewalk	Surv	survey	WW	water well		
S	siemens	Sym	symmetrical	W	watt		
SD	sight distance	SI	systems international	Wrng	wearing		

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
08-03-15	General Revisions

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 08/03/15 and the original document is stored at the North Dakota Department of Transportation

NDDOT UTILITY COMPANY AND ORGANIZATION ABBREVIATIONS






D-101-10

702COM	702 Communications	GT PLNS NAT GAS	Great Plains Natural Gas Company	RED RIV TEL	Red River Rural Telephone
ACCENT	Accent Communications	HALS TEL	Halstad Telephone Company	RESVTN TEL	Reservation Telephone
AGASSIZ WU	Agassiz Water Users Incorporated	IDEA1	Idea1	ROBRTS TEL	Roberts Company Telephone
AGC	Associated General Contractors of America	INT-COMM TEL	Inter-Community Telephone Company	R-RIDER ELEC	Roughrider Electric Coop
All PI	Alliance Pipeline	KANEB PL	Kaneb Pipeline Company	RRVW	Red River Valley & Western Railroad
ALL SEAS WU	All Seasons Water Users Association	KEM ELEC	Kem Electric Cooperative Incorporated	RSR ELEC	R.S.R. Electric Cooperative
AMOCO PI	Amoco Pipeline Company	KOCH GATH SYS	Koch Gathering Systems Incorporated	S E W U	South East Water Users Incorporated
AMRDA HESS	Amerada Hess Corporation	LKHD PL	Lakehead Pipeline Company	SCOTT CABLE	Scott Cable Television Dickinson
AT&T	AT&T Corporation	LNGDN RWU	Langdon Rural Water Users Incorporated	SHERDN ELEC	Sheridan Electric Cooperative
B PAW	Bear Paw Energy Incorporated	LWR YELL R ELEC	Lower Yellowstone Rural Electric	SHEYN VLY ELEC	Sheyenne Valley Electric Cooperative
BAKER ELEC	Baker Electric	MCKNZ CON	McKenzie Consolidated Telcom	SKYTECH	Skyland Technologies Incorporated
BASIN ELEC	Basin Electric Cooperative Incorporated	MCKNZ ELEC	McKenzie Electric Cooperative	SLOPE ELEC	Slope Electric Cooperative Incorporated
BEK TEL	Bek Communications Cooperative	MCKNZ WRD	McKenzie County Water Resource District	SOURIS RIV TELCOM	Souris River Telecommunications
BELLE PL	Belle Fourche Pipeline Company	MCLEOD	McLeod USA	ST WAT COMM	State Water Commission
BLM	Bureau of Land Management	MCLN ELEC	McLean Electric Cooperative	STATE LN WATER	State Line Water Cooperative
BNSF	Burlington Northern Santa Fe Railway	MCLN-SHRDN R WAT	McLean-Sheridan Rural Water	STER ENG	Sterling Energy
BOEING	Boeing	MDU	Montana-dakota Utilities	STUT RWU	Stutsman Rural Water Users
BRNS RWD	Barnes Rural Water District	MID-CONT CABLE	Mid-Continent Cable	SW PL PRJ	Southwest Pipeline Project
BURK-DIV ELEC	Burke-Divide Electric Cooperative	MIDSTATE TEL	Midstate Telephone Company	T M C	Turtle Mountain Communications
BURL WU	Burleigh Water Users	MINOT CABLE	Minot Cable Television	TCI	TCI of North Dakota
Cable One	Cable One	MINOT TEL	Minot Telephone Company	TESORO GHG PLNS PL	Tesoro High Plains Pipeline
CABLE SERV	Cable Services	MISS W W S	Missouri West Water System	TRI-CNTY WU	Tri-County Water Users Incorporated
CAP ELEC	Capital Electric Cooperative Incorporat	MNKOTA PWR	Minnkota Power	TRL CO RWU	Traill County Rural Water Users
CASS CO ELEC	Cass County Electric Cooperative	MOR-GRAN-SOU ELEC	Mor-gran-sou Electric Cooperative	UNTD TEL	United Telephone
CASS RWU	Cass Rural Water Users Incorporated	MOUNT-WILLI ELEC	Mountrail-williams Electric Cooperative	UPPR SOUR WUA	Upper Souris Water Users Association
CAV ELEC	Cavalier Rural Electric Cooperative	MRE LBTY TEL	Moore & Liberty Telephone	US SPRINT	U.S. Sprint
CBLCOM	Cablecom Of Fargo	MUNICIPAL	City Water And Sewer	USAF MSL CABLE	U.S.A.F. Missile Cable
CENEX PL	Cenex Pipeline	MUNICIPAL	City Of '.....'	USFWS	US Fish and Wildlife Service
CENT PL WATER DIST	Central Pipe Line Water District	N CENT ELEC	North Central Electric Cooperative	USW COMM	U.S. West Communications
CENT PWR ELEC	Central Power Electric Cooperative	N VALL W DIST	North Valley Water District	VRNDRY ELEC	Verendrye Electric Cooperative
COE	Corps of Engineers	ND PKS & REC	North Dakota Parks And Recreation	W RIV TEL	West River Telephone Incorporated
CONS TEL	Consolidated Telephone	ND TEL	North Dakota Telephone Company	WEB	W. E. B. Water Development Association
CONT RES	Continental Resource Inc	NDDOT	North Dakota Department of Transportation	WILLI RWA	Williams Rural Water Association
CPR	Canadian Pacific Railway	NDSU SOIL SCI DEPT	NDSU Soil Science Department	WILSTN BAS PL	Williston Basin Interstate Pipeline Company
D O E	Department Of Energy	NEMONT TEL	Nemont Telephone	WLSH RWD	Walsh Water Rural Water District
DAK CARR	Dakota Carrier Network	NODAK R ELEC	Nodak Rural Electric Cooperative	WOLVRTN TEL	Wolverton Telephone
DAK CENT TEL	Dakota Central Telephone	NOON FRMS TEL	Noonan Farmers Telephone Company	XLENER	Xcel Energy
DAK RWD	Dakota Rural Water District	NPR	Northern Plains Railroad	YSVR	Yellowstone Valley Railroad
DGC	Dakota Gasification Company	NSP	Northern States Power		
DICKEY R NET	Dickey Rural Networks	NTH PRAIR RW	Northern Prairie Rural Water Association		
DICKEY RWU	Dickey Rural Water Users Association	NTHN BRDR PL	Northern Border Pipeline		
DICKEY TEL	Dickey Telephone	NTHN PLNS ELEC	Northern Plains Electric Cooperative Incorporated		
DNRR	Dakota Northern Railroad	NTHWSTRN REF	Northwestern Refinery Company		
DOPE PL	Dome Pipeline Company	NW COMM	Northwest Communication Cooperation		
DVELEC	Dakota Valley Electric Cooperative	ONEOK	Oneok gas		
DVMW	Dakota, Missouri Valley & Western	OSHA	Occupational Safety and Health Administration		
ENBRDG	Enbridge Pipelines Incorporated	OTTR TL PWR	Otter Tail Power Company		
ENVENTIS	Enventis Telephone	P L E M	Prairielands Energy Marketing		
FALK MNG	Falkirk Mining Company	POLAR COM	Polar Communications		
FHWA	Federal Highway Administration	PVT ELEC	Private Electric		
G FKS-TRL WD	Grand Forks-traill Water District	QWEST	Qwest Communications		
GETTY TRD & TRAN	Getty Trading & Transportation	R&T W SUPPLY	R & T Water Supply Association		
GLDN W ELEC	Golden West Electric Cooperative	RAMSEY R SEW	Ramsey Rural Sewer Association		
GRGS CO TEL	Griggs County Telephone	RAMSEY RW	Ramsey Rural Water Association		
		RAMSEY UTIL	Ramsey County Rural Utilities		

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 07/01/14 and the original document is stored at the North Dakota Department of Transportation

Line Styles

	Subgrade Reinforcement		Existing Railroad Switch		Sheet Piling
	Existing Down Guy Wire Down Guy		Overhead Sign Structure Cantilever		W-Beam w Posts
	Existing Fence		24 Inch Pipe		Existing W-Beam Guardrail with Posts
	Existing Railroad		Reinforced Concrete Pipe		Exst Wet Area-Vegetation Break
	Existing Sanitary Sewer		Signal Head with Mast Arm		Existing Wetland Delineated
	Existing Sanitary Force Main		Existing Signal Head with Mast Arm		
	Existing Storm Drain		Tie Bar at Random Spacing		
	Existing Storm Drain Force Main		3-Cable w Posts		
	Fence		Existing 3-Cable w Posts		
	Silt Fence		Site Boundary		
	Existing Field Line		Fiber Rolls		
	Exst Flow		Doweled Joint		
	Flow		Tie Bar 30 Inch 4 Foot Center to Center		
	Existing Culvert		Tie Bar 18 Inch 3 Foot Center to Center		
	Existing Curb		Existing Berm, Dike, Pit, or Earth Dam		
	Existing Valley Gutter		Existing Ditch Block		
	Existing Driveway Gutter		Depression Contours		
	Existing Curb and Gutter		Existing City Corporate Limits or Reservation Boundary		
	Existing Mountable Curb and Gutter		Gravel Pit - Borrow Area		
	Existing Double Micro Loop Detector		Existing Tree Boundary		
	Micro Loop Detector Double		Tree Row		
	Existing Overhead Sign Structure		Existing Brush or Shrub Boundary		
	Existing Micro Loop Detector		Existing Retaining Wall		
	Micro Loop Detector		Existing Planter or Wall		
	Existing Overhead Sign Structure Cantilever		Retaining Wall (Plan View)		

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 07/01/14 and the original document is stored at the North Dakota Department of Transportation

Symbols

	North Arrow (Half Scale)		Attenuation Device		Existing Railroad Battery Box		Existing Delineator Type E
	Truck Mounted Attenuator		Diamond Grade Delineator Type A		Existing Bush or Shrub		Existing EFB Misc
	Type I Barricade		Diamond Grade Delineator Type B		Existing Gas Cap or Stub		Existing Flashing Beacon
	Type II Barricade		Diamond Grade Delineator Type C		Existing Sanitary Cap or Stub		Existing Pipe Mounted Flasher
	Type III Barricade		Diamond Grade Delineator Type D		Existing Storm Drain Cap or Stub		Existing Pad Mounted Feed Point
	Catch Basin		Diamond Grade Delineator Type E		Existing Water Cap or Stub		Existing Pipe Mounted Feed Point with Pad
	Cairn or Stone Circle		Flexible Delineator		Existing Sanitary Cleanout		Existing Pole Mounted Feed Point
	Video Detection Camera		Flexible Delineator Type A		Existing Concrete Foundation		Existing Railroad Frog
	Storm Drain Cap or Stub		Flexible Delineator Type B		Existing Traffic Signal Controller		Existing Snow Gate 18
	Corrugated Metal End Section 18 Inch		Flexible Delineator Type C		Existing Pad Mounted Signal Controller		Existing Snow Gate 28
	Corrugated Metal End Section 24 Inch		Flexible Delineator Type D		Existing Sixteenth Section Corner		Existing Snow Gate 40
	Corrugated Metal End Section 30 Inch		Flexible Delineator Type E		Existing Quarter Section Corner		Existing Headwall
	Corrugated Metal End Section 36 Inch		Delineator Type A		Existing Section Corner		Existing Pedestrian Head with Number
	Corrugated Metal End Section 42 Inch		Delineator Type A Reset		Existing Railroad Crossbuck		Existing Signal Head
	Corrugated Metal End Section 48 Inch		Delineator Type B		Existing Satellite Dish		Existing Sprinkler Head
	Concrete Foundation		Delineator Type B Reset		Existing Fuel Dispensers		Existing Fire Hydrant
	Ground Connection Conductor		Delineator Type C		Existing Flexible Delineator Type A		Existing Catch Basin Drop Inlet
	Neutral Connection Conductor		Delineator Type D		Existing Flexible Delineator Type B		Existing Curb Inlet
	Phase 1 Connection Conductor		Delineator Type E		Existing Flexible Delineator Type C		Existing Manhole Inlet
	Phase 2 Connection Conductor		Delineator Drums		Existing Flexible Delineator Type D		Existing Junction Box
	Traffic Cone		Spot Elevation		Existing Flexible Delineator Type E		
	Signal Controller		Existing Access Control Arrow		Existing Delineator Type A		
	Pad Mounted Signal Controller		Existing Artifact		Existing Delineator Type B		
	Alignment Data Point		Existing Flashing Beacon		Existing Delineator Type C		
	Emergency Vehicle Detector		Existing Benchmark		Existing Delineator Type D		

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 07/01/14 and the original document is stored at the North Dakota Department of Transportation

Symbols

	Existing Light Standard		Existing Manhole with Valve Water		Existing Telephone Pole		Existing Undefined Manhole
	Existing High Mast Light Standard 10 Luminaire		Existing Water Manhole		Existing Wood Pole		Existing Undefined Pull Box
	Existing High Mast Light Standard 3 Luminaire		Existing Mile Post Type A		Existing Post		Existing Undefined Pedestal
	Existing High Mast Light Standard 4 Luminaire		Existing Mile Post Type B		Existing Pedestrian Push Button Post		Existing Undefined Valve
	Existing High Mast Light Standard 5 Luminaire		Existing Mile Post Type C		Existing Control Point CP		Existing Undefined Pipe Vent
	Existing High Mast Light Standard 6 Luminaire		Existing Reference Marker		Existing Control Point GPS-RTK		Existing Gas Valve
	Existing High Mast Light Standard 7 Luminaire		Existing RW Marker		Existing Control Point TRI		Existing Water Valve
	Existing High Mast Light Standard 8 Luminaire		Existing Utility Marker		Existing Reference Marker Point NGS		Existing Fuel Pipe Vent
	Existing High Mast Light Standard 9 Luminaire		Iron Monument Found		Existing Pull Box		Existing Gas Pipe Vent
	Existing Overhead Sign Structure Load Center		Iron Pin R/W Monument		Existing Intelligent Transportation Pull Box		Existing Sanitary Pipe Vent
	Existing Luminaire		Existing Object Marker Type I		Existing Water Pump		Existing Storm Drain Pipe Vent
	Existing Light Standard Luminaire		Existing Object Marker Type II		Existing Slotted Reinforced Concrete Pipe		Existing Water Pipe Vent
	Existing Federal Mailbox		Existing Object Marker Type III		Existing RR Profile Spot		Existing Weather Station
	Existing Private Mailbox		Existing Electrical Pedestal		Existing Fuel Leak Sensors		Existing Ground Water Well Bore Hole
	Existing Meander Section Corner		Existing Telephone Pedestal		Existing Highway Sign		Existing Windmill or Tower
	Existing Meter		Existing Fiber Optic Telephone Pedestal		Existing Miscellaneous Spot		Existing Witness Corner
	Existing Electrical Manhole		Existing TV Pedestal		Existing Lighting Standard Pole		Flashing Beacon
	Existing Gas Manhole		Existing Fiber Optic TV Pedestal		Existing Traffic Signal Standard		Flagger
	Existing Sanitary Manhole		Existing Fuel Filler Pipes		Existing Transformer		Pipe Mounted Flasher
	Existing Sanitary Force Main Manhole		Existing Traverse PI Aerial Panel		Existing Large Evergreen Tree		Sanitary Force Main with Valve
	Existing Sanitary Manhole with Valve		Existing Pole		Existing Small Evergreen Tree		
	Existing Storm Drain Manhole		Existing Power Pole		Existing Large Tree		
	Existing Force Main Storm Drain Manhole		Existing Power Pole with Transformer		Existing Small Tree		
	Existing Force Main Storm Drain Manhole with Valve				Existing Tree Trunk		
	Existing Telephone Manhole				Existing Pad Mounted Traffic Signal Control Box		

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 07/01/14 and the original document is stored at the North Dakota Department of Transportation

Symbols

D-101-32

 Pad Mounted Feed Point  Pipe Mounted Feed Point with Pad  Pole Mounted Feed Point  Headwall  Double Headwall with Vegetation Barrier  Single Headwall with Vegetation Barrier  Pole Mounted Head  Sprinkler Head  Fire Hydrant  Inlet Type 1  Inlet Type 2  Double Inlet Type 2  Inlet Gate Type 2  Junction Box  High Mast Light Standard 10 Luminaire  High Mast Light Standard 3 Luminaire  High Mast Light Standard 4 Luminaire  High Mast Light Standard 5 Luminaire  High Mast Light Standard 6 Luminaire  High Mast Light Standard 7 Luminaire  High Mast Light Standard 8 Luminaire  High Mast Light Standard 9 Luminaire  Relocate Light Standard  Overhead Sign Structure Load Center  Light Standard 100 Watt High Pressure Sodium Vapor Luminaire	 Light Standard 1000 Watt High Pressure Sodium Vapor Luminaire  Light Standard 150 Watt High Pressure Sodium Vapor Luminaire  Light Standard 175 Watt High Pressure Sodium Vapor Luminaire  Light Standard 200 Watt High Pressure Sodium Vapor Luminaire  Light Standard 250 Watt High Pressure Sodium Vapor Luminaire  Light Standard 310 Watt High Pressure Sodium Vapor Luminaire  Light Standard 35 Watt High Pressure Sodium Vapor Luminaire  Light Standard 400 Watt High Pressure Sodium Vapor Luminaire  Light Standard 50 Watt High Pressure Sodium Vapor Luminaire  Light Standard 70 Watt High Pressure Sodium Vapor Luminaire  Light Standard 700 Watt High Pressure Sodium Vapor Luminaire  Manhole  Manhole 48 Inch  Sanitary Force Main Manhole  Sanitary Sewer Manhole  Storm Drain Manhole  Storm Drain Manhole with Inlet  Reset Mile Post  Mile Post Type A  Mile Post Type B  Mile Post Type C  Right of Way Marker  Tubular Marker  Alignment Monument  Iron Pin Reference Monument	 Object Marker Type I  Object Marker Type II  Object Marker Type III  Caution Mode Arrow Panel  Back to Back Vertical Panel Sign  Double Direction Arrow Panel  Left Directional Arrow Panel  Right Directional Arrow Panel  Sequencing Arrow Panel  Truck Mounted Arrow Panel  Power Pole  Wood Pole  Pedestrian Push Button Post  Property Corner  Pull Box  Intelligent Transportation Pull Box  Sanitary Pump  Storm Drain Pump  Reinforced Pavement  Reinforced Concrete End Section 15 Inch  Reinforced Concrete End Section 18 Inch  Reinforced Concrete End Section 24 Inch  Reinforced Concrete End Section 30 Inch  Reinforced Concrete End Section 36 Inch  Reinforced Concrete End Section 42 Inch	 Reinforced Concrete End Section 48 Inch  Reinforced Concrete End Section 54 Inch  Reset Right of Way Marker  Reset USGS Marker  Right of Way Markers  Riser 30 Inch  Continuous Split Barrel Sample  Flight Auger Sample  Split Barrel Sample  Thinwall Tube Sample  Highway Sign  SNOW GATE 18 FT  SNOW GATE 28 FT  SNOW GATE 40 FT  Standard Penetration Test  Transformer  Inclinometer Tube  Underdrain Cleanout  Excavation Unit  Water Valve
---	--	---	--

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by
Roger Weigel,
 Registration Number
 PE-2930,
 on 07/01/14 and the original document is stored at the
 North Dakota Department
 of Transportation

STANDARD RURAL APPROACHES

D-203-8


NOTES:

1. Max breakover between approach storage platform and highway shall not exceed 5%.
2. The approach slope shall be measured outside the area of mainline inslope influence.




CRITERIA FOR RURAL APPROACH TYPES

	Field Drives	Private Drives	Low Volume Public Roads
Radius	R=24 ft	R=30 ft	R=40 ft
Maximum Grade	10%	7%	7%
Storage Platform	20 ft	24 ft	30 ft
Vertical Curve Length	10 ft	10 ft	Varies (Min. 20 mph)




SECTION A-A



*2.1% crown for paved surface
*3.0% crown for gravel surface




SECTION B-B




SECTION C-C



APPROACH GRADE ON FILL SECTION




APPROACH GRADE ON DEEP FILL SECTION




APPROACH GRADE ON CUT SECTION

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
2-25-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 02/25/14 and the original document is stored at the North Dakota Department of Transportation.



SILT FENCE
SUPPORTED AND UNSUPPORTED




SILT FENCE
CROSS SECTION

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-03-13	
REVISIONS	
DATE	CHANGE
06-26-14	Standard drawing resulted from splitting standard D-708-2.


This document was originally issued and sealed by
 Roger Weigel
 Registration Number
 PE-2930,
 on 06/26/14 and the original document is stored at the North Dakota Department of Transportation

EROSION CONTROL
FIBER ROLL PLACEMENT DETAILS




*Optional Weir. Use in flat areas, such as the Red River Valley, where there is potential for water to back up on adjacent property. Lower fiber roll enough to prevent water from backing up on adjacent property. Do not use 20-inch fiber rolls in flat areas where there is potential for water to back up on adjacent property.


12 OR 20 INCH FIBER ROLL - DITCH BOTTOM




PLAN VIEW FOR SLOPE APPLICATION



PLAN VIEW FOR DITCH APPLICATION



Detail A
Fiber Roll Overlapping Staking Detail



Detail B
Fiber Roll Staking Detail



FIBER ROLL DIAMETER	NOMINAL STAKE SIZE	MINIMUM STAKE LENGTH	MINIMUM TRENCH DEPTH	MAXIMUM TRENCH DEPTH
6"	2" x 2"	18"	2"	2"
12"	2" x 2"	24"	2"	3"
20"	2" x 2"	36"	3"	5"

NOTE: Runoff must not be allowed to run under or around roll.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
11-18-10	
REVISIONS	
DATE	CHANGE
06-10-13	Added plan view for ditch and slope application, Added table with values for stake and trench dimensions.
10-04-13	Revised fiber roll overlap detail.
06-26-14	Changed standard drawing number from D-708-7 to D-261-1



This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 06/26/14 and the original document is stored at the North Dakota Department of Transportation

Two Lane, Two Way Roadways



Typical Protection Vehicle

Multilane Roadways




Typical Protection Vehicle

- Notes:
1. The working vehicle shall display a 360 degree rotating, flashing, oscillating or strobe light.
 2. The shadow vehicle shall display a 360 degree rotating, flashing, oscillating or strobe light. The shadow vehicle for Multilane Roadway shall also have a sequencing arrow panel Type C operated in the chevron mode.
 3. This application is for use during daylight hours and in areas of good visibility only.
 4. Two lane, two way roadway, a flagger shall be used to protect the work area and warn oncoming traffic.


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-25-12	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 9/25/2012 and the original document is stored at the North Dakota Department of Transportation




Multi-Directional Slip Base Assembly

Perforated Tube



Top Post Receiver
Plate - ASTM A572 grade 50
Angle Receiver - 2 1/2"x2 1/2"x3/8" ASTM A36 structural angle



Bottom Soil Stub
Tube - 3"x3"x7 gauge ASTM A500 grade B tube
Stabilizing Wing - 7 gauge H.R.P.O. ASTM A1011
Plate - ASTM A572 grade 50


Notes:

1. Slip base bolts shall be torqued as specified by the manufacturer.
2. Anchor shall have a yield strength of 43.9 KSI and tensile strength of 59.3 KSI.
3. The 4" vertical clearance is required for the anchor or breakaway base. The 4"x60" measurement shall be made above and below post location and also back and ahead of the post.
4. When used in concrete sidewalk, anchor shall be same except without the wings.
5. Four post signs shall have over 7' between the first and the fourth posts.


Telescoping Perforated Tube						
Number of Posts	Post Size in.	Wall Thickness Gauge	Sleeve Size in.	Wall Thickness Gauge	Slip Base	Anchor Size without Slip Base in.
1	2	12			No	2 1/4
1	2 1/4	12			No	2 1/2
1	2 1/2	12			(A)	3
1	2 1/2	10			Yes	
1	2 1/4	12	2	12	Yes	
1	2 1/2	12	2 1/4	12	Yes	
2	2	12			No	2 1/4
2	2 1/4	12			No	2 1/2
2	2 1/2	12			Yes	
2	2 1/2	12			Yes	
2	2 1/4	10	2	12	Yes	
2	2 1/2	12	2 1/4	12	Yes	
3 & 4	2 1/2	12			Yes	
3 & 4	2 1/2	10			Yes	
3 & 4	2 1/2	12	2 1/4	12	Yes	
3 & 4	2 1/4	12	2	12	Yes	
3 & 4	2 1/2	10	2 3/16	10	Yes	

Properties of Telescoping Perforated Tube						
Tube Size in.	Wall Thickness in.	U.S. Standard Gauge	Weight per Foot lbs.	Moment of Inertia in. ⁴	Cross Sec. Area in. ²	Section Modulus in. ³
1 1/2 x 1 1/2	0.105	12	1.702	0.129	0.380	0.172
2 x 2	0.105	12	2.416	0.372	0.590	0.372
2 1/4 x 2 1/4	0.105	12	2.773	0.561	0.695	0.499
2 3/16 x 2 3/16	0.135	10	3.432	0.605	0.841	0.590
2 1/2 x 2 1/2	0.105	12	3.141	0.804	0.803	0.643
2 1/2 x 2 1/2	0.135	10	4.006	0.979	1.010	0.785


Top Post Receiver Data Table						
Square Post Sizes (B)	A	B	C	D	E	F
2 3/16"x10 ga.	1 9/64"	2 1/2"	3 1/32"	2 5/32"	1 33/64"	1 1/8"
2 1/2"x10 ga.	1 9/32"	2 1/2"	3 5/16"	5/8"	1 21/32"	1 3/4"




Anchor Unit and Post Assembly



Multi-Directional Slip Base Anchor Unit and Post Sleeve Assembly



Bolt Retainer for Base Connection
Bolt Retainer - 1/32" Reprocessed Teflon





Anchor plate shall be a minimum 10 gauge (two post installation)

- (A) The breakaway base is required when the support is placed in weak soils. The Engineer shall determine if the soils are weak.
(B) The 2 3/16"x10 ga. may be inserted into 2 1/2"x10 ga. for additional wind load.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
2-28-14	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 2/28/14 and the original document is stored at the North Dakota Department of Transportation

U-Channel Post




Breakaway U-Channel Detail Alternate A

A maximum of 2 posts shall be installed within 7'.




Retainer Strap Detail



Breakaway U-Channel Splice Detail Alternate B (2.5 and 3 lb/ft)

A maximum of 3 posts shall be installed within 7'.



Breakaway U-Channel Splice Detail Alternate C (2.5 and 3 lb/ft)

A maximum of 3 posts shall be installed within 7'.

Alternate A Steps of Installation:












1. a) Drive anchor unit to within 12" of ground level.
b) Proper assembly established by lining up the bottom hole of retainer strap with the 6th hole from the top of the anchor unit.
c) Assemble strap to back of anchor unit using 5/16"x2" bolt, lock washer and nut.
d) Rotate strap 90° to left.
2. a) Drive anchor unit to 4" above ground.
b) Rotate strap to vertical position.
3. a) Place 5/16"x2" bolt, lock washer and nut in bottom of sign post to facilitate alignment of sign post with proper hole in anchor unit.
b) Alternately tighten two connector bolts.
4. Complete assembly by tightening 5/16"x2" bolt (this fastens sign post to retainer strap).
5. The base post, strap and sign post shall be properly nested. Proper nesting occurs when all flat surfaces of the base post, strap, and sign post at the bolts have full contact across the entire width.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
2-28-14	
REVISIONS	
DATE	CHANGE




This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 2/28/14 and the original document is stored at the North Dakota Department of Transportation

CONSTRUCTION SIGN DETAILS
 TERMINAL AND GUIDE SIGNS

D-704-9



ARROW DETAILS



NOTES:


(A) Arrow may be right or left of the legend to indicate construction to the right or left.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-13-13	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by
 Roger Weigel,
 Registration Number
 PE-2930,
 on 8/13/13 and the original document is stored at the
 North Dakota Department
 of Transportation

CONSTRUCTION SIGN DETAILS
REGULATORY SIGNS


D-704-10




R1-50-24
Legend: black (non-refl)
Background: white



R11-3c-60
Legend: black (non-refl)
Background: white



R2-1a-24
Legend: black (non-refl)
Background: white



R11-4a-60
Legend: black (non-refl)
Background: white



R11-2a-48
Legend: black (non-refl)
Background: white


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-13-13	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 8/13/13 and the original document is stored at the North Dakota Department of Transportation


CONSTRUCTION SIGN DETAILS
WARNING SIGNS

WORD	LETTER SPACING
AHEAD	Standard
200 FT	Standard
350 FT	Standard
500 FT	Standard
1000 FT	Reduce 40%
1500 FT	Reduce 40%
½ MILE	Reduce 50%
1 MILE	Standard


* DISTANCE MESSAGES




W5-8-48
Legend: black (non-refl)
Background: orange




W8-54-48
Legend: black (non-refl)
Background: orange




W20-51-48
Legend: black (non-refl)
Background: orange




W21-51-48
Legend: black (non-refl)
Background: orange




W5-9-48
Legend: black (non-refl)
Background: orange




W8-55-48
Legend: black (non-refl)
Background: orange




W20-52-54
Legend: black (non-refl)
Background: orange




W22-8-48
Legend: black (non-refl)
Background: orange




W5-9-48
ARROW DETAILS



W8-53-48
Legend: black (non-refl)
Background: orange



W8-56-48
Legend: black (non-refl)
Background: orange




W21-50-48
Legend: black (non-refl)
Background: orange

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-13-13	
REVISIONS	
DATE	CHANGE



This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 8/13/13 and the original document is stored at the North Dakota Department of Transportation

SHOULDER CLOSURE TAPERS

D-704-12




SHOULDER CLOSURE WITH LANE CLOSURE
(when shoulder is 8' or wider)



SHOULDER CLOSURE USED WITH LANE CLOSURE
(when shoulder is less than 8' wide)

PORTABLE TRAFFIC SIGNAL OR CHANGEABLE MESSAGE SIGN ON SHOULDER



Sequencing
Arrow Panel

KEY	
● Delineator Drum	∞ Sequencing Arrow Panel
• Message Display	↳ Portable Traffic Signal


Notes:

- S = Posted Speed Limit in mph
W = Width of offset in feet
L = Taper length in feet
L = $WS^2/60$ (40mph or less)
L = WS (45mph or more)
- If a shoulder taper is used, it should have a length of approximately $1/3L$. If a shoulder is used as a travel lane, a normal merging or shifting taper should be used.
- When paved shoulders of 8 foot width or more are closed, channelizing devices shall be used to close the shoulder in advance to delineate the beginning of the work space and direct vehicular traffic to remain within the traveled way.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-3-13	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by
Roger Weigel
Registration Number
PE-2930,
on 10/3/13 and the original document is stored at the North Dakota Department of Transportation

BARRICADE AND CHANNELIZING DEVICE DETAILS




The markings on drums shall be horizontal, circumferential, alternating orange and white retroreflective stripes 4" to 6" wide. Each drum shall have a minimum of two orange and two white stripes with the top stripe being orange. Any nonretroreflectORIZED spaces between the horizontal orange and white stripes shall not exceed 3" wide. Stripes shall not be placed on ribs or indentations in the drum. Drums shall have closed tops that will not allow collection of construction debris or other debris. Ballast shall not be placed on the top of a drum.

Markings for vertical panels shall be alternating orange and white retroreflective stripes, sloping downward in the direction vehicular traffic is to pass. Retroreflective sheeting shall be placed on both sides of panel and shall have a minimum of 270 square inches of retroreflective area facing vehicular traffic. Where the height of the retroreflective material on the vertical panel is 36 inches or more, a stripe width of 6 inches shall be used.




RetroreflectORIZATION of cones more than 36" in height shall be provided by alternating orange and white retroreflective stripes. Each cone shall have a minimum of two orange and two white stripes with the top stripe being orange. Any nonretroreflectORIZED space between the orange and white stripes shall not exceed 3" wide.

RetroreflectORIZATION of tubular markers more than 42" in height shall be provided by alternating four 4" to 6" wide orange and white stripes with the top stripe being orange.



INSTALLATION NOTES:


1. Drill installation holes to diameter and depth as required by manufacturer's specifications.
2. For removal, remove anchors and fill installation hole with an epoxy designed to bond to pavement surface.
3. In lieu of bolted down base, the contractor may use an 8" x 8" butyl pad or hot melt butyl. Butyl shall be removed as close as possible to pavement surface.



BARRICADE BLADE DETAIL

ELEVATION VIEW

BARRICADE ASSEMBLY DETAIL (Aluminum Barricade Rails)




ELEVATION VIEW

SIDE VIEW

BARRICADE ASSEMBLY DETAIL (Wood or Plastic Rails)

NOTE: Markings for barricades shall be alternating orange and white retroreflective stripes, sloping downward in the direction traffic is to pass. Retroreflective sheeting shall be placed on both sides of the rails and shall have a minimum of 270 square inches of visible retroreflective area facing vehicular traffic. When the barricade length is less than 36", the rail stripe width shall be 4".




TYPE I BARRICADE

TYPE II BARRICADE

TYPE III BARRICADE

BARRICADE RAIL DETAILS



MINIMUM BALLAST (For each side of barricade support)

Without Sign	4 - 25 lb sandbags
With Sign	6 - 25 lb sandbags


Note: The number of sandbags are based on a wind speed of 55 MPH. The sandbags are assumed to be placed at or near the ends of the skids.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-3-13	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 10/3/13 and the original document is stored at the North Dakota Department of Transportation

CONSTRUCTION SIGN PUNCHING AND MOUNTING DETAILS

Note: Signs placed in sections with curb shall have a minimum horizontal clearance of 2' from the face of the curb to the near edge of the sign.



NOTES:

1. Sign Supports: Supports shall be galvanized or painted. Minimum post sizes are 2.5 lb/ft u-channel or 2" x 2" x 12 gauge steel perforated tube, except where noted. When installing signs on u-channel, the minimum post size for assemblies containing a secondary sign is 3.0 lb/ft. Post sizes are based on a wind speed of 55 MPH.

Signs over 50 square feet should be installed on 2 1/2" x 2 1/2" perforated tube supports as a minimum.

Guy wires shall not be attached to sign supports. Wind beams may be attached to u-posts behind the sign panels.

2. Sign Panels: Provide sign panels made of 0.100" aluminum, 1/2" plywood, or other approved material, except where noted. All holes to be punched round for 3/8" bolts.

3. Alternate Messages: The signs that have alternate messages may have these alternate messages placed on a reflectorized plate (without a border) and installed and removed as required. (i.e. "Left" and "Right" message on a lane closure sign)

4. Route Marker Auxiliary Signs: Provide route marker auxiliary signs, such as the cardinal direction and directional arrows, with a background and legend that match the route marker they are used with:

Interstate - white legend on blue background
 Interstate Business Loop - white legend on green background
 US and State - black legend on white background
 County - yellow legend on blue background

5. Vertical Clearance: Install signs with a vertical clearance of 5'-0" (see TYPICAL SECTION.) In areas where parking or pedestrian movements are likely or the view of the sign may be obstructed, install signs with a vertical clearance of 7'-0" from the top of the curb or from the near edge of the driving lane in absence of a curb.

The vertical clearance to secondary signs is 1'-0" less than the vertical clearance as stated above.

Large signs having an area exceeding 50 square feet shall have a minimum clearance of 7'-0" from the ground at the post.

6. Portable Signs: Provide portable signs that meet the vertical clearance as stated above. Use portable signs when it is necessary to place signs within the pavement surface.

When portable signs are used for 5 days or less, low-mounting height (minimum 12" vertical clearance) sign supports may be used as long as the view of the sign is not obstructed. Time delays caused by unforeseen circumstances, such as equipment breakdown, rain, subgrade failures, etc., will not accrue towards the 5 day period. The R9-8 through R9-11a series, W1-5 through W1-8 series, M4-10, and E5-1 may be used for longer than 5 days.

Signs mounted to the portable sign supports shown in the LOW-MOUNTING HEIGHT and HIGH-MOUNTING HEIGHT Details shall have a maximum surface area of 16 square feet.

MINIMUM BALLAST
 (For each side of sign support base)

Sign Panel Mounting Height (ft)	Number of 25 lb sandbags for 4' x 4' sign panel
1'	6
5'	8
7'	10

Note: The number of sandbags are based on a wind speed of 55 MPH. The sandbags are assumed to be placed at or near the ends of the skids.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-4-13	
REVISIONS	
DATE	CHANGE
11-14-13	Revised Note 6.

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 11/14/13 and the original document is stored at the North Dakota Department of Transportation

ROAD CLOSURE LAYOUTS

Notes

- Variables
 - S = Numerical value of speed limit or 85th percentile.
 - W = The width of taper.
 - L = Minimum length of taper, or S x W for freeways, expressways, and all other roads with speeds of 45 mph or greater, or $W \times S^2/60$ for urban, residential, and other streets with speeds of 40 mph or less.
- Barricades placed on roadway shall be on a moveable assembly. Signs placed on roadway shall be placed on skid mounted assemblies.
- Delineator drums, barricades or cones used for tapering traffic shall be spaced at the dimension "S". Delineator drums or cones used for tangents shall be spaced at 2 times dimension "S".
- Sequencing Arrow Panels
 - Panels should normally be placed at the beginning of the taper. Where shoulder width does not provide sufficient room, the panel should be moved closer to the work area so that it can be placed on the roadway surface. See Shoulder Closure Standard Drawing.
 - Type A shall be used on roadways with slow moving traffic speeds and low volume (25 mph or less and 750 ADT or less).
 - Type B shall be used on roadways with moderate traffic speeds and volumes (40 mph or less and 5000 ADT or less).
 - Type C shall be used on roadways with high traffic speeds and volumes (over 40 mph or over 5000 ADT).
- The speed limit shall be re-established. The exact speed limit shall be determined in the field, dependent on location and conditions.
- The reduced speed limit shall be determined dependent on the in place speed limit before construction. The speed limit reduction should not exceed 10 mph below the existing speed limit, unless the design speed of the work zone feature has been reduced below the 10 mph. In this case, the speed limit reduction shall not exceed 30 MPH. Where speed limits are to be reduced more than 30 MPH, a second speed limit sign shall be installed with the desired speed reduction but shall not exceed 30 MPH. The second speed limit sign shall be placed at 1/2 B.
- Use when work area is 1 mile or longer.
- When warning signs are used in urban areas and the signs are not portable, flags shall be installed. The flags shall be 24 inches square, mounted perpendicular to the edges of the diamond sign, and at such a distance above the edge so that when the flag is limp it will not touch the sign. Rural areas will not require flags.
- Existing speed limit signs within a reduced speed zone shall be covered.
- Where necessary, safe speed to be determined by the Engineer.
- The contractor has the option of using portable sign supports in lieu of post mounted signs in accordance with the NDDOT Standard Specifications.
- G20-55-96 sign is not required if this standard is part of other traffic control layouts, or the work is less than 15 days.

Road Type	Distance Between Signs Min. (ft)		
	A	B	C
Urban - Low Speed (30 mph or less)	150	150	150
Urban - Low Speed (over 30 to 40 mph)	280	280	280
Urban - High Speed (over 40 mph to 50 mph)	360	360	360
Rural - High Speed (over 50 mph to 65 mph)	720	720	720
Urban Expressway and Freeway (55 mph to 60 mph)	850	1350	2200
Rural Expressway and Freeway (70 mph to 75 mph)	1000	1500	2640
Interstate/4-Lane Divided (Maintenance and Surveying)	750	1000	1500


KEY

	Type III barricade		Work area
	Sign		Flagger
	Delineator drum		Sequencing arrow panel
	Tubular markers		Vertical panels back to back

Speed (mph)	Length Min (feet)
20	115
25	155
30	200
35	250
40	305
45	360
50	425
55	495
60	570
65	645
70	730
75	820

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-27-13	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel Registration Number PE-2930, on 09/27/13 and the original document is stored at the North Dakota Department of Transportation




TYPE A TEMPORARY ROAD CLOSURE
When a pilot car is used, there is no need to provide G20-55-96 or R2-1a-24 sign on the project as the pilot car will control the speed.

TYPE B ROAD CLOSURE WITH A DIVERSION
Two lane highway where roadway is closed and detour is provided (signing shown for one direction of travel only). Use on bridge and culvert installation where closure is 1/2 mile or less.

TYPE C HALF ROAD CLOSURE ON A MULTI-LANE, HIGH SPEED HIGHWAY
4 lane undivided highway with half the roadway closed.

TERMINAL AND SEAL COAT SIGN LAYOUTS

D-704-20



1. Barricades placed on roadway shall be on a moveable assembly. Signs placed on the roadway shall be placed on skid mounted assemblies.
2. The speed limit shall be re-established. The exact speed limit shall be determined in the field, dependent on location and conditions.
3. The reduced speed limit shall be determined dependent on the in place speed limit before construction. The speed limit reduction should not exceed 10 MPH below the existing speed limit, unless the design speed of the work zone feature has been reduced below the 10 MPH. In this case, the speed limit reduction shall not exceed 30 MPH. Where speed limits are to be reduced more than 30 MPH, a second speed limit sign shall be installed with the desired speed reduction but shall not exceed 30 MPH. The second speed limit sign shall be placed at 1/2 B.
4. When warning signs are used in urban areas and the signs are not portable, flags shall be installed. The flags shall be 24 inches square, mounted perpendicular to the edges of the diamond sign, and at such a distance above the edge so that when the flag is limp it will not touch the sign. Rural areas will not require flags.
5. Existing speed limit signs within a reduced speed zone shall be covered.
6. On seal projects, signs R2-1-48, R2-1a-24, R4-1-48, W22-8-48 and W20-52-54 shall be placed just after all important intersections and at five mile intervals thereafter. Sign W8-12-48 shall be placed just after all important intersections and at 2 mile intervals thereafter until the short term center line pavement marking is in place. No short term pavement markings are placed when traffic volumes are 750 ADT or less.
7. The contractor has the option of using portable sign supports in lieu of post mounted signs in accordance with the NDDOT Standard Specifications.
8. Type H construction sign traffic control shall have the speed limit signs covered or removed once the loose aggregate has been removed.
9. The contractor shall install the G20-1b-60 sign when work is suspended for winter.
10. Other traffic control layouts will be required in the immediate work areas. If the speed limit is reduced in the work area, speed limit signs shall have the R2-1a-24 sign placed below.
11. G20-55-96 sign is not required if work is less than 15 days.

KEY

Type III barricade
 Sign


ADVANCE WARNING SIGN SPACING			
Road Type	Distance Between Signs Min. (ft)		
	A	B	C
Urban - Low Speed (30 mph or less)	150	150	150
Urban - Low Speed (over 30 to 40 mph)	280	280	280
Urban - High Speed (over 40 mph to 50 mph)	360	360	360
Rural - High Speed (over 50 mph to 65 mph)	720	720	720
Urban Expressway and Freeway (55 mph to 60 mph)	850	1350	2200
Rural Expressway and Freeway (70 mph to 75 mph)	1000	1500	2640
Interstate/4-Lane Divided (Maintenance and Surveying)	750	1000	1500

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-27-13	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by
Roger Weigel
 Registration Number
PE-2930,
 on 09/27/13 and the original document is stored at the
 North Dakota Department
 of Transportation

CONSTRUCTION TRUCK AND TEMPORARY DETOUR LAYOUTS

D-704-22



- Notes
1. Barricades placed on roadway shall be on a moveable assembly. Signs placed on the roadway shall be placed on skid mounted assemblies. Where necessary, safe speed to be determined by the Engineer.
 2. The reduced speed limit shall be determined dependent on the in place speed limit before construction. The speed limit reduction should not exceed 10 mph below the existing speed limit, unless the design speed of the work zone feature has been reduced below the 10 mph. In this case, the speed limit reduction shall not exceed 30 MPH. Where speed limits are to be reduced more than 30 MPH, a second speed limit sign shall be installed with the desired speed reduction but shall not exceed 30 MPH. The second speed limit sign shall be placed at 1/2 B.
 3. When warning signs are used in urban areas and the signs are not portable, flags shall be installed. The flags shall be 24 inches square, mounted perpendicular to the edges of the diamond sign, and at such a distance above the edge so that when the flag is limp it will not touch the sign. Rural areas will not require flags.
 4. Existing speed limit signs within a reduced speed zone shall be covered. Obliterated or covered pavement marking shall be paid for as Obliteration of Pavement Marking. The covering shall be approved by the engineer.
 5. The contractor has the option of using portable sign supports in lieu of post mounted signs in accordance with the NDDOT Standard Specifications.
 6. The contractor shall install the G20-1b-60 sign when work is suspended for winter.
 7. If existing stop sign is in place, a 48" stop sign is not required.
 8. G20-55-96 sign is not required if this standard is part of other traffic control layouts with this sign or the work is less than 15 days.



ADVANCE WARNING SIGN SPACING

Road Type	Distance Between Signs Min. (ft)		
	A	B	C
Urban - Low Speed (30 mph or less)	150	150	150
Urban - Low Speed (over 30 to 40mph)	280	280	280
Urban - High Speed (over 40 mph to 50 mph)	360	360	360
Rural - High Speed (over 50 mph to 65 mph)	720	720	720
Urban Expressway and Freeway (55 mph to 60 mph)	850	1350	2200
Rural Expressway and Freeway (70 mph to 75 mph)	1000	1500	2640
Interstate/4-Lane Divided (Maintenance and Surveying)	750	1000	1500

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION

9-27-13


REVISIONS

DATE	CHANGE

This document was originally issued and sealed by Roger Weigel Registration Number PE-2930, on 09/27/13 and the original document is stored at the North Dakota Department of Transportation

SHOULDER CLOSURES AND BRIDGE PAINTING LAYOUTS


D-704-24



- Notes
- Variables
S = Numerical value of speed limit or 85th percentile.
W = The width of the taper.
L = Minimum length of taper, or $S \times W$ for freeways, expressways, and all other roads with speeds of 45 mph or greater, or $W \times S^2 / 60$ for urban, residential, and other streets with speeds of 40 mph or less.
 - Delineator drums used for tapering traffic shall be spaced at dimension "S".
Delineator drums or tubular markers used for tangents shall be spaced at 2 times "S".
 - Sequencing Arrow Panels
Type A shall be used on roadways with slow moving traffic speeds and low volume (25 mph or less and 750 ADT or less).
Type B shall be used on roadways with moderate traffic speeds and volumes (40 mph or less and 5000 ADT or less).
Type C shall be used on roadways with high traffic speeds and volumes (over 40 mph or over 5000 ADT).
 - The speed limit shall be re-established. The exact speed limit shall be determined in the field, dependent on location and conditions.
 - The reduced speed limit shall be determined dependent on the in place speed limit before construction. The speed limit reduction should not exceed 10 mph below the existing speed limit, unless the design speed of the work zone feature has been reduced below the 10 mph. In this case, the speed limit reduction shall not exceed 30 MPH. Where speed limits are to be reduced more than 30 MPH, a second speed limit sign shall be installed with the desired speed reduction but shall not exceed 30 MPH. The second speed limit sign shall be placed at $\frac{1}{2}B$.
 - When warning signs are used in urban areas and the signs are not portable, flags shall be installed. The flags shall be 24 inches square, mounted perpendicular to the edges of the diamond sign, and at such a distance above the edge so that when the flag is limp it will not touch the sign. Rural areas will not require flags.
 - Existing speed limit signs within a reduced speed zone shall be covered.
 - The contractor has the option of using portable sign supports in lieu of post mounted signs in accordance with the NDDOT Standard Specifications.

Longitudinal Buffer Space	
Speed (mph)	Length Min (feet)
20	115
25	155
30	200
35	250
40	305
45	360
50	425
55	495
60	570
65	645
70	730
75	820

ADVANCE WARNING SIGN SPACING			
Road Type	Distance Between Signs Min. (ft)		
	A	B	C
Urban - Low Speed (30 mph or less)	150	150	150
Urban - Low Speed (over 30 to 40 mph)	280	280	280
Urban - High Speed (over 40 mph to 50 mph)	360	360	360
Rural - High Speed (over 50 mph to 65 mph)	720	720	720
Urban Expressway and Freeway (55 mph to 60 mph)	850	1350	2200
Rural Expressway and Freeway (70 mph to 75 mph)	1000	1500	2640
Interstate/4-Lane Divided (Maintenance and Surveying)	750	1000	1500




NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-27-13	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by
 Roger Weigel
 Registration Number
 PE-2930,
 on 09/27/13 and the original document is stored at the
 North Dakota Department
 of Transportation

MISCELLANEOUS SIGN LAYOUTS


D-704-26



TYPE Y
To be used where the haul road crosses a highway outside a major work area.




TYPE AA
To be used where survey crew is being used




TYPE KK
To be used at major intersections within pilot car control area


- Notes
1. The speed limit shall be re-established. The exact speed limit shall be determined in the field, dependent on location and conditions.
 2. The reduced speed limit shall be determined dependent on the in place speed limit before construction. The speed limit reduction should not exceed 10 mph below the existing speed limit, unless the design speed of the work zone feature has been reduced below the 10 mph. In this case, the speed limit reduction shall not exceed 30 MPH. Where speed limits are to be reduced more than 30 MPH, a second speed limit sign shall be installed with the desired speed reduction but shall not exceed 30 MPH. The second speed limit sign shall be placed at 1/2 B.
 3. When warning signs are used in urban areas and the signs are not portable, flags shall be installed. The flags shall be 24 inches square, mounted perpendicular to the edges of the diamond sign, and at such a distance above the edge so that when the flag is limp it will not touch the sign. Rural areas will not require flags.
 4. Existing speed limit signs within a reduced speed zone shall be covered.
 5. The contractor has the option of using portable sign supports in lieu of post mounted signs in accordance with the NDDOT Standard Specifications.
 6. G20-55-96 signs are not required if this standard is part of other traffic control layouts, or the work is less than 15 days.
 7. When a pilot car operation is used, place a G20-4b-36 "Wait For Pilot Car" sign at major intersections within pilot car control area.




TYPE BB
To be used within a major work area where the sign conditions exist




TYPE CC
To be used where the sign conditions exist



TYPE DD
To be used where the sign conditions exist




TYPE Z
To be used where speed zone is needed




TYPE JJ
To be used where there is a break in the pavement. These signs may be skid mounted or post mounted and shall be installed when conditions exist and removed when not applicable.

Longitudinal Buffer Space	
*Speed (mph)	Length Min (feet)
20	115
25	155
30	200
35	250
40	305
45	360
50	425
55	495
60	570
65	645
70	730
75	820


* Posted speed, off-peak 85th percentile speed prior to work starting, or the anticipated operating speed in mph.



TYPE GG
To be used where a difference of elevation between lanes exist



TYPE EE
To be used where the sign conditions exist



TYPE FF
To be used where the sign conditions exist

Road Type	Distance Between Signs Min. (ft)		
	A	B	C
Urban - Low Speed (30 mph or less)	150	150	150
Urban - Low Speed (over 30 to 40 mph)	280	280	280
Urban - High Speed (over 40 mph to 50 mph)	360	360	360
Rural - High Speed (over 50 mph to 65 mph)	720	720	720
Urban Expressway and Freeway (55 mph to 60 mph)	850	1350	2200
Rural Expressway and Freeway (70 mph to 75 mph)	1000	1500	2640
Interstate/4-Lane Divided (Maintenance and Surveying)	750	1000	1500

KEY

Sign (represented by a vertical line with a horizontal bar)

Flagger (represented by a square with a diagonal line)








Cones (represented by a triangle)

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-27-13	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by Roger Weigel Registration Number PE-2930, on 09/27/13 and the original document is stored at the North Dakota Department of Transportation

TRAFFIC CONTROL PLAN FOR MOVING OPERATIONS

D-704-27




- Notes
1. If the contractor chooses to place more vehicles in the convoy than are shown, these vehicles shall have the truck mounted attenuator and shall be at the contractor's expense.
 2. Shadow and work vehicles shall display yellow rotating beacons or strobe lights unless otherwise stated elsewhere in the plans.
 3. Flashing arrow panels shall be Type B or Type C. The panel operation shall be controlled from inside the vehicle.
 4. Each vehicle shall have two-way electronic communication capability.
 5. When work convoys must change lanes, shadow vehicle 1 should change lanes first to shadow other convoy vehicles.
 6. Vehicle spacing between the shadow vehicle 1 and shadow vehicle 2 will vary depending on sight distance restrictions. Motorists approaching the work convoy should be able to see the trail vehicle in time to slow down and/or change lanes as they approach the shadow vehicle.
 7. Sign Colors
Letters = Black
Border = Black
Background = Orange
 8. Shadow vehicle 2 may be used as the paint tender vehicle.
 9. Sign CW21-10A shall only be used during a painting operation.
 10. On two lane - two way roadways, the work and shadow vehicles should pull over periodically to allow motor vehicle traffic to pass.



NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-27-13	
REVISIONS	
DATE	CHANGE
6-18-14	Removed shadow vehicle 2 on two lane roadways


This document was originally issued and sealed by
 Roger Weigel
 Registration Number
 PE-2930,
 on 06/18/14 and the original document is stored at the
 North Dakota Department
 of Transportation

SIGN LAYOUT FOR ONE LANE CLOSURE




RIGHT LANE CLOSED WORKERS IN WORK AREA (Detail Mirrored for Left Lane Closure)

- Notes:
- Advance signs for flagging should be installed when flaggers are present.
 - The advanced flagger sign and the speed limit signs shall be moved as the work area moves through the construction zone. When the work area is not visible from the flagger, the flagger station shall be placed so the work area is visible. The 40 mph speed limit sign shall be spaced at 1/2 A in advance of the flagger sign. The 60 mph speed limit sign shall also be moved. Upon completion of the work day or when workers are not present, the 40 mph speed limit and the Minimum Fee \$80 signs shall be covered or removed. The exact speed limit shall be determined in the field, dependent on location and conditions.
 - Approaches: When the work area encompasses an approach, the approach shall be controlled by installing a 40 mph speed limit sign. If this approach is on the side of the lane closure, the existing stop sign shall be covered and a new portable stop sign shall be installed. When the main line 40 mph speed zone is moved past the approach, the approach speed limit sign shall be removed.
 - Variables:
 - S=Numerical value of speed limit or 85th percentile
 - W=The width of taper.
 - L=Minimum length of taper, or SxW for freeways, expressways, and all other roads with speeds of 45 mph or greater, or (WxSxS)/60 for urban, residential, and other streets with speeds of 40 mph or less.
 - Delineator drums, used for tapering traffic shall be spaced at the dimension "S". Tubular markers used for tangents shall be spaced at 2 times dimension "S".
 - Sequencing arrow panels should normally be placed at the beginning of the taper. Where shoulder width does not provide sufficient room, the panel should be moved closer to the work area so that it can be placed on the roadway surface.
 - Type A shall be used on roadways with slow moving traffic speeds and low volume (25 mph or less and 750 ADT or less).
 - Type B shall be used on roadways with moderate traffic speeds and volumes (40 mph or less and 5000 ADT or less).
 - Type C shall be used on roadways with high traffic speeds and volumes (over 40 mph or over 5000 ADT).
 - The speed limit shall be re-established. The exact speed limit shall be determined in the field, dependent on location and conditions.
 - Existing speed limit signs within a reduced speed zone shall be covered.
 - When warning signs are used in urban areas and the signs are not portable, flags shall be installed. The flags shall be 24 inches square, mounted perpendicular to the edges of the diamond sign, and at such a distance above the edge so that when the flag is limp it will not touch the sign. Rural areas will not require flags.
 - The reduced speed limit shall be determined dependent on the in place speed limit before construction. The speed limit reduction should not exceed 10 mph below the existing speed limit, unless the design speed of the work zone feature has been reduced below the 10 mph. In this case, the speed limit reduction shall not exceed 30 mph. Where speed limits are to be reduced more than 30 mph, a second speed limit sign shall be installed with the desired speed reduction, but shall not exceed 30 mph. The second speed limit sign shall be placed at 1/2 B.
 - The contractor has the option of using portable sign supports in lieu of post mounted signs in accordance with NDDOT Standard Specifications.
 - Sign G20-55-96 is not required if this standard is part of other traffic control layouts or the work is less than 15 days.



LEFT SHOULDER TAPER DETAIL



RIGHT SHOULDER TAPER DETAIL

Longitudinal Buffer Space	
Speed (mph)*	Length Min (feet)
20	115
25	155
30	200
35	250
40	305
45	360
50	425
55	495
60	570
65	645
70	730
75	820


*Posted speed, off-peak 85th percentile speed prior to work starting, or the anticipated operating speed in mph.

ADVANCE WARNING SIGN SPACING			
Road Type	Distance Between Signs Min (ft)		
	A	B	C
Urban - Low Speed (30 mph or less)	150	150	150
Urban - Low Speed (over 30 to 40 mph)	280	280	280
Urban - High Speed (over 40 mph to 50 mph)	360	360	360
Rural - High Speed (over 50 mph to 65 mph)	720	720	720
Urban Expressway and Freeway (55 mph to 60 mph)	850	1350	2200
Rural Expressway and Freeway (70 mph to 75 mph)	1000	1500	2640
Interstate/4-Lane Divided (Maintenance and Surveying)	750	1000	1500


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-26-2012	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 9/26/2012 and the original document is stored at the North Dakota Department of Transportation

MOBILE OPERATION
Grinding Shoulder Rumble Strips




TWO LANE - TWO WAY ROADWAY




TWO LANE - TWO WAY ROADWAY
Typical Protection Vehicle with
Flashing Arrow Panel In Caution Mode

Notes:


1. If the contractor chooses to place more vehicles in the convoy than are shown, these vehicles shall have the truck mounted attenuator and shall be at the contractors expense.
2. Vehicles shall have a rotating, flashing, oscillating or strobe lights.
3. Flashing arrow panels shall be Type B or Type C. The panel operation shall be controlled from inside the vehicle.
4. Each vehicle shall have two - way electronic communication capability.
5. Vehicle spacing between the protection vehicle and work vehicle will vary depending on sight distance restrictions. Motorists approaching the work convoy should be able to see the protection vehicle in time to slow down and safely pass the work vehicles.
6. ROAD WORK AHEAD SIGN: Advance Road Work Ahead signs shall be moved as the work area moves through the construction zone.
7. Next XX Miles sign required when the distance from Road Work Ahead sign to the work location is two miles or greater.



INTERSTATE & 4 LANE DIVIDED HIGHWAY



INTERSTATE & 4 LANE DIVIDED HIGHWAY
Typical Protection Vehicle with Flashing Arrow
Panel In Flashing Arrow Mode




NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
11-15-12	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel Registration Number PE-2930, on 11/15/12 and the original document is stored at the North Dakota Department of Transportation



BITUMINOUS LABORATORY

D-706-1



Provide a laboratory with the following:


1. A 1'x1' shelf at 36" above the regular countertop.
2. Double compartment stainless steel sink, with each compartment a minimum of 16"x14"x10" deep. Provide water service lines made of copper or plastic and a diameter of 1/2 inch.
3. An exhaust fan capable of removing inside air at a rate of 400 CFM.
4. Fresh air vent hinged to open or close manually.
5. 24" x 48" table capable of holding a 200 lb masonry saw with a minimum clearance of 36" above the table.
6. A water supply tank with a capacity of 500 gallons and a 20 gallon capacity pressure tank on the pump.
7. Heavy duty type locks, latches, and hinges for doors made to withstand the intense use in service.
8. A wall between the office and the work area properly insulated to prevent the transmission of heat and noise.
9. The steel cable tie downs and ground anchors at each corner of the lab.
10. Electrical service entrance wired for 100 amps and separate circuits for air conditioners. Space convenience outlets in counter areas a minimum of four feet apart.




NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-03-13	
REVISIONS	
DATE	CHANGE
07-30-14	Changed standard's title and revised notes.
01-11-16	Revised notes.

This document was originally issued and sealed by
Roger Weigel
 Registration Number
PE- 2930,
 on 01/11/16 and the original document is stored at the North Dakota Department of Transportation

REINFORCED CONCRETE PIPE CULVERTS AND END SECTIONS
(Round Pipe)




PERSPECTIVE




END VIEW

Standard Reinforcement for Class III pipe reinforced as per AASHTO M170



SIDE VIEW




TOP VIEW


REINFORCED CONCRETE PIPE - FLARED END SECTION

Reinforcement to be equivalent to Class III RCP

TRAVERSABLE END SECTION							
DIA	B	C	D	E	F	R	S
15"	4'	9"	4'-9"	1'-7½"	2½"	3"	6
18"	5'-9"	9"	6'-6"	1'-11"	2½"	3"	6
24"	6'	1'	7'	2'-6"	3"	3"	4
30"	7'-6"	1'	8'-6"	3'-1"	3½"	3½"	4
36"	7'-3"	15"	8'-6"	3'-8"	4"	3"	4



SIDE VIEW




END VIEW

NOTES (Traversable End Section):

1. Manufactured in accordance with applicable portions of ASTM C76/AASHTO M170.
2. Reinforcement per Class III RCP with double reinforcement in the upper 120° of the full barrel portion.


REINFORCED CONCRETE PIPE - TRAVERSABLE END SECTION

Reinforcement to be equivalent to Class III RCP




END VIEW

CIRCULAR PIPE




TONGUE & GROOVE JOINT



BELL & SPIGOT JOINT

JOINTS FOR REINFORCED CONCRETE PIPE



CONCRETE PIPE PLUG

FLARED END SECTION						
TERMINAL DIMENSIONS						
DIA	A	B	C	D	E	U
12	0'-4"	2'-0"	4'-0½"	6'-0½"	2'-0"	2"
15	0'-6"	2'-3"	3'-10"	6'-1"	2'-6"	2½"
18	0'-9"	2'-3"	3'-10"	6'-1"	3'-0"	2½"
21	0'-9"	3'-0"	3'-1"	6'-1"	3'-6"	2½"
24	0'-9½"	3'-7½"	2'-6"	6'-1½"	4'-0"	3"
27	0'-10½"	4'-0"	2'-1½"	6'-1½"	4'-6"	3½"
30	1'-0"	4'-6"	1'-7¾"	6'-1¾"	5'-0"	3½"
36	1'-3"	5'-3"	2'-9"	8'-0"	6'-0"	4"
42	1'-9"	5'-3"	2'-9"	8'-0"	6'-6"	4½"
48	2'-0"	6'-0"	2'-0"	8'-0"	7'-0"	5"
54	2'-3"	5'-5"	2'-9½"	8'-2½"	7'-6"	5½"
60	2'-11"	5'-0"	3'-3"	8'-3"	8'-0"	5"
66	2'-6"	6'-0"	2'-3"	8'-3"	8'-6"	5½"
72	3'-0"	6'-6"	1'-9"	8'-3"	9'-0"	6"
78	3'-0"	7'-6"	1'-9"	9'-3"	9'-6"	6½"
84	3'-0"	7'-6½"	1'-9"	9'-3½"	10'-0"	6½"
90	3'-5"	7'-3½"	2'-0"	9'-3½"	11'-0"	6½"

All Classifications of Round Concrete Pipe

Internal Dia. of Pipe (In.)	Cross-Sectional Water Area (Sq. ft.)	Weight per Lin. Foot of Pipe (Lbs.)	Joint Groove Min./Max. (In.)	Joint Tongue Min./Max. (In.)	Minimum Wall Thickness (In.)
12	0.79	92	1½-2¾	¾	2
15	1.23	127	1¾-2¾	¾	2½
18	1.77	168	1¾-2¾	1	2½
21	2.40	214	1¾-3¾	1½	2¾
24	3.14	265	2¾-3¾	1½	3
27	3.98	322	2¾-4	1¾	3¼
30	4.91	384	3¾-4¼	1¾	3½
33	5.94	452	3¾-4¼	1½	3¾
36	7.07	524	3¾-4¼	1½	4
42	9.62	685	3¾-4¼	1¾	4½
48	12.57	885	3¾-4¼	1¾	5
54	15.90	1070	4½-5½	2	5½
60	19.63	1296	4½-5½	2¼	6
66	23.76	1542	5-6	2½	6½
72	28.27	1810	5½-6¾	2½	7
78	33.18	2098	6¼-7¼	2½	7½
84	38.48	2410	5½-7¼	3¾	8
90	44.18	2793	6¾-8½	3¾	8½
96	50.27	3092	7-8¼	3½	9
102	56.75	3466	7-8¼	3½	9½
108	63.62	3864	7¼-8½	3¾	10

SEE STANDARD DRAWING D-714-22 FOR DETAILS OF CONCRETE PIPE TIES (TIE BOLTS).

NOTES:

1. All reinforcing steel shall meet AASHTO M170 requirements.
2. All circular, longitudinal, and elliptical reinforcement shall be assembled and securely fastened in cage fashion so as to maintain reinforcement in exact shape and correct positions within the forms.
3. Laying length of pipe: 12" to 66" (incl.) = not less than 4 feet
66" to 108" (incl.) = not less than 6 feet
4. Joints shall be sealed with rubber gaskets or with sealer approved by the engineer whenever pipe are specified for storm drain or sanitary sewers.
5. For Class IV and Class V reinforced concrete pipe and end section sizes which do not have reinforcement specified by AASHTO M170, shop drawings and design calculations shall be prepared and sealed by a Professional Engineer and submitted for the Engineer's review.

NORTH DAKOTA
DEPARTMENT OF TRANSPORTATION

05-12-14
REVISIONS




DATE	CHANGE
------	--------

01-21-15	Revised Note 5
----------	----------------

This document was originally issued and sealed by Terrence R. Udland, Registration Number PE-2674, on 01/21/15 and the original document is stored at the North Dakota Department of Transportation

ROUND CORRUGATED STEEL PIPE CULVERTS AND END SECTIONS

D-714-4



PIPE DIA. IN	GALV. THICK.	END SECTION DIMENSIONS					APPROX. SLOPE	BODY PIECE
		A IN	B IN	H IN	L IN	W IN		
15	0.064	7	8	6	26	30	2 1/2:1	1
18	0.064	8	10	6	31	36	2 1/2:1	1
24	0.064	10	13	6	41	48	2 1/2:1	1
30	0.079	12	16	8	51	60	2 1/2:1	1 or 2
36	0.079	14	19	9	60	72	2 1/2:1	2
42	0.109	16	22	11	69	84	2 1/2:1	2
48	0.109	18	27	12	78	90	2 1/2:1	2
54	0.109	18	30	12	84	102	2:1	2
* 60	0.109	18	33	12	87	114	1 1/2:1	3
* 66	0.109	18	36	12	87	120	1 1/2:1	3
* 72	0.109	18	39	12	87	126	1 1/3 :1	3
* 78	0.109	18	42	12	87	132	1 1/2:1	3
* 84	0.109	18	45	12	87	138	1 1/6 :1	3



















- These sizes have 0.109" sides and 0.138" center panels.
 - Pipe diameter is equal to dimension "D" of end section.
- Manufacturers tolerances of above dimensions will be allowed.
- Splices to be the lap riveted type.

Multiple panel bodies shall have lap seams which are to be tightly joined with 3/8" dia. galv. bolts or rivets. Nuts to be torqued to 25 foot-lbs ±.

NOTES:

1. Pipes and connecting bands shall conform to applicable sections of NDDOT Standard Specifications and to AASHTO M-36.
2. Top edge of all end sections to have rolled edges for reinforcement (see Section A-A). The reinforced edges are to be supplemented with 2" x 2" x 1/4" galv. angle for 60" through 72" dia. and 2 1/2" x 2 1/2" x 1/4" galv. angle for 78" and 84" dia.. Angles to be attached by galv. 3/8" dia. bolts and nuts. Angles are to extend from pipe to the corner wing bend.
3. Elongated pipes shall be factory preformed so that the vertical diameter shall be 5% greater and the horizontal diameter 5% less than a circular pipe.
4. Coupling bands shall be two-piece for pipes larger than 36" as shown in Section C-C & D-D details. For pipes 36" and smaller, a one-piece band is acceptable.
5. 1/2" x 8" bolts may be used as a substitute for the 1/2" x 6" bolts shown in the details.
6. Coupling bands wider than 14" may be used if a minimum of four 1/2" bolts with maximum spacing of 5 1/2" are used for the connection.
7. Length of spot welds shall be minimum 1/2".

COUPLING BAND DIMENSIONS				
COUPLING TYPE	CORRUGATION PITCH x DEPTH	PIPE SIZE	COUPLING BAND LENGTH	MIN. BAND THICKNESS
Hat Band	2 3/8" x 1/2"	12" - 48"	2 3/4"	.064"
Annular Band	2 3/8" x 1/2"	12" - 72"	12"	.052"
		78" - 84"	12"	.079"
Hugger Band	2 3/8" x 1/2" Rerolled End	12" - 72"	10 1/2"	.052"
		78" - 84"	10 1/2"	.079"
	3" x 1" Rerolled End	48" - 120"	10 1/2"	.052"
	5" x 1" Rerolled End	48" - 120"	12"	.064"






NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
08-06-13	
REVISIONS	
DATE	CHANGE
01-07-14	End Section Plan View
02-27-14	3" x 1" Corrugation Detail




This document was originally issued and sealed by Terrence R. Udland, Registration Number PE- 2674 , on 02/27/2014 and the original document is stored at the North Dakota Department of Transportation

CONCRETE PIPE OR PRECAST CONCRETE BOX CULVERT TIES




REQUIRED SIZE OF TIE BOLTS		
Pipe Size	Thread ϕ	XXS Pipe Sleeve Inner ϕ
18" - 24"	$\frac{5}{8}$ " See note 2	$\frac{3}{4}$ "
30" - 66"	$\frac{3}{4}$ "	1"
72" - 78"	1"	1 $\frac{1}{4}$ "
RCB		



SECTION A-A




DETAIL A




DETAIL B

NOTES:

- The pipe size listed is the inside diameter of round pipe or the equivalent diameter of pipe arch.
- Nuts and washers are not required on Jacked and Bored pipes or pipes with a 24" diameter or less. Where nuts and washers are not used, the tie bars shall be inserted and grouted into place.
- Ties are only for holding pipe or RCB sections together, not for pulling sections tight.
- Tie bolt assembly shall be hot dip galvanized in accordance with AASHTO M232.
- Holes in pipes to accommodate tie bolts can be precast or drilled. Tapered holes are permitted when precast. Holes shall have a diameter 1/4" larger than the diameter of the thread. Holes in precast RCB's shall contain cast-in bolt sleeves with an inside diameter of 1 1/4".
- The contractor has the option of selecting the type of tie bolt used from those shown.
- The cost of precasting or drilling the required holes and furnishing and installing the tie bolts shall be included in the price bid for the appropriate conduit or RCB pay item.
- All centerline and approach RCP culvert joints shall be tied. Storm drain systems shall have the first three joints including the end section of all free ends tied. Free ends are defined as any storm drain end which does not terminate at an inlet or manhole. Outfall culverts with end sections which drain adjacent ditches are examples of free ends.
- When joint wrap is specified in the plans, place wrap beneath ties. Overlap the joint by 12" in both directions.
- Tie bolts shall conform to ASTM A 36. Nuts shall be heavy hex and conform to ASTM A 563. Washers shall conform to ASTM F 436, Type 1. Welded pipe sleeves and cast-in bolt sleeves shall conform to ASTM A 53, Grade B.
- Cattle Pass and Jacked and Bored pipes shall have pipe ties inserted from the inside of the pipes and grouted into place. Jacked and bored pipes with a diameter of 24" or less do not require pipe ties.
- RCB tie locations shall be as shown on the plans.



PLAN VIEW




END VIEW


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
3-18-14	
REVISIONS	
DATE	CHANGE
7-21-15	Note 8

This document was originally issued and sealed by Terrence R. Udland, Registration Number PE-2674, on 07/21/15 and the original document is stored at the North Dakota Department of Transportation

PIPE INSTALLATION DETAIL FOR LONGITUDINAL MAINLINE PIPE
OR PIPE NOT UNDER THE ROADWAY



EXCAVATION DETAIL A



EXCAVATION DETAIL B

Pay Items

- 1) Pipe*
- 2) Removal of Pipe (if required)


*Included in Pipe Pay Item

- 1) Pipe
- 2) Trench excavation
- 3) Aggregate base course CI 3 or CI 5
- 4) Embankment


NOTES:

- 1) This drawing does not apply to pipes in approaches.
- 2) It is the contractor's option to select Detail A or B.
- 3) Embankment may be either Borrow Excavation or Common Excavation - Type A

Bedding and Haunch (A)
Pipes Not Under Roadway = 0.5 O.D. + 4 Inches
Pipes Under the Roadway = 0.5 O.D. + 2 Feet
Backfill Cover (B)
Concrete Pipe = 0.5 O.D.
Metal and Plastic = 0.5 O.D. + 1 Foot
Backfill Material (C)
Top of Pipe 4 Feet or Less Below the Top of Proposed Subgrade = Aggregate Base Course CI3 or CI 5
Top of Pipe Greater than 4 Feet Below the Top of Proposed Subgrade = Common Excavation - Type A
Pipe Not Under Roadway = Common Excavation - Type B



BACKFILL DETAIL A




BACKFILL DETAIL B

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
7-26-13	
REVISIONS	
DATE	CHANGE
10-15-13 1-21-15 12-10-15	Label Formatting Nomenclature Added Plastic Pipe

This document was originally issued and sealed by
Ron Horner,
Registration Number
PE- 2087 ,
on 12/10/2015 and the original document is stored at the
North Dakota Department
of Transportation

LETTER AND ARROW DETAILS FOR VARIABLE LENGTH SIGNS



D-754-9




SIZE OF THE FRACTION IS DETERMINED AS FOLLOWS:

SYMBOL	TITLE	RATIO TO HEIGHT OF CAPITAL OR UPPER CASE
A	Letter height	1.0 of capital or upper case
B	Fraction height	1.5 X A
C	Fraction width	2.5 X A
D	Fraction width	2 X A
E	Space to next character	1 to 1.5 X A
F(A)	Length of diagonal	1.75 X A



(A) Diagonal stroke of fraction is to be centered optically.



"EXIT" LETTER SIZE (Upper Case)	A	B	C	D	E	R
8"	15 1/8"	11 1/16"	3 3/4"	1 5/16"	25"	13 1/16"
10" - 13 1/3"	18 1/4"	14"	4 1/2"	1 1/2"	30"	3 1/4"



LETTER SIZE (Upper Case)	A	B	C	D	E	R
8"	15 1/8"	11 1/16"	3 3/4"	1 5/16"	17"	13 1/16"
10" - 13 1/3"	18 1/4"	14"	4 1/2"	1 1/2"	20"	3 1/4"
16" - 20"	22 1/4"	17"	5 3/8"	1 3/4"	25"	1"



LETTER SIZE (Upper Case)	A	B	C	D	E	F
4"	1 3/4"	2"	3 9/16"	5/16"	3/8"	6"
6"	2 3/4"	3"	5 9/16"	7/16"	9/16"	9"
8"	3 1/2"	4"	7 1/8"	9/16"	1 1/16"	12"
12"	5 1/4"	6"	10 5/8"	1 3/16"	1 1/16"	18"

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-3-11	
REVISIONS	
DATE	CHANGE
7-8-14	Revised gore sign and added 4" D & D arrow


This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 7/8/14 and the original document is stored at the North Dakota Department of Transportation

PERFORATED TUBE ASSEMBLY DETAILS

D-754-23


Notes:

1. Curbed Roadways: The clearance from the face of the curb should be 3' except where right of way or sidewalk width is limited, a minimum clearance of 2' shall be provided. The horizontal clearance may need to be increased to maintain a minimum sidewalk clear width of 4' from the sign support, not including any attached curb.
2. Minimum vertical clearance: Signs installed at the side of the road in rural districts shall be at least 5' measured from the bottom of the sign to the edge of the driving lane or auxiliary lane. Where parking or pedestrian movements occur, the clearance to the bottom of the sign shall be at least 7'.
- Signs on expressways shall be installed with a minimum height of 7'.
- Adopt-a-highway signs installed on Freeways shall be at least 7' above the edge of the driving lane.
- The vertical clearance shall have a maximum height of 6" above the vertical clearance specified above.
3. Offset signs: Where signs are placed at least 30 feet or more from the edge of the traveled way, the height to the bottom of such sign shall be 5' above the edge of the driving lane.
4. The clearance from edge of shared use path to edge of sign should be 3' except where width is limited, a minimum clearance of 2' shall be provided.




Typical Section (without curb)

Horizontal Clearance Table	
Shoulder Width ft	Offset ft
0 to 2	16
>2 to 4	18
>4 to 6	20
>6 to 8	22
>8 to 10	24




Typical Section (with curb)
Residential or Business District



Stop Sign Location
Wide Throat Intersection

This layout is to be used for the placement of "Stop" signs.

Radius ft.	Y-max. ft.	Y-min. ft.
40	50	15
45	50	18
50	50	21
55	50	25
60	50	28
65	50	32
70	50	35
75	50	39
80	50	43






Shared Use Path
Bicycle - Pedestrian Path

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-3-13	
REVISIONS	
DATE	CHANGE
7-8-14	Revised note 2, added note 4.




This document was originally issued and sealed by
Roger Weigel
 Registration Number
 PE-2930,
 on 7/8/14 and the original document is stored at the
 North Dakota Department
 of Transportation

**SIGN PUNCHING, STRINGER AND SUPPORT LOCATION DETAILS -
DIVIDED HIGHWAY CONTROL SIGNS**

D-754-77



ASSEMBLY NO. 445 & 449



ASSEMBLY NO. 446 & 450


Notes:

1. The minimum sign backing material thickness shall be 0.100 inch.
2. Perforated square tube stringer shall be 1½"x1½".
3. All holes shall be punched round for ⅜" bolt.
4. Assemblies 445 and 446 have single one way signs.
Assemblies 449 and 450 have back to back one way signs.


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-22-12	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by
Roger Weigel
Registration Number
PE-2930,
on 8/22/12 and the original document is stored at the North Dakota Department of Transportation

**RUMBLE STRIPS
DIVIDED HIGHWAYS (NON-INTERSTATE)**




Divided Highways (Non-Interstate)




Inset B - Shoulder Rumble Strip

NOTES:


1) Discontinue rumble strips through the entire length of turn lanes & ramps, 100' before turn lane tapers, 100' before or after ramp tapers, and at the radius of a paved or gravel highway, section line, approach, or private drive as shown below.



Profile of Rumble Strips - Bituminous and PCC Pavements



Discontinue rumble strip approx. 12" on both sides of PCC transverse joint




NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
12-29-09	
REVISIONS	
DATE	CHANGE
2-25-10	Note 4 was added.
9-8-11	Revised Notes and D-760-2.


This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930 , on 9/8/11 and the original document is stored at the North Dakota Department of Transportation

PAVEMENT MARKING


D-762-4




Two Lane Two Way
RURAL ROADWAY




Two Lane Roadway
INTERSTATE HIGHWAY
Concrete Section




RURAL FIVE LANE ROADWAY
Concrete Section




Two Lane Divided
Rural Roadway
PRIMARY HIGHWAY
Asphalt Section




RURAL FIVE LANE ROADWAY
Asphalt Section




URBAN FIVE LANE SECTION
Concrete Section




Two Lane Roadway
PRIMARY HIGHWAY
Concrete Section




URBAN FIVE LANE SECTION
Asphalt Section




RURAL FOUR LANE ROADWAY
Asphalt Section




Two Lane Roadway
INTERSTATE HIGHWAY
Asphalt Section




RURAL FOUR LANE ROADWAY
Concrete Section



URBAN FOUR LANE SECTION
Asphalt Section



URBAN FOUR LANE SECTION
Concrete Section




CENTERLINE PAVEMENT MARKING SKIP SPACING DETAIL

NOTES:
1. Edge lines shall be continued through private drives and field drives and broken for intersections.


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
12-1-10	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 12-1-10 and the original document is stored at the North Dakota Department of Transportation

SHORT-TERM PAVEMENT MARKING




Painted or Tape Lines




Raised Pavement Markers

TWO-LANE TWO-WAY ROADWAY




Painted or Tape Lines




Raised Pavement Markers

FOUR LANE ROADWAY




Painted or Tape Lines




Raised Pavement Markers

FIVE LANE ROADWAY TWO WAY LEFT TURN



Painted or Tape Lines



Raised Pavement Markers

FIVE LANE ROADWAY WITH MARKED ISLANDS

NOTES:

- Two-lane two-way roadways shall have no passing zones placed as shown. No passing zone signs may be placed in lieu of short term no passing zone pavement markings. These signs will be allowed to remain in place for three days, at which time the short term no passing zone pavement marking shall be placed.
- Short term center line stripe (paint) on top lift shall be carefully placed with exact spacing so that the permanent stripe will match when applied.
- Raised markers and tape markings shall be removed after permanent pavement marking has been installed. Removed markings shall become the property of the contractor.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
12-1-10	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 12-1-10 and the original document is stored at the North Dakota Department of Transportation