

DESIGN DATA			
Traffic		Average Daily	
Current 2016 (127.662)	Pass: 7,415	Trucks: 2,330	Total: 9,745
Forecast 2036 (127.662)	Pass: 10,610	Trucks: 3,010	Total: 13,620
Current 2016 (182.488)	Pass: 6,070	Trucks: 2,905	Total: 8,975
Forecast 2036 (182.488)	Pass: 8,685	Trucks: 3,925	Total: 12,610
Clear Zone Dist. 34 feet	Design Speed: 75 mph		
Minimum Sight Dist. for Stopping:	Bridges:		
Full Control of Access, No Point of Access Other Than at Interchange Ramps			
Pavement Design Life (years)			
Design Accumulated One-way	ESALs:		




# JOB # 5 NORTH DAKOTA DEPARTMENT OF TRANSPORTATION

**HEN-1-999(028)**  
Morton and Burleigh County  
I-94 New Salem Interchange  
I-94 Sterling Interchange  
Lighting

STATE	PROJECT NO.	PCN	SECTION NO.	SHEET NO.
ND	HEN-1-999(028)	21519	1	1

**GOVERNING SPECIFICATIONS:**  
2014 Standard Specifications adopted by the North Dakota Department of Transportation and the Supplemental Specifications effective on the date the project is advertised.

PROJECT NUMBER \ DESCRIPTION	NET MILES	GROSS MILES
HEN-1-999(028)		



**STATE COUNTY MAP**

**DESIGNERS**

\_\_\_\_\_  
Blaine Johanneson /s/

\_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

APPROVED DATE 8/25/16  
\_\_\_\_\_  
for Roger Weigel /s/  
OFFICE OF PROJECT DEVELOPMENT  
ND DEPARTMENT OF TRANSPORTATION

I hereby certify that the attached plans were prepared by me or under my direct supervision and that I am a duly registered professional engineer under the laws of the state of ND.

APPROVED DATE 8/25/16  
\_\_\_\_\_  
James Douglas Rath /s/  
NDDOT DIV-DIST OR CONSULTANT FIRM

This document was originally issued and sealed by James Douglas Rath, Registration Number PE- 4288, on 08/25/16 and the original document is stored at the North Dakota Department of Transportation

**TABLE OF CONTENTS**

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	HEN-1-999(028)	2	1

**PLAN SECTIONS**

Section	Page(s)	Description
1	1	Title Sheet
2	1	Table of Contents
6	1	Notes
8	1	Quantities
100	1	Work Zone Traffic Control
140	1 - 8	Lighting

**LIST OF STANDARD DRAWINGS**

Number	Description
D-101-1	NDDOT Abbreviations
D-101-2	NDDOT Abbreviations
D-101-3	NDDOT Abbreviations
D-101-10	NDDOT Utility Company and Organization Abbreviations
D-101-20	Line Styles
D-101-21	Line Styles
D-101-30	Symbols
D-101-31	Symbols
D-101-32	Symbols
D-704-7	Breakaway Systems For Construction Zone Signs - Perforated Tube
D-704-8	Breakaway Systems For Construction Zone Signs - U-Channel Post
D-704-9	Construction Sign Details - Terminal And Guide Signs
D-704-10	Construction Sign Details - Regulatory Signs
D-704-11	Construction Sign Details - Warning Signs
D-704-12	Shoulder Closure Tapers
D-704-13	Barricade And Channelizing Device Details
D-704-14	Construction Sign Punching And Mounting Details
D-704-24	Shoulder Closures And Bridge Painting Layouts
D-704-35	Sign Layout For One Lane Closure - Interstate System
D-704-50	Portable Sign Support Assembly
D-770-1	Concrete Foundations (Traffic Signals & Highway Lighting)
D-770-2	Feed Points (Roadway Lighting)
D-770-4	Lighting And Signal Details
D-770-5	Light Standard Details

**NOTES**

**SECTION 100**

704-P01 LIGHTING SYSTEM TRAFFIC CONTROL: Provide traffic control according to the following layouts on the Standard Drawings for traffic control:

Traffic control device quantities are based on a 3150 foot work zone.

D-704-24, type U: For lighting installation when shoulder closure is needed.  
D-704-35, right lane closed: For lighting installation when lane closure is needed.

Enough traffic control devices are provided for two lane closures.

**Section 140**

770-P01 LED LUMINAIRE: Provide luminaires that meet the following:

<b>Light Source</b>	LED
<b>Light Output</b>	18,000 lm to 22,000 lm
<b>Driver</b>	650 mA to 1000 mA
<b>Wattage</b>	160W to 190W
<b>Color Temperature</b>	4000K ±300K
<b>Operating Temperature Range</b>	-40°C to +40°C
<b>Luminaire Housing</b>	Die Cast Aluminum
<b>Vibration Testing</b>	ANSI/NEMA C136.31 Level 2, 3 G
<b>Surge Suppression Rating</b>	ANSI/IEEE C62.41 Cat C
<b>Outdoor rating for housing, wiring, and drivers</b>	ANSI C136.25 IP-65
<b>Photo Control on each luminaire</b>	No
<b>Tool-less Access</b>	Yes
<b>Qualified with DesignLights Consortium</b>	Yes

Ensure the Effective Projected Area of the luminaire does not exceed the capacity of the light standard.

The lighting system was designed using these values:

<b>Roadway Classification</b>	Principal Arterial-Interstate-Rural
<b>Average Maintained Illuminance</b>	0.6 to 0.8 foot-candles
<b>Illuminance Uniformity Ratio (avg/min)</b>	3.0:1 to 4.0:1
<b>Minimum Illuminance</b>	0.2
<b>Light Loss Factor</b>	0.69

Provide one of the luminaires listed or an approved equal:

Company	Catalog Number
American Electric Lighting	ATB2 60BLEDE85 MVOLT R2
Philips	RFL-180W80LED4K-T-R2M

770-P02 LIGHT STANDARD: Design the light standard base with a minimum of 4 anchor bolts. Install davit type galvanized light standards with 12' mast arms.

770-P03 MULTIPLE UNDERGROUND CABLE: The plans call for using Multiple Underground Cable and Conduit in various locations. In lieu of the Multiple Underground Cable, the contractor may furnish and install rigid conduit and single RHW conductors of the same size for the Multiple Underground Cable.

Install conduit size as specified by the National Electric Code. If the contractor chooses to use the conduit and single conductors, the cost to furnish conduit and conductors shall be included in the item Multiple Underground Cable. Include the cost of installing conduit with single conductors in the bid price for the "Lighting System".

Include the conduit shown in the plans under roadways for installing Multiple Underground Cable in the item "Lighting System".

This document was originally issued and sealed by Blaine D. Johanneson, Registration Number PE-5038, on 8/25/16 and the original document is stored at the North Dakota Department of Transportation.


# ESTIMATE OF QUANTITIES

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	HEN-1-999(028)	8	1

SPEC CODE	ITEM DESCRIPTION	UNIT	HEN1999028	TOTAL
				-----
103	0100 CONTRACT BOND	L SUM	0.84	0.84
702	0100 MOBILIZATION	L SUM	0.84	0.84
704	0100 FLAGGING	MHR	40	40
704	1000 TRAFFIC CONTROL SIGNS	UNIT	2,092	2,092
704	1052 TYPE III BARRICADE	EA	2	2
704	1060 DELINEATOR DRUMS	EA	56	56
704	1067 TUBULAR MARKERS	EA	60	60
704	1087 SEQUENCING ARROW PANEL-TYPE C	EA	2	2
770	0001 LIGHTING SYSTEM	EA	2	2




STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	HEN-1-999(028)	140	1



This document was originally issued and sealed by Blaine D. Johanneson, Registration Number PE- 5038, on 08/25/16 and the original document is stored at the North Dakota Department of Transportation

Lighting System  
 Partial Interchange Lighting Layout  
 New Salem Interchange (ND 31)  
 North of New Salem

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	HEN-1-999(028)	140	2



This document was originally issued and sealed by Blaine D. Johanneson, Registration Number PE- 5038, on 08/25/16 and the original document is stored at the North Dakota Department of Transportation

Lighting System  
 Partial Interchange Lighting Layout  
 New Salem Interchange (ND 31)  
 North of New Salem

Light Std Number	Station	Cable Trench	Conduit Runs		Cable Runs	
		LF	LF	Dia	LF	Type
5 3	2702+50-91' lt to 2700+00-86' lt	248			258	3 No. 4 USE
3 1	2700+00-86' lt to 2697+50-81' lt	248			258	3 No. 4 USE
1 2	2697+50-81' lt to 2697+50-75' rt to 2698+32-77' rt	81	155	2"	246	3 No. 4 USE
2 4	2698+32-77' rt to 2700+82-83' rt	248			258	3 No. 4 USE
4 6	2700+82-83' rt to 2703+32-93' rt	248			258	3 No. 4 USE
6 7	2703+32-93' rt to 2705+66-130' rt to 2705+82-70' rt	236	61	2"	307	3 No. 4 USE
7 8	2705+82-70' rt to 2705+66-130' rt (I-94) = 6+28.5-12' rt (SWR) to 13+61-12' rt (SWR) = 95+71-79' lt (ND 31) to 94+65-29' lt (ND 31)	730 124	61	2"	925	3 No. 4 USE
8 9	94+65-29' lt (ND 31) to 94+65-29' rt (ND 31) to 95+68-76' rt (ND 31) to 96+65-29' rt (ND 31)	119	58 107	2" 2"	294	3 No. 4 USE
9 FP	96+65-29' rt (ND 31) to 95+68-76' rt (ND 31) = 0+78.5-12' rt (SER) to 4+92-12' rt (SER) to 4+92-120' rt (SER)	413 107	107	2"	643	3 No. 4 USE
10 11	103+35-29' lt (ND 31) to 104+35-78' lt (ND 31) to 105+35-28' lt (ND 31) to 105+35-29' rt (ND 31)	120	111 56	2" 2"	297	3 No. 4 USE
11 12	105+35-29' rt (ND 31) to 104+29-89' rt (ND 31) = 13+58-12' rt (NER) to 6+31-12' rt (NER) = 2720+48.5-131' lt (I-94) to 2720+32-70' lt (I-94)	126 725			923	3 No. 4 USE
12 13	2720+32-70' lt to 2720+48.5-131' lt to 2722+82-92' lt	236	62	2"	308	3 No. 4 USE
13 15	2722+82-92' lt to 2725+32-83' lt	248			258	3 No. 4 USE
15 17	2725+32-83' lt to 2727+82-77' lt	248			258	3 No. 4 USE
17 18	2727+82-77' lt to 2728+65-75' lt to 2728+65-82' rt	82	156	2"	248	3 No. 4 USE
18 16	2728+65-82' rt to 2726+15-87' rt	248			258	3 No. 4 USE
16 14	2726+15-87' rt to 2723+65-92' rt	248			258	3 No. 4 USE
14 FP	2723+65-92' rt to 4+92-12' rt (SER) to 4+92-120' rt (SER)	635 107			758	3 No. 4 USE

Lighting Quantities (A)									
Concrete Foundation - Highway Lighting	Concrete Foundation - Feed Point - Type B	Cable Trench - Type II	2" Dia Rigid Conduit	Multiple Underground Cable 3 No. 4 Style USE	Feed Point - Type I - Pad Mounted	Light Std 12' MA 42' Pole Breakaway	LED Luminaire		Lighting System
EA	EA	LF	LF	LF	EA	EA	EA		EA
18	1	5825	996	7013	1	18	18		1

(A) Do not bid separately but include in the item "Lighting System".


Light Standards						
No.	Station	Wattage	Circuit	Distribution	Pole Ht.	Mast Arm
1	2697+50-81' lt	160 - 190	1	2	42' (B)	12'
2	2698+32-77' rt	160 - 190	1	2	42' (B)	12'
3	2700+00-86' lt	160 - 190	1	2	42' (B)	12'
4	2700+82-83' rt	160 - 190	1	2	42' (B)	12'
5	2702+50-91' lt	160 - 190	1	2	42' (B)	12'
6	2703+32-93' rt	160 - 190	1	2	42' (B)	12'
7	2705+82-70' rt	160 - 190	1	2	42' (B)	12'
8	94+65-29' lt	160 - 190	1	2	42' (B)	12'
9	96+65-29' rt	160 - 190	1	2	42' (B)	12'
10	103+35-29' lt	160 - 190	2	2	42' (B)	12'
11	105+35-29' rt	160 - 190	2	2	42' (B)	12'
12	2720+32-70' lt	160 - 190	2	2	42' (B)	12'
13	2722+82-92' lt	160 - 190	2	2	42' (B)	12'
14	2723+65-92' rt	160 - 190	2	2	42' (B)	12'
15	2725+32-83' lt	160 - 190	2	2	42' (B)	12'
16	2726+15-87' rt	160 - 190	2	2	42' (B)	12'
17	2727+82-77' lt	160 - 190	2	2	42' (B)	12'
18	2728+65-82' rt	160 - 190	2	2	42' (B)	12'

LIGHTING FOUNDATION TABLE		
Description	Footing Depth "D" 24" and 30" Dia	Footing Depth "D" 36" and 42" Dia
Light Standard 42' Pole	6'	5'

This document was originally issued and sealed by Blaine D. Johanneson, Registration Number PE- 5038, on 08/25/16 and the original document is stored at the North Dakota Department of Transportation

Lighting System  
Light Standards, Cable Runs, and Quantities  
New Salem Interchange (ND 31)  
North of New Salem

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	HEN-1-999(028)	140	4




**LEGEND**

- Phase conductor
- - - Phase conductor
- Ground conductor
- (Y) Multiple Underground Cable 3 No. 4 USE
- ⊗ LED luminaire 120v x 240v operated on 240v
- Light standard
- 8 Light standard number

This document was originally issued and sealed by Blaine D. Johanneson, Registration Number PE- 5038, on 08/25/16 and the original document is stored at the North Dakota Department of Transportation

Lighting System  
 Lighting Schematic  
 New Salem Interchange (ND 31)  
 North of New Salem


STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	HEN-1-999(028)	140	5



This document was originally issued and sealed by Blaine D. Johanneson, Registration Number PE- 5038, on 08/25/16 and the original document is stored at the North Dakota Department of Transportation

Lighting System  
 Partial Interchange Lighting Layout  
 Sterling Interchange (US 83/ND 14)  
 North of Sterling

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	HEN-1-999(028)	140	6



This document was originally issued and sealed by Blaine D. Johanneson, Registration Number PE- 5038, on 08/25/16 and the original document is stored at the North Dakota Department of Transportation

Lighting System  
 Partial Interchange Lighting Layout  
 Sterling Interchange (US 83/ND 14)  
 North of Sterling

Light Std Number	Station	Cable Trench	Conduit Runs		Cable Runs	
		LF	LF	Dia	LF	Type
11	3486+57-40' rt (US 83) to 3486+57-38' lt (US 83) to 3485+63-81' lt (US 83) to 3484+57-28' lt (US 83)	106	77	2"	311	3 No. 4 USE
10			118	2"		
10	3484+57-28' lt (US 83) to 3485+63-81' lt (US 83) = 0+85-12' rt (NWR) to 10+36-12' rt (NWR) = 9625+77-94' lt (I-94) to 9624+85-92' lt (I-94)	948	118	2"	1167	3 No. 4 USE
6		91				
6	9624+85-92' lt to 9622+35-86' lt	248			258	3 No. 4 USE
4	9622+35-86' lt to 9619+85-80' lt	248			258	3 No. 4 USE
2	9619+85-80' lt to 9619+50-77' rt		159	2"	169	3 No. 4 USE
1	9619+50-77' rt to 9622+00-83.5' rt	248			258	3 No. 4 USE
3	9622+00-83.5' rt to 9624+50-93' rt	248			258	3 No. 4 USE
5	9624+50-93' rt to 9626+83-132' rt to 9627+00-72' rt	236	62	2"	308	3 No. 4 USE
7			62	2"		
7	9627+00-72' rt to 9626+83-132' rt (I-94) = 9+94-12' rt (SWR) to 17+60-12' rt (SWR) = 3476+63-169' lt (US 83) to 3475+29-144' lt (US 83)	768	62	2"	982	3 No. 4 USE
FP		136				
FP	3475+29-144' lt (US 83) to 3475+86-35' lt (US 83)	121			137	3 No. 4 USE
8	3475+86-35' lt (US 83) to 3475+86-50' rt (US 83) to 3476+89-85' rt (US 83) to 3477+91-34' rt (US 83)	109	84	2"	316	3 No. 4 USE
9			113	2"		
9	3477+91-34' rt (US 83) to 3476+89-85' rt (US 83) = 0+83-23' rt (SER) to 3+00-16' rt (SER) to 11+32-16.5' rt (SER) = 9645+90-91' rt (I-94)	217	113	2"	1164	3 No. 4 USE
13		824				
13	9645+90-91' rt to 9648+40-86' rt	248			258	3 No. 4 USE
15	9648+40-86' rt to 9650+90-81' rt	248			258	3 No. 4 USE
17	9650+90-81' rt to 9651+20-76' lt		158	2"	168	3 No. 4 USE
18	9651+20-76' lt to 9648+70-83' lt	248			258	3 No. 4 USE
16	9648+70-83' lt to 9646+20-93' lt	248			258	3 No. 4 USE
14	9646+20-93' lt to 9643+86-131' lt to 9643+70-72' lt	236	61	2"	307	3 No. 4 USE
12						

Lighting Quantities (A)									
Concrete Foundation - Highway Lighting	Concrete Foundation - Feed Point - Type B	Cable Trench - Type II	2" Dia Rigid Conduit	Multiple Underground Cable 3 No. 6 Style USE	Feed Point - Type I - Pad Mounted	Light Std 12' MA 42' Pole Breakaway	LED Luminaire		Lighting System
EA	EA	LF	LF	LF	EA	EA	EA		EA
18	1	5776	1125	7093	1	18	18		1

(A) Do not bid separately but include in the item "Lighting System".


Light Standards						
No.	Station	Wattage	Circuit	Distribution	Pole Ht.	Mast Arm
1	9619+50-77' rt	160 - 190	1	2	42' (B)	12'
2	9619+85-80' lt	160 - 190	1	2	42' (B)	12'
3	9622+00-83.5' rt	160 - 190	1	2	42' (B)	12'
4	9622+35-86' lt	160 - 190	1	2	42' (B)	12'
5	9624+50-93' rt	160 - 190	1	2	42' (B)	12'
6	9624+85-92' lt	160 - 190	1	2	42' (B)	12'
7	9627+00-72' rt	160 - 190	1	2	42' (B)	12'
8	3475+86-35' lt (US 83)	160 - 190	1	2	42' (B)	12'
9	3477+91-34' rt (US 83)	160 - 190	1	2	42' (B)	12'
10	3484+57-28' lt (US 83)	160 - 190	2	2	42' (B)	12'
11	3486+57-40' rt (US 83)	160 - 190	2	2	42' (B)	12'
12	9643+70-72' lt	160 - 190	2	2	42' (B)	12'
13	9645+90-91' rt	160 - 190	2	2	42' (B)	12'
14	9646+20-93' lt	160 - 190	2	2	42' (B)	12'
15	9648+40-86' rt	160 - 190	2	2	42' (B)	12'
16	9648+70-83' lt	160 - 190	2	2	42' (B)	12'
17	9650+90-81' rt	160 - 190	2	2	42' (B)	12'
18	9651+20-76' lt	160 - 190	2	2	42' (B)	12'

LIGHTING FOUNDATION TABLE		
Description	Footing Depth "D" 24" and 30" Dia	Footing Depth "D" 36" and 42" Dia
Light Standard 42' Pole	6'	5'

This document was originally issued and sealed by Blaine D. Johanneson, Registration Number PE- 5038, on 08/25/16 and the original document is stored at the North Dakota Department of Transportation

Lighting System  
Light Standards, Cable Runs, and Quantities  
Sterling Interchange (US 83/ND 14)  
North of Sterling

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	HEN-1-999(028)	140	8



Sta 3475+29-144' rt (US 83)  
Feed point - type II -  
pad mounted

**LEGEND**

- Phase conductor
- Phase conductor
- Ground conductor
- (Y) Multiple Underground Cable 3 No. 4 USE
- ⊗ LED luminaire 120v x 240v operated on 240v
- Light standard
- 13 Light standard number

This document was originally issued and sealed by Blaine D. Johanneson, Registration Number PE- 5038, on 08/25/16 and the original document is stored at the North Dakota Department of Transportation

Lighting System  
Lighting Schematic  
Sterling Interchange (US 83/ND 14)  
North of Sterling

NDDOT ABBREVIATIONS

? This is a special text character used in the labeling of existing features. It indicates a feature that has an unknown characteristic, potentially based on: lack of description, location accuracy or purpose.

Abn abandoned  
 Abut abutment  
 Ac acres  
 Adj adjusted  
 Aggr aggregate  
 Ahd ahead  
 ARV air release valve  
 Align alignment  
 Al alley  
 Alt alternate  
 Alum aluminum  
 ADA Americans with Disabilities Act  
 A ampere  
 & and  
 Appr approach  
 Approx approximate  
 ACP asbestos cement pipe  
 Asph asphalt  
 AC asphalt cement  
 Assmd assumed  
 @ at  
 Atten attenuation  
 ATR automatic traffic recorder  
 Ave Avenue  
 Avg average  
 ADT average daily traffic  
 Az azimuth  
 Bk back  
 BF back face  
 Bs backsight  
 Balc balcony  
 B Wire barbed wire  
 Barr barricade  
 Btry battery  
 Brg bearing  
 BI beehive inlet  
 Beg begin  
 BM bench mark  
 Bkwy bikeway  
 Bit bituminous  
 Blk block  
 Bd Ft board feet  
 BH bore hole  
 BS both sides  
 Bot bottom  
 Blvd Boulevard  
 Bndry boundary  
 BC brass cap  
 Brkwy breakaway  
 Br bridge  
 Bldg building

BV butterfly valve  
 Byp bypass  
 C Gdrl cable guardrail  
 Calc calculate  
 Cd candela  
 CIP cast iron pipe  
 CB catch basin  
 CRS cationic rapid setting  
 C Gd cattle guard  
 C To C center to center  
 Cl or C centerline  
 Cm centimeter  
 Ch chain  
 Chnlk chain-link  
 Ch Blk channel block  
 Ch Ch channel change  
 Chk check  
 Chsld chiseled  
 Cir circle  
 Cl class  
 Cl clay  
 Cl F clay fill  
 Cl Hvy clay heavy  
 Cl Lm clay loam  
 Clnt clean-out  
 Clr clear  
 Cl&gr clearing & grubbing  
 Co S coal slack  
 Comb. combination  
 Coml commercial  
 Compr compression  
 CADD computer aided drafting & design  
 Conc concrete  
 Cond conductor  
 Const construction  
 Cont continuous  
 CSB continuous split barrel sample  
 Contr contraction  
 Contr contractor  
 CP control point  
 Coord coordinate  
 Cor corner  
 Corr corrected  
 CAES corrugated aluminum end section  
 CAP corrugated aluminum pipe  
 CMES corrugated metal end section  
 CMP corrugated metal pipe  
 CPVCP corrugated poly-vinyl chloride pipe  
 CSES corrugated steel end section  
 CSP corrugated steel pipe  
 C coulomb  
 Co County  
 Crse course  
 C Gr course gravel  
 CS course sand

Ct Court  
 Xarm cross arm  
 Xbuck cross buck  
 Xsec cross sections  
 Xing crossing  
 Xrd Crossroad  
 Crn crown  
 CF cubic feet  
 M3 cubic meter  
 M3/s cubic meters per second  
 CY cubic yard  
 Cy/mi cubic yards per mile  
 Culv culvert  
 C&G curb & gutter  
 CI curb inlet  
 CR curb ramp  
 CS curve to spiral  
 C cut  
 Dd Ld dead load  
 Defl deflection  
 Defm deformed  
 Deg or D degree  
 DInt delineate  
 DIntr delineator  
 Depr depression  
 Desc description  
 Det detail  
 DWP detectable warning panel  
 Dtr detour  
 Dia diameter  
 Dir direction  
 Dist distance  
 DM disturbed material  
 DB ditch block  
 DG ditch grade  
 Dbl double  
 Dn down  
 Dwg drawing  
 Dr drive  
 Drwy driveway  
 DI drop inlet  
 D dry density  
 Ea each  
 Esmt easement  
 E East  
 EB Eastbound  
 Elast elastomeric  
 EL electric locker  
 E Mtr electric meter  
 Elec electric/al  
 EDM electronic distance meter  
 Elev or El elevation  
 Ellipt elliptical  
 Emb embankment  
 Emuls emulsion/emulsified

ES end section  
 Engr engineer  
 ESS environmental sensor station  
 Eq equal  
 Eq equation  
 Evgr evergreen  
 Exc excavation  
 Exst existing  
 Exp expansion  
 Expy Expressway  
 E external of curve  
 Extru extruded  
 FOS factor of safety  
 F Fahrenheit  
 FS far side  
 F farad  
 Fed Federal  
 FP feed point  
 Ft feet/foot  
 Fn fence  
 Fn P fence post  
 FO fiber optic  
 FB field book  
 FD field drive  
 F fill  
 FAA fine aggregate angularity  
 FS fine sand  
 FH fire hydrant  
 Fl flange  
 Flrd flared  
 FES flared end section  
 F Bcn flashing beacon  
 FA flight auger sample  
 FL flow line  
 Ftg footing  
 FM force main  
 Fs foresight  
 Fnd found  
 Fdn foundation  
 Frac fractional  
 Frwy freeway  
 Frt front  
 FF front face  
 F Disp fuel dispenser

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 07/01/14 and the original document is stored at the North Dakota Department of Transportation

NDDOT ABBREVIATIONS

D-101-2

FFP	fuel filler pipes	IPn	Iron Pin	MC	medium curing	Ped	pedestal
FLS	fuel leak sensor	IP	iron Pipe	M	mega	Ped	pedestrian
Furn	furnish/ed	Jt	joint	Mer	meridian	PPP	pedestrian pushbutton post
Gal	gallon	J	joule	M	meter	Pen.	penetration
Galv	galvanized	Jct	junction	M/s	meters per second	Perf	perforated
Gar	garage	K	kelvin	M	mid ordinate of curve	Per.	perimeter
Gs L	gas line	Kn	kilo newton	Mi	mile	PL	pipeline
G Reg	gas line regulator	Kpa	kilo pascal	MM	mile marker	PI	place
GMV	gas main valve	Kg	kilogram	MP	mile post	P&P	plan & profile
G Mtr	gas meter	Kg/m3	kilogram per cubic meter	MI	milliliter	PL	plastic limit
GSV	gas service valve	Km	kilometer	Mm	millimeter	PI	plate
GVP	gas vent pipe	K	Kip(s)	Mm/hr	millimeters per hour	Pt	point
GV	gate valve	LS	Land Surveyor (licensed)	Min	minimum	PCC	point of compound curve
Ga	gauge	LSIT	Land Surveyor In Training	Misc	miscellaneous	PC	point of curve
Geod	geodetic	Ln	lane	Mon	monument	PI	point of intersection
GIS	Geographical Information System	Lg	large	Mnd	mound	PRC	point of reverse curvature
G	giga	Lat	latitude	Mtbl	mountable	PT	point of tangent
GPS	Global Positioning System	Lt	left	Mtd	mounted	POC	point on curve
Gov	government	L	length of curve	Mtg	mounting	POT	point on tangent
Grd	graded/grade	Lens	lenses	Mk	muck	PE	polyethylene
Gr	gravel	Lvl	level	Mun	municipal	PVC	polyvinyl chloride
Grnd	ground	LB	level book	N	nano	PCC	Portland Cement concrete
GWM	ground water monitor	Lvng	leveling	NGS	National Geodetic Survey	Lb or #	pounds
Gdrl	guardrail	Lht	light	NS	near side	PP	power pole
Gtr	gutter	LP	light pole	Neop	neoprene	Preempt	preemption
H Plg	H piling	Ltg	lighting	Ntwk	network	Prefab	prefabricated
Hdwl	headwall	Lig Co	lignite coal	N	newton	Prfmd	performed
Ha	hectare	Lig Sl	lignite slack	N	North	Prep	preparation
Ht	height	LF	linear foot	NE	North East	Press.	pressure
HI	height of instrument	Liq	liquid	NW	North West	PRV	pressure relief valve
Hel	helical	LL	liquid limit	NB	Northbound	Prestr	prestressed
H	henry	L	litre	No. or #	number	Pvt	private
HZ	hertz	Lm	loam	Obsc	obscure(d)	PD	private drive
HDPE	high density polyethylene	Loc	location	Obsn	observation	Prod.	production/produce
HM	high mast	LC	long chord	Ocpd	occupied	Prog	programmed
HP	high pressure	Long.	longitude	Ocpy	occupy	Prop.	property
HPS	high pressure sodium	Lp	loop	Off Loc	office location	Prop Ln	property line
Hwy	highway	LD	loop detector	O/s	offset	Ppsd	proposed
Hor	horizontal	Lm	lumen	OC	on center	PB	pull box
HBP	hot bituminous pavement	Lum	luminaire	C	one dimensional consolidation		
HMA	hot mix asphalt	L Sum	lump sum	OC	organic content		
Hr	hour(s)	Lx	lux	Orig	original		
Hyd	hydrant	ML	main line	O To O	out to out		
Ph	hydrogen ion content	M Hr	man hour	OD	outside diameter		
Id	identification	MH	manhole	OH	overhead		
In or "	inch	Mkd	marked	PMT	pad mounted transformer		
Incl	inclinometer tube	Mkr	marker	Pg	pages		
IMH	inlet manhole	Mkg	marking	Pntd	painted		
ID	inside diameter	MA	mast arm	Pr	pair		
Inst	instrument	Matl	material	Pnl	panel		
Intchg	interchange	Max	maximum	Pk	park		
Intmdt	intermediate	MC	meander corner	PK	Parker-Kalon nail		
Intscn	intersection	Meas	measure	Pa	pascal		
Inv	invert	Mdn	median	PSD	passing sight distance		
IM	iron monument	MD	median drain	Pvmt	pavement		

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
08-03-15	General Revisions

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 08/03/15 and the original document is stored at the North Dakota Department of Transportation

NDDOT ABBREVIATIONS

D-101-3

Qty	quantity	SN	sign number	Tan	tangent	Wb	weber
Qtr	quarter	Sig	signal	T	tangent (semi)	WIM	weigh in motion
Rad or R	radius	Si Cl	silt clay	TS	tangent to spiral	W	west
RR	railroad	Si Cl Lm	silty clay loam	Tel	telephone	WB	westbound
Rlwy	railway	Si Lm	silty loam	Tel B	Telephone Booth	Wrng	wiring
Rsd	raised	Sgl	single	Tel P	telephone pole	W/	with
RTP	random traverse point	SC	slow curing	Tv	television	W/o	without
Rge or R	range	SS	slow setting	Temp	temperature	WC	witness corner
RC	rapid curing	Sm	small	Temp	temporary	WGS	world geodetic system
Rec	record	S	South	TBM	temporary bench mark	Z	zenith
Rcy	recycle	SE	South East	T	tesla		
RAP	recycled asphalt pavement	SW	South West	T	thinwall tube sample		
RPCC	recycled portland cement concrete	SB	Southbound	T/mi	tons per mile		
Ref	reference	Sp	spaces	Ts	topsoil		
R Mkr	reference marker	Spcl	special	Twp or T	township		
RM	reference monument	SA	special assembly	Traf	traffic		
Refl	reflectorized	SP	special provisions	TSCB	traffic signal control box		
RCB	reinforced concrete box	G	specific gravity	Tr	trail		
RCES	reinforced concrete end section	Spk	spike	Transf	transformer		
RCP	reinforced concrete pipe	SC	spiral to curve	TB	transit book		
RCPS	reinforced concrete pipe sewer	ST	spiral to tangent	Trans	transition		
Reinf	reinforcement	SB	split barrel sample	TT	transmission tower		
Res	reservation	SH	sprinkler head	Trans	transverse		
Ret	retaining	SV	sprinkler valve	Trav	traverse		
Rev	reverse	Sq	square	TP	traverse point		
Rt	right	SF	square feet	Trtd	treated		
R/W	right of way	Km2	square kilometer	Trmt	treatment		
Riv	river	M2	square meter	Qc	triaxial compression		
Rd	road	SY	square yard	TERO	tribal employment rights ordinance		
Rdbd	road bed	Stk	stake	Tpl	triple		
Rdwy	roadway	Std	standard	TP	turning point		
RWIS	roadway weather information system	N	standard penetration test	Typ	typical		
Rk	rock	Std Specs	standard specifications	Qu	unconfined compressive strength		
Rt	route	Sta	station	Ugrnd	underground		
Salv	salvage(d)	Sta Yd	station yards	USC&G	US Coast & Geodetic Survey		
Sd	sand	Stm L	steam line	USGS	US Geologic Survey		
Sdy Cl	sandy clay	SEC	steel encased concrete	Util	utility		
Sdy Cl Lm	sandy clay loam	SMA	stone matrix asphalt	VG	valley gutter		
Sdy Fl	sandy fill	SSD	stopping sight distance	Vap	vapor		
Sdy Lm	sandy loam	SD	storm drain	Vert	vertical		
San	sanitary sewer line	St	street	VC	vertical curve		
Sc	scoria	SPP	structural plate pipe	VCP	vitrified clay pipe		
Sec	seconds	SPPA	structural plate pipe arch	V	volt		
Sec	section	Str	structure	Vol	volume		
SL	section line	Subd	subdivision	Wkwy	walkway		
Sep	separation	Sub	subgrade	W	water content		
Seq	sequence	Sub Prep	subgrade preperation	WGV	water gate valve		
Serv	service	Ss	subsoil	WL	water line		
Sh	shale	SE	superelevation	WM	water main		
Sht	sheet	SS	supplement specification	WMV	water main valve		
Shtng	sheeting	Supp	supplemental	W Mtr	water meter		
Shldr	shoulder	Surf	surfacing	WSV	water service valve		
Sw	sidewalk	Surv	survey	WW	water well		
S	siemens	Sym	symmetrical	W	watt		
SD	sight distance	SI	systems international	Wrng	wearing		

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
08-03-15	General Revisions

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 08/03/15 and the original document is stored at the North Dakota Department of Transportation

NDDOT UTILITY COMPANY AND ORGANIZATION ABBREVIATIONS

D-101-10

702COM 702 Communications  
 ACCENT Accent Communications  
 AGASSIZ WU Agassiz Water Users Incorporated  
 AGC Associated General Contractors of America  
 AII PI Alliance Pipeline  
 ALL SEAS WU All Seasons Water Users Association  
 AMOCO PI Amoco Pipeline Company  
 AMRDA HESS Amerada Hess Corporation  
 AT&T AT&T Corporation  
 B PAW Bear Paw Energy Incorporated  
 BAKER ELEC Baker Electric  
 BASIN ELEC Basin Electric Cooperative Incorporated  
 BEK TEL Bek Communications Cooperative  
 BELLE PL Belle Fourche Pipeline Company  
 BLM Bureau of Land Management  
 BNSF Burlington Northern Santa Fe Railway  
 BOEING Boeing  
 BRNS RWD Barnes Rural Water District  
 BURK-DIV ELEC Burke-Divide Electric Cooperative  
 BURL WU Burleigh Water Users  
 Cable One Cable One  
 CABLE SERV Cable Services  
 CAP ELEC Capital Electric Cooperative Incorporat  
 CASS CO ELEC Cass County Electric Cooperative  
 CASS RWU Cass Rural Water Users Incorporated  
 CAV ELEC Cavalier Rural Electric Cooperative  
 CBLCOM Cablecom Of Fargo  
 CENEX PL Cenex Pipeline  
 CENT PL WATER DIST Central Pipe Line Water District  
 CENT PWR ELEC Central Power Electric Cooperative  
 COE Corps of Engineers  
 CONS TEL Consolidated Telephone  
 CONT RES Continental Resource Inc  
 CPR Canadian Pacific Railway  
 D O E Department Of Energy  
 DAK CARR Dakota Carrier Network  
 DAK CENT TEL Dakota Central Telephone  
 DAK RWD Dakota Rural Water District  
 DGC Dakota Gasification Company  
 DICKEY R NET Dickey Rural Networks  
 DICKEY RWU Dickey Rural Water Users Association  
 DICKEY TEL Dickey Telephone  
 DNRR Dakota Northern Railroad  
 DOME PL Dome Pipeline Company  
 DVELEC Dakota Valley Electric Cooperative  
 DVMW Dakota, Missouri Valley & Western  
 ENBRDG Enbridge Pipelines Incorporated  
 ENVENTIS Enventis Telephone  
 FALK MNG Falkirk Mining Company  
 FHWA Federal Highway Administration  
 G FKS-TRL WD Grand Forks-trail Water District  
 GETTY TRD & TRAN Getty Trading & Transportation  
 GLDN W ELEC Golden West Electric Cooperative  
 GRGS CO TEL Griggs County Telephone

GT PLNS NAT GAS Great Plains Natural Gas Company  
 HALS TEL Halstad Telephone Company  
 IDEA1 Idea1  
 INT-COMM TEL Inter-Community Telephone Company  
 KANEB PL Kaneb Pipeline Company  
 KEM ELEC Kem Electric Cooperative Incorporated  
 KOCH GATH SYS Koch Gathering Systems Incorporated  
 LKHD PL Lakehead Pipeline Company  
 LNGDN RWU Langdon Rural Water Users Incorporated  
 LWR YELL R ELEC Lower Yellowstone Rural Electric  
 MCKNZ CON McKenzie Consolidated Telcom  
 MCKENZIE ELEC McKenzie Electric Cooperative  
 MCKNZ WRD McKenzie County Water Resource District  
 MCLEOD McLeod USA  
 MCLN ELEC McLean Electric Cooperative  
 MCLN-SHRDN R WAT McLean-Sheridan Rural Water  
 MDU Montana-dakota Utilities  
 MID-CONT CABLE Mid-Continent Cable  
 MIDSTATE TEL Midstate Telephone Company  
 MINOT CABLE Minot Cable Television  
 MINOT TEL Minot Telephone Company  
 MISS W W S Missouri West Water System  
 MNKOTA PWR Minnkota Power  
 MOR-GRAN-SOU ELEC Mor-gran-sou Electric Cooperative  
 MOUNT-WILLI ELEC Mountrail-williams Electric Cooperative  
 MRE LBTY TEL Moore & Liberty Telephone  
 MUNICIPAL City Water And Sewer  
 MUNICIPAL City Of '.....'  
 N CENT ELEC North Central Electric Cooperative  
 N VALL W DIST North Valley Water District  
 ND PKS & REC North Dakota Parks And Recreation  
 ND TEL North Dakota Telephone Company  
 NDDOT North Dakota Department of Transportation  
 NDSU SOIL SCI DEPT NDSU Soil Science Department  
 NEMONT TEL Nemont Telephone  
 NODAK R ELEC Nodak Rural Electric Cooperative  
 NOON FRMS TEL Noonan Farmers Telephone Company  
 NPR Northern Plains Railroad  
 NSP Northern States Power  
 NTH PRAIR RW Northern Prairie Rural Water Association  
 NTHN BRDR PL Northern Border Pipeline  
 NTHN PLNS ELEC Northern Plains Electric Cooperative Incorporated  
 NTHWSTRN REF Northwestern Refinery Company  
 NW COMM Northwest Communication Cooperation  
 ONEOK Oneok gas  
 OSHA Occupational Safety and Health Administration  
 OTTR TL PWR Otter Tail Power Company  
 P L E M Prairielands Energy Marketing  
 POLAR COM Polar Communications  
 PVT ELEC Private Electric  
 QWEST Qwest Communications  
 R&T W SUPPLY R & T Water Supply Association  
 RAMSEY R SEW Ramsey Rural Sewer Association  
 RAMSEY RW Ramsey Rural Water Association  
 RAMSEY UTIL Ramsey County Rural Utilities

RED RIV TEL Red River Rural Telephone  
 RESVTN TEL Reservation Telephone  
 ROBRTS TEL Roberts Company Telephone  
 R-RIDER ELEC Roughrider Electric Coop  
 RRVW Red River Valley & Western Railroad  
 RSR ELEC R.S.R. Electric Cooperative  
 S E W U South East Water Users Incorporated  
 SCOTT CABLE Scott Cable Television Dickinson  
 SHERDN ELEC Sheridan Electric Cooperative  
 SHEYN VLY ELEC Sheyenne Valley Electric Cooperative  
 SKYTECH Skyland Technologies Incorporated  
 SLOPE ELEC Slope Electric Cooperative Incorporated  
 SOURIS RIV TELCOM Souris River Telecommunications  
 ST WAT COMM State Water Commission  
 STATE LN WATER State Line Water Cooperative  
 STER ENG Sterling Energy  
 STUT RWU Stutsman Rural Water Users  
 SW PL PRJ Southwest Pipeline Project  
 T M C Turtle Mountain Communications  
 TCI TCI of North Dakota  
 TESORO GHG PLNS PL Tesoro High Plains Pipeline  
 TRI-CNTY WU Tri-County Water Users Incorporated  
 TRL CO RWU Traill County Rural Water Users  
 UNTD TEL United Telephone  
 UPPR SOUR WUA Upper Souris Water Users Association  
 US SPRINT U.S. Sprint  
 USAF MSL CABLE U.S.A.F. Missile Cable  
 USFWS US Fish and Wildlife Service  
 USW COMM U.S. West Communications  
 VRNDRY ELEC Verendrye Electric Cooperative  
 W RIV TEL West River Telephone Incorporated  
 WEB W. E. B. Water Development Association  
 WILLI RWA Williams Rural Water Association  
 WILSTN BAS PL Williston Basin Interstate Pipeline Company  
 WLSH RWD Walsh Water Rural Water District  
 WOLVRTN TEL Wolverton Telephone  
 XLENER Xcel Energy  
 YSVR Yellowstone Valley Railroad

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 07/01/14 and the original document is stored at the North Dakota Department of Transportation





Line Styles

.....	Limits of Const Transition Line	—— s —— s ——	Floating Silt Curtain	—— ——— ———	Existing Aggregate (Cross Section View)	- - - - -	Existing Centerline
.....	Bale Check	—— ——— T ——	Existing Telephone Line	—— ——— ———	Existing Curb and Gutter (Cross Section View)	- - - - -	Supplemental Contour
.....	Rock Check	—— ——— TV ——	Existing TV Line	—— ——— ———	Existing Riprap	—— - - - - -	Right of Way
.....	Sight Distance Triangle Line	Void — void — void — v	Existing Assumed Ground (Not Surveyed)	—— ——— ———	Existing Underground Vault or Lift Station	—— - - - - -	Existing Right of Way
- - - - -	Small Hidden Object	Void — void — void — v	Tentative Ground Line	—— ——— ———	Tangent Line	—— - - - - -	Existing Right of Way Railroad
- - - - -	Dimension Leader	—— ——— w ——	Existing Water or Steam Line	- - - - -	Hidden Object	- - - - -	Failure Line
- - - - -	Existing Ground	=====	Existing Under Drain	—— - - - - -	Existing Dirt Surface	- - - - -	Existing Conditions
- - - - -	Existing Topsoil (Cross Section View)	=====	Under Drain	—— ——— ———	Existing Conduit	- - - - -	Existing Ground (Details)
—— ——— ———	Large Hidden Object	=====	Wall	—— ——— ———	Topsoil Profile	—— - - - - -	Existing Sixteenth Section Line
—— ——— ———	Edge Drain	=====	Existing Slotted Drain	- - - - -	Existing Conductor	- - - - -	Existing Right of Way Not State Owned
—— D —— D ——	Geotextile Fabric Type D	—— + —— + ——	Existing Cemetary Boundary	- - - - -	Conductor	- - - - -	Phantom Object
—— ——— E ——	Existing Electrical	—— ——— ———	Centerline Pavement Marking	- - - - -	Fiber Optic	- - - - -	Centerline Main
—— ——— FO ——	Existing Fiber Optic Line	=====	Barrier with Centerline Pavement Marking	- - - - -	Existing Loop Detector	- . . . .	Existing Guardrail Cable
—— ——— FO ——	Existing TV Fiber Optic	=====	Barrier Pavement Marking	- - - - -	Subgrade, Subcut or Ditch Grade	— • — • — • — •	Existing Guardrail Metal
—— ——— G ——	Existing Gas Pipe	- - - - -	Stripe 4 IN Dotted Extension White	—— ——— ———	Existing Asphalt Surface	—— . ——— . ——— . ——— .	Existing Edge of Water
—— <b>Geo</b> —— <b>Geo</b> ——	Geogrid	- - - - -	Stripe 8 IN Dotted Extension White	—— ——— ———	Existing Asphalt (Cross Section View)	- - - - -	Excavation Limits
—— ——— OH ——	Existing Overhead Utility Line	- - - - -	Stripe 8 IN Lane Drop	—— ——— ———	Existing Reinforcement Rebar	—— . . . . ——— . . . . ——— . . . .	Existing Government Lot Line
—— ——— P ——	Existing Power	—— ——— ———	Wetland Mitigation	—— ——— ———	Existing Tie Point Line	.....	Existing Adjacent Block Lines
—— ——— PL ——	Existing Fuel Pipeline	- - - - -	Existing Box Culvert Bridge	—— ——— ———	Existing State or International Line	.....	Existing Adjacent Lot Lines
—— ——— <b>PL</b> ——	Existing Undefined Above Ground Pipe Line	- - - - -	Existing Concrete Surface	—— ——— ———	Existing Quarter Section Line	.....	Existing Adjacent Property Line
—— ——— R —— R ——	Geotextile Fabric Type R	- - - - -	Existing Drainage Structure	—— ——— ———	Existing County	.....	Existing Adjacent Subdivision Lines
—— ——— R —— R ——	Geotextile Fabric Type R1	- - - - -	Easement	—— ——— ———	Existing Section Line	.....	
—— REMOVE —— REMOVE ——	Remove Line	- - - - -	Existing Concrete	—— ——— ———	Existing Township	.....	
—— RR —— RR ——	Geotextile Fabric Type RR	- - - - -	Existing Easement	—— ——— ———	Existing Railroad Centerline	.....	
—— S —— S ——	Geotextile Fabric Type S	—— ——— ———	Existing Gravel Surface	—— ——— ———	Centerline	.....	

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 07/01/14 and the original document is stored at the North Dakota Department of Transportation

Line Styles

	Subgrade Reinforcement		Existing Railroad Switch		Sheet Piling
	Existing Down Guy Wire Down Guy		Overhead Sign Structure Cantilever		W-Beam w Posts
	Existing Fence		24 Inch Pipe		Existing W-Beam Guardrail with Posts
	Existing Railroad		Reinforced Concrete Pipe		Exst Wet Area-Vegetation Break
	Existing Sanitary Sewer		Signal Head with Mast Arm		Existing Wetland Delineated
	Existing Sanitary Force Main		Existing Signal Head with Mast Arm		
	Existing Storm Drain		Tie Bar at Random Spacing		
	Existing Storm Drain Force Main		3-Cable w Posts		
	Fence		Existing 3-Cable w Posts		
	Silt Fence		Site Boundary		
	Existing Field Line		Fiber Rolls		
	Exst Flow		Doweled Joint		
	Flow		Tie Bar 30 Inch 4 Foot Center to Center		
	Existing Culvert		Tie Bar 18 Inch 3 Foot Center to Center		
	Existing Curb		Existing Berm, Dike, Pit, or Earth Dam		
	Existing Valley Gutter		Existing Ditch Block		
	Existing Driveway Gutter		Depression Contours		
	Existing Curb and Gutter		Existing City Corporate Limits or Reservation Boundary		
	Existing Mountable Curb and Gutter		Gravel Pit - Borrow Area		
	Existing Double Micro Loop Detector		Existing Tree Boundary		
	Micro Loop Detector Double		Tree Row		
	Existing Overhead Sign Structure		Existing Brush or Shrub Boundary		
	Existing Micro Loop Detector		Existing Retaining Wall		
	Micro Loop Detector		Existing Planter or Wall		
	Existing Overhead Sign Structure Cantilever		Retaining Wall (Plan View)		

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 07/01/14 and the original document is stored at the North Dakota Department of Transportation

Symbols

	North Arrow (Half Scale)		Attenuation Device		Existing Railroad Battery Box		Existing Delineator Type E
	Truck Mounted Attenuator		Diamond Grade Delineator Type A		Existing Bush or Shrub		Existing EFB Misc
	Type I Barricade		Diamond Grade Delineator Type B		Existing Gas Cap or Stub		Existing Flashing Beacon
	Type II Barricade		Diamond Grade Delineator Type C		Existing Sanitary Cap or Stub		Existing Pipe Mounted Flasher
	Type III Barricade		Diamond Grade Delineator Type D		Existing Storm Drain Cap or Stub		Existing Pad Mounted Feed Point
	Catch Basin		Diamond Grade Delineator Type E		Existing Water Cap or Stub		Existing Pipe Mounted Feed Point with Pad
	Cairn or Stone Circle		Flexible Delineator		Existing Sanitary Cleanout		Existing Pole Mounted Feed Point
	Video Detection Camera		Flexible Delineator Type A		Existing Concrete Foundation		Existing Railroad Frog
	Storm Drain Cap or Stub		Flexible Delineator Type B		Existing Traffic Signal Controller		Existing Snow Gate 18
	Corrugated Metal End Section 18 Inch		Flexible Delineator Type C		Existing Pad Mounted Signal Controller		Existing Snow Gate 28
	Corrugated Metal End Section 24 Inch		Flexible Delineator Type D		Existing Sixteenth Section Corner		Existing Snow Gate 40
	Corrugated Metal End Section 30 Inch		Flexible Delineator Type E		Existing Quarter Section Corner		Existing Headwall
	Corrugated Metal End Section 36 Inch		Delineator Type A		Existing Section Corner		Existing Pedestrian Head with Number
	Corrugated Metal End Section 42 Inch		Delineator Type A Reset		Existing Railroad Crossbuck		Existing Signal Head
	Corrugated Metal End Section 48 Inch		Delineator Type B		Existing Satellite Dish		Existing Sprinkler Head
	Concrete Foundation		Delineator Type B Reset		Existing Fuel Dispensers		Existing Fire Hydrant
	Ground Connection Conductor		Delineator Type C		Existing Flexible Delineator Type A		Existing Catch Basin Drop Inlet
	Neutral Connection Conductor		Delineator Type D		Existing Flexible Delineator Type B		Existing Curb Inlet
	Phase 1 Connection Conductor		Delineator Type E		Existing Flexible Delineator Type C		Existing Manhole Inlet
	Phase 2 Connection Conductor		Delineator Drums		Existing Flexible Delineator Type D		Existing Junction Box
	Traffic Cone		Spot Elevation		Existing Flexible Delineator Type E		
	Signal Controller		Existing Access Control Arrow		Existing Delineator Type A		
	Pad Mounted Signal Controller		Existing Artifact		Existing Delineator Type B		
	Alignment Data Point		Existing Flashing Beacon		Existing Delineator Type C		
	Emergency Vehicle Detector		Existing Benchmark		Existing Delineator Type D		

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 07/01/14 and the original document is stored at the North Dakota Department of Transportation

Symbols

	Existing Light Standard		Existing Manhole with Valve Water		Existing Telephone Pole		Existing Undefined Manhole
	Existing High Mast Light Standard 10 Luminaire		Existing Water Manhole		Existing Wood Pole		Existing Undefined Pull Box
	Existing High Mast Light Standard 3 Luminaire		Existing Mile Post Type A		Existing Post		Existing Undefined Pedestal
	Existing High Mast Light Standard 4 Luminaire		Existing Mile Post Type B		Existing Pedestrian Push Button Post		Existing Undefined Valve
	Existing High Mast Light Standard 5 Luminaire		Existing Mile Post Type C		Existing Control Point CP		Existing Undefined Pipe Vent
	Existing High Mast Light Standard 6 Luminaire		Existing Reference Marker		Existing Control Point GPS-RTK		Existing Gas Valve
	Existing High Mast Light Standard 7 Luminaire		Existing RW Marker		Existing Control Point TRI		Existing Water Valve
	Existing High Mast Light Standard 8 Luminaire		Existing Utility Marker		Existing Reference Marker Point NGS		Existing Fuel Pipe Vent
	Existing High Mast Light Standard 9 Luminaire		Iron Monument Found		Existing Pull Box		Existing Gas Pipe Vent
	Existing Overhead Sign Structure Load Center		Iron Pin R/W Monument		Existing Intelligent Transportation Pull Box		Existing Sanitary Pipe Vent
	Existing Luminaire		Existing Object Marker Type I		Existing Water Pump		Existing Storm Drain Pipe Vent
	Existing Light Standard Luminaire		Existing Object Marker Type II		Existing Slotted Reinforced Concrete Pipe		Existing Water Pipe Vent
	Existing Federal Mailbox		Existing Object Marker Type III		Existing RR Profile Spot		Existing Weather Station
	Existing Private Mailbox		Existing Electrical Pedestal		Existing Fuel Leak Sensors		Existing Ground Water Well Bore Hole
	Existing Meander Section Corner		Existing Telephone Pedestal		Existing Highway Sign		Existing Windmill or Tower
	Existing Meter		Existing Fiber Optic Telephone Pedestal		Existing Miscellaneous Spot		Existing Witness Corner
	Existing Electrical Manhole		Existing TV Pedestal		Existing Lighting Standard Pole		Flashing Beacon
	Existing Gas Manhole		Existing Fiber Optic TV Pedestal		Existing Traffic Signal Standard		Flagger
	Existing Sanitary Manhole		Existing Fuel Filler Pipes		Existing Transformer		Pipe Mounted Flasher
	Existing Sanitary Force Main Manhole		Existing Traverse PI Aerial Panel		Existing Large Evergreen Tree		Sanitary Force Main with Valve
	Existing Sanitary Manhole with Valve		Existing Pole		Existing Small Evergreen Tree		
	Existing Storm Drain Manhole		Existing Power Pole		Existing Large Tree		
	Existing Force Main Storm Drain Manhole		Existing Power Pole with Transformer		Existing Small Tree		
	Existing Force Main Storm Drain Manhole with Valve				Existing Tree Trunk		
	Existing Telephone Manhole				Existing Pad Mounted Traffic Signal Control Box		

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 07/01/14 and the original document is stored at the North Dakota Department of Transportation


# Symbols

D-101-32

 Pad Mounted Feed Point  Pipe Mounted Feed Point with Pad  Pole Mounted Feed Point  Headwall  Double Headwall with Vegetation Barrier  Single Headwall with Vegetation Barrier  Pole Mounted Head  Sprinkler Head  Fire Hydrant  Inlet Type 1  Inlet Type 2  Double Inlet Type 2  Inlet Gate Type 2  Junction Box  High Mast Light Standard 10 Luminaire  High Mast Light Standard 3 Luminaire  High Mast Light Standard 4 Luminaire  High Mast Light Standard 5 Luminaire  High Mast Light Standard 6 Luminaire  High Mast Light Standard 7 Luminaire  High Mast Light Standard 8 Luminaire  High Mast Light Standard 9 Luminaire  Relocate Light Standard  Overhead Sign Structure Load Center  Light Standard 100 Watt High Pressure Sodium Vapor Luminaire	 Light Standard 1000 Watt High Pressure Sodium Vapor Luminaire  Light Standard 150 Watt High Pressure Sodium Vapor Luminaire  Light Standard 175 Watt High Pressure Sodium Vapor Luminaire  Light Standard 200 Watt High Pressure Sodium Vapor Luminaire  Light Standard 250 Watt High Pressure Sodium Vapor Luminaire  Light Standard 310 Watt High Pressure Sodium Vapor Luminaire  Light Standard 35 Watt High Pressure Sodium Vapor Luminaire  Light Standard 400 Watt High Pressure Sodium Vapor Luminaire  Light Standard 50 Watt High Pressure Sodium Vapor Luminaire  Light Standard 70 Watt High Pressure Sodium Vapor Luminaire  Light Standard 700 Watt High Pressure Sodium Vapor Luminaire  Manhole  Manhole 48 Inch  Sanitary Force Main Manhole  Sanitary Sewer Manhole  Storm Drain Manhole  Storm Drain Manhole with Inlet  Reset Mile Post  Mile Post Type A  Mile Post Type B  Mile Post Type C  Right of Way Marker  Tubular Marker  Alignment Monument  Iron Pin Reference Monument	 Object Marker Type I  Object Marker Type II  Object Marker Type III  Caution Mode Arrow Panel  Back to Back Vertical Panel Sign  Double Direction Arrow Panel  Left Directional Arrow Panel  Right Directional Arrow Panel  Sequencing Arrow Panel  Truck Mounted Arrow Panel  Power Pole  Wood Pole  Pedestrian Push Button Post  Property Corner  Pull Box  Intelligent Transportation Pull Box  Sanitary Pump  Storm Drain Pump  Reinforced Pavement  Reinforced Concrete End Section 15 Inch  Reinforced Concrete End Section 18 Inch  Reinforced Concrete End Section 24 Inch  Reinforced Concrete End Section 30 Inch  Reinforced Concrete End Section 36 Inch  Reinforced Concrete End Section 42 Inch	 Reinforced Concrete End Section 48 Inch  Reinforced Concrete End Section 54 Inch  Reset Right of Way Marker  Reset USGS Marker  Right of Way Markers  Riser 30 Inch  Continuous Split Barrel Sample  Flight Auger Sample  Split Barrel Sample  Thinwall Tube Sample  Highway Sign  SNOW GATE 18 FT  SNOW GATE 28 FT  SNOW GATE 40 FT  Standard Penetration Test  Transformer  Inclinometer Tube  Underdrain Cleanout  Excavation Unit  Water Valve
---	--	---	--


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by  
**Roger Weigel,**  
 Registration Number  
**PE-2930,**  
 on 07/01/14 and the original document is stored at the  
 North Dakota Department  
 of Transportation




Multi-Directional Slip Base Assembly

Perforated Tube



Top Post Receiver  
Plate - ASTM A572 grade 50  
Angle Receiver - 2 1/2"x2 1/2"x3/8" ASTM A36 structural angle



Bottom Soil Stub  
Tube - 3"x3"x7 gauge ASTM A500 grade B tube  
Stabilizing Wing - 7 gauge H.R.P.O. ASTM A1011  
Plate - ASTM A572 grade 50


Notes:

1. Slip base bolts shall be torqued as specified by the manufacturer.
2. Anchor shall have a yield strength of 43.9 KSI and tensile strength of 59.3 KSI.
3. The 4" vertical clearance is required for the anchor or breakaway base. The 4"x60" measurement shall be made above and below post location and also back and ahead of the post.
4. When used in concrete sidewalk, anchor shall be same except without the wings.
5. Four post signs shall have over 7' between the first and the fourth posts.


Telescoping Perforated Tube						
Number of Posts	Post Size in.	Wall Thickness Gauge	Sleeve Size in.	Wall Thickness Gauge	Slip Base	Anchor Size without Slip Base in.
1	2	12			No	2 1/4
1	2 1/4	12			No	2 1/2
1	2 1/2	12			(A)	3
1	2 1/2	10			Yes	
1	2 1/4	12	2	12	Yes	
1	2 1/2	12	2 1/4	12	Yes	
2	2	12			No	2 1/4
2	2 1/4	12			No	2 1/2
2	2 1/2	12			Yes	
2	2 1/2	12			Yes	
2	2 1/4	10	2	12	Yes	
2	2 1/2	12	2 1/4	12	Yes	
3 & 4	2 1/2	12			Yes	
3 & 4	2 1/2	10			Yes	
3 & 4	2 1/2	12	2 1/4	12	Yes	
3 & 4	2 1/4	12	2	12	Yes	
3 & 4	2 1/2	10	2 3/16	10	Yes	

Properties of Telescoping Perforated Tube						
Tube Size in.	Wall Thickness in.	U.S. Standard Gauge	Weight per Foot lbs.	Moment of Inertia in. <sup>4</sup>	Cross Sec. Area in. <sup>2</sup>	Section Modulus in. <sup>3</sup>
1 1/2 x 1 1/2	0.105	12	1.702	0.129	0.380	0.172
2 x 2	0.105	12	2.416	0.372	0.590	0.372
2 1/4 x 2 1/4	0.105	12	2.773	0.561	0.695	0.499
2 3/16 x 2 3/16	0.135	10	3.432	0.605	0.841	0.590
2 1/2 x 2 1/2	0.105	12	3.141	0.804	0.803	0.643
2 1/2 x 2 1/2	0.135	10	4.006	0.979	1.010	0.785


Top Post Receiver Data Table						
Square Post Sizes (B)	A	B	C	D	E	F
2 3/16"x10 ga.	1 9/64"	2 1/2"	3 1/32"	2 5/32"	1 33/64"	1 1/8"
2 1/2"x10 ga.	1 9/32"	2 1/2"	3 5/16"	5/8"	1 21/32"	1 3/4"



Anchor Unit and Post Assembly




Multi-Directional Slip Base Anchor Unit and Post Sleeve Assembly



Bolt Retainer for Base Connection  
Bolt Retainer - 1/32" Reprocessed Teflon

- (A) The breakaway base is required when the support is placed in weak soils. The Engineer shall determine if the soils are weak.  
(B) The 2 3/16"x10 ga. may be inserted into 2 1/2"x10 ga. for additional wind load.





Anchor plate shall be a minimum 10 gauge (two post installation)

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
2-28-14	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 2/28/14 and the original document is stored at the North Dakota Department of Transportation

U-Channel Post




Breakaway U-Channel Detail Alternate A

A maximum of 2 posts shall be installed within 7'.




Retainer Strap Detail



Breakaway U-Channel Splice Detail Alternate B (2.5 and 3 lb/ft)

A maximum of 3 posts shall be installed within 7'.



Breakaway U-Channel Splice Detail Alternate C (2.5 and 3 lb/ft)

A maximum of 3 posts shall be installed within 7'.

Alternate A Steps of Installation:












1. a) Drive anchor unit to within 12" of ground level.  
b) Proper assembly established by lining up the bottom hole of retainer strap with the 6th hole from the top of the anchor unit.  
c) Assemble strap to back of anchor unit using 5/16"x2" bolt, lock washer and nut.  
d) Rotate strap 90° to left.
2. a) Drive anchor unit to 4" above ground.  
b) Rotate strap to vertical position.
3. a) Place 5/16"x2" bolt, lock washer and nut in bottom of sign post to facilitate alignment of sign post with proper hole in anchor unit.  
b) Alternately tighten two connector bolts.
4. Complete assembly by tightening 5/16"x2" bolt (this fastens sign post to retainer strap).
5. The base post, strap and sign post shall be properly nested. Proper nesting occurs when all flat surfaces of the base post, strap, and sign post at the bolts have full contact across the entire width.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
2-28-14	
REVISIONS	
DATE	CHANGE



This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 2/28/14 and the original document is stored at the North Dakota Department of Transportation

CONSTRUCTION SIGN DETAILS  
 TERMINAL AND GUIDE SIGNS

D-704-9



ARROW DETAILS



NOTES:


(A) Arrow may be right or left of the legend to indicate construction to the right or left.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-13-13	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 8/13/13 and the original document is stored at the North Dakota Department of Transportation

CONSTRUCTION SIGN DETAILS  
REGULATORY SIGNS


D-704-10




R1-50-24  
Legend: black (non-refl)  
Background: white



R11-3c-60  
Legend: black (non-refl)  
Background: white



R2-1a-24  
Legend: black (non-refl)  
Background: white



R11-4a-60  
Legend: black (non-refl)  
Background: white



R11-2a-48  
Legend: black (non-refl)  
Background: white


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-13-13	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 8/13/13 and the original document is stored at the North Dakota Department of Transportation


CONSTRUCTION SIGN DETAILS  
WARNING SIGNS

WORD	LETTER SPACING
AHEAD	Standard
200 FT	Standard
350 FT	Standard
500 FT	Standard
1000 FT	Reduce 40%
1500 FT	Reduce 40%
½ MILE	Reduce 50%
1 MILE	Standard


\* DISTANCE MESSAGES




W5-8-48  
Legend: black (non-refl)  
Background: orange




W8-54-48  
Legend: black (non-refl)  
Background: orange




W20-51-48  
Legend: black (non-refl)  
Background: orange




W21-51-48  
Legend: black (non-refl)  
Background: orange




W5-9-48  
Legend: black (non-refl)  
Background: orange




W8-55-48  
Legend: black (non-refl)  
Background: orange




W20-52-54  
Legend: black (non-refl)  
Background: orange




W22-8-48  
Legend: black (non-refl)  
Background: orange




W5-9-48  
ARROW DETAILS



W8-53-48  
Legend: black (non-refl)  
Background: orange



W8-56-48  
Legend: black (non-refl)  
Background: orange




W21-50-48  
Legend: black (non-refl)  
Background: orange

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-13-13	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 8/13/13 and the original document is stored at the North Dakota Department of Transportation

# SHOULDER CLOSURE TAPERS



D-704-12



SHOULDER CLOSURE WITH LANE CLOSURE  
(when shoulder is 8' or wider)



SHOULDER CLOSURE USED WITH LANE CLOSURE  
(when shoulder is less than 8' wide)



PORTABLE TRAFFIC SIGNAL OR CHANGEABLE MESSAGE SIGN ON SHOULDER

KEY	
● Delineator Drum	∞ Sequencing Arrow Panel
• Message Display	↳ Portable Traffic Signal


Notes:

- S = Posted Speed Limit in mph  
W = Width of offset in feet  
L = Taper length in feet  
L = WS<sup>2</sup>/60 (40mph or less)  
L = WS (45mph or more)
- If a shoulder taper is used, it should have a length of approximately 1/3L. If a shoulder is used as a travel lane, a normal merging or shifting taper should be used.
- When paved shoulders of 8 foot width or more are closed, channelizing devices shall be used to close the shoulder in advance to delineate the beginning of the work space and direct vehicular traffic to remain within the traveled way.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-3-13	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel Registration Number PE-2930, on 10/3/13 and the original document is stored at the North Dakota Department of Transportation

BARRICADE AND CHANNELIZING DEVICE DETAILS




DELINEATOR DRUM

VERTICAL PANEL

The markings on drums shall be horizontal, circumferential, alternating orange and white retroreflective stripes 4" to 6" wide. Each drum shall have a minimum of two orange and two white stripes with the top stripe being orange. Any nonretroreflectORIZED spaces between the horizontal orange and white stripes shall not exceed 3" wide. Stripes shall not be placed on ribs or indentations in the drum. Drums shall have closed tops that will not allow collection of construction debris or other debris. Ballast shall not be placed on the top of a drum.

Markings for vertical panels shall be alternating orange and white retroreflective stripes, sloping downward in the direction vehicular traffic is to pass. Retroreflective sheeting shall be placed on both sides of panel and shall have a minimum of 270 square inches of retroreflective area facing vehicular traffic. Where the height of the retroreflective material on the vertical panel is 36 inches or more, a stripe width of 6 inches shall be used.




TRAFFIC CONE

TUBULAR MARKER

RetroreflectORIZATION of cones more than 36" in height shall be provided by alternating orange and white retroreflective stripes. Each cone shall have a minimum of two orange and two white stripes with the top stripe being orange. Any nonretroreflectORIZED space between the orange and white stripes shall not exceed 3" wide.


RetroreflectORIZATION of tubular markers more than 42" in height shall be provided by alternating four 4" to 6" wide orange and white stripes with the top stripe being orange.



FLEXIBLE DELINEATOR

INSTALLATION NOTES:


1. Drill installation holes to diameter and depth as required by manufacturer's specifications.
2. For removal, remove anchors and fill installation hole with an epoxy designed to bond to pavement surface.
3. In lieu of bolted down base, the contractor may use an 8" x 8" butyl pad or hot melt butyl. Butyl shall be removed as close as possible to pavement surface.



BARRICADE BLADE DETAIL

ELEVATION VIEW

BARRICADE ASSEMBLY DETAIL (Aluminum Barricade Rails)




ELEVATION VIEW


BARRICADE ASSEMBLY DETAIL (Wood or Plastic Rails)

SIDE VIEW

NOTE: Markings for barricades shall be alternating orange and white retroreflective stripes, sloping downward in the direction traffic is to pass. Retroreflective sheeting shall be placed on both sides of the rails and shall have a minimum of 270 square inches of visible retroreflective area facing vehicular traffic. When the barricade length is less than 36", the rail stripe width shall be 4".




TYPE I BARRICADE




TYPE II BARRICADE

BARRICADE RAIL DETAILS



TYPE III BARRICADE



REFLECTOR DETAIL

DELINEATORS

MINIMUM BALLAST (For each side of barricade support)

Without Sign	4 - 25 lb sandbags
With Sign	6 - 25 lb sandbags


Note: The number of sandbags are based on a wind speed of 55 MPH. The sandbags are assumed to be placed at or near the ends of the skids.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-3-13	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 10/3/13 and the original document is stored at the North Dakota Department of Transportation

CONSTRUCTION SIGN PUNCHING AND MOUNTING DETAILS


Note: Signs placed in sections with curb shall have a minimum horizontal clearance of 2' from the face of the curb to the near edge of the sign.




TYPICAL SECTION (48" x 48" diamond warning sign shown)




24" x 24" ROUTE MARKER ASSEMBLY




36" x 36" ROUTE MARKER ASSEMBLY




48" x 48" DIAMOND SIGN (with 30" x 30" secondary sign)




18" x 18" DIAMOND SIGN




48" x 48" DIAMOND SIGN (with 30" x 24" secondary sign)




108" x 48" SIGN




96" x 48" SIGN




72" x 36" SIGN




72" x 24" SIGN




60" x 24" SIGN




48" x 24" SIGN




R1-2-60 - YIELD SIGN




W14-3-64 - PENNANT SIGN




R1-1-48 - STOP SIGN (with R6-1-54 sign as required)




R1-1-48 - STOP SIGN (with R1-50-24 sign as required)




48" x 48" SIGN (with R6-1-54 sign as required)




48" x 48" SIGN (with R2-1a-24 sign as required)



24" x 36" SIGN



PORTABLE SIGN SUPPORT LOW-MOUNTING HEIGHT



PORTABLE SIGN SUPPORT HIGH-MOUNTING HEIGHT

NOTES:

- Sign Supports: Supports shall be galvanized or painted. Minimum post sizes are 2.5 lb/ft u-channel or 2" x 2" x 12 gauge steel perforated tube, except where noted. When installing signs on u-channel, the minimum post size for assemblies containing a secondary sign is 3.0 lb/ft. Post sizes are based on a wind speed of 55 MPH.  
Signs over 50 square feet should be installed on 2 1/2" x 2 1/2" perforated tube supports as a minimum.  
Guy wires shall not be attached to sign supports. Wind beams may be attached to u-posts behind the sign panels.
- Sign Panels: Provide sign panels made of 0.100" aluminum, 1/2" plywood, or other approved material, except where noted. All holes to be punched round for 3/8" bolts.
- Alternate Messages: The signs that have alternate messages may have these alternate messages placed on a reflectorized plate (without a border) and installed and removed as required. (i.e. "Left" and "Right" message on a lane closure sign)
- Route Marker Auxiliary Signs: Provide route marker auxiliary signs, such as the cardinal direction and directional arrows, with a background and legend that match the route marker they are used with:  
Interstate - white legend on blue background  
Interstate Business Loop - white legend on green background  
US and State - black legend on white background  
County - yellow legend on blue background
- Vertical Clearance: Install signs with a vertical clearance of 5'-0" (see TYPICAL SECTION.) In areas where parking or pedestrian movements are likely or the view of the sign may be obstructed, install signs with a vertical clearance of 7'-0" from the top of the curb or from the near edge of the driving lane in absence of a curb.  
The vertical clearance to secondary signs is 1'-0" less than the vertical clearance as stated above.  
Large signs having an area exceeding 50 square feet shall have a minimum clearance of 7'-0" from the ground at the post.
- Portable Signs: Provide portable signs that meet the vertical clearance as stated above. Use portable signs when it is necessary to place signs within the pavement surface.  
When portable signs are used for 5 days or less, low-mounting height (minimum 12" vertical clearance) sign supports may be used as long as the view of the sign is not obstructed. Time delays caused by unforeseen circumstances, such as equipment breakdown, rain, subgrade failures, etc., will not accrue towards the 5 day period. The R9-8 through R9-11a series, W1-5 through W1-8 series, M4-10, and E5-1 may be used for longer than 5 days.  
Signs mounted to the portable sign supports shown in the LOW-MOUNTING HEIGHT and HIGH-MOUNTING HEIGHT Details shall have a maximum surface area of 16 square feet.

MINIMUM BALLAST (For each side of sign support base)

Sign Panel Mounting Height (ft)	Number of 25 lb sandbags for 4' x 4' sign panel
1'	6
5'	8
7'	10


Note: The number of sandbags are based on a wind speed of 55 MPH. The sandbags are assumed to be placed at or near the ends of the skids.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-4-13	
REVISIONS	
DATE	CHANGE
11-14-13	Revised Note 6.

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 11/14/13 and the original document is stored at the North Dakota Department of Transportation

# SHOULDER CLOSURES AND BRIDGE PAINTING LAYOUTS


D-704-24



- Notes
- Variables  
S = Numerical value of speed limit or 85th percentile.  
W = The width of the taper.  
L = Minimum length of taper, or  $S \times W$  for freeways, expressways, and all other roads with speeds of 45 mph or greater, or  $W \times S^2 / 60$  for urban, residential, and other streets with speeds of 40 mph or less.
  - Delineator drums used for tapering traffic shall be spaced at dimension "S".  
Delineator drums or tubular markers used for tangents shall be spaced at 2 times "S".
  - Sequencing Arrow Panels  
Type A shall be used on roadways with slow moving traffic speeds and low volume (25 mph or less and 750 ADT or less).  
Type B shall be used on roadways with moderate traffic speeds and volumes (40 mph or less and 5000 ADT or less).  
Type C shall be used on roadways with high traffic speeds and volumes (over 40 mph or over 5000 ADT).
  - The speed limit shall be re-established. The exact speed limit shall be determined in the field, dependent on location and conditions.
  - The reduced speed limit shall be determined dependent on the in place speed limit before construction. The speed limit reduction should not exceed 10 mph below the existing speed limit, unless the design speed of the work zone feature has been reduced below the 10 mph. In this case, the speed limit reduction shall not exceed 30 MPH. Where speed limits are to be reduced more than 30 MPH, a second speed limit sign shall be installed with the desired speed reduction but shall not exceed 30 MPH. The second speed limit sign shall be placed at  $\frac{1}{2}B$ .
  - When warning signs are used in urban areas and the signs are not portable, flags shall be installed. The flags shall be 24 inches square, mounted perpendicular to the edges of the diamond sign, and at such a distance above the edge so that when the flag is limp it will not touch the sign. Rural areas will not require flags.
  - Existing speed limit signs within a reduced speed zone shall be covered.
  - The contractor has the option of using portable sign supports in lieu of post mounted signs in accordance with the NDDOT Standard Specifications.

Longitudinal Buffer Space	
Speed (mph)	Length Min (feet)
20	115
25	155
30	200
35	250
40	305
45	360
50	425
55	495
60	570
65	645
70	730
75	820


ADVANCE WARNING SIGN SPACING			
Road Type	Distance Between Signs Min. (ft)		
	A	B	C
Urban - Low Speed (30 mph or less)	150	150	150
Urban - Low Speed (over 30 to 40 mph)	280	280	280
Urban - High Speed (over 40 mph to 50 mph)	360	360	360
Rural - High Speed (over 50 mph to 65 mph)	720	720	720
Urban Expressway and Freeway (55 mph to 60 mph)	850	1350	2200
Rural Expressway and Freeway (70 mph to 75 mph)	1000	1500	2640
Interstate/4-Lane Divided (Maintenance and Surveying)	750	1000	1500



NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-27-13	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 09/27/13 and the original document is stored at the North Dakota Department of Transportation.

SIGN LAYOUT FOR ONE LANE CLOSURE  
INTERSTATE SYSTEM



KEY

	Type I barricade		Work area
	Type II barricade		Flagger
	Type III barricade		Sequencing arrow panel
	Sign		Tubular markers
	Delineator drum		



LEFT LANE CLOSED  
WORKERS IN WORK AREA

Longitudinal Buffer Space



Speed (mph)*	Length Min (feet)
20	115
25	155
30	200
35	250
40	305
45	360
50	425
55	495
60	570
65	645
70	730
75	820

\*Posted speed, off-peak 85th percentile speed prior to work starting, or the anticipated operating speed in mph.

- Notes:
1. Install advance signs for flagging when flaggers are flagging.
  2. Move the advanced flagger sign and the speed limit signs as the work area moves through the construction zone. When the work area is not visible from the flagger, move the flagger station so the work area is visible. Space the 40 mph speed limit sign at 1/2 A in advance of the flagger sign and move the 65 mph speed limit sign. Cover or remove the 40 mph speed limit and Minimum Fee \$80 signs and the 65 mph speed limit sign upon completion of the work day or when workers are not present.
  3. RAMPS: When the work area encompasses an entrance ramp, install a 40 mph speed limit sign on the ramp and cover any existing yield sign. Install new yield sign as necessary. Remove the ramp speed limit sign when the main line 40 mph speed zone is moved past the ramp.
  4. Variables:  
S= Numerical value of speed limit or 85th percentile  
W= The width of taper.  
L= Minimum length of taper, or SxW for freeways, expressways, and all other roads with speeds of 45 mph or greater, or WxSxS/60 for urban, residential, and other streets with speeds of 40 mph or less.
  5. Space delineator drums for tapering traffic at the dimension "S". Space tubular markers used for tangents at 2 times dimension "S".
  6. Place sequencing arrow panels at the beginning of the taper when possible. Where shoulder width does not provide sufficient room, move the panel closer to the work area and place on the roadway surface.  
Use Type C on roadways with high traffic speeds and volumes (over 40 mph or 5000 ADT or greater).
  7. Re-establish the speed limit. Determine the exact speed limit in the field, dependent on location and conditions.
  8. Cover existing speed limit signs within a reduced speed zone.
  9. Upon approval, the Engineer will measure obliterated or covered pavement marking as Obliteration of Pavement Marking.
  10. Install flags when warning signs are used in urban areas and the signs are not portable. Mount 24 inch square flags perpendicular to the edges of the diamond sign, and at such a distance above the edge that the flag does not touch the sign when limp. Rural areas will not require flags.
  11. Determine the reduced speed limit dependent on the in place speed limit before construction. Do not exceed a speed limit reduction of 10 mph below the existing speed limit, unless the design speed of the work zone feature has been reduced below the 10 mph. When speed limits are to be reduced more than 30 mph, install a second speed limit sign so no single speed reduction exceeds 30 mph. Place the second speed limit sign at 1/2 B.
  12. The contractor has the option of using portable sign supports in lieu of post mounted signs in accordance with NDDOT Standard Specifications.

ADVANCE WARNING SIGN SPACING

Road Type	Distance Between Signs Min. (ft)		
	A	B	C
Rural - High Speed (over 50 mph to 65 mph)	720	720	720
Urban Expressway and Freeway (55 mph to 60 mph)	850	1350	2200
Rural Expressway and Freeway (70 mph to 75 mph)	1000	1500	2640
Interstate/4-Lane Divided (Maintenance and Surveying)	750	1000	1500



RIGHT LANE CLOSED  
WORKERS IN WORK AREA

NORTH DAKOTA  
DEPARTMENT OF TRANSPORTATION  
9-7-2012


REVISIONS	
DATE	CHANGE
6/23/2014	Revised Note 12
3/15/2016	Removed Do Not Pass signs and updated notes

This document was originally issued and sealed by  
Roger Weigel,  
Registration Number  
PE-2930,  
on 3/15/16 and the original document is stored at the North Dakota Department of Transportation

SPEED LIMIT ENFORCED  
MINIMUM FEE \$80  
WHEN WORKERS PRESENT  
G20-55-96  
Post mounted  
Install this sign only when ramp volume is 1000 ADT or more

PORTABLE SIGN SUPPORT ASSEMBLY

D-704-50




Notes:

- ① The maximum weight of the assembly is 250 pounds.
- ② Use a 14" wheel and tire.
- ③ Automotive and equipment axle assemblies may not be used for trailer-mounted sign supports.
- ④ Other NCHRP 350 crash tested assemblies are acceptable.


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
11-23-10	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 11/23/10 and the original document is stored at the North Dakota Department of Transportation.

**CONCRETE FOUNDATIONS  
(TRAFFIC SIGNALS & HIGHWAY LIGHTING)**




PLAN



ELEVATION

**CONTROLLER CABINET FOUNDATION PAD MOUNT**

The Controller Cabinet Foundation shall be bid as Concrete Foundation - Traffic Signals.




PLAN


ELEVATION

**TRANSFORMER & FEED POINT CABINET FOUNDATION PAD MOUNT**

The Transformer & Feed Point Cabinet Foundation Pad Mount shall be bid as Concrete Foundation ~ Feed Point ~ Type A.




PLAN




ELEVATION

**WORKING AREA SLAB**

The Working Area Slab shall be installed where shown on the plans and shall not be bid separately but shall be included in the price bid for Concrete Foundation - Traffic Signals.




PLAN




ELEVATION

**FEED POINT CABINET FOUNDATION PAD MOUNT**


The Feed Point Cabinet Foundation Pad Mount shall be bid as Concrete Foundation ~ Feed Point ~ Type B.



ANCHOR BOLT DETAIL



PLAN



ELEVATION

**LIGHT & SIGNAL STANDARD FOUNDATION**

**NOTES:**

**LIGHT & SIGNAL STANDARD FOUNDATIONS:**  
See plans for conduit size, number of bends and correct position for each foundation. When conduit does not continue beyond the foundation, conduit with a 105° bend and bushings on both ends may be substituted for the 90° bends shown. See plans for correct size & location of foundations. The grade and exact location shall be established by the Engineer in the field. All reinforcing shall be Grade 60. Tie bars shall have a minimum of a 12" lap. Reinforcing may be omitted for Type I, II, V, VI & VII signal standard foundations if the anchor bolts extend to within 3" to 6" above the bottom of the foundation. A minimum of 6 anchor bolts shall be used for cantilevered structures.

**CONTROLLER CABINET FOUNDATION PAD MOUNT FOUNDATION:** See plans for the number of 90° bends per foundation and correct positioning. The foundation for Pad Mounted Controller Cabinet shall be of sufficient size so that there is a minimum of 3" of clearance from the outside edge of cabinet to the outside edge of the foundation on any side. The contractor shall ensure a water-tight seal between the controller cabinet and the foundation by caulking, except for V-groove.

**WORKING AREA SLAB:** The materials and preparation of this slab shall be as approved by the Engineer in the field.

**TRANSFORMER & FEED POINT CABINET FOUNDATION PAD MOUNTED:** The foundation shall have a wood float finish. All conduits shown shall be installed. Conduit that is not used at this time shall be plugged with an expandable plug.





**FEED POINT CABINET FOUNDATION PAD MOUNTED:** The foundation shall have a wood float finish. All conduits shown shall be installed. Conduit that is not used at this time shall be plugged with an expandable plug.

LIGHT & SIGNAL FOUNDATION TABLE	
FOOTING DEPTH (ft)	LONGITUDINAL REINFORCING
≤ 12	8 - #5
13 - 14	8 - #6
15 - 16	8 - #7
17 - 19	8 - #8

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
6-15-10	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Terrence R. Udland Registration Number PE-2674, on 6/15/10 and the original document is stored at the North Dakota Department of Transportation

FEED POINTS  
(ROADWAY LIGHTING)




Type I feed point is similar to Type IV except only one electrical circuit, one 50 Amp - 2 pole breakers and one lighting relay, normally open, shall be installed.

Type II feed point is similar to Type IV except only two electrical circuit, two 50 Amp - 2 pole breakers and two lighting relays, normally open, shall be installed.



Type III feed point is similar to Type IV except only three electrical circuits, three 50 Amp - 2 pole breakers and three lighting relays, normally open, shall be installed.

(A) Install when festoon circuit is required.




Notes:

1. Photo Cell: The electrical contractor shall furnish and install the photoelectric cell. The photo lens shall face north.
2. Meter Socket: The contractor shall install the meter socket and trim if the meter is required by local Utility Company. Meter to be furnished and installed by Utility Company.
3. Pole Mounted Cabinet: Cabinet shall have lock drip shield, factory installed steel backing, stainless steel hardware, and side hinge door. Cabinet shall be shop coated with one coat of primer and have two coats of exterior gray enamel.  
Type I and II feed point shall be 30" high x 24" wide x 8" deep, Type III and IV feed point shall be 30" high x 42" wide x 10" deep or 36" high x 36" wide x 10" deep.
4. Wood Pole: Minimum 20' Class VII full length penta pressure treated wood pole. (if required, see layout sheets)
5. Pad Mounted Cabinet: Cabinet shall be 56" high x 26" wide x 14" deep. Minimum 12 gauge steel or aluminum with provisions for padlock. Cabinet shall be weatherproof. A steel cabinet shall have one coat of primer and two coats of exterior dark green enamel.
6. Grounding Grid: The grounding grid shall have a ground resistance not to exceed 25 ohms. This shall be obtained by one or more 3/8"x10' copperweld ground rods in parallel or series at two corners. Minimum distance between ground unit assemblies shall be 6'0".
7. Meter Location: The meter (if required) shall not be mounted on the same side of the cabinet as the photo cell.



Conduit Standoff Bracket

The conduit standoff brackets may be omitted if not required by the local utility company.




Use this detail if there is a continuous run of conduit from the feed point to the first light standard.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-8-13	
REVISIONS	
DATE	CHANGE
7-8-14	Revised note 3


This document was originally issued and sealed by  
Roger Weigel,  
Registration Number  
PE-2930,  
on 07/08/14 and the original document is stored at the  
North Dakota Department  
of Transportation

LIGHTING AND SIGNAL DETAILS




Surface Patch Details

Note: All trenches shall be saw cut. The replacement concrete shall be P.C.C. pavement and the coarse aggregate gradation, maximum size and method of curing shall be as approved by the Engineer. Immediately prior to pouring replacement concrete, all surfaces shall be painted with an approved epoxy compound.




Cable Trench


Note: The entire area which is disturbed by the trenching shall be sodded or as directed by the Engineer.



Plan View




Elevation View  
Conduit Placement under Railroad Tracks




Light Standard Numbering


Note: On the roadway side of each light standard, the Contractor shall stencil on the pole number using black paint or an adhesive coated plastic such as Scotchcal by 3M or as approved by the Engineer. See layout sheets for pole numbers.



Side View Front View  
Terminal Block Detail




Emergency Vehicle Detector Detail




Alternate Emergency Vehicle Detector Detail (adjustable)


Notes:  
1. Two-way Detector shall have Type X Unilet with two Par lamp holders and lamps. (one in each direction).  
2. One-way Detector shall have the unused end plugged with metal pipe plug.  
3. Two-way Detector shall have the detector lens rotated to face the direction of travel, and shall have Type X Unilet with two Par lamp holders and lamps (one in each direction).




Bridge Mounted Conduit Hanger



Curb Mounted Conduit



Terminal Block (rigid mounted)




Revise Concrete Foundation


Note: Jackhammer or drill to remove material and provide a location for conduit. Make opening no larger than necessary. Place conduit, fill with concrete and finish foundation to original appearance.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-8-13	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 10/08/13 and the original document is stored at the North Dakota Department of Transportation



Light Standard Details




Concrete Foundation Location




Breakaway Support Stub Clearance Diagram


LIGHT STANDARD DETAILS




Truss Mast Arm



Top View




Steel Base Detail




Plan View

Keeper Plate Detail (A)

(A) ASTM A446 Grade "A" 28 gauge keeper plate on top of middle flat washer. The Keeper plate shall be galvanized after fabrication.




Slip Base Placement Detail




Anchor Bolt Detail

Multi-Directional Slip Base



Optional: Festoon receptacle mounted on multi-sided pole.



Pole Wiring Diagram

Receptacle Mounting Detail (B)

(B) Receptacle shall be mounted on the side of the pole that faces the street side. Festoon Receptacle shall be installed only when specified in the plans.

Notes:

Light Standard Locations: The offset distance shall have a minimum offset from the curb face of 3 feet. Light standards that are placed in urban areas and where speeds are less than 30 mph, may be placed at 3 feet. Where speeds are 30 mph or more, light standards shall be placed at least 16 feet from the driving lane.

Steel Standards: Marred or scratched areas shall be touched up after erection.

Luminaire: Shall be internal ballast-constant wattage 120x240 voltage. See layout sheets for type of luminaire, wattage, I.E.S. distribution, and operating system.

Fusing: Fusing in base, see specifications.

Slip Base Bolt Torque Procedure:

1. Tighten all bolts the maximum possible with 12" to 15" wrench to bed washers and to clean bolt threads, then loosen.
2. Retighten bolts with a systematic order to prescribed torque.
3. Loosen each bolt and retighten to prescribed torque in the same order as initial retightening.
4. Burr threads of junction with nut using center punch to prevent nut loosening.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-8-13	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by  
 Roger Weigel,  
 Registration Number  
 PE-2930,  
 on 10/08/13 and the original document is stored at the  
 North Dakota Department  
 of Transportation