

DESIGN DATA				
Traffic	Average Daily			
Current 2016	Pass: 3570	Trucks: 1180	Total: 4750	
Forecast 2036	Pass: 5105	Trucks: 1525	Total: 6630	
Clear Zone Distance:		Design Speed: 70		
Minimum Sight Dist. for Stopping:		Bridges: None		
Limited Access Control				
Pavement Design Life (years)				
Design Accumulated One-way ESALs:				

STATE	PROJECT NO.	PCN	SECTION NO.	SHEET NO.
ND	NH-4-083(135)182	21502	1	1

JOB # 11
NORTH DAKOTA
DEPARTMENT OF TRANSPORTATION



NH-4-083(135)182

GOVERNING SPECIFICATIONS:
 2014 Standard Specifications adopted by the North Dakota Department of Transportation and the Supplemental Specifications effective on the date the project is advertised.

Ward County
 0.5 Miles South of ND 23 to Minot - Northbound Roadway

PROJECT NUMBER \ DESCRIPTION	NET MILES	GROSS MILES
NH-4-083(135)182	15.224	15.224

HMA, GUARDRAIL, & SIGNING



STATE COUNTY MAP

DESIGNERS
Lonnie Heth
Travis Cork

DISTRICT REVIEW
James L. Redding /s/
MINOT DISTRICT ENGINEER
APPROVED DATE 9/1/16
Roger Weigel /s/
OFFICE OF PROJECT DEVELOPMENT ND DEPARTMENT OF TRANSPORTATION

I hereby certify that the attached plans were prepared by me or under my direct supervision and that I am a duly registered professional engineer under the laws of the state of ND. APPROVED DATE 08/26/16 Chad E. Beggs /s/ NDDOT - MINOT DISTRICT

This document was originally issued and sealed by Chad E. Beggs Registration Number PE- 5436 , on 08/26/16 and the original document is stored at the North Dakota Department of Transportation

TABLE OF CONTENTS

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	NH-4-083(135)182	2	1

PLAN SECTIONS

Section	Page(s)	Description
1	1	Title Sheet
2	1	Table of Contents
4	1	Scope of Work
6	2	Notes
8	2	Quantities
10	2	Basis of Estimate
20	2	General Details
30	3	Typical Sections
76	1	Temporary Erosion Control
77	1	Permanent Erosion Control
90	1	Paving Layouts
100	2	Work Zone Traffic Control
110	4	Signing
120	1	Pavement Marking
130	4	Guardrail
200	4	Cross Sections




LIST OF STANDARD DRAWINGS




Number	Description
D-101-1, 2,3	NDDOT Abbreviations
D-101-10	NDDOT Utility Company and Organization Abbreviations
D-101-20, 21	Line Styles
D-101-30, 31,32	Symbols
D-704-7	Breakaway Systems For Construction Zone Signs - Perforated Tube
D-704-8	Breakaway Systems For Construction Zone Signs - U-Channel Post
D-704-9	Construction Sign Details - Terminal And Guide Signs
D-704-10	Construction Sign Details - Regulatory Signs
D-704-11	Construction Sign Details - Warning Signs
D-704-12	Shoulder Closure Tapers
D-704-13	Barricade And Channelizing Device Details
D-704-14	Construction Sign Punching And Mounting Details
D-704-20	Terminal And Seal Coat Sign Layouts
D-704-22	Construction Truck And Temporary Detour Layouts
D-704-26	Miscellaneous Sign Layouts
D-704-27	Traffic Control Plan For Moving Operations
D-704-32	Sign Layout For One Lane Closure Divided Highway Moving Operation
D-704-34	Sign Layout For One Lane Closure
D-704-34A	Traffic Control System Lane Shift Between A Lane Closure And An Opposite Lane Closure
D-704-50	Portable Sign Support Assembly
D-706-1	Bituminous Laboratory
D-754-20	(Expressway-Freeway Use) Mile Posts
D-754-23	Perforated Tube Assembly Details
D-754-24, 25	Mounting Details Perforated Tube
D-754-24A	Breakaway Coupler System For Perforated Tubes
D-754-29	Sign Punching, Stringer And Support Location Details Regulatory, Warning, And Guide Signs
D-754-60, 74	Sign Punching, Stringer And Support Location Details - Route Marker Signs
D-754-87	Sign Punching, Stringer And Support Location Details For Street Name Signs And 911 Signs
D-760-2	Rumble Strips Divided Highways (Non-Interstate)
D-760-5	Saw Slotted Rumble Strips At Intersections
D-762-1	Pavement Marking Message Details
D-762-4	Pavement Marking
D-762-6	Pavement Marking for Standard 90 Degree Flared Intersection-(Center Left turn Lane on Major Road)
D-762-11	Short-Term Pavement Marking
D-764-1	W-Beam Guardrail General Details
D-764-6	Flared Energy Absorbing Terminal
D-764-7	Slotted Rail Terminal
D-764-14	Special W-Beam Guardrail Anchor
D-764-23	Typical Grading At Obstructions With W-Beam Guardrail

SPECIAL PROVISIONS

Number	Description
SP 5128(14)	Permits and Environmental Considerations

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	NH-4-083(135)182	4	1



-  1.0" Mill and 3" Overlay
RAP Superpave FAA 45
-  Milled Tapers
(See Sec. 20-1)
-  Remove and Replace Guardrail
RP 197.152 - 197.328
-  3" Overlay
RAP Superpave FAA 45
-  Rumble Strip - Intersection

This document was originally issued and sealed by
Chad E. Beggs
Registration Number
PE- 5436,
on 08/26/16 and the original document is stored at the
North Dakota Department
of Transportation

Scope of Work

NOTES

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	NH-4-083(135)182	6	1

411-P01 MILLED PAVEMENT SURFACE: Deliver milled material not required for RAP production to the NDDOT Maintenance yard at 1305 Hwy. 2 Bypass E. in Minot. Stockpile milled material using a payloader. Keep payloader tires off of stockpile. Include all costs associated with this work in the contract price bid for "MILLING PAVEMENT SURFACE".

Contact Project Engineer 24 hours prior to milling to determine location in maintenance yard where millings will be delivered and stockpiled.

Do not allow traffic on 1" milled pavement surface. (RP 182.302 – 197.526 NB)

704-P01 TRAFFIC CONTROL: Traffic control for the HMA overlay and the milling operations shall consist of lane closures, and flagging. Traffic Control Devices shall comply with the following Standard Drawings:

1. Standard D-704-20, layout G: For project terminal signing during paving and milling operations.
2. Standard D-704-22, layouts K and L: For trucks hauling material.
3. Standard D-704-34, layout for temporary lane closure during milling & paving operations.
4. Standard D-704-34A, layout of lane shift between a lane closure and an opposite lane closure.

Quantities have been developed based on 1 (one) 8 mile lane closure for Milling, HMA, and Class 5 operations and 1 (one) 1 mile lane closure for guardrail operations. The required traffic control signs and devices are included in the "Traffic Control Devices List" and will be measured and paid at the Contact Unit Price for each device

706-P01 BITUMINOUS LABORATORY: Supply a copy machine, with reduction capabilities, and toner for the "Bituminous Laboratory".

Include payment for these items in the price bid for "BITUMINOUS LABORATORY".

This document was originally issued and sealed by Chad E. Beggs, Registration Number PE-5436, on 09/02/16 and the original document is stored at the North Dakota Department of Transportation.

NOTES

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	NH-4-083(135)182	6	2

SECTION 130

203-P01 GUARDRAIL EMBANKMENT: The embankment material required for guardrail installation is not available within the highway right of way. It will be the contractor's responsibility to obtain embankment material.

The backslope is an avoidance area.

Include all costs to locate the embankment material in the contract unit price bid for Guardrail Embankment."

764-P01 RESET W-BEAM GUARDRAIL: The existing W-beam guardrail installations utilize U-shaped block-outs. Do not use the existing posts, block-outs, or mounting bolts in the reset guardrail installations.

The Contractor will be required to supply and install the following new materials to reset the W-beam guardrail:

- (80) 6"X8"X6'-0" timber posts
- (80) 6"X8"X14" timber blocks
- (80) 5/8"X18" long guardrail bolts

Include these items in the contract unit price bid for the item "Reset W-Beam Guardrail."

This document was originally issued and sealed by Douglas A Schumaker, Registration Number PE-5047, on 9/2/2016 and the original document is stored at the North Dakota Department of Transportation.

ESTIMATE OF QUANTITIES

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	NH-4-083(135)182	8	1

SPEC CODE	ITEM DESCRIPTION	UNIT	MAINLINE	TOTAL
-----	-----	-----	-----	-----
103	0100 CONTRACT BOND	L SUM	1	1
203	0218 GUARDRAIL EMBANKMENT	EA	1	1
216	0100 WATER	M GAL	250	250
230	0125 SHOULDER PREPARATION	MILE	30.448	30.448
261	0112 FIBER ROLLS 12IN	LF	760	760
302	0120 AGGREGATE BASE COURSE CL 5	TON	500	500
401	0050 TACK COAT	GAL	49,752	49,752
401	0060 PRIME COAT	GAL	210	210
411	0100 MILLING PAVEMENT SURFACE	TON	18,218	18,218
430	0145 RAP - SUPERPAVE FAA 45	TON	53,399	53,399
430	1000 CORED SAMPLE	EA	175	175
430	6428 PG 64-28 ASPHALT CEMENT	TON	2,403	2,403
702	0100 MOBILIZATION	L SUM	1	1
704	0100 FLAGGING	MHR	400	400
704	1000 TRAFFIC CONTROL SIGNS	UNIT	3,467	3,467
704	1052 TYPE III BARRICADE	EA	20	20
704	1060 DELINEATOR DRUMS	EA	81	81
704	1067 TUBULAR MARKERS	EA	400	400
704	1087 SEQUENCING ARROW PANEL-TYPE C	EA	2	2
706	0550 BITUMINOUS LABORATORY	EA	1	1
706	0600 CONTRACTOR'S LABORATORY	EA	1	1
754	0110 FLAT SHEET FOR SIGNS-TYPE XI REFL SHEETING	SF	40	40
754	0112 FLAT SHEET FOR SIGNS-TYPE IV REFL SHEETING	SF	86	86
754	0206 STEEL GALV POSTS-TELESCOPING PERFORATED TUBE	LF	140	140
754	0557 INTERSTATE MILE POSTS-TYPE C	EA	1	1
754	0592 RESET SIGN PANEL	EA	2	2
760	0005 RUMBLE STRIPS - ASPHALT SHOULDER	MILE	30.448	30.448
760	0010 RUMBLE STRIPS - INTERSECTION	SET	0.67	0.67
762	0111 EPOXY PVMT MK 12IN LINE	LF	220	220
762	0112 EPOXY PVMT MK MESSAGE	SF	1,088	1,088
762	0113 EPOXY PVMT MK 4IN LINE	LF	182,761	182,761
762	0115 EPOXY PVMT MK 8IN LINE	LF	7,955	7,955
762	0117 EPOXY PVMT MK 24IN LINE	LF	60	60

ESTIMATE OF QUANTITIES

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	NH-4-083(135)182	8	2

SPEC CODE	ITEM DESCRIPTION	UNIT	MAINLINE	TOTAL
-----	-----	-----	-----	-----
762	0430 SHORT TERM 4IN LINE-TYPE NR	LF	20,096	20,096
764	0131 W-BEAM GUARDRAIL	LF	1,077	1,077
764	0145 W-BEAM GUARDRAIL END TERMINAL	EA	1	1
764	0151 REMOVE W-BEAM GUARDRAIL & POSTS	LF	963	963
764	1050 RESET W-BEAM GUARDRAIL	LF	213	213
764	2081 REMOVE END TREATMENT & TRANSITION	EA	1	1

BASIS OF ESTIMATE

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	NH-4-083(135)182	10	1

Additional Turn Lane Quantities See Section 90 Sheet 1 for Paving Details

Material	Unit	Typical Section 1		Typical Section 2 Right & Left Turn Lane		Typical Section 3 Left Turn Lane		Typical Section 4 Right Turn Lane		Typical Section 5 ND 23 Cross-over		Approaches
		Width (ft)	Qty. per Mile	Width (ft)	Qty. per Mile	Width (ft)	Qty. per Mile	Width (ft)	Qty. per Mile	Width (ft)	Qty. per Mile	Area = varies
1" Milling (2.0 Ton / CY)	Ton	36.5	1,189.6	----	----	----	----	----	----	38'	1,238.5	----
Tack Coat @ 0.05 Gal/SY (Wearing Course)	Gal	34"	997	15'	440	11'	322.7	4'	117.3	34'	997	129 Gal
Tack Coat @ 0.10 Gal/SY (Leveling Course)	Gal	36.'	2,141	----	----	----	----	----	----	38'	2,229	259 Gal
RAP Superpave FAA 45 (Wearing Course)	Ton	32.5' 2 - 2.0' sloughs	2,277	11' 2 - 2.0' sloughs	928.5	9' 1 - 2.0' slough	692.6	2' 1 - 2.0' slough	237.7	34' 2-2.0' sloughs	2,412	746 Ton
RAP Superpave FAA 45 (Leveling Course)	Ton	34' No slough	1,108	----	----	----	----	----	----	34' No sloughs	1,108	
PG 64-28 Asphalt Cement @ 4.5% (Wearing Course)	Ton	----	102.5	----	41.8	----	31.2	---	10.6	----	108.5	33 Ton
PG 64-28 Asphalt Cement @ 4.5% (Leveling Course)	Ton	----	49.9	----	----	----	----	----	----	----	50	

		Guardrail Embankment	Approaches
Aggregate Class 5	Ton	312	188

Short-term Pavement Marking

Location	Basis	Qty.	
Centerline	1,320 LF / Mile	20,096	LF

Permanent Pavement Marking 4" Line

Centerline Skips	1,320 LF/ Mile	20,096	LF
Lt & Rt. Edgeline	10,560 LF/ Mile	160,766	LF

Permanent Pavement Marking 8" Line

Channel Line (In-place)		7,465	LF
-------------------------	--	-------	----

Water

25 MGal/Mile

HMA Cored Samples							
Specification Section	A Lanes	B Lifts	C Distance (Feet)	D Sublots (A x B x C) ÷ 2000	Quantity (D x 2)	Quantity (1 per mile)	Unit
430.04 I.2.b(1), "General"	2	1	80,382	80	160	N/A	EA
430.04 I.2.b(2), "Pavement Thickness Determination Cores"					0	15	EA
Total					160	15	EA

This document was originally issued and sealed by Chad E. Beggs, Registration Number PE-5436, on 08/26/16 and the original document is stored at the North Dakota Department of Transportation.

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	NH-4-083(135)182	10	2


BASIS OF ESTIMATE

ESTIMATED QUANTITIES - GUARDRAIL EMBANKMENT SURFACING


	UNIT	Steep Embankment RP 197.228 Rt	Total
Aggregate Base Course CI 5 @ 1.875 Ton/CY	TON	311.5	311.5
Tack Coat @ 0.05 Gal/SY	GAL	42	42
Prime Coat @ 0.25 Gal/SY	GAL	210	210
RAP - Superpave FAA 45 @ 2 Ton/CY	TON	87.5	87.5
PG 64-28 Asphalt Cement @ 4.5%	TON	3.9	3.9

See Section 130 and Standard Drawing D-764-23 for details


This document was originally issued and sealed by Douglas A. Schumaker, Registration Number PE- 5047 , on 8/30/2016 and the original document is stored at the North Dakota Department of Transportation




(1) Paved Section Line, County Road, or Street Approach



(2) Gravel Section Line, County Road, or Street Approach




(3) Private Drives and Field Approaches



(4) Median Cross-overs

Notes:

1. A longer HMA wedge may be needed if an existing elevation difference between the mainline and the approach exists. Actual HMA paving and salvaged base locations may vary in the field for situations, as approved by the Engineer.
2. Quantity totals have been included in the bid items of the "Estimate of Quantities" of the plans.




Section A-A

BASIS OF ESTIMATE	UNIT	(1)	(2)	(3)	(4)	TOTALS
		Paved Section Line	Gravel Section Line	Private Drives and Field Approaches	Median Cross-overs	
Number of Locations	EACH	3	25	20	46	94
Aggr. Surf. Cl. 5	TON	2 Ton ea. 6	2 Ton ea. 50	2 Ton ea. 40	2 Ton ea. 92	188
Tack Coat	GAL	17 Gal. ea. 51	9 Gal. ea. 225	1 Gal. ea. 20	2 Gal. ea. 92	388
Superpave FAA 45	TON	38 Ton ea. 114	20 Ton ea. 500	2 Ton ea. 40	2 Ton ea. 92	746
Asphalt Cement 4.5%	TON	4	29	2	2	33


This document was originally issued and sealed by Chad E. Beggs, Registration Number PE- 5436, on 08/26/16 and the original document is stored at the North Dakota Department of Transportation

Approach Paving Details for Preventive Maintenance or Minor Rehabilitation Projects



Milling Transition

Milling						
X	Begin Mill Transition RP	Y	End Mill Transition RP	YY	XXX	End Mill RP
100 ft	197.488	0 in	197.507	2 in	100 ft	197.526
100 ft	182.340	0 in	182.321	2 in	100 ft	182.302



Paving Transition





Paving								
Y	Begin Paving Transition RP	X	YY	Intermediate Paving Transition RP	XX	End Paving Transition RP	XXX	End Paving RP
3 in *	197.479	50 ft	2 in	197.488	100 ft	197.507	100 ft	197.526
3 in *	182.349	50 ft	2 in	182.340	100 ft	182.321	100 ft	182.302

* Includes 1" Leveling Course

This document was originally issued and sealed by
 Chad E. Beggs
 Registration Number
 PE- 5436,
 on 08/26/16 and the original document is stored at the
 North Dakota Department
 of Transportation

Milling and Paving Transitions





STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	NH-4-083(135)182	30	1



This document was originally issued and sealed by Chad E. Beggs, Registration Number PE- 5436, on 08/26/16 and the original document is stored at the North Dakota Department of Transportation.

EXISTING TYPICALS






STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	NH-4-083(135)182	30	2



This document was originally issued and sealed by
 Chad E. Beggs
 Registration Number
 PE- 5436,
 on 08/26/16 and the original document is stored at the
 North Dakota Department
 of Transportation

PROPOSED MILLING
 TYPICALS

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	NH-4-083(135)182	30	3



* Area shown is for Basis of Estimate only.
Extend Leveling Course to cover milled area.


This document was originally issued and sealed by
Chad E. Beggs
Registration Number
PE- 5436,
on 08/26/16 and the original document is stored at the
North Dakota Department
of Transportation

PROPOSED MILLING
TYPICALS

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	NH-4-083(135)182	76	1



SPEC	CODE	BID ITEM	QTY	UNIT
261	112	FIBER ROLLS 12IN RP 197.228 Rt	380	LF



This document was originally issued and sealed by Douglas A. Schumaker, Registration Number PE- 5047, on 8/30/2016 and the original document is stored at the North Dakota Department of Transportation

Temporary Erosion Control
Guardrail Embankment


Steep Embankment
RP 197.228 Rt

US 83 Northbound

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	NH-4-083(135)182	77	1



SPEC	CODE	BID ITEM	QTY	UNIT
261	112	FIBER ROLLS 12IN		
		RP 197.228 Rt	380	LF




This document was originally issued and sealed by Douglas A. Schumaker, Registration Number PE- 5047, on 8/30/2016 and the original document is stored at the North Dakota Department of Transportation

Permanent Erosion Control
Guardrail Embankment

Steep Embankment
RP 197.228 Rt

US 83 Northbound




Left Turn Lane	Transition Length	Turn Lane Length	Tack (Gal.)	RAP Superpave FAA 45 (Ton)	PG 64-28 (Ton)
182.594	250	590	51.6	172.1	7.7
184.340	80	290	23.8	79.4	3.6
185.725	100	325	27.1	90.3	4.1
187.734	125	325	28.0	93.3	4.2
189.745	165	240	23.3	77.6	3.5
190.765	125	170	16.8	56.0	2.5
193.748	90	315	26.0	86.7	3.9
195.658	165	740	59.4	198.0	8.9
	95	210	18.6	62.0	2.8
196.944	125	175	17.2	57.2	2.6
TOTALS			291.8	972.6	43.8

Right Turn Lane	Transition Length	Turn Lane Length	Tack (Gal.)	RAP Superpave FAA 45 (Ton)	PG 64-28 (Ton)
182.618	125	590	47.1	157.1	7.1
185.725	135	300	26.5	88.5	4.0
187.751	125	240	21.8	72.8	3.3
188.737	65	360	28.3	94.5	4.3
189.766	50	240	19.1	63.8	2.9
190.244	125	275	24.4	81.3	3.7
190.765	125	170	16.8	56.0	2.5
191.767	110	200	18.4	61.4	2.8
193.755	55	315	24.7	82.5	3.7
195.238	115	180	17.2	57.2	2.6
195.689	100	640	49.8	166.1	7.5
196.782	50	210	17.0	56.6	2.5
196.957	50	175	14.4	48.1	2.2
197.343	50	190	15.5	51.8	2.3
TOTALS			341.3	1137.5	51.2

This document was originally issued and sealed by
 Chad E. Beggs
 Registration Number
 PE- 5436,
 on 08/26/16 and the original document is stored at the
 North Dakota Department
 of Transportation

Turn Lane Paving Layout

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	NH-4-083(135)182	100	2



CONSTRUCTED BY
YOUR COMPANY NAME
YOUR TOWN, ND
[REDACTED]

This document was originally issued and sealed by
Chad E. Beggs
Registration Number
PE- 5436,
on 08/26/16 and the original document is stored at the
North Dakota Department
of Transportation


Construction
Signing

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
N.D.	NH-4-083(135)182	110	1

Station / RP	Sign No.	Assembly No.	Flat Sheet For Signs		Sign Support Length				Vert Clearance FT	Support Size	Max Post Len LF	Sleeve Length				Sleeve Size	Anchor EA	Anchor LF	Anchor Size	Reset Sign Panel EA	Reset Sign Support EA	Break-Away EA	Comments
			IV SF	XI SF	1st LF	2nd LF	3rd LF	4th LF				1st LF	2nd LF	3rd LF	4th LF								
RP 182.712 Rt		405	12.4		14.9				7.0	2.5 x 2.5 10 ga	16.0	5.0			2.19 x 2.19 10 ga	1	4	3 x 3 7 ga				1	
RP 185.645 Rt		437	8.4		15.7				7.0	2.25 x 2.25 12 ga	16.6	5.2			2 x 2 12 ga	1	4	3 x 3 7 ga				1	
RP 187.705 Rt		399	6.2		15.7				7.0	2.25 x 2.25 12 ga	16.6	5.2			2 x 2 12 ga	1	4	3 x 3 7 ga				1	
RP 196.745 Rt	437		6.2		15.7				7.0	2.25 x 2.25 12 ga	16.6	5.2			2 x 2 12 ga	1	4	3 x 3 7 ga	1			1	
RP 192.001 Rt	S.A.A		8.4		15.2				7.0	2.5 x 2.5 10 ga	17.1	4.5			2.19 x 2.19 10 ga	1	4	3 x 3 7 ga				1	
Sub Total			41.6	0.0	Total	77.2									Total	20			1	0		5	
Grand Total			41.6	0.0	Total	77.2									Total	20			1	0		5	

<p>This document was originally issued and sealed by Douglas A. Schumaker, Registration Number PE-5047, on 8/30/2016 and is stored at the North Dakota Department of Transportation.</p>	<p>Sign Summary Perforated Tube 0.5 Mi S Jact 23 - Urban Limit NB US Hwy 83</p>
--	---

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	NH-4-083(135)182	110	2



RP 197.146 Rt Mdn Remove



RP 196.000 Rt Sta 10348+10.83 Rt In place to remain



RP 192.001 Rt Special Assembly A

To be installed by state forces

Sign 1

RP 197.000 Rt Sta 10401+22.51 Rt New sign and support



RP 197.146 Rt Remove




RP 196.745 Rt New support Assembly 437



RP 196.745 Rt Remove



RP 182.712 Rt Assembly 405



RP 182.712 Rt Remove



RP 185.645 Rt Assembly 437



RP 185.645 Rt Remove



RP 187.705 Rt Remove



RP 187.705 Rt Assembly 399




RP 192.001 Rt Remove

This document was originally issued and sealed by Douglas A. Schumaker, Registration Number PE- 5047, on 8/30/2016 and the original document is stored at the North Dakota Department of Transportation

SPEC	CODE	BID ITEM	QTY	UNIT
754	557	INTERSTATE MILE POSTS - TYPE C STA 10401+22.51 Rt	1	EA

Sign Layout
0.5 Mi S Jct 23 - Urban Limit NB
US Hwy 83


	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	NH-4-083(135)182	110	4



Special Assembly A
 RP 192.001 Rt
 Pay Area: 3.8 SF

This document was originally issued and sealed by Douglas A. Schumaker, Registration Number PE- 5047, on 8/30/2016 and the original document is stored at the North Dakota Department of Transportation

Sign Assembly
 0.5 Mi S Jct 23 - Urban Limit NB
 US Hwy 83



EPOXY PVMT MK PAINTED 8" LINE
 8" White Channel Line 7955 LF

EPOXY PVMT MK PAINTED 12" LINE
 White Diagonal Line 220 LF

EPOXY PVMT MK MESSAGE
 68 Arrows @ 16 SF Ea. 1088 SF


Left Turn Lane	Turn Lane Length	Arrows	Right Turn Lane	Turn Lane Length	Turn Lane Length
182.594	590	3	182.618	590	3
184.340	290	3	185.725	300	3
185.725	325	3	187.751	240	3
187.734	325	3	188.737	360	3
189.745	240	3	189.766	240	3
190.765	170	2	190.244	275	3
193.748	315	3	190.765	170	2
195.826	1125	3	191.767	200	3
196.773	210	3	193.755	315	3
196.944	175	2	195.238	180	2
TOTALS	3675	28	195.826	745	3
			196.782	210	3
			196.957	175	3
			197.343	190	3
			TOTALS	4190	40

This document was originally issued and sealed by
 Chad E. Beggs
 Registration Number
 PE- 5436,
 on 08/26/16 and the original document is stored at the
 North Dakota Department
 of Transportation

Pavement Marking
 66th Ave. SW
 RP 195.826

23 USC § 409 Documents
 NDDOT Reserves All Objections

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	NH-4-083(135)182	130	1




This document was originally issued and sealed by Douglas A. Schumaker, Registration Number PE- 5047, on 8/30/2016 and the original document is stored at the North Dakota Department of Transportation

W-Beam Guardrail Layout
 Sheet 1 of 3
 Steep Embankment
 RP 197.228 Rt
 US 83 Northbound

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	NH-4-083(135)182	130	2

23 USC § 409 Documents
NDDOT Reserves All Objections



This document was originally issued and sealed by Douglas A. Schumaker, Registration Number PE- 5047, on 8/30/2016 and the original document is stored at the North Dakota Department of Transportation


W-Beam Guardrail Layout
Sheet 2 of 3

Steep Embankment
RP 197.228 Rt

US 83 Northbound

23 USC § 409 Documents
 NDDOT Reserves All Objections

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	NH-4-083(135)182	130	3



This document was originally issued and sealed by Douglas A. Schumaker, Registration Number PE- 5047, on 8/30/2016 and the original document is stored at the North Dakota Department of Transportation

- (A) Install either a FLEAT or a Slotted Rail Terminal at this location.
- If a FLEAT is installed, install the end terminal as shown above.
- If a Slotted Rail Terminal is installed, install it with the offset as shown on Standard D-764-7. Additional guardrail embankment required is at the contractor's expense.

W-Beam Guardrail Layout
 Sheet 3 of 3
 Steep Embankment
 RP 197.228 Rt
 US 83 Northbound

23 USC § 409 Documents
NDDOT Reserves All Objections

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	NH-4-083(135)182	130	4

W-BEAM GUARDRAIL SUMMARY OF QUANTITIES														
W-BEAM GUARDRAIL AT OBSTRUCTIONS DIVIDED HIGHWAYS														
LOCATION	(A) 5/8" Ø x 18" LONG BUTTON HEAD BOLT	(A) 5/8" Ø x 1 1/4" LONG BUTTON HEAD BOLT	(A) 5/8" Ø x 10" LONG GUARD- RAIL BOLT	(A) 6" x 8" x 14" TIMBER BLOCK	(A) 6" x 8" x 6'-0" TIMBER POST	(A) 12'-6" STRAIGHT RAIL SECTION	(A) 12'-6" CURVED RAIL SECTION	(A) REFLECTOR- IZED PLATES	(A) W-BEAM END SECTION (FLARED)	(A) BCT CABLE ASSEM- BLY AND BEARING PLATE	(A) BCT ANCHOR PLATE	(A) BCT TERMINAL POST	(A) 5/8" Ø x 1 1/2" LONG HEX HEAD BOLT	(B) GUARD RAIL EMBANK- MENT
	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	CY
Sta 342+52.72 to 342+66.99 lt	2	16	1	2	2	1			1	1	1	1	8	
Sta 344+79.49 to 355+45.42 lt	171	688		171	171	84	1	28						438
TOTAL	173	704	1	173	173	85	1	28	1	1	1	1	8	438

<u>W-beam guardrail</u>	
Sta 342+52.72 to 342+66.99 lt	14.3 LF
Sta 344+79.49 to 355+45.42 lt	1062.5 LF
Total	1076.8 LF
<u>Guardrail embankment - type C</u>	
Sta 342+52.72 to 356+65.88 lt	1 ea
<u>W-beam guardrail end terminal</u>	
Sta 355+45.42 to 355+95.60 lt	1 ea
<u>Remove W-beam guardrail & posts</u>	
Sta 343+35 to 352+23 lt	887.5 LF
Sta 449+59 to 450+14 lt	75 LF (D)
Total	962.5 LF
<u>Reset W-beam guardrail</u>	
Sta 342+66.99 to 344+79.49 lt	212.5 LF (C)
<u>Remove end treatment & transition</u>	
Sta 352+23 to 352+60 lt	1 ea

- (A) Include these items in the contract unit price bid for "W-Beam Guardrail".
- (B) The volume of guardrail embankment (cubic yards) is for informational purposes only.
- (C) Resetting this guardrail will require that the contractor supply the following new items:

 (33) 6"x8"x6'-0" timber posts
 (33) 6"x8"x14" timber blocks
 (33) 5/8"x18" long guardrail bolts


 Include these items in the contract price bid for the item "Reset W-beam guardrail."
- (D) This guardrail is located at RP 195.31 Rt.


This document was originally issued and sealed by Douglas A. Schumaker, Registration Number PE-5047, on 8/30/16 and the original document is stored at the North Dakota Department of Transportation


W-Beam Guardrail Quantities


Steep Embankment
RP 197.228 Rt

US 83 Northbound









NDDOT ABBREVIATIONS

? This is a special text character used in the labeling of existing features. It indicates a feature that has an unknown characteristic, potentially based on: lack of description, location accuracy or purpose.

Abn abandoned
 Abut abutment
 Ac acres
 Adj adjusted
 Aggr aggregate
 Ahd ahead
 ARV air release valve
 Align alignment
 Al alley
 Alt alternate
 Alum aluminum
 ADA Americans with Disabilities Act
 A ampere
 & and
 Appr approach
 Approx approximate
 ACP asbestos cement pipe
 Asph asphalt
 AC asphalt cement
 Assmd assumed
 @ at
 Atten attenuation
 ATR automatic traffic recorder
 Ave Avenue
 Avg average
 ADT average daily traffic
 Az azimuth
 Bk back
 BF back face
 Bs backsight
 Balc balcony
 B Wire barbed wire
 Barr barricade
 Btry battery
 Brg bearing
 BI beehive inlet
 Beg begin
 BM bench mark
 Bkwy bikeway
 Bit bituminous
 Blk block
 Bd Ft board feet
 BH bore hole
 BS both sides
 Bot bottom
 Blvd Boulevard
 Bndry boundary
 BC brass cap
 Brkwy breakaway
 Br bridge
 Bldg building

BV butterfly valve
 Byp bypass
 C Gdrl cable guardrail
 Calc calculate
 Cd candela
 CIP cast iron pipe
 CB catch basin
 CRS cationic rapid setting
 C Gd cattle guard
 C To C center to center
 Cl or C centerline
 Cm centimeter
 Ch chain
 Chnlk chain-link
 Ch Blk channel block
 Ch Ch channel change
 Chk check
 Chsld chiseled
 Cir circle
 Cl class
 Cl clay
 Cl F clay fill
 Cl Hvy clay heavy
 Cl Lm clay loam
 Clnt clean-out
 Clr clear
 Cl&gr clearing & grubbing
 Co S coal slack
 Comb. combination
 Coml commercial
 Compr compression
 CADD computer aided drafting & design
 Conc concrete
 Cond conductor
 Const construction
 Cont continuous
 CSB continuous split barrel sample
 Contr contraction
 Contr contractor
 CP control point
 Coord coordinate
 Cor corner
 Corr corrected
 CAES corrugated aluminum end section
 CAP corrugated aluminum pipe
 CMES corrugated metal end section
 CMP corrugated metal pipe
 CPVCP corrugated poly-vinyl chloride pipe
 CSES corrugated steel end section
 CSP corrugated steel pipe
 C coulomb
 Co County
 Crse course
 C Gr course gravel
 CS course sand

Ct Court
 Xarm cross arm
 Xbuck cross buck
 Xsec cross sections
 Xing crossing
 Xrd Crossroad
 Crn crown
 CF cubic feet
 M3 cubic meter
 M3/s cubic meters per second
 CY cubic yard
 Cy/mi cubic yards per mile
 Culv culvert
 C&G curb & gutter
 CI curb inlet
 CR curb ramp
 CS curve to spiral
 C cut
 Dd Ld dead load
 Defl deflection
 Defm deformed
 Deg or D degree
 DInt delineate
 DIntr delineator
 Depr depression
 Desc description
 Det detail
 DWP detectable warning panel
 Dtr detour
 Dia diameter
 Dir direction
 Dist distance
 DM disturbed material
 DB ditch block
 DG ditch grade
 Dbl double
 Dn down
 Dwg drawing
 Dr drive
 Drwy driveway
 DI drop inlet
 D dry density
 Ea each
 Esmt easement
 E East
 EB Eastbound
 Elast elastomeric
 EL electric locker
 E Mtr electric meter
 Elec electric/al
 EDM electronic distance meter
 Elev or El elevation
 Ellipt elliptical
 Emb embankment
 Emuls emulsion/emulsified

ES end section
 Engr engineer
 ESS environmental sensor station
 Eq equal
 Eq equation
 Evgr evergreen
 Exc excavation
 Exst existing
 Exp expansion
 Expy Expressway
 E external of curve
 Extru extruded
 FOS factor of safety
 F Fahrenheit
 FS far side
 F farad
 Fed Federal
 FP feed point
 Ft feet/foot
 Fn fence
 Fn P fence post
 FO fiber optic
 FB field book
 FD field drive
 F fill
 FAA fine aggregate angularity
 FS fine sand
 FH fire hydrant
 Fl flange
 Flrd flared
 FES flared end section
 F Bcn flashing beacon
 FA flight auger sample
 FL flow line
 Ftg footing
 FM force main
 Fs foresight
 Fnd found
 Fdn foundation
 Frac fractional
 Frwy freeway
 Frt front
 FF front face
 F Disp fuel dispenser

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 07/01/14 and the original document is stored at the North Dakota Department of Transportation

NDDOT ABBREVIATIONS

D-101-2

FFP	fuel filler pipes	IP	iron Pipe	M	mega	Ped	pedestrian
FLS	fuel leak sensor	Jt	joint	Mer	meridian	PPP	pedestrian pushbutton post
Furn	furnish/ed	J	joule	M	meter	Pen.	penetration
Gal	gallon	Jct	junction	M/s	meters per second	Perf	perforated
Galv	galvanized	K	kelvin	M	mid ordinate of curve	Per.	perimeter
Gar	garage	Kn	kilo newton	Mi	mile	PL	pipeline
Gs L	gas line	Kpa	kilo pascal	MM	mile marker	PI	place
G Reg	gas line regulator	Kg	kilogram	MP	mile post	P&P	plan & profile
GMV	gas main valve	Kg/m3	kilogram per cubic meter	MI	milliliter	PL	plastic limit
G Mtr	gas meter	Km	kilometer	Mm	millimeter	PI	plate
GSV	gas service valve	K	Kip(s)	Mm/hr	millimeters per hour	Pt	point
GVP	gas vent pipe	LS	Land Surveyor (licensed)	Min	minimum	PCC	point of compound curve
GV	gate valve	LSIT	Land Surveyor In Training	Misc	miscellaneous	PC	point of curve
Ga	gauge	Ln	lane	Mon	monument	PI	point of intersection
Geod	geodetic	Lg	large	Mnd	mound	PRC	point of reverse curvature
GIS	Geographical Information System	Lat	latitude	Mtbl	mountable	PT	point of tangent
G	giga	Lt	left	Mtd	mounted	POC	point on curve
GPS	Global Positioning System	L	length of curve	Mtg	mounting	POT	point on tangent
Gov	government	Lens	lenses	Mk	muck	PE	polyethylene
Grd	graded/grade	Lvl	level	Mun	municipal	PVC	polyvinyl chloride
Gr	gravel	LB	level book	N	nano	PCC	Portland Cement concrete
Grnd	ground	LvIng	leveling	NGS	National Geodetic Survey	Lb or #	pounds
GWM	ground water monitor	Lht	light	NS	near side	PP	power pole
Gdrl	guardrail	LP	light pole	Neop	neoprene	Preempt	preemption
Gtr	gutter	Ltg	lighting	Ntwk	network	Prefab	prefabricated
H Plg	H piling	Lig Co	lignite coal	N	newton	Prfmd	performed
Hdwl	headwall	Lig Sl	lignite slack	N	North	Prep	preparation
Ha	hectare	LF	linear foot	NE	North East	Press.	pressure
Ht	height	Liq	liquid	NW	North West	PRV	pressure relief valve
HI	height of instrument	LL	liquid limit	NB	Northbound	Prestr	prestressed
Hel	helical	L	litre	No. or #	number	Pvt	private
H	henry	Lm	loam	Obsc	obscure(d)	PD	private drive
HZ	hertz	Loc	location	Obsn	observation	Prod.	production/produce
HDPE	high density polyethylene	LC	long chord	Ocpd	occupied	Prog	programmed
HM	high mast	Long.	longitude	Ocpy	occupy	Prop.	property
HP	high pressure	Lp	loop	Off Loc	office location	Prop Ln	property line
HPS	high pressure sodium	LD	loop detector	O/s	offset	Ppsd	proposed
Hwy	highway	Lm	lumen	OC	on center	PB	pull box
Hor	horizontal	Lum	luminaire	C	one dimensional consolidation		
HBP	hot bituminous pavement	L Sum	lump sum	OC	organic content		
Hr	hour(s)	Lx	lux	Orig	original		
Hyd	hydrant	ML	main line	O To O	out to out		
Ph	hydrogen ion content	M Hr	man hour	OD	outside diameter		
Id	identification	MH	manhole	OH	overhead		
In or "	inch	Mkd	marked	PMT	pad mounted transformer		
Incl	inclinometer tube	Mkr	marker	Pg	pages		
IMH	inlet manhole	Mkg	marking	Pntd	painted		
ID	inside diameter	MA	mast arm	Pr	pair		
Inst	instrument	Matl	material	Pnl	panel		
Intchg	interchange	Max	maximum	Pk	park		
Intmdt	intermediate	MC	meander corner	PK	Parker-Kalon nail		
Intscn	intersection	Meas	measure	Pa	pascal		
Inv	invert	Mdn	median	PSD	passing sight distance		
IM	iron monument	MD	median drain	Pvmt	pavement		
IPn	Iron Pin	MC	medium curing	Ped	pedestal		

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 07/01/14 and the original document is stored at the North Dakota Department of Transportation

NDDOT ABBREVIATIONS

D-101-3

Qty	quantity	Sig	signal	TS	tangent to spiral	WB	Westbound
Qtr	quarter	Si Cl	silt clay	Tel	telephone	Wrng	wiring
Rad or R	radius	Si Cl Lm	silty clay loam	Tel B	Telephone Booth	W/	with
RR	railroad	Si Lm	silty loam	Tel P	telephone pole	W/o	without
Rlwy	railway	Sgl	single	Tv	television	WC	witness corner
Rsd	raised	SC	slow curing	Temp	temperature	WGS	World Geodetic System
RTP	random traverse point	SS	slow setting	Temp	temporary	Z	zenith
Rge or R	range	Sm	small	TBM	temporary bench mark		
RC	rapid curing	S	South	T	tesla		
Rec	record	S	South	T	thinwall tube sample		
Rcy	recycle	SE	South East	T/mi	tons per mile		
RPCC	recycled Portland cement concrete	SW	South West	Ts	topsoil		
Ref	reference	SB	Southbound	Twp or T	township		
R Mkr	reference marker	Sp	spaces	Traf	traffic		
RM	reference monument	Spcl	special	TSCB	traffic signal control box		
Refl	reflectorized	SA	special assembly	Tr	trail		
RCB	reinforced concrete box	SP	special provisions	Transf	transformer		
RCES	reinforced concrete end section	G	specific gravity	TB	transit book		
RCP	reinforced concrete pipe	Spk	spike	TB	transit book		
RCPS	reinforced concrete pipe sewer	SC	spiral to curve	Trans	transition		
Reinf	reinforcement	ST	spiral to tangent	TT	transmission tower		
Res	reservation	SB	split barrel sample	Trans	transverse		
Ret	retaining	SH	sprinkler head	Trav	traverse		
Rev	reverse	SV	sprinkler valve	TP	traverse point		
Rt	right	Sq	square	Trtd	treated		
R/W	right of way	SF	square feet	Trmt	treatment		
Riv	river	Km2	square kilometer	Qc	triaxial compression		
Rd	road	M2	square meter	TERO	tribal employment rights ordinance		
Rdbd	road bed	SY	square yard	Tpl	triple		
Rdwy	roadway	Stk	stake	TP	turning point		
RWIS	Roadway Weather Information System	Std	standard	Typ	typical		
Rk	rock	N	standard penetration test	Qu	unconfined compressive strength		
Rt	route	Std Specs	Standard Specifications	Ugrnd	underground		
Salv	salvage(d)	Sta	station	USC&G	US Coast & Geodetic Survey		
Sd	sand	Sta Yd	station yards	USGS	US Geologic Survey		
Sdy Cl	sandy clay	Stm L	steam line	Util	utility		
Sdy Cl Lm	sandy clay loam	SEC	steel encased concrete	VG	valley gutter		
Sdy Fl	sandy fill	SSD	stopping sight distance	Vap	vapor		
Sdy Lm	sandy loam	SD	storm drain	Vert	vertical		
San	sanitary sewer line	SD	street	VC	vertical curve		
Sc	scoria	St	street	VCP	vitrified clay pipe		
Sec	seconds	SPP	structural plate pipe	V	volt		
Sec	section	SPPA	structural plate pipe arch	Vol	volume		
SL	section line	Str	structure	Wkwy	walkway		
Sep	separation	Subd	subdivision	W	water content		
Seq	sequence	Sub	subgrade	WGV	water gate valve		
Serv	service	Sub Prep	subgrade preparation	WL	water line		
Sh	shale	Ss	subsoil	WM	water main		
Sht	sheet	SE	superelevation	WMV	water main valve		
Shtng	sheeting	SS	supplement specification	W Mtr	water meter		
Shldr	shoulder	Supp	supplemental	WSV	water service valve		
Sw	sidewalk	Surf	surfacing	WW	water well		
S	siemens	Surv	survey	W	watt		
SD	sight distance	Sym	symmetrical	Wrng	wearing		
SN	sign number	SI	Systems International	Wb	weber		
		Tan	tangent	WIM	Weigh In Motion		
		T	tangent (semi)	W	West		

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 07/01/14 and the original document is stored at the North Dakota Department of Transportation

NDDOT UTILITY COMPANY AND ORGANIZATION ABBREVIATIONS

D-101-10

702COM 702 Communications
 ACCENT Accent Communications
 AGASSIZ WU Agassiz Water Users Incorporated
 AGC Associated General Contractors of America
 AII PI Alliance Pipeline
 ALL SEAS WU All Seasons Water Users Association
 AMOCO PI Amoco Pipeline Company
 AMRDA HESS Amerada Hess Corporation
 AT&T AT&T Corporation
 B PAW Bear Paw Energy Incorporated
 BAKER ELEC Baker Electric
 BASIN ELEC Basin Electric Cooperative Incorporated
 BEK TEL Bek Communications Cooperative
 BELLE PL Belle Fourche Pipeline Company
 BLM Bureau of Land Management
 BNSF Burlington Northern Santa Fe Railway
 BOEING Boeing
 BRNS RWD Barnes Rural Water District
 BURK-DIV ELEC Burke-Divide Electric Cooperative
 BURL WU Burleigh Water Users
 Cable One Cable One
 CABLE SERV Cable Services
 CAP ELEC Capital Electric Cooperative Incorporat
 CASS CO ELEC Cass County Electric Cooperative
 CASS RWU Cass Rural Water Users Incorporated
 CAV ELEC Cavalier Rural Electric Cooperative
 CBLCOM Cablecom Of Fargo
 CENEX PL Cenex Pipeline
 CENT PL WATER DIST Central Pipe Line Water District
 CENT PWR ELEC Central Power Electric Cooperative
 COE Corps of Engineers
 CONS TEL Consolidated Telephone
 CONT RES Continental Resource Inc
 CPR Canadian Pacific Railway
 D O E Department Of Energy
 DAK CARR Dakota Carrier Network
 DAK CENT TEL Dakota Central Telephone
 DAK RWD Dakota Rural Water District
 DGC Dakota Gasification Company
 DICKEY R NET Dickey Rural Networks
 DICKEY RWU Dickey Rural Water Users Association
 DICKEY TEL Dickey Telephone
 DNRR Dakota Northern Railroad
 DOME PL Dome Pipeline Company
 DVELEC Dakota Valley Electric Cooperative
 DVMW Dakota, Missouri Valley & Western
 ENBRDG Enbridge Pipelines Incorporated
 ENVENTIS Enventis Telephone
 FALK MNG Falkirk Mining Company
 FHWA Federal Highway Administration
 G FKS-TRL WD Grand Forks-traill Water District
 GETTY TRD & TRAN Getty Trading & Transportation
 GLDN W ELEC Golden West Electric Cooperative
 GRGS CO TEL Griggs County Telephone

GT PLNS NAT GAS Great Plains Natural Gas Company
 HALS TEL Halstad Telephone Company
 IDEA1 Idea1
 INT-COMM TEL Inter-Community Telephone Company
 KANEB PL Kaneb Pipeline Company
 KEM ELEC Kem Electric Cooperative Incorporated
 KOCH GATH SYS Koch Gathering Systems Incorporated
 LKHD PL Lakehead Pipeline Company
 LNGDN RWU Langdon Rural Water Users Incorporated
 LWR YELL R ELEC Lower Yellowstone Rural Electric
 MCKNZ CON McKenzie Consolidated Telcom
 MCKENZ ELEC McKenzie Electric Cooperative
 MCKNZ WRD McKenzie County Water Resource District
 MCLEOD McLeod USA
 MCLN ELEC McLean Electric Cooperative
 MCLN-SHRDN R WAT McLean-Sheridan Rural Water
 MDU Montana-dakota Utilities
 MID-CONT CABLE Mid-Continent Cable
 MIDSTATE TEL Midstate Telephone Company
 MINOT CABLE Minot Cable Television
 MINOT TEL Minot Telephone Company
 MISS W W S Missouri West Water System
 MNKOTA PWR Minnkota Power
 MOR-GRAN-SOU ELEC Mor-gran-sou Electric Cooperative
 MOUNT-WILLI ELEC Mountrail-williams Electric Cooperative
 MRE LBTY TEL Moore & Liberty Telephone
 MUNICIPAL City Water And Sewer
 MUNICIPAL City Of '.....'
 N CENT ELEC North Central Electric Cooperative
 N VALL W DIST North Valley Water District
 ND PKS & REC North Dakota Parks And Recreation
 ND TEL North Dakota Telephone Company
 NDDOT North Dakota Department of Transportation
 NDSU SOIL SCI DEPT NDSU Soil Science Department
 NEMONT TEL Nemont Telephone
 NODAK R ELEC Nodak Rural Electric Cooperative
 NOON FRMS TEL Noonan Farmers Telephone Company
 NPR Northern Plains Railroad
 NSP Northern States Power
 NTH PRAIR RW Northern Prairie Rural Water Association
 NTHN BRDR PL Northern Border Pipeline
 NTHN PLNS ELEC Northern Plains Electric Cooperative Incorporated
 NTHWSTRN REF Northwestern Refinery Company
 NW COMM Northwest Communication Cooperation
 ONEOK Oneok gas
 OSHA Occupational Safety and Health Administration
 OTTR TL PWR Otter Tail Power Company
 P L E M Prairielands Energy Marketing
 POLAR COM Polar Communications
 PVT ELEC Private Electric
 QWEST Qwest Communications
 R&T W SUPPLY R & T Water Supply Association
 RAMSEY R SEW Ramsey Rural Sewer Association
 RAMSEY RW Ramsey Rural Water Association
 RAMSEY UTIL Ramsey County Rural Utilities

RED RIV TEL Red River Rural Telephone
 RESVTN TEL Reservation Telephone
 ROBRTS TEL Roberts Company Telephone
 R-RIDER ELEC Roughrider Electric Coop
 RRVW Red River Valley & Western Railroad
 RSR ELEC R.S.R. Electric Cooperative
 S E W U South East Water Users Incorporated
 SCOTT CABLE Scott Cable Television Dickinson
 SHERDN ELEC Sheridan Electric Cooperative
 SHEYN VLY ELEC Sheyenne Valley Electric Cooperative
 SKYTECH Skyland Technologies Incorporated
 SLOPE ELEC Slope Electric Cooperative Incorporated
 SOURIS RIV TELCOM Souris River Telecommunications
 ST WAT COMM State Water Commission
 STATE LN WATER State Line Water Cooperative
 STER ENG Sterling Energy
 STUT RWU Stutsman Rural Water Users
 SW PL PRJ Southwest Pipeline Project
 T M C Turtle Mountain Communications
 TCI TCI of North Dakota
 TESORO GHG PLNS PL Tesoro High Plains Pipeline
 TRI-CNTY WU Tri-County Water Users Incorporated
 TRL CO RWU Traill County Rural Water Users
 UNTD TEL United Telephone
 UPPR SOUR WUA Upper Souris Water Users Association
 US SPRINT U.S. Sprint
 USAF MSL CABLE U.S.A.F. Missile Cable
 USFWS US Fish and Wildlife Service
 USW COMM U.S. West Communications
 VRNDRY ELEC Verendrye Electric Cooperative
 W RIV TEL West River Telephone Incorporated
 WEB W. E. B. Water Development Association
 WILLI RWA Williams Rural Water Association
 WILSTN BAS PL Williston Basin Interstate Pipeline Company
 WLSH RWD Walsh Water Rural Water District
 WOLVRTN TEL Wolverton Telephone
 XLENER Xcel Energy
 YSVR Yellowstone Valley Railroad

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 07/01/14 and the original document is stored at the North Dakota Department of Transportation




Line Styles

.....	Limits of Const Transition Line	—— s —— s ——	Floating Silt Curtain	—— ——— ———	Existing Aggregate (Cross Section View)	- - - - -	Existing Centerline
.....	Bale Check	—— ——— T ——	Existing Telephone Line	—— ——— ———	Existing Curb and Gutter (Cross Section View)	- - - - -	Supplemental Contour
.....	Rock Check	—— ——— TV ——	Existing TV Line	—— ——— ———	Existing Riprap	—— - - - - -	Right of Way
.....	Sight Distance Triangle Line	Void — void — void — v	Existing Assumed Ground (Not Surveyed)	—— ——— ———	Existing Underground Vault or Lift Station	—— - - - - -	Existing Right of Way
- - - - -	Small Hidden Object	Void — void — void — v	Tentative Ground Line	—— ——— ———	Tangent Line	—— - - - - -	Existing Right of Way Railroad
- - - - -	Dimension Leader	—— ——— w ——	Existing Water or Steam Line	- - - - -	Hidden Object	- - - - -	Failure Line
- - - - -	Existing Ground	=====	Existing Under Drain	—— ——— ———	Existing Dirt Surface	- - - - -	Existing Conditions
- - - - -	Existing Topsoil (Cross Section View)	=====	Under Drain	—— ——— ———	Existing Conduit	- - - - -	Existing Ground (Details)
—— ——— ———	Large Hidden Object	=====	Wall	—— ——— ———	Topsoil Profile	—— - - - - -	Existing Sixteenth Section Line
—— ——— ———	Edge Drain	=====	Existing Slotted Drain	- - - - -	Existing Conductor	- - - - -	Existing Right of Way Not State Owned
—— D —— D ——	Geotextile Fabric Type D	—— + —— + ——	Existing Cemetary Boundary	- - - - -	Conductor	- - - - -	Phantom Object
—— ——— E ——	Existing Electrical	—— ——— ———	Centerline Pavement Marking	- - - - -	Fiber Optic	- - - - -	Centerline Main
—— ——— FO ——	Existing Fiber Optic Line	=====	Barrier with Centerline Pavement Marking	- - - - -	Existing Loop Detector	-	Existing Guardrail Cable
—— ——— FO ——	Existing TV Fiber Optic	=====	Barrier Pavement Marking	- - - - -	Subgrade, Subcut or Ditch Grade	— . — . — . — .	Existing Guardrail Metal
—— ——— G ——	Existing Gas Pipe	- - - - -	Stripe 4 IN Dotted Extension White	—— ——— ———	Existing Asphalt Surface	—— . ——— . ——— .	Existing Edge of Water
—— Geo —— Geo ——	Geogrid	- - - - -	Stripe 8 IN Dotted Extension White	—— ——— ———	Existing Asphalt (Cross Section View)	- - - - -	Excavation Limits
—— ——— OH ——	Existing Overhead Utility Line	- - - - -	Stripe 8 IN Lane Drop	—— ——— ———	Existing Reinforcement Rebar	—— ———	Existing Government Lot Line
—— ——— P ——	Existing Power	—— v v v v ——	Wetland Mitigation	—— ——— ———	Existing Tie Point Line	Existing Adjacent Block Lines
—— ——— PL ——	Existing Fuel Pipeline	- - - - -	Existing Box Culvert Bridge	—— ——— ———	Existing State or International Line	Existing Adjacent Lot Lines
—— ——— PL ——	Existing Undefined Above Ground Pipe Line	- - - - -	Existing Concrete Surface	—— ——— ———	Existing Quarter Section Line	Existing Adjacent Property Line
—— ——— R —— R ——	Geotextile Fabric Type R	- - - - -	Existing Drainage Structure	—— ——— ———	Existing County	Existing Adjacent Subdivision Lines
—— ——— R —— R ——	Geotextile Fabric Type R1	- - - - -	Easement	—— ——— ———	Existing Section Line		
—— REMOVE —— REMOVE ——	Remove Line	- - - - -	Existing Concrete	—— ——— ———	Existing Township		
—— RR —— RR ——	Geotextile Fabric Type RR	- - - - -	Existing Easement	—— ——— ———	Existing Railroad Centerline		
—— S —— S ——	Geotextile Fabric Type S	—— ——— ———	Existing Gravel Surface	—— - - - - -	Centerline		

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 07/01/14 and the original document is stored at the North Dakota Department of Transportation

Line Styles

	Subgrade Reinforcement		Existing Railroad Switch		Sheet Piling
	Existing Down Guy Wire Down Guy		Overhead Sign Structure Cantilever		W-Beam w Posts
	Existing Fence		24 Inch Pipe		Existing W-Beam Guardrail with Posts
	Existing Railroad		Reinforced Concrete Pipe		Exst Wet Area-Vegetation Break
	Existing Sanitary Sewer		Signal Head with Mast Arm		Existing Wetland Delineated
	Existing Sanitary Force Main		Existing Signal Head with Mast Arm		
	Existing Storm Drain		Tie Bar at Random Spacing		
	Existing Storm Drain Force Main		3-Cable w Posts		
	Fence		Existing 3-Cable w Posts		
	Silt Fence		Site Boundary		
	Existing Field Line		Fiber Rolls		
	Exst Flow		Doweled Joint		
	Flow		Tie Bar 30 Inch 4 Foot Center to Center		
	Existing Culvert		Tie Bar 18 Inch 3 Foot Center to Center		
	Existing Curb		Existing Berm, Dike, Pit, or Earth Dam		
	Existing Valley Gutter		Existing Ditch Block		
	Existing Driveway Gutter		Depression Contours		
	Existing Curb and Gutter		Existing City Corporate Limits or Reservation Boundary		
	Existing Mountable Curb and Gutter		Gravel Pit - Borrow Area		
	Existing Double Micro Loop Detector		Existing Tree Boundary		
	Micro Loop Detector Double		Tree Row		
	Existing Overhead Sign Structure		Existing Brush or Shrub Boundary		
	Existing Micro Loop Detector		Existing Retaining Wall		
	Micro Loop Detector		Existing Planter or Wall		
	Existing Overhead Sign Structure Cantilever		Retaining Wall (Plan View)		

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 07/01/14 and the original document is stored at the North Dakota Department of Transportation

Symbols

	North Arrow (Half Scale)		Attenuation Device		Existing Railroad Battery Box		Existing Delineator Type E
	Truck Mounted Attenuator		Diamond Grade Delineator Type A		Existing Bush or Shrub		Existing EFB Misc
	Type I Barricade		Diamond Grade Delineator Type B		Existing Gas Cap or Stub		Existing Flashing Beacon
	Type II Barricade		Diamond Grade Delineator Type C		Existing Sanitary Cap or Stub		Existing Pipe Mounted Flasher
	Type III Barricade		Diamond Grade Delineator Type D		Existing Storm Drain Cap or Stub		Existing Pad Mounted Feed Point
	Catch Basin		Diamond Grade Delineator Type E		Existing Water Cap or Stub		Existing Pipe Mounted Feed Point with Pad
	Cairn or Stone Circle		Flexible Delineator		Existing Sanitary Cleanout		Existing Pole Mounted Feed Point
	Video Detection Camera		Flexible Delineator Type A		Existing Concrete Foundation		Existing Railroad Frog
	Storm Drain Cap or Stub		Flexible Delineator Type B		Existing Traffic Signal Controller		Existing Snow Gate 18
	Corrugated Metal End Section 18 Inch		Flexible Delineator Type C		Existing Pad Mounted Signal Controller		Existing Snow Gate 28
	Corrugated Metal End Section 24 Inch		Flexible Delineator Type D		Existing Sixteenth Section Corner		Existing Snow Gate 40
	Corrugated Metal End Section 30 Inch		Flexible Delineator Type E		Existing Quarter Section Corner		Existing Headwall
	Corrugated Metal End Section 36 Inch		Delineator Type A		Existing Section Corner		Existing Pedestrian Head with Number
	Corrugated Metal End Section 42 Inch		Delineator Type A Reset		Existing Railroad Crossbuck		Existing Signal Head
	Corrugated Metal End Section 48 Inch		Delineator Type B		Existing Satellite Dish		Existing Sprinkler Head
	Concrete Foundation		Delineator Type B Reset		Existing Fuel Dispensers		Existing Fire Hydrant
	Ground Connection Conductor		Delineator Type C		Existing Flexible Delineator Type A		Existing Catch Basin Drop Inlet
	Neutral Connection Conductor		Delineator Type D		Existing Flexible Delineator Type B		Existing Curb Inlet
	Phase 1 Connection Conductor		Delineator Type E		Existing Flexible Delineator Type C		Existing Manhole Inlet
	Phase 2 Connection Conductor		Delineator Drums		Existing Flexible Delineator Type D		Existing Junction Box
	Traffic Cone		Spot Elevation		Existing Flexible Delineator Type E		
	Signal Controller		Existing Access Control Arrow		Existing Delineator Type A		
	Pad Mounted Signal Controller		Existing Artifact		Existing Delineator Type B		
	Alignment Data Point		Existing Flashing Beacon		Existing Delineator Type C		
	Emergency Vehicle Detector		Existing Benchmark		Existing Delineator Type D		

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 07/01/14 and the original document is stored at the North Dakota Department of Transportation

Symbols

	Existing Light Standard		Existing Manhole with Valve Water		Existing Telephone Pole		Existing Undefined Manhole
	Existing High Mast Light Standard 10 Luminaire		Existing Water Manhole		Existing Wood Pole		Existing Undefined Pull Box
	Existing High Mast Light Standard 3 Luminaire		Existing Mile Post Type A		Existing Post		Existing Undefined Pedestal
	Existing High Mast Light Standard 4 Luminaire		Existing Mile Post Type B		Existing Pedestrian Push Button Post		Existing Undefined Valve
	Existing High Mast Light Standard 5 Luminaire		Existing Mile Post Type C		Existing Control Point CP		Existing Undefined Pipe Vent
	Existing High Mast Light Standard 6 Luminaire		Existing Reference Marker		Existing Control Point GPS-RTK		Existing Gas Valve
	Existing High Mast Light Standard 7 Luminaire		Existing RW Marker		Existing Control Point TRI		Existing Water Valve
	Existing High Mast Light Standard 8 Luminaire		Existing Utility Marker		Existing Reference Marker Point NGS		Existing Fuel Pipe Vent
	Existing High Mast Light Standard 9 Luminaire		Iron Monument Found		Existing Pull Box		Existing Gas Pipe Vent
	Existing Overhead Sign Structure Load Center		Iron Pin R/W Monument		Existing Intelligent Transportation Pull Box		Existing Sanitary Pipe Vent
	Existing Luminaire		Existing Object Marker Type I		Existing Water Pump		Existing Storm Drain Pipe Vent
	Existing Light Standard Luminaire		Existing Object Marker Type II		Existing Slotted Reinforced Concrete Pipe		Existing Water Pipe Vent
	Existing Federal Mailbox		Existing Object Marker Type III		Existing RR Profile Spot		Existing Weather Station
	Existing Private Mailbox		Existing Electrical Pedestal		Existing Fuel Leak Sensors		Existing Ground Water Well Bore Hole
	Existing Meander Section Corner		Existing Telephone Pedestal		Existing Highway Sign		Existing Windmill or Tower
	Existing Meter		Existing Fiber Optic Telephone Pedestal		Existing Miscellaneous Spot		Existing Witness Corner
	Existing Electrical Manhole		Existing TV Pedestal		Existing Lighting Standard Pole		Flashing Beacon
	Existing Gas Manhole		Existing Fiber Optic TV Pedestal		Existing Traffic Signal Standard		Flagger
	Existing Sanitary Manhole		Existing Fuel Filler Pipes		Existing Transformer		Pipe Mounted Flasher
	Existing Sanitary Force Main Manhole		Existing Traverse PI Aerial Panel		Existing Large Evergreen Tree		Sanitary Force Main with Valve
	Existing Sanitary Manhole with Valve		Existing Pole		Existing Small Evergreen Tree		
	Existing Storm Drain Manhole		Existing Power Pole		Existing Large Tree		
	Existing Force Main Storm Drain Manhole		Existing Power Pole with Transformer		Existing Small Tree		
	Existing Force Main Storm Drain Manhole with Valve				Existing Tree Trunk		
	Existing Telephone Manhole				Existing Pad Mounted Traffic Signal Control Box		

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 07/01/14 and the original document is stored at the North Dakota Department of Transportation


Symbols

D-101-32

 Pad Mounted Feed Point  Pipe Mounted Feed Point with Pad  Pole Mounted Feed Point  Headwall  Double Headwall with Vegetation Barrier  Single Headwall with Vegetation Barrier  Pole Mounted Head  Sprinkler Head  Fire Hydrant  Inlet Type 1  Inlet Type 2  Double Inlet Type 2  Inlet Gate Type 2  Junction Box  High Mast Light Standard 10 Luminaire  High Mast Light Standard 3 Luminaire  High Mast Light Standard 4 Luminaire  High Mast Light Standard 5 Luminaire  High Mast Light Standard 6 Luminaire  High Mast Light Standard 7 Luminaire  High Mast Light Standard 8 Luminaire  High Mast Light Standard 9 Luminaire  Relocate Light Standard  Overhead Sign Structure Load Center  Light Standard 100 Watt High Pressure Sodium Vapor Luminaire	 Light Standard 1000 Watt High Pressure Sodium Vapor Luminaire  Light Standard 150 Watt High Pressure Sodium Vapor Luminaire  Light Standard 175 Watt High Pressure Sodium Vapor Luminaire  Light Standard 200 Watt High Pressure Sodium Vapor Luminaire  Light Standard 250 Watt High Pressure Sodium Vapor Luminaire  Light Standard 310 Watt High Pressure Sodium Vapor Luminaire  Light Standard 35 Watt High Pressure Sodium Vapor Luminaire  Light Standard 400 Watt High Pressure Sodium Vapor Luminaire  Light Standard 50 Watt High Pressure Sodium Vapor Luminaire  Light Standard 70 Watt High Pressure Sodium Vapor Luminaire  Light Standard 700 Watt High Pressure Sodium Vapor Luminaire  Manhole  Manhole 48 Inch  Sanitary Force Main Manhole  Sanitary Sewer Manhole  Storm Drain Manhole  Storm Drain Manhole with Inlet  Reset Mile Post  Mile Post Type A  Mile Post Type B  Mile Post Type C  Right of Way Marker  Tubular Marker  Alignment Monument  Iron Pin Reference Monument	 Object Marker Type I  Object Marker Type II  Object Marker Type III  Caution Mode Arrow Panel  Back to Back Vertical Panel Sign  Double Direction Arrow Panel  Left Directional Arrow Panel  Right Directional Arrow Panel  Sequencing Arrow Panel  Truck Mounted Arrow Panel  Power Pole  Wood Pole  Pedestrian Push Button Post  Property Corner  Pull Box  Intelligent Transportation Pull Box  Sanitary Pump  Storm Drain Pump  Reinforced Pavement  Reinforced Concrete End Section 15 Inch  Reinforced Concrete End Section 18 Inch  Reinforced Concrete End Section 24 Inch  Reinforced Concrete End Section 30 Inch  Reinforced Concrete End Section 36 Inch  Reinforced Concrete End Section 42 Inch	 Reinforced Concrete End Section 48 Inch  Reinforced Concrete End Section 54 Inch  Reset Right of Way Marker  Reset USGS Marker  Right of Way Markers  Riser 30 Inch  Continuous Split Barrel Sample  Flight Auger Sample  Split Barrel Sample  Thinwall Tube Sample  Highway Sign  SNOW GATE 18 FT  SNOW GATE 28 FT  SNOW GATE 40 FT  Standard Penetration Test  Transformer  Inclinometer Tube  Underdrain Cleanout  Excavation Unit  Water Valve
---	--	---	--


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by
Roger Weigel,
 Registration Number
PE-2930,
 on 07/01/14 and the original document is stored at the
 North Dakota Department
 of Transportation




Multi-Directional Slip Base Assembly

Perforated Tube



Top Post Receiver
Plate - ASTM A572 grade 50
Angle Receiver - 2 1/2"x2 1/2"x3/8" ASTM A36 structural angle



Bottom Soil Stub
Tube - 3"x3"x7 gauge ASTM A500 grade B tube
Stabilizing Wing - 7 gauge H.R.P.O. ASTM A1011
Plate - ASTM A572 grade 50


Notes:

1. Slip base bolts shall be torqued as specified by the manufacturer.
2. Anchor shall have a yield strength of 43.9 KSI and tensile strength of 59.3 KSI.
3. The 4" vertical clearance is required for the anchor or breakaway base. The 4"x60" measurement shall be made above and below post location and also back and ahead of the post.
4. When used in concrete sidewalk, anchor shall be same except without the wings.
5. Four post signs shall have over 7' between the first and the fourth posts.


Telescoping Perforated Tube						
Number of Posts	Post Size in.	Wall Thickness Gauge	Sleeve Size in.	Wall Thickness Gauge	Slip Base	Anchor Size without Slip Base in.
1	2	12			No	2 1/4
1	2 1/4	12			No	2 1/2
1	2 1/2	12			(A)	3
1	2 1/2	10			Yes	
1	2 1/4	12	2	12	Yes	
1	2 1/2	12	2 1/4	12	Yes	
2	2	12			No	2 1/4
2	2 1/4	12			No	2 1/2
2	2 1/2	12			Yes	
2	2 1/2	12			Yes	
2	2 1/4	10	2	12	Yes	
2	2 1/2	12	2 1/4	12	Yes	
3 & 4	2 1/2	12			Yes	
3 & 4	2 1/2	10			Yes	
3 & 4	2 1/2	12	2 1/4	12	Yes	
3 & 4	2 1/4	12	2	12	Yes	
3 & 4	2 1/2	10	2 3/16	10	Yes	

Properties of Telescoping Perforated Tube						
Tube Size in.	Wall Thickness in.	U.S. Standard Gauge	Weight per Foot lbs.	Moment of Inertia in. ⁴	Cross Sec. Area in. ²	Section Modulus in. ³
1 1/2 x 1 1/2	0.105	12	1.702	0.129	0.380	0.172
2 x 2	0.105	12	2.416	0.372	0.590	0.372
2 1/4 x 2 1/4	0.105	12	2.773	0.561	0.695	0.499
2 3/16 x 2 3/16	0.135	10	3.432	0.605	0.841	0.590
2 1/2 x 2 1/2	0.105	12	3.141	0.804	0.803	0.643
2 1/2 x 2 1/2	0.135	10	4.006	0.979	1.010	0.785


Top Post Receiver Data Table						
Square Post Sizes (B)	A	B	C	D	E	F
2 3/16"x10 ga.	1 9/64"	2 1/2"	3 1/32"	2 5/32"	1 33/64"	1 1/8"
2 1/2"x10 ga.	1 9/32"	2 1/2"	3 5/16"	5/8"	1 21/32"	1 3/4"



Anchor Unit and Post Assembly



Multi-Directional Slip Base Anchor Unit and Post Sleeve Assembly




Bolt Retainer for Base Connection
Bolt Retainer - 1/32" Reprocessed Teflon

- (A) The breakaway base is required when the support is placed in weak soils. The Engineer shall determine if the soils are weak.
- (B) The 2 3/16"x10 ga. may be inserted into 2 1/2"x10 ga. for additional wind load.


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
2-28-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 2/28/14 and the original document is stored at the North Dakota Department of Transportation

U-Channel Post



Detail A




Front View

Side View


Back View

Breakaway U-Channel Detail Alternate A

A maximum of 2 posts shall be installed within 7'.




Retainer Strap Detail



Breakaway U-Channel Splice Detail Alternate B
(2.5 and 3 lb/ft)

A maximum of 3 posts shall be installed within 7'.



Breakaway U-Channel Splice Detail Alternate C
(2.5 and 3 lb/ft)

A maximum of 3 posts shall be installed within 7'.

Alternate A Steps of Installation:












1. a) Drive anchor unit to within 12" of ground level.
b) Proper assembly established by lining up the bottom hole of retainer strap with the 6th hole from the top of the anchor unit.
c) Assemble strap to back of anchor unit using 5/16"x2" bolt, lock washer and nut.
d) Rotate strap 90° to left.
2. a) Drive anchor unit to 4" above ground.
b) Rotate strap to vertical position.
3. a) Place 5/16"x2" bolt, lock washer and nut in bottom of sign post to facilitate alignment of sign post with proper hole in anchor unit.
b) Alternately tighten two connector bolts.
4. Complete assembly by tightening 5/16"x2" bolt (this fastens sign post to retainer strap).
5. The base post, strap and sign post shall be properly nested. Proper nesting occurs when all flat surfaces of the base post, strap, and sign post at the bolts have full contact across the entire width.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
2-28-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by
 Roger Weigel,
 Registration Number
 PE-2930,
 on 2/28/14 and the original document is stored at the
 North Dakota Department
 of Transportation

CONSTRUCTION SIGN DETAILS
 TERMINAL AND GUIDE SIGNS

D-704-9





ARROW DETAILS

NOTES:

(A) Arrow may be right or left of the legend to indicate construction to the right or left.


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-13-13	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by
 Roger Weigel,
 Registration Number
 PE-2930,
 on 8/13/13 and the original document is stored at the
 North Dakota Department
 of Transportation




CONSTRUCTION SIGN DETAILS
REGULATORY SIGNS


D-704-10




R1-50-24
Legend: black (non-refl)
Background: white



R11-3c-60
Legend: black (non-refl)
Background: white



R2-1a-24
Legend: black (non-refl)
Background: white



R11-4a-60
Legend: black (non-refl)
Background: white



R11-2a-48
Legend: black (non-refl)
Background: white


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-13-13	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 8/13/13 and the original document is stored at the North Dakota Department of Transportation


CONSTRUCTION SIGN DETAILS
WARNING SIGNS

WORD	LETTER SPACING
AHEAD	Standard
200 FT	Standard
350 FT	Standard
500 FT	Standard
1000 FT	Reduce 40%
1500 FT	Reduce 40%
½ MILE	Reduce 50%
1 MILE	Standard


* DISTANCE MESSAGES




W5-8-48
Legend: black (non-refl)
Background: orange




W8-54-48
Legend: black (non-refl)
Background: orange




W20-51-48
Legend: black (non-refl)
Background: orange




W21-51-48
Legend: black (non-refl)
Background: orange




W5-9-48
Legend: black (non-refl)
Background: orange




W8-55-48
Legend: black (non-refl)
Background: orange




W20-52-54
Legend: black (non-refl)
Background: orange




W22-8-48
Legend: black (non-refl)
Background: orange




W5-9-48
ARROW DETAILS



W8-53-48
Legend: black (non-refl)
Background: orange



W8-56-48
Legend: black (non-refl)
Background: orange




W21-50-48
Legend: black (non-refl)
Background: orange

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-13-13	
REVISIONS	
DATE	CHANGE




This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 8/13/13 and the original document is stored at the North Dakota Department of Transportation

SHOULDER CLOSURE TAPERS

D-704-12



SHOULDER CLOSURE WITH LANE CLOSURE
(when shoulder is 8' or wider)



Sequencing Arrow Panel

SHOULDER CLOSURE USED WITH LANE CLOSURE
(when shoulder is less than 8' wide)

PORTABLE TRAFFIC SIGNAL OR CHANGEABLE MESSAGE SIGN ON SHOULDER

KEY	
● Delineator Drum	∞ Sequencing Arrow Panel
• Message Display	↳ Portable Traffic Signal


Notes:

- S = Posted Speed Limit in mph
W = Width of offset in feet
L = Taper length in feet
L = $WS^2/60$ (40mph or less)
L = WS (45mph or more)
- If a shoulder taper is used, it should have a length of approximately $1/3L$. If a shoulder is used as a travel lane, a normal merging or shifting taper should be used.
- When paved shoulders of 8 foot width or more are closed, channelizing devices shall be used to close the shoulder in advance to delineate the beginning of the work space and direct vehicular traffic to remain within the traveled way.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-3-13	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by Roger Weigel Registration Number PE-2930, on 10/3/13 and the original document is stored at the North Dakota Department of Transportation

BARRICADE AND CHANNELIZING DEVICE DETAILS




The markings on drums shall be horizontal, circumferential, alternating orange and white retroreflective stripes 4" to 6" wide. Each drum shall have a minimum of two orange and two white stripes with the top stripe being orange. Any nonretroreflectORIZED spaces between the horizontal orange and white stripes shall not exceed 3" wide. Stripes shall not be placed on ribs or indentations in the drum. Drums shall have closed tops that will not allow collection of construction debris or other debris. Ballast shall not be placed on the top of a drum.

Markings for vertical panels shall be alternating orange and white retroreflective stripes, sloping downward in the direction vehicular traffic is to pass. Retroreflective sheeting shall be placed on both sides of panel and shall have a minimum of 270 square inches of retroreflective area facing vehicular traffic. Where the height of the retroreflective material on the vertical panel is 36 inches or more, a stripe width of 6 inches shall be used.




RetroreflectORIZATION of cones more than 36" in height shall be provided by alternating orange and white retroreflective stripes. Each cone shall have a minimum of two orange and two white stripes with the top stripe being orange. Any nonretroreflectORIZED space between the orange and white stripes shall not exceed 3" wide.

RetroreflectORIZATION of tubular markers more than 42" in height shall be provided by alternating four 4" to 6" wide orange and white stripes with the top stripe being orange.



INSTALLATION NOTES:


1. Drill installation holes to diameter and depth as required by manufacturer's specifications.
2. For removal, remove anchors and fill installation hole with an epoxy designed to bond to pavement surface.
3. In lieu of bolted down base, the contractor may use an 8" x 8" butyl pad or hot melt butyl. Butyl shall be removed as close as possible to pavement surface.



BARRICADE BLADE DETAIL

ELEVATION VIEW

BARRICADE ASSEMBLY DETAIL (Aluminum Barricade Rails)




ELEVATION VIEW

SIDE VIEW

BARRICADE ASSEMBLY DETAIL (Wood or Plastic Rails)

NOTE: Markings for barricades shall be alternating orange and white retroreflective stripes, sloping downward in the direction traffic is to pass. Retroreflective sheeting shall be placed on both sides of the rails and shall have a minimum of 270 square inches of visible retroreflective area facing vehicular traffic. When the barricade length is less than 36", the rail stripe width shall be 4".




TYPE I BARRICADE

TYPE II BARRICADE

TYPE III BARRICADE

BARRICADE RAIL DETAILS



REFLECTOR DETAIL

ELEVATION

DELINEATORS

MINIMUM BALLAST (For each side of barricade support)

Without Sign	4 - 25 lb sandbags
With Sign	6 - 25 lb sandbags


Note: The number of sandbags are based on a wind speed of 55 MPH. The sandbags are assumed to be placed at or near the ends of the skids.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-3-13	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 10/3/13 and the original document is stored at the North Dakota Department of Transportation

CONSTRUCTION SIGN PUNCHING AND MOUNTING DETAILS


Note: Signs placed in sections with curb shall have a minimum horizontal clearance of 2' from the face of the curb to the near edge of the sign.




TYPICAL SECTION
(48" x 48" diamond warning sign shown)




24" x 24" ROUTE MARKER ASSEMBLY




36" x 36" ROUTE MARKER ASSEMBLY




18" x 18" DIAMOND SIGN




48" x 48" DIAMOND SIGN
(with 30" x 30" secondary sign)




48" x 48" DIAMOND SIGN
(with 30" x 24" secondary sign)




R1-2-60 - YIELD SIGN




W14-3-64 - PENNANT SIGN




R1-1-48 - STOP SIGN
(with R6-1-54 sign as required)




R1-1-48 - STOP SIGN
(with R1-50-24 sign as required)




48" x 48" SIGN
(with R6-1-54 sign as required)




48" x 48" SIGN
(with R2-1a-24 sign as required)




24" x 36" SIGN




30" x 24" SIGN




108" x 48" SIGN




96" x 48" SIGN




72" x 36" SIGN




72" x 24" SIGN




60" x 24" SIGN



48" x 24" SIGN



PORTABLE SIGN SUPPORT
LOW-MOUNTING HEIGHT



PORTABLE SIGN SUPPORT
HIGH-MOUNTING HEIGHT

NOTES:

1. Sign Supports: Supports shall be galvanized or painted. Minimum post sizes are 2.5 lb/ft u-channel or 2" x 2" x 12 gauge steel perforated tube, except where noted. When installing signs on u-channel, the minimum post size for assemblies containing a secondary sign is 3.0 lb/ft. Post sizes are based on a wind speed of 55 MPH.

Signs over 50 square feet should be installed on 2 1/2" x 2 1/2" perforated tube supports as a minimum.

Guy wires shall not be attached to sign supports. Wind beams may be attached to u-posts behind the sign panels.

2. Sign Panels: Provide sign panels made of 0.100" aluminum, 1/2" plywood, or other approved material, except where noted. All holes to be punched round for 3/8" bolts.

3. Alternate Messages: The signs that have alternate messages may have these alternate messages placed on a reflectorized plate (without a border) and installed and removed as required. (i.e. "Left" and "Right" message on a lane closure sign)

4. Route Marker Auxiliary Signs: Provide route marker auxiliary signs, such as the cardinal direction and directional arrows, with a background and legend that match the route marker they are used with:

Interstate - white legend on blue background
Interstate Business Loop - white legend on green background
US and State - black legend on white background
County - yellow legend on blue background

5. Vertical Clearance: Install signs with a vertical clearance of 5'-0" (see TYPICAL SECTION.) In areas where parking or pedestrian movements are likely or the view of the sign may be obstructed, install signs with a vertical clearance of 7'-0" from the top of the curb or from the near edge of the driving lane in absence of a curb.

The vertical clearance to secondary signs is 1'-0" less than the vertical clearance as stated above.

Large signs having an area exceeding 50 square feet shall have a minimum clearance of 7'-0" from the ground at the post.

6. Portable Signs: Provide portable signs that meet the vertical clearance as stated above. Use portable signs when it is necessary to place signs within the pavement surface.

When portable signs are used for 5 days or less, low-mounting height (minimum 12" vertical clearance) sign supports may be used as long as the view of the sign is not obstructed. Time delays caused by unforeseen circumstances, such as equipment breakdown, rain, subgrade failures, etc., will not accrue towards the 5 day period. The R9-8 through R9-11a series, W1-5 through W1-8 series, M4-10, and E5-1 may be used for longer than 5 days.

Signs mounted to the portable sign supports shown in the LOW-MOUNTING HEIGHT and HIGH-MOUNTING HEIGHT Details shall have a maximum surface area of 16 square feet.

MINIMUM BALLAST
(For each side of sign support base)

Sign Panel Mounting Height (ft)	Number of 25 lb sandbags for 4' x 4' sign panel
1'	6
5'	8
7'	10


Note: The number of sandbags are based on a wind speed of 55 MPH. The sandbags are assumed to be placed at or near the ends of the skids.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-4-13	
REVISIONS	
DATE	CHANGE
11-14-13	Revised Note 6.

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 11/14/13 and the original document is stored at the North Dakota Department of Transportation

TERMINAL AND SEAL COAT SIGN LAYOUTS

D-704-20



- Barricades placed on roadway shall be on a moveable assembly. Signs placed on the roadway shall be placed on skid mounted assemblies.
- The speed limit shall be re-established. The exact speed limit shall be determined in the field, dependent on location and conditions.
- The reduced speed limit shall be determined dependent on the in place speed limit before construction. The speed limit reduction should not exceed 10 MPH below the existing speed limit, unless the design speed of the work zone feature has been reduced below the 10 MPH. In this case, the speed limit reduction shall not exceed 30 MPH. Where speed limits are to be reduced more than 30 MPH, a second speed limit sign shall be installed with the desired speed reduction but shall not exceed 30 MPH. The second speed limit sign shall be placed at 1/2 B.
- When warning signs are used in urban areas and the signs are not portable, flags shall be installed. The flags shall be 24 inches square, mounted perpendicular to the edges of the diamond sign, and at such a distance above the edge so that when the flag is limp it will not touch the sign. Rural areas will not require flags.
- Existing speed limit signs within a reduced speed zone shall be covered.
- On seal projects, signs R2-1-48, R2-1a-24, R4-1-48, W22-8-48 and W20-52-54 shall be placed just after all important intersections and at five mile intervals thereafter. Sign W8-12-48 shall be placed just after all important intersections and at 2 mile intervals thereafter until the short term center line pavement marking is in place. No short term pavement markings are placed when traffic volumes are 750 ADT or less.
- The contractor has the option of using portable sign supports in lieu of post mounted signs in accordance with the NDDOT Standard Specifications.
- Type H construction sign traffic control shall have the speed limit signs covered or removed once the loose aggregate has been removed.
- The contractor shall install the G20-1b-60 sign when work is suspended for winter.
- Other traffic control layouts will be required in the immediate work areas. If the speed limit is reduced in the work area, speed limit signs shall have the R2-1a-24 sign placed below.
- G20-55-96 sign is not required if work is less than 15 days.

KEY

≡ Type III barricade

┌ Sign

ADVANCE WARNING SIGN SPACING			
Road Type	Distance Between Signs Min. (ft)		
	A	B	C
Urban - Low Speed (30 mph or less)	150	150	150
Urban - Low Speed (over 30 to 40 mph)	280	280	280
Urban - High Speed (over 40 mph to 50 mph)	360	360	360
Rural - High Speed (over 50 mph to 65 mph)	720	720	720
Urban Expressway and Freeway (55 mph to 60 mph)	850	1350	2200
Rural Expressway and Freeway (70 mph to 75 mph)	1000	1500	2640
Interstate/4-Lane Divided (Maintenance and Surveying)	750	1000	1500


NORTH DAKOTA
DEPARTMENT OF TRANSPORTATION
9-27-13
REVISIONS

DATE	CHANGE

This document was originally issued and sealed by Roger Weigel Registration Number PE-2930, on 09/27/13 and the original document is stored at the North Dakota Department of Transportation

CONSTRUCTION TRUCK AND TEMPORARY DETOUR LAYOUTS

D-704-22



- Notes
1. Barricades placed on roadway shall be on a moveable assembly. Signs placed on the roadway shall be placed on skid mounted assemblies. Where necessary, safe speed to be determined by the Engineer.
 2. The reduced speed limit shall be determined dependent on the in place speed limit before construction. The speed limit reduction should not exceed 10 mph below the existing speed limit, unless the design speed of the work zone feature has been reduced below the 10 mph. In this case, the speed limit reduction shall not exceed 30 MPH. Where speed limits are to be reduced more than 30 MPH, a second speed limit sign shall be installed with the desired speed reduction but shall not exceed 30 MPH. The second speed limit sign shall be placed at 1/2 B.
 3. When warning signs are used in urban areas and the signs are not portable, flags shall be installed. The flags shall be 24 inches square, mounted perpendicular to the edges of the diamond sign, and at such a distance above the edge so that when the flag is limp it will not touch the sign. Rural areas will not require flags.
 4. Existing speed limit signs within a reduced speed zone shall be covered. Obliterated or covered pavement marking shall be paid for as Obliteration of Pavement Marking. The covering shall be approved by the engineer.
 5. The contractor has the option of using portable sign supports in lieu of post mounted signs in accordance with the NDDOT Standard Specifications.
 6. The contractor shall install the G20-1b-60 sign when work is suspended for winter.
 7. If existing stop sign is in place, a 48" stop sign is not required.
 8. G20-55-96 sign is not required if this standard is part of other traffic control layouts with this sign or the work is less than 15 days.

KEY

- Type III barricade
- Work area
- Sign
- Flagger


Road Type	ADVANCE WARNING SIGN SPACING		
	Distance Between Signs Min. (ft)		
	A	B	C
Urban - Low Speed (30 mph or less)	150	150	150
Urban - Low Speed (over 30 to 40mph)	280	280	280
Urban - High Speed (over 40 mph to 50 mph)	360	360	360
Rural - High Speed (over 50 mph to 65 mph)	720	720	720
Urban Expressway and Freeway (55 mph to 60 mph)	850	1350	2200
Rural Expressway and Freeway (70 mph to 75 mph)	1000	1500	2640
Interstate/4-Lane Divided (Maintenance and Surveying)	750	1000	1500

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-27-13	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by Roger Weigel Registration Number PE-2930, on 09/27/13 and the original document is stored at the North Dakota Department of Transportation

MISCELLANEOUS SIGN LAYOUTS


D-704-26



TYPE Y
To be used where the haul road crosses a highway outside a major work area.




TYPE AA
To be used where survey crew is being used




TYPE KK
To be used at major intersections within pilot car control area


- Notes
- The speed limit shall be re-established. The exact speed limit shall be determined in the field, dependent on location and conditions.
 - The reduced speed limit shall be determined dependent on the in place speed limit before construction. The speed limit reduction should not exceed 10 mph below the existing speed limit, unless the design speed of the work zone feature has been reduced below the 10 mph. In this case, the speed limit reduction shall not exceed 30 MPH. Where speed limits are to be reduced more than 30 MPH, a second speed limit sign shall be installed with the desired speed reduction but shall not exceed 30 MPH. The second speed limit sign shall be placed at 1/2 B.
 - When warning signs are used in urban areas and the signs are not portable, flags shall be installed. The flags shall be 24 inches square, mounted perpendicular to the edges of the diamond sign, and at such a distance above the edge so that when the flag is limp it will not touch the sign. Rural areas will not require flags.
 - Existing speed limit signs within a reduced speed zone shall be covered.
 - The contractor has the option of using portable sign supports in lieu of post mounted signs in accordance with the NDDOT Standard Specifications.
 - G20-55-96 signs are not required if this standard is part of other traffic control layouts, or the work is less than 15 days.
 - When a pilot car operation is used, place a G20-4b-36 "Wait For Pilot Car" sign at major intersections within pilot car control area.




TYPE BB
To be used within a major work area where the sign conditions exist




TYPE CC
To be used where the sign conditions exist



TYPE DD
To be used where the sign conditions exist




TYPE Z
To be used where speed zone is needed




TYPE JJ
To be used where there is a break in the pavement. These signs may be skid mounted or post mounted and shall be installed when conditions exist and removed when not applicable.

Longitudinal Buffer Space	
*Speed (mph)	Length Min (feet)
20	115
25	155
30	200
35	250
40	305
45	360
50	425
55	495
60	570
65	645
70	730
75	820


* Posted speed, off-peak 85th percentile speed prior to work starting, or the anticipated operating speed in mph.



TYPE GG
To be used where a difference of elevation between lanes exist



TYPE EE
To be used where the sign conditions exist



TYPE FF
To be used where the sign conditions exist

KEY

Sign (represented by a vertical line with a horizontal bar)

Flagger (represented by a square with a diagonal line)

Cones (represented by a triangle)







Road Type	Distance Between Signs Min. (ft)		
	A	B	C
Urban - Low Speed (30 mph or less)	150	150	150
Urban - Low Speed (over 30 to 40 mph)	280	280	280
Urban - High Speed (over 40 mph to 50 mph)	360	360	360
Rural - High Speed (over 50 mph to 65 mph)	720	720	720
Urban Expressway and Freeway (55 mph to 60 mph)	850	1350	2200
Rural Expressway and Freeway (70 mph to 75 mph)	1000	1500	2640
Interstate/4-Lane Divided (Maintenance and Surveying)	750	1000	1500

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-27-13	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by Roger Weigel Registration Number PE-2930, on 09/27/13 and the original document is stored at the North Dakota Department of Transportation

TRAFFIC CONTROL PLAN FOR MOVING OPERATIONS

D-704-27



Sign Details



- Notes
1. If the contractor chooses to place more vehicles in the convoy than are shown, these vehicles shall have the truck mounted attenuator and shall be at the contractor's expense.
 2. Shadow and work vehicles shall display yellow rotating beacons or strobe lights unless otherwise stated elsewhere in the plans.
 3. Flashing arrow panels shall be Type B or Type C. The panel operation shall be controlled from inside the vehicle.
 4. Each vehicle shall have two-way electronic communication capability.
 5. When work convoys must change lanes, shadow vehicle 1 should change lanes first to shadow other convoy vehicles.
 6. Vehicle spacing between the shadow vehicle 1 and shadow vehicle 2 will vary depending on sight distance restrictions. Motorists approaching the work convoy should be able to see the trail vehicle in time to slow down and/or change lanes as they approach the shadow vehicle.
 7. Sign Colors
Letters = Black
Border = Black
Background = Orange
 8. Shadow vehicle 2 may be used as the paint tender vehicle.
 9. Sign CW21-10A shall only be used during a painting operation.
 10. On two lane - two way roadways, the work and shadow vehicles should pull over periodically to allow motor vehicle traffic to pass.


KEY	
	Sign
	Truck mounted attenuator
	Flashing arrow panels:
	Right directional
	Left directional
	Double arrow directional
	Caution Mode

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-27-13	
REVISIONS	
DATE	CHANGE
6-18-14	Removed shadow vehicle 2 on two lane roadways

This document was originally issued and sealed by
 Roger Weigel
 Registration Number
 PE-2930,
 on 06/18/14 and the original document is stored at the
 North Dakota Department
 of Transportation

SIGN LAYOUT FOR ONE LANE CLOSURE DIVIDED HIGHWAY MOVING OPERATION


D-704-32



Longitudinal Buffer Space	
*Speed (mph)	Length Min (feet)
20	115
25	155
30	200
35	250
40	305
45	360
50	425
55	495
60	570
65	645
70	730
75	820

* Posted speed, off-peak 85th percentile speed prior to work starting, or the anticipated operating speed in mph.

Road Type	Distance Between Signs Min. (ft)		
	A	B	C
Urban - Low Speed (30 mph or less)	150	150	150
Urban - Low Speed (over 30 to 40 mph)	280	280	280
Urban - High Speed (over 40 mph to 50 mph)	360	360	360
Rural - High Speed (over 50 mph to 65 mph)	720	720	720
Urban Expressway and Freeway (55 mph to 60 mph)	850	1350	2200
Rural Expressway and Freeway (70 mph to 75 mph)	1000	1500	2640
Interstate/4-Lane Divided (Maintenance and Surveying)	750	1000	1500




Notes

- If the moving operation is not visible to the motorist from the end of the taper, an additional sequencing arrow panel should be provided near the work area placed in the closed lane.
- Variables
 S = Numerical value of speed limit or 85th percentile.
 W = The width of the taper.
 L = Minimum length of taper, or S x W for freeways, expressways, and all other roads with speeds of 45 mph or greater, or W x S² / 60 for urban, residential, and other streets with speeds of 40 mph or less.
- Delineator drums used for tapering traffic shall be spaced at the dimension "S".
- Sequencing Arrow Panels
 Panels should normally be placed at the beginning of the taper. Where shoulder width does not provide sufficient room, the panel should be moved closer to the work area so that it can be placed on the roadway surface.
 Type A shall be used on roadways with slow moving traffic speeds and low volume (25 mph & 750 ADT or less).
 Type B shall be used on roadways with moderate traffic speeds and volumes (40 mph and 5000 ADT or less).
 Type C shall be used on roadways with high traffic speeds and volumes (over 40 mph and 5000 ADT).
- The speed limit shall be re-established. The exact speed limit shall be determined in the field, dependent on location and conditions.
- The reduced speed limit shall be determined dependent on the in place speed limit before construction. The speed limit reduction should not exceed 10 mph below the existing speed limit, unless the design speed of the work zone feature has been reduced below the 10 mph. In this case, the speed limit reduction shall not exceed 30 MPH. Where speed limits are to be reduced more than 30 MPH, a second speed limit sign shall be installed with the desired speed reduction but shall not exceed 30 MPH. The second speed limit sign shall be placed at 1/2 B.
- When warning signs are used in urban areas and the signs are not portable, flags shall be installed. The flags shall be 24 inches square, mounted perpendicular to the edges of the diamond sign, and at such a distance above the edge so that when the flag is limp it will not touch the sign. Rural areas will not require flags.
- Existing speed limit signs within a reduced speed zone shall be covered.
- The contractor has the option of using portable sign supports in lieu of post mounted sign in accordance with the NDDOT Standard Specifications.
- If the shoulder is 8' or wider, a shoulder taper shall be provided.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-27-13	
REVISIONS	
DATE	CHANGE
6-24-14	Revised Note 9

This document was originally issued and sealed by
Roger Weigel
 Registration Number
 PE-2930,
 on 6/24/14 and the original document is stored at the
 North Dakota Department
 of Transportation

SIGN LAYOUT FOR ONE LANE CLOSURE





Speed (mph)*	Length Min (feet)
20	115
25	155
30	200
35	250
40	305
45	360
50	425
55	495
60	570
65	645
70	730
75	820

*Posted speed, off-peak 85th percentile speed prior to work starting, or the anticipated operating speed in mph.

KEY	
	Type I barricade
	Type II barricade
	Type III barricade
	Sign
	Delineator drum
	Work area
	Flagger
	Sequencing arrow panel
	Tubular markers

- Notes:
- Install advance signs for flagging when flaggers are flagging.
 - Move the advanced flagger sign and speed limit signs as the work area moves through the construction zone. When the work area is not visible from the flagger, move the flagger station so the work area is visible. Place the 40 mph speed limit sign at 1/2 A in advance of the flagger sign and move the 60 mph speed limit sign. Cover or remove the 40 mph speed limit and the Minimum Fee \$80 signs upon completion of the work day or when workers are not present. Determine the exact speed limit in the field, dependent on location and conditions.
 - Approaches: When the work area encompasses an approach, install a 40 mph speed limit sign to control the approach. Cover the existing stop sign and install a new portable stop sign when the approach is on the side of the lane closure. Remove the approach speed limit sign once the main line 40 mph speed zone is moved past the approach.
 - Variables:
 - S= Numerical value of speed limit or 85th percentile
 - W= The width of taper.
 - L= Minimum length of taper, or $S \times W$ for freeways, expressways, and all other roads with speeds of 45 mph or greater, or $(W \times S \times S) / 60$ for urban, residential, and other streets with speeds of 40 mph or less.
 - Space delineator drums for tapering traffic at the dimension "S". Space tubular markers used for tangents at 2 times dimension "S".
 - Place sequencing arrow panels at the beginning of the taper when possible. Where shoulder width does not provide sufficient room, move the panel closer to the work area and place on the roadway surface.
 - Use Type A on roadways with slow moving traffic speeds and low volume (25 mph or less and 750 ADT or less).
 - Use Type B on roadways with moderate traffic speeds and volumes (40 mph or less and 5000 ADT or less).
 - Use Type C on roadways with high traffic speeds and volumes (over 40 mph or over 5000 ADT).
 - Re-establish the speed limit. Determine the exact speed limit in the field, dependent on location and conditions.
 - Cover existing speed limit signs within a reduced speed zone.
 - Install flags when warning signs are used in urban areas and the signs are not portable. Mount 24 inch square flags perpendicular to the edges of the diamond sign, and at such a distance above the edge that the flag does not touch the sign when limp. Rural areas will not require flags.
 - Determine the reduced speed limit dependent on the in place speed limit before construction. Do not exceed a speed limit reduction of 10 mph below the existing speed limit, unless the design speed of the work zone feature has been reduced below the 10 mph. Where speed limits are to be reduced more than 30 mph, install a second speed limit sign so no single speed reduction exceeds 30 mph. Place the second speed limit sign at 1/2 B.
 - The contractor has the option of using portable sign supports in lieu of post mounted signs in accordance with NDDOT Standard Specifications.
 - Sign G20-55-96 is not required if this standard is part of other traffic control layouts or the work is less than 15 days.




ADVANCE WARNING SIGN SPACING			
Road Type	Distance Between Signs Min (ft)		
	A	B	C
Urban - Low Speed (30 mph or less)	150	150	150
Urban - Low Speed (over 30 to 40 mph)	280	280	280
Urban - High Speed (over 40 mph to 50 mph)	360	360	360
Rural - High Speed (over 50 mph to 65 mph)	720	720	720
Urban Expressway and Freeway (55 mph to 60 mph)	850	1350	2200
Rural Expressway and Freeway (70 mph to 75 mph)	1000	1500	2640
Interstate/4-Lane Divided (Maintenance and Surveying)	750	1000	1500

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-26-2012	
REVISIONS	
DATE	CHANGE
3-15-16	Removed Do Not Pass signs and updated notes

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 03/15/2016 and the original document is stored at the North Dakota Department of Transportation

TRAFFIC CONTROL SYSTEM LANE SHIFT BETWEEN A LANE CLOSURE AND AN OPPOSITE LANE CLOSURE

D-704-34A



W1-4-48
Post Mounted

QUANTITIES	
TYPE III BARRICADES	2 Each
DELINEATOR DRUMS	14 Each
TUBULAR MARKERS	14 Each
RAISED PAVEMENT MARKERS (White)	Varies
OBLITERATION OF PAVEMENT MARKING	Varies

KEY			
	Work area		Delineator drum
	Type III barricade		Tubular markers
	Traffic Direction		Sign

LEGEND	
E	Obliteration of pavement marking (10' line, 30' skip centerline)
G	Raised pavement markers (white) 5' ctrs.

Notes

- Variables
 - S = Numerical value of posted speed limit, off-peak 85th percentile speed prior to work starting, or the anticipated operating speed in mph.
 - W = Width of offset in feet.
 - L = Taper length in feet. Speeds 40 mph or less $L = WS^2 / 60$. Speeds 45 mph or greater $L = WS$.
- Signs and barricade shown to be placed on roadway shall be placed on moveable assemblies.
- Existing speed limit signs within a reduced speed zone shall be covered.
- Obliterated or covered pavement marking shall be paid for as Obliteration of Pavement Marking. The covering shall be approved by the Engineer.
- The contractor has the option of using portable sign supports in lieu of post mounted sign as shown on the standard drawings in accordance with NDDOT Standard Specifications.
- When placing traffic control devices, speed reductions will be necessary. The "Minimum Fee \$80" sign shall be placed below these speed limit signs.
- Obliteration of pavement marking (10' line, 30' skip, centerline) and raised pavement markers are not necessary when the work is 14 days or less.

Longitudinal Buffer Space	
*Speed (mph)	Length Min (feet)
20	115
25	155
30	200
35	250
40	305
45	360
50	425
55	495
60	570
65	645
70	730
75	820

* Posted speed, off-peak 85th percentile speed prior to work starting, or the anticipated operating speed in mph.


ADVANCE WARNING SIGN SPACING			
Road Type	Distance Between Signs Min. (ft)		
	A	B	C
Urban - Low Speed (30 mph or less)	150	150	150
Urban - Low Speed (over 30 to 40 mph)	280	280	280
Urban - High Speed (over 40 mph to 50 mph)	360	360	360
Rural - High Speed (over 50 mph to 65 mph)	720	720	720
Urban Expressway and Freeway (55 mph to 60 mph)	850	1350	2200
Rural Expressway and Freeway (70 mph to 75 mph)	1000	1500	2640
Interstate/4-Lane Divided (Maintenance and Surveying)	750	1000	1500

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-26-2012	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by
 Roger Weigel,
 Registration Number
 PE- 2930,
 on 10/26/12 and the original document is stored at the
 North Dakota Department
 of Transportation

PORTABLE SIGN SUPPORT ASSEMBLY

D-704-50



Notes:


- ① The maximum weight of the assembly is 250 pounds.
- ② Use a 14" wheel and tire.
- ③ Automotive and equipment axle assemblies may not be used for trailer-mounted sign supports.
- ④ Other NCHRP 350 crash tested assemblies are acceptable.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
11-23-10	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 11/23/10 and the original document is stored at the North Dakota Department of Transportation.

BITUMINOUS LABORATORY

D-706-1



AIR CONDITIONER (110 VOLT) 8,000 BTU


NOTES:

There shall be a minimum of six screened exterior windows on two or more sides, with a minimum of one window in each room. Windows shall have a minimum area of 4 square feet each. Suggested locations are shown on drawing.

The lab shall be equipped with a 1'x1' shelf at 36" above the regular countertop to hold the stock solution container for the Sand Equivalent test.

The sink shall be double compartment stainless steel. Each compartment shall be a minimum of 16"x14"x10" deep. The sink shall be drained to an outside waste line. A trap is not required. Water service lines shall be copper or plastic having a diameter of 1/2 inch.

The lab shall be equipped with an exhaust fan capable of removing inside air at a rate of 400 CFM.



The fresh air vent shall be hinged to open or close manually.

24" x 48" table shall be provided capable of holding a 200 lb. masonry saw. The table shall have a minimum clearance of 36" overhead.


The water supply tank shall have a capacity of 500 gallons.

Steps and a landing for each set of steps shall be provided for each of two entrance doors. Steps for each area shall be made of, or covered with, a material providing for a non-slip surface. They shall be heavy duty steps that are capable of withstanding heavy loadings and extensive use.

The pressure tank on the pump shall be 20 gallon capacity.

Locks, latches, and hinges for main doors shall be heavy duty type to withstand the intense use in service.

The wall between the office and the work area shall be properly insulated to prevent the transmission of heat and noise.



The floor beneath the marshall area shall be heavily reinforced.

The lab shall be equipped with steel cable tie downs and ground anchors at each corner of the lab.




Electrical service entrance shall be wired for 100 amps, and have separate circuits for air conditioners. Convenience outlets shall have a minimum spacing of four feet in counter areas.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-03-13	
REVISIONS	
DATE	CHANGE
07-30-14	Changed standard's title and revised notes.

This document was originally issued and sealed by
 Roger Weigel
 Registration Number PE-2930,
 on 07/30/14 and the original document is stored at the North Dakota Department of Transportation

(EXPRESSWAY-FREEWAY USE) MILE POSTS

D-754-20



(A) 8' Clearance to finished shoulder or in line with existing delineator posts

- NOTES:**
- Installation: Posts shall be installed along right shoulder in line with delineators.
 - Mile Sign Backing: Backing shall be fabricated of 0.080 aluminum. Sheeting shall conform to section 894.01 of the Standard Specifications.
 - Posts: Posts shall conform to section 894.03 of the Standard Specifications.
 - Fasteners: The mile signs shall be attached to the post by tension pin type fastener or other suitable vandal resistant non-rust fastener.
 - Reflective Sheeting: Sheeting shall be Type IV.
 - Numbers: Numbers shall be of the series shown and may be screened or applied copy. Screening and reflective sheeting for applied copy shall conform to section 754 & 894 of the Standard Specifications.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
12-1-10	
REVISIONS	
DATE	CHANGE
7-8-14	Revised post and reflective sheeting notes


This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 7/8/14 and the original document is stored at the North Dakota Department of Transportation

PERFORATED TUBE ASSEMBLY DETAILS

D-754-23


Notes:

1. Curbed Roadways: The clearance from the face of the curb should be 3' except where right of way or sidewalk width is limited, a minimum clearance of 2' shall be provided. The horizontal clearance may need to be increased to maintain a minimum sidewalk clear width of 4' from the sign support, not including any attached curb.
2. Minimum vertical clearance: Signs installed at the side of the road in rural districts shall be at least 5' measured from the bottom of the sign to the edge of the driving lane or auxiliary lane. Where parking or pedestrian movements occur, the clearance to the bottom of the sign shall be at least 7'.
- Signs on expressways shall be installed with a minimum height of 7'.
- Adopt-a-highway signs installed on Freeways shall be at least 7' above the edge of the driving lane.
- The vertical clearance shall have a maximum height of 6" above the vertical clearance specified above.
3. Offset signs: Where signs are placed at least 30 feet or more from the edge of the traveled way, the height to the bottom of such sign shall be 5' above the edge of the driving lane.
4. The clearance from edge of shared use path to edge of sign should be 3' except where width is limited, a minimum clearance of 2' shall be provided.




Typical Section (without curb)

Horizontal Clearance Table	
Shoulder Width ft	Offset ft
0 to 2	16
>2 to 4	18
>4 to 6	20
>6 to 8	22
>8 to 10	24




Typical Section (with curb)
Residential or Business District



Stop Sign Location
Wide Throat Intersection

This layout is to be used for the placement of "Stop" signs.

Radius ft.	Y-max. ft.	Y-min. ft.
40	50	15
45	50	18
50	50	21
55	50	25
60	50	28
65	50	32
70	50	35
75	50	39
80	50	43





Shared Use Path
Bicycle - Pedestrian Path

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-3-13	
REVISIONS	
DATE	CHANGE
7-8-14	Revised note 2, added note 4.

This document was originally issued and sealed by
Roger Weigel
 Registration Number
 PE-2930,
 on 7/8/14 and the original document is stored at the
 North Dakota Department
 of Transportation


Number of Posts	Telescoping Perforated Tube						
	Post Size In.	Wall Thickness Gauge	Sleeve Size In.	Wall Thickness Gauge	Slip Base	Anchor Size Without Slip Base In.	Anchor Wall Thickness Gauge
1	2	12			No	2 1/2	12
1	2 1/2	12			No	2 1/2	12
1	2 1/2	12			(B)	3(C)	7
1	2 1/2	10			Yes		7
1	2 1/2	12	2 1/2(D)	12	Yes		7
1	2 1/2	12	2 1/2	12	Yes		7
2	2 1/2	10			Yes		7
2	2 1/2	12	2 1/2(D)	12	Yes		7
2	2 1/2	12	2 1/2	12	Yes		7
3 & 4	2 1/2	12			Yes		7
3 & 4	2 1/2	10			Yes		7
3 & 4	2 1/2	12	2 1/2	12	Yes		7
3 & 4	2 1/2	12	2 1/2(D)	12	Yes		7
3 & 4	2 1/2	10	2 1/2	10	Yes		7

(B) - The 2 1/2", 12 gauge posts do not need breakaway bases when placed in standard soils, but require a shim as specified by the manufacturer. The breakaway base is required when the support is placed in weak soils. The Engineer shall determine if the soils are weak. Weak soils are classified as boggy, wet, or loose soil areas.
 (C) - 3" anchor unit
 (D) - 2 1/2" x 12 ga. x 18" minimum length external sleeve required.




MULTI-DIRECTIONAL SLIP BASE ASSEMBLY:
 2 1/2" x 12 ga. may be inserted with 2 1/2" x 12 ga. & 2 1/2" 10 ga. may be inserted with 2 3/8" x 10 ga. to achieve higher load ability.

Mounting Details Perforated Tube




SLIP BASE FOR 2 1/2" POST



2 1/2" SQUARE POST RECEIVER

Ductile Iron Casting class 65-45-12. Hot Dip Galvanize ASTM A153




SLIP BASE DETAIL

Properties of Telescoping Perforated Tubes						
Tube Size In.	Wall Thickness in.	U.S. Standard Gauge	Weight Per Foot Lbs.	Moment of Inertia In. ⁴	Cross Sect. Area In. ²	Section Modulus In. ³
1 1/2 x 1 1/2	0.105	12	1.702	0.129	0.380	0.172
2 x 2	0.105	12	2.416	0.372	0.590	0.372
2 1/2 x 2 1/2	0.105	12	2.773	0.561	0.695	0.499
2 3/8 x 2 3/8	0.135	10	3.432	0.605	0.841	0.590
2 1/2 x 2 1/2	0.105	12	3.141	0.804	0.803	0.643
2 1/2 x 2 1/2	0.135	10	4.006	0.979	1.010	0.783

The 2 3/8" size 10 gauge is shown as 2.19" size on the plans; The 2 1/2" size is shown as 2.51" size on the plans.

NOTE:

- 4" Vertical clearance of anchor or breakaway base. The 4" x 60" measurement shall be made above and below post location and also back and ahead of post.
- Anchor material shall be 7 gauge H.R.P.O. Commercial quality ASTM A569 and 3" x 3" x 7" gauge ASTM A500 grade B. Anchor shall have a yield strength 43.9 KSI and tensile strength of 59.3 KSI. Anchor shall be hot dipped galvanized per ASTM A123/153. All tolerances on anchor unit and slip base bottom assembly are +/- 0.005" unless otherwise noted.
- When used in concrete sidewalk, anchor shall be the same concept without the wings.
- Four post signs shall have over 8" between the first and fourth posts.
- Installation procedures as per manufacturers recommendation.
- Concrete fasteners for surface mount breakaway base shall be a minimum 1/2" diameter x 4" grade 8.




SURFACE MOUNT ANCHOR BASE

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-6-09	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930, on 08/06/09 and the original document is stored at the North Dakota Department of Transportation

SHOULDER BOLT

Shimming agent to reduce tolerance between 3" anchor unit and 2 1/2" post. (standard 3/8" diameter grade 8 bolt may be used with proper shim)




3" ANCHOR UNIT


Mounting Details Perforated Tube

Note:

- Horizontal stringers - In lieu of perforated tubes, the contractor may substitute z bar stringers. The z bar stringers shall be 1 1/2" x 3/16" thick, 1.08 lbs./ft aluminum or 3.16 lbs./ft steel.
- Metal washers used on sign face shall have a minimum outside diameter of 5/16" ± 1/64" and 10 gauge thickness.
- No Parking Signs: All no parking signs with directional arrows shall be placed at a 30 to 45 degree angle with the line of traffic flow. No parking signs required at the above angles may have the support turned to the correct angle. If the no parking sign is placed with another sign that has to be placed at a 90 degree angle with the line of traffic flow, the detailed angle strap should be used to mount the no parking sign. Flat washers and lock washers shall be used with all nylon washers.
- In lieu of using the bent bolt to attach the post to the stringer, the contractor may choose to punch the sign backing and place the bolt through the sign, the stringer and the post.
- 4" vertical clearance of anchor or breakaway base. The 4" x 60" measurement shall be made above and below post location and also back and ahead of post.




Side View




Top View


STRINGER MOUNTING
(WITH STRINGER IN FRONT OF POST)



STREET NAME SIGNS
AND ONE WAY SIGNS
SINGLE POST ASSEMBLY
ONE STRINGER OR
BACK TO BACK MOUNTING




Side View




Top View


STRAP DETAIL



ANCHOR UNIT AND
POST ASSEMBLY




BOLT MOUNTING



Top View

BACK TO BACK
MOUNTING



Properties of Telescoping Perforated Tubes						
Tube Size In.	Wall Thickness In.	U.S. Standard Gauge	Weight Per Foot Lbs.	Moment of Inertia In. ⁴	Cross Sect. area In. ²	Section Modulus In. ³
1 1/2 x 1 1/2	0.105	12	1.702	0.129	0.380	0.172
2 x 2	0.105	12	2.416	0.372	0.590	0.372
2 1/4 x 2 1/4	0.105	12	2.773	0.561	0.695	0.499
2 3/8 x 2 3/8	0.135	10	3.432	0.605	0.841	0.590
2 1/2 x 2 1/2	0.105	12	3.141	0.804	0.803	0.643
2 1/2 x 2 1/2	0.135	10	4.006	0.979	1.010	0.783

The 2 3/8" size 10 gauge is shown as 2.19" size on the plans.
The 2 1/2" size is shown as 2.51" size on the plans.


Number of Posts	Telescoping Perforated Tube						
	Post Size In.	Wall Thickness Gauge	Sleeve Size In.	Wall Thickness Gauge	Slip Base	Anchor Size Without Slip Base In.	Anchor Wall Thickness Gauge
1	2	12			No	2 1/4	12
1	2 1/4	12			No	2 1/2	12
1	2 1/2	12			(B)	3(C)	7
1	2 1/2	10			Yes		7
1	2 1/4	12	2 1/2(D)	12	Yes		7
1	2 1/2	12	2 1/4	12	Yes		7
2	2 1/2	10			Yes		7
2	2 1/4	12	2 1/2(D)	12	Yes		7
2	2 1/2	12	2 1/4	12	Yes		7
3 & 4	2 1/2	12			Yes		7
3 & 4	2 1/2	10			Yes		7
3 & 4	2 1/2	12	2 1/4	12	Yes		7
3 & 4	2 1/4	12	2 1/2(D)	12	Yes		7
3 & 4	2 1/2	10	2 3/8	10	Yes		7

(B) - The 2 1/2", 12 gauge posts do not need breakaway bases when placed in standard soils, but require a shim as specified by the manufacturer. The breakaway base is required when the support is placed in weak soils. The Engineer shall determine if the soils are weak. Weak soils are classified as boggy, wet, or loose soil areas.
(C) - 3" anchor unit
(D) - 2 1/2" x 12 ga. x 18" minimum length external sleeve required.


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-6-09	
REVISIONS	
DATE	CHANGE
7-8-14	Revised Note 3

This document was originally issued and sealed by
Roger Weigel,
Registration Number
PE- 2930 ,
on 7/8/14 and the original document is stored at the
North Dakota Department
of Transportation




SIGN PUNCHING, STRINGER AND SUPPORT LOCATION
DETAILS REGULATORY, WARNING AND GUIDE SIGNS






Assembly No. 18



Assembly No. 19



Assembly No. 20



Assembly No. 21

Notes:


1. See Standard D-754-25 for mounting details.
2. The minimum sign backing material thickness shall be 0.100 inch.
3. Perforated square tube stringer shall be 1½" x 1½".
4. All holes shall be punched round for ⅜" bolt.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
12-1-10	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 12-1-10 and the original document is stored at the North Dakota Department of Transportation

SIGN PUNCHING, STRINGER AND SUPPORT LOCATION DETAILS - ROUTE MARKER SIGNS


D-754-60



1 Post



2 Posts




3 Posts


Notes:

1. The minimum sign backing material thickness shall be 0.100 inch.
2. Perforated square tube stringer shall be 1½" x 1½".
3. All holes shall be punched round for ⅜" bolt.


ASSEMBLY NO. 403



1 Post




2 Posts




3 Posts


ASSEMBLY NO. 404



1 Post



2 Posts



3 Posts

ASSEMBLY NO. 405

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION 8-22-12	
REVISIONS	
DATE	CHANGE




This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 8/22/12 and the original document is stored at the North Dakota Department of Transportation.

SIGN PUNCHING, STRINGER AND SUPPORT LOCATION DETAILS - ROUTE MARKER SIGNS




D-754-74

Notes:




1. The minimum sign backing material thickness shall be 0.100 inch.
2. Perforated square tube stringer shall be 1½"x1½".
3. All holes shall be punched round for ⅜" bolt.



ASSEMBLY NO. 435



ASSEMBLY NO. 436




ASSEMBLY NO. 437

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-25-12	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 9/25/2012 and the original document is stored at the North Dakota Department of Transportation

SIGN PUNCHING, STRINGER AND SUPPORT LOCATION DETAILS FOR STREET NAME SIGNS AND 911 SIGNS

- A - Single sign
- B - Single sign back to back
- C - Single sign each direction
- D - Single sign one direction, back to back other direction
- E - Back to back both directions




Special Assembly 1 (A, B, C, D or E)




Special Assembly 2 (A, B, C, D or E)


Special Assembly 3 (A, B, C, D or E)



Special Assembly 4 (A, B, C, D or E)




Special Assembly 5 (A, B, C, D or E)




Sleeve Splice Detail


Note: The splice method may be used upon approval of the engineer.



Sign Stringer Detail




Detail A or B



Detail D or E


Note: See Standard Drawing D-754-86 for 911 support information and sign layout details.



Intersection Layout

Note: This layout is to be used for street name signs or 911 signs that are used with Special Assembly 1.

Sign Arrangements




Detail C


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-3-13	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by
 Roger Weigel
 Registration Number
 PE-2930,
 on 10/3/13 and the original document is stored at the
 North Dakota Department
 of Transportation

RUMBLE STRIPS
DIVIDED HIGHWAYS (NON-INTERSTATE)




Divided Highways (Non-Interstate)




Inset B - Shoulder Rumble Strip

NOTES:


1) Discontinue rumble strips through the entire length of turn lanes & ramps, 100' before turn lane tapers, 100' before or after ramp tapers, and at the radius of a paved or gravel highway, section line, approach, or private drive as shown below.



Profile of Rumble Strips - Bituminous and PCC Pavements






Discontinue rumble strip approx. 12" on both sides of PCC transverse joint



NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
12-29-09	
REVISIONS	
DATE	CHANGE
2-25-10	Note 4 was added.
9-8-11	Revised Notes and D-760-2.

This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930 , on 9/8/11 and the original document is stored at the North Dakota Department of Transportation


SAW SLOTTED RUMBLE STRIPS AT INTERSECTIONS




NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
12-29-09	
REVISIONS	
DATE	CHANGE
2-22-10	Saw Slotted width revised.
2-25-10	Note 7 was added.
9-8-11	Revised Notes and D-760-5.
7-7-14	Deleted Notes.

This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930 , on 7/7/14 and the original document is stored at the North Dakota Department of Transportation


PAVEMENT MARKING




Two Lane Two Way
RURAL ROADWAY




Two Lane Roadway
INTERSTATE HIGHWAY
Concrete Section




RURAL FIVE LANE ROADWAY
Concrete Section




Two Lane Divided
Rural Roadway
PRIMARY HIGHWAY
Asphalt Section




RURAL FIVE LANE ROADWAY
Asphalt Section




URBAN FIVE LANE SECTION
Concrete Section




Two Lane Roadway
PRIMARY HIGHWAY
Concrete Section




URBAN FIVE LANE SECTION
Asphalt Section




RURAL FOUR LANE ROADWAY
Asphalt Section




Two Lane Roadway
INTERSTATE HIGHWAY
Asphalt Section




RURAL FOUR LANE ROADWAY
Concrete Section



URBAN FOUR LANE SECTION
Asphalt Section



URBAN FOUR LANE SECTION
Concrete Section



CENTERLINE PAVEMENT MARKING SKIP SPACING DETAIL

NOTES:
1. Edge lines shall be continued through private drives and field drives and broken for intersections.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
12-1-10	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 12-1-10 and the original document is stored at the North Dakota Department of Transportation




PAVEMENT MARKING FOR STANDARD 90 DEGREE FLARED INTERSECTION

(Center Left Turn Lane on Major Road)

D-762-6

Notes

- At "T" intersections (3-leg), additionally install left turn pavement marking message arrow.




- 4" Marking
- 8" Marking
- 24" Marking

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
3-29-16	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by Roger Weigel Registration Number PE-2930, on 03/29/16 and the original document is stored at the North Dakota Department of Transportation

SHORT-TERM PAVEMENT MARKING

D-762-11




Painted or Tape Lines




Raised Pavement Markers

TWO-LANE TWO-WAY ROADWAY




Painted or Tape Lines




Raised Pavement Markers

FOUR LANE ROADWAY




Painted or Tape Lines




Raised Pavement Markers

FIVE LANE ROADWAY TWO WAY LEFT TURN



Painted or Tape Lines



Raised Pavement Markers

FIVE LANE ROADWAY WITH MARKED ISLANDS

NOTES:

- Two-lane two-way roadways shall have no passing zones placed as shown. No passing zone signs may be placed in lieu of short term no passing zone pavement markings. These signs will be allowed to remain in place for three days, at which time the short term no passing zone pavement marking shall be placed.
- Short term center line stripe (paint) on top lift shall be carefully placed with exact spacing so that the permanent stripe will match when applied.
- Raised markers and tape markings shall be removed after permanent pavement marking has been installed. Removed markings shall become the property of the contractor.




NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
12-1-10	
REVISIONS	
DATE	CHANGE
3-29-16	Re-numbered to be D-762-11 (previously was D-762-6)

This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930, on 03/29/16 and the original document is stored at the North Dakota Department of Transportation



W-BEAM GUARDRAIL GENERAL DETAILS

NOTES:


1. ReflectORIZED plates: Reflector plates shall begin at the first post and be spaced at 25' centers on guardrail less than 250' in length and at 50' centers for guardrail over 250' in length. The reflector shall be the same color as the pavement marking adjacent to that reflector unless noted otherwise on the plans.
2. Manner of replacing bituminous material at guardrail post: All excess earth from excavations for guard posts shall be disposed of as directed by the engineer. Replace bituminous material wherever guardrail is installed after mat has been laid. Cost of excavation and replacing of bituminous material to be included in the price bid for other items.
3. The Object Marker shall fit within the vertical edges of the Impact Plate. The retroreflective sheeting shall be type XI sheeting meeting the requirements of Section 894.02.B of the standard specifications. The sheeting shall be applied to 0.100 Aluminum sheeting meeting the requirements Section 894.01.A. The Object Marker shall attach to the Impact Head Plate with rivets or some other attachment device. The rivets or attachment device shall be non-rust. The stripes shall slope downward toward the roadway side.
4. Guardrail installation height tolerance = $-\frac{1}{4}"$, $+1"$.




REFLECTORIZED PLATE DETAIL
Additional reflectors are added to the W-beam guardrail quantities for placement on end treatment.




W BEAM TERMINAL CONNECTOR




TYPICAL POST ATTACHMENT DETAIL




C6x8 RUB RAIL AND SPLICE PLATE




6"x8" TIMBER POST & BLOCK




SPLICE DETAIL




5/8" Diameter Guardrail Bolt	
L	Thread Length
1 1/4"	Full length thread
2"	1 3/4" Min thread length
9 1/2"	4" Min thread length
18"	4" Min thread length
20"	4" Min thread length
22"	4" Min thread length
25"	4" Min thread length




5/8" Diameter Carriage Bolt	
L	Thread Length
1 1/2"	Full length thread
3"	1 1/2" Min thread length
11"	1 3/4" Min thread length
13"	1 3/4" Min thread length



5/8" CARRIAGE BOLT & NUT



IMPACT HEAD OBJECT MARKER




W-BEAM CROSS SECTION

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-11-13	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 10/11/13 and the original document is stored at the North Dakota Department of Transportation

FLARED ENERGY ABSORBING TERMINAL

D-764-6





ITEM #	QTY	BILL OF MATERIALS
F3000	1	IMPACT HEAD
F1303	1	W-BEAM GUARDRAIL END SECTION, 12 GA
G1203	2	W-BEAM GUARDRAIL, 12 GA
HP1A	1	FIRST POST ASSEMBLY TOP
HP1B	1	FIRST POST ASSEMBLY BOTTOM
HP2A	1	SECOND POST ASSEMBLY TOP
HP2B	1	SECOND POST ASSEMBLY BOTTOM
P671	5	WOOD CRT POST
P675	5	TIMBER BLOCKOUT OR RECYCLED EQUIVALENT
E750	1	BEARING PLATE
S760	1	CABLE ANCHOR BOX
E770	1	BCT CABLE ANCHOR ASSEMBLY
S785	1	GROUND STRUT HINGED POST
HARDWARE (ALL DIMENSIONS IN INCHES)		
B140404	2	1/4 Dia x 4 HEX BOLT
WO14	4	1/4 WASHER
N014	2	1/4 HEX NUT
B580122	17	5/8 Dia x 1 1/4 SPLICE BOLT
B581802	4	5/8 Dia x 10 H.G.R. BOLT (POSTS 3 THRU 6)
B580904A	1	5/8 Dia x 9 HEX BOLT GR 5
W050	5	5/8 WASHER
N050	22	5/8 Dia H.G.R. NUT
B340854A	1	3/4 Dia x 8 1/2 HEX BOLT GR A449
N030	1	3/4 Dia HEX NUT
N100	2	1 ANCHOR CABLE HEX NUT
W100	2	1 ANCHOR CABLE WASHER
SB58A	8	CABLE ANCHOR BOX SHOULDER BOLT
N055A	8	1/2 Dia A325 STRUCTURAL NUT
W050A	16	1 1/16 OD x 3/16 ID A325 STR. WASHER




GENERAL NOTES

- Wood posts are required with the Flared Energy Absorbing Terminal except posts #1 and #2.
- All bolts, nuts, cable assemblies, cable anchors and bearing plates shall be galvanized.
- The lower sections of the posts shall not protrude more than 4 inches above the ground (measured along a 60 inch cord). Site grading may be necessary to meet this requirement.
- Lower post sections shall not be driven with the upper post attached. If the post is placed in a drilled hole, the backfill material must be satisfactory compacted to prevent settlement.
- When rock is encountered during excavation, a 12" diameter post hole 20" deep may be used if approved by the Engineer. Granular material will be placed in the bottom of the hole approximately 2 1/2" deep to provide drainage. The soil tubes shall be field cut to length, placed in the hole and back filled with adequately compacted material excavated from the hole.
- The breakaway cable assembly shall be taut. A locking device (vice grips or channel lock pliers) should be used to prevent cable from twisting when tightening nuts.
- The wood blockouts shall be "toe nailed" to the rectangular wood posts to prevent them from turning when wood shrinks. The nail shall be 20 penny and galvanized.
- The Flared Energy Absorbing Terminal shall be flared only when the approach guardrail is parallel with the roadway. When the approach guardrail is flared at 16:1 to 10:1, the Flared Energy Absorbing Terminal shall have only the flare rate of the guardrail. When the guardrail flare is between 10:1 and 7:1, the Flared Energy Absorbing Terminal shall be turned parallel to the roadway.




POST #1 CONNECTION DETAILS


IMPACT HEAD CONNECTION DETAIL



SECTION B-B
POST 3 THRU 7



SECTION A-A
at Post #2




IMPACT HEAD CONNECTING DETAIL

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-11-13	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by
 Roger Weigel,
 Registration Number
 PE-2930,
 on 10/11/13 and the original document is stored at the
 North Dakota Department
 of Transportation

SPECIAL W-BEAM GUARDRAIL ANCHOR


D-764-14





BCT ANCHOR PLATE




SECTION B-B




BCT CABLE END PLATE




BEARING PLATE




POST SLEEVE




PLAN




BCT CABLE ASSEMBLY



ELEVATION



BCT TERMINAL POST DETAILS




W BEAM END SECTION (FLARED)

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-11-13	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 10/11/13 and the original document is stored at the North Dakota Department of Transportation

TYPICAL GRADING AT OBSTRUCTIONS
WITH W-BEAM GUARDRAIL


D-764-23




TYPICAL SECTION



PLAN LAYOUT
FLARED GUARDRAIL WITH END TERMINAL



PLAN LAYOUT
NON-FLARED GUARDRAIL TANGENT END TERMINAL



PLAN LAYOUT
NON-FLARED GUARDRAIL WITH FLARED END TERMINAL

NOTES:

- (A) Slope flatter than 10:1 may be required to provide proper guardrail height.
- (B) Where normal inslope is 4:1 the added fill shall be 4:1. Where normal inslope is 6:1 the added fill shall be 6:1.
- (C) Measured from top of guardrail to top of surfacing at front face of guardrail.
- (D) Dimension at end terminals may vary per Plan Layouts shown on this sheet.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-3-13	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 10-3-13 and the original document is stored at the North Dakota Department of Transportation