

DESIGN DATA

Traffic	Average Daily		
Current 2016	Pass: 3452	Trucks:1347	Total:4799
Preventive Maintenance			

JOB # 20

NORTH DAKOTA

DEPARTMENT OF TRANSPORTATION

IM-2-094(154)248

Stutsman County

W of CMC 4725 to Jct CMC 4739 EB

Microsurfacing

STATE	PROJECT NO.	PCN	SECTION NO.	SHEET NO.
ND	IM-2-094(154)248	21878	1	1

GOVERNING SPECIFICATIONS:

2014 Standard Specifications adopted by the North Dakota Department of Transportation and the Supplemental Specifications effective on the date the project is advertised.

PROJECT NUMBER \ DESCRIPTION	NET MILES	GROSS MILES
IM-2-094(154)248	10.442	10.442

DESIGNERS

Martin Avelino /s/

STATE COUNTY MAP

APPROVED DATE 5/16/2017

Nathan Haaland /s/

Valley City Assistant District Engineer

ND DEPARTMENT OF TRANSPORTATION

I hereby certify that the attached plans were prepared by me or under my direct supervision and that I am a duly registered professional engineer under the laws of the state of ND.

APPROVED DATE 5/12/2017

Daniel R. Viau /s/

NDDOT - Valley City District

This document was originally issued and sealed by Daniel R. Viau Registration Number PE- 6329, on 5/12/2017 and the original document is stored at the North Dakota Department of Transportation

5/17/20171:16:03 PMamcmahonF:\VC\DESIGNS\Micro Surfacing\I 94 RP 248\001TS\_001\_title.dgn

TABLE OF CONTENTS						STATE	PROJECT NO.	SECTION NO.	SHEET NO.
						ND	IM-2-094(154)248	2	1
PLAN SECTIONS			LIST OF STANDARD DRAWINGS						
Section	Page(s)	Description	Number	Description					
1	1	Title Sheet	D-101-1, 2 ,3	NDDOT Abbreviations					
2	1	Table of Contents	D-101-10	NDDOT Utility Company and Organization Abbreviations					
6	1	Notes	D-101-20, 21	Line Styles					
8	1	Quantities	D-101-30, 31 ,32	Symbols					
10	1 - 2	Basis of Estimate	D-704-3	Lane Markers (Spotting Tab For Seal Projects Only)					
20	1 - 11	General Details	D-704-7	Breakaway Systems For Construction Zone Signs - Perforated Tube					
30	1	Typical Sections	D-704-8	Breakaway Systems For Construction Zone Signs - U-Channel Post					
100	1 - 2	Work Zone Traffic Control	D-704-9	Construction Sign Details - Terminal And Guide Signs					
			D-704-10	Construction Sign Details - Regulatory Signs					
			D-704-11	Construction Sign Details - Warning Signs					
			D-704-12	Shoulder Closure Tapers					
			D-704-13	Barricade And Channelizing Device Details					
			D-704-14	Construction Sign Punching And Mounting Details					
			D-704-22	Construction Truck And Temporary Detour Layouts					
			D-704-27	Traffic Control Plan For Moving Operations					
			D-704-34A	Traffic Control System Lane Shift Between A Lane Closure And An Opposite Lane Closure					
			D-704-35	Sign Layout For One Lane Closure - Interstate System					
			D-704-50	Portable Sign Support Assembly					
			D-762-2	Interstate Pavement Marking 4 Lane Divided Highway					
			D-762-4	Pavement Marking					
			D-762-11	Short-Term Pavement Marking					

NOTES

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	IM-2-094(154)248	6	1

704-P01 TRAFFIC CONTROL FOR MICROSURFACING: Provide traffic control consisting of a lane closure and flagging.

The maximum work zone length is limited to one day's production. The length of the work zone includes the daily construction area plus the longitudinal buffer space and does not include tapers.

For estimating purposes, the traffic control device list is based on a 6 mile work zone and the following list:

- 1. Standard D-704-22 layouts K and L;
- 2. Standard D-704-34A; and
- 3. Standard D-704-35;

Removed lane closures if no work is scheduled for the following day. Lane closures may remain in place for up to 3 days if weather prevents work from being performed on days when work was scheduled to take place.

The Department will pay for all necessary deployed devices, regardless of the number and length of the lane closures.

704-P02 TRAFFIC CONTROL FOR MICROSURFACE: Allow the CRS2 Emulsified Asphalt placed on the shoulder to cure for 24 hours before removing the adjacent lane closure.

704-P03 TRAFFIC CONTROL FOR MICROSURFACE: Apply microsurfacing to half the width of ramps at a time to allow the passage of traffic. Allow the placed material to properly cure before moving traffic onto the material. A quantity of 40 tubular markers has been provided to protect traffic from entering the fresh microsurface.

762-P01 SHORT TERM PAVEMENT MARKING: Install short term pavement marking prior to the removal of the temporary lane closure. Short term pavement marking on mainline will consist of the installation of 8" channel line, 4" edge line, and 4" centerline.

This document was originally issued and sealed by Daniel R. Viau, Registration Number PE-6329, on 05/12/2017 and the original document is stored at the North Dakota Department of Transportation.

ESTIMATE OF QUANTITIES

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	IM-2-094(154)248	8	1

SPEC CODE	ITEM DESCRIPTION	UNIT	MAINLINE	TOTAL
-----	-----	----	-----	-----
103	0100 CONTRACT BOND	L SUM	1	1
420	0101 CRS2 EMULSIFIED ASPHALT	GAL	15,997	15,997
421	0011 AGGREGATE FOR MICROSURFACING TYPE III	TON	2,053	2,053
421	0020 ASPHALT EMULSION FOR MICROSURFACING	GAL	68,141	68,141
702	0100 MOBILIZATION	L SUM	1	1
704	0100 FLAGGING	MHR	100	100
704	1000 TRAFFIC CONTROL SIGNS	UNIT	1,418	1,418
704	1052 TYPE III BARRICADE	EA	26	26
704	1060 DELINEATOR DRUMS	EA	109	109
704	1067 TUBULAR MARKERS	EA	300	300
704	1087 SEQUENCING ARROW PANEL-TYPE C	EA	1	1
762	0430 SHORT TERM 4IN LINE-TYPE NR	LF	137,835	137,835
762	1104 PVMT MK PAINTED 4IN LINE	LF	139,693	139,693
762	1108 PVMT MK PAINTED 8IN LINE	LF	5,535	5,535



**BASIS OF ESTIMATE**

Surfacing Quantities	Application Rate	Unit	Width (ft)	Quantity per Mile
<b>Mainline</b>				
Aggregate for Micro surfacing Type III	24 Lbs/SY	Ton	25	176
Asphalt Emulsion for Micro surfacing	0.3986 Gal/SY	Gal	25	5846
CRS2 Emulsified Asphalt for Shoulders	0.2 Gal/SY	Gal	3.5 & 9.5	1525

Surfacing Quantities	Application Rate	Unit	Width (ft)	Area (SY)	Total
<b>Lippert Interchange - Exit Ramp</b>					
Aggregate for Micro surfacing Type III	24 Lbs/SY	Ton	Varies	764.60	9
Asphalt Emulsion for Micro surfacing	0.3986 Gal/SY	Gal	Varies	764.60	305
CRS2 P Emulsified Asphalt for Shoulders	0.2 Gal/SY	Gal	6.5	553.263	111
<b>Lippert Interchange - Entrance Ramp</b>					
Aggregate for Micro surfacing Type III	24 Lbs/SY	Ton	Varies	880.438	11
Asphalt Emulsion for Micro surfacing	0.3986 Gal/SY	Gal	Varies	880.438	351
CRS2 Emulsified Asphalt for Shoulders	0.2 Gal/SY	Gal	6.5	776.123	155

Surfacing Quantities	Application Rate	Unit	Width (ft)	Area (SY)	Total
<b>Eldridge Interchange - Exit Ramp</b>					
Aggregate for Micro surfacing Type III	24 Lbs/SY	Ton	Varies	842.254	10
Asphalt Emulsion for Micro surfacing	0.3986 Gal/SY	Gal	Varies	842.254	336
CRS2 Emulsified Asphalt for Shoulders	0.2 Gal/SY	Gal	6.5	651.658	130
<b>Eldridge Interchange - Entrance Ramp</b>					
Aggregate for Micro surfacing Type III	24 Lbs/SY	Ton	Varies	973.695	12
Asphalt Emulsion for Micro surfacing	0.3986 Gal/SY	Gal	Varies	973.695	388
CRS2 Emulsified Asphalt for Shoulders	0.2 Gal/SY	Gal	6.5	689.60	138

Surfacing Quantities	Application Rate	Unit	Width (ft)	Area (SY)	Total
<b>Jamestown Rest Area - Exit Ramp</b>					
Aggregate for Micro surfacing Type III	24 Lbs/SY	Ton	Varies	831.274	10
Asphalt Emulsion for Micro surfacing	0.3986 Gal/SY	Gal	Varies	831.274	331
CRS2 Emulsified Asphalt for Shoulders	0.2 Gal/SY	Gal	6.5	597.158	119

Surfacing Quantities	Application Rate	Unit	Width (ft)	Area (SY)	Total
<b>Jamestown Rest Area - Entrance Ramp</b>					
Aggregate for Micro surfacing Type III	24 Lbs/SY	Ton	Varies	1278.085	15
Asphalt Emulsion for Micro surfacing	0.3986 Gal/SY	Gal	Varies	1278.085	510
CRS2 Emulsified Asphalt for Shoulders	0.2 Gal/SY	Gal	6.5	877.827	176

Surfacing Quantities	Application Rate	Unit	Width (ft)	Area (SY)	Total
<b>Woodbury Interchange - Exit Ramp</b>					
Aggregate for Micro surfacing Type III	24 Lbs/SY	Ton	Varies	760	9
Asphalt Emulsion for Micro surfacing	0.3986 Gal/SY	Gal	Varies	760	303
CRS2 Emulsified Asphalt for Shoulders	0.2 Gal/SY	Gal	6.5	578.847	116
<b>Woodbury Interchange - Entrance Ramp</b>					
Aggregate for Micro surfacing Type III	24 Lbs/SY	Ton	Varies	970.107	12
Asphalt Emulsion for Micro surfacing	0.3986 Gal/SY	Gal	Varies	970.107	387
CRS2 Emulsified Asphalt for Shoulders	0.2 Gal/SY	Gal	6.5	743.578	149

Surfacing Quantities	Application Rate	Unit	Width (ft)	Area (SY)	Total
<b>Exit 257-West Jamestown - Exit Ramp</b>					
Aggregate for Micro surfacing Type III	24 Lbs/SY	Ton	Varies	1015.173	12
Asphalt Emulsion for Micro surfacing	0.3986 Gal/SY	Gal	Varies	1015.173	405
CRS2 Emulsified Asphalt for Shoulders	0.2 Gal/SY	Gal	6.5	693.73	139
<b>Exit US 281 Interchange – Exit Ramp</b>					
Aggregate for Micro surfacing Type III	24 Lbs/SY	Ton	Varies	1232	15
Asphalt Emulsion for Micro surfacing	0.3986 Gal/SY	Gal	Varies	1232	491
CRS2 Emulsified Asphalt for Shoulders	0.2 Gal/SY	Gal	6.5	663.03	133
<b>US 281 Interchange – Entrance Ramp</b>					
Aggregate for Micro surfacing Type III	24 Lbs/SY	Ton	Varies	1085.50	13
Asphalt Emulsion for Micro surfacing	0.3986 Gal/SY	Gal	Varies	1085.50	433
CRS2 Emulsified Asphalt for Shoulders	0.2 Gal/SY	Gal	6.5	700.871	140

This document was originally issued and sealed by Daniel R. Viau, Registration Number PE-6329, on 05/12/2017 and the original document is stored at the North Dakota Department of Transportation.

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	IM-2-094(154)248	10	2

**BASIS OF ESTIMATE**

**Short Term Pavement Markings – Type NR**

<u>Mainline</u>	<u>Basis</u>	<u>Total (LF)</u>
4 IN White Centerline Line, 10' line, 30' skip x 2	1,320 LF / Mile	27,567
4 IN Yellow Edge Line	5,280 LF / Mile	55,134
4 IN White Edge Line	5,280 LF / Mile	55,134


**Permanent Pavement Markings**

<u>Mainline</u>	<u>Basis</u>	<u>Total (LF)</u>
4 IN White Centerline Line, 10' line, 30' skip	1,320 LF / Mile	13,783
4 IN Yellow Edge Line	5,280 LF / Mile	55,134
4 IN White Edge Line	5,280 LF / Mile	55,134
8 IN White Channel Line	265 LF / Mile	2,906

<u>Ramps (11 Each)</u>	<u>Basis</u>	<u>Total (LF)</u>
4 IN Dotted White Line, 2' line, 6' skip	185 LF / Each	2,035
4 IN Yellow Edge Line	201 LF / Each	2,211
4 IN White Edge Line	1,036 LF/ Each	11,396
8 IN White Channel Line	239 LF / Each	2,629

This document was originally issued and sealed by Daniel R. Viau, Registration Number PE-6329, on 05/12/2017 and the original document is stored at the North Dakota Department of Transportation.

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	IM-2-094(154)248	20	1




Basis of Estimate				
Item	Application Rate	Unit	Area (SY)	Total
Aggregate for Microsurfacing Type III	24 Lbs / SY	Ton	764.60	9
Asphalt Emulsion for Microsurfacing (14 % by weight at 8.43 lb/gal)	0.3986 Gal / SY	Gal	764.60	305
CRS2 Emulsified Asphalt for shoulders	0.2 Gal / SY	Gal	553.263	111

This document was originally issued and sealed by  
Daniel R. Viau  
Registration Number  
PE- 6329,  
on 5/12/2017 and the original document is stored at the  
North Dakota Department  
of Transportation

Lippert Interchange  
Exit Ramp

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	IM-2-094(154)248	20	2




Basis of Estimate				
Item	Application Rate	Unit	Area (SY)	Total
Aggregate for Microsurfacing Type III	24 Lbs / SY	Ton	880.438	11
Asphalt Emulsion for Microsurfacing (14 % by weight at 8.43 lb/gal)	0.3986 Gal / SY	Gal	880.438	351
CRS2 Emulsified Asphalt for shoulders	0.2 Gal / SY	Gal	776.123	155

This document was originally issued and sealed by  
Daniel R. Viau  
Registration Number  
PE- 6329,  
on 5/12/2017 and the original document is stored at the  
North Dakota Department  
of Transportation

Lippert Interchange  
Entrance Ramp

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	IM-2-094(154)248	20	3




Basis of Estimate				
Item	Application Rate	Unit	Area (SY)	Total
Aggregate for Microsurfacing Type III	24 Lbs / SY	Ton	842.254	10
Asphalt Emulsion for Microsurfacing (14 % by weight at 8.43 lb/gal)	0.3986 Gal / SY	Gal	842.254	336
CRS2 Emulsified Asphalt for shoulders	0.2 Gal / SY	Gal	651.658	130

This document was originally issued and sealed by  
Daniel R. Viau  
Registration Number  
PE- 6329,  
on 5/12/2017 and the original document is stored at the  
North Dakota Department  
of Transportation

Eldridge Interchange  
Exit Ramp

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	IM-2-094(154)248	20	4




Basis of Estimate				
Item	Application Rate	Unit	Area (SY)	Total
Aggregate for Microsurfacing Type III	24 Lbs / SY	Ton	973.695	12
Asphalt Emulsion for Microsurfacing (14 % by weight at 8.43 lb/gal)	0.3986 Gal / SY	Gal	973.695	388
CRS2 Emulsified Asphalt for shoulders	0.2 Gal / SY	Gal	689.60	138

This document was originally issued and sealed by  
Daniel R. Viau  
Registration Number  
PE- 6329,  
on 5/12/2017 and the original document is stored at the  
North Dakota Department  
of Transportation

Eldridge Interchange  
Entrance Ramp

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	IM-2-094(154)248	20	5




Basis of Estimate				
Item	Application Rate	Unit	Area (SY)	Total
Aggregate for Microsurfacing Type III	24 Lbs / SY	Ton	831.274	10
Asphalt Emulsion for Microsurfacing (14 % by weight at 8.43 lb/gal)	0.3986 Gal / SY	Gal	831.274	331
CRS2 Emulsified Asphalt for shoulders	0.2 Gal / SY	Gal	597.158	119

This document was originally issued and sealed by  
Daniel R. Viau  
Registration Number  
PE- 6329,  
on 5/12/2017 and the original document is stored at the  
North Dakota Department  
of Transportation

Jamestown Rest Area  
Exit Ramp

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	IM-2-094(154)248	20	6




Basis of Estimate				
Item	Application Rate	Unit	Area (SY)	Total
Aggregate for Microsurfacing Type III	24 Lbs / SY	Ton	1278.085	15
Asphalt Emulsion for Microsurfacing (14 % by weight at 8.43 lb/gal)	0.3986 Gal / SY	Gal	1278.085	510
CRS2 Emulsified Asphalt for shoulders	0.2 Gal / SY	Gal	877.827	176

This document was originally issued and sealed by  
Daniel R. Viau  
Registration Number  
PE- 6329,  
on 5/12/2017 and the original document is stored at the  
North Dakota Department  
of Transportation

Jamestown Rest Area  
Entrance Ramp



	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	IM-2-094(154)248	20	7





Basis of Estimate				
Item	Application Rate	Unit	Area (SY)	Total
Aggregate for Microsurfacing Type III	24 Lbs / SY	Ton	760	9
Asphalt Emulsion for Microsurfacing (14 % by weight at 8.43 lb/gal)	0.3986 Gal / SY	Gal	760	303
CRS2 Emulsified Asphalt for shoulders	0.2 Gal / SY	Gal	578.847	116

This document was originally issued and sealed by  
Daniel R. Viau  
Registration Number  
PE- 6329,  
on 5/12/2017 and the original document is stored at the  
North Dakota Department  
of Transportation

Woodbury Interchange  
Exit Ramp

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	IM-2-094(154)248	20	8




Basis of Estimate				
Item	Application Rate	Unit	Area (SY)	Total
Aggregate for Microsurfacing Type III	24 Lbs / SY	Ton	970.107	12
Asphalt Emulsion for Microsurfacing (14 % by weight at 8.43 lb/gal)	0.3986 Gal / SY	Gal	970.107	387
CRS2 Emulsified Asphalt for shoulders	0.2 Gal / SY	Gal	743.578	149

This document was originally issued and sealed by  
Daniel R. Viau  
Registration Number  
PE- 6329,  
on 5/12/2017 and the original document is stored at the  
North Dakota Department  
of Transportation

Woodbury Interchange  
Entrance Ramp

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	IM-2-094(154)248	20	9




This document was originally issued and sealed by  
Daniel R. Viau  
Registration Number  
PE- 6329,  
on 5/12/2017 and the original document is stored at the  
North Dakota Department  
of Transportation

Basis of Estimate				
Item	Application Rate	Unit	Area (SY)	Total
Aggregate for Microsurfacing Type III	24 Lbs / SY	Ton	1015.173	12
Asphalt Emulsion for Microsurfacing (14 % by weight at 8.43 lb/gal)	0.3986 Gal / SY	Gal	1015.173	405
CRS2 Emulsified Asphalt for shoulders	0.2 Gal / SY	Gal	693.73	139

Exit 257 - West Jamestown  
Exit Ramp


	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	IM-2-094(154)248	20	10



This document was originally issued and sealed by Daniel R. Viau Registration Number PE- 6329, on 5/12/2017 and the original document is stored at the North Dakota Department of Transportation

Exit US 281 Interchange Exit Ramp

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	IM-2-094(154)248	20	11




Basis of Estimate				
Item	Application Rate	Unit	Area (SY)	Total
Aggregate for Microsurfacing Type III	24 Lbs / SY	Ton	1085.50	13
Asphalt Emulsion for Microsurfacing (14 % by weight at 8.43 lb/gal)	0.3986 Gal / SY	Gal	1085.50	433
CRS2 Emulsified Asphalt for shoulders	0.2 Gal / SY	Gal	700.871	140

This document was originally issued and sealed by  
Daniel R. Viau  
Registration Number  
PE- 6329,  
on 5/12/2017 and the original document is stored at the  
North Dakota Department  
of Transportation


US 281 Interchange  
Entrance Ramp

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	IM-2-094(154)248	30	1




Existing Typical Section  
RP 248.000 to RP 258.442

\* Curve Section same as Tangent  
except for superelevation




Existing Typical Section  
(Ramps)



Proposed Typical Section  
RP 248.000 to RP 258.442

\* Curve Section same as Tangent  
except for superelevation



Proposed Typical Section  
(Ramps)

This document was originally  
issued and sealed by  
Daniel R. Viau  
Registration Number  
PE- 6329,  
on 5/12/2017 and the original  
document is stored at the  
North Dakota Department  
of Transportation

Existing & proposed Typical Sections

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	IM-2-094(154)248	100	1

SIGN NUMBER	SIGN SIZE	DESCRIPTION	AMOUNT REQUIRED	UNITS PER AMOUNT	UNITS SUB TOTAL
D3-36	36"x6"	STREET NAME SIGN (Sign and installation only)		6	
G20-1-60	60"x24"	ROAD WORK NEXT ___ MILES	2	34	68
G20-1b-60	60"x24"	WORK IN PROGRESS/ NO WORK IN PROGRESS (Sign and installation only)		26	
G20-2-48	48"x24"	END ROAD WORK	7	19	133
G20-4-36	36"x18"	PILOT CAR FOLLOW ME (Mounted to back of pilot car)		18	
G20-10-108	108"x48"	CONTRACTOR SIGN		64	
G20-50a-72	72"x36"	ROAD WORK NEXT ___ MILES RT & LT ARROWS		37	
G20-52a-72	72"x24"	ROAD WORK NEXT ___ MILES RT or LT ARROW		30	
G20-55-96	96"x48"	SPEED LIMIT ENFORCED - MINIMUM FEE \$80 WHEN WORKERS PRESENT	2	59	118
M1-1-36	36"x36"	INTERSTATE ROUTE MARKER (Post and installation only)		10	
M1-4-24	24"x24"	U.S. ROUTE MARKER (Post and installation only)		10	
M1-5-24	24"x24"	STATE ROUTE MARKER (Post and installation only)		10	
M3-1-24	24"x12"	NORTH (Mounted on route marker post)		7	
M3-2-24	24"x12"	EAST (Mounted on route marker post)		7	
M3-3-24	24"x12"	SOUTH (Mounted on route marker post)		7	
M3-4-24	24"x12"	WEST (Mounted on route marker post)		7	
M4-8-24	24"x12"	DETOUR (Mounted on route marker post)		7	
M4-9-30	30"x24"	DETOUR ARROW RIGHT or LEFT/AHD AND RT or LT		15	
M4-10-48	48"x18"	DETOUR ARROW RIGHT or LEFT		23	
M5-1-21	21"x15"	ARROW AHD AND RT or LT(Mounted on route marker post)		7	
M5-2-21	21"x15"	ARROW AHD UP & RT or LT (Mounted on route marker post)		7	
M6-1-21	21"x15"	ARROW RT or LT (Mounted on route marker post)		7	
M6-2-21	21"x15"	ARROW UP & RT or LT (Mounted on route marker post)		7	
M6-3-21	21"x15"	ARROW AHD (Mounted on route marker post)		7	
R1-1-48	48"x48"	STOP	2	32	64
R1-1a-18	18"x18"	STOP and SLOW PADDLE Back to Back	1	5	5
R1-2-60	60"x60"	YIELD	3	29	87
R2-1-48	48"x60"	SPEED LIMIT ___	4	39	156
R2-1a-24	24"x18"	MINIMUM FEE \$80 (Mounted on Speed Limit post)		10	
R2-1aP-24	24"x18"	MINIMUM FEE \$80 (Mounted on Speed Limit post)	4	10	40
R3-7-48	48"x48"	LEFT or RIGHT LANE MUST TURN LEFT or RIGHT		35	
R4-1-48	48"x60"	DO NOT PASS		39	
R4-7-48	48"x60"	KEEP RIGHT SYMBOL		39	
R5-1-48	48"x48"	DO NOT ENTER		35	
R6-1-36	36"x12"	ONE WAY RIGHT or LEFT		13	
R7-1-12	12"x18"	NO PARKING		11	
R10-6-24	24"x36"	STOP HERE ON RED		16	
R11-2-48	48"x30"	ROAD CLOSED		28	
R11-2a-48	48"x30"	STREET CLOSED		28	
R11-3a-60	60"x30"	ROAD CLOSED ___ MILES AHEAD LOCAL TRAFFIC ONLY		31	
R11-3c-60	60"x30"	STREET CLOSED ___ MILES AHEAD LOCAL TRAFFIC ONLY		31	
R11-4a-60	60"x30"	STREET CLOSED TO THRU TRAFFIC		31	
W1-3-48	48"x48"	RIGHT or LEFT SHARP REVERSE CURVE ARROW		35	
W1-4-48	48"x48"	RIGHT or LEFT REVERSE CURVE ARROW		35	
W1-4b-48	48"x48"	DOUBLE RIGHT or LEFT REVERSE CURVE ARROW		35	
W1-6-48	48"x24"	LARGE ARROW		26	
W3-1-48	48"x48"	STOP AHEAD SYMBOL		35	
W3-3-48	48"x48"	SIGNAL AHEAD SYMBOL		35	
W3-4-48	48"x48"	BE PREPARED TO STOP	2	35	70
W3-5-48	48"x48"	SPEED REDUCTION AHEAD	5	35	175
W4-2-48	48"x48"	RIGHT or LEFT LANE TRANSITION SYMBOL	2	35	70
W5-1-48	48"x48"	ROAD NARROWS		35	
W5-8-48	48"x48"	THRU TRAFFIC RIGHT LANE		35	
W5-9-48	48"x48"	ROAD WORK TRAFFIC ONLY DOWN & LT or RT ARROW		35	
W6-3-48	48"x48"	TWO WAY TRAFFIC SYMBOL		35	
W8-1-48	48"x48"	BUMP		35	
W8-3-48	48"x48"	PAVEMENT ENDS		35	
W8-7-48	48"x48"	LOOSE GRAVEL		35	
W8-9a-48	48"x48"	SHOULDER DROP-OFF		35	
W8-11-48	48"x48"	UNEVEN LANES		35	
W8-12-48	48"x48"	NO CENTER STRIPE		35	
W8-53-48	48"x48"	TRUCKS ENTERING HIGHWAY		35	
W8-54-48	48"x48"	TRUCKS ENTERING AHEAD or ___ FT.	2	35	70
W8-55-48	48"x48"	TRUCKS CROSSING AHEAD or ___ FT.		35	
W8-56-48	48"x48"	TRUCKS EXITING HIGHWAY		35	
W9-3a-48	48"x48"	CENTER LANE CLOSED SYMBOL		35	
W12-2-48	48"x48"	LOW CLEARANCE SYMBOL		35	
W13-1-24	24"x24"	___ MPH ADVISORY SPEED PLATE (Mounted on warning sign post)		11	
W13-4-48	48"x60"	RAMP ARROW	3	39	117
W14-3-48	48"x36"	NO PASSING ZONE		23	
W20-1-48	48"x48"	ROAD WORK AHEAD or ___ FT or ___ MILE	4	35	140
W20-2-48	48"x48"	DETOUR AHEAD or ___ FT		35	
W20-3-48	48"x48"	ROAD or STREET CLOSED AHEAD or ___ FT.		35	
W20-4-48	48"x48"	ONE LANE ROAD AHEAD or ___ FT.		35	
W20-5-48	48"x48"	RIGHT or LEFT LANE CLOSED AHEAD or ___ FT.	2	35	70
W20-7a-48	48"x48"	FLAGGING SYMBOL	1	35	35
W20-7k-24	24"x18"	___ FEET (Mounted on warning sign post)		10	
W20-8-48	48"x48"	STREET CLOSED		35	
W20-51-48	48"x48"	EQUIPMENT WORKING		35	
W20-52-54	54"x12"	NEXT ___ MILES (Mounted on warning sign post)		12	
W21-1a-48	48"x48"	WORKERS SYMBOL		35	
W21-2-48	48"x48"	FRESH OIL		35	

[illegible][illegible]

SPEC & CODE			
704-1000	TRAFFIC CONTROL SIGNS	TOTAL UNITS	1418


SPEC & CODE	DESCRIPTION	UNIT	QUANTITY
<b>704-1000</b>	<b>FLAGGING</b>	<b>MHR</b>	<b>100</b>
704-1041	ATTENUATION DEVICE-TYPE B-55	EACH	
704-1043	ATTENUATION DEVICE-TYPE B-65	EACH	
704-1044	ATTENUATION DEVICE-TYPE B-70	EACH	
704-1050	TYPE I BARRICADES	EACH	
704-1051	TYPE II BARRICADES	EACH	
<b>704-1052</b>	<b>TYPE III BARRICADES</b>	<b>EACH</b>	<b>26</b>
<b>704-1060</b>	<b>DELINEATOR DRUMS</b>	<b>EACH</b>	<b>109</b>
704-1065	TRAFFIC CONES	EACH	
<b>704-1067</b>	<b>TUBULAR MARKERS</b>	<b>EACH</b>	<b>300</b>
704-1070	DELINEATOR	EACH	
704-1072	FLEXIBLE DELINEATORS	EACH	
704-1081	VERTICAL PANELS - BACK TO BACK	EACH	
704-1085	SEQUENCING ARROW PANEL - TYPE A	EACH	
704-1086	SEQUENCING ARROW PANEL - TYPE B	EACH	
<b>704-1087</b>	<b>SEQUENCING ARROW PANEL - TYPE C</b>	<b>EACH</b>	<b>1</b>
704-1088	SEQUENCING ARROW PANEL - TYPE C - CROSSOVER	EACH	
704-1095	TYPE B FLASHERS	EACH	
704-1500	OBLITERATION OF PVMT MK	SF	
704-3501	PORTABLE PRECAST CONCRETE MED BARRIER	LF	
704-3510	PRECAST CONCRETE MED BARRIER - STATE FURNISHED	EACH	
762-0200	RAISED PAVEMENT MARKERS	EACH	
762-0420	SHORT TERM 4IN LINE - TYPE R	LF	
<b>762-0430</b>	<b>SHORT TERM 4IN LINE - TYPE NR</b>	<b>LF</b>	<b>137835</b>
772-2110	FLASHING BEACON - POST MOUNTED	EACH	

**NOTE:**  
If additional signs are required, units will be calculated using the formula from Section III-19.06 of the Design Manual.  
<http://www.dot.nd.gov/>

This document was  
originally issued  
and sealed by  
Daniel R. Viau,  
Registration Number  
PE-6329,  
on 8/30/17 and the  
original document  
is stored at the North Dakota  
Department of Transportation.

## Traffic Control Devices List

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	IM-2-094(154)248	100	2



This document was originally issued and sealed by Daniel R. Viau, Registration Number PE- 6329, on 5/12/2017 and the original document is stored at the North Dakota Department of Transportation

Construction Sign Layout



?	This is a special text character used in the labeling of existing features. It indicates a feature that has an unknown characteristic, potentially based on: lack of description, location accuracy or purpose.		
Abn	abandoned	BV	butterfly valve
Abut	abutment	Byp	bypass
Ac	acres	C Gdrl	cable guardrail
Adj	adjusted	Calc	calculate
Aggr	aggregate	Cd	candela
Ahd	ahead	CIP	cast iron pipe
ARV	air release valve	CB	catch basin
Align	alignment	CRS	cationic rapid setting
Al	alley	C Gd	cattle guard
Alt	alternate	C To C	center to center
Alum	aluminum	Cl or $\text{C}$	centerline
ADA	Americans with Disabilities Act	Cm	centimeter
A	ampere	Ch	chain
&	and	Chnlk	chain-link
Appr	approach	Ch Blk	channel block
Approx	approximate	Ch Ch	channel change
ACP	asbestos cement pipe	Chk	check
Asph	asphalt	Chsld	chiseled
AC	asphalt cement	Cir	circle
Assmd	assumed	Cl	class
@	at	Cl	clay
Atten	attenuation	Cl F	clay fill
ATR	automatic traffic recorder	Cl Hvy	clay heavy
Ave	Avenue	Cl Lm	clay loam
Avg	average	Clnt	clean-out
ADT	average daily traffic	Clr	clear
Az	azimuth	Cl&gr	clearing & grubbing
Bk	back	Co S	coal slack
BF	back face	Comb.	combination
Bs	backsight	Coml	commercial
Balc	balcony	Compr	compression
B Wire	barbed wire	CADD	computer aided drafting & design
Barr	barricade	Conc	concrete
Btry	battery	Cond	conductor
Brg	bearing	Const	construction
BI	beehive inlet	Cont	continuous
Beg	begin	CSB	continuous split barrel sample
BM	bench mark	Contr	contraction
Bkwy	bikeway	Contr	contractor
Bit	bituminous	CP	control point
Blk	block	Coord	coordinate
Bd Ft	board feet	Cor	corner
BH	bore hole	Corr	corrected
BS	both sides	CAES	corrugated aluminum end section
Bot	bottom	CAP	corrugated aluminum pipe
Blvd	Boulevard	CMES	corrugated metal end section
Bndry	boundary	CMP	corrugated metal pipe
BC	brass cap	CPVCP	corrugated poly-vinyl chloride pipe
Brkwy	breakaway	CSES	corrugated steel end section
Br	bridge	CSP	corrugated steel pipe
Bldg	building	CSP	corrugated steel pipe
		C	coulomb
		Co	County
		Crse	course
		C Gr	course gravel
		CS	course sand
		Ct	Court
		Xarm	cross arm
		Xbuck	cross buck
		Xsec	cross sections
		Xing	crossing
		Xrd	Crossroad
		Crn	crown
		CF	cubic feet
		M3	cubic meter
		M3/s	cubic meters per second
		CY	cubic yard
		Cy/mi	cubic yards per mile
		Culv	culvert
		C&G	curb & gutter
		CI	curb inlet
		CR	curb ramp
		CS	curve to spiral
		C	cut
		Dd Ld	dead load
		Defl	deflection
		Defm	deformed
		Deg or D	degree
		DInt	delineate
		DIntr	delineator
		Depr	depression
		Desc	description
		Det	detail
		DWP	detectable warning panel
		Dtr	detour
		Dia	diameter
		Dir	direction
		Dist	distance
		DM	disturbed material
		DB	ditch block
		DG	ditch grade
		Dbl	double
		Dn	down
		Dwg	drawing
		Dr	drive
		Drwy	driveway
		DI	drop inlet
		D	dry density
		Ea	each
		Esmt	easement
		E	East
		EB	Eastbound
		Elast	elastomeric
		EL	electric locker
		E Mtr	electric meter
		Elec	electric/al
		EDM	electronic distance meter
		Elev or EI	elevation
		Ellipt	elliptical
		Emb	embankment
		Emuls	emulsion/emulsified
		ES	end section
		Engr	engineer
		ESS	environmental sensor station
		Eq	equal
		Eq	equation
		Evgr	evergreen
		Exc	excavation
		Exst	existing
		Exp	expansion
		Expy	Expressway
		E	external of curve
		Extru	extruded
		FOS	factor of safety
		F	Fahrenheit
		FS	far side
		F	farad
		Fed	Federal
		FP	feed point
		Ft	feet/foot
		Fn	fence
		Fn P	fence post
		FO	fiber optic
		FB	field book
		FD	field drive
		F	fill
		FAA	fine aggregate angularity
		FS	fine sand
		FH	fire hydrant
		FI	flange
		Flrd	flared
		FES	flared end section
		F Bcn	flashing beacon
		FA	flight auger sample
		FL	flow line
		Ftg	footing
		FM	force main
		Fs	foresight
		Fnd	found
		Fdn	foundation
		Frac	fractional
		Frwy	freeway
		Frt	front
		FF	front face
		F Disp	fuel dispenser

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930 , on 07/01/14 and the original document is stored at the North Dakota Department of Transportation

NDDOT ABBREVIATIONS

D-101-2

FFP	fuel filler pipes	IPn	Iron Pin	MC	medium curing	Ped	pedestal
FLS	fuel leak sensor	IP	Iron Pipe	M	mega	Ped	pedestrian
Furn	furnish/ed	Jt	joint	Mer	meridian	PPP	pedestrian pushbutton post
Gal	gallon	J	joule	M	meter	Pen.	penetration
Galv	galvanized	Jct	junction	M/s	meters per second	Perf	perforated
Gar	garage	K	kelvin	M	mid ordinate of curve	Per.	perimeter
Gs L	gas line	Kn	kilo newton	Mi	mile	PL	pipeline
G Reg	gas line regulator	Kpa	kilo pascal	MM	mile marker	PI	place
GMV	gas main valve	Kg	kilogram	MP	mile post	P&P	plan & profile
G Mtr	gas meter	Kg/m3	kilogram per cubic meter	MI	milliliter	PL	plastic limit
GSV	gas service valve	Km	kilometer	Mm	millimeter	PI	plate
GVP	gas vent pipe	K	Kip(s)	Mm/hr	millimeters per hour	Pt	point
GV	gate valve	LS	Land Surveyor (licensed)	Min	minimum	PCC	point of compound curve
Ga	gauge	LSIT	Land Surveyor In Training	Misc	miscellaneous	PC	point of curve
Geod	geodetic	Ln	lane	Mon	monument	PI	point of intersection
GIS	Geographical Information System	Lg	large	Mnd	mound	PRC	point of reverse curvature
G	giga	Lat	latitude	Mtbl	mountable	PT	point of tangent
GPS	Global Positioning System	Lt	left	Mtd	mounted	POC	point on curve
Gov	government	L	length of curve	Mtg	mounting	POT	point on tangent
Grd	graded/grade	Lens	lenses	Mk	muck	PE	polyethylene
Gr	gravel	Lvl	level	Mun	municipal	PVC	polyvinyl chloride
Grnd	ground	LB	level book	N	nano	PCC	Portland Cement concrete
GWM	ground water monitor	Lvlng	leveling	NGS	National Geodetic Survey	Lb or #	pounds
Gdrl	guardrail	Lht	light	NS	near side	PP	power pole
Gtr	gutter	LP	light pole	Neop	neoprene	Preempt	preemption
H Plg	H piling	Ltg	lighting	Ntwk	network	Prefab	prefabricated
Hdwl	headwall	Lig Co	lignite coal	N	newton	Prfmd	preformed
Ha	hectare	Lig Sl	lignite slack	N	North	Prep	preperation
Ht	height	LF	linear foot	NE	North East	Press.	pressure
HI	height of instrument	Liq	liquid	NW	North West	PRV	pressure relief valve
Hel	helical	LL	liquid limit	NB	Northbound	Prestr	prestressed
H	henry	L	litre	No. or #	number	Pvt	private
Hz	hertz	Lm	loam	Obsc	obscure(d)	PD	private drive
HDPE	high density polyethylene	Loc	location	Obsn	observation	Prod.	production/produce
HM	high mast	LC	long chord	Ocpd	occupied	Prog	programmed
HP	high pressure	Long.	longitude	Ocpy	occupy	Prop.	property
HPS	high pressure sodium	Lp	loop	Off Loc	office location	Prop Ln	property line
Hwy	highway	LD	loop detector	O/s	offset	Ppsd	proposed
Hor	horizontal	Lm	lumen	OC	on center	PB	pull box
HBP	hot bituminous pavement	Lum	luminaire	C	one dimensional consolidation		
HMA	hot mix asphalt	L Sum	lump sum	OC	organic content		
Hr	hour(s)	Lx	lux	Orig	original		
Hyd	hydrant	ML	main line	O To O	out to out		
Ph	hydrogen ion content	M Hr	man hour	OD	outside diameter		
Id	identification	MH	manhole	OH	overhead		
In or "	inch	Mkd	marked	PMT	pad mounted transformer		
Incl	inclinometer tube	Mkr	marker	Pg	pages		
IMH	inlet manhole	Mkg	marking	Pntd	painted		
ID	inside diameter	MA	mast arm	Pr	pair		
Inst	instrument	Matl	material	Pnl	panel		
Intchg	interchange	Max	maximum	Pk	park		
Intmdt	intermediate	MC	meander corner	PK	Parker-Kalon nail		
Intscn	intersection	Meas	measure	Pa	pascal		
Inv	invert	Mdn	median	PSD	passing sight distance		
IM	iron monument	MD	median drain	Pvmt	pavement		

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
08-03-15	General Revisions

This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930 , on 08/03/15 and the original document is stored at the North Dakota Department of Transportation

NDDOT ABBREVIATIONS

D-101-3

Qty	quantity	SN	sign number	Tan	tangent	Wb	weber
Qtr	quarter	Sig	signal	T	tangent (semi)	WIM	weigh in motion
Rad or R	radius	Si Cl	silt clay	TS	tangent to spiral	W	west
RR	railroad	Si Cl Lm	silty clay loam	Tel	telephone	WB	westbound
Rlwy	railway	Si Lm	silty loam	Tel B	Telephone Booth	Wrng	wiring
Rsd	raised	Sgl	single	Tel P	telephone pole	W/	with
RTP	random traverse point	SC	slow curing	Tv	television	W/o	without
Rge or R	range	SS	slow setting	Temp	temperature	WC	witness corner
RC	rapid curing	Sm	small	Temp	temporary	WGS	world geodetic system
Rec	record	S	South	TBM	temporary bench mark	Z	zenith
Rcy	recycle	SE	South East	T	tesla		
RAP	recycled asphalt pavement	SW	South West	T	thinwall tube sample		
RPCC	recycled portland cement concrete	SB	Southbound	T/mi	tons per mile		
Ref	reference	Sp	spaces	Ts	topsoil		
R Mkr	reference marker	Spcl	special	Twp or T	township		
RM	reference monument	SA	special assembly	Traf	traffic		
Refl	reflectorized	SP	special provisions	TSCB	traffic signal control box		
RCB	reinforced concrete box	G	specific gravity	Tr	trail		
RCES	reinforced concrete end section	Spk	spike	Transf	transformer		
RCP	reinforced concrete pipe	SC	spiral to curve	TB	transit book		
RCPS	reinforced concrete pipe sewer	ST	spiral to tangent	Trans	transition		
Reinf	reinforcement	SB	split barrel sample	TT	transmission tower		
Res	reservation	SH	sprinkler head	Trans	transverse		
Ret	retaining	SV	sprinkler valve	Trav	traverse		
Rev	reverse	Sq	square	TP	traverse point		
Rt	right	SF	square feet	Trtd	treated		
R/W	right of way	Km2	square kilometer	Trmt	treatment		
Riv	river	M2	square meter	Qc	triaxial compression		
Rd	road	SY	square yard	TERO	tribal employment rights ordinance		
Rdbd	road bed	Stk	stake	Tpl	triple		
Rdwy	roadway	Std	standard	TP	turning point		
RWIS	roadway weather information system	N	standard penetration test	Typ	typical		
Rk	rock	Std Specs	standard specifications	Qu	unconfined compressive strength		
Rt	route	Sta	station	Ugrnd	underground		
Salv	salvage(d)	Sta Yd	station yards	USC&G	US Coast & Geodetic Survey		
Sd	sand	Stm L	steam line	USGS	US Geologic Survey		
Sdy Cl	sandy clay	SEC	steel encased concrete	Util	utility		
Sdy Cl Lm	sandy clay loam	SMA	stone matrix asphalt	VG	valley gutter		
Sdy Fl	sandy fill	SSD	stopping sight distance	Vap	vapor		
Sdy Lm	sandy loam	SD	storm drain	Vert	vertical		
San	sanitary sewer line	St	street	VC	vertical curve		
Sc	scoria	SPP	structural plate pipe	VCP	vitrified clay pipe		
Sec	seconds	SPPA	structural plate pipe arch	V	volt		
Sec	section	Str	structure	Vol	volume		
SL	section line	Subd	subdivision	Wkwy	walkway		
Sep	separation	Sub	subgrade	W	water content		
Seq	sequence	Sub Prep	subgrade preperation	WGV	water gate valve		
Serv	service	Ss	subsoil	WL	water line		
Sh	shale	SE	superelevation	WM	water main		
Sht	sheet	SS	supplement specification	WMV	water main valve		
Shtng	sheeting	Supp	supplemental	W Mtr	water meter		
Shldr	shoulder	Surf	surfacing	WSV	water service valve		
Sw	sidewalk	Surv	survey	WW	water well		
S	siemens	Sym	symmetrical	W	watt		
SD	sight distance	SI	systems international	Wrng	wearing		

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
08-03-15	General Revisions

This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930 , on 08/03/15 and the original document is stored at the North Dakota Department of Transportation

NDDOT UTILITY COMPANY AND ORGANIZATION ABBREVIATIONS
























702COM	702 Communications	GT PLNS NAT GAS	Great Plains Natural Gas Company	RED RIV TEL	Red River Rural Telephone
ACCENT	Accent Communications	HALS TEL	Halstad Telephone Company	RESVTN TEL	Reservation Telephone
AGASSIZ WU	Agassiz Water Users Incorporated	IDEA1	Idea1	ROBRTS TEL	Roberts Company Telephone
AGC	Associated General Contractors of America	INT-COMM TEL	Inter-Community Telephone Company	R-RIDER ELEC	Roughrider Electric Coop
All PI	Alliance Pipeline	KANEB PL	Kaneb Pipeline Company	RRVW	Red River Valley & Western Railroad
ALL SEAS WU	All Seasons Water Users Association	KEM ELEC	Kem Electric Cooperative Incorporated	RSR ELEC	R.S.R. Electric Cooperative
AMOCO PI	Amoco Pipeline Company	KOCH GATH SYS	Koch Gathering Systems Incorporated	S E W U	South East Water Users Incorporated
AMRDA HESS	Amerada Hess Corporation	LKHD PL	Lakehead Pipeline Company	SCOTT CABLE	Scott Cable Television Dickinson
AT&T	AT&T Corporation	LNGDN RWU	Langdon Rural Water Users Incorporated	SHERDN ELEC	Sheridan Electric Cooperative
B PAW	Bear Paw Energy Incorporated	LWR YELL R ELEC	Lower Yellowstone Rural Electric	SHEYN VLY ELEC	Sheyenne Valley Electric Cooperative
BAKER ELEC	Baker Electric	MCKNZ CON	McKenzie Consolidated Telcom	SKYTECH	Skyland Technologies Incorporated
BASIN ELEC	Basin Electric Cooperative Incorporated	MCKNZ ELEC	McKenzie Electric Cooperative	SLOPE ELEC	Slope Electric Cooperative Incorporated
BEK TEL	Bek Communications Cooperative	MCKNZ WRD	McKenzie County Water Resource District	SOURIS RIV TELCOM	Souris River Telecommunications
BELLE PL	Belle Fourche Pipeline Company	MCLEOD	McLeod USA	ST WAT COMM	State Water Commission
BLM	Bureau of Land Management	MCLN ELEC	McLean Electric Cooperative	STATE LN WATER	State Line Water Cooperative
BNSF	Burlington Northern Santa Fe Railway	MCLN-SHRDN R WAT	McLean-Sheridan Rural Water	STER ENG	Sterling Energy
BOEING	Boeing	MDU	Montana-dakota Utilities	STUT RWU	Stutsman Rural Water Users
BRNS RWD	Barnes Rural Water District	MID-CONT CABLE	Mid-Continent Cable	SW PL PRJ	Southwest Pipeline Project
BURK-DIV ELEC	Burke-Divide Electric Cooperative	MIDSTATE TEL	Midstate Telephone Company	T M C	Turtle Mountain Communications
BURL WU	Burleigh Water Users	MINOT CABLE	Minot Cable Television	TCI	TCI of North Dakota
Cable One	Cable One	MINOT TEL	Minot Telephone Company	TESORO HGH PLNS PL	Tesoro High Plains Pipeline
CABLE SERV	Cable Services	MISS W W S	Missouri West Water System	TRI-CNTY WU	Tri-County Water Users Incorporated
CAP ELEC	Capital Electric Cooperative Incorporat	MNKOTA PWR	Minnkota Power	TRL CO RWU	Traill County Rural Water Users
CASS CO ELEC	Cass County Electric Cooperative	MOR-GRAN-SOU ELEC	Mor-gran-sou Electric Cooperative	UNTD TEL	United Telephone
CASS RWU	Cass Rural Water Users Incorporated	MOUNT-WILLI ELEC	Mountrail-williams Electric Cooperative	UPPR SOUR WUA	Upper Souris Water Users Association
CAV ELEC	Cavalier Rural Electric Cooperative	MRE LBTY TEL	Moore & Liberty Telephone	US SPRINT	U.S. Sprint
CBLCOM	Cablecom Of Fargo	MUNICIPAL	City Water And Sewer	USAF MSL CABLE	U.S.A.F. Missile Cable
CENEX PL	Cenex Pipeline	MUNICIPAL	City Of '.....'	USFWS	US Fish and Wildlife Service
CENT PL WATER DIST	Central Pipe Line Water District	N CENT ELEC	North Central Electric Cooperative	USW COMM	U.S. West Communications
CENT PWR ELEC	Central Power Electric Cooperative	N VALL W DIST	North Valley Water District	VRNDRY ELEC	Verendrye Electric Cooperative
COE	Corps of Engineers	ND PKS & REC	North Dakota Parks And Recreation	W RIV TEL	West River Telephone Incorporated
CONS TEL	Consolidated Telephone	ND TEL	North Dakota Telephone Company	WEB	W. E. B. Water Development Association
CONT RES	Continental Resource Inc	NDDOT	North Dakota Department of Transportation	WILLI RWA	Williams Rural Water Association
CPR	Canadian Pacific Railway	NDSU SOIL SCI DEPT	NDSU Soil Science Department	WILSTN BAS PL	Williston Basin Interstate Pipeline Company
D O E	Department Of Energy	NEMONT TEL	Nemont Telephone	WLSH RWD	Walsh Water Rural Water District
DAK CARR	Dakota Carrier Network	NODAK R ELEC	Nodak Rural Electric Cooperative	WOLVRTN TEL	Wolverton Telephone
DAK CENT TEL	Dakota Central Telephone	NOON FRMS TEL	Noonan Farmers Telephone Company	XLENER	Xcel Energy
DAK RWD	Dakota Rural Water District	NPR	Northern Plains Railroad	YSVR	Yellowstone Valley Railroad
DGC	Dakota Gasification Company	NSP	Northern States Power		
DICKEY R NET	Dickey Rural Networks	NTH PRAIR RW	Northern Prairie Rural Water Association		
DICKEY RWU	Dickey Rural Water Users Association	NTHN BRDR PL	Northern Border Pipeline		
DICKEY TEL	Dickey Telephone	NTHN PLNS ELEC	Northern Plains Electric Cooperative Incorporated		
DNRR	Dakota Northern Railroad	NTHWSTRN REF	Northwestern Refinery Company		
DOME PL	Dome Pipeline Company	NW COMM	Northwest Communication Cooperation		
DVELEC	Dakota Valley Electric Cooperative	ONEOK	Oneok gas		
DVMW	Dakota, Missouri Valley & Western	OSHA	Occupational Safety and Health Administration		
ENBRDG	Enbridge Pipelines Incorporated	OTTR TL PWR	Otter Tail Power Company		
ENVENTIS	Enventis Telephone	P L E M	Prairielands Energy Marketing		
FALK MNG	Falkirk Mining Company	POLAR COM	Polar Communications		
FHWA	Federal Highway Administration	PVT ELEC	Private Electric		
G FKS-TRL WD	Grand Forks-trail Water District	QWEST	Qwest Communications		
GETTY TRD & TRAN	Getty Trading & Transportation	R&T W SUPPLY	R & T Water Supply Association		
GLDN W ELEC	Golden West Electric Cooperative	RAMSEY R SEW	Ramsey Rural Sewer Association		
GRGS CO TEL	Griggs County Telephone	RAMSEY RW	Ramsey Rural Water Association		
		RAMSEY UTIL	Ramsey County Rural Utilities		













NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930 , on 07/01/14 and the original document is stored at the North Dakota Department of Transportation
---








Line Styles

Existing Topography























	Existing Ground Void
	Existing Cemetary Boundary
	Existing Box Culvert Bridge
	Existing Concrete Surface
	Existing Drainage Structure
	Existing Gravel Surface
	Existing Riprap
	Existing Dirt Surface
	Existing Asphalt Surface
	Existing Tie Point Line
	Existing Railroad Centerline
	Existing Guardrail Cable
	Existing Guardrail Metal
	Existing Edge of Water
	Existing Fence
	Existing Railroad
	Existing Field Line
	Exst Flow
	Existing Curb
	Existing Valley Gutter
	Existing Driveway Gutter
	Existing Curb and Gutter
	Existing Mountable Curb and Gutter

	Existing 3-Cable w Posts
	Site Boundary
	Existing Berm, Dike, Pit, or Earth Dam
	Existing Ditch Block
	Existing Tree Boundary
	Existing Brush or Shrub Boundary
	Existing Retaining Wall
	Existing Planter or Wall
	Existing W-Beam Guardrail with Posts
	Existing Railroad Switch
	Gravel Pit - Borrow Area
	Existing Wet Area-Vegetation Break





Proposed Topography

	3-Cable w Posts
	Flow
	Fence
	Remove Line
	Wall
	Retaining Wall (Plan View)
	W-Beam w Posts










Existing Utilities

	Existing Electrical
	Existing Fiber Optic Line
	Existing TV Fiber Optic
	Existing Gas Pipe
	Existing Overhead Utility Line
	Existing Power
	Existing Fuel Pipeline
	Existing Undefined Above Ground Pipe Line
	Existing Sanitary Sewer
	Existing Sanitary Force Main
	Existing Storm Drain
	Existing Storm Drain Force Main
	Existing Culvert
	Existing Telephone Line
	Existing TV Line
	Existing Water or Steam Line
	Existing Under Drain
	Existing Slotted Drain
	Existing Conduit
	Existing Conductor
	Existing Down Guy Wire Down Guy
	Existing Underground Vault or Lift Station




Proposed Utilities

	24 Inch Pipe
	Reinforced Concrete Pipe
	Under Drain
	Edge Drain

Traffic Utilities

	Conductor
	Fiber Optic
	Existing Loop Detector
	Existing Double Micro Loop Detector
	Micro Loop Detector Double
	Existing Micro Loop Detector
	Micro Loop Detector
	Signal Head with Mast Arm
	Existing Signal Head with Mast Arm

Sign Structures

	Existing Overhead Sign Structure
	Existing Overhead Sign Structure Cantilever
	Overhead Sign Structure Cantilever

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
09-23-16	Added and Revised Items, Organized by Functional Groups

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 09/23/16 and the original document is stored at the North Dakota Department of Transportation

Line Styles

Right Of Way

	Easement
	Existing Easement
	Right of Way
	Existing Right of Way
	Existing Right of Way Railroad
	Existing Right of Way Not State Owned
	Existing Government Lot Line
	Existing Adjacent Block Lines
	Existing Adjacent Lot Lines
	Existing Adjacent Property Line
	Existing Adjacent Subdivision Lines
	Sight Distance Triangle Line
	Dimension Leader

Boundary Control

	Existing City Corporate Limits or Reservation Boundary
	Existing State or International Line
	Existing Township
	Existing County
	Existing Section Line
	Existing Quarter Section Line
	Existing Sixteenth Section Line
	Existing Centerline
	Tangent Line

Cross Sections and Typicals

	Existing Ground
	Existing Topsoil (Cross Section View)
	Existing Ground Void (Not Surveyed)
	Existing Concrete
	Existing Aggregate (Cross Section View)
	Existing Curb and Gutter (Cross Section View)
	Existing Asphalt (Cross Section View)
	Existing Reinforcement Rebar

Geotechnical

	Geotextile Fabric Type D
	Geogrid
	Geotextile Fabric Type R
	Geotextile Fabric Type R1
	Geotextile Fabric Type RR
	Geotextile Fabric Type S
	Subgrade Reinforcement
	Failure Line

Countours

	Depression Contours
	Supplemental Contour

Profile

	Subgrade, Subcut or Ditch Grade
	Topsoil Profile

Striping

	Centerline Pavement Marking
	Barrier with Centerline Pavement Marking
	Barrier Pavement Marking
	Stripe 4 IN Dotted Extension White
	Stripe 8 IN Dotted Extension White
	Stripe 8 IN Lane Drop

Pavement Joints

	Doweled Joint
	Tie Bar 30 Inch 4 Foot Center to Center
	Tie Bar 18 Inch 3 Foot Center to Center
	Tie Bar at Random Spacing

Bridge Details

	Hidden Object
	Small Hidden Object
	Large Hidden Object
	Phantom Object
	Centerline Main
	Centerline
	Existing Ground (Details)
	Existing Conditions
	Sheet Piling

Erosion Control

	Limits of Const Transition Line
	Bale Check
	Rock Check
	Floating Silt Curtain
	Silt Fence
	Excavation Limits
	Fiber Rolls

Environmental

	Wetland Mitigation
	Existing Wetland Easement USFWS
	Existing Wetland Jurisdictional
	Existing Wetland
	Tree Row

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
09-23-16	Added and Revised Items, Organized by Functional Groups





















































































This document was originally issued and sealed by  
Roger Weigel,  
Registration Number  
PE-2930 ,  
on 09/23/16 and the original document is stored at the  
North Dakota Department  
of Transportation

Symbols

	North Arrow (Half Scale)		Attenuation Device		Existing Railroad Battery Box		Existing Delineator Type E										
	Truck Mounted Attenuator		Diamond Grade Delineator Type A		Existing Bush or Shrub		Existing EFB Misc										
	Type I Barricade		Diamond Grade Delineator Type B		Existing Gas Cap or Stub		Existing Flashing Beacon										
	Type II Barricade		Diamond Grade Delineator Type C		Existing Sanitary Cap or Stub		Existing Pipe Mounted Flasher										
	Type III Barricade		Diamond Grade Delineator Type D		Existing Storm Drain Cap or Stub		Existing Pad Mounted Feed Point										
	Catch Basin		Diamond Grade Delineator Type E		Existing Water Cap or Stub		Existing Pipe Mounted Feed Point with Pad										
	Cairn or Stone Circle		Flexible Delineator		Existing Sanitary Cleanout		Existing Pole Mounted Feed Point										
	Video Detection Camera		Flexible Delineator Type A		Existing Concrete Foundation		Existing Railroad Frog										
	Storm Drain Cap or Stub		Flexible Delineator Type B		Existing Traffic Signal Controller		Existing Snow Gate 18										
	Corrugated Metal End Section 18 Inch		Flexible Delineator Type C		Existing Pad Mounted Signal Controller		Existing Snow Gate 28										
	Corrugated Metal End Section 24 Inch		Flexible Delineator Type D		Existing Sixteenth Section Corner		Existing Snow Gate 40										
	Corrugated Metal End Section 30 Inch		Flexible Delineator Type E		Existing Quarter Section Corner		Existing Headwall										
	Corrugated Metal End Section 36 Inch		Delineator Type A		Existing Section Corner		Existing Pedestrian Head with Number										
	Corrugated Metal End Section 42 Inch		Delineator Type A Reset		Existing Railroad Crossbuck		Existing Signal Head										
	Corrugated Metal End Section 48 Inch		Delineator Type B		Existing Satellite Dish		Existing Sprinkler Head										
	Concrete Foundation		Delineator Type B Reset		Existing Fuel Dispensers		Existing Fire Hydrant										
	Ground Connection Conductor		Delineator Type C		Existing Flexible Delineator Type A		Existing Catch Basin Drop Inlet										
	Neutral Connection Conductor		Delineator Type D		Existing Flexible Delineator Type B		Existing Curb Inlet										
	Phase 1 Connection Conductor		Delineator Type E		Existing Flexible Delineator Type C		Existing Manhole Inlet										
	Phase 2 Connection Conductor		Delineator Drums		Existing Flexible Delineator Type D		Existing Junction Box										
	Traffic Cone		Spot Elevation		Existing Flexible Delineator Type E	<table><tr><th colspan="2">NORTH DAKOTA DEPARTMENT OF TRANSPORTATION</th></tr><tr><th colspan="2">07-01-14</th></tr><tr><th colspan="2">REVISIONS</th></tr><tr><th>DATE</th><th>CHANGE</th></tr><tr><td></td><td></td></tr></table>		NORTH DAKOTA DEPARTMENT OF TRANSPORTATION		07-01-14		REVISIONS		DATE	CHANGE		
NORTH DAKOTA DEPARTMENT OF TRANSPORTATION																	
07-01-14																	
REVISIONS																	
DATE	CHANGE																
	Signal Controller		Existing Access Control Arrow		Existing Delineator Type A												
	Pad Mounted Signal Controller		Existing Artifact		Existing Delineator Type B												
	Alignment Data Point		Existing Flashing Beacon		Existing Delineator Type C												
	Emergency Vehicle Detector		Existing Benchmark		Existing Delineator Type D												

Symbols

D-101-31

	Existing Light Standard		Existing Manhole with Valve Water		Existing Telephone Pole		Existing Undefined Manhole
	Existing High Mast Light Standard 10 Luminaire		Existing Water Manhole		Existing Wood Pole		Existing Undefined Pull Box
	Existing High Mast Light Standard 3 Luminaire		Existing Mile Post Type A		Existing Post		Existing Undefined Pedestal
	Existing High Mast Light Standard 4 Luminaire		Existing Mile Post Type B		Existing Pedestrian Push Button Post		Existing Undefined Valve
	Existing High Mast Light Standard 5 Luminaire		Existing Mile Post Type C		Existing Control Point CP		Existing Undefined Pipe Vent
	Existing High Mast Light Standard 6 Luminaire		Existing Reference Marker		Existing Control Point GPS-RTK		Existing Gas Valve
	Existing High Mast Light Standard 7 Luminaire		Existing RW Marker		Existing Control Point TRI		Existing Water Valve
	Existing High Mast Light Standard 8 Luminaire		Existing Utility Marker		Existing Reference Marker Point NGS		Existing Fuel Pipe Vent
	Existing High Mast Light Standard 9 Luminaire		Iron Monument Found		Existing Pull Box		Existing Gas Pipe Vent
	Existing Overhead Sign Structure Load Center		Iron Pin R/W Monument		Existing Intelligent Transportation Pull Box		Existing Sanitary Pipe Vent
	Existing Luminaire		Existing Object Marker Type I		Existing Water Pump		Existing Storm Drain Pipe Vent
	Existing Light Standard Luminaire		Existing Object Marker Type II		Existing Slotted Reinforced Concrete Pipe		Existing Water Pipe Vent
	Existing Federal Mailbox		Existing Object Marker Type III		Existing RR Profile Spot		Existing Weather Station
	Existing Private Mailbox		Existing Electrical Pedestal		Existing Fuel Leak Sensors		Existing Ground Water Well Bore Hole
	Existing Meander Section Corner		Existing Telephone Pedestal		Existing Highway Sign		Existing Windmill or Tower
	Existing Meter		Existing Fiber Optic Telephone Pedestal		Existing Miscellaneous Spot		Existing Witness Corner
	Existing Electrical Manhole		Existing TV Pedestal		Existing Lighting Standard Pole		Flashing Beacon
	Existing Gas Manhole		Existing Fiber Optic TV Pedestal		Existing Traffic Signal Standard		Flagger
	Existing Sanitary Manhole		Existing Fuel Filler Pipes		Existing Transformer		Pipe Mounted Flasher
	Existing Sanitary Force Main Manhole		Existing Traverse PI Aerial Panel		Existing Large Evergreen Tree		Sanitary Force Main with Valve
	Existing Sanitary Manhole with Valve		Existing Pole		Existing Small Evergreen Tree		
	Existing Storm Drain Manhole		Existing Power Pole		Existing Large Tree		
	Existing Force Main Storm Drain Manhole		Existing Power Pole with Transformer		Existing Small Tree		
	Existing Force Main Storm Drain Manhole with Valve				Existing Tree Trunk		
	Existing Telephone Manhole				Existing Pad Mounted Traffic Signal Control Box		

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 07/01/14 and the original document is stored at the North Dakota Department of Transportation



Symbols



Pad Mounted Feed Point



Pipe Mounted Feed Point with Pad



Pole Mounted Feed Point



Headwall



Double Headwall with Vegetation Barrier



Single Headwall with Vegetation Barrier



Pole Mounted Head



Sprinkler Head



Fire Hydrant



Inlet Type 1



Inlet Type 2



Double Inlet Type 2



Inlet Grate Type 2



Junction Box



High Mast Light Standard 10 Luminaire



High Mast Light Standard 3 Luminaire



High Mast Light Standard 4 Luminaire



High Mast Light Standard 5 Luminaire



High Mast Light Standard 6 Luminaire



High Mast Light Standard 7 Luminaire



High Mast Light Standard 8 Luminaire



High Mast Light Standard 9 Luminaire



Relocate Light Standard



Overhead Sign Structure Load Center



Light Standard 100 Watt High Pressure Sodium Vapor Luminaire



Light Standard 1000 Watt High Pressure Sodium Vapor Luminaire



Light Standard 150 Watt High Pressure Sodium Vapor Luminaire



Light Standard 175 Watt High Pressure Sodium Vapor Luminaire



Light Standard 200 Watt High Pressure Sodium Vapor Luminaire



Light Standard 250 Watt High Pressure Sodium Vapor Luminaire



Light Standard 310 Watt High Pressure Sodium Vapor Luminaire



Light Standard 35 Watt High Pressure Sodium Vapor Luminaire



Light Standard 400 Watt High Pressure Sodium Vapor Luminaire



Light Standard 50 Watt High Pressure Sodium Vapor Luminaire



Light Standard 70 Watt High Pressure Sodium Vapor Luminaire



Light Standard 700 Watt High Pressure Sodium Vapor Luminaire



Manhole



Manhole 48 Inch



Sanitary Force Main Manhole



Sanitary Sewer Manhole



Storm Drain Manhole



Storm Drain Manhole with Inlet



Reset Mile Post



Mile Post Type A



Mile Post Type B



Mile Post Type C



Right of Way Marker



Tubular Marker



Alignment Monument



Iron Pin Reference Monument



Object Marker Type I



Object Marker Type II



Object Marker Type III



Caution Mode Arrow Panel



Back to Back Vertical Panel Sign



Double Direction Arrow Panel



Left Directional Arrow Panel



Right Directional Arrow Panel



Sequencing Arrow Panel



Truck Mounted Arrow Panel



Power Pole



Wood Pole



Pedestrian Push Button Post



Property Corner



Pull Box



Intelligent Transportation Pull Box



Sanitary Pump



Storm Drain Pump



Reinforced Pavement



Reinforced Concrete End Section 15 Inch



Reinforced Concrete End Section 18 Inch



Reinforced Concrete End Section 24 Inch



Reinforced Concrete End Section 30 Inch



Reinforced Concrete End Section 36 Inch



Reinforced Concrete End Section 42 Inch



Reinforced Concrete End Section 48 Inch



Reinforced Concrete End Section 54 Inch



Reset Right of Way Marker



Reset USGS Marker



Right of Way Markers



Riser 30 Inch



Continuous Split Barrel Sample



Flight Auger Sample



Split Barrel Sample



Thinwall Tube Sample



Highway Sign



SNOW GATE 18 FT



SNOW GATE 28 FT



SNOW GATE 40 FT



Standard Penetration Test



Transformer



Inclinometer Tube



Underdrain Cleanout



Excavation Unit




Water Valve

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 07/01/14 and the original document is stored at the North Dakota Department of Transportation

LANE MARKERS  
(Spotting Tab for Seal Projects only)

D-704-3



Marker Body




Marker Body with Protective Cover


- Notes:
- 1. The lane line markers shall be installed as shown, prior to the beginning of the seal coat.
  - 2. The cover shall be attached to the vertical part of the marker in such a way that traffic will not cause it to detach and so that it may be easily removed manually.
  - 3. The protective covers shall be removed, immediately after the seal coat is applied.
  - 4. The markers shall be removed after permanent pavement marking has been installed.
  - 5. The marker body and cover shall be manufactured from polyurethane material.
  - 6. Marker types:  
Type Y - Yellow body and cover with yellow reflective tape on both sides.  
Type W - White body and cover with white reflective tape on one side.
  - 7. The reflective tape shall be a retroreflective material. The tape shall have a minimum reflectance of 1200 candle power per foot-candle per square foot, using a .1 degree observation angle and 0 degree entrance angle.
  - 8. The adhesive shall conform to AASHTO M 237.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-3-13	
REVISIONS	
DATE	CHANGE



This document was originally issued and sealed by Roger Weigel Registration Number PE- 2930 , on 10/3/13 and the original document is stored at the North Dakota Department of Transportation




Multi-Directional Slip Base Assembly



Anchor Unit and Post Assembly




Multi-Directional Slip Base Anchor Unit and Post Sleeve Assembly




Top Post Receiver

Plate - ASTM A572 grade 50  
Angle Receiver - 2 1/2"x2 1/2"x3/8" ASTM A36 structural angle



Bottom Soil Stub

Tube - 3"x3"x7 gauge ASTM A500 grade B tube  
Stabilizing Wing - 7 gauge H.R.P.O. ASTM A1011  
Plate - ASTM A572 grade 50



Bolt Retainer for Base Connection  
Bolt Retainer- 1/32" Reprocessed Teflon

Notes:

1. Slip base bolts shall be torqued as specified by the manufacturer.
2. Anchor shall have a yield strength of 43.9 KSI and tensile strength of 59.3 KSI.
3. The 4" vertical clearance is required for the anchor or breakaway base. The 4"x60" measurement shall be made above and below post location and also back and ahead of the post.
4. When used in concrete sidewalk, anchor shall be same except without the wings.
5. Four post signs shall have over 7' between the first and the fourth posts.

Telescoping Perforated Tube						
Number of Posts	Post Size in.	Wall Thickness Gauge	Sleeve Size in.	Wall Thickness Gauge	Slip Base	Anchor Size without Slip Base in.
1	2	12			No	2 1/4
1	2 1/4	12			No	2 1/2
1	2 1/2	12			(A)	3
1	2 1/2	10			Yes	
1	2 1/4	12	2	12	Yes	
1	2 1/2	12	2 1/4	12	Yes	
2	2	12			No	2 1/4
2	2 1/4	12			No	2 1/2
2	2 1/2	12			Yes	
2	2 1/2	12			Yes	
2	2 1/4	10	2	12	Yes	
2	2 1/2	12	2 1/4	12	Yes	
3 & 4	2 1/2	12			Yes	
3 & 4	2 1/2	10			Yes	
3 & 4	2 1/2	12	2 1/4	12	Yes	
3 & 4	2 1/4	12	2	12	Yes	
3 & 4	2 1/2	10	2 3/16	10	Yes	

Properties of Telescoping Perforated Tube						
Tube Size in.	Wall Thickness in.	U.S. Standard Gauge	Weight per Foot lbs.	Moment of Inertia in. <sup>4</sup>	Cross Sec. Area in. <sup>2</sup>	Section Modulus in. <sup>3</sup>
1 1/2 x 1 1/2	0.105	12	1.702	0.129	0.380	0.172
2 x 2	0.105	12	2.416	0.372	0.590	0.372
2 1/4 x 2 1/4	0.105	12	2.773	0.561	0.695	0.499
2 3/16 x 2 3/16	0.135	10	3.432	0.605	0.841	0.590
2 1/2 x 2 1/2	0.105	12	3.141	0.804	0.803	0.643
2 1/2 x 2 1/2	0.135	10	4.006	0.979	1.010	0.785

Top Post Receiver Data Table						
Square Post Sizes (B)	A	B	C	D	E	F
2 3/16"x10 ga.	1 9/64"	2 1/2"	3 1/32"	2 5/32"	1 33/64"	1 7/8"
2 1/2"x10 ga.	1 9/32"	2 1/2"	3 5/16"	5/8"	1 21/32"	1 3/4"



(A) The breakaway base is required when the support is placed in weak soils. The Engineer shall determine if the soils are weak.

(B) The 2 3/16"x10 ga. may be inserted into 2 1/2"x10 ga. for additional wind load.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
2-28-14	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by  
Roger Weigel,  
Registration Number  
PE-2930,  
on 2/28/14 and the original document is stored at the  
North Dakota Department  
of Transportation

U-Channel Post




Breakaway U-Channel Detail Alternate A

A maximum of 2 posts shall be installed within 7'.




Retainer Strap Detail



Breakaway U-Channel Splice Detail Alternate B (2.5 and 3 lb/ft)

A maximum of 3 posts shall be installed within 7'.



Breakaway U-Channel Splice Detail Alternate C (2.5 and 3 lb/ft)

A maximum of 3 posts shall be installed within 7'.

Alternate A Steps of Installation:


- a) Drive anchor unit to within 12" of ground level.  
b) Proper assembly established by lining up the bottom hole of retainer strap with the 6th hole from the top of the anchor unit.  
c) Assemble strap to back of anchor unit using  $\frac{5}{16}$ "x2" bolt, lock washer and nut.  
d) Rotate strap 90° to left.
- a) Drive anchor unit to 4" above ground.  
b) Rotate strap to vertical position.
- a) Place  $\frac{5}{16}$ "x2" bolt, lock washer and nut in bottom of sign post to facilitate alignment of sign post with proper hole in anchor unit.  
b) Alternately tighten two connector bolts.
- Complete assembly by tightening  $\frac{5}{16}$ "x2" bolt (this fastens sign post to retainer strap).
- The base post, strap and sign post shall be properly nested. Proper nesting occurs when all flat surfaces of the base post, strap, and sign post at the bolts have full contact across the entire width.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
2-28-14	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by  
Roger Weigel,  
Registration Number  
PE- 2930 ,  
on 2/28/14 and the original document is stored at the  
North Dakota Department  
of Transportation

CONSTRUCTION SIGN DETAILS  
TERMINAL AND GUIDE SIGNS


D-704-9



G20-1-60  
Legend: black (non-refl)  
Background: orange




G20-1b-60  
Legend: black (non-refl)  
Background: orange




G20-2-48  
Legend: black (non-refl)  
Background: orange




G20-4b-36  
Legend: black (non-refl)  
Background: orange




G20-50a-72  
Legend: black (non-refl)  
Background: orange




G20-52a-72  
Legend: black (non-refl)  
Background: orange




G20-55-96  
Legend: black (non-refl)  
Background: orange




E5-1(L or R)-48  
Legend: white  
Background: green (orange optional)




M4-8-36  
Legend: black (non-refl)  
Background: orange




M4-9(L or R)-30 &  
M4-9-30  
Legend: black (non-refl)  
Background: orange




E5-1-48




G20-50a-72  
G20-52a-72



M4-9(L or R)-30  
Right or Left



M4-9(L or R)-30  
Advanced Right or Left



M4-9-30  
Straight






ARROW DETAILS

- NOTES:
- (A) Arrow may be right or left of the legend to indicate construction to the right or left.





NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-13-13	
REVISIONS	
DATE	CHANGE
8-17-17	Added sign & background color

This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930, on 8/17/17 and the original document is stored at the North Dakota Department of Transportation








D-704-10



NORTH DAKOTA DEPARTMENT OF TRANSPORTATION		<p>This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930 , on 8/17/17 and the original document is stored at the North Dakota Department of Transportation</p>
8-13-13		
REVISIONS		
DATE	CHANGE	
8-17-17	Revised sign number	




### \* DISTANCE MESSAGES




This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 8/17/17 and the original document is stored at the North Dakota Department of Transportation

SHOULDER CLOSURE TAPERS


D-704-12



SHOULDER CLOSURE WITH LANE CLOSURE  
(when shoulder is 8' or wider)



SHOULDER CLOSURE USED WITH LANE CLOSURE  
(when shoulder is less than 8' wide)



PORTABLE TRAFFIC SIGNAL OR CHANGEABLE MESSAGE SIGN ON SHOULDER

KEY			
●	Delineator Drum	∞	Sequencing Arrow Panel
•	Message Display	↳	Portable Traffic Signal

- Notes:
- S = Posted Speed Limit in mph  
W = Width of offset in feet  
L = Taper length in feet  
L =  $WS^2/60$  (40mph or less)  
L = WS (45mph or more)
  - If a shoulder taper is used, it should have a length of approximately  $\frac{1}{3}L$ . If a shoulder is used as a travel lane, a normal merging or shifting taper should be used.
  - When paved shoulders of 8 foot width or more are closed, channelizing devices shall be used to close the shoulder in advance to delineate the beginning of the work space and direct vehicular traffic to remain within the traveled way.


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-3-13	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by  
Roger Weigel  
Registration Number  
PE-2930,  
on 10/3/13 and the original document is stored at the  
North Dakota Department  
of Transportation



BARRICADE AND CHANNELIZING DEVICE DETAILS

D-704-13




The markings on drums shall be horizontal, circumferential, alternating orange and white retroreflective stripes 4" to 6" wide. Each drum shall have a minimum of two orange and two white stripes with the top stripe being orange. Any nonretroreflectorized spaces between the horizontal orange and white stripes shall not exceed 3" wide. Stripes shall not be placed on ribs or indentations in the drum. Drums shall have closed tops that will not allow collection of construction debris or other debris. Ballast shall not be placed on the top of a drum.

Markings for vertical panels shall be alternating orange and white retroreflective stripes, sloping downward in the direction vehicular traffic is to pass. Retroreflective sheeting shall be placed on both sides of panel and shall have a minimum of 270 square inches of retroreflective area facing vehicular traffic. Where the height of the retroreflective material on the vertical panel is 36 inches or more, a stripe width of 6 inches shall be used.

Retroreflectorization of cones more than 36" in height shall be provided by alternating orange and white retroreflective stripes. Each cone shall have a minimum of two orange and two white stripes with the top stripe being orange. Any nonretroreflectorized space between the orange and white stripes shall not exceed 3" wide.

Retroreflectorization of tubular markers more than 42" in height shall be provided by alternating four 4" to 6" wide orange and white stripes with the top stripe being orange.


- INSTALLATION NOTES:
1. Drill installation holes to diameter and depth as required by manufacturer's specifications.
  2. For removal, remove anchors and fill installation hole with an epoxy designed to bond to pavement surface.
  3. In lieu of bolted down base, the contractor may use an 8" x 8" butyl pad or hot melt butyl. Butyl shall be removed as close as possible to pavement surface.




BARRICADE BLADE DETAIL

BARRICADE ASSEMBLY DETAIL (Aluminum Barricade Rails)

NOTE: Markings for barricades shall be alternating orange and white retroreflective stripes, sloping downward in the direction traffic is to pass. Retroreflective sheeting shall be placed on both sides of the rails and shall have a minimum of 270 square inches of visible retroreflective area facing vehicular traffic. When the barricade length is less than 36", the rail stripe width shall be 4".




TYPE I BARRICADE




TYPE II BARRICADE

BARRICADE RAIL DETAILS



TYPE III BARRICADE



ELEVATION VIEW

BARRICADE ASSEMBLY DETAIL (Wood or Plastic Rails)

SIDE VIEW

MINIMUM BALLAST (For each side of barricade support)

Without Sign	4 - 25 lb sandbags
With Sign	6 - 25 lb sandbags


Note: The number of sandbags are based on a wind speed of 55 MPH. The sandbags are assumed to be placed at or near the ends of the skids.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-3-13	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by  
Roger Weigel,  
Registration Number  
PE-2930,  
on 10/3/13 and the original document is stored at the  
North Dakota Department  
of Transportation

# CONSTRUCTION SIGN PUNCHING AND MOUNTING DETAILS


Note: Signs placed in sections with curb shall have a minimum horizontal clearance of 2' from the face of the curb to the near edge of the sign.




TYPICAL SECTION  
(48" x 48" diamond warning sign shown)




24" x 24" ROUTE MARKER ASSEMBLY




36" x 36" ROUTE MARKER ASSEMBLY




18" x 18" DIAMOND SIGN




48" x 48" DIAMOND SIGN  
(with 30" x 30" secondary sign)




48" x 48" DIAMOND SIGN  
(with 30" x 24" secondary sign)




R1-2-60 - YIELD SIGN




W14-3-64 - PENNANT SIGN




R1-1-48 - STOP SIGN  
(with R6-1-54 sign as required)




R1-1-48 - STOP SIGN  
(with R1-50-24 sign as required)




48" x 48" SIGN  
(with R6-1-54 sign as required)




48" x 48" SIGN  
(with R2-1a-24 sign as required)




24" x 36" SIGN




30" x 24" SIGN




108" x 48" SIGN




96" x 48" SIGN




72" x 36" SIGN




72" x 24" SIGN




60" x 24" SIGN



48" x 24" SIGN



PORTABLE SIGN SUPPORT  
LOW-MOUNTING HEIGHT



PORTABLE SIGN SUPPORT  
HIGH-MOUNTING HEIGHT

## NOTES:

1. Sign Supports: Supports shall be galvanized or painted. Minimum post sizes are 2.5 lb/ft u-channel or 2" x 2" x 12 gauge steel perforated tube, except where noted. When installing signs on u-channel, the minimum post size for assemblies containing a secondary sign is 3.0 lb/ft. Post sizes are based on a wind speed of 55 MPH.

Signs over 50 square feet should be installed on 2½" x 2½" perforated tube supports as a minimum.

Guy wires shall not be attached to sign supports. Wind beams may be attached to u-posts behind the sign panels.

2. Sign Panels: Provide sign panels made of 0.100" aluminum, ½" plywood, or other approved material, except where noted. All holes to be punched round for ⅜" bolts.

3. Alternate Messages: The signs that have alternate messages may have these alternate messages placed on a reflectorized plate (without a border) and installed and removed as required. (i.e. "Left" and "Right" message on a lane closure sign)

4. Route Marker Auxiliary Signs: Provide route marker auxiliary signs, such as the cardinal direction and directional arrows, with a background and legend that match the route marker they are used with:

Interstate - white legend on blue background  
Interstate Business Loop - white legend on green background  
US and State - black legend on white background  
County - yellow legend on blue background

5. Vertical Clearance: Install signs with a vertical clearance of 5'-0" (see TYPICAL SECTION.) In areas where parking or pedestrian movements are likely or the view of the sign may be obstructed, install signs with a vertical clearance of 7'-0" from the top of the curb or from the near edge of the driving lane in absence of a curb.

The vertical clearance to secondary signs is 1'-0" less than the vertical clearance as stated above.

Large signs having an area exceeding 50 square feet shall have a minimum clearance of 7'-0" from the ground at the post.

6. Portable Signs: Provide portable signs that meet the vertical clearance as stated above. Use portable signs when it is necessary to place signs within the pavement surface.

When portable signs are used for 5 days or less, low-mounting height (minimum 12" vertical clearance) sign supports may be used as long as the view of the sign is not obstructed. Time delays caused by unforeseen circumstances, such as equipment breakdown, rain, subgrade failures, etc., will not accrue towards the 5 day period. The R9-8 through R9-11a series, W1-6 through W1-8 series, M4-10, and E5-1 may be used for longer than 5 days.

Signs mounted to the portable sign supports shown in the LOW-MOUNTING HEIGHT and HIGH-MOUNTING HEIGHT Details shall have a maximum surface area of 16 square feet.

## MINIMUM BALLAST (For each side of sign support base)

Sign Panel Mounting Height (ft)	Number of 25 lb sandbags for 4' x 4' sign panel
1'	6
5'	8
7'	10


Note: The number of sandbags are based on a wind speed of 55 MPH. The sandbags are assumed to be placed at or near the ends of the skids.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-4-13	
REVISIONS	
DATE	CHANGE
11-14-13	Revised Note 6.

This document was originally issued and sealed by  
Roger Weigel,  
Registration Number  
PE-2930,  
on 11/14/13 and the original document is stored at the  
North Dakota Department  
of Transportation

CONSTRUCTION TRUCK AND TEMPORARY DETOUR LAYOUTS

D-704-22



Notes

- Place barricades on a moveable assemblies and signs on portable assemblies when located on roadway.
- Where necessary, safe speed to be determined by the Engineer.
- Determine the reduced speed limit based on the in-place speed limit before construction. Where speed reductions exceed 30 mph, install a second speed limit sign with the desired speed reduction (not to exceed 30 mph.) Place the second speed limit sign at 1/2 B.
- Install flags on warning signs in urban areas when signs are not portable. Mount 24 inch square flags perpendicular to the edges of the sign, and at such a distance above the edge that the flag does not touch the sign when limp.
- Cover existing speed limit signs within a reduced speed zone.
- Covered (when approved by engineer) or obliterated pavement marking measured as Obliteration of Pavement Marking.
- As an option, use portable sign supports in lieu of post mounted signs in accordance with NDDOT Standard Specifications.
- Install sign G20-1b-60 when work is suspended for winter.
- If existing stop sign is in place, a 48" stop sign is not required.
- Sign G20-55-96 is not required if layout is part of other traffic control or if work is less than 15 days.
- Recommend using 40 mph speed limit in vicinity of workers, unless location and conditions dictate otherwise.







ADVANCE WARNING SIGN SPACING			
Road Type	Distance Between Signs		
	A	B	C
Urban - Low Speed (30 mph or less)	150	150	150
Urban - Low Speed (over 30 to 40mph)	280	280	280
Urban - High Speed (over 40 mph to 50 mph)	360	360	360
Rural - High Speed (over 50 mph to 65 mph)	720	720	720
Urban Expressway and Freeway (55 mph to 60 mph)	850	1350	2200
Rural Expressway and Freeway (70 mph to 75 mph)	1000	1500	2640
Interstate/4-Lane Divided (Maintenance and Surveying)	750	1000	1500

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-27-13	
REVISIONS	
DATE	CHANGE
8-17-17	Update notes & sign numbers


This document was originally issued and sealed by  
Roger Weigel  
Registration Number  
PE- 2930,  
on 08/17/17 and the original document is stored at the  
North Dakota Department  
of Transportation

TRAFFIC CONTROL PLAN FOR MOVING OPERATIONS

D-704-27



Sign Details



Notes

1. If the contractor chooses to place more vehicles in the convoy than are shown, these vehicles shall have the truck mounted attenuator and shall be at the contractor's expense.
2. Shadow and work vehicles shall display yellow rotating beacons or strobe lights unless otherwise stated elsewhere in the plans.
3. Flashing arrow panels shall be Type B or Type C. The panel operation shall be controlled from inside the vehicle.
4. Each vehicle shall have two-way electronic communication capability.
5. When work convoys must change lanes, shadow vehicle 1 should change lanes first to shadow other convoy vehicles.
6. Vehicle spacing between the shadow vehicle 1 and shadow vehicle 2 will vary depending on sight distance restrictions. Motorists approaching the work convoy should be able to see the trail vehicle in time to slow down and/or change lanes as they approach the shadow vehicle.
7. Sign Colors  
Letters = Black  
Border = Black  
Background = Orange
8. Shadow vehicle 2 may be used as the paint tender vehicle.
9. Sign CW21-10A shall only be used during a painting operation.
10. On two lane - two way roadways, the work and shadow vehicles should pull over periodically to allow motor vehicle traffic to pass.

KEY


- Sign
- Truck mounted attenuator
- Flashing arrow panels:
  - Right directional
  - Left directional
  - Double arrow directional
  - Caution Mode

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-27-13	
REVISIONS	
DATE	CHANGE
6-18-14	Removed shadow vehicle 2 on two lane roadways

This document was originally issued and sealed by  
Roger Weigel  
Registration Number  
PE- 2930 ,  
on 06/18/14 and the original document is stored at the  
North Dakota Department  
of Transportation

TRAFFIC CONTROL SYSTEM  
LANE SHIFT BETWEEN A LANE CLOSURE AND AN OPPOSITE LANE CLOSURE

D-704-34A



QUANTITIES	
TYPE III BARRICADES	2 Each
DELINEATOR DRUMS	14 Each
TUBULAR MARKERS	14 Each
RAISED PAVEMENT MARKERS (White)	Varies
OBLITERATION OF PAVEMENT MARKING	Varies

KEY	
	Work area
	Type III barricade
	Traffic Direction
	Delineator drum
	Tublar markers
	Sign

LEGEND	
E	Obliteration of pavement marking (10' line, 30' skip centerline)
G	Raised pavement markers (white) 5' ctrs.

- Notes
- Variables
    - S = Numerical value of posted speed limit, off-peak 85th percentile speed prior to work starting, or the anticipated operating speed in mph.
    - W = Width of offset in feet.
    - L = Taper length in feet. Speeds 40 mph or less  $L=WS^2/60$ . Speeds 45 mph or greater  $L=WS$ .
  - Signs and barricade shown to be placed on roadway shall be placed on moveable assemblies.
  - Existing speed limit signs within a reduced speed zone shall be covered.
  - Obliterated or covered pavement marking shall be paid for as Obliteration of Pavement Marking. The covering shall be approved by the Engineer.
  - The contractor has the option of using portable sign supports in lieu of post mounted sign as shown on the standard drawings in accordance with NDDOT Standard Specifications.
  - When placing traffic control devices, speed reductions will be necessary. The "Minimum Fee \$80" sign shall be placed below these speed limit signs.
  - Obliteration of pavement marking (10' line, 30' skip, centerline) and raised pavement markers are not necessary when the work is 14 days or less.



Longitudinal Buffer Space	
*Speed (mph)	Length Min (feet)
20	115
25	155
30	200
35	250
40	305
45	360
50	425
55	495
60	570
65	645
70	730
75	820

\* Posted speed, off-peak 85th percentile speed prior to work starting, or the anticipated operating speed in mph.

ADVANCE WARNING SIGN SPACING			
Road Type	Distance Between Signs Min. (ft)		
	A	B	C
Urban - Low Speed (30 mph or less)	150	150	150
Urban - Low Speed (over 30 to 40 mph)	280	280	280
Urban - High Speed (over 40 mph to 50 mph)	360	360	360
Urban - High Speed (over 50 mph to 65 mph)	720	720	720
Urban Expressway and Freeway (55 mph to 60 mph)	850	1350	2200
Rural Expressway and Freeway (70 mph to 75 mph)	1000	1500	2640
Interstate/4-Lane Divided (Maintenance and Surveying)	750	1000	1500

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-26-2012	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by  
Roger Weigel,  
Registration Number  
PE- 2930,  
on 10/26/12 and the original document is stored at the  
North Dakota Department  
of Transportation

SIGN LAYOUT FOR ONE LANE CLOSURE  
INTERSTATE SYSTEMLEFT LANE CLOSED  
WORKERS IN WORK AREA

LEFT SHOULDER TAPER DETAIL



ADVANCE WARNING SIGN SPACING			
Road Type	Distance Between Signs Min. (ft)		
	A	B	C
Rural - High Speed (over 50 mph to 65 mph)	720	720	720
Urban Expressway and Freeway (55 mph to 60 mph)	850	1350	2200
Rural Expressway and Freeway (70 mph to 75 mph)	1000	1500	2640
Interstate/4-Lane Divided (Maintenance and Surveying)	750	1000	1500

Longitudinal Buffer Space	
Speed (mph)*	Length Min (feet)
20	115
25	155
30	200
35	250
40	305
45	360
50	425
55	495
60	570
65	645
70	730
75	820

\*Posted speed, off-peak 85th percentile speed prior to work starting, or the anticipated operating speed in mph.

## Notes:

1. Install advance signs for flagging when flaggers are flagging.
2. Move the advanced flagger sign and the speed limit signs as the work area moves through the construction zone. When the work area is not visible from the flagger, move the flagger station so the work area is visible. Space the 40 mph speed limit sign at  $\frac{1}{2}A$  in advance of the flagger sign and move the 65 mph speed limit sign. Cover or remove the 40 mph speed limit and Minimum Fee \$80 signs and the 65 mph speed limit sign upon completion of the work day or when workers are not present.
3. RAMPs: When the work area encompasses an entrance ramp, install a 40 mph speed limit sign on the ramp and cover any existing yield sign. Install new yield sign as necessary. Remove the ramp speed limit sign when the main line 40 mph speed zone is moved past the ramp.
4. Variables:  
 S=Numerical value of speed limit or 85th percentile  
 W=The width of taper.  
 L=Minimum length of taper, or  $S \times W$  for freeways, expressways, and all other roads with speeds of 45 mph or greater, or  $W \times S \times S/60$  for urban, residential, and other streets with speeds of 40 mph or less.
5. Space delineator drums for tapering traffic at the dimension "S". Space the tubular markers used for tangents at 2 times dimension "S".
6. Place sequencing arrow panels at the beginning of the taper when possible. Where shoulder width does not provide sufficient room, move the panel closer to the work area and place on the roadway surface.  
 Use Type C on roadways with high traffic speeds and volumes (over 40 mph or 5000 ADT or greater).
7. Re-establish the speed limit. Determine the exact speed limit in the field, dependent on location and conditions.
8. Cover existing speed limit signs within a reduced speed zone.
9. Upon approval, the Engineer will measure obliterated or covered pavement marking as Obliteration of Pavement Marking.
10. Install flags on warning signs in urban areas when signs are not portable. Mount 24 inch square flags perpendicular to the edges of the diamond sign, and at such a distance above the edge that the flag does not touch the sign when limp.
11. Determine the reduced speed limit dependent on the in place speed limit before construction. When speed limits are to be reduced more than 30 mph, install a second speed limit sign with the desired speed reduction (not to exceed 30 mph.) Place the second speed limit sign at  $\frac{1}{2}B$ .
12. As an option, use portable sign supports in lieu of post mounted signs in accordance with NDDOT Standard Specifications.
13. Sign G20-55-96 is not required if this standard is part of other traffic control, or the work is less than 15 days.


RIGHT LANE CLOSED  
WORKERS IN WORK AREA

RIGHT SHOULDER TAPER DETAIL

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION		
9-7-2012		
REVISIONS		
DATE	CHANGE	
6/23/2014	Revised Note 12	
3/15/2016	Removed Do Not Pass signs and updated notes	
8/17/2017	Moved speed signs. Added note	

This document was originally issued and sealed by  
 Roger Weigel,  
 Registration Number  
 PE-2930,  
 on 08/17/17 and the original document is stored at the  
 North Dakota Department  
 of Transportation

D-704-50



NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
11-23-10	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by  
Roger Weigel  
Registration Number  
PE- 2930 ,  
on 11/23/10 and the original document is stored at the  
North Dakota Department  
of Transportation

INTERSTATE PAVEMENT MARKING  
4 LANE DIVIDED HIGHWAY

D-762-2

NOTE:

- (A) 4" White edge line  
(B) 4" Yellow edge line  
(C) Assume "varies" to equal 790' for purpose of estimate. The pavement marking shall begin at the beginning of the taper and end at the 8" line.  
(D) Beginning of physical gore to theoretical gore.  
(E) If the distance is less than 350' then extend the 8" channel line to the theoretical gore, otherwise use 195'.  
(F) 195' was used for estimating purposes.  
(G) Not required when crossroad approaches have gravel surface.  
(H) 4' minimum, 15' maximum from the nearest edge of the intersection traveled way.



BASIS OF ESTIMATE		
LOCATION	ITEM	
Right or Left Side Exit Ramp TAPERED	8" White channel line	580 LF
	24" White stop line	60 LF
	4" White dotted line	148 LF
	4" White edge line	1115 LF
	4" Yellow edge line	1075 LF
Entrance Ramp TAPERED	8" White channel line	390 LF
	4" White dotted line	258 LF
	4" White edge line	1270 LF
	4" Yellow edge line	1075 LF
Right or Left Side Exit Ramp PARALLEL	8" White channel line	396 LF
	24" White stop line	60 LF
	4" White dotted line (C)	258 LF
	4" White edge line	1115 LF
	4" Yellow edge line	1075 LF
Entrance Ramp PARALLEL	8" White channel line	388 LF
	4" White dotted line	283 LF
	4" White edge line	1275 LF
	4" Yellow edge line	1075 LF
Main Line (Both Roadways)	4" White line, 10' line, 30' skip	2640 LF/M
	4" White edge line	10,560 LF/M
	4" Yellow edge line	10,560 LF/M
Cross Road	4" White edge line	2000 LF
	4" Dbl yellow barrier line (4" between)	2000 LF

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-3-11	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by  
Roger Weigel,  
Registration Number  
PE- 2930,  
on 08/03/11 and the original document is stored at the  
North Dakota Department  
of Transportation




PAVEMENT MARKING

D-762-4


NOTES:  
1. Edge lines shall be continued through private drives and field drives and broken for intersections.




Two Lane Two Way  
RURAL ROADWAY




Two Lane Roadway  
INTERSTATE HIGHWAY  
Concrete Section




RURAL FIVE LANE ROADWAY  
Concrete Section




Two Lane Divided  
Rural Roadway  
PRIMARY HIGHWAY  
Asphalt Section




RURAL FIVE LANE ROADWAY  
Asphalt Section




URBAN FIVE LANE SECTION  
Concrete Section




Two Lane Roadway  
PRIMARY HIGHWAY  
Concrete Section




URBAN FIVE LANE SECTION  
Asphalt Section




RURAL FOUR LANE ROADWAY  
Asphalt Section




Two Lane Roadway  
INTERSTATE HIGHWAY  
Asphalt Section




RURAL FOUR LANE ROADWAY  
Concrete Section



URBAN FOUR LANE SECTION  
Asphalt Section



URBAN FOUR LANE SECTION  
Concrete Section




CENTERLINE PAVEMENT MARKING SKIP SPACING DETAIL

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
12-1-10	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930, on 12-1-10 and the original document is stored at the North Dakota Department of Transportation

SHORT-TERM PAVEMENT MARKING

D-762-11




Painted or Tape Lines




Raised Pavement Markers

TWO-LANE TWO-WAY ROADWAY




Painted or Tape Lines




Raised Pavement Markers

FOUR LANE ROADWAY




Painted or Tape Lines




Raised Pavement Markers

FIVE LANE ROADWAY TWO WAY LEFT TURN



Painted or Tape Lines



Raised Pavement Markers

FIVE LANE ROADWAY WITH MARKED ISLANDS

- NOTES:
- Two-lane two-way roadways shall have no passing zones placed as shown. No passing zone signs may be placed in lieu of short term no passing zone pavement markings. These signs will be allowed to remain in place for three days, at which time the short term no passing zone pavement marking shall be placed.
  - Short term center line stripe (paint) on top lift shall be carefully placed with exact spacing so that the permanent stripe will match when applied.
  - Raised markers and tape markings shall be removed after permanent pavement marking has been installed. Removed markings shall become the property of the contractor.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
12-1-10	
REVISIONS	
DATE	CHANGE
3-29-16	Re-numbered to be D-762-11 (previously was D-762-6)

This document was originally issued and sealed by  
Roger Weigel,  
Registration Number  
PE- 2930 ,  
on 03/29/16 and the original document is stored at the  
North Dakota Department  
of Transportation