

DESIGN DATA				
Traffic	Average Daily			
Current 2016	Pass: 490	Trucks: 120	Total: 610	
Forecast 2036	Pass: 635	Trucks: 155	Total: 790	
Clear Zone Distance: Existing		Design Speed: 65 MPH		
Minimum Sight Dist. for Stopping: Existing		Bridges: N/A		
Sight Dist. for No Passing Zone: Existing				
Pavement Design Life: N/A				
Design Accumulated One-way Flexible ESALs: N/A				

JOB # 37

NORTH DAKOTA

DEPARTMENT OF TRANSPORTATION

NH-3-001(027)161

Nelson County


1 Mile South of US HWY 2 to US HWY 2

HMA Overlay

	STATE	PROJECT NO.	PCN	SECTION NO.	SHEET NO.
	ND	NH-3-001(027)161	21667	1	1

GOVERNING SPECIFICATIONS:
2014 Standard Specifications adopted by the North Dakota
Department of Transportation and the Supplemental Specifications
effective on the date the project is advertised.

PROJECT NUMBER \ DESCRIPTION	NET MILES	GROSS MILES
NH-3-001(027)161 HMA Overlay	0.942	0.942



STATE COUNTY MAP

DESIGNERS

Dustin Legacie

APPROVED DATE 08/29/17

Wyatt Hanson

NDDOT DEVILS LAKE DISTRICT

I hereby certify that the attached plans were prepared by me or under my direct supervision and that I am a duly registered professional engineer under the laws of the state of ND.

APPROVED DATE 08/29/17




Wyatt Hanson

NDDOT DEVILS LAKE DISTRICT


This document was originally issued and sealed by Wyatt Hanson Registration Number PE- 6867 , on 08/29/17 and the original document is stored at the North Dakota Department of Transportation

TABLE OF CONTENTS						STATE	PROJECT NO.	SECTION NO.	SHEET NO.
						ND	NH-3-001(027)161	2	1
PLAN SECTIONS			LIST OF STANDARD DRAWINGS						
Section	Page(s)	Description	Number	Description					
1	1	Title Sheet	D-101-1, 2, 3	NDDOT Abbreviations					
2	1	Table of Contents	D-101-10	NDDOT Utility Company and Organization Abbreviations					
4	1	Scope of Work	D-101-20, 21	Line Styles					
6	1	Notes	D-101-30, 31, 32	Symbols					
8	1	Quantities	D-704-2	Traffic Control For Coring Of Hot Bituminous Pavement					
10	1	Basis of Estimate	D-704-7	Breakaway Systems For Construction Zone Signs - Perforated Tube					
20	1-2	General Details	D-704-8	Breakaway Systems For Construction Zone Signs - U-Channel Post					
30	1-2	Typical Sections	D-704-9	Construction Sign Details - Terminal And Guide Signs					
100	1-2	Work Zone Traffic Control	D-704-10	Construction Sign Details - Regulatory Signs					
			D-704-11	Construction Sign Details - Warning Signs					
			D-704-13	Barricade And Channelizing Device Details					
			D-704-14	Construction Sign Punching And Mounting Details					
			D-704-15	Road Closure Layouts					
			D-704-19	Road Closure And Lane Closure On A Two Way Road Layouts					
			D-704-22	Construction Truck And Temporary Detour Layouts					
			D-704-50	Portable Sign Support Assembly					
			D-704-56	Mobile Operation - Grinding Shoulder Rumble Strips					
			D-706-1	Bituminous Laboratory					
			D-760-3	Rumble Strips Undivided Highways (Shoulders 4' Or Greater)					
			D-760-5	Saw Slotted Rumble Strips At Intersections					
			D-762-4	Pavement Marking					
			D-762-5	Pavement Marking for Standard 90 Degree Flared Intersection-(No Center Left Turn Lane on Major Road)					
			D-762-11	Short-Term Pavement Marking					

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	NH-3-001(027)161	4	1



3" HMA Overlay



0"-1.5" Milling Transition

This document was originally issued and sealed by
Korby Seward
Registration Number
PE- 10774,
on 08/29/17 and the original document is stored at the
North Dakota Department
of Transportation

Scope of Work

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	NH-3-001(027)161	6	1

NOTES

- 107-P01 HAUL ROAD RESTORATION: Use Class 13 aggregate for haul road restoration.
- 107-P02 HEIGHT RESTRICTION FOR CONSTRUCTION EQUIPMENT: Between RP 161.794 and RP 162.736, equipment is restricted to a height of 20 feet or less due to Lakota Airport restrictions. Equipment height will be measured from the centerline of the roadway and will include the extended box height of end dumps.
- 401-P01 FOG COAT: Fog seal after final rolling with a minimum mat temperature of 125 degrees F. Blotter sand shall be applied with equipment as specified in section 154.02 of the Standard Specifications or as approved by the engineer. All costs for providing and placing the blotter sand shall be included in the price bid for "Fog Coat".
- 430-P01 CONTRACTOR CORING: Before placing bituminous material into core holes, apply a tack coat on all sides of the core holes as Specified in Section 401.
- 704-P01 TRAFFIC CONTROL FOR BITUMINOUS PAVEMENT: Provide traffic control consisting of a temporary lane closure, flagging, and a pilot car.
- Traffic control device quantities are based on the 1 mile length of project and the list below.
1. Standard D-704-15
 2. Standard D-704-19, Layout F
 3. Standard D-704-22, Layout K and L
- 762-P01 SHORT TERM 4IN LINE-TYPE NR: Quantity for three applications of short term centerline pavement marking has been included in the plans. Additional applications required to accommodate the contractor's operation shall be at the contractor's expense.
- One application for Superpave FAA 45
 - One application for fog coat
 - One application for rumble strips

This document was originally issued and sealed by Korby Seward , Registration Number PE-10774, on 08/29/17 and the original document is stored at the North Dakota Department of Transportation.

ESTIMATE OF QUANTITIES

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	NH-3-001(027)161	8	1

SPEC CODE	ITEM DESCRIPTION	UNIT	MAINLINE	TOTAL
-----	-----	----	-----	-----
103	0100 CONTRACT BOND	L SUM	0.065	0.065
230	0125 SHOULDER PREPARATION	MILE	1.88	1.88
302	0120 AGGREGATE BASE COURSE CL 5	TON	50	50
401	0050 TACK COAT	GAL	1,769	1,769
401	0070 FOG SEAL	GAL	663	663
411	0105 MILLING PAVEMENT SURFACE	SY	258	258
430	0045 SUPERPAVE FAA 45	TON	3,631	3,631
430	1000 CORED SAMPLE	EA	21	21
430	5828 PG 58-28 ASPHALT CEMENT	TON	218	218
702	0100 MOBILIZATION	L SUM	0.065	0.065
704	0100 FLAGGING	MHR	200	200
704	1000 TRAFFIC CONTROL SIGNS	UNIT	1,204	1,204
704	1067 TUBULAR MARKERS	EA	60	60
704	1185 PILOT CAR	HR	100	100
706	0550 BITUMINOUS LABORATORY	EA	1	1
706	0600 CONTRACTOR'S LABORATORY	EA	1	1
760	0005 RUMBLE STRIPS - ASPHALT SHOULDER	MILE	1.88	1.88
760	0007 RUMBLE STRIPS - ASPHALT CENTERLINE	MILE	0.94	0.94
760	0010 RUMBLE STRIPS - INTERSECTION	SET	1	1
762	0430 SHORT TERM 4IN LINE-TYPE NR	LF	7,119	7,119
762	1104 PVMT MK PAINTED 4IN LINE	LF	12,321	12,321

NH-3-001(027)161							
			Sta 8581+17 to Sta 8592+96				
			Sta 8543+22 to Sta 8560+29		Sta 8560+29 to Sta 8581+17		
Materials	Basis	UNIT	Width (ft)	Quantity/Mile	Width (ft)	Quantity/Mile	Totals
SUPERPAVE FAA 45	2 Ton/CY	Ton	32.00	4,012.8	32.00	3,520.0	3,585 Tons
PG 58-28 ASPHALT CEMENT	6.0 % of HBP	Ton	---		--		215 Tons
TACK COAT	0.05 Gal/SY	Gal	32.00	938.7	32.00	938.7	1,769 Gals
FOG COAT	0.05 Gal/SY	Gal	24.00	704.0	24.00	704.0	663 Gals

NH-3-001(027)161

Short Term Pavement Marking	
Mainline	Amount
Short Term 4in Line - Type NR	7,119.00 LF
Broken Line=1083 LF NPZ=645 LF	
Note: 1 Lift HMA, 2 Lift HMA, Fog Coat, and Rumble Strips	7,119.00 LF

Permanent Pavement Marking	
Mainline	Amount
Centerline - 4" Yellow 10' Line, 30' skip	1,083.00 LF
Centerline - 4" Yellow, Barrier Line	1,290.00 LF
Edge Lines - 4" White	9,948.00 LF
Total	12,321.00 LF

Rumble Strips				
NH-3-001(027)161				
Item	Begin Station	End Station	Road Miles	Total Miles
RUMBLE STRIPS - ASPHALT SHOULDER	8543+22	8592+96	0.94 Miles	1.88 Miles
RUMBLE STRIPS - ASPHALT CENTERLINE	8543+22	8592+96	0.94 Miles	0.94 Miles


NH-3-001(027)161					
Milling Pavement Surface 1.5" to 0"					
Location	Begin Sta	End Sta	Length (ft)	Width (ft)	Qty
Start of Project	8543+22	8543+97	75	31	258 SY
				Total	258 SY

	A	B	C	D			
Specification Section	Lanes	Lifts	Distance (Feet)	Sublots	Quantity	Quantity	Unit
				(A × B × C)÷2000	(D × 2)	(1 per mile)	
430.04 I.2.b(1), "General"	2	2	4974	10	20	N/A	EA
430.04 I.2.b(2),					N/A	1	EA
"Pavement Thickness Determination Cores"							
				Total	20	1	EA


This document was originally issued and sealed by
Korby Seward
Registration Number
PE-10774
on 08/29/17 and the original document is stored at the
North Dakota Department
of Transportation

BASIS OF ESTIMATE

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	NH-3-001(027)161	20	1



Milling Transition Detail




Paving Transition Detail



This document was originally issued and sealed by
Korby Seward
Registration Number
PE-10774
on 08/29/17 and the original document is stored at the
North Dakota Department
of Transportation

Milling Pavement Surface Detail

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	NH-3-001(027)161	20	2






(3) Paved Private Drive Approach



(4) Gravel Private or Field Drive Approach

Notes:

1. Actual HMA paving and aggregate base course locations may vary in the field, as approved by the Engineer.
2. Quantity totals have been included in the bid items of the "Estimate of Quantities" of the plans.
3. Aggregate base course has been provided in the quantities to fill in around the radii. This material will be required when sloughs are steeper than 4:1 (see section C-C)



NH-3-001(027)161						
Approach Paving Details						
Item	Unit	Paved Section Line, Road, or Street Approach	Gravel Section Line, Road, or Street Approach	Paved Private Drive	Gravel Private Drive or Field Drive	Total
Number of Locations	EA	0	0	0	3	3
TACK COAT	GAL	0	0	0	14	14
MILLING PAVEMENT SURFACE	TON	0	0	0	0	0
SUPERPAVE FAA 43	TON	0	0	0	46	46
PG 58-28 ASPHALT CEMENT	TON	0	0	0	3	3
AGGREGATE CLASS - 5	TON	---	0	---	5	15

35 tons of class 5 was added to be placed at engineers discretion


This document was originally issued and sealed by
Korby Seward
Registration Number
PE-10774
on 08/29/17 and the original document is stored at the
North Dakota Department
of Transportation

APPROACH PAVING DETAILS


ND 1

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	NH-3-001(027)161	30	1

*Existing cross slope of roadway may vary than listed in the existing typical



Existing Typical Section
STA 8543+21.50 TO STA 8560+29
STA 8581+17 TO STA 8592+96.27




Existing Typical Section
STA 8560+29 TO STA 8581+17

This document was originally issued and sealed by
Korby Seward
Registration Number
PE-10774
on 08/29/17 and the original document is stored at the
North Dakota Department
of Transportation


Existing Typicals

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	NH-3-001(027)161	30	2

*Match existitng cross slope of roadway



Proposed Typical Section
STA 8543+21.50 TO STA 8560+29
STA 8581+17 TO STA 8592+96.27





Proposed Typical Section
STA 8560+29 TO STA 8581+17

This document was originally
issued and sealed by
Korby Seward
Registration Number
PE-10774
on 08/29/17 and the original
document is stored at the
North Dakota Department
of Transportation

Proposed Typical Section

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	NH-3-001(027)161	100	2



This document was originally issued and sealed by
Korby Seward
Registration Number
PE-10774
on 08/29/17 and the original document is stored at the
North Dakota Department
of Transportation

Work Zone Traffic Control

?	This is a special text character used in the labeling of existing features. It indicates a feature that has an unknown characteristic, potentially based on: lack of description, location accuracy or purpose.		
Abn	abandoned	BV	butterfly valve
Abut	abutment	Byp	bypass
Ac	acres	C Gdrl	cable guardrail
Adj	adjusted	Calc	calculate
Aggr	aggregate	Cd	candela
Ahd	ahead	CIP	cast iron pipe
ARV	air release valve	CB	catch basin
Align	alignment	CRS	cationic rapid setting
Al	alley	C Gd	cattle guard
Alt	alternate	C To C	center to center
Alum	aluminum	Cl or C	centerline
ADA	Americans with Disabilities Act	Cm	centimeter
A	ampere	Ch	chain
&	and	Chnlk	chain-link
Appr	approach	Ch Blk	channel block
Approx	approximate	Ch Ch	channel change
ACP	asbestos cement pipe	Chk	check
Asph	asphalt	Chsld	chiseled
AC	asphalt cement	Cir	circle
Assmd	assumed	Cl	class
@	at	Cl	clay
Atten	attenuation	Cl F	clay fill
ATR	automatic traffic recorder	Cl Hvy	clay heavy
Ave	Avenue	Cl Lm	clay loam
Avg	average	Clnt	clean-out
ADT	average daily traffic	Clr	clear
Az	azimuth	Cl&gr	clearing & grubbing
Bk	back	Co S	coal slack
BF	back face	Comb.	combination
Bs	backsight	Coml	commercial
Balc	balcony	Compr	compression
B Wire	barbed wire	CADD	computer aided drafting & design
Barr	barricade	Conc	concrete
Btry	battery	Cond	conductor
Brg	bearing	Const	construction
BI	beehive inlet	Cont	continuous
Beg	begin	CSB	continuous split barrel sample
BM	bench mark	Contr	contraction
Bkwy	bikeway	Contr	contractor
Bit	bituminous	CP	control point
Blk	block	Coord	coordinate
Bd Ft	board feet	Cor	corner
BH	bore hole	Corr	corrected
BS	both sides	CAES	corrugated aluminum end section
Bot	bottom	CAP	corrugated aluminum pipe
Blvd	Boulevard	CMES	corrugated metal end section
Bndry	boundary	CMP	corrugated metal pipe
BC	brass cap	CPVCP	corrugated poly-vinyl chloride pipe
Brkwy	breakaway	CSES	corrugated steel end section
Br	bridge	CSP	corrugated steel pipe
Bldg	building	CSP	corrugated steel pipe
		C	coulomb
		Co	County
		Crse	course
		C Gr	course gravel
		CS	course sand
		Ct	Court
		Xarm	cross arm
		Xbuck	cross buck
		Xsec	cross sections
		Xing	crossing
		Xrd	Crossroad
		Crn	crown
		CF	cubic feet
		M3	cubic meter
		M3/s	cubic meters per second
		CY	cubic yard
		Cy/mi	cubic yards per mile
		Culv	culvert
		C&G	curb & gutter
		CI	curb inlet
		CR	curb ramp
		CS	curve to spiral
		C	cut
		Dd Ld	dead load
		Defl	deflection
		Defm	deformed
		Deg or D	degree
		DInt	delineate
		DIntr	delineator
		Depr	depression
		Desc	description
		Det	detail
		DWP	detectable warning panel
		Dtr	detour
		Dia	diameter
		Dir	direction
		Dist	distance
		DM	disturbed material
		DB	ditch block
		DG	ditch grade
		Dbl	double
		Dn	down
		Dwg	drawing
		Dr	drive
		Drwy	driveway
		DI	drop inlet
		D	dry density
		Ea	each
		Esmt	easement
		E	East
		EB	Eastbound
		Elast	elastomeric
		EL	electric locker
		E Mtr	electric meter
		Elec	electric/al
		EDM	electronic distance meter
		Elev or El	elevation
		Ellipt	elliptical
		Emb	embankment
		Emuls	emulsion/emulsified
		ES	end section
		Engr	engineer
		ESS	environmental sensor station
		Eq	equal
		Eq	equation
		Evgr	evergreen
		Exc	excavation
		Exst	existing
		Exp	expansion
		Expy	Expressway
		E	external of curve
		Extru	extruded
		FOS	factor of safety
		F	Fahrenheit
		FS	far side
		F	farad
		Fed	Federal
		FP	feed point
		Ft	feet/foot
		Fn	fence
		Fn P	fence post
		FO	fiber optic
		FB	field book
		FD	field drive
		F	fill
		FAA	fine aggregate angularity
		FS	fine sand
		FH	fire hydrant
		FI	flange
		Flrd	flared
		FES	flared end section
		F Bcn	flashing beacon
		FA	flight auger sample
		FL	flow line
		Ftg	footing
		FM	force main
		Fs	foresight
		Fnd	found
		Fdn	foundation
		Frac	fractional
		Frwy	freeway
		Frt	front
		FF	front face
		F Disp	fuel dispenser

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930 , on 07/01/14 and the original document is stored at the North Dakota Department of Transportation

NDDOT ABBREVIATIONS

D-101-2

FFP	fuel filler pipes	IPn	Iron Pin	MC	medium curing	Ped	pedestal
FLS	fuel leak sensor	IP	Iron Pipe	M	mega	Ped	pedestrian
Furn	furnish/ed	Jt	joint	Mer	meridian	PPP	pedestrian pushbutton post
Gal	gallon	J	joule	M	meter	Pen.	penetration
Galv	galvanized	Jct	junction	M/s	meters per second	Perf	perforated
Gar	garage	K	kelvin	M	mid ordinate of curve	Per.	perimeter
Gs L	gas line	Kn	kilo newton	Mi	mile	PL	pipeline
G Reg	gas line regulator	Kpa	kilo pascal	MM	mile marker	PI	place
GMV	gas main valve	Kg	kilogram	MP	mile post	P&P	plan & profile
G Mtr	gas meter	Kg/m3	kilogram per cubic meter	MI	milliliter	PL	plastic limit
GSV	gas service valve	Km	kilometer	Mm	millimeter	PI	plate
GVP	gas vent pipe	K	Kip(s)	Mm/hr	millimeters per hour	Pt	point
GV	gate valve	LS	Land Surveyor (licensed)	Min	minimum	PCC	point of compound curve
Ga	gauge	LSIT	Land Surveyor In Training	Misc	miscellaneous	PC	point of curve
Geod	geodetic	Ln	lane	Mon	monument	PI	point of intersection
GIS	Geographical Information System	Lg	large	Mnd	mound	PRC	point of reverse curvature
G	giga	Lat	latitude	Mtbl	mountable	PT	point of tangent
GPS	Global Positioning System	Lt	left	Mtd	mounted	POC	point on curve
Gov	government	L	length of curve	Mtg	mounting	POT	point on tangent
Grd	graded/grade	Lens	lenses	Mk	muck	PE	polyethylene
Gr	gravel	Lvl	level	Mun	municipal	PVC	polyvinyl chloride
Grnd	ground	LB	level book	N	nano	PCC	Portland Cement concrete
GWM	ground water monitor	Lvlng	leveling	NGS	National Geodetic Survey	Lb or #	pounds
Gdrl	guardrail	Lht	light	NS	near side	PP	power pole
Gtr	gutter	LP	light pole	Neop	neoprene	Preempt	preemption
H Plg	H piling	Ltg	lighting	Ntwk	network	Prefab	prefabricated
Hdwl	headwall	Lig Co	lignite coal	N	newton	Prfmd	preformed
Ha	hectare	Lig Sl	lignite slack	N	North	Prep	preperation
Ht	height	LF	linear foot	NE	North East	Press.	pressure
HI	height of instrument	Liq	liquid	NW	North West	PRV	pressure relief valve
Hel	helical	LL	liquid limit	NB	Northbound	Prestr	prestressed
H	henry	L	litre	No. or #	number	Pvt	private
Hz	hertz	Lm	loam	Obsc	obscure(d)	PD	private drive
HDPE	high density polyethylene	Loc	location	Obsn	observation	Prod.	production/produce
HM	high mast	LC	long chord	Ocpd	occupied	Prog	programmed
HP	high pressure	Long.	longitude	Ocpy	occupy	Prop.	property
HPS	high pressure sodium	Lp	loop	Off Loc	office location	Prop Ln	property line
Hwy	highway	LD	loop detector	O/s	offset	Ppsd	proposed
Hor	horizontal	Lm	lumen	OC	on center	PB	pull box
HBP	hot bituminous pavement	Lum	luminaire	C	one dimensional consolidation		
HMA	hot mix asphalt	L Sum	lump sum	OC	organic content		
Hr	hour(s)	Lx	lux	Orig	original		
Hyd	hydrant	ML	main line	O To O	out to out		
Ph	hydrogen ion content	M Hr	man hour	OD	outside diameter		
Id	identification	MH	manhole	OH	overhead		
In or "	inch	Mkd	marked	PMT	pad mounted transformer		
Incl	inclinometer tube	Mkr	marker	Pg	pages		
IMH	inlet manhole	Mkg	marking	Pntd	painted		
ID	inside diameter	MA	mast arm	Pr	pair		
Inst	instrument	Matl	material	Pnl	panel		
Intchg	interchange	Max	maximum	Pk	park		
Intmdt	intermediate	MC	meander corner	PK	Parker-Kalon nail		
Intscn	intersection	Meas	measure	Pa	pascal		
Inv	invert	Mdn	median	PSD	passing sight distance		
IM	iron monument	MD	median drain	Pvmt	pavement		

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
08-03-15	General Revisions

This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930 , on 08/03/15 and the original document is stored at the North Dakota Department of Transportation

NDDOT ABBREVIATIONS

D-101-3

Qty	quantity	SN	sign number	Tan	tangent	Wb	weber
Qtr	quarter	Sig	signal	T	tangent (semi)	WIM	weigh in motion
Rad or R	radius	Si Cl	silt clay	TS	tangent to spiral	W	west
RR	railroad	Si Cl Lm	silty clay loam	Tel	telephone	WB	westbound
Rlwy	railway	Si Lm	silty loam	Tel B	Telephone Booth	Wrng	wiring
Rsd	raised	Sgl	single	Tel P	telephone pole	W/	with
RTP	random traverse point	SC	slow curing	Tv	television	W/o	without
Rge or R	range	SS	slow setting	Temp	temperature	WC	witness corner
RC	rapid curing	Sm	small	Temp	temporary	WGS	world geodetic system
Rec	record	S	South	TBM	temporary bench mark	Z	zenith
Rcy	recycle	SE	South East	T	tesla		
RAP	recycled asphalt pavement	SW	South West	T	thinwall tube sample		
RPCC	recycled portland cement concrete	SB	Southbound	T/mi	tons per mile		
Ref	reference	Sp	spaces	Ts	topsoil		
R Mkr	reference marker	Spcl	special	Twp or T	township		
RM	reference monument	SA	special assembly	Traf	traffic		
Refl	reflectorized	SP	special provisions	TSCB	traffic signal control box		
RCB	reinforced concrete box	G	specific gravity	Tr	trail		
RCES	reinforced concrete end section	Spk	spike	Transf	transformer		
RCP	reinforced concrete pipe	SC	spiral to curve	TB	transit book		
RCPS	reinforced concrete pipe sewer	ST	spiral to tangent	Trans	transition		
Reinf	reinforcement	SB	split barrel sample	TT	transmission tower		
Res	reservation	SH	sprinkler head	Trans	transverse		
Ret	retaining	SV	sprinkler valve	Trav	traverse		
Rev	reverse	Sq	square	TP	traverse point		
Rt	right	SF	square feet	Trtd	treated		
R/W	right of way	Km2	square kilometer	Trmt	treatment		
Riv	river	M2	square meter	Qc	triaxial compression		
Rd	road	SY	square yard	TERO	tribal employment rights ordinance		
Rdbd	road bed	Stk	stake	Tpl	triple		
Rdwy	roadway	Std	standard	TP	turning point		
RWIS	roadway weather information system	N	standard penetration test	Typ	typical		
Rk	rock	Std Specs	standard specifications	Qu	unconfined compressive strength		
Rt	route	Sta	station	Ugrnd	underground		
Salv	salvage(d)	Sta Yd	station yards	USC&G	US Coast & Geodetic Survey		
Sd	sand	Stm L	steam line	USGS	US Geologic Survey		
Sdy Cl	sandy clay	SEC	steel encased concrete	Util	utility		
Sdy Cl Lm	sandy clay loam	SMA	stone matrix asphalt	VG	valley gutter		
Sdy Fl	sandy fill	SSD	stopping sight distance	Vap	vapor		
Sdy Lm	sandy loam	SD	storm drain	Vert	vertical		
San	sanitary sewer line	St	street	VC	vertical curve		
Sc	scoria	SPP	structural plate pipe	VCP	vitrified clay pipe		
Sec	seconds	SPPA	structural plate pipe arch	V	volt		
Sec	section	Str	structure	Vol	volume		
SL	section line	Subd	subdivision	Wkwy	walkway		
Sep	separation	Sub	subgrade	W	water content		
Seq	sequence	Sub Prep	subgrade preperation	WGV	water gate valve		
Serv	service	Ss	subsoil	WL	water line		
Sh	shale	SE	superelevation	WM	water main		
Sht	sheet	SS	supplement specification	WMV	water main valve		
Shtng	sheeting	Supp	supplemental	W Mtr	water meter		
Shldr	shoulder	Surf	surfacing	WSV	water service valve		
Sw	sidewalk	Surv	survey	WW	water well		
S	siemens	Sym	symmetrical	W	watt		
SD	sight distance	SI	systems international	Wrng	wearing		

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
08-03-15	General Revisions

This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930 , on 08/03/15 and the original document is stored at the North Dakota Department of Transportation

NDDOT UTILITY COMPANY AND ORGANIZATION ABBREVIATIONS

702COM 702 Communications
ACCENT Accent Communications
AGASSIZ WU Agassiz Water Users Incorporated
AGC Associated General Contractors of America
All PI Alliance Pipeline
ALL SEAS WU All Seasons Water Users Association
AMOCO PI Amoco Pipeline Company
AMRDA HESS Amerada Hess Corporation
AT&T AT&T Corporation
B PAW Bear Paw Energy Incorporated
BAKER ELEC Baker Electric
BASIN ELEC Basin Electric Cooperative Incorporated
BEK TEL Bek Communications Cooperative
BELLE PL Belle Fourche Pipeline Company
BLM Bureau of Land Management
BNSF Burlington Northern Santa Fe Railway
BOEING Boeing
BRNS RWD Barnes Rural Water District
BURK-DIV ELEC Burke-Divide Electric Cooperative
BURL WU Burleigh Water Users
Cable One Cable One
CABLE SERV Cable Services
CAP ELEC Capital Electric Cooperative Incorporat
CASS CO ELEC Cass County Electric Cooperative
CASS RWU Cass Rural Water Users Incorporated
CAV ELEC Cavalier Rural Electric Cooperative
CBLCOM Cablecom Of Fargo
CENEX PL Cenex Pipeline
CENT PL WATER DIST Central Pipe Line Water District
CENT PWR ELEC Central Power Electric Cooperative
COE Corps of Engineers
CONS TEL Consolidated Telephone
CONT RES Continental Resource Inc
CPR Canadian Pacific Railway
D O E Department Of Energy
DAK CARR Dakota Carrier Network
DAK CENT TEL Dakota Central Telephone
DAK RWD Dakota Rural Water District
DGC Dakota Gasification Company
DICKY R NET Dickey Rural Networks
DICKY RWU Dickey Rural Water Users Association
DICKY TEL Dickey Telephone
DNRR Dakota Northern Railroad
DOME PL Dome Pipeline Company
DVELEC Dakota Valley Electric Cooperative
DVMW Dakota, Missouri Valley & Western
ENBRDG Enbridge Pipelines Incorporated
ENVENTIS Enventis Telephone
FALK MNG Falkirk Mining Company
FHWA Federal Highway Administration
G FKS-TRL WD Grand Forks-trail Water District
GETTY TRD & TRAN Getty Trading & Transportation
GLDN W ELEC Golden West Electric Cooperative
GRGS CO TEL Griggs County Telephone
























GT PLNS NAT GAS Great Plains Natural Gas Company
HALS TEL Halstad Telephone Company
IDEA1 Idea1
INT-COMM TEL Inter-Community Telephone Company
KANEB PL Kaneb Pipeline Company
KEM ELEC Kem Electric Cooperative Incorporated
KOCH GATH SYS Koch Gathering Systems Incorporated
LKHD PL Lakehead Pipeline Company
LNGDN RWU Langdon Rural Water Users Incorporated
LWR YELL R ELEC Lower Yellowstone Rural Electric
MCKNZ CON McKenzie Consolidated Telcom
MCKNZ ELEC McKenzie Electric Cooperative
MCKNZ WRD McKenzie County Water Resource District
MCLEOD McLeod USA
MCLN ELEC McLean Electric Cooperative
MCLN-SHRDN R WAT McLean-Sheridan Rural Water
MDU Montana-dakota Utilities
MID-CONT CABLE Mid-Continent Cable
MIDSTATE TEL Midstate Telephone Company
MINOT CABLE Minot Cable Television
MINOT TEL Minot Telephone Company
MISS W W S Missouri West Water System
MNKOTA PWR Minnkota Power
MOR-GRAN-SOU ELEC Mor-gran-sou Electric Cooperative
MOUNT-WILLI ELEC Mountrail-williams Electric Cooperative
MRE LBTY TEL Moore & Liberty Telephone
MUNICIPAL City Water And Sewer
MUNICIPAL City Of '.....'
N CENT ELEC North Central Electric Cooperative
N VALL W DIST North Valley Water District
ND PKS & REC North Dakota Parks And Recreation
ND TEL North Dakota Telephone Company
NDDOT North Dakota Department of Transportation
NDSU SOIL SCI DEPT NDSU Soil Science Department
NEMONT TEL Nemont Telephone
NODAK R ELEC Nodak Rural Electric Cooperative
NOON FRMS TEL Noonan Farmers Telephone Company
NPR Northern Plains Railroad
NSP Northern States Power
NTH PRAIR RW Northern Prairie Rural Water Association
NTHN BRDR PL Northern Border Pipeline
NTHN PLNS ELEC Northern Plains Electric Cooperative Incorporated
NTHWSTRN REF Northwestern Refinery Company
NW COMM Northwest Communication Cooperation
ONEOK Oneok gas
OSHA Occupational Safety and Health Administration
OTTR TL PWR Otter Tail Power Company
P L E M Prairielands Energy Marketing
POLAR COM Polar Communications
PVT ELEC Private Electric
QWEST Qwest Communications
R&T W SUPPLY R & T Water Supply Association
RAMSEY R SEW Ramsey Rural Sewer Association
RAMSEY RW Ramsey Rural Water Association
RAMSEY UTIL Ramsey County Rural Utilities













RED RIV TEL Red River Rural Telephone
RESVTN TEL Reservation Telephone
ROBRTS TEL Roberts Company Telephone
R-RIDER ELEC Roughrider Electric Coop
RRVW Red River Valley & Western Railroad
RSR ELEC R.S.R. Electric Cooperative
S E W U South East Water Users Incorporated
SCOTT CABLE Scott Cable Television Dickinson
SHERDN ELEC Sheridan Electric Cooperative
SHEYN VLY ELEC Sheyenne Valley Electric Cooperative
SKYTECH Skyland Technologies Incorporated
SLOPE ELEC Slope Electric Cooperative Incorporated
SOURIS RIV TELCOM Souris River Telecommunications
ST WAT COMM State Water Commission
STATE LN WATER State Line Water Cooperative
STER ENG Sterling Energy
STUT RWU Stutsman Rural Water Users
SW PL PRJ Southwest Pipeline Project
T M C Turtle Mountain Communications
TCI TCI of North Dakota
TESORO HGH PLNS PL Tesoro High Plains Pipeline
TRI-CNTY WU Tri-County Water Users Incorporated
TRL CO RWU Traill County Rural Water Users
UNTD TEL United Telephone
UPPR SOUR WUA Upper Souris Water Users Association
US SPRINT U.S. Sprint
USAF MSL CABLE U.S.A.F. Missile Cable
USFWS US Fish and Wildlife Service
USW COMM U.S. West Communications
VRNDRY ELEC Verendrye Electric Cooperative
W RIV TEL West River Telephone Incorporated
WEB W. E. B. Water Development Association
WILLI RWA Williams Rural Water Association
WILSTN BAS PL Williston Basin Interstate Pipeline Company
WLSH RWD Walsh Water Rural Water District
WOLVRTN TEL Wolverton Telephone
XLENER Xcel Energy
YSVR Yellowstone Valley Railroad

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE








This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930 , on 07/01/14 and the original document is stored at the North Dakota Department of Transportation

Existing Topography























	Existing Ground Void
	Existing Cemetary Boundary
	Existing Box Culvert Bridge
	Existing Concrete Surface
	Existing Drainage Structure
	Existing Gravel Surface
	Existing Riprap
	Existing Dirt Surface
	Existing Asphalt Surface
	Existing Tie Point Line
	Existing Railroad Centerline
	Existing Guardrail Cable
	Existing Guardrail Metal
	Existing Edge of Water
	Existing Fence
	Existing Railroad
	Existing Field Line
	Exst Flow
	Existing Curb
	Existing Valley Gutter
	Existing Driveway Gutter
	Existing Curb and Gutter
	Existing Mountable Curb and Gutter

	Existing 3-Cable w Posts
	Site Boundary
	Existing Berm, Dike, Pit, or Earth Dam
	Existing Ditch Block
	Existing Tree Boundary
	Existing Brush or Shrub Boundary
	Existing Retaining Wall
	Existing Planter or Wall
	Existing W-Beam Guardrail with Posts
	Existing Railroad Switch
	Gravel Pit - Borrow Area
	Existing Wet Area-Vegetation Break





Proposed Topography

	3-Cable w Posts
	Flow
	Fence
	Remove Line
	Wall
	Retaining Wall (Plan View)
	W-Beam w Posts










Existing Utilities

	Existing Electrical
	Existing Fiber Optic Line
	Existing TV Fiber Optic
	Existing Gas Pipe
	Existing Overhead Utility Line
	Existing Power
	Existing Fuel Pipeline
	Existing Undefined Above Ground Pipe Line
	Existing Sanitary Sewer
	Existing Sanitary Force Main
	Existing Storm Drain
	Existing Storm Drain Force Main
	Existing Culvert
	Existing Telephone Line
	Existing TV Line
	Existing Water or Steam Line
	Existing Under Drain
	Existing Slotted Drain
	Existing Conduit
	Existing Conductor
	Existing Down Guy Wire Down Guy
	Existing Underground Vault or Lift Station




Proposed Utilities

	24 Inch Pipe
	Reinforced Concrete Pipe
	Under Drain
	Edge Drain

Traffic Utilities

	Conductor
	Fiber Optic
	Existing Loop Detector
	Existing Double Micro Loop Detector
	Micro Loop Detector Double
	Existing Micro Loop Detector
	Micro Loop Detector
	Signal Head with Mast Arm
	Existing Signal Head with Mast Arm

Sign Structures














	Existing Overhead Sign Structure
	Existing Overhead Sign Structure Cantilever
	Overhead Sign Structure Cantilever

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
09-23-16	Added and Revised Items, Organized by Functional Groups










This document was originally issued and sealed by
Roger Weigel,
Registration Number
PE-2930,
on 09/23/16 and the original document is stored at the
North Dakota Department
of Transportation

Line Styles









Right Of Way

	Easement
	Existing Easement
	Right of Way
	Existing Right of Way
	Existing Right of Way Railroad
	Existing Right of Way Not State Owned
	Existing Government Lot Line
	Existing Adjacent Block Lines
	Existing Adjacent Lot Lines
	Existing Adjacent Property Line
	Existing Adjacent Subdivision Lines
	Sight Distance Triangle Line
	Dimension Leader







Boundary Control



	Existing City Corporate Limits or Reservation Boundary
	Existing State or International Line
	Existing Township
	Existing County
	Existing Section Line
	Existing Quarter Section Line
	Existing Sixteenth Section Line
	Existing Centerline
	Tangent Line

Cross Sections and Typicals



	Existing Ground
	Existing Topsoil (Cross Section View)
	Existing Ground Void (Not Surveyed)
	Existing Concrete
	Existing Aggregate (Cross Section View)
	Existing Curb and Gutter (Cross Section View)
	Existing Asphalt (Cross Section View)
	Existing Reinforcement Rebar

Geotechnical



	Geotextile Fabric Type D
	Geogrid
	Geotextile Fabric Type R
	Geotextile Fabric Type R1
	Geotextile Fabric Type RR
	Geotextile Fabric Type S

	Subgrade Reinforcement
	Failure Line







Countours

	Depression Contours
	Supplemental Contour





Profile

	Subgrade, Subcut or Ditch Grade
	Topsoil Profile










Striping

	Centerline Pavement Marking
	Barrier with Centerline Pavement Marking
	Barrier Pavement Marking
	Stripe 4 IN Dotted Extension White
	Stripe 8 IN Dotted Extension White
	Stripe 8 IN Lane Drop








Pavement Joints

	Doweled Joint
	Tie Bar 30 Inch 4 Foot Center to Center
	Tie Bar 18 Inch 3 Foot Center to Center
	Tie Bar at Random Spacing






Bridge Details

	Hidden Object
	Small Hidden Object
	Large Hidden Object
	Phantom Object
	Centerline Main
	Centerline
	Existing Ground (Details)
	Existing Conditions
	Sheet Piling

Erosion Control

	Limits of Const Transition Line
	Bale Check
	Rock Check
	Floating Silt Curtain
	Silt Fence
	Excavation Limits
	Fiber Rolls

Environmental

	Wetland Mitigation
	Existing Wetland Easement USFWS
	Existing Wetland Jurisdictional
	Existing Wetland
	Tree Row

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
09-23-16	Added and Revised Items, Organized by Functional Groups





















































































This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930 , on 09/23/16 and the original document is stored at the North Dakota Department of Transportation

Symbols

	North Arrow (Half Scale)		Attenuation Device		Existing Railroad Battery Box		Existing Delineator Type E										
	Truck Mounted Attenuator		Diamond Grade Delineator Type A		Existing Bush or Shrub		Existing EFB Misc										
	Type I Barricade		Diamond Grade Delineator Type B		Existing Gas Cap or Stub		Existing Flashing Beacon										
	Type II Barricade		Diamond Grade Delineator Type C		Existing Sanitary Cap or Stub		Existing Pipe Mounted Flasher										
	Type III Barricade		Diamond Grade Delineator Type D		Existing Storm Drain Cap or Stub		Existing Pad Mounted Feed Point										
	Catch Basin		Diamond Grade Delineator Type E		Existing Water Cap or Stub		Existing Pipe Mounted Feed Point with Pad										
	Cairn or Stone Circle		Flexible Delineator		Existing Sanitary Cleanout		Existing Pole Mounted Feed Point										
	Video Detection Camera		Flexible Delineator Type A		Existing Concrete Foundation		Existing Railroad Frog										
	Storm Drain Cap or Stub		Flexible Delineator Type B		Existing Traffic Signal Controller		Existing Snow Gate 18										
	Corrugated Metal End Section 18 Inch		Flexible Delineator Type C		Existing Pad Mounted Signal Controller		Existing Snow Gate 28										
	Corrugated Metal End Section 24 Inch		Flexible Delineator Type D		Existing Sixteenth Section Corner		Existing Snow Gate 40										
	Corrugated Metal End Section 30 Inch		Flexible Delineator Type E		Existing Quarter Section Corner		Existing Headwall										
	Corrugated Metal End Section 36 Inch		Delineator Type A		Existing Section Corner		Existing Pedestrian Head with Number										
	Corrugated Metal End Section 42 Inch		Delineator Type A Reset		Existing Railroad Crossbuck		Existing Signal Head										
	Corrugated Metal End Section 48 Inch		Delineator Type B		Existing Satellite Dish		Existing Sprinkler Head										
	Concrete Foundation		Delineator Type B Reset		Existing Fuel Dispensers		Existing Fire Hydrant										
	Ground Connection Conductor		Delineator Type C		Existing Flexible Delineator Type A		Existing Catch Basin Drop Inlet										
	Neutral Connection Conductor		Delineator Type D		Existing Flexible Delineator Type B		Existing Curb Inlet										
	Phase 1 Connection Conductor		Delineator Type E		Existing Flexible Delineator Type C		Existing Manhole Inlet										
	Phase 2 Connection Conductor		Delineator Drums		Existing Flexible Delineator Type D		Existing Junction Box										
	Traffic Cone		Spot Elevation		Existing Flexible Delineator Type E	<table><tr><th colspan="2">NORTH DAKOTA DEPARTMENT OF TRANSPORTATION</th></tr><tr><th colspan="2">07-01-14</th></tr><tr><th colspan="2">REVISIONS</th></tr><tr><th>DATE</th><th>CHANGE</th></tr><tr><td></td><td></td></tr></table>		NORTH DAKOTA DEPARTMENT OF TRANSPORTATION		07-01-14		REVISIONS		DATE	CHANGE		
NORTH DAKOTA DEPARTMENT OF TRANSPORTATION																	
07-01-14																	
REVISIONS																	
DATE	CHANGE																
	Signal Controller		Existing Access Control Arrow		Existing Delineator Type A												
	Pad Mounted Signal Controller		Existing Artifact		Existing Delineator Type B												
	Alignment Data Point		Existing Flashing Beacon		Existing Delineator Type C												
	Emergency Vehicle Detector		Existing Benchmark		Existing Delineator Type D												

Symbols

D-101-31

	Existing Light Standard		Existing Manhole with Valve Water		Existing Telephone Pole		Existing Undefined Manhole
	Existing High Mast Light Standard 10 Luminaire		Existing Water Manhole		Existing Wood Pole		Existing Undefined Pull Box
	Existing High Mast Light Standard 3 Luminaire		Existing Mile Post Type A		Existing Post		Existing Undefined Pedestal
	Existing High Mast Light Standard 4 Luminaire		Existing Mile Post Type B		Existing Pedestrian Push Button Post		Existing Undefined Valve
	Existing High Mast Light Standard 5 Luminaire		Existing Mile Post Type C		Existing Control Point CP		Existing Undefined Pipe Vent
	Existing High Mast Light Standard 6 Luminaire		Existing Reference Marker		Existing Control Point GPS-RTK		Existing Gas Valve
	Existing High Mast Light Standard 7 Luminaire		Existing RW Marker		Existing Control Point TRI		Existing Water Valve
	Existing High Mast Light Standard 8 Luminaire		Existing Utility Marker		Existing Reference Marker Point NGS		Existing Fuel Pipe Vent
	Existing High Mast Light Standard 9 Luminaire		Iron Monument Found		Existing Pull Box		Existing Gas Pipe Vent
	Existing Overhead Sign Structure Load Center		Iron Pin R/W Monument		Existing Intelligent Transportation Pull Box		Existing Sanitary Pipe Vent
	Existing Luminaire		Existing Object Marker Type I		Existing Water Pump		Existing Storm Drain Pipe Vent
	Existing Light Standard Luminaire		Existing Object Marker Type II		Existing Slotted Reinforced Concrete Pipe		Existing Water Pipe Vent
	Existing Federal Mailbox		Existing Object Marker Type III		Existing RR Profile Spot		Existing Weather Station
	Existing Private Mailbox		Existing Electrical Pedestal		Existing Fuel Leak Sensors		Existing Ground Water Well Bore Hole
	Existing Meander Section Corner		Existing Telephone Pedestal		Existing Highway Sign		Existing Windmill or Tower
	Existing Meter		Existing Fiber Optic Telephone Pedestal		Existing Miscellaneous Spot		Existing Witness Corner
	Existing Electrical Manhole		Existing TV Pedestal		Existing Lighting Standard Pole		Flashing Beacon
	Existing Gas Manhole		Existing Fiber Optic TV Pedestal		Existing Traffic Signal Standard		Flagger
	Existing Sanitary Manhole		Existing Fuel Filler Pipes		Existing Transformer		Pipe Mounted Flasher
	Existing Sanitary Force Main Manhole		Existing Traverse PI Aerial Panel		Existing Large Evergreen Tree		Sanitary Force Main with Valve
	Existing Sanitary Manhole with Valve		Existing Pole		Existing Small Evergreen Tree		
	Existing Storm Drain Manhole		Existing Power Pole		Existing Large Tree		
	Existing Force Main Storm Drain Manhole		Existing Power Pole with Transformer		Existing Small Tree		
	Existing Force Main Storm Drain Manhole with Valve				Existing Tree Trunk		
	Existing Telephone Manhole				Existing Pad Mounted Traffic Signal Control Box		

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 07/01/14 and the original document is stored at the North Dakota Department of Transportation

Symbols



Pad Mounted Feed Point



Pipe Mounted Feed Point with Pad



Pole Mounted Feed Point



Headwall



Double Headwall with Vegetation Barrier



Single Headwall with Vegetation Barrier



Pole Mounted Head



Sprinkler Head



Fire Hydrant



Inlet Type 1



Inlet Type 2



Double Inlet Type 2



Inlet Grate Type 2



Junction Box



High Mast Light Standard 10 Luminaire



High Mast Light Standard 3 Luminaire



High Mast Light Standard 4 Luminaire



High Mast Light Standard 5 Luminaire



High Mast Light Standard 6 Luminaire



High Mast Light Standard 7 Luminaire



High Mast Light Standard 8 Luminaire



High Mast Light Standard 9 Luminaire



Relocate Light Standard



Overhead Sign Structure Load Center



Light Standard 100 Watt High Pressure Sodium Vapor Luminaire



Light Standard 1000 Watt High Pressure Sodium Vapor Luminaire



Light Standard 150 Watt High Pressure Sodium Vapor Luminaire



Light Standard 175 Watt High Pressure Sodium Vapor Luminaire



Light Standard 200 Watt High Pressure Sodium Vapor Luminaire



Light Standard 250 Watt High Pressure Sodium Vapor Luminaire



Light Standard 310 Watt High Pressure Sodium Vapor Luminaire



Light Standard 35 Watt High Pressure Sodium Vapor Luminaire



Light Standard 400 Watt High Pressure Sodium Vapor Luminaire



Light Standard 50 Watt High Pressure Sodium Vapor Luminaire



Light Standard 70 Watt High Pressure Sodium Vapor Luminaire



Light Standard 700 Watt High Pressure Sodium Vapor Luminaire



Manhole



Manhole 48 Inch



Sanitary Force Main Manhole



Sanitary Sewer Manhole



Storm Drain Manhole



Storm Drain Manhole with Inlet



Reset Mile Post



Mile Post Type A



Mile Post Type B



Mile Post Type C



Right of Way Marker



Tubular Marker



Alignment Monument



Iron Pin Reference Monument



Object Marker Type I



Object Marker Type II



Object Marker Type III



Caution Mode Arrow Panel



Back to Back Vertical Panel Sign



Double Direction Arrow Panel



Left Directional Arrow Panel



Right Directional Arrow Panel



Sequencing Arrow Panel



Truck Mounted Arrow Panel



Power Pole



Wood Pole



Pedestrian Push Button Post



Property Corner



Pull Box



Intelligent Transportation Pull Box



Sanitary Pump



Storm Drain Pump



Reinforced Pavement



Reinforced Concrete End Section 15 Inch



Reinforced Concrete End Section 18 Inch



Reinforced Concrete End Section 24 Inch



Reinforced Concrete End Section 30 Inch



Reinforced Concrete End Section 36 Inch



Reinforced Concrete End Section 42 Inch



Reinforced Concrete End Section 48 Inch



Reinforced Concrete End Section 54 Inch



Reset Right of Way Marker



Reset USGS Marker



Right of Way Markers



Riser 30 Inch



Continuous Split Barrel Sample



Flight Auger Sample



Split Barrel Sample



Thinwall Tube Sample



Highway Sign



SNOW GATE 18 FT



SNOW GATE 28 FT



SNOW GATE 40 FT



Standard Penetration Test



Transformer



Inclinometer Tube



Underdrain Cleanout



Excavation Unit





Water Valve

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE



This document was originally issued and sealed by
Roger Weigel,
Registration Number
PE-2930,
on 07/01/14 and the original document is stored at the
North Dakota Department
of Transportation

Two Lane, Two Way Roadways



Typical Protection Vehicle

Multilane Roadways




Typical Protection Vehicle


- Notes:
1. The working vehicle shall display a 360 degree rotating, flashing, oscillating or strobe light.
 2. The shadow vehicle shall display a 360 degree rotating, flashing, oscillating or strobe light. The shadow vehicle for Multilane Roadway shall also have a sequencing arrow panel Type C operated in the chevron mode.
 3. This application is for use during daylight hours and in areas of good visibility only.
 4. Two lane, two way roadway, a flagger shall be used to protect the work area and warn oncoming traffic.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-25-12	
REVISIONS	
DATE	CHANGE



This document was originally issued and sealed by
Roger Weigel,
Registration Number
PE- 2930 ,
on 9/25/2012 and the original document is stored at the
North Dakota Department
of Transportation




Multi-Directional Slip Base Assembly



Anchor Unit and Post Assembly




Multi-Directional Slip Base Anchor Unit and Post Sleeve Assembly




Top Post Receiver

Plate - ASTM A572 grade 50
Angle Receiver - 2 1/2"x2 1/2"x3/8" ASTM A36 structural angle



Bottom Soil Stub

Tube - 3"x3"x7 gauge ASTM A500 grade B tube
Stabilizing Wing - 7 gauge H.R.P.O. ASTM A1011
Plate - ASTM A572 grade 50



Bolt Retainer for Base Connection
Bolt Retainer- 1/32" Reprocessed Teflon

Notes:

1. Slip base bolts shall be torqued as specified by the manufacturer.
2. Anchor shall have a yield strength of 43.9 KSI and tensile strength of 59.3 KSI.
3. The 4" vertical clearance is required for the anchor or breakaway base. The 4"x60" measurement shall be made above and below post location and also back and ahead of the post.
4. When used in concrete sidewalk, anchor shall be same except without the wings.
5. Four post signs shall have over 7' between the first and the fourth posts.

Telescoping Perforated Tube						
Number of Posts	Post Size in.	Wall Thickness Gauge	Sleeve Size in.	Wall Thickness Gauge	Slip Base	Anchor Size without Slip Base in.
1	2	12			No	2 1/4
1	2 1/4	12			No	2 1/2
1	2 1/2	12			(A)	3
1	2 1/2	10			Yes	
1	2 1/4	12	2	12	Yes	
1	2 1/2	12	2 1/4	12	Yes	
2	2	12			No	2 1/4
2	2 1/4	12			No	2 1/2
2	2 1/2	12			Yes	
2	2 1/2	12			Yes	
2	2 1/4	10	2	12	Yes	
2	2 1/2	12	2 1/4	12	Yes	
3 & 4	2 1/2	12			Yes	
3 & 4	2 1/2	10			Yes	
3 & 4	2 1/2	12	2 1/4	12	Yes	
3 & 4	2 1/4	12	2	12	Yes	
3 & 4	2 1/2	10	2 3/16	10	Yes	



Properties of Telescoping Perforated Tube						
Tube Size in.	Wall Thickness in.	U.S. Standard Gauge	Weight per Foot lbs.	Moment of Inertia in. ⁴	Cross Sec. Area in. ²	Section Modulus in. ³
1 1/2 x 1 1/2	0.105	12	1.702	0.129	0.380	0.172
2 x 2	0.105	12	2.416	0.372	0.590	0.372
2 1/4 x 2 1/4	0.105	12	2.773	0.561	0.695	0.499
2 3/16 x 2 3/16	0.135	10	3.432	0.605	0.841	0.590
2 1/2 x 2 1/2	0.105	12	3.141	0.804	0.803	0.643
2 1/2 x 2 1/2	0.135	10	4.006	0.979	1.010	0.785

Top Post Receiver Data Table						
Square Post Sizes (B)	A	B	C	D	E	F
2 3/16"x10 ga.	1 9/64"	2 1/2"	3 1/32"	2 5/32"	1 33/64"	1 7/8"
2 1/2"x10 ga.	1 9/32"	2 1/2"	3 5/16"	5/8"	1 21/32"	1 3/4"

- (A) The breakaway base is required when the support is placed in weak soils. The Engineer shall determine if the soils are weak.
- (B) The 2 3/16"x10 ga. may be inserted into 2 1/2"x10 ga. for additional wind load.



NORTH DAKOTA DEPARTMENT OF TRANSPORTATION		This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930 , on 2/28/14 and the original document is stored at the North Dakota Department of Transportation
2-28-14		
REVISIONS		
DATE	CHANGE	

U-Channel Post




Breakaway U-Channel Detail Alternate A

A maximum of 2 posts shall be installed within 7'.



Breakaway U-Channel Splice Detail Alternate B (2.5 and 3 lb/ft)

A maximum of 3 posts shall be installed within 7'.



Breakaway U-Channel Splice Detail Alternate C (2.5 and 3 lb/ft)

A maximum of 3 posts shall be installed within 7'.

Alternate A Steps of Installation:
















- a) Drive anchor unit to within 12" of ground level.
b) Proper assembly established by lining up the bottom hole of retainer strap with the 6th hole from the top of the anchor unit.
c) Assemble strap to back of anchor unit using $\frac{5}{16}$ "x2" bolt, lock washer and nut.
d) Rotate strap 90° to left.
- a) Drive anchor unit to 4" above ground.
b) Rotate strap to vertical position.
- a) Place $\frac{5}{16}$ "x2" bolt, lock washer and nut in bottom of sign post to facilitate alignment of sign post with proper hole in anchor unit.
b) Alternately tighten two connector bolts.
- Complete assembly by tightening $\frac{5}{16}$ "x2" bolt (this fastens sign post to retainer strap).
- The base post, strap and sign post shall be properly nested. Proper nesting occurs when all flat surfaces of the base post, strap, and sign post at the bolts have full contact across the entire width.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
2-28-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by
Roger Weigel,
Registration Number
PE- 2930 ,
on 2/28/14 and the original document is stored at the
North Dakota Department
of Transportation

CONSTRUCTION SIGN DETAILS

TERMINAL AND GUIDE SIGNS



ARROW DETAILS

NOTES:


(A) Arrow may be right or left of the legend to indicate construction to the right or left.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-13-13	
REVISIONS	
DATE	CHANGE
8-17-17	Added sign & background color

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 8/17/17 and the original document is stored at the North Dakota Department of Transportation


CONSTRUCTION SIGN DETAILS
REGULATORY SIGNS

D-704-10




R1-50P-24

Legend: black (non-refl)
Background: white




R11-3c-60

Legend: black (non-refl)
Background: white




R2-1aP-24

Legend: black (non-refl)
Background: white



R11-4a-60

Legend: black (non-refl)
Background: white




R11-2a-48

Legend: black (non-refl)
Background: white

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION		This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930, on 8/17/17 and the original document is stored at the North Dakota Department of Transportation
8-13-13		
REVISIONS		
DATE	CHANGE	
8-17-17	Revised sign number	


CONSTRUCTION SIGN DETAILS
WARNING SIGNS

D-704-11




W5-8-48

Legend: black (non-refl)
Background: orange




W8-54-48

Legend: black (non-refl)
Background: orange



W20-51-48

Legend: black (non-refl)
Background: orange




W21-51-48

Legend: black (non-refl)
Background: orange


WORD	LETTER SPACING
AHEAD	Standard
200 FT	Standard
350 FT	Standard
500 FT	Standard
1000 FT	Reduce 40%
1500 FT	Reduce 40%
1/2 MILE	Reduce 50%
1 MILE	Standard

* DISTANCE MESSAGES




W5-9-48

Legend: black (non-refl)
Background: orange




W8-55-48

Legend: black (non-refl)
Background: orange




W20-52P-54

Legend: black (non-refl)
Background: orange




W22-8-48

Legend: black (non-refl)
Background: orange




W5-9-48

ARROW DETAILS




W8-53-48

Legend: black (non-refl)
Background: orange



W8-56-48

Legend: black (non-refl)
Background: orange



W21-50-48

Legend: black (non-refl)
Background: orange

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-13-13	
REVISIONS	
DATE	CHANGE
8-17-17	Updated sign number

This document was originally issued and sealed by
Roger Weigel,
Registration Number
PE- 2930,
on 8/17/17 and the original document is stored at the
North Dakota Department
of Transportation



ROAD CLOSURE LAYOUTS

- Notes
1. Variables
- S = Numerical value of speed limit or 85th percentile.
W = The width of taper in feet.
L = Minimum length of taper, S x W for freeways, expressways, and other roads with speeds of 45 mph or greater, or $W \times S^2/60$ for urban, residential, and other streets with speeds of 40 mph or less.
2. Place barricades on moveable assemblies and signs on portable assemblies when located on roadway.
3. Place delineator drums, barricades or cones for tapering traffic at dimension "S" and for tangents space at 2 times dimension "S".
4. Place Sequencing Arrow Panels at the beginning of the taper when possible. Where shoulder width does not provide sufficient room, move the panel closer to the work area and place on roadway surface. See Shoulder Closure Standard Drawing.
- Use Type A on roadways with slow moving traffic speeds and low volume (25 mph or less and 750 ADT or less).
Use Type B on roadways with moderate traffic speeds and volumes (40 mph or less and 5000 ADT or less).
Use Type C on roadways with high traffic speeds and volumes (over 40 mph or over 5000 ADT).
5. Re-establish speed. Determine exact speed limit in the field, dependent on location and conditions.
6. Determine the reduced speed limit based on the in-place speed limit before construction. Where speed reductions exceed 30 mph, install a second speed limit sign with the desired speed reduction (not to exceed 30 mph.) Place the second speed limit sign at $\frac{1}{2}$ B.
7. Use when work area is 1 mile or longer.
8. Install flags on warning signs in urban areas when signs are not portable. Mount 24 inch square flags perpendicular to the edges of the sign, and at such a distance above the edge that the flag does not touch the sign when limp.
9. Cover existing speed limit signs within reduced speed zones.
10. Where necessary, engineer will determine safe speed.
11. As an option, use portable sign supports in lieu of post mounted signs in accordance with NDDOT Standard Specifications.
12. Sign G20-55-96 is not required if this standard is part of other traffic control, or the work is less than 15 days.
13. Recommend using 40 mph speed limit in vicinity of workers, unless location and conditions dictate otherwise.

ADVANCE WARNING SIGN SPACING			
Road Type	Distance Between Signs Min. (ft)		
	A	B	C
Urban - Low Speed (30 mph or less)	150	150	150
Urban - Low Speed (over 30 to 40 mph)	280	280	280
Urban - High Speed (over 40 mph to 50 mph)	360	360	360
Rural - High Speed (over 50 mph to 65 mph)	720	720	720
Urban Expressway and Freeway (55 mph to 60 mph)	850	1350	2200
Rural Expressway and Freeway (70 mph to 75 mph)	1000	1500	2640
Interstate/4-Lane Divided (Maintenance and Surveying)	750	1000	1500

KEY	
	Type III barricade
	Sign
	Delineator drum
	Tubular markers
	Work area
	Flagger
	Sequencing arrow panel
	Vertical panels back to back

Longitudinal Buffer Space	
Speed (mph)	Length Min (feet)
20	115
25	155
30	200
35	250
40	305
45	360
50	425
55	495
60	570
65	645
70	730
75	820



NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-27-13	
REVISIONS	
DATE	CHANGE
8-17-17	Updated notes & Speed Limit signs


This document was originally issued and sealed by

Roger Weigel


Registration Number PE-2930,

on 08/17/17 and the original document is stored at the North Dakota Department of Transportation

ROAD CLOSURE AND LANE CLOSURE ON A TWO WAY ROAD LAYOUTS



ADVANCE WARNING SIGN SPACING			
Road Type	Distance Between Signs Min. (ft)		
	A	B	C
Urban - Low Speed (30 mph or less)	150	150	150
Urban - Low Speed (over 30 to 40mph)	280	280	280
Urban - High Speed (over 40 mph to 50 mph)	360	360	360
Rural - High Speed (over 50 mph to 65 mph)	720	720	720
Urban Expressway and Freeway (55 mph to 60 mph)	850	1350	2200
Rural Expressway and Freeway (70 mph to 75 mph)	1000	1500	2640
Interstate/4-Lane Divided (Maintenance and Surveying)	750	1000	1500



- Notes
- Variables
S = Numerical value of speed limit or 85th percentile.
W = The width of taper in feet
L = Minimum length of taper in feet. S x W for freeways, expressways, and roads with speeds of 45 mph or greater, or W x S²/60 for urban, residential, and streets with speeds of 40 mph or less.
 - Place barricades on moveable assemblies and signs on portable assemblies when located on the roadway.
 - Place delineator drums for tapering traffic at 3 equal spaces and for tangents space them at 2 times dimension "S".
 - Re-establish speed limit. Determine exact speed limit in the field, dependent on location and conditions.
 - Determine the reduced speed limit based on the in place speed limit before construction. Where speed reductions exceed 30 mph, install a second speed limit sign with the desired speed reduction (not to exceed 30 mph.) Place second speed limit sign at 1/2B.
 - Install flags on warning signs in urban areas when signs are not portable. Mount 24 inch square flags perpendicular to the edges of the sign, and at such a distance above the edge that the flag does not touch the sign when limp.
 - Cover existing speed limit signs within a reduced speed zone.
 - Where necessary, safe speed to be determined by the Engineer.
 - As an option, use portable sign supports in lieu of post mounted signs in accordance with NDDOT Standard Specifications.
 - Signs G20-55-96 or R2-1aP-24 are not required when pilot car operation is used, if this standard is part of other traffic control layouts, or if work is less than 15 days.
 - When highway-rail grade crossings exist either within or in the vicinity of the roadway work activities:
 - Extra care shall be taken to minimize the probability of conditions being created, either by lane restrictions, flagging or other operations, where vehicles might be stopped within the highway-rail grade crossing (considered as being 15 feet on either side of the closest and farthest rail.)
 - Place "Do Not Stop on Tracks" sign (R8-8-24) near cross buck in each direction while lane closure is near tracks.
 - Extend buffer space between work zone and lane closure transition upstream of the highway-rail grade crossing to prevent flagging queue from extending across highway-rail grade crossing.
 - If queuing extends across highway-rail crossing, provide flagger at crossing to prevent vehicles from stopping within the crossing (even when automatic warning devices are in place.)
 - Recommend using 40 mph speed limit in vicinity of workers, unless location and conditions dictate otherwise.


KEY		
Delineator Drum	Type III Barricade	Flagger
Sign	Work/Hazard Area	

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-27-13	
REVISIONS	
DATE	CHANGE
3-13-14	Revised Sign Call "ROAD WORK XXX FT"
8-17-17	Update notes & sign numbers

This document was originally issued and sealed by
Roger Weigel
Registration Number
PE-2930,
on **08/17/17** and the original document is stored at the
North Dakota Department
of Transportation

CONSTRUCTION TRUCK AND TEMPORARY DETOUR LAYOUTS

D-704-22



Notes

- Place barricades on a moveable assemblies and signs on portable assemblies when located on roadway.
- Where necessary, safe speed to be determined by the Engineer.
- Determine the reduced speed limit based on the in-place speed limit before construction. Where speed reductions exceed 30 mph, install a second speed limit sign with the desired speed reduction (not to exceed 30 mph.) Place the second speed limit sign at 1/2 B.
- Install flags on warning signs in urban areas when signs are not portable. Mount 24 inch square flags perpendicular to the edges of the sign, and at such a distance above the edge that the flag does not touch the sign when limp.
- Cover existing speed limit signs within a reduced speed zone.
- Covered (when approved by engineer) or obliterated pavement marking measured as Obliteration of Pavement Marking.
- As an option, use portable sign supports in lieu of post mounted signs in accordance with NDDOT Standard Specifications.
- Install sign G20-1b-60 when work is suspended for winter.
- If existing stop sign is in place, a 48" stop sign is not required.
- Sign G20-55-96 is not required if layout is part of other traffic control or if work is less than 15 days.
- Recommend using 40 mph speed limit in vicinity of workers, unless location and conditions dictate otherwise.


ADVANCE WARNING SIGN SPACING			
Road Type	Distance Between Signs		
	A	B	C
Urban - Low Speed (30 mph or less)	150	150	150
Urban - Low Speed (over 30 to 40mph)	280	280	280
Urban - High Speed (over 40 mph to 50 mph)	360	360	360
Rural - High Speed (over 50 mph to 65 mph)	720	720	720
Urban Expressway and Freeway (55 mph to 60 mph)	850	1350	2200
Rural Expressway and Freeway (70 mph to 75 mph)	1000	1500	2640
Interstate/4-Lane Divided (Maintenance and Surveying)	750	1000	1500

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-27-13	
REVISIONS	
DATE	CHANGE
8-17-17	Update notes & sign numbers

This document was originally issued and sealed by
Roger Weigel
Registration Number
PE- 2930,
on 08/17/17 and the original document is stored at the
North Dakota Department
of Transportation

PORTABLE SIGN SUPPORT ASSEMBLY

D-704-50



Notes:


- ① The maximum weight of the assembly is 250 pounds.
- ② Use a 14" wheel and tire.
- ③ Automotive and equipment axle assemblies may not be used for trailer-mounted sign supports.
- ④ Other NCHRP 350 crash tested assemblies are acceptable.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
11-23-10	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by
Roger Weigel
Registration Number
PE- 2930 ,
on 11/23/10 and the original document is stored at the
North Dakota Department
of Transportation

MOBILE OPERATION
Grinding Shoulder Rumble Strips

D-704-56




TWO LANE - TWO WAY ROADWAY




TWO LANE - TWO WAY ROADWAY

Typical Protection Vehicle with
Flashing Arrow Panel In Caution Mode

- Notes:
1. Provide truck mounted attenuators on additional vehicles in the convoy, at no additional cost.
 2. Provide rotating, flashing, oscillating, or strobe lights on vehicles.
 3. Provide Type B or Type C flashing arrow panels that are controlled from inside the vehicle.
 4. Provide two - way electronic communication capability in each vehicle.
 5. Vary vehicle spacing between the protection vehicle and work vehicle depending on sight distance restrictions. Keep the spacing of the convoy vehicles such that motorists approaching the work convoy can see the protection vehicle in time to slow down and safely pass the work vehicles.
 6. Move advance Road Work Ahead signs as the work area moves through the construction zone.




INTERSTATE & 4 LANE DIVIDED HIGHWAY



INTERSTATE & 4 LANE DIVIDED HIGHWAY

Typical Protection Vehicle with Flashing Arrow
Panel In Flashing Arrow Mode





NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
11-15-12	
REVISIONS	
DATE	CHANGE
8-17-17	Updated notes & signs

This document was originally
issued and sealed by
Roger Weigel
Registration Number
PE- 2930,
on 08/17/17 and the original
document is stored at the
North Dakota Department
of Transportation


BITUMINOUS LABORATORY

D-706-1



Provide a laboratory with the following:






1. A 1'x1' shelf at 36" above the regular countertop.
2. Double compartment stainless steel sink, with each compartment a minimum of 16"x14"x10" deep. Provide water service lines made of copper or plastic and a diameter of ½ inch.
3. An exhaust fan capable of removing inside air at a rate of 400 CFM.
4. Fresh air vent hinged to open or close manually.
5. 24" x 48" table capable of holding a 200 lb masonry saw with a minimum clearance of 36" above the table.
6. A water supply tank with a capacity of 500 gallons and a 20 gallon capacity pressure tank on the pump.
7. Heavy duty type locks, latches, and hinges for doors made to withstand the intense use in service.
8. A wall between the office and the work area properly insulated to prevent the transmission of heat and noise.
9. The steel cable tie downs and ground anchors at each corner of the lab.
10. Electrical service entrance wired for 100 amps and separate circuits for air conditioners. Space convenience outlets in counter areas a minimum of four feet apart.




NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-03-13	
REVISIONS	
DATE	CHANGE
07-30-14	Changed standard's title and revised notes.
01-11-16	Revised notes.

This document was originally issued and sealed by
Roger Weigel
Registration Number
PE- 2930 ,
on 01/11/16 and the original document is stored at the
North Dakota Department
of Transportation

RUMBLE STRIPS
UNDIVIDED HIGHWAYS (SHOULDERS 4' OR GREATER)



Discontinue rumble strip approx. 12" on both sides of PCC transverse joint






NOTES:

- 1) Discontinue shoulder rumble strips through the entire length of right turn lanes, 100' before right turn lane tapers, and at the radius of a paved or gravel highway, section line, approach, or private drive.
- 2) Discontinue centerline rumble strips through the entire length of left turn lanes, 100' before left turn lane tapers and median islands, and 100' before and after a paved or gravel highway, section line, approach, or private drive.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
12-29-09	
REVISIONS	
DATE	CHANGE
2-25-10	Note 4 was added.
4-19-10	Revised Note 5, Note 6, and Turn Lane (Right & Left).
9-8-11	Revised Notes and D-760-3.

This document was originally
issued and sealed by
Roger Weigel,
Registration Number
PE- 2930 ,
on 9/8/11 and the original
document is stored at the
North Dakota Department
of Transportation

SAW SLOTTED RUMBLE STRIPS AT INTERSECTIONS




NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
12-29-09	
REVISIONS	
DATE	CHANGE
2-22-10	Saw Slotted width revised.
2-25-10	Note 7 was added.
9-8-11	Revised Notes and D-760-5.
7-7-14	Deleted Notes.

This document was originally issued and sealed by
Roger Weigel,
Registration Number
PE- 2930 ,
on 7/7/14 and the original document is stored at the
North Dakota Department
of Transportation


PAVEMENT MARKING

D-762-4


NOTES:
1. Edge lines shall be continued through private drives and field drives and broken for intersections.




Two Lane Two Way
RURAL ROADWAY




Two Lane Roadway
INTERSTATE HIGHWAY
Concrete Section




RURAL FIVE LANE ROADWAY
Concrete Section




Two Lane Divided
Rural Roadway
PRIMARY HIGHWAY
Asphalt Section




RURAL FIVE LANE ROADWAY
Asphalt Section




URBAN FIVE LANE SECTION
Concrete Section




Two Lane Roadway
PRIMARY HIGHWAY
Concrete Section




URBAN FIVE LANE SECTION
Asphalt Section




RURAL FOUR LANE ROADWAY
Asphalt Section




Two Lane Roadway
INTERSTATE HIGHWAY
Asphalt Section




RURAL FOUR LANE ROADWAY
Concrete Section



URBAN FOUR LANE SECTION
Asphalt Section



URBAN FOUR LANE SECTION
Concrete Section




CENTERLINE PAVEMENT MARKING SKIP SPACING DETAIL

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
12-1-10	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930, on 12-1-10 and the original document is stored at the North Dakota Department of Transportation

PAVEMENT MARKING FOR STANDARD 90 DEGREE FLARED INTERSECTION
(No Center Left Turn Lane on Major Road)



D-762-5



Notes

- 1. At "T" intersections (3-leg), additionally install left turn pavement marking message arrow.
- 2. The barrier lines have variable distances dependent on speed limit. Obtain barrier line length from table below (stopping sight distance.)

Table for Length of Barrier Line									
Speed Limit (mph)	30	35	40	45	50	55	60	65	70
Minimum Length	200'	250'	305'	360'	425'	495'	570'	645'	730'




- 4" Marking
- 8" Marking
- 24" Marking

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
3-29-16	
REVISIONS	
DATE	CHANGE
8-17-17	Updated note & dimensioning


This document was originally issued and sealed by
Roger Weigel
Registration Number
PE- 2930,
on 08/17/17 and the original document is stored at the
North Dakota Department
of Transportation

SHORT-TERM PAVEMENT MARKING


D-762-11




Painted or Tape Lines




Raised Pavement Markers
TWO-LANE TWO-WAY ROADWAY




Painted or Tape Lines




Raised Pavement Markers
FOUR LANE ROADWAY




Painted or Tape Lines



Raised Pavement Markers
FIVE LANE ROADWAY TWO WAY LEFT TURN



Painted or Tape Lines



Raised Pavement Markers
FIVE LANE ROADWAY WITH MARKED ISLANDS

- NOTES:
- Two-lane two-way roadways shall have no passing zones placed as shown. No passing zone signs may be placed in lieu of short term no passing zone pavement markings. These signs will be allowed to remain in place for three days, at which time the short term no passing zone pavement marking shall be placed.
 - Short term center line stripe (paint) on top lift shall be carefully placed with exact spacing so that the permanent stripe will match when applied.
 - Raised markers and tape markings shall be removed after permanent pavement marking has been installed. Removed markings shall become the property of the contractor.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
12-1-10	
REVISIONS	
DATE	CHANGE
3-29-16	Re-numbered to be D-762-11 (previously was D-762-6)

This document was originally issued and sealed by
Roger Weigel,
Registration Number
PE- 2930 ,
on 03/29/16 and the original document is stored at the
North Dakota Department
of Transportation