

NDDOT ABBREVIATIONS

? This is a special text character used in the labeling of existing features. It indicates a feature that has an unknown characteristic, potentially based on: lack of description, location accuracy or purpose.

Abn abandoned
 Abut abutment
 Ac acres
 Adj adjusted
 Aggr aggregate
 Ahd ahead
 ARV air release valve
 Align alignment
 Al alley
 Alt alternate
 Alum aluminum
 ADA Americans with Disabilities Act
 A ampere
 & and
 Appr approach
 Approx approximate
 ACP asbestos cement pipe
 Asph asphalt
 AC asphalt cement
 Assmd assumed
 @ at
 Atten attenuation
 ATR automatic traffic recorder
 Ave Avenue
 Avg average
 ADT average daily traffic
 Az azimuth
 Bk back
 BF back face
 Bs backsight
 Balc balcony
 B Wire barbed wire
 Barr barricade
 Btry battery
 Brg bearing
 BI beehive inlet
 Beg begin
 BM bench mark
 Bkwy bikeway
 Bit bituminous
 Blk block
 Bd Ft board feet
 BH bore hole
 BS both sides
 Bot bottom
 Blvd Boulevard
 Bndry boundary
 BC brass cap
 Brkwy breakaway
 Br bridge
 Bldg building

BV butterfly valve
 Byp bypass
 C Gdrl cable guardrail
 Calc calculate
 Cd candela
 CIP cast iron pipe
 CB catch basin
 CRS cationic rapid setting
 C Gd cattle guard
 C To C center to center
 Cl or C centerline
 Cm centimeter
 Ch chain
 Chnlk chain-link
 Ch Blk channel block
 Ch Ch channel change
 Chk check
 Chsld chiseled
 Cir circle
 Cl class
 Cl clay
 Cl F clay fill
 Cl Hvy clay heavy
 Cl Lm clay loam
 Clnt clean-out
 Clr clear
 Cl&gr clearing & grubbing
 Co S coal slack
 Comb. combination
 Coml commercial
 Compr compression
 CADD computer aided drafting & design
 Conc concrete
 Cond conductor
 Const construction
 Cont continuous
 CSB continuous split barrel sample
 Contr contraction
 Contr contractor
 CP control point
 Coord coordinate
 Cor corner
 Corr corrected
 CAES corrugated aluminum end section
 CAP corrugated aluminum pipe
 CMES corrugated metal end section
 CMP corrugated metal pipe
 CPVCP corrugated poly-vinyl chloride pipe
 CSES corrugated steel end section
 CSP corrugated steel pipe
 C coulomb
 Co County
 Crse course
 C Gr course gravel
 CS course sand

Ct Court
 Xarm cross arm
 Xbuck cross buck
 Xsec cross sections
 Xing crossing
 Xrd Crossroad
 Crn crown
 CF cubic feet
 M3 cubic meter
 M3/s cubic meters per second
 CY cubic yard
 Cy/mi cubic yards per mile
 Culv culvert
 C&G curb & gutter
 CI curb inlet
 CR curb ramp
 CS curve to spiral
 C cut
 Dd Ld dead load
 Defl deflection
 Defm deformed
 Deg or D degree
 DInt delineate
 DIntr delineator
 Depr depression
 Desc description
 Det detail
 DWP detectable warning panel
 Dtr detour
 Dia diameter
 Dir direction
 Dist distance
 DM disturbed material
 DB ditch block
 DG ditch grade
 Dbl double
 Dn down
 Dwg drawing
 Dr drive
 Drwy driveway
 DI drop inlet
 D dry density
 Ea each
 Esmt easement
 E East
 EB Eastbound
 Elast elastomeric
 EL electric locker
 E Mtr electric meter
 Elec electric/al
 EDM electronic distance meter
 Elev or El elevation
 Ellipt elliptical
 Emb embankment
 Emuls emulsion/emulsified

ES end section
 Engr engineer
 ESS environmental sensor station
 Eq equal
 Eq equation
 Evgr evergreen
 Exc excavation
 Exst existing
 Exp expansion
 Expy Expressway
 E external of curve
 Extru extruded
 FOS factor of safety
 F Fahrenheit
 FS far side
 F farad
 Fed Federal
 FP feed point
 Ft feet/foot
 Fn fence
 Fn P fence post
 FO fiber optic
 FB field book
 FD field drive
 F fill
 FAA fine aggregate angularity
 FS fine sand
 FH fire hydrant
 Fl flange
 Flrd flared
 FES flared end section
 F Bcn flashing beacon
 FA flight auger sample
 FL flow line
 Ftg footing
 FM force main
 Fs foresight
 Fnd found
 Fdn foundation
 Frac fractional
 Frwy freeway
 Frt front
 FF front face
 F Disp fuel dispenser

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 07/01/14 and the original document is stored at the North Dakota Department of Transportation

NDDOT ABBREVIATIONS

D-101-2

FFP	fuel filler pipes	IPn	Iron Pin	MC	medium curing	Ped	pedestal
FLS	fuel leak sensor	IP	iron Pipe	M	mega	Ped	pedestrian
Furn	furnish/ed	Jt	joint	Mer	meridian	PPP	pedestrian pushbutton post
Gal	gallon	J	joule	M	meter	Pen.	penetration
Galv	galvanized	Jct	junction	M/s	meters per second	Perf	perforated
Gar	garage	K	kelvin	M	mid ordinate of curve	Per.	perimeter
Gs L	gas line	Kn	kilo newton	Mi	mile	PL	pipeline
G Reg	gas line regulator	Kpa	kilo pascal	MM	mile marker	PI	place
GMV	gas main valve	Kg	kilogram	MP	mile post	P&P	plan & profile
G Mtr	gas meter	Kg/m3	kilogram per cubic meter	MI	milliliter	PL	plastic limit
GSV	gas service valve	Km	kilometer	Mm	millimeter	PI	plate
GVP	gas vent pipe	K	Kip(s)	Mm/hr	millimeters per hour	Pt	point
GV	gate valve	LS	Land Surveyor (licensed)	Min	minimum	PCC	point of compound curve
Ga	gauge	LSIT	Land Surveyor In Training	Misc	miscellaneous	PC	point of curve
Geod	geodetic	Ln	lane	Mon	monument	PI	point of intersection
GIS	Geographical Information System	Lg	large	Mnd	mound	PRC	point of reverse curvature
G	giga	Lat	latitude	Mtbl	mountable	PT	point of tangent
GPS	Global Positioning System	Lt	left	Mtd	mounted	POC	point on curve
Gov	government	L	length of curve	Mtg	mounting	POT	point on tangent
Grd	graded/grade	Lens	lenses	Mk	muck	PE	polyethylene
Gr	gravel	Lvl	level	Mun	municipal	PVC	polyvinyl chloride
Grnd	ground	LB	level book	N	nano	PCC	Portland Cement concrete
GWM	ground water monitor	Lvng	leveling	NGS	National Geodetic Survey	Lb or #	pounds
Gdrl	guardrail	Lht	light	NS	near side	PP	power pole
Gtr	gutter	LP	light pole	Neop	neoprene	Preempt	preemption
H Plg	H piling	Ltg	lighting	Ntwk	network	Prefab	prefabricated
Hdwl	headwall	Lig Co	lignite coal	N	newton	Prfmd	performed
Ha	hectare	Lig Sl	lignite slack	N	North	Prep	preparation
Ht	height	LF	linear foot	NE	North East	Press.	pressure
HI	height of instrument	Liq	liquid	NW	North West	PRV	pressure relief valve
Hel	helical	LL	liquid limit	NB	Northbound	Prestr	prestressed
H	henry	L	litre	No. or #	number	Pvt	private
HZ	hertz	Lm	loam	Obsc	obscure(d)	PD	private drive
HDPE	high density polyethylene	Loc	location	Obsn	observation	Prod.	production/produce
HM	high mast	LC	long chord	Ocpd	occupied	Prog	programmed
HP	high pressure	Long.	longitude	Ocpy	occupy	Prop.	property
HPS	high pressure sodium	Lp	loop	Off Loc	office location	Prop Ln	property line
Hwy	highway	LD	loop detector	O/s	offset	Ppsd	proposed
Hor	horizontal	Lm	lumen	OC	on center	PB	pull box
HBP	hot bituminous pavement	Lum	luminaire	C	one dimensional consolidation		
HMA	hot mix asphalt	L Sum	lump sum	OC	organic content		
Hr	hour(s)	Lx	lux	Orig	original		
Hyd	hydrant	ML	main line	O To O	out to out		
Ph	hydrogen ion content	M Hr	man hour	OD	outside diameter		
Id	identification	MH	manhole	OH	overhead		
In or "	inch	Mkd	marked	PMT	pad mounted transformer		
Incl	inclinometer tube	Mkr	marker	Pg	pages		
IMH	inlet manhole	Mkg	marking	Pntd	painted		
ID	inside diameter	MA	mast arm	Pr	pair		
Inst	instrument	Matl	material	Pnl	panel		
Intchg	interchange	Max	maximum	Pk	park		
Intmdt	intermediate	MC	meander corner	PK	Parker-Kalon nail		
Intscn	intersection	Meas	measure	Pa	pascal		
Inv	invert	Mdn	median	PSD	passing sight distance		
IM	iron monument	MD	median drain	Pvmt	pavement		

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
08-03-15	General Revisions

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 08/03/15 and the original document is stored at the North Dakota Department of Transportation

NDDOT ABBREVIATIONS

D-101-3

Qty	quantity	SN	sign number	Tan	tangent	Wb	weber
Qtr	quarter	Sig	signal	T	tangent (semi)	WIM	weigh in motion
Rad or R	radius	Si Cl	silt clay	TS	tangent to spiral	W	west
RR	railroad	Si Cl Lm	silty clay loam	Tel	telephone	WB	westbound
Rlwy	railway	Si Lm	silty loam	Tel B	Telephone Booth	Wrng	wiring
Rsd	raised	Sgl	single	Tel P	telephone pole	W/	with
RTP	random traverse point	SC	slow curing	Tv	television	W/o	without
Rge or R	range	SS	slow setting	Temp	temperature	WC	witness corner
RC	rapid curing	Sm	small	Temp	temporary	WGS	world geodetic system
Rec	record	S	South	TBM	temporary bench mark	Z	zenith
Rcy	recycle	SE	South East	T	tesla		
RAP	recycled asphalt pavement	SW	South West	T	thinwall tube sample		
RPCC	recycled portland cement concrete	SB	Southbound	T/mi	tons per mile		
Ref	reference	Sp	spaces	Ts	topsoil		
R Mkr	reference marker	Spcl	special	Twp or T	township		
RM	reference monument	SA	special assembly	Traf	traffic		
Refl	reflectorized	SP	special provisions	TSCB	traffic signal control box		
RCB	reinforced concrete box	G	specific gravity	Tr	trail		
RCES	reinforced concrete end section	Spk	spike	Transf	transformer		
RCP	reinforced concrete pipe	SC	spiral to curve	TB	transit book		
RCPS	reinforced concrete pipe sewer	ST	spiral to tangent	Trans	transition		
Reinf	reinforcement	SB	split barrel sample	TT	transmission tower		
Res	reservation	SH	sprinkler head	Trans	transverse		
Ret	retaining	SV	sprinkler valve	Trav	traverse		
Rev	reverse	Sq	square	TP	traverse point		
Rt	right	SF	square feet	Trtd	treated		
R/W	right of way	Km2	square kilometer	Trmt	treatment		
Riv	river	M2	square meter	Qc	triaxial compression		
Rd	road	SY	square yard	TERO	tribal employment rights ordinance		
Rdbd	road bed	Stk	stake	Tpl	triple		
Rdwy	roadway	Std	standard	TP	turning point		
RWIS	roadway weather information system	N	standard penetration test	Typ	typical		
Rk	rock	Std Specs	standard specifications	Qu	unconfined compressive strength		
Rt	route	Sta	station	Ugrnd	underground		
Salv	salvage(d)	Sta Yd	station yards	USC&G	US Coast & Geodetic Survey		
Sd	sand	Stm L	steam line	USGS	US Geologic Survey		
Sdy Cl	sandy clay	SEC	steel encased concrete	Util	utility		
Sdy Cl Lm	sandy clay loam	SMA	stone matrix asphalt	VG	valley gutter		
Sdy Fl	sandy fill	SSD	stopping sight distance	Vap	vapor		
Sdy Lm	sandy loam	SD	storm drain	Vert	vertical		
San	sanitary sewer line	St	street	VC	vertical curve		
Sc	scoria	SPP	structural plate pipe	VCP	vitrified clay pipe		
Sec	seconds	SPPA	structural plate pipe arch	V	volt		
Sec	section	Str	structure	Vol	volume		
SL	section line	Subd	subdivision	Wkwy	walkway		
Sep	separation	Sub	subgrade	W	water content		
Seq	sequence	Sub Prep	subgrade preperation	WGV	water gate valve		
Serv	service	Ss	subsoil	WL	water line		
Sh	shale	SE	superelevation	WM	water main		
Sht	sheet	SS	supplement specification	WMV	water main valve		
Shtng	sheeting	Supp	supplemental	W Mtr	water meter		
Shldr	shoulder	Surf	surfacing	WSV	water service valve		
Sw	sidewalk	Surv	survey	WW	water well		
S	siemens	Sym	symmetrical	W	watt		
SD	sight distance	SI	systems international	Wrng	wearing		

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
08-03-15	General Revisions

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 08/03/15 and the original document is stored at the North Dakota Department of Transportation

NDDOT UTILITY COMPANY AND ORGANIZATION ABBREVIATIONS

D-101-10

702COM 702 Communications
 ACCENT Accent Communications
 AGASSIZ WU Agassiz Water Users Incorporated
 AGC Associated General Contractors of America
 All PI Alliance Pipeline
 ALL SEAS WU All Seasons Water Users Association
 AMOCO PI Amoco Pipeline Company
 AMRDA HESS Amerada Hess Corporation
 AT&T AT&T Corporation
 B PAW Bear Paw Energy Incorporated
 BAKER ELEC Baker Electric
 BASIN ELEC Basin Electric Cooperative Incorporated
 BEK TEL Bek Communications Cooperative
 BELLE PL Belle Fourche Pipeline Company
 BLM Bureau of Land Management
 BNSF Burlington Northern Santa Fe Railway
 BOEING Boeing
 BRNS RWD Barnes Rural Water District
 BURK-DIV ELEC Burke-Divide Electric Cooperative
 BURL WU Burleigh Water Users
 Cable One Cable One
 CABLE SERV Cable Services
 CAP ELEC Capital Electric Cooperative Incorporat
 CASS CO ELEC Cass County Electric Cooperative
 CASS RWU Cass Rural Water Users Incorporated
 CAV ELEC Cavalier Rural Electric Cooperative
 CBLCOM Cablecom Of Fargo
 CENEX PL Cenex Pipeline
 CENT PL WATER DIST Central Pipe Line Water District
 CENT PWR ELEC Central Power Electric Cooperative
 COE Corps of Engineers
 CONS TEL Consolidated Telephone
 CONT RES Continental Resource Inc
 CPR Canadian Pacific Railway
 D O E Department Of Energy
 DAK CARR Dakota Carrier Network
 DAK CENT TEL Dakota Central Telephone
 DAK RWD Dakota Rural Water District
 DGC Dakota Gasification Company
 DICKEY R NET Dickey Rural Networks
 DICKEY RWU Dickey Rural Water Users Association
 DICKEY TEL Dickey Telephone
 DNRR Dakota Northern Railroad
 DOME PL Dome Pipeline Company
 DVELEC Dakota Valley Electric Cooperative
 DVMW Dakota, Missouri Valley & Western
 ENBRDG Enbridge Pipelines Incorporated
 ENVENTIS Enventis Telephone
 FALK MNG Falkirk Mining Company
 FHWA Federal Highway Administration
 G FKS-TRL WD Grand Forks-traill Water District
 GETTY TRD & TRAN Getty Trading & Transportation
 GLDN W ELEC Golden West Electric Cooperative
 GRGS CO TEL Griggs County Telephone

GT PLNS NAT GAS Great Plains Natural Gas Company
 HALS TEL Halstad Telephone Company
 IDEA1 Idea1
 INT-COMM TEL Inter-Community Telephone Company
 KANEB PL Kaneb Pipeline Company
 KEM ELEC Kem Electric Cooperative Incorporated
 KOCH GATH SYS Koch Gathering Systems Incorporated
 LKHD PL Lakehead Pipeline Company
 LNGDN RWU Langdon Rural Water Users Incorporated
 LWR YELL R ELEC Lower Yellowstone Rural Electric
 MCKNZ CON McKenzie Consolidated Telcom
 MCKENZIE ELEC McKenzie Electric Cooperative
 MCKNZ WRD McKenzie County Water Resource District
 MCLEOD McLeod USA
 MCLN ELEC McLean Electric Cooperative
 MCLN-SHRDN R WAT McLean-Sheridan Rural Water
 MDU Montana-dakota Utilities
 MID-CONT CABLE Mid-Continent Cable
 MIDSTATE TEL Midstate Telephone Company
 MINOT CABLE Minot Cable Television
 MINOT TEL Minot Telephone Company
 MISS W W S Missouri West Water System
 MNKOTA PWR Minnkota Power
 MOR-GRAN-SOU ELEC Mor-gran-sou Electric Cooperative
 MOUNT-WILLI ELEC Mountrail-williams Electric Cooperative
 MRE LBTY TEL Moore & Liberty Telephone
 MUNICIPAL City Water And Sewer
 MUNICIPAL City Of '.....'
 N CENT ELEC North Central Electric Cooperative
 N VALL W DIST North Valley Water District
 ND PKS & REC North Dakota Parks And Recreation
 ND TEL North Dakota Telephone Company
 NDDOT North Dakota Department of Transportation
 NDSU SOIL SCI DEPT NDSU Soil Science Department
 NEMONT TEL Nemont Telephone
 NODAK R ELEC Nodak Rural Electric Cooperative
 NOON FRMS TEL Noonan Farmers Telephone Company
 NPR Northern Plains Railroad
 NSP Northern States Power
 NTH PRAIR RW Northern Prairie Rural Water Association
 NTHN BRDR PL Northern Border Pipeline
 NTHN PLNS ELEC Northern Plains Electric Cooperative Incorporated
 NTHWSTRN REF Northwestern Refinery Company
 NW COMM Northwest Communication Cooperation
 ONEOK Oneok gas
 OSHA Occupational Safety and Health Administration
 OTTR TL PWR Otter Tail Power Company
 P L E M Prairielands Energy Marketing
 POLAR COM Polar Communications
 PVT ELEC Private Electric
 QWEST Qwest Communications
 R&T W SUPPLY R & T Water Supply Association
 RAMSEY R SEW Ramsey Rural Sewer Association
 RAMSEY RW Ramsey Rural Water Association
 RAMSEY UTIL Ramsey County Rural Utilities

RED RIV TEL Red River Rural Telephone
 RESVTN TEL Reservation Telephone
 ROBRTS TEL Roberts Company Telephone
 R-RIDER ELEC Roughrider Electric Coop
 RRVW Red River Valley & Western Railroad
 RSR ELEC R.S.R. Electric Cooperative
 S E W U South East Water Users Incorporated
 SCOTT CABLE Scott Cable Television Dickinson
 SHERDN ELEC Sheridan Electric Cooperative
 SHEYN VLY ELEC Sheyenne Valley Electric Cooperative
 SKYTECH Skyland Technologies Incorporated
 SLOPE ELEC Slope Electric Cooperative Incorporated
 SOURIS RIV TELCOM Souris River Telecommunications
 ST WAT COMM State Water Commission
 STATE LN WATER State Line Water Cooperative
 STER ENG Sterling Energy
 STUT RWU Stutsman Rural Water Users
 SW PL PRJ Southwest Pipeline Project
 T M C Turtle Mountain Communications
 TCI TCI of North Dakota
 TESORO GH PLNS PL Tesoro High Plains Pipeline
 TRI-CNTY WU Tri-County Water Users Incorporated
 TRL CO RWU Traill County Rural Water Users
 UNTD TEL United Telephone
 UPPR SOUR WUA Upper Souris Water Users Association
 US SPRINT U.S. Sprint
 USAF MSL CABLE U.S.A.F. Missile Cable
 USFWS US Fish and Wildlife Service
 USW COMM U.S. West Communications
 VRNDRY ELEC Verendrye Electric Cooperative
 W RIV TEL West River Telephone Incorporated
 WEB W. E. B. Water Development Association
 WILLI RWA Williams Rural Water Association
 WILSTN BAS PL Williston Basin Interstate Pipeline Company
 WLSH RWD Walsh Water Rural Water District
 WOLVRTN TEL Wolverton Telephone
 XLENER Xcel Energy
 YSVR Yellowstone Valley Railroad

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 07/01/14 and the original document is stored at the North Dakota Department of Transportation

Line Styles

D-101-20

Existing Topography

- Existing Ground Void
- Existing Cemetary Boundary
- Existing Box Culvert Bridge
- Existing Concrete Surface
- Existing Drainage Structure
- Existing Gravel Surface
- Existing Riprap
- Existing Dirt Surface
- Existing Asphalt Surface
- Existing Tie Point Line
- Existing Railroad Centerline
- Existing Guardrail Cable
- Existing Guardrail Metal
- Existing Edge of Water
- Existing Fence
- Existing Railroad
- Existing Field Line
- Exst Flow
- Existing Curb
- Existing Valley Gutter
- Existing Driveway Gutter
- Existing Curb and Gutter
- Existing Mountable Curb and Gutter

- Existing 3-Cable w Posts
- Site Boundary
- Existing Berm, Dike, Pit, or Earth Dam
- Existing Ditch Block
- Existing Tree Boundary
- Existing Brush or Shrub Boundary
- Existing Retaining Wall
- Existing Planter or Wall
- Existing W-Beam Guardrail with Posts
- Existing Railroad Switch
- Gravel Pit - Borrow Area
- Existing Wet Area-Vegetation Break

Proposed Topography

- 3-Cable w Posts
- Flow
- Fence
- Remove Line
- Wall
- Retaining Wall (Plan View)
- W-Beam w Posts

Existing Utilities

- Existing Electrical
- Existing Fiber Optic Line
- Existing TV Fiber Optic
- Existing Gas Pipe
- Existing Overhead Utility Line
- Existing Power
- Existing Fuel Pipeline
- Existing Undefined Above Ground Pipe Line
- Existing Sanitary Sewer
- Existing Sanitary Force Main
- Existing Storm Drain
- Existing Storm Drain Force Main
- Existing Culvert
- Existing Telephone Line
- Existing TV Line
- Existing Water or Steam Line
- Existing Under Drain
- Existing Slotted Drain
- Existing Conduit
- Existing Conductor
- Existing Down Guy Wire Down Guy
- Existing Underground Vault or Lift Station

Proposed Utilities

- 24 Inch Pipe
- Reinforced Concrete Pipe
- Under Drain
- Edge Drain

Traffic Utilities

- Conductor
- Fiber Optic
- Existing Loop Detector
- Existing Double Micro Loop Detector
- Micro Loop Detector Double
- Existing Micro Loop Detector
- Micro Loop Detector
- Signal Head with Mast Arm
- Existing Signal Head with Mast Arm

Sign Structures

- Existing Overhead Sign Structure
- Existing Overhead Sign Structure Cantilever
- Overhead Sign Structure Cantilever

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
09-23-16	Added and Revised Items, Organized by Functional Groups

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 09/23/16 and the original document is stored at the North Dakota Department of Transportation

Line Styles

D-101-21

Right Of Way

- Easement
- Existing Easement
- Right of Way
- Existing Right of Way
- Existing Right of Way Railroad
- Existing Right of Way Not State Owned
- Existing Government Lot Line
- Existing Adjacent Block Lines
- Existing Adjacent Lot Lines
- Existing Adjacent Property Line
- Existing Adjacent Subdivision Lines
- Sight Distance Triangle Line
- Dimension Leader

Boundary Control

- Existing City Corporate Limits or Reservation Boundary
- Existing State or International Line
- Existing Township
- Existing County
- Existing Section Line
- Existing Quarter Section Line
- Existing Sixteenth Section Line
- Existing Centerline
- Tangent Line

Cross Sections and Typical

- Existing Ground
- Existing Topsoil (Cross Section View)
- Existing Ground Void (Not Surveyed)
- Existing Concrete
- Existing Aggregate (Cross Section View)
- Existing Curb and Gutter (Cross Section View)
- Existing Asphalt (Cross Section View)
- Existing Reinforcement Rebar

Geotechnical

- Geotextile Fabric Type D
- Geogrid
- Geotextile Fabric Type R
- Geotextile Fabric Type R1
- Geotextile Fabric Type RR
- Geotextile Fabric Type S

Countours

- Depression Contours
- Supplemental Contour

Profile

- Subgrade, Subcut or Ditch Grade
- Topsoil Profile

Striping

- Centerline Pavement Marking
- Barrier with Centerline Pavement Marking
- Barrier Pavement Marking
- Stripe 4 IN Dotted Extension White
- Stripe 8 IN Dotted Extension White
- Stripe 8 IN Lane Drop

Pavement Joints

- Doweled Joint
- Tie Bar 30 Inch 4 Foot Center to Center
- Tie Bar 18 Inch 3 Foot Center to Center
- Tie Bar at Random Spacing

Bridge Details

- Hidden Object
- Small Hidden Object
- Large Hidden Object
- Phantom Object
- Centerline Main
- Centerline
- Existing Ground (Details)
- Existing Conditions
- Sheet Piling

Erosion Control

- Limits of Const Transition Line
- Bale Check
- Rock Check
- Floating Silt Curtain
- Silt Fence
- Excavation Limits
- Fiber Rolls

Environmental

- Wetland Mitigation
- Existing Wetland Easement USFWS
- Existing Wetland Jurisdictional
- Existing Wetland
- Tree Row

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
09-23-16	Added and Revised Items, Organized by Functional Groups

This document was originally issued and sealed by
Roger Weigel,
 Registration Number
PE-2930,
 on **09/23/16** and the original document is stored at the
 North Dakota Department
 of Transportation

Symbols

	North Arrow (Half Scale)		Attenuation Device		Existing Railroad Battery Box		Existing Delineator Type E
	Truck Mounted Attenuator		Diamond Grade Delineator Type A		Existing Bush or Shrub		Existing EFB Misc
	Type I Barricade		Diamond Grade Delineator Type B		Existing Gas Cap or Stub		Existing Flashing Beacon
	Type II Barricade		Diamond Grade Delineator Type C		Existing Sanitary Cap or Stub		Existing Pipe Mounted Flasher
	Type III Barricade		Diamond Grade Delineator Type D		Existing Storm Drain Cap or Stub		Existing Pad Mounted Feed Point
	Catch Basin		Diamond Grade Delineator Type E		Existing Water Cap or Stub		Existing Pipe Mounted Feed Point with Pad
	Cairn or Stone Circle		Flexible Delineator		Existing Sanitary Cleanout		Existing Pole Mounted Feed Point
	Video Detection Camera		Flexible Delineator Type A		Existing Concrete Foundation		Existing Railroad Frog
	Storm Drain Cap or Stub		Flexible Delineator Type B		Existing Traffic Signal Controller		Existing Snow Gate 18
	Corrugated Metal End Section 18 Inch		Flexible Delineator Type C		Existing Pad Mounted Signal Controller		Existing Snow Gate 28
	Corrugated Metal End Section 24 Inch		Flexible Delineator Type D		Existing Sixteenth Section Corner		Existing Snow Gate 40
	Corrugated Metal End Section 30 Inch		Flexible Delineator Type E		Existing Quarter Section Corner		Existing Headwall
	Corrugated Metal End Section 36 Inch		Delineator Type A		Existing Section Corner		Existing Pedestrian Head with Number
	Corrugated Metal End Section 42 Inch		Delineator Type A Reset		Existing Railroad Crossbuck		Existing Signal Head
	Corrugated Metal End Section 48 Inch		Delineator Type B		Existing Satellite Dish		Existing Sprinkler Head
	Concrete Foundation		Delineator Type B Reset		Existing Fuel Dispensers		Existing Fire Hydrant
	Ground Connection Conductor		Delineator Type C		Existing Flexible Delineator Type A		Existing Catch Basin Drop Inlet
	Neutral Connection Conductor		Delineator Type D		Existing Flexible Delineator Type B		Existing Curb Inlet
	Phase 1 Connection Conductor		Delineator Type E		Existing Flexible Delineator Type C		Existing Manhole Inlet
	Phase 2 Connection Conductor		Delineator Drums		Existing Flexible Delineator Type D		Existing Junction Box
	Traffic Cone		Spot Elevation		Existing Flexible Delineator Type E		
	Signal Controller		Existing Access Control Arrow		Existing Delineator Type A		
	Pad Mounted Signal Controller		Existing Artifact		Existing Delineator Type B		
	Alignment Data Point		Existing Flashing Beacon		Existing Delineator Type C		
	Emergency Vehicle Detector		Existing Benchmark		Existing Delineator Type D		

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 07/01/14 and the original document is stored at the North Dakota Department of Transportation

Symbols
































































































	Existing Light Standard		Existing Manhole with Valve Water		Existing Telephone Pole		Existing Undefined Manhole
	Existing High Mast Light Standard 10 Luminaire		Existing Water Manhole		Existing Wood Pole		Existing Undefined Pull Box
	Existing High Mast Light Standard 3 Luminaire		Existing Mile Post Type A		Existing Post		Existing Undefined Pedestal
	Existing High Mast Light Standard 4 Luminaire		Existing Mile Post Type B		Existing Pedestrian Push Button Post		Existing Undefined Valve
	Existing High Mast Light Standard 5 Luminaire		Existing Mile Post Type C		Existing Control Point CP		Existing Undefined Pipe Vent
	Existing High Mast Light Standard 6 Luminaire		Existing Reference Marker		Existing Control Point GPS-RTK		Existing Gas Valve
	Existing High Mast Light Standard 7 Luminaire		Existing RW Marker		Existing Control Point TRI		Existing Water Valve
	Existing High Mast Light Standard 8 Luminaire		Existing Utility Marker		Existing Reference Marker Point NGS		Existing Fuel Pipe Vent
	Existing High Mast Light Standard 9 Luminaire		Iron Monument Found		Existing Pull Box		Existing Gas Pipe Vent
	Existing Overhead Sign Structure Load Center		Iron Pin R/W Monument		Existing Intelligent Transportation Pull Box		Existing Sanitary Pipe Vent
	Existing Luminaire		Existing Object Marker Type I		Existing Water Pump		Existing Storm Drain Pipe Vent
	Existing Light Standard Luminaire		Existing Object Marker Type II		Existing Slotted Reinforced Concrete Pipe		Existing Water Pipe Vent
	Existing Federal Mailbox		Existing Object Marker Type III		Existing RR Profile Spot		Existing Weather Station
	Existing Private Mailbox		Existing Electrical Pedestal		Existing Fuel Leak Sensors		Existing Ground Water Well Bore Hole
	Existing Meander Section Corner		Existing Telephone Pedestal		Existing Highway Sign		Existing Windmill or Tower
	Existing Meter		Existing Fiber Optic Telephone Pedestal		Existing Miscellaneous Spot		Existing Witness Corner
	Existing Electrical Manhole		Existing TV Pedestal		Existing Lighting Standard Pole		Flashing Beacon
	Existing Gas Manhole		Existing Fiber Optic TV Pedestal		Existing Traffic Signal Standard		Flagger
	Existing Sanitary Manhole		Existing Fuel Filler Pipes		Existing Transformer		Pipe Mounted Flasher
	Existing Sanitary Force Main Manhole		Existing Traverse PI Aerial Panel		Existing Large Evergreen Tree		Sanitary Force Main with Valve
	Existing Sanitary Manhole with Valve		Existing Pole		Existing Small Evergreen Tree		
	Existing Storm Drain Manhole		Existing Power Pole		Existing Large Tree		
	Existing Force Main Storm Drain Manhole		Existing Power Pole with Transformer		Existing Small Tree		
	Existing Force Main Storm Drain Manhole with Valve				Existing Tree Trunk		
	Existing Telephone Manhole				Existing Pad Mounted Traffic Signal Control Box		

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 07/01/14 and the original document is stored at the North Dakota Department of Transportation

Symbols

D-101-32








 Pad Mounted Feed Point  Pipe Mounted Feed Point with Pad  Pole Mounted Feed Point  Headwall  Double Headwall with Vegetation Barrier  Single Headwall with Vegetation Barrier  Pole Mounted Head  Sprinkler Head  Fire Hydrant  Inlet Type 1  Inlet Type 2  Double Inlet Type 2  Inlet Gate Type 2  Junction Box  High Mast Light Standard 10 Luminaire  High Mast Light Standard 3 Luminaire  High Mast Light Standard 4 Luminaire  High Mast Light Standard 5 Luminaire  High Mast Light Standard 6 Luminaire  High Mast Light Standard 7 Luminaire  High Mast Light Standard 8 Luminaire  High Mast Light Standard 9 Luminaire  Relocate Light Standard  Overhead Sign Structure Load Center  Light Standard 100 Watt High Pressure Sodium Vapor Luminaire	 Light Standard 1000 Watt High Pressure Sodium Vapor Luminaire  Light Standard 150 Watt High Pressure Sodium Vapor Luminaire  Light Standard 175 Watt High Pressure Sodium Vapor Luminaire  Light Standard 200 Watt High Pressure Sodium Vapor Luminaire  Light Standard 250 Watt High Pressure Sodium Vapor Luminaire  Light Standard 310 Watt High Pressure Sodium Vapor Luminaire  Light Standard 35 Watt High Pressure Sodium Vapor Luminaire  Light Standard 400 Watt High Pressure Sodium Vapor Luminaire  Light Standard 50 Watt High Pressure Sodium Vapor Luminaire  Light Standard 70 Watt High Pressure Sodium Vapor Luminaire  Light Standard 700 Watt High Pressure Sodium Vapor Luminaire  Manhole  Manhole 48 Inch  Sanitary Force Main Manhole  Sanitary Sewer Manhole  Storm Drain Manhole  Storm Drain Manhole with Inlet  Reset Mile Post  Mile Post Type A  Mile Post Type B  Mile Post Type C  Right of Way Marker  Tubular Marker  Alignment Monument  Iron Pin Reference Monument	 Object Marker Type I  Object Marker Type II  Object Marker Type III  Caution Mode Arrow Panel  Back to Back Vertical Panel Sign  Double Direction Arrow Panel  Left Directional Arrow Panel  Right Directional Arrow Panel  Sequencing Arrow Panel  Truck Mounted Arrow Panel  Power Pole  Wood Pole  Pedestrian Push Button Post  Property Corner  Pull Box  Intelligent Transportation Pull Box  Sanitary Pump  Storm Drain Pump  Reinforced Pavement  Reinforced Concrete End Section 15 Inch  Reinforced Concrete End Section 18 Inch  Reinforced Concrete End Section 24 Inch  Reinforced Concrete End Section 30 Inch  Reinforced Concrete End Section 36 Inch  Reinforced Concrete End Section 42 Inch	 Reinforced Concrete End Section 48 Inch  Reinforced Concrete End Section 54 Inch  Reset Right of Way Marker  Reset USGS Marker  Right of Way Markers  Riser 30 Inch  Continuous Split Barrel Sample  Flight Auger Sample  Split Barrel Sample  Thinwall Tube Sample  Highway Sign  SNOW GATE 18 FT  SNOW GATE 28 FT  SNOW GATE 40 FT  Standard Penetration Test  Transformer  Inclinometer Tube  Underdrain Cleanout  Excavation Unit  Water Valve
---	--	---	--

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by
Roger Weigel,
 Registration Number
PE-2930,
 on 07/01/14 and the original document is stored at the
 North Dakota Department
 of Transportation

BRIDGE APPROACH SLAB DRAINAGE DETAIL

D-255-1




NOTES:
 Don't place longitudinal seams along the channel bottom.
 Top seam must be minimum 0.5' above the channel bottom.




NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
11-23-10	
REVISIONS	
DATE	CHANGE
06-26-14	Changed standard drawing number from D-708-4 to D-255-1.
07-27-15	Changed installation details.

This document was originally issued and sealed by
 Roger Weigel
 Registration Number PE-2930,
 on 07/27/15 and the original document is stored at the North Dakota Department of Transportation




EROSION AND SILTATION CONTROL
EROSION CONTROL BLANKET INSTALLATION




NOTE:
If a Single Net Blanket is used the side with the netting should be on the top once the blanket is installed.



PIPE INLETS
INSTALLATION AT PIPE ENDS




3.8 staples per square yard
using 8-inch 11 gauge wire
"u" staples.



NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-03-13	
REVISIONS	
DATE	CHANGE
06-26-14	Changed standard drawing number from D-708-5 to D-255-2.
07-27-15	Changed installation details such as trench depth and overlap dimensions.


This document was originally issued and sealed by
Roger Weigel
Registration Number
PE-2930,
on 07/27/15 and the original document is stored at the
North Dakota Department
of Transportation

EROSION AND SILTATION CONTROLS - SILT FENCE




INSTALLATION DETAIL


Minimize disturbance of ground around trench and smooth surface after excavation to avoid concentrating flows. Compact to prevent undercutting flows.




TYPICAL ISOMETRIC



MACHINE SLICED SILT FENCE



SILT FENCE SUPPORTED




SILT FENCE UNSUPPORTED

- NOTES:
1. Install the ends of the silt fence to point slightly upslope to prevent sediment from flowing around the ends of the fence.
 2. Place splices outside low spots.
 3. Install silt fencing parallel to contour lines.
 4. Do not embed silt fence when placed in standing water.
 5. Silt fence material does not need to reach the top of woven wire support.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-03-13	
REVISIONS	
DATE	CHANGE
06-26-14	Standard drawing resulted from splitting standard D-708-2.
06-27-16	Revised details & added new ones.


This document was originally issued and sealed by
 Roger Weigel
 Registration Number
 PE- 2930,
 on 06/27/16 and the original document is stored at the
 North Dakota Department
 of Transportation

EROSION CONTROL
FIBER ROLL PLACEMENT DETAILS




*Optional Weir. Use in flat areas, such as the Red River Valley, where there is potential for water to back up on adjacent property. Lower fiber roll enough to prevent water from backing up on adjacent property. Do not use 20-inch fiber rolls in flat areas where there is potential for water to back up on adjacent property.


12 OR 20 INCH FIBER ROLL - DITCH BOTTOM




PLAN VIEW FOR SLOPE APPLICATION



PLAN VIEW FOR DITCH APPLICATION



Detail A
Fiber Roll Overlapping Staking Detail



Detail B
Fiber Roll Staking Detail

FIBER ROLL DIAMETER	NOMINAL STAKE SIZE	MINIMUM STAKE LENGTH	MINIMUM TRENCH DEPTH	MAXIMUM TRENCH DEPTH
6"	2" x 2"	18"	2"	2"
12"	2" x 2"	24"	2"	3"
20"	2" x 2"	36"	3"	5"

NOTE: Runoff must not be allowed to run under or around roll.


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
11-18-10	
REVISIONS	
DATE	CHANGE
06-10-13	Added plan view for ditch and slope application, Added table with values for stake and trench dimensions.
10-04-13	Revised fiber roll overlap detail.
06-26-14	Changed standard drawing number from D-708-7 to D-261-1

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 06/26/14 and the original document is stored at the North Dakota Department of Transportation


LONGITUDINAL JOINT DETAILS

D-550-2

UNTIED JOINTS




TIED JOINTS



Notes:


1. Provide hot poured joint sealant meeting the requirements of Section 826.02A.2 of the Standard Specifications.
2. Include all costs of the longitudinal joint and seal in the price bid for the PCC pavement.
3. Do not place tie bars within 18 inches of a transverse skewed joint.
4. Use Grade 40 steel for tie bars installed bent and later straightened.
5. Increase the tie bar spacing up to 10%, when necessary to facilitate construction.
6. Place tie Bars at a 48 inch maximum spacing.
7. A "Warp" joint is a sawed joint or a construction joint with a keyway.
8. A "Butt joint" is a construction joint with no keyway.




BAR SIZE
GRADE STEEL
DIST TO FREE EDGE
JOINT TYPE
PVTM THICKNESS

TIEBAR SPACINGS (In)

BAR SIZE GRADE STEEL DIST TO FREE EDGE JOINT TYPE PVTM THICKNESS		TIEBAR SPACINGS (In)																																																	
		# 3 BAR						# 4 BAR						# 5 BAR						# 6 BAR																															
		GRADE 40 24"				GRADE 60 30"				GRADE 40 24"				GRADE 60 36"				GRADE 40 30"				GRADE 60 42"				GRADE 40 36"				GRADE 60 48"																					
6"	WARP	48	48	39	24	48	48	44	35	29	25	48	42	35	30	26	48	48	48	45	39	28	26	48	48	47	41	30	27	48	48	48	48	45	41	48	48	48	48	48	43	39	48	48	48	48	48	48	48		
8"	WARP	48	39	29	24	48	48	44	35	29	25	48	42	35	30	26	48	48	48	45	39	28	26	48	48	47	41	30	27	48	48	48	48	45	41	48	48	48	48	48	43	39	48	48	48	48	48	48	48		
8 1/2"	WARP	48	37	28	48	48	42	33	28	24	48	39	33	28	24	48	48	48	42	37	27	24	48	48	44	38	28	25	48	48	48	48	42	38	48	48	48	48	47	40	37	48	48	48	48	48	48	48			
9"	WARP	48	35	26	48	48	39	31	26	47	37	31	26	48	48	47	40	35	25	48	48	47	40	35	25	48	48	42	36	26	24	48	48	48	48	40	36	48	48	48	48	44	38	35	48	48	48	48	48	48	48
9 1/2"	WARP	48	33	25	48	48	37	30	25	44	35	29	25	48	48	44	38	33	24	48	46	39	34	25	48	48	48	38	34	48	48	48	48	42	36	33	48	48	48	48	48	48	48								
10"	WARP	47	31	48	47	35	28	42	34	28	24	48	48	42	36	31	48	44	37	33	24	48	48	48	48	36	33	48	48	48	48	40	34	31	48	48	48	48	48	48	48										
10 1/2"	WARP	45	30	48	45	34	27	40	32	26	48	48	40	34	30	48	42	36	31	48	48	48	47	34	31	48	48	48	47	34	31	48	48	48	48	45	38	33	30	48	48	48	48	48	48	48					
11"	WARP	43	28	48	43	32	26	38	31	25	48	46	38	33	28	48	40	34	30	48	48	48	45	32	30	48	48	48	43	36	31	28	48	48	48	48	48	48	48	48											
11 1/2"	WARP	41	27	48	41	31	24	36	29	24	48	44	36	31	27	48	48	48	42	37	27	48	48	48	48	32	28	48	48	48	48	41	34	30	27	48	48	48	48	48	48	48	48								
12"	WARP	39	26	48	39	29	35	28	48	42	35	30	26	44	36	31	28	48	48	47	41	30	27	48	48	47	41	30	27	48	48	48	48	40	33	28	26	48	48	48	48	48	48	48	48						
12 1/2"	WARP	38	25	48	38	28	33	27	48	40	33	29	25	42	35	30	26	48	48	45	39	28	26	48	48	48	48	32	27	25	48	48	48	48	48	48	48	48													
13"	WARP	36	24	48	36	27	32	26	48	39	32	27	24	40	33	29	25	48	48	43	38	27	25	48	48	48	41	36	30	26	24	48	48	48	48	48	48	48	48												
13 1/2"	WARP	35	48	35	26	31	25	47	37	31	26	39	32	28	24	48	48	42	36	26	24	48	48	42	36	26	24	48	47	40	35	29	25	48	48	48	48	44	38	35											
14"	WARP	34	48	34	25	30	24	45	36	30	25	37	31	27	48	47	40	35	25	48	45	38	34	28	24	48	48	48	48	48	48	48	48																		
14 1/2"	WARP	32	48	32	24	29	43	35	29	25	36	30	26	48	45	39	34	24	48	43	37	32	27	48	43	37	32	27	48	48	48	48	48	48	48	48															
15"	WARP	31	47	31	28	42	33	28	24	35	29	25	48	44	37	33	24	48	42	36	31	26	48	42	36	31	26	48	48	48	48	48	48	48	48																




JOINT SEALER DETAILS




NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-15-2010	
REVISIONS	
DATE	CHANGE
10/23/2012	Expanded Tie Bar Table
03/16/2016	Updated Jt Details & notes

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 3/16/2016 and the original document is stored at the North Dakota Department of Transportation


TRANSVERSE CONSTRUCTION JOINT




PLAN VIEW




DETAIL "A"



DETAIL "B"




DEFORMED INSERT




DEFORMED SPLICER BAR


STAGES OF CONSTRUCTION



Stage 1



Stage 2



Stage 3



Notes

1. Saw and seal all construction joints.
2. Include all costs for transverse construction joints in the price bid for PCC pavement.
3. Do not saturate the subgrade during the sawing operation.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-15-2010	
REVISIONS	
DATE	CHANGE
3-16-16	Revised Joint Details and notes

This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930 , on 3/16/2016 and the original document is stored at the North Dakota Department of Transportation


ATTENUATION DEVICE



Outer Containers




Cones



Typical Assembly

Typical Module Construction Detail




Reflective Sheet Detail

Note:
The last attenuation device facing traffic shall have a reflective sheet, following the details above, directly applied to the outer container. The sheet may also be applied to a metallic sheet and attached to the container with approved fasteners. The reflective sheeting shall be Type IV as specified in NDDOT Standard Specifications.


(A) 3" orange sheeting shall be used for temporary installations, and 3" yellow sheeting shall be used for permanent installations.

	Fill Chart				
	Module Weights (LBS)				
Distance from top edge	200	400	700	1400	2100
	8 1/2"	5"	4"	3"	0"



Type B Layout

Note:
When attenuation devices are placed at piers offset from roadway, they shall be angled 10 degrees towards traffic.



Section A-A (Type B Layout)

Type B Attenuation Device											
Module Number	Dash Number										
	75	70	65	60	55	50	45	40	35	30	25
Module Weights (LBS)											
B1	2100										
B2	2100										
B3	2100	2100	2100	2100	2100	2100	2100	2100	2100		
B4	2100	2100	2100	2100	2100	2100	2100	2100	2100	2100	
B5	1400	1400	1400	1400	1400	1400	1400	1400	1400	1400	1400
B6	1400	1400	1400	1400	1400	1400	1400	1400	1400	1400	1400
B7	1400	1400	1400	1400	1400	1400	1400	1400	1400	1400	1400
B8	1400	1400	1400	1400	1400	1400	1400	1400	1400	1400	1400
B9	700	700	700	700	700	700	700	700	700	700	700
B10	700	700	700	700	700	700	700	700	700	700	700
B11	700	700	700	700	700	700	700	700	700	700	700
B12	700	700	700	700	700	700	700	700	700	700	700
B13	700	700	700	700	700	700	700	700	700	700	700
B14	400	400	400	400	400	400	400	400	400	400	400
B15	400	400	400	400	400	400	400	400	400	400	400
B16	200	200	200	200	200	200	200	200	200	200	200
Length (L)	34.2'	30.7'	30.7'	30.7'	30.7'	30.7'	30.7'	30.7'	30.7'	27.2'	27.2'
Module Weights (LBS)	Replacement Module										
	2100	1400	700	400	200	2100	1400	700	400	200	2100
2100	1	1	1	1	1	1	1	1	1	1	1
1400	1	1	1	1	1	1	1	1	1	1	1
700	2	2	2	2	2	2	2	2	2	2	2
400	1	1	1	1	1	1	1	1	1	1	1
200	2	2	2	1	1	1	1	1	1	1	1

Notes:

- Materials
 - A) Modules shall be manufactured from a frangible polyethylene material which will shatter upon impact.
 - B) Modules shall be filled with class 43 aggregate meeting the requirements for aggregate according to NDDOT Standard Specifications. The fill unit weight shall be at least 100 pounds per cubic foot. Fill left over winter shall have a moisture content of 2% or less.
- Modules
 - The modules shall be provided in two sizes to contain volumes of either 2, 4, 7, 14, or 21 cubic feet as a minimum.
 - A) The module for the 2, 4 or 7 cubic foot container shall consist of three components:
 - 1) A 14 C.F., yellow outer container.
 - 2) A black lid which locks securely over the top lip of the container.
 - 3) A cone-shaped supporting insert. The insert shall be varied to allow for the three sizes of modules and capable of supporting 200, 400, or 700 pounds of sand mass. The cone inserts shall be placed inside the 14 cubic foot container.
 - B) The module for the 21 cubic foot container shall consist of two components:
 - 1) A 36" height X 36" width yellow outer container.
 - 2) A black lid which locks securely over the top of the container.
- For temporary use: The modules shall be Energite or Fitch attenuation barrels manufactured by Energy Absorption Systems of Chicago, IL, TrafFix barrels manufactured by TrafFix Devices, Inc. of San Clemente, CA, or an approved equal. The attenuation devices may be placed on pallets to facilitate maintenance. Pallets shall have a maximum thickness of 3 1/2".
- For permanent use: Barrel Attenuation Device installations, the outer sand container portion of the modules shall consist of a one-piece container with separate detachable lid. The modules which meet these requirements are Energite attenuation barrels manufactured by Energy Absorption Systems of Chicago, IL, TrafFix barrels manufactured by TrafFix Devices, Inc. of San Clemente, CA, or an approved equal. Modules having outer sand containers assembled from multiple pieces shall not be accepted for permanent installations.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-25-12	
REVISIONS	
DATE	CHANGE
7-18-14	Revised sheeting in reflective sheet detail

This document was originally issued and sealed by
 Roger Weigel,
 Registration Number
 PE-2930,
 on 7/18/14 and the original document is stored at the North Dakota Department of Transportation

CONSTRUCTION SIGN DETAIL

D-704-5

SIGN NUMBER G20-10-108		STATION(S):		AREA: 36.0 Sq.Ft.					
WIDTH x HEIGHT 9'-0" x 4'-0"									
BORDER WIDTH 1.25" (inset 0.75")									
CORNER RADIUS 3"									
MOUNTING Ground									
BACKGROUND TYPE: IV Reflective									
COLOR: Fluorescent Orange									
LEGEND/BORDER TYPE: Non-Refl									
COLOR: Black									
SYMBOL	X					Y	WID	HT	ANGLE
	42.1					6.2	24	4	0

LETTER POSITION (X)																	LENGTH	SIZE	SERIES
C	O	N	S	T	R	U	C	T	E	D	B	Y					69.7	6	D 2000
19.2	24.5	30	35.1	39.7	44.3	49.4	54.8	59.7	64.3	69	73.1	79.1	83.7						
Y	O	U	R		C	O	M	P	A	N	Y		N	A	M	E	91.5	6	D 2000
8.3	14.2	19.8	25.3	29.4	35.4	40.7	46.2	52.4	56.8	62.8	67.8	72.9	78.9	83.9	89.9	96			
Y	O	U	R		T	O	W	N				N	D				64.6	6	D 2000
21.7	27.6	33.2	38.7	42.8	48.8	53.3	58.4	64.6	69.6	70.7	76.7	82.2							

Dimensions are in inches.tenths Letter locations are panel edge to lower left corner


Notes:

1. Sign shall be placed a distance of 1/2 A following the End Road Work (G20-2a-48) sign. There shall be a maximum of 2 signs per project.
2. Sign shall be post mounted.
3. Sign required on rural projects with a 30 day or longer duration and it is not required on seal coat projects or other short duration projects.
4. Sign shall not be placed in urban areas or within city limits.

Advance Warning Sign Spacing (A)			
Road Type	Distance between signs min. (ft)		
	A	B	C
Urban - Low Speed (30 mph or less)	150	150	150
Urban - Low Speed (over 30 to 40 mph)	280	280	280
Urban - High Speed (over 40 mph to 50 mph)	360	360	360
Rural - High Speed (over 50 mph to 65 mph)	720	720	720
Urban Expressway and Freeway (55 mph to 60 mph)	850	1350	2200
Rural Expressway and Freeway (70 mph to 75 mph)	1000	1500	2640
Interstate/4-Lane Divided (Maintenance and Surveying)	750	1000	1500


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION 8-22-12	
REVISIONS	
DATE	CHANGE
7-18-14	Revise sheeting to type IV

This document was originally issued and sealed by
Roger Weigel
 Registration Number
PE- 2930 ,
 on **7/18/14** and the original document is stored at the
 North Dakota Department
 of Transportation




Multi-Directional Slip Base Assembly

Perforated Tube



Top Post Receiver
Plate - ASTM A572 grade 50
Angle Receiver - 2 1/2"x2 1/2"x3/8" ASTM A36 structural angle



Bottom Soil Stub
Tube - 3"x3"x7 gauge ASTM A500 grade B tube
Stabilizing Wing - 7 gauge H.R.P.O. ASTM A1011
Plate - ASTM A572 grade 50


Notes:

1. Slip base bolts shall be torqued as specified by the manufacturer.
2. Anchor shall have a yield strength of 43.9 KSI and tensile strength of 59.3 KSI.
3. The 4" vertical clearance is required for the anchor or breakaway base. The 4"x60" measurement shall be made above and below post location and also back and ahead of the post.
4. When used in concrete sidewalk, anchor shall be same except without the wings.
5. Four post signs shall have over 7' between the first and the fourth posts.


Telescoping Perforated Tube						
Number of Posts	Post Size in.	Wall Thickness Gauge	Sleeve Size in.	Wall Thickness Gauge	Slip Base	Anchor Size without Slip Base in.
1	2	12			No	2 1/4
1	2 1/4	12			No	2 1/2
1	2 1/2	12			(A)	3
1	2 1/2	10			Yes	
1	2 1/4	12	2	12	Yes	
1	2 1/2	12	2 1/4	12	Yes	
2	2	12			No	2 1/4
2	2 1/4	12			No	2 1/2
2	2 1/2	12			Yes	
2	2 1/2	12			Yes	
2	2 1/4	10	2	12	Yes	
2	2 1/2	12	2 1/4	12	Yes	
3 & 4	2 1/2	12			Yes	
3 & 4	2 1/2	10			Yes	
3 & 4	2 1/2	12	2 1/4	12	Yes	
3 & 4	2 1/4	12	2	12	Yes	
3 & 4	2 1/2	10	2 3/16	10	Yes	

Properties of Telescoping Perforated Tube						
Tube Size in.	Wall Thickness in.	U.S. Standard Gauge	Weight per Foot lbs.	Moment of Inertia in. ⁴	Cross Sec. Area in. ²	Section Modulus in. ³
1 1/2 x 1 1/2	0.105	12	1.702	0.129	0.380	0.172
2 x 2	0.105	12	2.416	0.372	0.590	0.372
2 1/4 x 2 1/4	0.105	12	2.773	0.561	0.695	0.499
2 3/16 x 2 3/16	0.135	10	3.432	0.605	0.841	0.590
2 1/2 x 2 1/2	0.105	12	3.141	0.804	0.803	0.643
2 1/2 x 2 1/2	0.135	10	4.006	0.979	1.010	0.785


Top Post Receiver Data Table						
Square Post Sizes (B)	A	B	C	D	E	F
2 3/16"x10 ga.	1 9/64"	2 1/2"	3 1/32"	2 5/32"	1 33/64"	1 1/8"
2 1/2"x10 ga.	1 9/32"	2 1/2"	3 5/16"	5/8"	1 21/32"	1 3/4"



Anchor Unit and Post Assembly



Multi-Directional Slip Base Anchor Unit and Post Sleeve Assembly





Bolt Retainer for Base Connection
Bolt Retainer - 1/32" Reprocessed Teflon

- (A) The breakaway base is required when the support is placed in weak soils. The Engineer shall determine if the soils are weak.
(B) The 2 3/16"x10 ga. may be inserted into 2 1/2"x10 ga. for additional wind load.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
2-28-14	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 2/28/14 and the original document is stored at the North Dakota Department of Transportation

U-Channel Post




Breakaway U-Channel Detail Alternate A

A maximum of 2 posts shall be installed within 7'.




Retainer Strap Detail



Breakaway U-Channel Splice Detail Alternate B (2.5 and 3 lb/ft)

A maximum of 3 posts shall be installed within 7'.



Breakaway U-Channel Splice Detail Alternate C (2.5 and 3 lb/ft)

A maximum of 3 posts shall be installed within 7'.

Alternate A Steps of Installation:


1. a) Drive anchor unit to within 12" of ground level.
b) Proper assembly established by lining up the bottom hole of retainer strap with the 6th hole from the top of the anchor unit.
c) Assemble strap to back of anchor unit using 5/16"x2" bolt, lock washer and nut.
d) Rotate strap 90° to left.
2. a) Drive anchor unit to 4" above ground.
b) Rotate strap to vertical position.
3. a) Place 5/16"x2" bolt, lock washer and nut in bottom of sign post to facilitate alignment of sign post with proper hole in anchor unit.
b) Alternately tighten two connector bolts.
4. Complete assembly by tightening 5/16"x2" bolt (this fastens sign post to retainer strap).
5. The base post, strap and sign post shall be properly nested. Proper nesting occurs when all flat surfaces of the base post, strap, and sign post at the bolts have full contact across the entire width.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
2-28-14	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 2/28/14 and the original document is stored at the North Dakota Department of Transportation

CONSTRUCTION SIGN DETAILS
TERMINAL AND GUIDE SIGNS


D-704-9




G20-1-60
Legend: black (non-refl)
Background: orange




G20-1b-60
Legend: black (non-refl)
Background: orange




G20-2-48
Legend: black (non-refl)
Background: orange




G20-4b-36
Legend: black (non-refl)
Background: orange




G20-50a-72
Legend: black (non-refl)
Background: orange




G20-52a-72
Legend: black (non-refl)
Background: orange




G20-55-96
Legend: black (non-refl)
Background: orange




E5-1(L or R)-48
Legend: white
Background: green (orange optional)




M4-8-36
Legend: black (non-refl)
Background: orange




M4-9(L or R)-30 & M4-9-30
Legend: black (non-refl)
Background: orange




E5-1-48




G20-50a-72
G20-52a-72



M4-9(L or R)-30
Right or Left



M4-9(L or R)-30
Advanced Right or Left



M4-9-30
Straight

ARROW DETAILS


NOTES:

(A) Arrow may be right or left of the legend to indicate construction to the right or left.


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-13-13	
REVISIONS	
DATE	CHANGE
8-17-17	Added sign & background color

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 8/17/17 and the original document is stored at the North Dakota Department of Transportation


CONSTRUCTION SIGN DETAILS
REGULATORY SIGNS




R1-50P-24
Legend: black (non-refl)
Background: white




R11-3c-60
Legend: black (non-refl)
Background: white



R2-1aP-24
Legend: black (non-refl)
Background: white



R11-4a-60
Legend: black (non-refl)
Background: white




R11-2a-48
Legend: black (non-refl)
Background: white

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-13-13	
REVISIONS	
DATE	CHANGE
8-17-17	Revised sign number


This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930, on 8/17/17 and the original document is stored at the North Dakota Department of Transportation

CONSTRUCTION SIGN DETAILS
WARNING SIGNS




W5-8-48

Legend: black (non-refl)
Background: orange




W8-54-48

Legend: black (non-refl)
Background: orange




W20-51-48

Legend: black (non-refl)
Background: orange




W21-51-48

Legend: black (non-refl)
Background: orange




W5-9-48

Legend: black (non-refl)
Background: orange




W8-55-48

Legend: black (non-refl)
Background: orange




W20-52P-54

Legend: black (non-refl)
Background: orange




W22-8-48

Legend: black (non-refl)
Background: orange




W5-9-48

ARROW DETAILS




W8-53-48

Legend: black (non-refl)
Background: orange



W8-56-48

Legend: black (non-refl)
Background: orange



W21-50-48

Legend: black (non-refl)
Background: orange

WORD	LETTER SPACING
AHEAD	Standard
200 FT	Standard
350 FT	Standard
500 FT	Standard
1000 FT	Reduce 40%
1500 FT	Reduce 40%
1/2 MILE	Reduce 50%
1 MILE	Standard


* DISTANCE MESSAGES

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-13-13	
REVISIONS	
DATE	CHANGE
8-17-17	Updated sign number




This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 8/17/17 and the original document is stored at the North Dakota Department of Transportation

SHOULDER CLOSURE TAPERS

D-704-12



SHOULDER CLOSURE WITH LANE CLOSURE
(when shoulder is 8' or wider)



SHOULDER CLOSURE USED WITH LANE CLOSURE
(when shoulder is less than 8' wide)

PORTABLE TRAFFIC SIGNAL OR CHANGEABLE MESSAGE SIGN ON SHOULDER

KEY	
● Delineator Drum	∞ Sequencing Arrow Panel
• Message Display	↳ Portable Traffic Signal


Notes:

- S = Posted Speed Limit in mph
W = Width of offset in feet
L = Taper length in feet
L = $WS^2/60$ (40mph or less)
L = WS (45mph or more)
- If a shoulder taper is used, it should have a length of approximately $1/2L$. If a shoulder is used as a travel lane, a normal merging or shifting taper should be used.
- When paved shoulders of 8 foot width or more are closed, channelizing devices shall be used to close the shoulder in advance to delineate the beginning of the work space and direct vehicular traffic to remain within the traveled way.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-3-13	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel Registration Number PE-2930, on 10/3/13 and the original document is stored at the North Dakota Department of Transportation

BARRICADE AND CHANNELIZING DEVICE DETAILS




DELINEATOR DRUM

VERTICAL PANEL


The markings on drums shall be horizontal, circumferential, alternating orange and white retroreflective stripes 4" to 6" wide. Each drum shall have a minimum of two orange and two white stripes with the top stripe being orange. Any nonretroreflectORIZED spaces between the horizontal orange and white stripes shall not exceed 3" wide. Stripes shall not be placed on ribs or indentations in the drum. Drums shall have closed tops that will not allow collection of construction debris or other debris. Ballast shall not be placed on the top of a drum.

Markings for vertical panels shall be alternating orange and white retroreflective stripes, sloping downward in the direction vehicular traffic is to pass. Retroreflective sheeting shall be placed on both sides of panel and shall have a minimum of 270 square inches of retroreflective area facing vehicular traffic. Where the height of the retroreflective material on the vertical panel is 36 inches or more, a stripe width of 6 inches shall be used.




TRAFFIC CONE

RetroreflectORIZATION of cones more than 36" in height shall be provided by alternating orange and white retroreflective stripes. Each cone shall have a minimum of two orange and two white stripes with the top stripe being orange. Any nonretroreflectORIZED space between the orange and white stripes shall not exceed 3" wide.



TUBULAR MARKER


RetroreflectORIZATION of tubular markers more than 42" in height shall be provided by alternating four 4" to 6" wide orange and white stripes with the top stripe being orange.



FLEXIBLE DELINEATOR

INSTALLATION NOTES:


1. Drill installation holes to diameter and depth as required by manufacturer's specifications.
2. For removal, remove anchors and fill installation hole with an epoxy designed to bond to pavement surface.
3. In lieu of bolted down base, the contractor may use an 8" x 8" butyl pad or hot melt butyl. Butyl shall be removed as close as possible to pavement surface.



BARRICADE BLADE DETAIL

ELEVATION VIEW

BARRICADE ASSEMBLY DETAIL (Aluminum Barricade Rails)




ELEVATION VIEW


BARRICADE ASSEMBLY DETAIL (Wood or Plastic Rails)

SIDE VIEW

NOTE: Markings for barricades shall be alternating orange and white retroreflective stripes, sloping downward in the direction traffic is to pass. Retroreflective sheeting shall be placed on both sides of the rails and shall have a minimum of 270 square inches of visible retroreflective area facing vehicular traffic. When the barricade length is less than 36", the rail stripe width shall be 4".




TYPE I BARRICADE




TYPE II BARRICADE

BARRICADE RAIL DETAILS




TYPE III BARRICADE




REFLECTOR DETAIL

DELINEATORS



SECTION VIEW



MOUNTING DETAIL

MINIMUM BALLAST (For each side of barricade support)

Without Sign	4 - 25 lb sandbags
With Sign	6 - 25 lb sandbags


Note: The number of sandbags are based on a wind speed of 55 MPH. The sandbags are assumed to be placed at or near the ends of the skids.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-3-13	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 10/3/13 and the original document is stored at the North Dakota Department of Transportation

CONSTRUCTION SIGN PUNCHING AND MOUNTING DETAILS


Note: Signs placed in sections with curb shall have a minimum horizontal clearance of 2' from the face of the curb to the near edge of the sign.




TYPICAL SECTION
(48" x 48" diamond warning sign shown)




24" x 24" ROUTE MARKER ASSEMBLY




36" x 36" ROUTE MARKER ASSEMBLY




18" x 18" DIAMOND SIGN




48" x 48" DIAMOND SIGN
(with 30" x 30" secondary sign)




48" x 48" DIAMOND SIGN
(with 30" x 24" secondary sign)




R1-2-60 - YIELD SIGN




W14-3-64 - PENNANT SIGN




R1-1-48 - STOP SIGN
(with R6-1-54 sign as required)




R1-1-48 - STOP SIGN
(with R1-50-24 sign as required)




48" x 48" SIGN
(with R6-1-54 sign as required)




48" x 48" SIGN
(with R2-1a-24 sign as required)




24" x 36" SIGN




30" x 24" SIGN




108" x 48" SIGN




96" x 48" SIGN




72" x 36" SIGN




72" x 24" SIGN




60" x 24" SIGN



48" x 24" SIGN



PORTABLE SIGN SUPPORT
LOW-MOUNTING HEIGHT



PORTABLE SIGN SUPPORT
HIGH-MOUNTING HEIGHT

NOTES:

- Sign Supports:** Supports shall be galvanized or painted. Minimum post sizes are 2.5 lb/ft u-channel or 2" x 2" x 12 gauge steel perforated tube, except where noted. When installing signs on u-channel, the minimum post size for assemblies containing a secondary sign is 3.0 lb/ft. Post sizes are based on a wind speed of 55 MPH.

Signs over 50 square feet should be installed on 2 1/2" x 2 1/2" perforated tube supports as a minimum.

Guy wires shall not be attached to sign supports. Wind beams may be attached to u-posts behind the sign panels.
- Sign Panels:** Provide sign panels made of 0.100" aluminum, 1/2" plywood, or other approved material, except where noted. All holes to be punched round for 3/8" bolts.
- Alternate Messages:** The signs that have alternate messages may have these alternate messages placed on a reflectorized plate (without a border) and installed and removed as required. (i.e. "Left" and "Right" message on a lane closure sign)
- Route Marker Auxiliary Signs:** Provide route marker auxiliary signs, such as the cardinal direction and directional arrows, with a background and legend that match the route marker they are used with:

Interstate - white legend on blue background
Interstate Business Loop - white legend on green background
US and State - black legend on white background
County - yellow legend on blue background
- Vertical Clearance:** Install signs with a vertical clearance of 5'-0" (see TYPICAL SECTION.) In areas where parking or pedestrian movements are likely or the view of the sign may be obstructed, install signs with a vertical clearance of 7'-0" from the top of the curb or from the near edge of the driving lane in absence of a curb.

The vertical clearance to secondary signs is 1'-0" less than the vertical clearance as stated above.

Large signs having an area exceeding 50 square feet shall have a minimum clearance of 7'-0" from the ground at the post.
- Portable Signs:** Provide portable signs that meet the vertical clearance as stated above. Use portable signs when it is necessary to place signs within the pavement surface.

When portable signs are used for 5 days or less, low-mounting height (minimum 12" vertical clearance) sign supports may be used as long as the view of the sign is not obstructed. Time delays caused by unforeseen circumstances, such as equipment breakdown, rain, subgrade failures, etc., will not accrue towards the 5 day period. The R9-8 through R9-11a series, W1-5 through W1-8 series, M4-10, and E5-1 may be used for longer than 5 days.

Signs mounted to the portable sign supports shown in the LOW-MOUNTING HEIGHT and HIGH-MOUNTING HEIGHT Details shall have a maximum surface area of 16 square feet.

MINIMUM BALLAST
(For each side of sign support base)

Sign Panel Mounting Height (ft)	Number of 25 lb sandbags for 4' x 4' sign panel
1'	6
5'	8
7'	10

Note: The number of sandbags are based on a wind speed of 55 MPH. The sandbags are assumed to be placed at or near the ends of the skids.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-4-13	
REVISIONS	
DATE	CHANGE
11-14-13	Revised Note 6.

This document was originally issued and sealed by
Roger Weigel,
Registration Number
PE-2930,
on 11/14/13 and the original document is stored at the North Dakota Department of Transportation

ROAD CLOSURE LAYOUTS



Notes

- Variables
 - S = Numerical value of speed limit or 85th percentile.
 - W = The width of taper in feet.
 - L = Minimum length of taper, S x W for freeways, expressways, and other roads with speeds of 45 mph or greater, or W x S²/60 for urban, residential, and other streets with speeds of 40 mph or less.
- Place barricades on moveable assemblies and signs on portable assemblies when located on roadway.
- Place delineator drums, barricades or cones for tapering traffic at dimension "S" and for tangents space at 2 times dimension "S".
- Place Sequencing Arrow Panels at the beginning of the taper when possible. Where shoulder width does not provide sufficient room, move the panel closer to the work area and place on roadway surface. See Shoulder Closure Standard Drawing.
 - Use Type A on roadways with slow moving traffic speeds and low volume (25 mph or less and 750 ADT or less).
 - Use Type B on roadways with moderate traffic speeds and volumes (40 mph or less and 5000 ADT or less).
 - Use Type C on roadways with high traffic speeds and volumes (over 40 mph or over 5000 ADT).
- Re-establish speed. Determine exact speed limit in the field, dependent on location and conditions.
- Determine the reduced speed limit based on the in-place speed limit before construction. Where speed reductions exceed 30 mph, install a second speed limit sign with the desired speed reduction (not to exceed 30 mph.) Place the second speed limit sign at 1/2 B.
- Use when work area is 1 mile or longer.
- Install flags on warning signs in urban areas when signs are not portable. Mount 24 inch square flags perpendicular to the edges of the sign, and at such a distance above the edge that the flag does not touch the sign when limp.
- Cover existing speed limit signs within reduced speed zones.
- Where necessary, engineer will determine safe speed.
- As an option, use portable sign supports in lieu of post mounted signs in accordance with NDDOT Standard Specifications.
- Sign G20-55-96 is not required if this standard is part of other traffic control, or the work is less than 15 days.
- Recommend using 40 mph speed limit in vicinity of workers, unless location and conditions dictate otherwise.

Road Type	Distance Between Signs Min. (ft)		
	A	B	C
Urban - Low Speed (30 mph or less)	150	150	150
Urban - Low Speed (over 30 to 40 mph)	280	280	280
Urban - High Speed (over 40 mph to 50 mph)	360	360	360
Rural - High Speed (over 50 mph to 65 mph)	720	720	720
Urban Expressway and Freeway (55 mph to 60 mph)	850	1350	2200
Rural Expressway and Freeway (70 mph to 75 mph)	1000	1500	2640
Interstate/4-Lane Divided (Maintenance and Surveying)	750	1000	1500

KEY	
	Type III barricade
	Work area
	Sign
	Flagger
	Delineator drum
	Sequencing arrow panel
	Tubular markers
	Vertical panels back to back

Speed (mph)	Length Min (feet)
20	115
25	155
30	200
35	250
40	305
45	360
50	425
55	495
60	570
65	645
70	730
75	820




NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-27-13	
REVISIONS	
DATE	CHANGE
8-17-17	Updated notes & Speed Limit signs

This document was originally issued and sealed by Roger Weigel Registration Number PE-2930, on 08/17/17 and the original document is stored at the North Dakota Department of Transportation

SIGN LAYOUT FOR ONE LANE CLOSURE TWO LANE ROADWAY

D-704-17



SPEED LIMIT ENFORCED
MINIMUM FEE \$80
WHEN WORKERS PRESENT
G20-55-96
Post mounted

SPEED LIMIT ENFORCED
MINIMUM FEE \$80
WHEN WORKERS PRESENT
G20-55-96
Post mounted

KEY

- Delineator drum
- Sign
- Type III barricade
- Work area
- Flagger




- Notes**
- Place barricades on moveable assemblies and signs on portable assemblies when located on roadway.
 - Remove existing striping as required. Use back to back delineators when inslope is 4:1 or flatter and roadway alignment is visible to approaching vehicles. Place back to back vertical panels when roadways have steep slopes and alignment is not visible to approaching traffic.
 - Re-establish speed limit. Determine exact speed limit in the field, dependent on location and conditions.
 - Determine the reduced speed limit based on the in-place speed limit before construction. Where speed reductions exceed 30 MPH, install a second speed limit sign with the desired speed reduction (not to exceed 30 MPH.) Place the second speed limit sign at 1/2 B.
 - Install flags on warning signs in urban areas when signs are not portable. Mount 24 inch square flags perpendicular to the edges of the sign, and at such a distance above the edge that the flag does not touch the sign when limp.
 - As an option, use portable sign supports in lieu of post mounted signs in accordance with NDDOT Standard Specifications.
 - Cover existing speed limit signs within a reduced speed zone.
 - Sign G20-55-96 is not required if layout is part of other traffic control or if work is less than 15 days.
 - Recommend using 40 mph speed limit in vicinity of workers, unless location and conditions dictate otherwise.

ADVANCE WARNING SIGN SPACING			
Road Type	Distance Between Signs Min. (ft)		
	A	B	C
Urban - Low Speed (30 mph or less)	150	150	150
Urban - Low Speed (over 30 to 40 mph)	280	280	280
Urban - High Speed (over 40 mph to 50 mph)	360	360	360
Rural - High Speed (over 50 mph to 65 mph)	720	720	720
Urban Expressway and Freeway (55 mph to 60 mph)	850	1350	2200
Rural Expressway and Freeway (70 mph to 75 mph)	1000	1500	2640
Interstate/4-Lane Divided (Maintenance and Surveying)	750	1000	1500

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-27-13	
REVISIONS	
DATE	CHANGE
8-17-17	Note update & sign numbers

This document was originally issued and sealed by
Roger Weigel
 Registration Number
PE-2930,
 on **08/17/17** and the original document is stored at the North Dakota Department of Transportation

DETOUR AND ROADWAY DIVERSION SIGN LAYOUTS



KEY

- Type III barricade
- Work area
- Sign
- Vertical panels back to back
- Delineator drum

- Notes**
- Variables
S=Numerical value of speed limit or 85th percentile. W=The width of taper.
L=Minimum length of taper, or S x W for freeways, expressways, and all other roads with speeds of 45 mph or greater, or W x S² / 60 for urban, residential, and other streets with speeds of 40 mph or less.
 - Place barricades on moveable assemblies and signs on portable assemblies when on roadway.
 - Space delineator drums and vertical panels at dimension "S" for tapering traffic. Space delineator drums, tubular markers and vertical panels at 2 times "S" for tangents.
 - Determine the reduced speed limit based on the in place speed limit before construction. Where speed limits exceed 30 MPH, install a second speed limit sign with the desired speed reduction (not to exceed 30 mph.) Place the second speed limit sign at 1/2 B.
 - Install flags on warning signs in urban areas when signs are not portable. Mount 24 inches square flags perpendicular to the edges of the sign, and at such a distance above the edge that the flag does not touch the sign when limp.
 - Cover existing speed limit signs within a reduced speed limit zone.
 - Covered (when approved by engineer) or obliterated pavement marking measured as Obliteration of Pavement Marking.
 - As an option, use portable sign supports in lieu of post mounted signs in accordance with NDDOT Standard Specifications.
 - If the tangent between tapers is less than 600', as an option, use sign W24-1-48 in place of double reverse curve signs.
 - Recommend using 40 mph speed limit in vicinity of workers, unless location and conditions dictate otherwise.
 - Re-establish speed limit. Determine exact speed limit in the field, dependent on location and conditions.

Use layout when work is less than 5 days or is within a project.

ADVANCE WARNING SIGN SPACING

Road Type	Distance Between Signs Min. (ft)		
	A	B	C
Urban - Low Speed (30 mph or less)	150	150	150
Urban - Low Speed (over 30 to 40 mph)	280	280	280
Urban - High Speed (over 40 mph to 50 mph)	360	360	360
Rural - High Speed (over 50 mph to 65 mph)	720	720	720
Urban Expressway and Freeway (55 mph to 60 mph)	850	1350	2200
Rural Expressway and Freeway (70 mph to 75 mph)	1000	1500	2640
Interstate/4-Lane Divided (Maintenance and Surveying)	750	1000	1500

NORTH DAKOTA
DEPARTMENT OF TRANSPORTATION

9-27-13

REVISIONS


DATE	CHANGE
8-17-17	Updated notes. Added speed limit.

This document was originally issued and sealed by
Roger Weigel
Registration Number
PE-2930,
on **08/17/17** and the original document is stored at the North Dakota Department of Transportation

CONSTRUCTION TRUCK AND TEMPORARY DETOUR LAYOUTS

KEY

- Type III barricade
- Sign
- Work area
- Flagger




- Notes
- Place barricades on a moveable assemblies and signs on portable assemblies when located on roadway.
 - Where necessary, safe speed to be determined by the Engineer.
 - Determine the reduced speed limit based on the in-place speed limit before construction. Where speed reductions exceed 30 mph, install a second speed limit sign with the desired speed reduction (not to exceed 30 mph.) Place the second speed limit sign at 1/2 B.
 - Install flags on warning signs in urban areas when signs are not portable. Mount 24 inch square flags perpendicular to the edges of the sign, and at such a distance above the edge that the flag does not touch the sign when limp.
 - Cover existing speed limit signs within a reduced speed zone.
 - Covered (when approved by engineer) or obliterated pavement marking measured as Obliteration of Pavement Marking.
 - As an option, use portable sign supports in lieu of post mounted signs in accordance with NDDOT Standard Specifications.
 - Install sign G20-1b-60 when work is suspended for winter.
 - If existing stop sign is in place, a 48" stop sign is not required.
 - Sign G20-55-96 is not required if layout is part of other traffic control or if work is less than 15 days.
 - Recommend using 40 mph speed limit in vicinity of workers, unless location and conditions dictate otherwise.

Road Type	ADVANCE WARNING SIGN SPACING		
	Distance Between Signs Min. (ft)		
	A	B	C
Urban - Low Speed (30 mph or less)	150	150	150
Urban - Low Speed (over 30 to 40mph)	280	280	280
Urban - High Speed (over 40 mph to 50 mph)	360	360	360
Rural - High Speed (over 50 mph to 65 mph)	720	720	720
Urban Expressway and Freeway (55 mph to 60 mph)	850	1350	2200
Rural Expressway and Freeway (70 mph to 75 mph)	1000	1500	2640
Interstate/4-Lane Divided (Maintenance and Surveying)	750	1000	1500


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-27-13	
REVISIONS	
DATE	CHANGE
8-17-17	Update notes & sign numbers

This document was originally issued and sealed by Roger Weigel Registration Number PE-2930, on 08/17/17 and the original document is stored at the North Dakota Department of Transportation


MISCELLANEOUS SIGN LAYOUTS




TYPE Y
Where haul road crosses highway outside major work area.




TYPE Z
Where speed zone is needed




TYPE AA
Where survey crew is used




TYPE BB
Within major work area where sign conditions exist




TYPE CC
Where sign conditions exist




TYPE DD
Where sign conditions exist




TYPE EE
Where sign conditions exist




TYPE FF
Where sign conditions exist



TYPE GG
Where elevation difference exists between lanes



TYPE JJ
For break in pavement. Install signs when conditions exist and remove when not applicable.



TYPE KK
At major intersections within pilot car control area

- Notes**
1. Re-establish speed limit. Determine exact speed limit in the field, dependent on location and conditions.
 2. Determine reduced speed limit based on in-place speed limit before construction. Where speed reductions exceed 30 mph, install a second speed limit sign with the desired speed reduction (not to exceed 30 mph.) Place the second speed limit sign at 1/2B.
 3. Install flags on warning signs in urban areas when signs are not portable. Mount 24 inch square flags perpendicular to the edges of the sign, and at such a distance above the edge that the flag does not touch the sign when limp.
 4. Cover existing speed limit signs within reduced speed zones.
 5. As an option, use portable sign supports in lieu of post mounted signs in accordance with NDDOT Standard Specifications.
 6. Sign G20-55-96 is not required if this standard is part of other traffic control layouts, or work is less than 15 days.
 7. When pilot car operation is used, place sign G20-4b-36 "Wait For Pilot Car" at major intersections within pilot car control area.
 8. Recommend 40 mph speed limit in vicinity of workers, unless location and conditions dictate otherwise.

ADVANCE WARNING SIGN SPACING			
Road Type	Distance Between Signs Min. (ft)		
	A	B	C
Urban - Low Speed (30 mph or less)	150	150	150
Urban - Low Speed (over 30 to 40 mph)	280	280	280
Urban - High Speed (over 40 mph to 50 mph)	360	360	360
Rural - High Speed (over 50 mph to 65 mph)	720	720	720
Urban Expressway and Freeway (55 mph to 60 mph)	850	1350	2200
Rural Expressway and Freeway (70 mph to 75 mph)	1000	1500	2640
Interstate/4-Lane Divided (Maintenance and Surveying)	750	1000	1500

Longitudinal Buffer Space	
*Speed (mph)	Length Min (feet)
20	115
25	155
30	200
35	250
40	305
45	360
50	425
55	495
60	570
65	645
70	730
75	820

* Posted speed, off-peak 85th percentile speed prior to work starting, or the anticipated operating speed in mph.

KEY

Sign Flagger Cones







S = Numerical value of speed limit or 85th percentile.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-27-13	
REVISIONS	
DATE	CHANGE
8-17-17	Added speed limit signs. Updated notes & sign numbers


This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 08/17/17 and the original document is stored at the North Dakota Department of Transportation

TRAFFIC CONTROL PLAN FOR MOVING OPERATIONS

D-704-27



Sign Details



Notes

- If the contractor chooses to place more vehicles in the convoy than are shown, these vehicles shall have the truck mounted attenuator and shall be at the contractor's expense.
- Shadow and work vehicles shall display yellow rotating beacons or strobe lights unless otherwise stated elsewhere in the plans.
- Flashing arrow panels shall be Type B or Type C. The panel operation shall be controlled from inside the vehicle.
- Each vehicle shall have two-way electronic communication capability.
- When work convoys must change lanes, shadow vehicle 1 should change lanes first to shadow other convoy vehicles.
- Vehicle spacing between the shadow vehicle 1 and shadow vehicle 2 will vary depending on sight distance restrictions. Motorists approaching the work convoy should be able to see the trail vehicle in time to slow down and/or change lanes as they approach the shadow vehicle.
- Sign Colors
Letters = Black
Border = Black
Background = Orange
- Shadow vehicle 2 may be used as the paint tender vehicle.
- Sign CW21-10A shall only be used during a painting operation.
- On two lane - two way roadways, the work and shadow vehicles should pull over periodically to allow motor vehicle traffic to pass.


KEY

- Sign
- Truck mounted attenuator
- Flashing arrow panels:
 - Right directional
 - Left directional
 - Double arrow directional
 - Caution Mode

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-27-13	
REVISIONS	
DATE	CHANGE
6-18-14	Removed shadow vehicle 2 on two lane roadways


This document was originally issued and sealed by
 Roger Weigel
 Registration Number
 PE-2930,
 on 06/18/14 and the original document is stored at the
 North Dakota Department
 of Transportation

SIGN LAYOUT FOR ONE LANE CLOSURE INTERSTATE SYSTEM



KEY

- Type I barricade
- Type II barricade
- Type III barricade
- Sign
- Delineator drum
- Work area
- Flagger
- Sequencing arrow panel
- Tubular markers





LEFT LANE CLOSED WORKERS IN WORK AREA

Longitudinal Buffer Space	
Speed (mph)*	Length Min (feet)
20	115
25	155
30	200
35	250
40	305
45	360
50	425
55	495
60	570
65	645
70	730
75	820

*Posted speed, off-peak 85th percentile speed prior to work starting, or the anticipated operating speed in mph.

- Notes:
1. Install advance signs for flagging when flaggers are flagging.
 2. Move the advanced flagger sign and the speed limit signs as the work area moves through the construction zone. When the work area is not visible from the flagger, move the flagger station so the work area is visible. Space the 40 mph speed limit sign at 1/2 A in advance of the flagger sign and move the 65 mph speed limit sign. Cover or remove the 40 mph speed limit and Minimum Fee \$80 signs and the 65 mph speed limit sign upon completion of the work day or when workers are not present.
 3. RAMPS: When the work area encompasses an entrance ramp, install a 40 mph speed limit sign on the ramp and cover any existing yield sign. Install new yield sign as necessary. Remove the ramp speed limit sign when the main line 40 mph speed zone is moved past the ramp.
 4. Variables:
 S= Numerical value of speed limit or 85th percentile
 W= The width of taper.
 L= Minimum length of taper, or SxW for freeways, expressways, and all other roads with speeds of 45 mph or greater, or WxSxS/60 for urban, residential, and other streets with speeds of 40 mph or less.
 S= Space delineator drums for tapering traffic at the dimension "S". Space tubular markers used for tangents at 2 times dimension "S".
 5. Space delineator drums for tapering traffic at the dimension "S". Space tubular markers used for tangents at 2 times dimension "S".
 6. Place sequencing arrow panels at the beginning of the taper when possible. Where shoulder width does not provide sufficient room, move the panel closer to the work area and place on the roadway surface.
 Use Type C on roadways with high traffic speeds and volumes (over 40 mph or 5000 ADT or greater).
 7. Re-establish the speed limit. Determine the exact speed limit in the field, dependent on location and conditions.
 8. Cover existing speed limit signs within a reduced speed zone.
 9. Upon approval, the Engineer will measure obliterated or covered pavement marking as Obliteration of Pavement Marking.
 10. Install flags on warning signs in urban areas when signs are not portable. Mount 24 inch square flags perpendicular to the edges of the diamond sign, and at such a distance above the edge that the flag does not touch the sign when limp.
 11. Determine the reduced speed limit dependent on the in place speed limit before construction. When speed limits are to be reduced more than 30 mph, install a second speed limit sign with the desired speed reduction (not to exceed 30 mph). Place the second speed limit sign at 1/2 B.
 12. As an option, use portable sign supports in lieu of post mounted signs in accordance with NDDOT Standard Specifications.
 13. Sign G20-55-96 is not required if this standard is part of other traffic control, or the work is less than 15 days.

ADVANCE WARNING SIGN SPACING			
Road Type	Distance Between Signs Min. (ft)		
	A	B	C
Rural - High Speed (over 50 mph to 65 mph)	720	720	720
Urban Expressway and Freeway (55 mph to 60 mph)	850	1350	2200
Rural Expressway and Freeway (70 mph to 75 mph)	1000	1500	2640
Interstate/4-Lane Divided (Maintenance and Surveying)	750	1000	1500



RIGHT LANE CLOSED WORKERS IN WORK AREA

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-7-2012	
REVISIONS	
DATE	CHANGE
6/23/2014	Revised Note 12
3/15/2016	Removed Do Not Pass signs and updated notes
8/17/2017	Moved speed signs. Added note


This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 08/17/17 and the original document is stored at the North Dakota Department of Transportation

TRAFFIC CONTROL SYSTEM MEDIAN CROSSOVER (800 FT TRANSITION) 55 MPH SPEED LIMIT OR GREATER

ADVANCE WARNING SIGN SPACING

Road Type	Minimum Distance Between Signs (ft)		
	A	B	C
Rural - High Speed (over 50 mph to 65 mph)	720	720	720
Urban Expressway and Freeway (55 mph to 60 mph)	850	1,350	2,200
Rural Expressway and Freeway (70 mph to 75 mph)	1,000	1,500	2,640
Interstate/4-Lane Divided (Maintenance and Surveying)	750	1,000	1,500

LEGEND
 E Obliteration of pavement marking (10' line, 30' skip, centerline)
 F Obliteration of pavement marking (edge lines)
 G Raised pavement markers (white) @ 5' centers
 H Raised pavement markers (yellow) @ 5' centers
 J Drums spaced @ "S" centers
 K Drums spaced @ 40' centers



*Not required for projects on roadways with 55 mph existing speed limit.

SPEED LIMIT SIGNING

ROADWAY EXISTING SPEED LIMIT	SPEED LIMIT TO BE USED XX	YY
55	50	55
60	50	60
65	55	65
70	60	70
75	65	75




CROSSOVER QUANTITY SUMMARY

	ROADWAY EXISTING SPEED LIMIT				
	55 MPH	60 MPH	65 MPH	70 MPH	75 MPH
TYPE III BARRICADES	3 Each	3 Each	3 Each	3 Each	3 Each
FLASHING BEACON	1 Each	1 Each	1 Each	1 Each	1 Each
DELINEATOR DRUMS	25 Each	25 Each	25 Each	25 Each	25 Each
SEQUENCING ARROW PANEL TYPE C-CROSSOVER	1 Each	1 Each	1 Each	1 Each	1 Each
PORTABLE PRECAST CONCRETE MEDIAN BARRIER	See "PRECAST CONCRETE MEDIAN BARRIER TABLE"				
ATTENUATION DEVICES	1-Type B-55	1-Type B-60	1-Type B-65	1-Type B-70	1-Type B-75
RAISED PAVEMENT MARKERS (YELLOW)	151 Each	151 Each	151 Each	151 Each	151 Each
RAISED PAVEMENT MARKERS (WHITE)	351 Each	369 Each	387 Each	405 Each	423 Each
OBLITERATION OF PAVEMENT MARKING	310 SF	318 SF	325 SF	338 SF	346 SF

PRECAST CONCRETE MEDIAN BARRIER TABLE

Roadway ϕ to roadway ϕ	Number	Median barrier length
75'	48	480'
84'	44	440'
104'	43	430'

- Notes:**
- Variables:
 S=Numerical value of posted speed limit, off-peak 85th percentile speed prior to work starting, or anticipated operating speed in MPH.
 W=Width of offset in feet
 L=Taper length in feet. Speeds 45 mph or greater L=WS.
 - Place signs and barricades on the roadway on moveable assemblies. Mount signs on barricades with the sign bottom on the top of the top barricade bar.
 - Install signs R4-1-48, W6-3-48, and W20-52P-54 at one mile increments and after each interchange.
 - Place the speed limit sign only if the crossover is more than 1 mile from an interchange exit ramp.
 - Place Sequencing Arrow Panels at the beginning of the taper when possible. Where shoulder width does not provide sufficient room, move the panel closer to the work area and place on the roadway surface. Use Type C on roadways with high traffic speeds and volumes (over 40 mph or 5000 ADT or greater)
 - Cover existing speed limit signs within a reduced speed zone.
 - Upon approval, the Engineer will measure obliterated or covered pavement marking as Obliteration of Pavement Marking.
 - As an option, use portable sign supports in lieu of post mounted signs in accordance with NDDOT Standard Specifications.
 - Reduce speed when placing traffic control devices. Place "Minimum Fee \$80" signs below speed limit signs in reduced speed areas. Place "Work Zone Speed Limit Enforced" sign in advance of the project at the time traffic control devices are installed.
 - Determine proper size, waterproof junction box, and attach to skid or vertical brace assembly.



NORTH DAKOTA
DEPARTMENT OF TRANSPORTATION

9-7-2012


REVISIONS

DATE	CHANGE
6/23/2014	Revised Note 8
3/15/2016	Removed Do Not Pass sign and updated notes
11/14/2016	Revised Attenuation width
8/17/2017	Termination area and quantities Updated note & quantities

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 08/17/17 and the original document is stored at the North Dakota Department of Transportation

TRAFFIC CONTROL SYSTEM
 MEDIAN CROSSOVER (800 FT TRANSITION)
 55 MPH SPEED LIMIT OR GREATER

*Not required for projects on roadways with 55 mph existing speed limit.



ADVANCE WARNING SIGN SPACING

ROAD TYPE	Minimum Distance Between Signs (ft)		
	A	B	C
Rural - High Speed (over 50 mph to 65 mph)	720	720	720
Urban Expressway and Freeway (55 mph to 60 mph)	850	1,350	2,200
Rural Expressway and Freeway (70 mph to 75 mph)	1,000	1,500	2,640
Interstate/4-Lane Divided (Maintenance and Surveying)	750	1,000	1,500

PRECAST CONCRETE MEDIAN BARRIER TABLE

Roadway ϕ to roadway ϕ	Number-median barrier length
75'	37 - 370'
84'	36 - 360'
104'	36 - 360'

ROADWAY EXISTING SPEED LIMIT TO BE USED

SPEED LIMIT	XX	YY
55	50	55
60	50	60
65	55	65
70	60	70
75	65	75




- Notes:
- Variables:
 S= Numerical value of posted speed limit, off-peak 85th percentile speed prior to work starting, or anticipated operating speed in MPH.
 W= Width of offset in feet
 L= Taper length in feet. Speeds 45 mph or greater L=WS.
 - Place signs and barricades on the roadway on moveable assemblies. Mount signs on barricades with the sign bottom on the top of the top barricade bar.
 - Install signs R4-1-48, W6-3-48, and W20-52P-54 at one mile increments and after each interchange.
 - Place the speed limit sign only if the crossover is more than 1 mile from an interchange exit ramp.
 - Place Sequencing Arrow Panels at the beginning of the taper when possible. Where shoulder width does not provide sufficient room, move the panel closer to the work area and place on the roadway surface. Use Type C on roadways with high traffic speeds and volumes (over 40 mph or 5000 ADT or greater)
 - Cover existing speed limit signs within a reduced speed zone.
 - Upon approval, the Engineer will measure obliterated or covered pavement marking as Obliteration of Pavement Marking.
 - As an option, use portable sign supports in lieu of post mounted signs in accordance with NDDOT Standard Specifications.
 - Reduce speed when placing traffic control devices. Place "Minimum Fee \$80" signs below speed limit signs in reduced speed areas. Place "Work Zone Speed Limit Enforced" sign in advance of the project at the time traffic control devices are installed.
 - Determine proper size, waterproof junction box, and attach to skid or vertical brace assembly.

KEY

- Type I barricade
- Type II barricade
- Type III barricade
- Sign
- Work area
- Flagger
- Sequencing arrow panel
- Delineator drum
- Flexible Delineator

LEGEND

- E Obliteration of pavement marking (10' line, 30' skip, ϕ)
- F Obliteration of pavement marking (edge lines)
- G Raised pavement markers (white) 5' centers
- H Raised pavement markers (yellow) 5' centers
- J Drums spaced @ "S" centers
- K Flexible delineators-4 spaces @ 20'



CROSSOVER QUANTITY SUMMARY

	ROADWAY EXISTING SPEED LIMIT				
	55 MPH	60 MPH	65 MPH	70 MPH	75 MPH
TYPE III BARRICADES	3 Each	3 Each	3 Each	3 Each	3 Each
FLASHING BEACON	1 Each	1 Each	1 Each	1 Each	1 Each
FLEXIBLE DELINEATORS	5 Each	5 Each	5 Each	5 Each	5 Each
DELINEATOR DRUMS	17 Each	17 Each	17 Each	17 Each	17 Each
SEQUENCING ARROW PANELS TYPE C-CROSSOVER	1 Each	1 Each	1 Each	1 Each	1 Each
PORTABLE PRECAST CONCRETE MEDIAN BARRIERS	See "PRECAST CONCRETE MEDIAN BARRIER TABLE"				
ATTENUATION DEVICES	1-Type B-55	1-Type B-60	1-Type B-65	1-Type B-70	1-Type B-75
RAISED PAVEMENT MARKERS (Yellow)	370 Each	388 Each	406 Each	424 Each	442 Each
RAISED PAVEMENT MARKERS (White)	173 Each	173 Each	173 Each	173 Each	173 Each
OBLITERATION OF PAVEMENT MARKING	298 SF	305 SF	313 SF	332 SF	339 SF

NORTH DAKOTA
 DEPARTMENT OF TRANSPORTATION
 5-31-12

REVISIONS




DATE	CHANGE
6/23/2014	Revised Note 8
3/15/2016	Removed Do Not Pass sign and updated notes
11/14/2016	Revised attenuation width
8/17/2017	Termination area and quantities Updated note and quantity

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 08/17/17 and the original document is stored at the North Dakota Department of Transportation

Place conductor behind barricade away from traffic, tie at each barrier connection, and drape above the ground. Place conductors a minimum of 6" underground between the barrier and pole.

CONSTRUCTION SIGNING MEDIAN CROSSOVER

D-704-45



NOTES:

1. Flagger #1 shall not be used to slow interstate traffic. Flagger #1 is intended to assist truck driver in viewing oncoming traffic for the truck's safe entry into traffic. When the ADT is over 2000 Flagger #2 shall be used to slow interstate traffic when trucks are entering traffic. Flagger #2 shall not be used to stop interstate traffic. Barricades shall be installed on the median access when not in use. The barricades shall be placed at 45 degrees away from approaching traffic.

KEY

- Type III Barricade
- Sign
- Work Area
- Flagger


Road Type	ADVANCE WARNING SIGN SPACING		
	Distance Between Signs Min. (FT)		
	A	B	C
Urban - Low Speed (30 mph or less)	150	150	150
Urban - Low Speed (Over 30 mph to 40 mph)	280	280	280
Urban - High Speed (Over 40 mph to 50 mph)	360	360	360
Rural - High Speed (Over 50 mph to 65 mph)	720	720	720
Urban Expressway and Freeway (55 mph to 60 mph)	850	1350	2200
Rural Expressway and Freeway	1000	1500	2640
Interstate/4-Lane Divided (Maintenance and Surveying)	750	1000	1500

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
11-19-12	
REVISIONS	
DATE	CHANGE
06-19-14	Deleted sign W16-2-24.

This document was originally issued and sealed by
 Roger Weigel,
 Registration Number
 PE- 2930,
 on 06/19/14 and the original document is stored at the
 North Dakota Department
 of Transportation

PORTABLE SIGN SUPPORT ASSEMBLY

D-704-50




Notes:

- ① The maximum weight of the assembly is 250 pounds.
- ② Use a 14" wheel and tire.
- ③ Automotive and equipment axle assemblies may not be used for trailer-mounted sign supports.
- ④ Other NCHRP 350 crash tested assemblies are acceptable.


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
11-23-10	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 11/23/10 and the original document is stored at the North Dakota Department of Transportation.


PORTABLE PRECAST CONCRETE MEDIAN BARRIER
(TEMPORARY USAGE)




Plan View




End View




Connecting Bolt Detail
(One per 10 Ft section)




Side View



Bolt Connection Detail




U1 Bar Detail




Barrier Marker Detail


Color of reflective faces shall be the same as the edge line along barrier edge. Two way reflective on Surface 1 & 2.




Dap Detail



C1 Bar Detail



U2 Bar Detail



U3 Bar Detail

Notes:

- All exposed hardware shall be galvanized as per ASTM A153, except for the loop inserts.
- Concrete shall be Class AAE-3.
- All steel shall conform to Section 612 of the NDDOT Standard Specifications.
- Barrier ends shall be imprinted A and B as shown with 4 inch letters. Field placement shall match the A end with the B end.
- Barrier markers shall be placed at the center of the barrier at 20' centers.
- Barrier sections shall be connected together with the 1 1/4" Dia A-307 double hex connecting bolt. The bottom nut and washer connection shall be maintained by the contractor for the duration of the barrier installation.
- Barrier shall be placed such that openings between individual sections shall be kept to a minimum.

Reflective Tape
The reflector shall be a retroreflective, acrylic microprism material with acrylic backing, 3" wide, providing the following minimum optical performance with an observation angle of 0.1° measured in candlepower:

Entrance Angle	Specific Intensity
Yellow - 4"	136
White - 4"	200

Adhesive
Markers shall be temporarily mounted to the portable concrete barrier with factory applied solid butyl rubber 1/8" thick, 2" wide on 2 1/4" wide release paper on surface 3.

Bar List				
Mark	Size	No.	Length	Shape
C1	4	6	9'- 4"	Straight
U1	4	2	4'- 8"	Bent
U2	4	2	4'- 10 1/4"	Bent
U3	4	15	5'- 4"	Bent


Marker Body
The marker shall be made of a high impact, weatherable engineering thermo-plastic material which conforms to the following:

Property	Result	ASTM Test Method
Thickness (min)	.090"	—
Tensile strength (min psi) @ yield	5,500	D638
Impact strength @ -20°F (ft-lbs/in of notch)	3.2	D256 Method A
Impact strength @ 73°F (ft-lbs/in of notch)	14.0	D256 Method A
Flexural strength, PSI 1/4" @ 73°F	8,000	D790
Flexural modulus, PSI 1/4" @ 73°F	300,000	D790
Elongation @ yield	30%	D638


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-20-12	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by
Roger Weigel
Registration Number
PE- 2930,
on 07/20/12 and the original document is stored at the
North Dakota Department
of Transportation

MOBILE OPERATION Grinding Shoulder Rumble Strips




TWO LANE - TWO WAY ROADWAY




TWO LANE - TWO WAY ROADWAY
Typical Protection Vehicle with
Flashing Arrow Panel In Caution Mode


- Notes:
1. Provide truck mounted attenuators on additional vehicles in the convoy, at no additional cost.
 2. Provide rotating, flashing, oscillating, or strobe lights on vehicles.
 3. Provide Type B or Type C flashing arrow panels that are controlled from inside the vehicle.
 4. Provide two - way electronic communication capability in each vehicle.
 5. Vary vehicle spacing between the protection vehicle and work vehicle depending on sight distance restrictions. Keep the spacing of the convoy vehicles such that motorists approaching the work convoy can see the protection vehicle in time to slow down and safely pass the work vehicles.
 6. Move advance Road Work Ahead signs as the work area moves through the construction zone.



INTERSTATE & 4 LANE DIVIDED HIGHWAY



INTERSTATE & 4 LANE DIVIDED HIGHWAY
Typical Protection Vehicle with Flashing Arrow
Panel In Flashing Arrow Mode




NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
11-15-12	
REVISIONS	
DATE	CHANGE
8-17-17	Updated notes & signs



This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 08/17/17 and the original document is stored at the North Dakota Department of Transportation

BITUMINOUS LABORATORY

D-706-1




- Provide a laboratory with the following:
1. A 1'x1' shelf at 36" above the regular countertop.
 2. Double compartment stainless steel sink, with each compartment a minimum of 16"x14"x10" deep. Provide water service lines made of copper or plastic and a diameter of 1/2 inch.
 3. An exhaust fan capable of removing inside air at a rate of 400 CFM.
 4. Fresh air vent hinged to open or close manually.
 5. 24" x 48" table capable of holding a 200 lb masonry saw with a minimum clearance of 36" above the table.
 6. A water supply tank with a capacity of 500 gallons and a 20 gallon capacity pressure tank on the pump.
 7. Heavy duty type locks, latches, and hinges for doors made to withstand the intense use in service.
 8. A wall between the office and the work area properly insulated to prevent the transmission of heat and noise.
 9. The steel cable tie downs and ground anchors at each corner of the lab.
 10. Electrical service entrance wired for 100 amps and separate circuits for air conditioners. Space convenience outlets in counter areas a minimum of four feet apart.




NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-03-13	
REVISIONS	
DATE	CHANGE
07-30-14	Changed standard's title and revised notes.
01-11-16	Revised notes.

This document was originally issued and sealed by
Roger Weigel
Registration Number
PE- 2930,
on **01/11/16** and the original document is stored at the North Dakota Department of Transportation


EROSION AND SILTATION CONTROLS
MEDIAN OR DITCH INLET PROTECTION




FIBER ROLL PROTECTION
(MEDIAN OR DITCH INLET)




FIBER ROLL PROTECTION
(INLET OF CULVERT)




SILT FENCE PROTECTION
(MEDIAN OR DITCH INLET)



GRAVEL INLET PROTECTION
(MEDIAN OR DITCH INLET)



SANDBAG PROTECTION
(LOW POINT)




SANDBAG PROTECTION
(ON SLOPE)


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-03-13	
REVISIONS	
DATE	CHANGE
06-26-14	Updated reference to standard drawing number for fiber roll staking details.
10-01-14	Updated reference to standard drawing number for silt fence.

This document was originally issued and sealed by
 Roger Weigel
 Registration Number
 PE-2930,
 on 10/01/14 and the original document is stored at the
 North Dakota Department
 of Transportation

REINFORCED CONCRETE PIPE CULVERTS AND END SECTIONS
(Round Pipe)




PERSPECTIVE




END VIEW

Standard Reinforcement for Class III pipe reinforced as per AASHTO M170



SIDE VIEW




TOP VIEW


REINFORCED CONCRETE PIPE - FLARED END SECTION

Reinforcement to be equivalent to Class III RCP

TRAVERSABLE END SECTION							
DIA	B	C	D	E	F	R	S
15"	4'	9"	4'-9"	1'-7 1/2"	2 1/2"	3"	6
18"	5'-9"	9"	6'-6"	1'-11"	2 1/2"	3"	6
24"	6'	1'	7'	2'-6"	3"	3"	4
30"	7'-6"	1'	8'-6"	3'-1"	3 1/2"	3 1/2"	4
36"	7'-3"	15"	8'-6"	3'-8"	4"	3"	4



SIDE VIEW



END VIEW


NOTES (Traversable End Section):

- Manufactured in accordance with applicable portions of ASTM C76/AASHTO M170.
- Reinforcement per Class III RCP with double reinforcement in the upper 120° of the full barrel portion.

End may be supplied with flat bottom


REINFORCED CONCRETE PIPE - TRAVERSABLE END SECTION

Reinforcement to be equivalent to Class III RCP




END VIEW

CIRCULAR PIPE




TONGUE & GROOVE JOINT



BELL & SPIGOT JOINT

JOINTS FOR REINFORCED CONCRETE PIPE



CONCRETE PIPE PLUG

FLARED END SECTION						
TERMINAL DIMENSIONS						
DIA	A	B	C	D	E	U
12	0'-4"	2'-0"	4'-0 7/8"	6'-0 7/8"	2'-0"	2"
15	0'-6"	2'-3"	3'-10"	6'-1"	2'-6"	2 1/2"
18	0'-9"	2'-3"	3'-10"	6'-1"	3'-0"	2 1/2"
21	0'-9"	3'-0"	3'-1"	6'-1"	3'-6"	2 1/2"
24	0'-9 1/2"	3'-7 1/2"	2'-6"	6'-1 1/2"	4'-0"	3"
27	0'-10 1/2"	4'-0"	2'-1 1/2"	6'-1 1/2"	4'-6"	3 1/2"
30	1'-0"	4'-6"	1'-7 3/4"	6'-1 3/4"	5'-0"	3 1/2"
36	1'-3"	5'-3"	2'-9"	8'-0"	6'-0"	4"
42	1'-9"	5'-3"	2'-9"	8'-0"	6'-6"	4 1/2"
48	2'-0"	6'-0"	2'-0"	8'-0"	7'-0"	5"
54	2'-3"	5'-5"	2'-9 1/4"	8'-2 1/4"	7'-6"	5 1/2"
60	2'-11"	5'-0"	3'-3"	8'-3"	8'-0"	5"
66	2'-6"	6'-0"	2'-3"	8'-3"	8'-6"	5 1/2"
72	3'-0"	6'-6"	1'-9"	8'-3"	9'-0"	6"
78	3'-0"	7'-6"	1'-9"	9'-3"	9'-6"	6 1/2"
84	3'-0"	7'-6 1/2"	1'-9"	9'-3 1/2"	10'-0"	6 1/2"
90	3'-5"	7'-3 1/2"	2'-0"	9'-3 1/2"	11'-0"	6 1/2"

All Classifications of Round Concrete Pipe

Internal Dia. of Pipe (In.)	Cross-Sectional Water Area (Sq. ft.)	Weight per Lin. Foot of Pipe (Lbs.)	Joint Groove Min./Max. (In.)	Joint Tongue Min./Max. (In.)	Minimum Wall Thickness (In.)
12	0.79	92	1 1/8-2 3/8	3/4	2
15	1.23	127	1 1/4-2 3/4	7/8	2 1/4
18	1.77	168	1 1/2-2 7/8	1	2 1/2
21	2.40	214	1 7/8-3 1/8	1 1/8	2 3/4
24	3.14	265	2 1/4-3 3/4	1 1/2	3
27	3.98	322	2 3/4-4	1 3/4	3 1/4
30	4.91	384	3 1/4-4 1/4	1 3/4	3 1/2
33	5.94	452	3 1/2-4 1/2	1 3/4	3 3/4
36	7.07	524	3 3/4-4 1/2	1 3/4	4
42	9.62	685	3 3/4-4 1/2	1 3/4	4 1/2
48	12.57	885	3 3/4-4 1/2	1 3/4	5
54	15.90	1070	4 1/2-5 1/2	2	5 1/2
60	19.63	1296	4 1/2-5 1/2	2 1/4	6
66	23.76	1542	5-6	2 1/2	6 1/2
72	28.27	1810	5 1/2-6 3/4	2 1/2	7
78	33.18	2098	6 1/4-7 1/4	2 1/2	7 1/2
84	38.48	2410	5 1/2-7 3/4	3 3/8	8
90	44.18	2793	6 3/4-8 1/2	3 1/2	8 1/2
96	50.27	3092	7-8 1/4	3 1/2	9
102	56.75	3466	7-8 1/4	3 1/2	9 1/2
108	63.62	3864	7 1/4-8 1/2	3 3/4	10

SEE STANDARD DRAWING D-714-22 FOR DETAILS OF CONCRETE PIPE TIES (TIE BOLTS).

NOTES:

- All reinforcing steel shall meet AASHTO M170 requirements.
- All circular, longitudinal, and elliptical reinforcement shall be assembled and securely fastened in cage fashion so as to maintain reinforcement in exact shape and correct positions within the forms.
- Laying length of pipe: 12" to 66" (incl.) = not less than 4 feet
66" to 108" (incl.) = not less than 6 feet
- Joints shall be sealed with rubber gaskets or with sealer approved by the engineer whenever pipe are specified for storm drain or sanitary sewers.
- For Class IV and Class V reinforced concrete pipe and end section sizes which do not have reinforcement specified by AASHTO M170, shop drawings and design calculations shall be prepared and sealed by a Professional Engineer and submitted for the Engineer's review.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
05-12-14	
REVISIONS	
DATE	CHANGE
01-21-15	Revised Note 5
11-21-16	Revised End Section Dimensions












This document was originally issued and sealed by
Jon Ketterling
Registration Number
PE-4684,
on 11/21/16 and the original document is stored at the
North Dakota Department
of Transportation

CONCRETE PIPE, CATTLE PASS, OR PRECAST CONCRETE BOX CULVERT TIES

REQUIRED SIZE OF TIE BOLTS		
Pipe Size	Thread ϕ	XXS Pipe Sleeve Inner ϕ
18" - 24"	$\frac{5}{8}$ " See note 2	$\frac{3}{4}$ "
30" - 66"	$\frac{3}{4}$ "	1"
72" - 78"	1"	$1\frac{1}{4}$ "
RCB/Cattle Pass		

NOTES:


- The pipe size listed is the inside diameter of round pipe or the equivalent diameter of pipe arch.
- Cattle Pass and Jacked and Bored pipes shall have pipe ties inserted from the inside of the pipes and grouted into place. Jacked and bored pipes with a diameter of 24" or less do not require pipe ties.
- Nuts and washers are not required on Jacked and Bored pipes or pipes with a 24" diameter or less. Where nuts and washers are not used, the tie bars shall be inserted and grouted into place.
- Ties are only for holding pipe or RCB sections together, not for pulling sections tight.
- Tie bolt assembly shall be hot dip galvanized in accordance with AASHTO M232.
- Holes in pipes to accommodate tie bolts can be precast or drilled. Tapered holes are permitted when precast. Holes shall have a diameter $\frac{1}{4}$ " larger than the diameter of the thread. Holes in precast RCB's shall contain cast-in bolt sleeves with an inside diameter of $1\frac{1}{4}$ ".
- The contractor has the option of selecting the type of tie bolt used from those shown.
- The cost of precasting or drilling the required holes and furnishing and installing the tie bolts shall be included in the price bid for the appropriate conduit or RCB pay item.
- All centerline and approach RCP culvert joints shall be tied. Storm drain systems shall have the first three joints including the end section of all free ends tied. Free ends are defined as any storm drain end which does not terminate at an inlet or manhole. Outfall culverts with end sections which drain adjacent ditches are examples of free ends.
- Place joint wrap prior to installing ties. Overlap the joint by 12" in both directions.
- Tie bolts shall conform to ASTM A 36. Nuts shall be heavy hex and conform to ASTM A 563. Washers shall conform to ASTM F 436, Type 1. Welded pipe sleeves and cast-in bolt sleeves shall conform to ASTM A 53, Grade B.
- RCB tie locations shall be as shown on the plans.



NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
3-18-14	
REVISIONS	
DATE	CHANGE
7-21-15	Note 8
6-6-17	Notes 2-11, Table, Title, Labels

This document was originally issued and sealed by Jonathan David Ketterling, Registration Number PE-4684, on 6/6/2017 and the original document is stored at the North Dakota Department of Transportation

TRANSVERSE MAINLINE PIPE INSTALLATION DETAIL
PIPES MORE THAN 4 FEET BELOW TOP OF SUBGRADE



Pay Items

- 1) Pipe*
- 2) Geosynthetic Material Type R1
- 3) Removal of Pipe (if required)



*Included in Pipe Pay Item

- 1) Pipe
- 2) Trench excavation
- 3) Aggregate Base Course CI 3 or CI 5
- 4) Embankment

NOTES:

- 1) This drawing applies to new/replaced mainline and paved intersection roadways (including ramps). It does not include pipes in approaches.
- 2) Embankment may be either Borrow Excavation or Common Excavation - Type A

Backfill Dimensions	
Pipe Materials	Dimension (A)
Concrete	0.5 O.D.
Metal and Plastic	0.5 O.D. + 1 Foot



NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
7-26-13	
REVISIONS	
DATE	CHANGE
10-15-13	Label Formatting
1-21-14	Nomenclature
9-18-15	Title Rewording
12-10-15	Added Plastic Pipe

This document was originally issued and sealed by
Ron Homer,
Registration Number
PE-2087,
on 12/10/2015 and the original document is stored at the North Dakota Department of Transportation

TRANSVERSE MAINLINE PIPE INSTALLATION DETAIL
 MULTIPLE PIPES MORE THAN 4 FEET BELOW TOP OF SUBGRADE

Pay Items

- 1) Pipe*
- 2) Geosynthetic Material Type R1
- 3) Removal of Pipe (if required)


*Included in Pipe Pay Items

- 1) Pipe
- 2) Trench Excavation
- 3) Aggregate Base Course CI 3 or CI 5
- 4) Embankment


NOTES:

- 1) This drawing applies to new/replaced mainline and paved intersection roadways (including ramps). It does not include pipes in approaches.
- 2) Embankment may be either Borrow Excavation or Common Excavation - Type A


Backfill Dimensions	
Pipe Materials	Dimension (A)
Concrete	0.5 O.D.
Metal and Plastic	0.5 O.D. + 1 Foot



EXCAVATION DETAIL



INSTALLATION DETAIL




CROSS SECTION


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
2-4-14	
REVISIONS	
DATE	CHANGE
3-3-14	Spelling Nomenclature Title Rewording Added Plastic Pipe
1-21-14	
9-18-15	
12-10-15	

This document was originally issued and sealed by
 Ron Horner
 Registration Number
 PE-2087,
 on 12/10/2015 and the original document is stored at the
 North Dakota Department
 of Transportation


TRANSVERSE MAINLINE PIPE INSTALLATION DETAIL
PIPES 4 FEET OR LESS BELOW TOP OF SUBGRADE



EXCAVATION DETAIL



INSTALLATION DETAIL



CROSS SECTION

Pay Items

- 1) Pipe*
- 2) Geosynthetic Material Type R1
- 3) Removal of Pipe (if required)

*Included in Pipe Pay Item

- 1) Pipe
- 2) Trench Excavation
- 3) Aggregate Base Course CI 3 or CI 5
- 4) Embankment


NOTES:

- 1) This drawing applies to new/replaced mainline and paved intersection roadway pipes only (including ramps). It does not include pipes in approaches.
- 2) Embankment may be either Borrow Excavation or Common Excavation - Type A

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
7-26-13	
REVISIONS	
DATE	CHANGE
10-15-13 1-21-15 9-18-15	Label Formatting Nomenclature Title Rewording

This document was originally issued and sealed by
Ron Homer,
Registration Number
PE-2087,
on 9/18/2015 and the original document is stored at the North Dakota Department of Transportation

TRANSVERSE MAINLINE PIPE INSTALLATION DETAIL
 MULTIPLE PIPES 4 FEET OR LESS BELOW TOP OF SUBGRADE



EXCAVATION DETAIL

Pay Items


- 1) Pipe*
- 2) Geosynthetic Material Type R1
- 3) Removal of Pipe (if required)

*Included in Pipe Pay Item


- 1) Pipe
- 2) Trench Excavation
- 3) Aggregate Base Course CI 3 or CI 5
- 4) Embankment

NOTES:

- 1) This drawing applies to new/replaced mainline and paved intersection roadway pipes only (including ramps). It does not include pipes in approaches.
- 2) Embankment may be either Borrow Excavation or Common Excavation - Type A



INSTALLATION DETAIL




CROSS SECTION

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
2-4-14	
REVISIONS	
DATE	CHANGE
1-21-15 9-18-15	Nomenclature Title Rewording

This document was originally issued and sealed by
 Ron Homer,
 Registration Number
 PE-2087,
 on 9/18/2015 and the original document is stored at the
 North Dakota Department
 of Transportation

PIPE INSTALLATION DETAIL FOR MULTIPLE LONGITUDINAL MAINLINE PIPE
OR PIPE NOT UNDER THE ROADWAY



EXCAVATION DETAIL A


EXCAVATION DETAIL B

- Pay Items
1) Pipe*
2) Removal of Pipe (if required)

- *Included in Pipe Pay Item
1) Pipe
2) Trench excavation
3) Aggregate base course CI 3 or CI 5
4) Embankment

- NOTES:
1) This drawing applies to new/extended mainline and paved intersection roadway pipes only (including ramps). It does not include pipes in approaches.
2) It is the contractor's option to select Detail A or B.
3) The exact location of the pipes will be shown in the plans.
4) Embankment may be either Borrow Excavation or Common Excavation - Type A

Bedding and Haunch (A)
Pipes Not Under Roadway = 0.5 O.D. + 4 Inches
Pipes Under the Roadway = 0.5 O.D. + 2 Feet
Backfill Cover (B)
Concrete Pipe = 0.5 O.D.
Metal and Plastic = 0.5 O.D. + 1 Foot
Backfill Material (C)
Top of Pipe 4 Feet or Less Below the Top of Proposed Subgrade = Aggregate Base Course CI3 or CI 5
Top of Pipe Greater than 4 Feet Below the Top of Proposed Subgrade = Common Excavation - Type A
Pipe Not Under Roadway = Common Excavation - Type B



BACKFILL DETAIL A

BACKFILL DETAIL B

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
2-4-14	
REVISIONS	
DATE	CHANGE
1-21-15 12-10-15	Nomenclature Added Plastic Pipe

This document was originally issued and sealed by
Ron Horner,
Registration Number
PE- 2087,
on 12/10/2015 and the original document is stored at the
North Dakota Department
of Transportation

STANDARD MONUMENTS AND RIGHT OF WAY MARKERS

NOTES:

The construction and installation of Alignment Monuments, Iron Pin Reference Monuments, Iron Pin R/W Monuments, and Right of Way Markers (witness posts) shall conform to Section 720 of the Standard Specifications.

ALIGNMENT MONUMENTS:

Iron Pin or Precast Concrete Alignment Monuments with aluminum caps will be placed on the centerline alignment PI's, section corners, quarter corners, section line crossings, quarter line crossings, and at curve points (PC's, PT's, TS's, and ST's) on the centerline.


IRON PIN R/W MONUMENT:

Iron pins with aluminum caps (No. 5 X 18") will be placed at breaks on the Right of Way line, and at curve points (PC's, PT's, TS's and ST's) on the Right of Way line.


IRON PIN REFERENCE MONUMENT:

Iron Pins without aluminum caps (No. 5 X 18") will be placed as reference monuments on the Right of Way line at section corners, quarter corners, section line crossings, and quarter line crossings.


ALIGNMENT MONUMENT DETAILS




IRON PIN
(Within Finished Roadway Surface)




IRON PIN
(Within Finished Roadway Surface)




PRECAST CONCRETE
(Outside Finished Roadway Surface)
(Inside R/W Limits)




IRON PIN
(Outside Finished Roadway Surface)
(Outside R/W Limits)



MARKING DETAIL




RECYCLED PLASTIC
RIGHT OF WAY MARKER
(WITNESS POST) DETAILS
&
IRON PIN REFERENCE AND R/W
MONUMENT DETAILS




SIGN DETAIL

Black letters on orange high intensity background sheeting meeting ASTM D-4956 Type III or higher on 80 gauge 5052-H38 aluminum. Silk screen graphics. One color print. Sign shall be attached by drilling two holes in the face of the post (side facing the private owner, away from the Department of Transportation right of way). Put inserts into the holes and mount the sign with #4 vandal proof screws. Sign shall be installed 2" from top of post.


VARIOUS MONUMENT AND MARKER PLACEMENTS




R/W BREAKS
SECTION LINE CROSSINGS
QUARTER LINE CROSSINGS




CURVE POINTS:
PI
SPIRAL CURVE (TS, ST)
SIMPLE CURVE (PC, PT)



DIVIDED HIGHWAYS
SECTION CORNERS
QUARTER CORNERS



SECTION CORNERS
QUARTER CORNERS



INTERSECTION OF HIGHWAYS
FLARED R/W BREAKS

LEGEND


- Iron Pin Reference Monument
- ⊙ R/W Marker (witness post)
- Alignment Monument
- Iron Pin R/W Monument

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-3-2013	
REVISIONS	
DATE	CHANGE
11/12/13	Note for SIGN DETAIL modified to meet ASTM D-4956 Type III or higher on 80 gauge 5052-H38


This document was originally issued and sealed by
Roger Weigel
Registration Number
PE-2930,
on 11/12/13 and the original document is stored at the
North Dakota Department
of Transportation

INLET - MOUNTABLE CURB


TYPE A
(Minimum Waterway Area 1.5 S.F.)





TYPE B
(Minimum Waterway Area 2.3 S.F.)



TYPE B ALTERNATE GRATE
Type "L" Vane Grate
(Minimum Waterway Area 2.3 S.F.)



CASTING DETAILS





NOTES:

1. Drainage structure castings shall be manufactured in accordance with AASHTO M 306. Metal used in the manufacture of castings shall conform to the requirements of AASHTO M 105 Class 35B.
2. Other castings, similar in dimension, may be used if the casting conforms to the riser section and has the grate style specified on the plans. If modifications to the inlet riser are required to accommodate the similar casting, the contractor must receive written approval from the engineer.
3. Type A precast risers shall be constructed in accordance with AASHTO M 199. Type B precast risers shall be constructed in accordance with ASTM C858.
4. Precast concrete bases shall be constructed in accordance with AASHTO M 199 and shall be reinforced as shown.
5. The contractor shall have the option of using precast or cast-in-place bases. Cast-in-place concrete shall be Class AE-3. Construction shall be in accordance with section 722 of the Standard Specifications.
6. On projects with P.C.C. pavement, all inlet risers shall be constructed 4 to 5 inches below final elevation and adjusted to final elevation after paving. Adjustment may be done with adjusting rings or cast-in-place concrete. All costs for this adjustment shall be included in the price bid for the inlet.

PAY ITEMS

- Inlet Mountable Curb - Type A Ea.
- Inlet Mountable Curb - Type B Ea.







RISER DETAILS

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
05-13-14	
REVISIONS	
DATE	CHANGE
07-07-14	Revision to Note 5

This document was originally issued and sealed by **TERRENCE R. UDLAND** Registration Number PE-2674, on 07/07/14, and the original document is stored at the North Dakota Department of Transportation




PRECAST CONCRETE MEDIAN DRAIN

D-722-7






Notes:

1. Use Neenah R-4370-23G, East Jordan 1310 grate, or equal with a minimum waterway of 1.2 SF. If modifications to the drain are required to facilitate similar castings, the contractor must receive written approval from the Engineer.
2. Castings shall be manufactured in accordance with AASHTO M 306. Metal used in the manufacture of castings shall conform to AASHTO M 105, Class 35B.
3. Precast concrete median drains, adjusting rings, and riser sections shall be constructed in accordance with AASHTO M 199. T-sections shall be constructed in accordance with AASHTO M 170.
4. All reinforcing steel shall be Grade 60 steel. Reinforcing for adjusting rings, riser sections, and T-sections shall be in accordance with AASHTO M170.
5. The cost of furnishing and installing the castings and drains shall be included in the price bid for "Median Drain Precast Concrete-Type A". The cost of furnishing and installing the adjusting rings and riser sections shall be included in the price bid for "Pipe Conc Reinf 24IN (CL _)". The cost of furnishing and installing the T-sections and concrete plugs shall be included in the price bid for "Pipe Conc Reinf (_ IN) (CL _)".
6. Seal all joints with rubber gaskets or with sealer approved by the engineer.




Dia = Diameter of drainage pipe
T = Wall thickness of drainage pipe




NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
6-30-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Terrence R. Udland, Registration Number PE-2674, on 06/30/14 and the original document is stored at the North Dakota Department of Transportation


Curb & Gutter and Valley Gutter




Curb & Gutter Type 1 (Sec. A & B)
Adjacent to Concrete Sidewalk,
Median, or Parking Lot.
(Sec. A shown. See Sec B for
additional details.)



Isolation Joint




36" Concrete Valley Gutter Detail




36" Concrete Valley Gutter Plan

NOTES:


1. Curb and Gutter Type 1 (Sec. A & B) to be used. Section "A" to be used with (-) pavement slopes and section "B" to be used with (+) pavement slopes.
2. Contraction Joints: Tool the Curb & Gutter 2" as shown on the contraction joint details.
3. Isolation Joints: Isolation joint material shall be 3/4" preformed expansion joint filler conforming to the standard specifications. The opening for the backer rod and joint sealant shall be formed by a pre-cut piece of wood or other material approved by the engineer. Dowel supports are not required on the second pour at a cold joint, plastic or metal caps and greased dowels shall be installed in the cold joint for the second pour.
4. Joint Spacing: For hot bituminous pavements the joint spacing for the curb and gutter shall be 10' max. with the panels on each side of the inlets. For concrete pavements the joint spacing for the curb and gutter shall match the pavement joint on PCC Pavements of approximately 15' spacing.
5. Joint sealing: All contraction and isolation joints shall be sealed as shown in the details. The joint sealant for contraction joints shall conform to section 826.02B. The sealant for expansion joints shall be as specified in note 3 above. The sealant shall be tooled and installed in accordance with the manufacturer's recommendations.
6. Depth of Face of Gutter: For hot bituminous pavement the depth of gutter shall be 7" as shown. For PCC pavements, the Contractor has the option to match the depth of gutter to the depth of the adjacent PCC pavement or to construct a 7" depth as shown.
7. When the curb and gutter abuts PCC pavement, it shall be tied to the PCC pavement. The tie bar shall consist of a No. 3 bar, 1'-6" in length spaced 4' center to center.
8. On street returns and other locations where the new curb and gutter ends and does not abut existing curb and gutter, the end two (2) feet of the curb shall be tapered from 6" in height to 0". A 1/2" preformed isolation joint which is full depth and the same shape as the curb and gutter shall be installed just ahead of the taper. An 18" tie bar shall be installed across the joint.
9. Valley Gutter Joints: Contraction joints are required at approx. 10' intervals. The contraction joints shall be 1/8" min. to 3/8" max. in width. The joints shall be formed by sawing or scoring to a minimum depth of 2". The joint sealant shall be a hot poured elastic type joint sealer in accordance with Section 826.02A.2 of the Standard Specifications. The joint and sealant shall be included in the price bid for Valley Gutter.




Curb & Gutter Type 1 (Sec. A)




Contraction Joint
(10' Max Spacing)




72" Concrete Valley Gutter Plan




Curb & Gutter Type 1 (Sec. B)




72" Concrete Valley Gutter Detail




Mountable Curb & Gutter Type 1 (Sec. A)




Keyway Detail for Curb & Gutter
(To be used with PCC Pavement and Drives)




Joint Location Detail



Mountable Curb & Gutter Type 1 (Sec. B)



Curb & Gutter Reinforcing at Inlets



Section A-A


NOTE: All bars shall be #4 deformed reinforcing bars. Splices will not be permitted. Reinforcing bars at inlet locations will not be paid for separately, but shall be included in the price bid for "Curb and Gutter - Type 1." This includes inlets located on radii. The reinforcement shall be extended to the second joint (rebar placed through the first joint) in cases where the 3' min. panel length cannot be obtained.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-7-2013	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by
Roger Weigel
Registration Number
PE-2930,
on 08/07/2013 and the original document is stored at the
North Dakota Department
of Transportation

PIPE OR W-SHAPE ASSEMBLY DETAILS


D-754-1




HORIZONTAL CLEARANCE TABLE

SHOULDER WIDTH ft	OFFSET ft
0 to 2	16
>2 to 4	18
>4 to 6	20
>6 to 8	22
>8 to 10	24

TYPICAL SECTION (FORESLOPE SIGNS) PIPE OR W-SHAPE




TYPICAL SECTION (OFFSET SIGNS) PIPE OR W-SHAPE



EXIT RAMP GORE SIGN PLACEMENT

NOTES:
MINIMUM VERTICAL CLEARANCE:
 Signs installed at the side of the road in rural districts shall be at least 5 feet measured from the bottom of the sign to the edge of driving lane, or Auxiliary Lane. Where parking or pedestrian movements occur, the clearance to the bottom of the sign shall be at least 7 feet.
 Signs on freeways, expressways, and multi-lane conventional roadways shall be installed with a minimum height of 7 feet.
 Where signs are placed at least 30 feet or more from the edge of the traveled way, the height to the bottom of such sign shall be 5 feet above the edge of driving lane.
 Signs may be placed a maximum of 6" above the vertical clearance specified above.




OBJECT MARKER INSTALLATION
 (Posts shall conform to section 894.04 A of Standard Specifications.)


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
12-1-10	
REVISIONS	
DATE	CHANGE
7-18-14	Modify notes and update reflective sheeting for object marker. Add correct section number for object marker post.

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 7/18/14 and the original document is stored at the North Dakota Department of Transportation


Breakaway Coupler System for Standard Pipe Stub Post




Single Post Sign and Stub Post Type A



Two or More Post Sign and Stub Post For two post signs with 8' or more post spacing and all three or more post signs Type C



Two Post Sign and Stub Post For signs with less than 8' post spacing Type B




Section C - C


Max. protection of the stub post is 4" above a 60" chord aligned radially to the center line of the highway and connecting any point, within the length of the chord, on the ground surface on one side of the support to a point in the ground surface on the other side.

Notes:

- In lieu of the breakaway base system on standards D-754-3 and D-754-4 the breakaway coupler system may be used. The breakaway coupler system shall be manufactured from material meeting the requirements of ASTM A325 fasteners with the special requirements as specified by DENT BREAKAWAY IND., INC. which meets the requirements of NCHRP Report 350.
- Fuse Joint Cuts - Steel posts may be cut after galvanizing and cut surface treated in accordance with ASTM A780 or the cut may be galvanized after fabrication. Aluminum posts will need no treatment.
- Shim as required to plumb post.
- Tighten all bolts the maximum possible with 12" to 15" wrench.



Plan Base Plate



Shim Detail


Furnish 2 - .012"± thick and 2 - .032"± thick shims per post. Shims shall be fabricated from brass shim stock or strip conforming to ASTM B36.

Dimension Nom. Pipe Size	Base Table Data										Stub Post Length
	Breakaway Coupling	A	B	C	D	E	F	G	t	W	
Steel											
3 1/2"	1/2" x 4 1/2"	5 1/2"	8 3/8"	13 1/16"	3 7/8"	13 1/16"	6 3/4"	9 1/16"	3/4"	3/8"	1'-6"
4"	5/8" x 4 1/2"	5 1/2"	8 3/4"	1"	3 1/2"	1"	6 3/4"	1 1/16"	3/4"	3/8"	1'-6"
5"	3/4" x 5 1/4"	6 1/2"	10"	1 1/8"	4 1/4"	1 1/8"	7 3/4"	13 1/16"	1"	7/16"	2'-0"
6"	1" x 5 1/2"	7 1/2"	11 3/4"	1 3/8"	4 3/4"	1 3/8"	9"	1 1/16"	1 1/4"	7/16"	2'-0"
8"	1" x 5 1/4"	9 1/2"	13 1/4"	1 3/8"	6 3/4"	1 3/8"	10 1/2"	1 1/16"	1 1/4"	7/16"	2'-6"
10"	1" x 5 1/4"	11 3/4"	15 1/4"	1 3/8"	9"	1 3/8"	12 1/2"	1 1/16"	1 1/4"	1/2"	3'-0"
12"	1" x 7"	13 3/4"	18"	1 5/8"	10 1/2"	1 5/8"	14 3/4"	1 1/16"	1 1/2"	1/2"	3'-0"
Aluminum											
3 1/2"	1/2" x 4 1/2"	5 1/2"	8 3/8"	13 1/16"	3 7/8"	13 1/16"	6 3/4"	9 1/16"	3/4"	3/8"	1'-6"
4"	5/8" x 4 1/2"	5 1/2"	8 3/4"	1"	3 1/2"	1"	6 3/4"	1 1/16"	1"	7/16"	1'-6"
5"	3/4" x 5 1/4"	6 1/2"	10"	1 1/8"	4 1/4"	1 1/8"	7 3/4"	13 1/16"	1"	1/2"	2'-0"
6"	1" x 5 1/4"	7 1/2"	11 3/4"	1 3/8"	4 3/4"	1 3/8"	9"	1 1/16"	1 1/4"	1/2"	2'-0"
8"	1" x 5 1/4"	9 1/2"	13 1/4"	1 3/8"	6 3/4"	1 3/8"	10 1/2"	1 1/16"	1 1/4"	1/2"	2'-6"
10"	1" x 5 1/4"	11 3/4"	15 1/4"	1 3/8"	9"	1 3/8"	12 1/2"	1 1/16"	1 1/2"	7/16"	3'-0"
12"	1" x 7"	13 3/4"	18"	1 5/8"	10 1/4"	1 5/8"	14 3/4"	1 1/16"	1 3/4"	1 1/16"	3'-0"


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-3-2013	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel Registration Number PE-2930, on 10/3/13 and the original document is stored at the North Dakota Department of Transportation


Breakaway System for Standard Pipe Stub Post




Stub Post Connection - Type A
Elevation View
(Single Post)



Stub Post Connection - Type B
Elevation View
(Two Posts)




Stub Post Connection - Type C
Elevation View
(Two Posts)




Base Plate Plan View

The bevel shall be toward the roadway on the approach side and away on the other.



Keeper Plate Detail

Keeper plate shall be placed above the center washer between the top and bottom slip bases. Keeper plate shall be fabricated from 28 gauge material, galvanized after fabrication conforming to ASTM A653 G60 coating.



Shim Detail

Furnish 2 each ±.012" thick and 2 each ±.032" thick shims per post. Shims shall be fabricated from brass shim stock or strip conforming to ASTM B36.

Notes:
When the base plate is fabricated in aluminum, the aluminum base plate washers shown shall be tack welded to the base as shown.

Use standard drawing D-754-6 for fuse plate, hinge plate, and foundation details.

Assembly Procedure:

1. Assemble post to stub with bolts and with one flat washer between base plates and keeper plate.
2. Shim as required.
3. Tighten all bolts the maximum possible with 12" to 15" wrench to bed washers and shims and to clean bolt threads, then loosen.
4. Retighten bolts in a systematic order to prescribed torque. (see table)
5. Loosen each bolt and apply thread locking liquid resin. The liquid locking resin shall conform to ASTM D5363-03 (2008). The thread locker shall secure the entire assembly from vibration, pressure and corrosion. The thread locker shall fill the gaps between the thread and the mating surface to form solid, one part assemblies.
6. Retighten each bolt to prescribed torque in the same order as initial retightening.

Base Data Table												
Nominal Post Size dia.	Bolt Size (dia. x length)	Base Bolt Torque ft. lb.	A	B	C	D	E	F	G	t	W	Stub Post Length
Steel												
3 1/2"	1/2"x2 1/2"	12	5 1/2"	8 3/8"	1 3/16"	3 7/8"	1 3/16"	6 3/4"	9/32"	3/4"	3/8"	1'-6"
4"	5/8"x2 3/4"	29	5 1/2"	8 3/4"	1"	3 1/2"	1"	6 3/4"	1 1/32"	3/4"	3/8"	1'-6"
5"	3/4"x3 1/2"	46	6 1/2"	10"	1 1/8"	4 1/4"	1 1/8"	7 3/4"	1 3/32"	1"	7/16"	2'-0"
6"	1"x4 1/4"	61	7 1/2"	11 1/4"	1 3/8"	4 3/4"	1 3/8"	9"	1 1/32"	1 1/4"	7/16"	2'-0"
Aluminum												
3 1/2"	1/2"x2 1/2"	12	5 1/2"	8 3/8"	1 3/16"	3 7/8"	1 3/16"	6 3/4"	9/32"	3/4"	3/8"	1'-6"
4"	5/8"x2 3/4"	29	5 1/2"	8 3/4"	1"	3 1/2"	1"	6 3/4"	1 1/32"	1"	7/16"	1'-6"
5"	3/4"x3 1/2"	46	6 1/2"	10"	1 1/8"	4 1/4"	1 1/8"	7 3/4"	1 3/32"	1"	1/2"	2'-0"
6"	1"x4 1/4"	61	7 1/2"	11 1/4"	1 3/8"	4 3/4"	1 3/8"	9"	1 1/32"	1 1/4"	1/2"	2'-0"

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
11-21-11	
REVISIONS	
DATE	CHANGE
2-28-14	Removed lower post and foundation details.

This document was originally issued and sealed by
Roger Weigel,
Registration Number
PE-5047,
on 2/28/14 and the original document is stored at the North Dakota Department of Transportation


Multi-Directional Breakaway System for Standard Pipe Stub Post

Notes:
When the base plate is fabricated in aluminum, the aluminum base plate washers shown shall be tack welded to the base as shown.


Use standard drawing D-754-6 for fuse plate, hinge plate, and foundation details.

Assembly Procedure:


1. Assemble post to stub with bolts and with one flat washer between base plates and keeper plate.
2. Shim as required.
3. Tighten all bolts the maximum possible with 12" to 15" wrench to bed washers and shims and to clean bolt threads, then loosen.
4. Retighten bolts in a systematic order to prescribed torque. (see table)
5. Loosen each bolt and apply thread locking liquid resin. The liquid locking resin shall conform to ASTM D5363-03 (2008). The thread locker shall secure the entire assembly from vibration, pressure and corrosion. The thread locker shall fill the gaps between the thread and the mating surface to form solid, one part assemblies.
6. Retighten each bolt to prescribed torque in the same order as initial retightening.




Stub Post Connection - Type D
Elevation View
(Single Post)



Stub Post Detail
Top View



Slip Base Orientation
Top View



Shim Detail


Furnish 2 each ±.012" thick and 2 each ±.032" thick shims per post. Shims shall be fabricated from brass shim stock or strip conforming to ASTM B36.

Base Data Table											
Nominal Post Size dia.	Outside Post dia.	Bolt Circle	a rad.	b rad.	c rad.	Bolt Size (dia. x length)	Base Plate Thickness	W	Base Bolt Torque ft. lb.	d rad.	Stub Post Length
Steel											
3 1/2"	4"	7"	1 1/16"	1/8"	1 1/8"	1" x 4"	1 1/4"	5/16"	55	1 1/8"	1'-6"
4"	4.5"	7 1/2"	1 1/16"	1/8"	1 1/8"	1" x 4 1/2"	1 1/2"	3/8"	98	1 1/8"	1'-6"
5"	5.563"	9 1/2"	1 5/16"	1/8"	1 1/8"	1 1/4" x 5"	1 1/2"	3/8"	167	1 3/8"	2'-0"
Aluminum											
3 1/2"	4"	7"	1 3/16"	1/8"	7/8"	3/4" x 3 1/2"	1"	5/16"	43	7/8"	1'-6"
4"	4.5"	7 1/2"	1 3/16"	1/8"	3/4"	3/4" x 4"	1 1/4"	5/16"	76	7/8"	1'-6"
5"	5.563"	9 1/2"	1 1/16"	1/8"	1 1/8"	1" x 4"	1 1/4"	5/16"	98	1 1/8"	2'-0"
6"	6.625"	10 1/4"	1 1/16"	1/8"	3/4"	1" x 4 1/2"	1 1/2"	3/8"	134	1 1/8"	2'-0"


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
2-28-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by
Roger Weigel,
Registration Number
PE-2930,
on 2/28/14 and the original document is stored at the North Dakota Department of Transportation


Hinge Plate, Fuse Plate and Foundation Details for Standard Pipe




Hinge Plate




Perforated Fuse Plate



Side View




Top View



Top View

See standard drawing D-754-5 for size, number and length of rebar. If using Type D only 3 bolt base plate is required.



Foundation Front View

Foundation detail for breakaway base with stub post connection.

Foundation diameter	Post Size
1'-4"	3 1/2"-4"
1'-9"	5"-6"

Notes:
Fuse joints cuts for steel posts may be cut after galvanizing and cut surface shall be treated with an approved method meeting ASTM A780 or the cut may be galvanized after fabrication. Aluminum posts will not require treatment.

Use standard drawings D-754-2, D-754-3 and D-754-4 for information on breakaway base details.

The vertical clearance of the break-away base, 4" height and 60" clearance, shall be made above and below post location, and also back and ahead of post.

Assembly Procedure:

1. Assemble hinge plate to post with bolts and one flat washer and lock washer under nut.
2. Tighten all bolts the maximum possible with 12" to 15" wrench.


Round Metal Posts							
Dimensions				Properties			
Nominal dia. in.	Outside dia. in.	Inside dia. in.	Wall Thickness in.	Weight per Foot Pound	Moment of Inertia in. ⁴	Cross Sec. Area in. ²	Section Diameter in. ²
Steel							
3 1/2	4.000	3.548	.226	9.11	4.788	2.680	2.394
4	4.500	4.026	.237	10.79	7.233	3.174	3.215
5	5.563	5.047	.258	14.62	15.16	4.300	5.449
6	6.625	6.065	.280	18.97	28.14	5.581	8.495
Aluminum							
3 1/2	4.000	3.548	.226	3.151	4.788	2.680	2.394
4	4.500	4.026	.237	3.733	7.232	3.174	3.214
5	5.563	5.047	.258	5.057	15.16	4.300	5.451
6	6.625	6.065	.280	6.564	28.14	5.581	8.496

Nominal Pipe Size dia.	Fuse and Hinge Plate Data										
	Bolt Size	A	B	C	D	E	F	G	H	I	J
3 1/2"	1/2" ϕ x 1 1/2"	5"	1 3/4"	1 1/16"	1 3/16"	7/8"	9/16"	1 5/32"	1/4"	1 3/32"	7/16"
4"	5/8" ϕ x 1 1/2"	5 3/4"	2"	1 7/8"	1"	1"	1 1/16"	1 7/32"	3/8"	1 5/32"	9/16"
5"	5/8" ϕ x 1 3/4"	5 3/4"	2"	1 7/8"	1"	1"	1 1/16"	9/16"	1/2"	7/16"	5/8"
6"	3/4" ϕ x 2 1/4"	6 1/4"	2 1/4"	2"	1 1/8"	1 1/8"	1 3/16"	5/8"	1/2"	1/2"	5/8"


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
2-28-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 2/28/14 and the original document is stored at the North Dakota Department of Transportation


PIPE SUPPORT AND SIGN MOUNTING DETAILS



Side View




Side View




Top View

Flat Sheet Sign Clamp Mounting Details




Top View


Panel Sign Clamp Mounting Details




Alternate A
12" Extruded Panel



Alternate B
12" Extruded Panel



Slotted Hole Detail




6" Extruded Panel

Aluminum Panel Details


(A) Slotted holes shall be punched in the aluminum panels at 1'-0" on center, spacing from end as listed below:

12" even length panels	4'-0" etc.
9" odd + 6" length panels	5'-6" etc.
6" odd length panels	5'-0" etc.
3" even + 6" length panels	4'-6" etc.


Wall thickness = .078" unless specified otherwise.
All inside and outside corners = .031" radius unless specified otherwise.



Flat Washer Detail




Side View




Top View

Post Cap Detail

Post caps shall be furnished for all steel or aluminum posts.
In place of post cap, a 1/8" plate welded all around may be used.



Clamp Detail




Steel Channel Detail

Post Size dia.	Clamp Gauge min.
3 1/2" to 5"	11
6" to 12"	10

Post Size dia. in.	D in.
3 1/2	3
4	3 3/16
5	5 1/8
6	7 1/16
8	13 1/16
10	20 3/4
12	29 5/8

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
2-21-14	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 2/21/14 and the original document is stored at the North Dakota Department of Transportation



SIZE OF THE FRACTION IS DETERMINED AS FOLLOWS:


SYMBOL	TITLE	RATIO TO HEIGHT OF CAPITAL OR UPPER CASE
A	Letter height	1.0 of capital or upper case
B	Fraction height	1.5 X A
C	Fraction width	2.5 X A
D	Fraction width	2 X A
E	Space to next character	1 to 1.5 X A
F(A)	Length of diagonal	1.75 X A

(A) Diagonal stroke of fraction is to be centered optically.



EXIT DIRECTION SIGNS


LETTER SIZE (Upper Case)	A	B	C	D	E	R
8"	15 1/8"	11 1/16"	3 3/4"	1 5/16"	17"	1 3/16"
10" - 13 1/3"	18 1/4"	14"	4 1/2"	1 1/2"	20"	3/4"
16" - 20"	22 1/4"	17"	5 3/8"	1 3/4"	25"	1"



(B) When there is no exit number in the sign face, the arrow shall be at 30°


GORE SIGNS

"EXIT" LETTER SIZE (Upper Case)	A	B	C	D	E	R
8"	15 1/8"	11 1/16"	3 3/4"	1 5/16"	25"	1 3/16"
10" - 13 1/3"	18 1/4"	14"	4 1/2"	1 1/2"	30"	3/4"




DISTANCE AND DESTINATION SIGNS

LETTER SIZE (Upper Case)	A	B	C	D	E	R
4"	4"	3 5/16"	1 1/2"	1/4"	6"	1/4"
6"	6"	4 7/8"	2 1/4"	3/8"	9"	3/8"
8"	8"	6 5/8"	3"	1/2"	12"	1/2"
12"	12"	10"	4 1/2"	7/8"	18"	7/8"



DOWN ARROW



TYPICAL SPACING


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-3-11	
REVISIONS	
DATE	CHANGE
7-8-14	Revised gore sign and added 4" D & D arrow
5-4-16	Revised Distance & Destination and Typical Spacing details

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 5/4/16 and the original document is stored at the North Dakota Department of Transportation


Breakaway Coupler System Structural Details for W-Shape Supports

Notes:


- In lieu of the breakaway base system shown on standard D-754-13 the breakaway coupling system may be used. The breakaway coupling system shall be manufactured from material meeting the requirements of ASTM A325 fasteners with the special requirements as specified by DENT BREAKAWAY IND., INC. which meets the requirements of NCHRP Report 350.
- Structural steel shall conform to Sec. 894.03 B.6. High strength bolts shall conform to ASTM - A325. Refer to "Sign Summary" sheet for specific data on each individual sign installation.
- Assembly procedure according to the manufacturer's recommendations.



Sign Post and Stub Post
Elevation




Section A - A
Section B - B
(See Table for Dimensions)




Section C - C

Max. protection of the stub post is 4" above a 60" chord aligned radially to the center line of the highway and connecting any point, within the length of the chord, on the ground surface on one side of the support to a point in the ground surface on the other side.

Sections shown are for installations on right shoulder and in gore. Plate slot bevels are opposite hand from that shown for installations on left shoulder.




Shim Detail



Stiffener Plate Detail
(See Table for Dimensions)

Furnish 2 - .012"± thick and 2 - .032"± thick shims per post. Shims shall be fabricated from brass shim stock or strip conforming to ASTM B36.




W-Shape - Pile Footing

W-Shape Post & Pile Size	Base Connection Data										W-Shape Pile Post "P"
	Bolt Size	A	B	C	D	E	t ₁	t ₂	W	F	
W4X13	3/4" x 5 1/4"	6"	2 1/2"	1 1/2"	3 1/2"	1 1/4"	1"	1/2"	1/4"	13/16"	14'
W5X16		6"	2 1/2"	1 1/2"	3 1/2"	1 1/4"	1"	1/2"	1/4"	13/16"	14'
W6X20	7/8" x 5 1/4"	8"	3"	1 3/4"	4"	2"	1 1/4"	1/2"	1/4"	15/16"	14'
W8X24		8"	3"	1 3/4"	4"	2"	1 1/4"	1/2"	1/4"	15/16"	14'
W8X28	1" x 5 1/4"	8"	3"	2"	4"	2"	1 1/2"	3/4"	5/16"	1 1/16"	14'


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-4-2013	
REVISIONS	
DATE	CHANGE
7-8-14	Revised notes 2 and 3

This document was originally issued and sealed by
Roger Weigel
Registration Number
PE-2930,
on 7/8/14 and the original document is stored at the North Dakota Department of Transportation


Breakaway System
Structural Details
for W-Shape Supports



Typical Panel Mounting on W-shape Sign Posts




Base Connection Detail




Section C-C
Stub Height Requirements


Maximum projection of base plate shall not extend above a line 4" parallel to any chord, which is perpendicular to, or aligned radially to, the center line of the highway and has the chord's end points on the ground surface on opposite sides of the stub post.




Perforated Fuse Plate



Hinge Plate




Fuse Joint
(Side View)



Section A-A


Section B-B

Sections shown are for installations on right shoulder. Installations on the left shoulder shall have the plate slot bevels reversed.




Shim Detail


Furnish 2 each .012"± thick and 2 each .032"± thick shims per post. Shims shall be fabricated from brass shim stock or strip conforming to ASTM B36.




Detail A




Keeper Plate



Stiffener Plate




Section E-E




Section F-F

Post clips shall be installed on both sides of each post at each panel joint as indicated.



Flat Washer Detail
Thickness = 5/64"

W-Shape Post and Pile Size	Base Connection Dimensions										Fuse and Hinge Plate Dimensions									
	Bolt Size and Torque	A	B	C	D	E	t ₁	t ₂	W	R	G	H	J	K	L	M	d ₁	d ₂	t ₃	Bolt dia.
W4x13	3/4" ø x 3 1/2" Torque = 600 in-lb	6"	2 1/2"	1 1/2"	3 1/2"	1 1/4"	1"	1/2"	1/4"	13/32"	2"	1 1/4"	4"	2 1/4"	7/8"	1"	1 1/16"	3/4"	3/8"	5/8"
W5x16	3/4" ø x 3 1/2" Torque = 600 in-lb	6"	2 1/2"	1 1/2"	3 1/2"	1 1/4"	1"	1/2"	1/4"	13/32"	2 1/2"	1 1/4"	5"	2 3/4"	1 1/8"	1 1/8"	13/16"	7/8"	3/8"	3/4"
W6x20	7/8" ø x 4 1/4" Torque = 800 in-lb	8"	3"	1 3/4"	4"	2"	1 1/4"	1/2"	1/4"	15/32"	2 1/2"	1 1/4"	6"	3 1/2"	1 1/4"	1 3/8"	13/16"	1 1/8"	3/8"	3/4"
W8x24	7/8" ø x 4 1/4" Torque = 800 in-lb	8"	3"	1 3/4"	4"	2"	1 1/4"	1/2"	1/4"	15/32"	2 1/2"	1 1/2"	6 1/2"	3 1/2"	1 1/2"	1 1/2"	15/16"	1 1/4"	1/2"	7/8"
W8x28	1" ø x 5" Torque = 1000 in-lb	8"	3"	2"	4"	2"	1 1/2"	3/4"	5/16"	17/32"	2 1/2"	1 1/2"	6 1/2"	3 1/2"	1 1/2"	1 5/8"	1 1/16"	1 1/8"	1/2"	1"
W8x31	1 1/8" ø x 5" Torque = 1200 in-lb	9"	3 1/2"	2"	5"	2"	1 1/2"	3/4"	5/16"	19/32"	3"	1 3/4"	8"	5 1/2"	1 1/4"	2"	1 1/16"	1 1/2"	1/2"	1"
W10x39	1 1/8" ø x 5" Torque = 1200 in-lb	9"	3 1/2"	2"	5"	2"	1 1/2"	3/4"	5/16"	19/32"	3"	1 3/4"	8"	5 1/2"	1 1/4"	1 7/8"	1 3/16"	1 3/8"	1/2"	1 1/8"




Section D-D

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
2-28-14	
REVISIONS	
DATE	CHANGE
7-18-14	Revised first note

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 7/18/14 and the original document is stored at the North Dakota Department of Transportation

WIND BEAMS AND ANCHOR PLATES
FOR W-SHAPE SUPPORTS




ASSEMBLY DETAIL
FOR WIND BEAMS
AND ANCHOR PLATES

Notes:


The B distance is calculated by the following formula, $B=A/4$.

The wind beam shall conform to Section 894.03 B.6 of the Standard Specifications.


The bolts shall conform to requirements of ASTM A307 and galvanized according to ASTM A153.



W4-13 & W5-16




W6-20, W8-24 & W8-28




W8-31 & W10-39


ANCHOR PLATE DETAILS




End View Top View
W4-13 & W5-16




End View Top View
W6-20, W8-24 and W8-28



End View Top View
W8-31



End View Top View
W10-39
WIND BEAM CONNECTION DETAILS



ASSEMBLY DETAIL FOR
EXIT NUMBER SIGNS


Note: Two aluminum angles required on each sign. The distance between angles varies depending on post spacing of sign in place. Angles shall be placed as near as possible to posts. The Engineer shall determine the exact location.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-3-13	
REVISIONS	
DATE	CHANGE
7-8-14	Revised second note

This document was originally issued and sealed by
Roger Weigel
Registration Number
PE-2930,
on 7/8/14 and the original document is stored at the North Dakota Department of Transportation

(EXPRESSWAY-FREEWAY USE) MILE POSTS



D-754-20



TYPE A
Area = 2.00 S.F.

TYPE B
Area = 3.00 S.F.

TYPE C
Area = 4.00 S.F.




(A) 8' Clearance to finished shoulder or in line with existing delineator posts

- NOTES:
- Installation: Posts shall be installed along right shoulder in line with delineators.
 - Mile Sign Backing: Backing shall be fabricated of 0.080 aluminum. Sheeting shall conform to section 894.01 of the Standard Specifications.
 - Posts: Posts shall conform to section 894.03 of the Standard Specifications.
 - Fasteners: The mile signs shall be attached to the post by tension pin type fastener or other suitable vandal resistant non-rust fastener.
 - Reflective Sheeting: Sheeting shall be Type IV.
 - Numbers: Numbers shall be of the series shown and may be screened or applied copy. Screening and reflective sheeting for applied copy shall conform to section 754 & 894 of the Standard Specifications.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
12-1-10	
REVISIONS	
DATE	CHANGE
7-8-14	Revised post and reflective sheeting notes

This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930, on 7/8/14 and the original document is stored at the North Dakota Department of Transportation


REFLECTORIZED DELINEATORS






Main line
One reflector
(Type A delineator)

Ramps
Two reflectors
(Type B delineator)


Narrow Bridges
Three reflectors
(Type C delineator)




Delineator Attachment Detail




U-type Post




Median
One reflector
(Type D delineator)




Median
One or Two reflectors
(Type E delineator)



Alternate Type E



Steel Post Detail
Approx. 2.0 lbs/ft



Aluminum Post Detail
Approx. 0.88 lbs/ft

Delineator Details
Type A, B, and C

Installation: Posts are to be installed along the right shoulder line unless shown otherwise on the plans.

Reflectors: Reflector shall be the same color as the adjacent pavement marking.

Spacing: Delineator spacing along main line tangents and curves with radius greater than 11500' (less than 0° 30') shall be at 528' centers. Curves with a radius less than 11500' but greater than 1200' the spacing shall be at 264' centers. With curves less than 1200' use spacing (S) = 3*√R-50

Type E


Alternate: One unit band consisting of two yellow stripes separated by a 2" black stripe may be used in place of two 3" yellow bands.

(A) The fastener shall be 3/8" dia. with flat washer having a min. outside dia. of 1 3/16". Fasteners shall be tension pin type or other non-rust vandal resistant fastener.


(B) The contractor may drill only those holes required to attach the number of reflectors on that post, or drill all the posts the same so that any number of reflectors may be added.

(C) Reflector to be mounted facing traffic at an angle of 93° away from oncoming traffic.

(D) The median width may vary. The sign and delineator assembly shall be placed in the median crossover an equal distance from each roadway.



Installation



Section A - A
Median Crossovers
Signing and Delineation system


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-25-12	
REVISIONS	
DATE	CHANGE
7-18-14	Revised reflective sheeting

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 7/18/14 and the original document is stored at the North Dakota Department of Transportation

TYPICAL INTERCHANGE DELINEATION

D-754-22A

Note: Delineator spacing along interstate mainline shall be at 528' centers on tangent and curves less than 0°30' and 264' on curves 0°30' and greater.




NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-25-12	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by
 Roger Weigel,
 Registration Number
 PE-2930,
 on 9/25/2012 and the original document is stored at the
 North Dakota Department
 of Transportation

TYPICAL REST AREA DELINEATION

D-754-22B

Note: Delineator spacing along interstate mainline shall be at 528' centers on tangent and curves less than 0°30' and 264' on curves 0°30' and greater.



NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-25-12	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 9/25/2012 and the original document is stored at the North Dakota Department of Transportation

PERFORATED TUBE ASSEMBLY DETAILS

D-754-23


Notes:

1. Curbed Roadways: The clearance from the face of the curb should be 3' except where right of way or sidewalk width is limited, a minimum clearance of 2' shall be provided. The horizontal clearance may need to be increased to maintain a minimum sidewalk clear width of 4' from the sign support, not including any attached curb.
2. Minimum vertical clearance: Signs installed at the side of the road in rural districts shall be at least 5' measured from the bottom of the sign to the edge of the driving lane or auxiliary lane. Where parking or pedestrian movements occur, the clearance to the bottom of the sign shall be at least 7'.
- Signs on expressways shall be installed with a minimum height of 7'.
- Adopt-a-highway signs installed on Freeways shall be at least 7' above the edge of the driving lane.
- The vertical clearance shall have a maximum height of 6" above the vertical clearance specified above.
3. Offset signs: Where signs are placed at least 30 feet or more from the edge of the traveled way, the height to the bottom of such sign shall be 5' above the edge of the driving lane.
4. The clearance from edge of shared use path to edge of sign should be 3' except where width is limited, a minimum clearance of 2' shall be provided.




Typical Section (without curb)

Horizontal Clearance Table	
Shoulder Width ft	Offset ft
0 to 2	16
>2 to 4	18
>4 to 6	20
>6 to 8	22
>8 to 10	24




Typical Section (with curb)
Residential or Business District



Stop Sign Location
Wide Throat Intersection

This layout is to be used for the placement of "Stop" signs.

Radius ft.	Y-max. ft.	Y-min. ft.
40	50	15
45	50	18
50	50	21
55	50	25
60	50	28
65	50	32
70	50	35
75	50	39
80	50	43





Shared Use Path
Bicycle - Pedestrian Path

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-3-13	
REVISIONS	
DATE	CHANGE
7-8-14	Revised note 2, added note 4.

This document was originally issued and sealed by
Roger Weigel
 Registration Number
 PE-2930,
 on 7/8/14 and the original document is stored at the
 North Dakota Department
 of Transportation


Number of Posts	Telescoping Perforated Tube						
	Post Size In.	Wall Thickness Gauge	Sleeve Size In.	Wall Thickness Gauge	Slip Base	Anchor Size Without Slip Base In.	Anchor Wall Thickness Gauge
1	2	12			No	2 1/2	12
1	2 1/2	12			No	2 1/2	12
1	2 1/2	12			(B)	3(C)	7
1	2 1/2	10			Yes		7
1	2 1/2	12	2 1/2(D)	12	Yes		7
1	2 1/2	12	2 1/2	12	Yes		7
2	2 1/2	10			Yes		7
2	2 1/2	12	2 1/2(D)	12	Yes		7
2	2 1/2	12	2 1/2	12	Yes		7
3 & 4	2 1/2	12			Yes		7
3 & 4	2 1/2	10			Yes		7
3 & 4	2 1/2	12	2 1/2	12	Yes		7
3 & 4	2 1/2	12	2 1/2(D)	12	Yes		7
3 & 4	2 1/2	10	2 1/2	10	Yes		7

(B) - The 2 1/2", 12 gauge posts do not need breakaway bases when placed in standard soils, but require a shim as specified by the manufacturer. The breakaway base is required when the support is placed in weak soils. The Engineer shall determine if the soils are weak. Weak soils are classified as boggy, wet, or loose soil areas.
 (C) - 3" anchor unit
 (D) - 2 1/2" x 12 ga. x 18" minimum length external sleeve required.




MULTI-DIRECTIONAL SLIP BASE ASSEMBLY:
 2 1/2" x 12 ga. may be inserted with 2 1/2" x 12 ga. & 2 1/2" 10 ga. may be inserted with 2 3/8" x 10 ga. to achieve higher load ability.

Mounting Details Perforated Tube




SLIP BASE FOR 2 1/2" POST



2 1/2" SQUARE POST RECEIVER

Ductile Iron Casting class 65-45-12. Hot Dip Galvanize ASTM A153




SLIP BASE DETAIL

Properties of Telescoping Perforated Tubes						
Tube Size In.	Wall Thickness in.	U.S. Standard Gauge	Weight Per Foot Lbs.	Moment of Inertia In. ⁴	Cross Sect. Area In. ²	Section Modulus In. ³
1 1/2 x 1 1/2	0.105	12	1.702	0.129	0.380	0.172
2 x 2	0.105	12	2.416	0.372	0.590	0.372
2 1/2 x 2 1/2	0.105	12	2.773	0.561	0.695	0.499
2 3/8 x 2 3/8	0.135	10	3.432	0.605	0.841	0.590
2 1/2 x 2 1/2	0.105	12	3.141	0.804	0.803	0.643
2 1/2 x 2 1/2	0.135	10	4.006	0.979	1.010	0.783


The 2 3/8" size 10 gauge is shown as 2.19" size on the plans; The 2 1/2" size is shown as 2.51" size on the plans.

NOTE:


- 4" Vertical clearance of anchor or breakaway base. The 4" x 60" measurement shall be made above and below post location and also back and ahead of post.
- Anchor material shall be 7 gauge H.R.P.O. Commercial quality ASTM A569 and 3" x 3" x 7" gauge ASTM A500 grade B. Anchor shall have a yield strength 43.9 KSI and tensile strength of 59.3 KSI. Anchor shall be hot dipped galvanized per ASTM A123/153. All tolerances on anchor unit and slip base bottom assembly are +/- 0.005" unless otherwise noted.
- When used in concrete sidewalk, anchor shall be the same concept without the wings.
- Four post signs shall have over 8" between the first and fourth posts.
- Installation procedures as per manufacturers recommendation.
- Concrete fasteners for surface mount breakaway base shall be a minimum 1/2" diameter x 4" grade 8.



SURFACE MOUNT ANCHOR BASE



3" ANCHOR UNIT



SHOULDER BOLT
 Shimming agent to reduce tolerance between 3" anchor unit and 2 1/2" post. (standard 3/8" diameter grade 8 bolt may be used with proper shim)



NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-6-09	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930, on 08/06/09 and the original document is stored at the North Dakota Department of Transportation

Breakaway Coupler System for Perforated Tubes

Notes:


- 4" Vertical clearance of anchor or breakaway base. The 4" x 60" measurement shall be made above and below post location and also back and ahead of post.
- Anchor unit shall be the same size as the post and shall have the same specification as the post.
- Four post signs shall have over 8' between the first and fourth post.
- In lieu of the breakaway base system on standard D-754-24 the breakaway coupling system may be used. The breakaway coupler system shall be manufactured from material meeting the requirements of ASTM A325 fasteners with the special requirements as specified by DENT BREAKAWAY IND., INC. which meets the test requirements of NCHRP Report 350.




Number of Posts	Telescoping Perforated Tube						
	Post Size In.	Wall Thickness Gauge	Sleeve Size In.	Wall Thickness Gauge	Slip Base	Anchor Size Without Slip Base In.	Anchor Wall Thickness Gauge
1	2	12			No	2 1/4	12
1	2 1/4	12			No	2 1/2	12
1	2 1/2	12			(B)	3(C)	7
1	2 1/2	10			Yes		7
1	2 1/4	12	2	12	Yes		7
1	2 1/2	12	2 1/4	12	Yes		7
2	2 1/2	10			Yes		7
2	2 1/4	12	2	12	Yes		7
2	2 1/2	12	2 1/4	12	Yes		7
3 & 4	2 1/2	12			Yes		7
3 & 4	2 1/2	10			Yes		7
3 & 4	2 1/2	12	2 1/4	12	Yes		7
3 & 4	2 1/4	12	2	12	Yes		7
3 & 4	2 1/2	10	2 3/16	10	Yes		7

(B) - The 2 1/2" 12 gauge posts do not need breakaway bases when placed in standard soils. The breakaway base is required when the support is placed in weak soils. The Engineer shall determine if the soils are weak. Weak soils are classified as boggy, wet, or loose soil areas.

(C) - 3" anchor unit



Max. protection of the stub post is 4" above a 60" chord aligned radially to the center line of the highway and connecting any point, within the length of the chord, on the ground surface on one side of the support to a point in the ground surface on the other side.




NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-3-2013	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel Registration Number PE-2930, on 10/3/13 and the original document is stored at the North Dakota Department of Transportation


Mounting Details Perforated Tube

Note:

- Horizontal stringers - In lieu of perforated tubes, the contractor may substitute z bar stringers. The z bar stringers shall be 1 1/2" x 3/16" thick, 1.08 lbs./ft aluminum or 3.16 lbs./ft steel.
- Metal washers used on sign face shall have a minimum outside diameter of 5/16" ± 1/65" and 10 gauge thickness.
- No Parking Signs: All no parking signs with directional arrows shall be placed at a 30 to 45 degree angle with the line of traffic flow. No parking signs required at the above angles may have the support turned to the correct angle. If the no parking sign is placed with another sign that has to be placed at a 90 degree angle with the line of traffic flow, the detailed angle strap should be used to mount the no parking sign. Flat washers and lock washers shall be used with all nylon washers.
- In lieu of using the bent bolt to attach the post to the stringer, the contractor may choose to punch the sign backing and place the bolt through the sign, the stringer and the post.
- 4" vertical clearance of anchor or breakaway base. The 4" x 60" measurement shall be made above and below post location and also back and ahead of post.




Side View




Top View

STRINGER MOUNTING
(WITH STRINGER IN FRONT OF POST)




These stringers shall be the same size as the post. Punch round and partial through angle so that excess metal fits stringer and post holes.

STREET NAME SIGNS
AND ONE WAY SIGNS
SINGLE POST ASSEMBLY
ONE STRINGER OR
BACK TO BACK MOUNTING




Side View



Top View


STRAP DETAIL



ANCHOR UNIT AND
POST ASSEMBLY


Number of Posts	Telescoping Perforated Tube						
	Post Size In.	Wall Thickness Gauge	Sleeve Size In.	Wall Thickness Gauge	Slip Base	Anchor Size Without Slip Base In.	Anchor Wall Thickness Gauge
1	2	12			No	2 1/4	12
1	2 1/4	12			No	2 1/2	12
1	2 1/2	12			(B)	3(C)	7
1	2 1/2	10			Yes		7
1	2 1/4	12	2 1/2(D)	12	Yes		7
1	2 1/2	12	2 1/4	12	Yes		7
2	2 1/2	10			Yes		7
2	2 1/4	12	2 1/2(D)	12	Yes		7
2	2 1/2	12	2 1/4	12	Yes		7
3 & 4	2 1/2	12			Yes		7
3 & 4	2 1/2	10			Yes		7
3 & 4	2 1/2	12	2 1/4	12	Yes		7
3 & 4	2 1/4	12	2 1/2(D)	12	Yes		7
3 & 4	2 1/2	10	2 3/16	10	Yes		7

(B) - The 2 1/2", 12 gauge posts do not need breakaway bases when placed in standard soils, but require a shim as specified by the manufacturer. The breakaway base is required when the support is placed in weak soils. The Engineer shall determine if the soils are weak. Weak soils are classified as boggy, wet, or loose soil areas.
(C) - 3" anchor unit
(D) - 2 1/2" x 12 ga. x 18" minimum length external sleeve required.




Properties of Telescoping Perforated Tubes						
Tube Size In.	Wall Thickness In.	U.S. Standard Gauge	Weight Per Foot Lbs.	Moment of Inertia In. ⁴	Cross Sect. area In. ²	Section Modulus In. ³
1 1/2 x 1 1/2	0.105	12	1.702	0.129	0.380	0.172
2 x 2	0.105	12	2.416	0.372	0.590	0.372
2 1/4 x 2 1/4	0.105	12	2.773	0.561	0.695	0.499
2 3/16 x 2 3/16	0.135	10	3.432	0.605	0.841	0.590
2 1/2 x 2 1/2	0.105	12	3.141	0.804	0.803	0.643
2 1/2 x 2 1/2	0.135	10	4.006	0.979	1.010	0.783

The 2 3/16" size 10 gauge is shown as 2.19" size on the plans. The 2 1/2" size is shown as 2.51" size on the plans.



BOLT MOUNTING



Top View

BACK TO BACK
MOUNTING


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-6-09	
REVISIONS	
DATE	CHANGE
7-8-14	Revised Note 3

This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930, on 7/8/14 and the original document is stored at the North Dakota Department of Transportation



SIGN PUNCHING, STRINGER AND SUPPORT LOCATION
DETAILS REGULATORY, WARNING AND GUIDE SIGNS

Notes:



1. See Standard D-754-25 for mounting details.
2. The minimum sign backing material thickness shall be 0.100 inch.
3. Perforated square tube stringer shall be 1½" x 1½".
4. All holes shall be punched round for ⅜" bolt.





Assembly No. 31






Assembly No. 32






Assembly No. 33






Assembly No. 34





Assembly No. 35



Assembly No. 36



Assembly No. 37












NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
12-1-10	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 12-1-10 and the original document is stored at the North Dakota Department of Transportation

SIGN PUNCHING, STRINGER AND SUPPORT LOCATION DETAILS FOR VARIABLE LENGTH SIGNS

D-754-49



3 POSTS			
Sign Length	Sign Overhang	Post Spacing	Bolt Spacing
4'-0"	0'-6"	1'-6"	18"
4'-6"	0'-6"	1'-9"	21"
5'-0"	0'-6"	2'-0"	24"
5'-6"	1'-3"	1'-6"	18"
6'-0"	1'-0"	2'-0"	20"
6'-6"	1'-3"	2'-0"	22"
7'-0"	1'-6"	2'-0"	24"
7'-6"	1'-6"	2'-3"	2-20" & 2-19"
8'-0"	1'-9"	2'-3"	21"
8'-6"	2'-0"	2'-3"	2-22" & 2-23"
9'-0"	1'-6"	3'-0"	24"
9'-6"	1'-9"	3'-0"	4-20" & 1-22"
10'-0"	1'-9"	3'-3"	2-21" & 3-22"
10'-6"	1'-9"	3'-6"	4-23" & 1-22"
11'-0"	2'-0"	3'-6"	24"
11'-6"	2'-3"	3'-6"	21"
12'-0"	2'-4"	3'-8"	22"
12'-6"	2'-5"	3'-10"	23"
13'-0"	2'-6"	4'-0"	24"
13'-6"	2'-9"	4'-0"	3-22" & 4-21"
14'-0"	3'-0"	4'-0"	2-23" & 5-22"
14'-6"	3'-3"	4'-0"	6-23" & 1-24"
15'-0"	3'-6"	4'-0"	24"
15'-6"	2'-4"	5'-5"	6-22" & 2-21"
16'-0"	2'-5"	5'-7"	4-23" & 4-22"
16'-6"	2'-5"	5'-10"	6-23" & 2-24"
17'-0"	2'-6"	6'-0"	24"
17'-6"	3'-3"	5'-6"	22"
18'-0"	3'-6"	5'-6"	6-23" & 3-22"
18'-6"	3'-9"	5'-6"	6-23" & 3-24"
19'-0"	3'-6"	6'-0"	24"
19'-6"	4'-3"	5'-6"	8-22" & 2-23"
20'-0"	4'-4"	5'-8"	8-23" & 2-22"



- Notes:
1. The minimum sign backing material thickness shall be 0.100 inch.
 2. Perforated square tube stringer shall be 1½" x 1½".
 3. All holes shall be punched round for ⅜" bolt.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-25-12	
REVISIONS	
DATE	CHANGE



This document was originally issued and sealed by
Roger Weigel,
Registration Number
PE-2930,
on 9/25/2012 and the original document is stored at the North Dakota Department of Transportation

OBJECT MARKERS - CULVERTS


D-754-83



Mainline Divided Highway
Culvert Openings Greater than 10'
Multiple Installations




Steel Post Detail
Approx. 2.0 lbs/ft



Aluminum Post Detail
Approx. 0.88 lbs/ft


- Notes:**
- Installation:** Construction requirements shall meet 754.04D. Each end of culverts crossing the roadway within the right-of-way shall be marked with a post as shown. Posts are to be installed in front of the culvert in the direction of travel along the side of the culvert and one foot from the culvert opening unless shown otherwise on the plans.
 - Posts:** Posts shall conform to section 894.04A of the Standard Specifications with the exception that the post may or may not have holes drilled.
 - Basis of Payment:** The quantity will be measured by the number of object markers each installed. All costs for furnishing and installing the markers shall be included in the price bid for the item "Object Markers - Culverts".




NORTH DAKOTA DEPARTMENT OF TRANSPORTATION 8-05-13	
REVISIONS	
DATE	CHANGE
7-7-14	Revised Notes

This document was originally issued and sealed by
Roger Weigel,
Registration Number
PE-2930,
on 7/7/2014 and the original document is stored at the North Dakota Department of Transportation

RUMBLE STRIPS
INTERSTATE HIGHWAYS




Interstate - 13' and 14' Concrete Width Mainline with Asphalt Shoulders



Interstate


NOTES:

1) Discontinue rumble strips through ramps and 100' before and after ramp tapers as shown below.




Entrance Ramp

Exit Ramp




Inset A - Edgeline Rumble Strip

Inset B - Shoulder Rumble Strip



Discontinue rumble strip approx. 12" on both sides of PCC transverse joint



Profile of Rumble Strips - Bituminous and PCC Pavements

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
12-29-09	
REVISIONS	
DATE	CHANGE
2-25-10	Note 4 was added.
9-8-11	Revised Notes and D-760-1


This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 9/8/11 and the original document is stored at the North Dakota Department of Transportation

INTERSTATE PAVEMENT MARKING 4 LANE DIVIDED HIGHWAY


D-762-2

NOTE:

- (A) 4" White edge line
- (B) 4" Yellow edge line
- (C) Assume "varies" to equal 790' for purpose of estimate. The pavement marking shall begin at the beginning of the taper and end at the 8" line.
- (D) Beginning of physical gore to theoretical gore.
- (E) If the distance is less than 350' then extend the 8" channel line to the theoretical gore, otherwise use 195'.
- (F) 195' was used for estimating purposes.
- (G) Not required when crossroad approaches have gravel surface.
- (H) 4' minimum, 15' maximum from the nearest edge of the intersection traveled way.



CROSS-ROAD & STRUCTURE
The engineer in the field shall determine the length to be striped.




BASIS OF ESTIMATE		
LOCATION	ITEM	
Right or Left Side Exit Ramp TAPERED	8" White channel line	580 LF
	24" White stop line	60 LF
	4" White dotted line	148 LF
	4" White edge line	1115 LF
	4" Yellow edge line	1075 LF
Entrance Ramp TAPERED	8" White channel line	390 LF
	4" White dotted line	258 LF
	4" White edge line	1270 LF
	4" Yellow edge line	1075 LF
Right or Left Side Exit Ramp PARALLEL	8" White channel line	396 LF
	24" White stop line	60 LF
	4" White dotted line (C)	258 LF
	4" White edge line	1115 LF
	4" Yellow edge line	1075 LF
Entrance Ramp PARALLEL	8" White channel line	388 LF
	4" White dotted line	283 LF
	4" White edge line	1275 LF
	4" Yellow edge line	1075 LF
Main Line (Both Roadways)	4" White line, 10' line, 30' skip	2840 LF/M
	4" White edge line	10,560 LF/M
	4" Yellow edge line	10,560 LF/M
Cross Road	4" White edge line	2000 LF
	4" Dotted yellow barrier line (4" between)	2000 LF


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-3-11	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by
Roger Weigel,
 Registration Number
PE-2930,
 on **08/03/11** and the original document is stored at the
 North Dakota Department
 of Transportation


PAVEMENT MARKING




Two Lane Two Way
RURAL ROADWAY




Two Lane Roadway
INTERSTATE HIGHWAY
Concrete Section




RURAL FIVE LANE ROADWAY
Concrete Section




Two Lane Divided
Rural Roadway
PRIMARY HIGHWAY
Asphalt Section




RURAL FIVE LANE ROADWAY
Asphalt Section




URBAN FIVE LANE SECTION
Concrete Section




Two Lane Roadway
PRIMARY HIGHWAY
Concrete Section




URBAN FIVE LANE SECTION
Asphalt Section




RURAL FOUR LANE ROADWAY
Asphalt Section




Two Lane Roadway
INTERSTATE HIGHWAY
Asphalt Section




RURAL FOUR LANE ROADWAY
Concrete Section



URBAN FOUR LANE SECTION
Asphalt Section



URBAN FOUR LANE SECTION
Concrete Section




CENTERLINE PAVEMENT MARKING SKIP SPACING DETAIL

NOTES:
1. Edge lines shall be continued through private drives and field drives and broken for intersections.


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
12-1-10	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 12-1-10 and the original document is stored at the North Dakota Department of Transportation

SHORT-TERM PAVEMENT MARKING




Painted or Tape Lines




Raised Pavement Markers

TWO-LANE TWO-WAY ROADWAY




Painted or Tape Lines




Raised Pavement Markers

FOUR LANE ROADWAY




Painted or Tape Lines




Raised Pavement Markers

FIVE LANE ROADWAY TWO WAY LEFT TURN



Painted or Tape Lines



Raised Pavement Markers

FIVE LANE ROADWAY WITH MARKED ISLANDS

NOTES:

1. Two-lane two-way roadways shall have no passing zones placed as shown. No passing zone signs may be placed in lieu of short term no passing zone pavement markings. These signs will be allowed to remain in place for three days, at which time the short term no passing zone pavement marking shall be placed.
2. Short term center line stripe (paint) on top lift shall be carefully placed with exact spacing so that the permanent stripe will match when applied.
3. Raised markers and tape markings shall be removed after permanent pavement marking has been installed. Removed markings shall become the property of the contractor.




NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
12-1-10	
REVISIONS	
DATE	CHANGE
3-29-16	Re-numbered to be D-762-11 (previously was D-762-6)

This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930, on 03/29/16 and the original document is stored at the North Dakota Department of Transportation



W-BEAM GUARDRAIL GENERAL DETAILS

NOTES:


1. ReflectORIZED plates: Reflector plates shall begin at the first post and be spaced at 25' centers on guardrail less than 250' in length and at 50' centers for guardrail over 250' in length. The reflector shall be the same color as the pavement marking adjacent to that reflector unless noted otherwise on the plans.
2. Manner of replacing bituminous material at guardrail post: All excess earth from excavations for guard posts shall be disposed of as directed by the engineer. Replace bituminous material wherever guardrail is installed after mat has been laid. Cost of excavation and replacing of bituminous material to be included in the price bid for other items.
3. The Object Marker shall fit within the vertical edges of the Impact Plate. The retroreflective sheeting shall be type XI sheeting meeting the requirements of Section 894.02.B of the standard specifications. The sheeting shall be applied to 0.100 Aluminum sheeting meeting the requirements Section 894.01.A. The Object Marker shall attach to the Impact Head Plate with rivets or some other attachment device. The rivets or attachment device shall be non-rust. The stripes shall slope downward toward the roadway side.
4. Guardrail installation height tolerance = $-\frac{1}{4}"$, $+1"$.




REFLECTORIZED PLATE DETAIL
Additional reflectors are added to the W-beam guardrail quantities for placement on end treatment.




W BEAM TERMINAL CONNECTOR




TYPICAL POST ATTACHMENT DETAIL




C6x8 RUB RAIL AND SPLICE PLATE




6"x8" TIMBER POST & BLOCK




SPLICE DETAIL




5/8" Diameter Guardrail Bolt	
L	Thread Length
1 1/4"	Full length thread
2"	1 3/4" Min thread length
9 1/2"	4" Min thread length
18"	4" Min thread length
20"	4" Min thread length
22"	4" Min thread length
25"	4" Min thread length




5/8" Diameter Carriage Bolt	
L	Thread Length
1 1/2"	Full length thread
3"	1 1/2" Min thread length
11"	1 3/4" Min thread length
13"	1 3/4" Min thread length




5/8" CARRIAGE BOLT & NUT



IMPACT HEAD OBJECT MARKER



W-BEAM CROSS SECTION




5/8" GUARDRAIL BOLT & RECESS NUT

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-11-13	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 10/11/13 and the original document is stored at the North Dakota Department of Transportation

SEQUENTIAL KINKING TERMINAL


D-764-5



PLAN



ELEVATION




SIDE VIEW

FRONT VIEW

POST #1 CONNECTION DETAILS


SIDE VIEW DETAIL OF POST #2

IMPACT HEAD CONNECTION DETAIL



SECTION A-A
Post #2

SECTION B-B
Posts #3 through #8



FLARED INSTALLATION
25:1 maximum flare rate

GENERAL NOTES:

- Breakaway posts are required with the SKT.
- All bolts, nuts, cable assemblies, cable anchors and bearing plates shall be galvanized.
- The SKT can be flared at a rate of up to 25:1 to prevent the impact head from encroaching on the shoulder.
- The lower sections of the posts shall not protrude more than 4" above the ground (measured along a 5' cord). Site grading may be necessary to meet this requirement.
- The lower section of the hinged posts should not be driven with the upper post attached. If the post is placed in a drilled hole, the backfill material must be satisfactorily compacted to prevent settlement.
- When rock is encountered, a 10" diameter post hole, 20" into the rock surface may be used if approved by the engineer. Granular material will be placed in the bottom of the hole, approximately 2 1/2" deep to provide drainage. Posts 1 & 2 can be field cut to length, placed in the hole and backfilled with adequately compacted material excavated from the hole.
- The breakaway cable assembly must be taut. A locking device (vice grips or channel lock pliers) should be used to prevent the cable from twisting when tightening nuts.
- The wood blockouts on post #3 through post #8 should be "toe nailed" with two 20 penny galvanized nails into each rectangular post, to prevent them from turning when the wood shrinks.



ITEM QTY		BILL OF MATERIALS
A	1	IMPACT HEAD
B	1	W-BEAM GUARDRAIL END SECTION, 12 Ga
C	3	W-BEAM GUARDRAIL, 12 Ga
D	1	FIRST POST ASSEMBLY TOP
E	1	FIRST POST ASSEMBLY BOTTOM
F	1	SECOND POST ASSEMBLY TOP
G	1	SECOND POST ASSEMBLY BOTTOM
K	1	BEARING PLATE
L	1	CABLE ANCHOR BOX
M	1	BCT CABLE ANCHOR ASSEMBLY
N	1	GROUND STRUT HINGED POST
P	6	WOOD CRT POST
R	6	TIMBER BLOCKOUT/RCY EQUIVALENT
HARDWARE		
a	2	1/4" x 4" HEX BOLT Grade 5
b	4	1/4" WASHER
c	2	1/4" HEX NUT
d	25	5/8" Dia x 1 1/4" SPLICE BOLT, POST #2
e	6	5/8" Dia x 18" H.G.R. BOLT (POSTS 3 THRU 8)
f	1	5/8" Dia x 9" HEX BOLT GRD 5
g	8	5/8" WASHER
h	32	5/8" Dia H.G.R. NUT
j	1	3/4" Dia x 8 1/2" HEX BOLT GRD A449
k	1	3/4" Dia HEX NUT
l	2	1" ANCHOR CABLE HEX NUT
m	2	1" ANCHOR CABLE WASHER
n	8	CABLE ANCHOR BOX SHOULDER BOLT
o	8	1/2" A325 STRUCTURAL NUT
p	16	1 1/16" OD x 3/16" ID A325 STR. WASHER

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION 10-11-13	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 10/11/13 and the original document is stored at the North Dakota Department of Transportation

FLARED ENERGY ABSORBING TERMINAL



D-764-6





ITEM #	QTY	BILL OF MATERIALS
F3000	1	IMPACT HEAD
F1303	1	W-BEAM GUARDRAIL END SECTION, 12 GA
G1203	2	W-BEAM GUARDRAIL, 12 GA
HP1A	1	FIRST POST ASSEMBLY TOP
HP1B	1	FIRST POST ASSEMBLY BOTTOM
HP2A	1	SECOND POST ASSEMBLY TOP
HP2B	1	SECOND POST ASSEMBLY BOTTOM
P671	5	WOOD CRT POST
P675	5	TIMBER BLOCKOUT OR RECYCLED EQUIVALENT
E750	1	BEARING PLATE
S760	1	CABLE ANCHOR BOX
E770	1	BCT CABLE ANCHOR ASSEMBLY
S785	1	GROUND STRUT HINGED POST
HARDWARE (ALL DIMENSIONS IN INCHES)		
B140404	2	1/4 Dia x 4 HEX BOLT
WO14	4	1/4 WASHER
N014	2	1/4 HEX NUT
B580122	17	5/8 Dia x 1 1/4 SPLICE BOLT
B581802	4	5/8 Dia x 10 H.G.R. BOLT (POSTS 3 THRU 6)
B580904A	1	5/8 Dia x 9 HEX BOLT GR 5
W050	5	5/8 WASHER
N050	22	5/8 Dia H.G.R. NUT
B340854A	1	3/4 Dia x 8 1/2 HEX BOLT GR A449
N030	1	3/4 Dia HEX NUT
N100	2	1 ANCHOR CABLE HEX NUT
W100	2	1 ANCHOR CABLE WASHER
SB58A	8	CABLE ANCHOR BOX SHOULDER BOLT
N055A	8	1/2 A325 STRUCTURAL NUT
W050A	16	1 1/16 OD x 3/16 ID A325 STR. WASHER

GENERAL NOTES


- Wood posts are required with the Flared Energy Absorbing Terminal except posts #1 and #2.
- All bolts, nuts, cable assemblies, cable anchors and bearing plates shall be galvanized.
- The lower sections of the posts shall not protrude more than 4 inches above the ground (measured along a 60 inch cord). Site grading may be necessary to meet this requirement.
- Lower post sections shall not be driven with the upper post attached. If the post is placed in a drilled hole, the backfill material must be satisfactory compacted to prevent settlement.
- When rock is encountered during excavation, a 12" diameter post hole 20" deep may be used if approved by the Engineer. Granular material will be placed in the bottom of the hole approximately 2 1/2" deep to provide drainage. The soil tubes shall be field cut to length, placed in the hole and back filled with adequately compacted material excavated from the hole.
- The breakaway cable assembly shall be taut. A locking device (vice grips or channel lock pliers) should be used to prevent cable from twisting when tightening nuts.
- The wood blockouts shall be "toe nailed" to the rectangular wood posts to prevent them from turning when wood shrinks. The nail shall be 20 penny and galvanized.
- The Flared Energy Absorbing Terminal shall be flared only when the approach guardrail is parallel with the roadway. When the approach guardrail is flared at 16:1 to 10:1, the Flared Energy Absorbing Terminal shall have only the flare rate of the guardrail. When the guardrail flare is between 10:1 and 7:1, the Flared Energy Absorbing Terminal shall be turned parallel to the roadway.




POST #1 CONNECTION DETAILS




IMPACT HEAD CONNECTION DETAIL



SECTION B-B
POST 3 THRU 7



SECTION A-A
at Post #2




IMPACT HEAD CONNECTING DETAIL

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-11-13	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 10/11/13 and the original document is stored at the North Dakota Department of Transportation

THRIE BEAM TRANSITION TO DOUBLE BOX BEAM RETROFIT


D-764-10




THRIE BEAM TERMINAL CONNECTOR






THRIE BEAM END VIEW



W-BEAM END VIEW



THRIE BEAM TO W-BEAM TRANSITION SECTION




NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-11-13	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 10/11/13 and the original document is stored at the North Dakota Department of Transportation

MGS FLARED ENERGY ABSORBING TERMINAL - WOOD POST


D-764-38




PLAN




ELEVATION



SIDE VIEW




DETAIL C
Post 1 (Impact Head connection)




SECTION A-A
Post 2

SECTION B-B
Posts 3 through 7




FRONT VIEW

DETAIL A
Post 1



DETAIL B
Post 2



SECTION C-C

GENERAL NOTES:

- Wood posts are required with the Flared Energy Absorbing Terminal except posts 1 and 2.
- Galvanize all bolts, nuts, cable assemblies, cable anchors, and bearing plates.
- Flare the Flared Energy Absorbing Terminal when the approach guardrail is parallel with the roadway. When the approach guardrail is flared at 16:1 to 10:1, ensure the Flared Energy Absorbing Terminal has only the flare rate of the guardrail. When the guardrail flare is between 10:1 and 7:1, ensure the Flared Energy Absorbing Terminal is turned parallel to the roadway.
- Ensure the lower sections of the posts do not protrude more than 4" above the ground (measured along a 5' cord). Site grading may be necessary to meet this requirement.
- Install the lower section of the hinged posts without the upper post attached. If the post is placed in a drilled hole, the backfill material must be compacted to prevent settlement.
- The breakaway cable assembly must be taut. Use a locking device (vice grips or channel lock pliers) to prevent cable from twisting when tightening nuts.
- "Toe nail" the wood blockouts to the rectangular wood posts. Use two 20 penny galvanized nails.

ITEM	ITEM NO.	BILL OF MATERIALS	QTY
A	F3000	IMPACT HEAD	1
B	SF1303	W-BEAM GUARDRAIL END SECTION, 12 Ga	1
C	G12025	9'-4 1/2" MGS W-BEAM RAIL SECTION, 12 Ga	1
D	G1203A	12'-6" MGS W-BEAM RAIL SECTION, 12 Ga	2
E	UHP1A	FIRST POST ASSEMBLY TOP	1
F	HP1B	FIRST POST ASSEMBLY BOTTOM	1
G	UHP2A	SECOND POST ASSEMBLY TOP	1
H	HP2B	SECOND POST ASSEMBLY BOTTOM	1
J	UP671	WOOD CRT POST	5
K	P675	WOOD BLOCKOUT OR RECYCLE EQUIVALENT	5
L	E750	BEARING PLATE	1
M	S760	CABLE ANCHOR BOX	1
N	E770	BCT CABLE ANCHOR ASSEMBLY	1
O	S785	GROUND STRUT HINGED POST	1
HARDWARE			
a	B5160304A	5/16" x 3" HEX BOLT A325	2
b	W0516	5/16" WASHER	4
c	N0516	5/16" HEX NUT	2
d	B580122	5/8" Dia x 1 1/4" SPLICE BOLT	33
e	B581802	5/8" Dia X 18" HGR BOLT	5
f	B580904A	5/8" Dia x 9" HEX BOLT GRD 5	1
g	W050	5/8" WASHER	7
h	N050	5/8" Dia HGR NUT	39
j	B340854A	3/4" Dia x 8 1/2" HEX BOLT GRD A449	1
k	N030	3/4" Dia HEX NUT	1
i	N100	1" ANCHOR CABLE HEX NUT	2
m	W100	1" ANCHOR CABLE WASHER	2
n	SB12A	1/2" RSI SHOULDER BOLT WITH WASHER	8
o	N012A	1/2" STRUCTURAL NUT	8
p	W012A	1/2" STRUCTURAL WASHER	8
r	CT-100ST	BEARING PLATE RETAINER TIE	1

NOTE: Standard wood line post, block, and associated hardware not included in Bill of Materials Table.


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
7-14-17	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 7/14/17 and the original document is stored at the North Dakota Department of Transportation


MGS W-BEAM GUARDRAIL GENERAL DETAILS

NOTES:


1. Begin reflector plates at the first post and space at 25' centers on guardrail less than 250' length and at 50' centers for guardrail over 250' length. Provide the reflector the same color as the pavement marking adjacent to it unless noted otherwise on the plans.
2. Replacing bituminous material at guardrail post: Dispose all excess earth from excavations for guard posts as directed by the engineer. Replace bituminous material wherever guardrail is installed after mat has been laid. Cost of excavation and replacing of bituminous material to be included in the price bid for other items.
3. Fit the Object Marker within the vertical edges of the Impact Plate. Provide type XI retroreflective sheeting meeting the requirements of Section 894.02.E of the standard specifications. Apply the sheeting to 0.100 Aluminum sheeting meeting the requirements of Section 894.01.A. Attach the Object Marker to the Impact Head Plate with rivets or other attachment device. Ensure the rivets or attachment device are non-rust. Slope the stripes downward toward the roadway side.
4. Guardrail installation height tolerance = ±1".




Splice Plate




Splice Detail





C6x8.2 RUB RAIL AND SPLICE PLATE




5/8" Diameter Guardrail Bolt	
L	Thread Length
1 1/4"	Full length thread
2"	1 3/4" Min thread length
9 1/2"	4" Min thread length
18"	4" Min thread length
20"	4" Min thread length
22"	4" Min thread length
25"	4" Min thread length



5/8" GUARDRAIL BOLT & RECESS NUT




W BEAM TERMINAL CONNECTOR




SPLICE DETAIL


NOTE: Do not install center bolt in the 3/4" x 2 1/2" slot at mid span splices.



5/8" Diameter Carriage Bolt	
L	Thread Length
1 1/2"	Full length thread
3"	1 1/2" Min thread length
11"	1 3/4" Min thread length
13"	1 3/4" Min thread length




5/8" CARRIAGE BOLT & NUT




REFLECTORIZED PLATE DETAIL

NOTE: Additional reflectors are added to the W-beam guardrail quantities for placement on end treatment.




TYPICAL WOOD POST ATTACHMENT DETAIL




6" x 8" WOOD POST & BLOCK


NOTE: Where soil conditions require, alternate lengths may be specified, in 6" increments.




IMPACT HEAD OBJECT MARKER



STANDARD MGS GUARDRAIL PANEL



STANDARD MGS GUARDRAIL SYSTEM




W-BEAM CROSS SECTION

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
7-14-17	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 7/14/17 and the original document is stored at the North Dakota Department of Transportation

TYPICAL GRADING AT BRIDGE ENDS
WITH MGS W-BEAM GUARDRAIL


D-764-48




TYPICAL SECTION



PLAN LAYOUT
FLARED GUARDRAIL WITH END TERMINAL



PLAN LAYOUT
NON-FLARED GUARDRAIL WITH TANGENT END TERMINAL



PLAN LAYOUT
NON-FLARED GUARDRAIL WITH FLARED END TERMINAL

NOTES:

- (A) Slope flatter than 10:1 may be required to provide proper guardrail height.
- (B) Where normal foreslope is 4:1 the added fill shall be 4:1. Where normal foreslope is 6:1 the added fill shall be 6:1.
- (C) Measured from top of guardrail to top of surfacing at front face of guardrail.
- (D) Dimension at end terminals may vary per Plan Layouts shown on this sheet.

NORTH DAKOTA
DEPARTMENT OF TRANSPORTATION

7-14-17



REVISIONS

DATE	CHANGE


This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 7/14/17 and the original document is stored at the North Dakota Department of Transportation

MASH SOFTSTOP END TERMINAL - STEEL POST


D-764-50




DETAIL E
Posts 1 & 2




DETAIL A
Post 0




DETAIL B
Post 0




DETAIL C
Post 1
(shown near ground)




SECTION A-A
Post 2



SECTION B-B
Posts 3 through 8



DETAIL D
Post 1



FLARED INSTALLATION
25:1 maximum flare rate

- GENERAL NOTES:
- Galvanize all bolts, nuts, cable assemblies, cable anchors, and bearing plates.
 - The SoftStop can be flared at a rate of 25:1 or flatter.
 - Do not curve the guardrail within the SoftStop under any circumstances.
 - It is acceptable to install the SoftStop impact head parallel to the grade line or with an upward tilt. See softstop assembly manual for specific details.

ITEM	ITEM NO.	BILL OF MATERIALS	QTY
A	000011	12 / 12'-6" / 3'-1 1/2" / S MGS W-BEAM RAIL SECTION	3
B	000533	6'-0" STEEL POST W6 x 8.5	6
C	006777	KING BLOCK 4" X 7 1/2" X 1'-2"	7
D	015000	6'-0" SYT POST / 8.5 / 31" GR HT	1
E	015200	SFST - ANCHOR GUARDRAIL 12'-6"	1
F	015201	SFST - ANCHOR ANGLE	2
G	015202	SFST - ANGLE STRUT	1
H	015203	SFST - POST #1 SYTP	1
J	015204	SFST - ANCHOR PADDLE	1
K	015205	SFST - POST #0	1
L	015206	SFST - PLATE WASHER	1
M	015207	SFST - KEEPER PLATE	1
N	015208	SFST - IMPACT HEAD	1



HARDWARE			
a	003240	5/16" ROUND WASHER WIDE	6
b	003245	5/16" HEX NUT	3
c	003340	5/8" GR HEX NUT	41
d	003360	5/8" x 1 1/4" GR BOLT	32
e	003391	5/8" x 1 3/4" HEX BOLT A325	1
f	003500	5/8" x 10" GR BOLT A307	7
g	003701	3/4" ROUND WASHER F436	4
h	003704	3/4" HVY HEX NUT A563 DH	2
j	003717	3/4" x 2 1/2" HEX BOLT A325	2
k	003908	1" HVY HEX NUT A563 DH	1
l	004372	5/8" WASHER F436	4
m	004489	5/8" x 9" HEX BOLT A325	1
n	004902	1" ROUND WASHER F436	1
o	105285	5/16" x 2 1/2" HEX BOLT GRD 5	2
p	105286	5/16" x 1 1/2" HEX BOLT GRD 5	1

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
7-14-17	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 7/14/17 and the original document is stored at the North Dakota Department of Transportation

MASH SEQUENTIAL KINKING TERMINAL - WOOD POST








D-764-51



- GENERAL NOTES:
- Galvanize all bolts, nuts, cable assemblies, cable anchors, and bearing plates.
 - The MSKT can be flared at a rate of up to 25:1 to prevent the impact head from encroaching on the shoulder.
 - Ensure the lower sections of the posts do not protrude more than 4" above the ground (measured along a 5' cord). Site grading may be necessary to meet this requirement.
 - Install the lower section of the hinged posts without the upper post attached. If the post is placed in a drilled hole, the backfill material must be compacted to prevent settlement.
 - The breakaway cable assembly must be taut. Use a locking device (vice grips or channel lock pliers) to prevent the cable from twisting when tightening nuts.
 - "Toe nail" the wood blockouts to the rectangular wood posts at post 3 through post 8. Use two 20 penny galvanized nails.

ITEM	ITEM NO.	BILL OF MATERIALS	QTY
A	MS3000	IMPACT HEAD	1
B	SF1303	W-BEAM GUARDRAIL END SECTION, 12 Ga	1
C	G12025	9'-4 1/2" MGS W-BEAM RAIL SECTION, 12 Ga	1
D	G1203A	12'-6" MGS W-BEAM RAIL SECTION, 12 Ga	2
E	MTPHP1A	FIRST POST ASSEMBLY TOP (6" X 6" X 1/2" Tube)	1
F	MTPHP1B	FIRST POST ASSEMBLY BOTTOM (6" W6X15)	1
G	UHP2A	SECOND POST ASSEMBLY TOP	1
H	HP2B	SECOND POST ASSEMBLY BOTTOM	1
K	E750	BEARING PLATE	1
L	S760	CABLE ANCHOR BOX	1
M	E770	BCT CABLE ANCHOR ASSEMBLY	1
N	MS785	STRUT	1
P	UP671	6" WOOD CRT POST	6
R	P675	WOOD BLOCKOUT OR RECYCLED EQUIVALENT	6

HARDWARE			
a	B5160104A	5/16" x 1" HEX BOLT GR 5	2
b	W0516	5/16" WASHER	4
c	N0516	5/16" HEX NUT	2
d	B580122	5/8" Dia x 1 1/4" SPLICE BOLT	33
e	B581802	5/8" Dia x 18" HGR BOLT (POSTS 3 THRU 8)	6
f	B580904A	5/8" x 9" HEX BOLT GR 5	2
g	W050	5/8" WASHER	9
h	N050	5/8" Dia HGR NUT	35
j	B340854A	3/4" Dia x 8 1/2" HEX BOLT GRD A449	1
k	N030	3/4" Dia HEX NUT	1
l	N100	1" ANCHOR CABLE HEX NUT	2
m	W100	1" ANCHOR CABLE WASHER	2
n	SB12A	1/2" RSI SHOULDER BOLT WITH WASHER	8
o	N012A	1/2" STRUCTURAL NUT	8
p	W012A	1/2" STRUCTURAL WASHER	8
r	CT-100ST	BEARING PLATE RETAINER TIE	1





NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
7-14-17	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 7/14/17 and the original document is stored at the North Dakota Department of Transportation

MGS W-BEAM TRANSITION WITH APPROACH CURB TO CONCRETE SINGLE SLOPE OR JERSEY BARRIER

D-764-60




5 - 7/8" Dia. (ASTM A325 or A449) Heavy Hex Head Bolts, with two 1 1/2" O.D. washers under each head and nut. Bolts shall be of sufficient length to extend through the full thickness of the rail, washer, and nut. Install with bolt heads on traffic face.





TRANSITION POST AND TIMBER BLOCKOUT SIZING		
POST NO.	POST SIZE	BLOCKOUT SIZE
1-6	6" X 8" X 7'-0" long	6" X 8" X 19"
7-12	6" X 8" X 6'-0" long	6" X 8" X 19"
13-16	6" X 8" X 6'-0" long	6" X 8" X 14"


ELEVATION VIEW



NON - SYMMETRICAL TRANSITION TO W-BEAM (10 GAUGE)



CONNECTION TO CONCRETE SINGLE SLOPE BRIDGE RAIL AND TRAFFIC BARRIERS




CONNECTION TO CONCRETE JERSEY BARRIER BRIDGE RAIL AND TRAFFIC BARRIERS

- (A) Where curb is required to continue past 15' length, taper the curb down to 3" height at the terminal point shown above, instead of 0" height. Between posts 10 and 16 the curb must be 3" height.
- (B) Install a 12'-6" length W-beam double rail section at this location where curb extends past 15' length.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
7-14-17	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 7/14/17 and the original document is stored at the North Dakota Department of Transportation

SINGLE SLOPE TO THRIE BEAM CONNECTOR PLATE DETAILS




PLAN


NOTE: Assembly Detail is shown for guardrail installation on right hand side of entrance end of bridge barrier. Mirror for opposite side installation.



SECTION A-A




PICTORIAL DRAWING
(Showing Back of Connector Plate)




ELEVATION

ASSEMBLY DETAIL
(Front View)



END



ELEVATION

WELDING DETAIL
(Back View)

WELDING INSTRUCTIONS:

- (A) Cover plate P3 shall be welded as follows: 3/16" continuous back weld on exterior sides and 3/16" fillet weld 1" long spaced at 2" center-to-center on interior sides.
- (B) Stiffeners located on the inside of the cover plates shall be welded as follows: 3/16" fillet weld 1" long spaced at 2" center-to-center.
- (C) Cover plates P1 and P2 shall be welded together with full penetration groove weld.




PLATE P3
Quantity: 1






PLATE P2
Quantity: 1

PLATE P1
Quantity: 1


COVER PLATES




TYPE S1
Quantity: 4



TYPE S7
Quantity: 1




TYPE S8
Quantity: 1




TYPE S9
Quantity: 1

VERTICAL PLATES




TYPE S10
Quantity: 1




TYPE S11
Quantity: 1


STIFFENER PLATES




TYPE S2
Quantity: 1




TYPE S3
Quantity: 1



TYPE S4
Quantity: 1



TYPE S5
Quantity: 1



TYPE S6
Quantity: 1


HORIZONTAL PLATES

NOTES:


- 1. Cover plates P1, P2, and P3 shall be fabricated from 3/16" thick ASTM A36 Grade structural steel.
- 2. Stiffener plates shall be fabricated from 1/4" thick ASTM A36 Grade structural steel.
- 3. Connector plate shall be galvanized in accordance with AASHTO M111.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
7-14-17	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 7/14/17 and the original document is stored at the North Dakota Department of Transportation




GENERAL LAYOUT FOR SINGLE SPAN




GENERAL LAYOUT FOR MULTIPLE SPAN

BRIDGE BENCH MARKS



CHECK POINT LOCATION DETAIL



BENCH MARK DETAIL

NOTES:

Elevation check points shall consist of $\frac{3}{8}$ " \varnothing x 3" galvanized carriage bolts (or equal) set in the concrete barrier at the points indicated on the General Layout sketches. The top of the bolt head shall project above the finished concrete $\frac{1}{8}$ ". Elevation check points shall be placed on each barrier over each unit of the substructure for each bridge at a structural location.

Two bench marks as detailed hereon shall be set at diagonal opposite positions away from the structure location and at least 300 feet from the nearest point on the bridge or bridges (if more than one at a location). These bench marks shall be constructed as detailed on this sheet and located near the Highway Right of Way lines. The two pipes shall extend 4'-0" above ground and be painted with two coats of white paint suitable for galvanized steel surfaces.

The Project Engineer shall run a set of levels determining the elevation of each check point on the structure and the two bench marks immediately after the completion of the bridge. Bench Mark #1 can be listed as having elevation 1000 or the actual surveyed elevation. This information shall be recorded on SFN 13420 and submitted to the Bridge Engineer with adequate information locating each check point and bench mark.

All metal parts are to be hot dip galvanized after punching, shearing, welding and fabrication.

Threads of cap and pipe are not to be galvanized. At the time of installation these threads are to be coated with synthetic grease with teflon and cap screwed to a snug fit.

METHOD OF MEASUREMENT:

Each set of Bridge Bench Marks consisting of two bench marks and the required number of elevation check points shall be considered as one unit for bidding purposes and the quantity to be paid for shall be the number of sets of bridge bench marks which have been installed complete in place and accepted by the Engineer.

BASIS OF PAYMENT:

Bridge Bench Marks shall be paid for at the contract price bid for each set of Bridge Bench Marks, which price shall be full compensation for all excavation, backfill and clean-up, and for furnishing, hauling and placing all elevation check points, galvanized pipe, caps, rods, sand backfill, concrete, rock equipment, tools and incidentals, including galvanizing and greasing, necessary to complete this item.

GALVANIZING:

After fabrication the complete assembly shall be hot-dip galvanized.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
09/14/11	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Terrence R. Udland, Registration Number PE-2674, on 09/14/11 and the original document is stored at the North Dakota Department of Transportation