


TABLE OF CONTENTS						STATE	PROJECT NO.	SECTION NO.	SHEET NO.
						ND	H-7-008(033)133	2	1
PLAN SECTIONS			LIST OF STANDARD DRAWINGS						
Section	Page(s)	Description	Number	Description					
1	1	Title Sheet	D-101-1, 2, 3	NDDOT Abbreviations					
2	1	Table of Contents	D-101-10	NDDOT Utility Company and Organization Abbreviations					
4	1	Scope of Work	D-101-20, 21	Line Styles					
6	1	Notes	D-101-30, 31,32	Symbols					
8	1	Quantities	D-261-1	Erosion Control - Fiber Roll Placement Details					
20	1,2	General Details	D-704-7	Breakaway Systems For Construction Zone Signs - Perforated Tube					
30	1	Typical Sections	D-704-8	Breakaway Systems For Construction Zone Signs - U-Channel Post					
50	1	Inlet and Manhole Summary	D-704-9	Construction Sign Details - Terminal And Guide Signs					
51	1	Allowable Pipe List	D-704-14	Construction Sign Punching And Mounting Details					
75	1	Wetland Impacts	D-704-26	Miscellaneous Sign Layouts					
76	1	Temporary Erosion Control	D-704-50	Portable Sign Support Assembly					
77	1	Permanent Erosion Control	D-708-6	Erosion And Siltation Controls - Median Or Ditch Inlet Protection					
100	1,2	Work Zone Traffic Control	D-714-1	Reinforced Concrete Pipe Culverts And End Sections (Round Pipe)					
			D-714-16	Jacked And Bored Pipe					
			D-714-22	Concrete Pipe Or Precast Concrete Box Culvert Ties					
			D-754-83	Object Markers - Culverts					



NOTES

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	H-7-008(033)133	6	1

107-900 THREE AFFILIATED TRIBES BIA COORDINATION: Coordinate work on lands held in trust by the Bureau of Indian Affairs (BIA), allotted and tribally owned trust land, through the Environmental/Compliance Officer.

Contact:
Jeff Desjarlais
Environmental/Compliance Officer, Ft. Berthold
(701) 627-4707, ext. 244

Coordinate work regarding materials sources, staging areas, office locations, and other activities that are not expressly detailed in the contract documents.

108-500 TERO COORDINATION: Invite the Tribal TERO Office to the Preconstruction Conference.

704-P01 TRAFFIC CONTROL: The traffic control devices shall comply with the following Standard Drawings:

D-704-26, Layout Type Z

714-P01 JACKED PIPE: The method used to install the conduits indicated as jacked on the plans shall be left to the discretion of the Contractor. The boring or jacked methods are acceptable.

If smooth walled steel pipe is to be used, this material shall be welded steel pipe of new material, meeting ASTM Specifications A-139, Grade B with a minimum yield strength of 35,000 psi. No hydrostatic testing will be performed. The following minimum wall thickness shall be used:

Diameter of Pipe	Minimum Wall Thickness Through Roadway Embankment
36 inches	0.469 inch

If the Contractor opts to install reinforced concrete pipe through the roadway, the bored or jacked sections shall be CL IV. Sections which will not be bored or jacked, and end sections may be CL III reinforced concrete pipe.

If the Contractor opts to install smooth wall steel pipe by boring, pipe sections on the upstream end which do not require boring, and the end section, may be either spiral rib corrugated steel pipe having a minimum wall thickness of 0.064 inches, with steel end section, or CL III reinforced concrete pipe with concrete end sections.

Pipe sections on the downstream end which do not require boring, and the end section, shall be reinforced concrete pipe with baffle rings and concrete end section.

Smooth walled steel pipe shall be tied to reinforced concrete as shown on Standard Drawing D-714-16. Connections between smooth walled steel pipe and spiral rib corrugated steel pipe shall be as recommended by the pipe manufacturer, and approved by the Engineer.

Regardless of the method or type of pipe used, the price bid for "Pipe Conduit 36 In – Jacked or Bored" shall be considered full compensation for the pipe and its installation, including all

costs for labor, equipment, excavation, embankment, and materials required for installing the pipe through the roadway by boring or jacking. Contractor must ensure the ditch bottom is graded to drain to/from the new pipe after the application of top soil, mulch, and seed with the in/end slopes matching the grade and slope of the existing pipe. Geosynthetic Material Type R1, Top soil, mulch, and seed are incidental to the cost of the Jack and Bore pipe.

After the installation of the pipe is complete the Contractor will have to prove to the satisfaction of the Engineer that the pipe is free of sediment or debris by passing a culvert cleanout device through the pipe. The device shall have a diameter that is not less than 95% of the inside diameter of the pipe. The test shall be performed a minimum of two weeks after the pipe is installed. All cost to complete this work shall be included in the price bid for "Pipe Conduit 36 In – Jacked or Bored."

This document was originally issued and sealed by Megan L. Isenhowe, Registration Number PE – 8775, on 05/31/18 and the original document is stored at the North Dakota Department of Transportation.

ESTIMATE OF QUANTITIES



STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	H-7-008(033)133	8	1

SPEC CODE	ITEM DESCRIPTION	UNIT	MAINLINE	TOTAL
103	0100 CONTRACT BOND	L SUM	1	1
255	0102 ECB TYPE 2	SY	30	30
256	0100 RIPRAP GRADE I	CY	20	20
261	0112 FIBER ROLLS 12IN	LF	400	400
261	0113 REMOVE FIBER ROLLS 12IN	LF	200	200
702	0100 MOBILIZATION	L SUM	1	1
704	1000 TRAFFIC CONTROL SIGNS	UNIT	434	434
714	4124 PIPE CONDUIT 36IN-JACKED OR BORED	LF	98	98
754	0805 OBJECT MARKERS - CULVERTS	EA	4	4



	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	H-7-008(033)133	20	1

Dia	X	Y	Surface area to be Protected	ECB Type 2
(In)	(Ft)	(Ft)	(SF)	(SY)
36	12.7	23.3	268.8	30

708 5651 ECB TYPE 2				
Location of Surface Area to be Protected	Pipe Dia	No.	Unit Quantity	Total Quantity
ND 8	(In)		(SY)	(SY)
7034+53	36	2	30	30




NOTE: Tuck the ECB a minimum of 6" into the embankment (against the flared end section) around the opening of the flared end section.



This document was originally issued and sealed by Megan L. Isenhowe, Registration Number PE- 8775, on 05/31/18 and the original document is stored at the North Dakota Department of Transportation

Culvert End Protection

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	H-7-008(033)133	20	2




Riprap Dimensions				
Culvert Diameter (inches)	L (feet)	W ₁ (feet)	W ₂ (feet)	Riprap Depth, D (feet)
36	12	9	17	2

Culvert Diameter (inches)	RR Fabric (SY)	Riprap (CY)
36	42	20

Pipe Stations - Riprap at Outlet End	
36" Pipe	7034+53


See Section 77 plan view locations.



This document was originally issued and sealed by
Megan L. Isenhowe
Registration Number
PE- 8775,
on 05/31/18 and the original document is stored at the
North Dakota Department
of Transportation

Riprap at Pipe Outlets

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	H-7-008(033)133	30	1



This document was originally issued and sealed by Megan L. Isenhower, Registration Number PE - 8775, on 05/31/18 and the original document is stored at the North Dakota Department of Transportation.

Typical Section

HYDRAULIC DATA FOR H-7-008(033)133 (A)									
STATION	EXISTING PIPE	PROPOSED PIPE SIZE	DRAINAGE AREA (ACRES)	25-YEAR DATA				100-YEAR DATA	
				DESIGN DISCHARGE (CFS)	DESIGN HEADWATER (FT)	DESIGN VELOCITY (FPS)	DESIGN STAGE (NAVD 88)	100-YEAR DISCHARGE (CFS)	100-YEAR STAGE (NAVD 88)
7034+53	36" RCP	DbI 36" (B)	160.5	46.0	3.12	12.20	2050.93	74.3	2051.92
(A) Hydraulic data provided is for smooth-walled (Manning's n=0.012) type conduits. (B) Existing 36" pipe to remain. Install new 36" pipe at a lower invert than the existing pipe as shown in the plans.									

This document was originally issued and sealed by
Randall Sandvig,
Registration Number
PE- 8783,
on 05/14/18 and the original document is stored at the
North Dakota Department
of Transportation

Culvert Hydraulic Data

Hwy 8
1 Mile North of Jct 23

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	SAP-7-008(025)132	51	1

Begin Station / Location	Begin Offset	End Station / Location	End Offset	Pipe Installation (Pay Item)			Allowable Material	Required Diameter	Steel Pipe Coatings	Steel Pipe Corrugations or Spiral Ribs	Steel Pipe Minimum Thickness	R1 Fabric	(*) End Sections		Applicable Backfill
				In	Bid Item	LF							Begin	End	
								In	Type		In	SY	EA	EA	
7034+53	47' Lt	7034+53	47' Rt	36	Pipe Conduit 36" - Jacked or Bored	98'	Reinforced Concrete Pipe - Class III (barrel length = 96 LF)	36				10	1 (TES)	1 (TES)	D-714-16
							Smooth Walled Steel								

Coatings: Z = Zinc
A = Aluminum
P = Polymeric (over Zinc or Aluminum)

Corrugations: 2 = 2-2/3"x1/2"
3 = 3"x1"
5 = 5"x1"

Spiral Ribs: 3/4 = 3/4"x3/4"@7-1/2"
1 = 3/4"x1"@11-1/2"

FES = Flared End Section
TES = Traversable End Section

This document was originally issued and sealed by Megan L. Isenhower, Registration Number PE- 8775, n 05/31/18 and the original document is stored at the North Dakota Department of Transportation

ALLOWABLE PIPE LIST


(*) Not paid for separately, to be included in the price bid for Pipe Conduit.

Wetland Impact Table												
Wetland Number	Location	Wetland Type	Wetland Feature	USACE Jurisdictional Wetlands ¹	Wetland Impacts Acre(s)		Wetland Mitigation					
							Mitigation Required		USACE/11990 Bank		11990 Bank	
					Temp.	Perm.	EO 11990	USACE	Location	Acre(s)	Location	Acre(s)
1a	Sec. 19, T146N, R95W	Linear Wetland	Natural	Yes	0.04							
1b	Sec. 6, T146N, R95W	Linear Wetland	Natural	Yes								
Totals					0.04							

¹Wetlands were assumed to be jurisdictional and a nonreporting NW3 404 Permit was used.

Impact Summary Table			
Permanent Impact Summary		Temporary Impacts and additional information	
Wetland Type	Total (Acres)	Wetland Type	Total (Acres/Lf)
Natural/JD		Temporary JD	0.04
Natural/Non-JD		Non-JD Temporary	
Artificial/JD		Permanent JD > 0.10	
Artificial /Non-JD		Permanent OW	
Total	0.00	Temporary OW	


Mitigation Summary Table					
	Location	Onsite Acre(s)	11990 Bank Acre(s)	USACE/11990 Bank Acre(s)	USFWS Bank Acre(s)
USACE Only	Onsite				
EO 11990 Only	Onsite and Vollrath 16/17				
USACE/11990	Onsite				
USFWS	Vollrath 15/21 UFWS Easement				
Total		0	0	0	0




Temporary Wetland Impact
*Drawing Not to Scale

This document was originally issued and sealed by
Megan L. Isenhowe
Registration Number
PE- 8775,
on 05/31/18 and the original document is stored at the
North Dakota Department
of Transportation

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	H-7-008(033)133	76	1



SPEC	CODE	BID ITEM	QTY	UNIT
261	0112	FIBER ROLLS 12IN	200	LF





— Fiber Rolls, 12IN
*Drawing Not to Scale

This document was originally issued and sealed by
Megan L. Isenhower,
Registration Number
PE- 8775,
on 05/31/18 and the original document is stored at the
North Dakota Department
of Transportation

Temporary Erosion Control

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	H-7-008(033)133	77	1

SPEC	CODE	BID ITEM	QTY	UNIT
261	0112	FIBER ROLLS 12 IN	400	LF
261	0113	REMOVE FIBER ROLLS 12 IN	200	LF
256	0100	RIPRAP GRADE 1	20	CY
255	0102	ECB TYPE 2	30	SY




- Fiber Rolls 12 IN
- Riprap
- ECB

This document was originally issued and sealed by Megan L. Isenhower, Registration Number PE- 8775, on 05/31/18 and the original document is stored at the North Dakota Department of Transportation

Permanent Erosion Control

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	H-7-009(033)133	100	2



This document was originally issued and sealed by Megan L. Isenhower, Registration Number PE- 8775, on 05/23/18 and the original document is stored at the North Dakota Department of Transportation

Traffic Control Sign Layout

*Drawing Not to Scale

?	This is a special text character used in the labeling of existing features. It indicates a feature that has an unknown characteristic, potentially based on: lack of description, location accuracy or purpose.	Bldg	building	CSP	corrugated steel pipe	EDM	electronic distance meter
Abn	abandoned	BV	butterfly valve	CSTES	corrugated steel traversable end section	Elev or El	elevation
Abut	abutment	Byp	bypass	C	coulomb	Ellipt	elliptical
Ac	acres	C Gdrl	cable guardrail	Co	County	Emb	embankment
Adj	adjusted	Calc	calculate	Crse	course	Emuls	emulsion/emulsified
Aggr	aggregate	Cd	candela	Ct	Court	ES	end section
Ahd	ahead	CIP	cast iron pipe	Xarm	cross arm	Engr	engineer
ARV	air release valve	CB	catch basin	Xbuck	cross buck	ESS	environmental sensor station
Align	alignment	CRS	cationic rapid setting	Xsec	cross sections	Eq	equal
Al	alley	C Gd	cattle guard	Xing	crossing	Eq	equation
Alt	alternate	C To C	center to center	Xrd	Crossroad	Evgr	evergreen
Alum	aluminum	Cl or \varnothing	centerline	Crn	crown	Exc	excavation
ADA	Americans with Disabilities Act	Cm	centimeter	CF	cubic feet	Exst	existing
A	ampere	Ch	chain	M3	cubic meter	Exp	expansion
&	and	Chnlk	chain-link	M3/s	cubic meters per second	Expy	Expressway
Appr	approach	Ch Blk	channel block	CY	cubic yard	E	external of curve
Approx	approximate	Ch Ch	channel change	Cy/mi	cubic yards per mile	Extru	extruded
ACP	asbestos cement pipe	Chk	check	Culv	culvert	FOS	factor of safety
Asph	asphalt	Chsld	chiseled	C&G	curb & gutter	F	Fahrenheit
AC	asphalt cement	Cir	circle	CI	curb inlet	FS	far side
Assmd	assumed	Cl	class	CR	curb ramp	F	farad
@	at	Cl	clay	CS	curve to spiral	Fed	Federal
Atten	attenuation	Cl F	clay fill	C	cut	FP	feed point
ATR	automatic traffic recorder	Cl Hvy	clay heavy	Dd Ld	dead load	Ft	feet/foot
Ave	Avenue	Cl Lm	clay loam	Defl	deflection	Fn	fence
Avg	average	Clnt	clean-out	Defm	deformed	Fn P	fence post
ADT	average daily traffic	Clr	clear	Deg or D	degree	FO	fiber optic
Az	azimuth	Cl&gr	clearing & grubbing	DInt	delineate	FB	field book
Bk	back	Co S	coal slack	DIntr	delineator	FD	field drive
BF	back face	C Gr	coarse gravel	Depr	depression	F	fill
Bs	backsight	CS	coarse sand	Desc	description	FAA	fine aggregate angularity
Balc	balcony	Comb.	combination	Det	detail	FS	fine sand
B Wire	barbed wire	Coml	commercial	DWP	detectable warning panel	FH	fire hydrant
Barr	barricade	Compr	compression	Dtr	detour	Fl	flange
Btry	battery	CADD	computer aided drafting & design	Dia or \varnothing	diameter	Flrd	flared
Brg	bearing	Conc	concrete	Dir	direction	FES	flared end section
BI	beehive inlet	CECB	concrete erosion control blanket	Dist	distance	F Bcn	flashing beacon
Beg	begin	Cond	conductor	DM	disturbed material	FA	flight auger sample
BM	bench mark	Const	construction	DB	ditch block	FL	flow line
Bkwy	bikeway	Cont	continuous	DG	ditch grade	Ftg	footing
Bit	bituminous	CSB	continuous split barrel sample	Dbl	double	FM	force main
Blk	block	Contr	contraction	Dn	down	Fs	foresight
Bd Ft	board feet	Contr	contractor	Dwg	drawing		
BH	bore hole	CP	control point	Dr	drive		
BS	both sides	Coord	coordinate	Drwy	driveway		
Bot	bottom	Cor	corner	DI	drop inlet		
Blvd	Boulevard	Corr	corrected	D	dry density		
Bndry	boundary	CAES	corrugated aluminum end section	Ea	each		
BC	brass cap	CAP	corrugated aluminum pipe	Esmt	easement		
Brkwy	breakaway	CMES	corrugated metal end section	E	East		
Br	bridge	CMP	corrugated metal pipe	EB	Eastbound		
		CPVCP	corrugated poly-vinyl chloride pipe	Elast	elastomeric		
		CSes	corrugated steel end section	EL	electric locker		
		CSFES	corrugated steel flared end section	E Mtr	electric meter		
				Elec	electric/al		

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
04-23-18	General Revisions

This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930 , on 04/23/18 and the original document is stored at the North Dakota Department of Transportation

NDDOT ABBREVIATIONS

D-101-2

Fnd	found	ID	inside diameter	Mkg	marking	PMT	pad mounted transformer
Fdn	foundation	Inst	instrument	MA	mast arm	Pg	pages
Frac	fractional	Intchg	interchange	Matl	material	Pntd	painted
Frwy	freeway	Intmdt	intermediate	Max	maximum	Pr	pair
Frt	front	Intscn	intersection	MC	meander corner	Pnl	panel
FF	front face	Inv	invert	Meas	measure	Pk	park
F Disp	fuel dispenser	IM	iron monument	Mdn	median	PK	Parker-Kalon nail
FFP	fuel filler pipes	I Pn	Iron Pin	MD	median drain	Pa	pascal
FLS	fuel leak sensor	IP	iron Pipe	MC	medium curing	PSD	passing sight distance
Furn	furnish/ed	Jt	joint	M	mega	Pvmt	pavement
Gal	gallon	J	joule	Mer	meridian	Ped	pedestal
Galv	galvanized	Jct	junction	M	meter	Ped	pedestrian
Gar	garage	K	kelvin	M/s	meters per second	PPP	pedestrian pushbutton post
Gs L	gas line	Kn	kilo newton	M	mid ordinate of curve	Pen.	penetration
G Reg	gas line regulator	Kpa	kilo pascal	MGS	Midwest Guardrail System	Perf	perforated
GMV	gas main valve	Kg	kilogram	Mi	mile	Per.	perimeter
G Mtr	gas meter	Kg/m3	kilogram per cubic meter	MM	mile marker	PL	pipeline
GSV	gas service valve	Km	kilometer	MP	mile post	PI	place
GVP	gas vent pipe	K	Kip(s)	MI	milliliter	P&P	plan & profile
GV	gate valve	LS	Land Surveyor (licensed)	Mm	millimeter	PL	plastic limit
Ga	gauge	LSIT	Land Surveyor In Training	Mm/hr	millimeters per hour	P Cap	plastic cap
Geod	geodetic	Ln	lane	Min	minimum	PI or \overline{P}	plate
GIS	Geographical Information System	Lg	large	Misc	miscellaneous	Pt	point
G	giga	Lat	latitude	Mon	monument	PCC	point of compound curve
GPS	Global Positioning System	Lt	left	Mnd	mound	PC	point of curve
Gov	government	L	length of curve	Mtbl	mountable	PI	point of intersection
Grd	graded/grade	Lens	lenses	Mtd	mounted	PRC	point of reverse curvature
Gr	gravel	Lvl	level	Mtg	mounting	PT	point of tangent
Grnd	ground	LB	level book	Mk	muck	POC	point on curve
GWM	ground water monitor	Lvng	leveling	Mun	municipal	POT	point on tangent
Gdrl	guardrail	Lht	light	N	nano	PE	polyethylene
Gtr	gutter	LP	light pole	NGS	National Geodetic Survey	PVC	polyvinyl chloride
H Plg	H piling	Ltg	lighting	NS	near side	PCC	Portland Cement concrete
Hdwl	headwall	Lig Co	lignite coal	Neop	neoprene	Lb or #	pounds
Ha	hectare	Lig Sl	lignite slack	Ntwk	network	PP	power pole
Ht	height	LF	linear foot	N	newton	Preempt	preemption
HI	height of instrument	Liq	liquid	N	North	Prefab	prefabricated
Hel	helical	LL	liquid limit	NE	North East	Prfmd or Pref	preformed
H	henry	L	litre	NW	North West	Prep	preperation
Hz	hertz	Lm	loam	NB	Northbound	Press.	pressure
HDPE	high density polyethylene	Loc	location	No. or #	number		
HM	high mast	LC	long chord	Obsc	obscure(d)		
HP	high pressure	Long.	longitude	Obsn	observation		
HPS	high pressure sodium	Lp	loop	Ocpd	occupied		
Hwy	highway	LD	loop detector	Ocpy	occupy		
Hor	horizontal	Lm	lumen	Off Loc	office location		
HBP	hot bituminous pavement	Lum	luminaire	O/s	offset		
HMA	hot mix asphalt	L Sum	lump sum	OC	on center		
Hr	hour(s)	Lx	lux	C	one dimensional consolidation		
Hyd	hydrant	Mb	mailbox	OC	organic content		
Ph	hydrogen ion content	ML	main line	Orig	original		
Id	identification	M Hr	man hour	O To O	out to out		
In or "	inch	MH	manhole	OD	outside diameter		
Incl	inclinometer tube	Mkd	marked	OH	overhead		
IMH	inlet manhole	Mkr	marker				

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
08-03-15 04-23-18	General Revisions General Revisions

This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930 , on 04/23/18 and the original document is stored at the North Dakota Department of Transportation

NDDOT ABBREVIATIONS

D-101-3

PRV	pressure relief valve	Sc	scoria	St	street	Vert	vertical
Prestr	prestressed	Sec	seconds	SPP	structural plate pipe	VC	vertical curve
Pvt	private	Sec	section	SPPA	structural plate pipe arch	VCP	vitrified clay pipe
PD	private drive	SL	section line	Str	structure	V	volt
Prod.	production/produce	Sep	separation	Subd	subdivision	Vol	volume
Prog	programmed	Seq	sequence	Sub	subgrade	Wkwy	walkway
Prop.	property	Serv	service	Sub Prep	subgrade preperation	W	water content
Prop Ln	property line	Sh	shale	Ss	subsoil	WGV	water gate valve
Ppsd	proposed	Sht	sheet	SE	superelevation	WL	water line
PB	pull box	Shtng	sheeting	SS	supplement specification	WM	water main
Qty	quantity	Shldr	shoulder	Supp	supplemental	WMV	water main valve
Qtr	quarter	Sw or Sdwk	sidewalk	Surf	surfacing	W Mtr	water meter
Rad or R	radius	S	siemens	Surv	survey	WSV	water service valve
RR	railroad	SD	sight distance	Sym	symmetrical	WW	water well
Rlwy	railway	SN	sign number	SI	systems international	W	watt
Rsd	raised	Sig	signal	Tan	tangent	Wrng	wearing
RTP	random traverse point	Si Cl	silt clay	T	tangent (semi)	Wb	weber
Rge or R	range	Si Cl Lm	silty clay loam	TS	tangent to spiral	WIM	weigh in motion
RC	rapid curing	Si Lm	silty loam	Tel	telephone	W	west
Rec	record	Sgl	single	Tel B	Telephone Booth	WB	westbound
Rcy	recycle	SRCP	slotted reinforced concrete pipe	Tel P	telephone pole	Wrng	wiring
RAP	recycled asphalt pavement	SC	slow curing	Tv	television	W/	with
RPCC	recycled portland cement concrete	SS	slow setting	Temp	temperature	W/o	without
Ref	reference	Sm	small	Temp	temporary	WC	witness corner
R Mkr	reference marker	S	South	TBM	temporary bench mark	WGS	world geodetic system
RM	reference monument	SE	South East	T	tesla	Z	zenith
RP	reference point	SW	South West	T	thinwall tube sample		
Refl	reflectorized	SB	Southbound	T/mi	tons per mile		
RCB	reinforced concrete box	Sp	spaces	Ts	topsoil		
RCES	reinforced concrete end section	Spcl	special	Twp or T	township		
RCFES	reinforced concrete flared end section	SA	special assembly	Traf	traffic		
RCTES	reinforced concrete traversable end section	SP	special provisions	TSCB	traffic signal control box		
RCP	reinforced concrete pipe	G	specific gravity	Tr	trail		
RCPS	reinforced concrete pipe sewer	Spk	spike	Transf	transformer		
Reinf	reinforcement	SC	spiral to curve	TB	transit book		
Res	reservation	ST	spiral to tangent	Trans	transition		
Rs	residence	SB	split barrel sample	TT	transmission tower		
Ret	retaining	SH	sprinkler head	TES	traversable end section		
Rev	reverse	SV	sprinkler valve	Trans	transverse		
Rt	right	Sq	square	Trav	traverse		
R/W	right of way	SF	square feet	TP	traverse point		
Riv	river	Km2	square kilometer	Trtd	treated		
Rd	road	M2	square meter	Trmt	treatment		
Rdbd	road bed	SY	square yard	Qc	triaxial compression		
Rdwy	roadway	Stk	stake	TERO	tribal employment rights ordinance		
RWIS	roadway weather information system	Std	standard	Tpl	triple		
Rk	rock	N	standard penetration test	TP	turning point		
Rt	route	Std Specs	standard specifications	Typ	typical		
Salv	salvage(d)	Sta	station	Qu	unconfined compressive strength		
Sd	sand	Sta Yd	station yards	Ugrnd	underground		
Sdy Cl	sandy clay	Stm L	steam line	USC&G	US Coast & Geodetic Survey		
Sdy Cl Lm	sandy clay loam	SEC	steel encased concrete	USGS	US Geologic Survey		
Sdy Fl	sandy fill	SMA	stone matrix asphalt	Util	utility		
Sdy Lm	sandy loam	SSD	stopping sight distance	VG	valley gutter		
San	sanitary sewer line	SD	storm drain	Vap	vapor		

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
08-03-15 04-23-18	General Revisions General Revisions
























This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930 , on 04/23/18 and the original document is stored at the North Dakota Department of Transportation













702COM	702 Communications	GT PLNS NAT GAS	Great Plains Natural Gas Company	RED RIV TEL	Red River Rural Telephone
ACCENT	Accent Communications	HALS TEL	Halstad Telephone Company	RESVTN TEL	Reservation Telephone
AGASSIZ WU	Agassiz Water Users Incorporated	IDEA1	Idea1	ROBRTS TEL	Roberts Company Telephone
AGC	Associated General Contractors of America	INT-COMM TEL	Inter-Community Telephone Company	R-RIDER ELEC	Roughrider Electric Cooperative
All PI	Alliance Pipeline	KANEB PL	Kaneb Pipeline Company	RRVW	Red River Valley & Western Railroad
ALL SEAS WU	All Seasons Water Users Association	KEM ELEC	Kem Electric Cooperative Incorporated	S CENT REG WD	South Central Regional Water District
AMOCO PI	Amoco Pipeline Company	KOCH GATH SYS	Koch Gathering Systems Incorporated	S E W U	South East Water Users Incorporated
AMRDA HESS	Amerada Hess Corporation	LKHD PL	Lakehead Pipeline Company	SCOTT CABLE	Scott Cable Television Dickinson
AT&T	AT&T Corporation	LNGDN RWU	Langdon Rural Water Users Incorporated	SHERDN ELEC	Sheridan Electric Cooperative
B PAW	Bear Paw Energy Incorporated	LWR YELL R ELEC	Lower Yellowstone Rural Electric	SHEYN VLY ELEC	Sheyenne Valley Electric Cooperative
BAKER ELEC	Baker Electric	MCKNZ CON	McKenzie Consolidated Telcom	SKYTECH	Skyland Technologies Incorporated
BASIN ELEC	Basin Electric Cooperative Incorporated	MCKNZ ELEC	McKenzie Electric Cooperative	SLOPE ELEC	Slope Electric Cooperative Incorporated
BEK TEL	Bek Communications Cooperative	MCKNZ WRD	McKenzie County Water Resource District	SOURIS RIV TELCOM	Souris River Telecommunications
BELLE PL	Belle Fourche Pipeline Company	MCLEOD	McLeod USA	ST WAT COMM	State Water Commission
BLM	Bureau of Land Management	MCLN ELEC	McLean Electric Cooperative	STATE LN WATER	State Line Water Cooperative
BNSF	Burlington Northern Santa Fe Railway	MCLN-SHRDN R WAT	McLean-Sheridan Rural Water	STER ENG	Sterling Energy
BOEING	Boeing	MDU	Montana-dakota Utilities	STUT RWU	Stutsman Rural Water Users
BRNS RWD	Barnes Rural Water District	MID-CONT CABLE	Mid-Continent Cable	SW PL PRJ	Southwest Pipeline Project
BURK-DIV ELEC	Burke-Divide Electric Cooperative	MIDSTATE TEL	Midstate Telephone Company	T M C	Turtle Mountain Communications
BURL WU	Burleigh Water Users	MINOT CABLE	Minot Cable Television	TCI	TCI of North Dakota
Cable One	Cable One	MINOT TEL	Minot Telephone Company	TESORO HGH PLNS PL	Tesoro High Plains Pipeline
CABLE SERV	Cable Services	MISS VALL COMM	Missouri Valley Communications	TRI-CNTY WU	Tri-County Water Users Incorporated
CAP ELEC	Capital Electric Cooperative Incorporat	MISS W W S	Missouri West Water System	TRL CO RWU	Traill County Rural Water Users
CASS CO ELEC	Cass County Electric Cooperative	MNKOTA PWR	Minnkota Power	UNTD TEL	United Telephone
CASS RWU	Cass Rural Water Users Incorporated	MOR-GRAN-SOU ELEC	Mor-gran-sou Electric Cooperative	UPPR SOUR WUA	Upper Souris Water Users Association
CAV ELEC	Cavalier Rural Electric Cooperative	MOUNT-WILLI ELEC	Mountrail-williams Electric Cooperative	US SPRINT	U.S. Sprint
CBLCOM	Cablecom Of Fargo	MRE LBTY TEL	Moore & Liberty Telephone	USAF MSL CABLE	U.S.A.F. Missile Cable
CENEX PL	Cenex Pipeline	MUNICIPAL	City Water And Sewer	USFWS	US Fish and Wildlife Service
CENT PL WATER DIST	Central Pipe Line Water District	MUNICIPAL	City Of '.....'	USW COMM	U.S. West Communications
CENT PWR ELEC	Central Power Electric Cooperative	N CENT ELEC	North Central Electric Cooperative	VRNDRY ELEC	Verendrye Electric Cooperative
COE	Corps of Engineers	N VALL W DIST	North Valley Water District	W RIV TEL	West River Telephone Incorporated
CONS TEL	Consolidated Telephone	ND PKS & REC	North Dakota Parks And Recreation	WEB	W. E. B. Water Development Association
CONT RES	Continental Resource Inc	ND TEL	North Dakota Telephone Company	WILLI RWA	Williams Rural Water Association
CPR	Canadian Pacific Railway	NDDOT	North Dakota Department of Transportation	WILSTN BAS PL	Williston Basin Interstate Pipeline Company
D O E	Department Of Energy	NDSU SOIL SCI DEPT	NDSU Soil Science Department	WLSH RWD	Walsh Water Rural Water District
DAK CARR	Dakota Carrier Network	NEMONT TEL	Nemont Telephone	WOLVRTN TEL	Wolverton Telephone
DAK CENT TEL	Dakota Central Telephone	NODAK R ELEC	Nodak Rural Electric Cooperative	XLENER	Xcel Energy
DAK RWD	Dakota Rural Water District	NOON FRMS TEL	Noonan Farmers Telephone Company	YSVR	Yellowstone Valley Railroad
DGC	Dakota Gasification Company	NPR	Northern Plains Railroad		
DICKEY R NET	Dickey Rural Networks	NSP	Northern States Power		
DICKEY RWU	Dickey Rural Water Users Association	NTH PRAIR RW	Northern Prairie Rural Water Association		
DICKEY TEL	Dickey Telephone	NTHN BRDR PL	Northern Border Pipeline		
DNRR	Dakota Northern Railroad	NTHN PLNS ELEC	Northern Plains Electric Cooperative Incorporated		
DOME PL	Dome Pipeline Company	NTHWSTRN REF	Northwestern Refinery Company		
DVELEC	Dakota Valley Electric Cooperative	NW COMM	Northwest Communication Cooperation		
DVMW	Dakota, Missouri Valley & Western	ONEOK	Oneok gas		
ENBRDG	Enbridge Pipelines Incorporated	OSHA	Occupational Safety and Health Administration		
ENVENTIS	Enventis Telephone	OTTR TL PWR	Otter Tail Power Company		
FALK MNG	Falkirk Mining Company	P L E M	Prairielands Energy Marketing		
FHWA	Federal Highway Administration	POLAR COM	Polar Communications		
G FKS-TRL WD	Grand Forks-trail Water District	PVT ELEC	Private Electric		
GETTY TRD & TRAN	Getty Trading & Transportation	QWEST	Qwest Communications		
GLDN W ELEC	Golden West Electric Cooperative	R&T W SUPPLY	R & T Water Supply Association		
GRGS CO TEL	Griggs County Telephone	RAMSEY R SEW	Ramsey Rural Sewer Association		
		RAMSEY RW	Ramsey Rural Water Association		
		RAMSEY UTIL	Ramsey County Rural Utilities		

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
04-23-18	General Revisions








This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930 , on 04/23/18 and the original document is stored at the North Dakota Department of Transportation

Existing Topography























	Existing Ground Void
	Existing Cemetary Boundary
	Existing Box Culvert Bridge
	Existing Concrete Surface
	Existing Drainage Structure
	Existing Gravel Surface
	Existing Riprap
	Existing Dirt Surface
	Existing Asphalt Surface
	Existing Tie Point Line
	Existing Railroad Centerline
	Existing Guardrail Cable
	Existing Guardrail Metal
	Existing Edge of Water
	Existing Fence
	Existing Railroad
	Existing Field Line
	Exst Flow
	Existing Curb
	Existing Valley Gutter
	Existing Driveway Gutter
	Existing Curb and Gutter
	Existing Mountable Curb and Gutter

	Existing 3-Cable w Posts
	Site Boundary
	Existing Berm, Dike, Pit, or Earth Dam
	Existing Ditch Block
	Existing Tree Boundary
	Existing Brush or Shrub Boundary
	Existing Retaining Wall
	Existing Planter or Wall
	Existing W-Beam Guardrail with Posts
	Existing Railroad Switch
	Gravel Pit - Borrow Area
	Existing Wet Area-Vegetation Break





Proposed Topography

	3-Cable w Posts
	Flow
	Fence
	Remove Line
	Wall
	Retaining Wall (Plan View)
	W-Beam w Posts










Existing Utilities

	Existing Electrical
	Existing Fiber Optic Line
	Existing TV Fiber Optic
	Existing Gas Pipe
	Existing Overhead Utility Line
	Existing Power
	Existing Fuel Pipeline
	Existing Undefined Above Ground Pipe Line
	Existing Sanitary Sewer
	Existing Sanitary Force Main
	Existing Storm Drain
	Existing Storm Drain Force Main
	Existing Culvert
	Existing Telephone Line
	Existing TV Line
	Existing Water or Steam Line
	Existing Under Drain
	Existing Slotted Drain
	Existing Conduit
	Existing Conductor
	Existing Down Guy Wire Down Guy
	Existing Underground Vault or Lift Station




Proposed Utilities

	24 Inch Pipe
	Reinforced Concrete Pipe
	Under Drain
	Edge Drain

Traffic Utilities

	Conductor
	Fiber Optic
	Existing Loop Detector
	Existing Double Micro Loop Detector
	Micro Loop Detector Double
	Existing Micro Loop Detector
	Micro Loop Detector
	Signal Head with Mast Arm
	Existing Signal Head with Mast Arm

Sign Structures














	Existing Overhead Sign Structure
	Existing Overhead Sign Structure Cantilever
	Overhead Sign Structure Cantilever

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
09-23-16	Added and Revised Items, Organized by Functional Groups










This document was originally issued and sealed by
Roger Weigel,
Registration Number
PE-2930,
on 09/23/16 and the original document is stored at the
North Dakota Department
of Transportation

Line Styles









Right Of Way

	Easement
	Existing Easement
	Right of Way
	Existing Right of Way
	Existing Right of Way Railroad
	Existing Right of Way Not State Owned
	Existing Government Lot Line
	Existing Adjacent Block Lines
	Existing Adjacent Lot Lines
	Existing Adjacent Property Line
	Existing Adjacent Subdivision Lines
	Sight Distance Triangle Line
	Dimension Leader









Boundary Control

	Existing City Corporate Limits or Reservation Boundary
	Existing State or International Line
	Existing Township
	Existing County
	Existing Section Line
	Existing Quarter Section Line
	Existing Sixteenth Section Line
	Existing Centerline
	Tangent Line



Cross Sections and Typicals

	Existing Ground
	Existing Topsoil (Cross Section View)
	Existing Ground Void (Not Surveyed)
	Existing Concrete
	Existing Aggregate (Cross Section View)
	Existing Curb and Gutter (Cross Section View)
	Existing Asphalt (Cross Section View)
	Existing Reinforcement Rebar



Geotechnical

	Geotextile Fabric Type D
	Geogrid
	Geotextile Fabric Type R
	Geotextile Fabric Type R1
	Geotextile Fabric Type RR
	Geotextile Fabric Type S
	Subgrade Reinforcement
	Failure Line







Countours

	Depression Contours
	Supplemental Contour





Profile

	Subgrade, Subcut or Ditch Grade
	Topsoil Profile










Striping

	Centerline Pavement Marking
	Barrier with Centerline Pavement Marking
	Barrier Pavement Marking
	Stripe 4 IN Dotted Extension White
	Stripe 8 IN Dotted Extension White
	Stripe 8 IN Lane Drop








Pavement Joints

	Doweled Joint
	Tie Bar 30 Inch 4 Foot Center to Center
	Tie Bar 18 Inch 3 Foot Center to Center
	Tie Bar at Random Spacing






Bridge Details

	Hidden Object
	Small Hidden Object
	Large Hidden Object
	Phantom Object
	Centerline Main
	Centerline
	Existing Ground (Details)
	Existing Conditions
	Sheet Piling

Erosion Control

	Limits of Const Transition Line
	Bale Check
	Rock Check
	Floating Silt Curtain
	Silt Fence
	Excavation Limits
	Fiber Rolls

Environmental

	Wetland Mitigation
	Existing Wetland Easement USFWS
	Existing Wetland Jurisdictional
	Existing Wetland
	Tree Row

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
09-23-16	Added and Revised Items, Organized by Functional Groups
























































































This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930 , on 09/23/16 and the original document is stored at the North Dakota Department of Transportation

Symbols

	North Arrow (Half Scale)		Attenuation Device		Existing Railroad Battery Box		Existing Delineator Type E										
	Truck Mounted Attenuator		Diamond Grade Delineator Type A		Existing Bush or Shrub		Existing EFB Misc										
	Type I Barricade		Diamond Grade Delineator Type B		Existing Gas Cap or Stub		Existing Flashing Beacon										
	Type II Barricade		Diamond Grade Delineator Type C		Existing Sanitary Cap or Stub		Existing Pipe Mounted Flasher										
	Type III Barricade		Diamond Grade Delineator Type D		Existing Storm Drain Cap or Stub		Existing Pad Mounted Feed Point										
	Catch Basin		Diamond Grade Delineator Type E		Existing Water Cap or Stub		Existing Pipe Mounted Feed Point with Pad										
	Cairn or Stone Circle		Flexible Delineator		Existing Sanitary Cleanout		Existing Pole Mounted Feed Point										
	Video Detection Camera		Flexible Delineator Type A		Existing Concrete Foundation		Existing Railroad Frog										
	Storm Drain Cap or Stub		Flexible Delineator Type B		Existing Traffic Signal Controller		Existing Snow Gate 18										
	Corrugated Metal End Section 18 Inch		Flexible Delineator Type C		Existing Pad Mounted Signal Controller		Existing Snow Gate 28										
	Corrugated Metal End Section 24 Inch		Flexible Delineator Type D		Existing Sixteenth Section Corner		Existing Snow Gate 40										
	Corrugated Metal End Section 30 Inch		Flexible Delineator Type E		Existing Quarter Section Corner		Existing Headwall										
	Corrugated Metal End Section 36 Inch		Delineator Type A		Existing Section Corner		Existing Pedestrian Head with Number										
	Corrugated Metal End Section 42 Inch		Delineator Type A Reset		Existing Railroad Crossbuck		Existing Signal Head										
	Corrugated Metal End Section 48 Inch		Delineator Type B		Existing Satellite Dish		Existing Sprinkler Head										
	Concrete Foundation		Delineator Type B Reset		Existing Fuel Dispensers		Existing Fire Hydrant										
	Ground Connection Conductor		Delineator Type C		Existing Flexible Delineator Type A		Existing Catch Basin Drop Inlet										
	Neutral Connection Conductor		Delineator Type D		Existing Flexible Delineator Type B		Existing Curb Inlet										
	Phase 1 Connection Conductor		Delineator Type E		Existing Flexible Delineator Type C		Existing Manhole Inlet										
	Phase 2 Connection Conductor		Delineator Drums		Existing Flexible Delineator Type D		Existing Junction Box										
	Traffic Cone		Spot Elevation		Existing Flexible Delineator Type E	<table><tr><th colspan="2">NORTH DAKOTA DEPARTMENT OF TRANSPORTATION</th></tr><tr><th colspan="2">07-01-14</th></tr><tr><th colspan="2">REVISIONS</th></tr><tr><th>DATE</th><th>CHANGE</th></tr><tr><td></td><td></td></tr></table>		NORTH DAKOTA DEPARTMENT OF TRANSPORTATION		07-01-14		REVISIONS		DATE	CHANGE		
NORTH DAKOTA DEPARTMENT OF TRANSPORTATION																	
07-01-14																	
REVISIONS																	
DATE	CHANGE																
	Signal Controller		Existing Access Control Arrow		Existing Delineator Type A												
	Pad Mounted Signal Controller		Existing Artifact		Existing Delineator Type B												
	Alignment Data Point		Existing Flashing Beacon		Existing Delineator Type C												
	Emergency Vehicle Detector		Existing Benchmark		Existing Delineator Type D												

Symbols

D-101-31

	Existing Light Standard		Existing Manhole with Valve Water		Existing Telephone Pole		Existing Undefined Manhole
	Existing High Mast Light Standard 10 Luminaire		Existing Water Manhole		Existing Wood Pole		Existing Undefined Pull Box
	Existing High Mast Light Standard 3 Luminaire		Existing Mile Post Type A		Existing Post		Existing Undefined Pedestal
	Existing High Mast Light Standard 4 Luminaire		Existing Mile Post Type B		Existing Pedestrian Push Button Post		Existing Undefined Valve
	Existing High Mast Light Standard 5 Luminaire		Existing Mile Post Type C		Existing Control Point CP		Existing Undefined Pipe Vent
	Existing High Mast Light Standard 6 Luminaire		Existing Reference Marker		Existing Control Point GPS-RTK		Existing Gas Valve
	Existing High Mast Light Standard 7 Luminaire		Existing RW Marker		Existing Control Point TRI		Existing Water Valve
	Existing High Mast Light Standard 8 Luminaire		Existing Utility Marker		Existing Reference Marker Point NGS		Existing Fuel Pipe Vent
	Existing High Mast Light Standard 9 Luminaire		Iron Monument Found		Existing Pull Box		Existing Gas Pipe Vent
	Existing Overhead Sign Structure Load Center		Iron Pin R/W Monument		Existing Intelligent Transportation Pull Box		Existing Sanitary Pipe Vent
	Existing Luminaire		Existing Object Marker Type I		Existing Water Pump		Existing Storm Drain Pipe Vent
	Existing Light Standard Luminaire		Existing Object Marker Type II		Existing Slotted Reinforced Concrete Pipe		Existing Water Pipe Vent
	Existing Federal Mailbox		Existing Object Marker Type III		Existing RR Profile Spot		Existing Weather Station
	Existing Private Mailbox		Existing Electrical Pedestal		Existing Fuel Leak Sensors		Existing Ground Water Well Bore Hole
	Existing Meander Section Corner		Existing Telephone Pedestal		Existing Highway Sign		Existing Windmill or Tower
	Existing Meter		Existing Fiber Optic Telephone Pedestal		Existing Miscellaneous Spot		Existing Witness Corner
	Existing Electrical Manhole		Existing TV Pedestal		Existing Lighting Standard Pole		Flashing Beacon
	Existing Gas Manhole		Existing Fiber Optic TV Pedestal		Existing Traffic Signal Standard		Flagger
	Existing Sanitary Manhole		Existing Fuel Filler Pipes		Existing Transformer		Pipe Mounted Flasher
	Existing Sanitary Force Main Manhole		Existing Traverse PI Aerial Panel		Existing Large Evergreen Tree		Sanitary Force Main with Valve
	Existing Sanitary Manhole with Valve		Existing Pole		Existing Small Evergreen Tree		
	Existing Storm Drain Manhole		Existing Power Pole		Existing Large Tree		
	Existing Force Main Storm Drain Manhole		Existing Power Pole with Transformer		Existing Small Tree		
	Existing Force Main Storm Drain Manhole with Valve				Existing Tree Trunk		
	Existing Telephone Manhole				Existing Pad Mounted Traffic Signal Control Box		

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 07/01/14 and the original document is stored at the North Dakota Department of Transportation

Symbols



Pad Mounted Feed Point



Pipe Mounted Feed Point with Pad



Pole Mounted Feed Point



Headwall



Double Headwall with Vegetation Barrier



Single Headwall with Vegetation Barrier



Pole Mounted Head



Sprinkler Head



Fire Hydrant



Inlet Type 1



Inlet Type 2



Double Inlet Type 2



Inlet Grate Type 2



Junction Box



High Mast Light Standard 10 Luminaire



High Mast Light Standard 3 Luminaire



High Mast Light Standard 4 Luminaire



High Mast Light Standard 5 Luminaire



High Mast Light Standard 6 Luminaire



High Mast Light Standard 7 Luminaire



High Mast Light Standard 8 Luminaire



High Mast Light Standard 9 Luminaire



Relocate Light Standard



Overhead Sign Structure Load Center



Light Standard 100 Watt High Pressure Sodium Vapor Luminaire



Light Standard 1000 Watt High Pressure Sodium Vapor Luminaire



Light Standard 150 Watt High Pressure Sodium Vapor Luminaire



Light Standard 175 Watt High Pressure Sodium Vapor Luminaire



Light Standard 200 Watt High Pressure Sodium Vapor Luminaire



Light Standard 250 Watt High Pressure Sodium Vapor Luminaire



Light Standard 310 Watt High Pressure Sodium Vapor Luminaire



Light Standard 35 Watt High Pressure Sodium Vapor Luminaire



Light Standard 400 Watt High Pressure Sodium Vapor Luminaire



Light Standard 50 Watt High Pressure Sodium Vapor Luminaire



Light Standard 70 Watt High Pressure Sodium Vapor Luminaire



Light Standard 700 Watt High Pressure Sodium Vapor Luminaire



Manhole



Manhole 48 Inch



Sanitary Force Main Manhole



Sanitary Sewer Manhole



Storm Drain Manhole



Storm Drain Manhole with Inlet



Reset Mile Post



Mile Post Type A



Mile Post Type B



Mile Post Type C



Right of Way Marker



Tubular Marker



Alignment Monument



Iron Pin Reference Monument



Object Marker Type I



Object Marker Type II



Object Marker Type III



Caution Mode Arrow Panel



Back to Back Vertical Panel Sign



Double Direction Arrow Panel



Left Directional Arrow Panel



Right Directional Arrow Panel



Sequencing Arrow Panel



Truck Mounted Arrow Panel



Power Pole



Wood Pole



Pedestrian Push Button Post



Property Corner



Pull Box



Intelligent Transportation Pull Box



Sanitary Pump



Storm Drain Pump



Reinforced Pavement



Reinforced Concrete End Section 15 Inch



Reinforced Concrete End Section 18 Inch



Reinforced Concrete End Section 24 Inch



Reinforced Concrete End Section 30 Inch



Reinforced Concrete End Section 36 Inch



Reinforced Concrete End Section 42 Inch



Reinforced Concrete End Section 48 Inch



Reinforced Concrete End Section 54 Inch



Reset Right of Way Marker



Reset USGS Marker



Right of Way Markers



Riser 30 Inch



Continuous Split Barrel Sample



Flight Auger Sample



Split Barrel Sample



Thinwall Tube Sample



Highway Sign



SNOW GATE 18 FT



SNOW GATE 28 FT



SNOW GATE 40 FT



Standard Penetration Test



Transformer



Inclinometer Tube



Underdrain Cleanout



Excavation Unit



Water Valve

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 07/01/14 and the original document is stored at the North Dakota Department of Transportation

EROSION CONTROL FIBER ROLL PLACEMENT DETAILS

D-261-1

*Optional Weir. Use in flat areas, such as the Red River Valley, where there is potential for water to back up on adjacent property. Lower fiber roll enough to prevent water from backing up on adjacent property. Do not use 20-inch fiber rolls in flat areas where there is potential for water to back up on adjacent property.

12 OR 20 INCH FIBER ROLL - DITCH BOTTOM

PLAN VIEW FOR SLOPE APPLICATION

Detail A
Fiber Roll Overlapping Staking Detail

Detail B
Fiber Roll Staking Detail

FIBER ROLL DIAMETER	NOMINAL STAKE SIZE	MINIMUM STAKE LENGTH	MINIMUM TRENCH DEPTH	MAXIMUM TRENCH DEPTH
6"	2" x 2"	18"	2"	2"
12"	2" x 2"	24"	2"	3"
20"	2" x 2"	36"	3"	5"




NOTE: Runoff must not be allowed to run under or around roll.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
11-18-10	
REVISIONS	
DATE	CHANGE
06-10-13	Added plan view for ditch and slope application. Added table with values for stake and trench dimensions.
10-04-13	Revised fiber roll overlap detail.
06-26-14	Changed standard drawing number from D-708-7 to D-261-1.

This document was originally issued and sealed by
Roger Weigel,
Registration Number
PE- 2930,
on 06/26/14 and the original document is stored at the
North Dakota Department
of Transportation

Perforated Tube

- Notes:
1. Torque slip base bolts as specified by manufacturer.
 2. Use anchor with 43.9 KSI yield strength and 59.3 KSI tensile strength.
 3. Provide 4" vertical clearance for anchor or breakaway base. Measure the 4"x60" measurement above and below post location and back and ahead of post.
 4. In concrete sidewalk, use same anchor without wings.
 5. Provide more than 7' between the first and fourth posts of a four post sign.




Telescoping Perforated Tube						
Number of Posts	Post Size in.	Wall Thick-ness Gauge	Sleeve Size in.	Wall Thick-ness Gauge	Slip Base	Anchor Size without Slip Base in.
1	2	12			No	2 1/4
1	2 1/4	12			No	2 1/2
1	2 1/2	12			(A)	3
1	2 1/2	10			Yes	
1	2 1/4	12	2	12	Yes	
1	2 1/2	12	2 1/4	12	Yes	
2	2	12			No	2 1/4
2	2 1/4	12			No	2 1/2
2	2 1/2	12			Yes	
2	2 1/2	12			Yes	
2	2 1/4	10	2	12	Yes	
2	2 1/2	12	2 1/4	12	Yes	
3 & 4	2 1/2	12			Yes	
3 & 4	2 1/2	10			Yes	
3 & 4	2 1/2	12	2 1/4	12	Yes	
3 & 4	2 1/4	12	2	12	Yes	
3 & 4	2 1/2	10	2 3/16	10	Yes	

Properties of Telescoping Perforated Tube						
Tube Size in.	Wall Thickness in.	U.S. Standard Gauge	Weight per Foot lbs.	Moment of Inertia in. ⁴	Cross Sec. Area in. ²	Section Modulus in. ³
1 1/2 x 1 1/2	0.105	12	1.702	0.129	0.380	0.172
2 x 2	0.105	12	2.416	0.372	0.590	0.372
2 1/4 x 2 1/4	0.105	12	2.773	0.561	0.695	0.499
2 3/8 x 2 3/8	0.135	10	3.432	0.605	0.841	0.590
2 1/2 x 2 1/2	0.105	12	3.141	0.804	0.803	0.643
2 1/2 x 2 1/2	0.135	10	4.006	0.979	1.010	0.785






Top Post Receiver Data Table						
Square Post Sizes (B)	A	B	C	D	E	F
2 3/16"x10 ga.	1 5/16"	2 1/2"	3 1/2"	2 5/32"	1 33/64"	1 7/8"
2 1/2"x10 ga.	1 3/32"	2 1/2"	3 5/16"	5/8"	1 21/32"	1 3/4"

- (A) Use breakaway base when support is placed in weak soils. Engineer determines if soils are weak.
- (B) For additional wind load, insert the 2 3/8"x10 ga. into 2 1/2"x10 ga.



NORTH DAKOTA DEPARTMENT OF TRANSPORTATION		This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930, on 9/27/2017 and the original document is stored at the North Dakota Department of Transportation
2-28-14		
REVISIONS		
DATE	CHANGE	
9-27-17	Updated to active voice	

U-Channel Post



Alternate A Steps of Installation:


- a) Drive anchor unit to within 12" of ground level.
b) Establish proper assembly by lining up bottom hole of retainer strap with 6th hole from the top of the anchor unit.
c) Assemble strap to back of anchor unit using $\frac{5}{16}$ "x2" bolt, lock washer and nut.
d) Rotate strap 90° to left.
- a) Drive anchor unit to 4" above ground.
b) Rotate strap to vertical position.
- a) Place $\frac{5}{16}$ "x2" bolt, lock washer and nut in bottom of sign post to facilitate alignment of sign post with proper hole in anchor unit.
b) Alternately tighten two connector bolts.
- Complete assembly by tightening $\frac{5}{16}$ "x2" bolt (this fastens sign post to retainer strap).
- Properly nest base post, strap, and sign post. Proper nesting occurs when all flat surfaces of the base post, strap, and sign post at the bolts have full contact across the entire width.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
2-28-14	
REVISIONS	
DATE	CHANGE
9-27-17	Updated to active voice


This document was originally issued and sealed by
Roger Weigel,
Registration Number
PE- 2930,
on 9/27/2017 and the original document is stored at the
North Dakota Department
of Transportation

CONSTRUCTION SIGN DETAILS
TERMINAL AND GUIDE SIGNS


D-704-9




G20-1-60
Legend: black (non-refl)
Background: orange




G20-50a-72
Legend: black (non-refl)
Background: orange




E5-1(L or R)-48
Legend: white
Background: green (orange optional)




E5-1-48




G20-50a-72
G20-52a-72




G20-1b-60
Legend: black (non-refl)
Background: orange




G20-52a-72
Legend: black (non-refl)
Background: orange




M4-8-36
Legend: black (non-refl)
Background: orange




M4-9(L or R)-30
Right or Left




G20-2-48
Legend: black (non-refl)
Background: orange



G20-55-96
Legend: black (non-refl)
Background: orange



M4-9(L or R)-30
Advanced Right or Left




M4-9-30
Straight

ARROW DETAILS

NOTES:
(A) Arrow may be right or left of the legend to indicate construction to the right or left.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-13-13	
REVISIONS	
DATE	CHANGE
8-17-17	Added sign & background color


This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930, on 8/17/17 and the original document is stored at the North Dakota Department of Transportation




M4-9(L or R)-30 & M4-9-30
Legend: black (non-refl)
Background: orange

CONSTRUCTION SIGN PUNCHING AND MOUNTING DETAILS


Note: In curb sections, place signs a minimum horizontal distance of 2' from face of the curb to near edge of the sign.




TYPICAL SECTION
(48" x 48" diamond warning sign shown)




24" x 24"
ROUTE MARKER
ASSEMBLY




36" x 36"
ROUTE MARKER
ASSEMBLY




18" x 18"
DIAMOND SIGN




48" x 48" DIAMOND SIGN
(with 30" x 30" secondary sign)




48" x 48" DIAMOND SIGN
(with 30" x 24" secondary sign)




108" x 48" SIGN




96" x 48" SIGN




R1-2-60 - YIELD SIGN




W14-3-64 - PENNANT SIGN




72" x 36" SIGN




R1-1-48 - STOP SIGN
(with R6-1-54 sign as required)




R1-1-48 - STOP SIGN
(with R1-50P-24 sign as required)




72" x 24" SIGN




48" x 48" SIGN
(with R6-1-54 sign as required)




48" x 48" SIGN
(with R2-1aP-24 sign as required)



60" x 24" SIGN



24" x 36" SIGN



30" x 24" SIGN

NOTES:

1. Sign Supports: Galvanize or paint supports. Minimum post sizes are 2.5 lb/ft u-channel or 2" x 2" x 12 gauge steel perforated tube, except where noted. When installing signs on u-channel, minimum post size for assemblies containing a secondary sign is 3.0 lb/ft. Post sizes based on a wind speed of 55 MPH.

Place signs over 50 square feet on 2½" x 2½" perforated tube supports as a minimum.

Do not attach guy wires to sign supports. Attach wind beams behind sign panels when used with u-posts.
2. Sign Panels: Provide sign panels made of 0.100" aluminum, ½" plywood, or other approved material, except where noted. Punch all holes round for ⅝" bolts.
3. Alternate Messages: Install and remove alternate message signs on reflectorized plate (without borders) as required. (i.e. "Left" and "Right" message on lane closure sign)
4. Route Marker Auxiliary Signs: Provide route marker auxiliary signs, such as the cardinal direction and directional arrows, with a background and legend that match the route marker they are used with:

Interstate - white legend on blue background
Interstate Business Loop - white legend on green background
US and State - black legend on white background
County - yellow legend on blue background

5. Vertical Clearance: Install signs with a vertical clearance of 5'-0" (see TYPICAL SECTION). In areas where parking or pedestrian movements are likely or the view of the sign may be obstructed, install signs with a vertical clearance of 7'-0" from the top of the curb or from the near edge of the driving lane in absence of a curb.

The vertical clearance to secondary signs is 1'-0" less than the vertical clearance stated above.

Provide a minimum clearance of 7'-0" from the ground at the post for signs with an area exceeding 50 square feet.

6. Portable Signs: Provide portable signs that meet the vertical clearance stated above when it is necessary to place signs within the pavement surface.


Use of low-mounting height (minimum 12" vertical clearance) portable signs for 5 days or less, is allowed as long as the view of the sign is not obstructed. Time delays caused by unforeseen circumstances, such as equipment breakdown, rain, subgrade failures, etc., will not accrue towards the 5 day period. Use of R9-8 through R9-11a series, W1-6 through W1-8 series, M4-10, and E5-1 is allowed for longer than 5 days.

Restrict signs mounted on portable sign supports shown in the LOW-MOUNTING HEIGHT and HIGH-MOUNTING HEIGHT details to a maximum surface area of 16 square feet.


MINIMUM BALLAST
(For each side of sign support base)

Sign Panel Mounting Height (ft)	Number of 25 lb sandbags for 4' x 4' sign panel
1'	6
5'	8
7'	10

Note: The number of sandbags are based on a wind speed of 55 MPH. Place sandbags at or near the ends of skids.



PORTABLE SIGN SUPPORT
LOW-MOUNTING HEIGHT







PORTABLE SIGN SUPPORT
HIGH-MOUNTING HEIGHT

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-4-13	
REVISIONS	
DATE	CHANGE
11-14-13 9-27-17	Revised Note 6, Updated to active voice


This document was originally issued and sealed by
Roger Weigel,
Registration Number
PE-2930,
on 9/27/2017 and the original document is stored at the
North Dakota Department
of Transportation

MISCELLANEOUS SIGN LAYOUTS


D-704-26




TYPE BB
Within major work area
where sign conditions exist




TYPE CC
Where sign conditions exist




TYPE DD
Where sign conditions exist




TYPE EE
Where sign conditions exist




TYPE FF
Where sign conditions exist



TYPE GG
Where elevation difference
exists between lanes



TYPE JJ
For break in pavement.
Install signs when conditions exist
and remove when not applicable.



TYPE KK
At major intersections
within pilot car control area

- Notes
1. Re-establish speed limit. Determine exact speed limit in the field, dependent on location and conditions.
 2. Determine reduced speed limit based on in-place speed limit before construction. Where speed reductions exceed 30 mph, install a second speed limit sign with the desired speed reduction (not to exceed 30 mph.) Place the second speed limit sign at 1/2B.
 3. Install flags on warning signs in urban areas when signs are not portable. Mount 24 inch square flags perpendicular to the edges of the sign, and at such a distance above the edge that the flag does not touch the sign when limp.
 4. Cover existing speed limit signs within reduced speed zones.
 5. As an option, use portable sign supports in lieu of post mounted signs in accordance with NDDOT Standard Specifications.
 6. Sign G20-55-96 is not required if this standard is part of other traffic control layouts, or work is less than 15 days.
 7. When pilot car operation is used, place sign G20-4b-36 "Wait For Pilot Car" at major intersections within pilot car control area.
 8. Recommend 40 mph speed limit in vicinity of workers, unless location and conditions dictate otherwise.

ADVANCE WARNING SIGN SPACING				
Road Type	Distance Between Signs Min. (ft)			
	A	B	C	
Urban - Low Speed (30 mph or less)	150	150	150	
Urban - Low Speed (over 30 to 40 mph)	280	280	280	
Urban - High Speed (over 40 mph to 50 mph)	360	360	360	
Rural - High Speed (over 50 mph to 65 mph)	720	720	720	
Urban Expressway and Freeway (55 mph to 60 mph)	850	1350	2200	
Rural Expressway and Freeway (70 mph to 75 mph)	1000	1500	2640	
Interstate/4-Lane Divided (Maintenance and Surveying)	750	1000	1500	

Longitudinal Buffer Space	
*Speed (mph)	Length Min (feet)
20	115
25	155
30	200
35	250
40	305
45	360
50	425
55	495
60	570
65	645
70	730
75	820

* Posted speed, off-peak 85th percentile speed prior to work starting, or the anticipated operating speed in mph.

KEY

Sign Flagger Cones


S = Numerical value of speed limit or 85th percentile.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-27-13	
REVISIONS	
DATE	CHANGE
8-17-17	Added speed limit signs. Updated notes & sign numbers

This document was originally issued and sealed by
Roger Weigel
Registration Number
PE- 2930,
on 08/17/17 and the original document is stored at the
North Dakota Department
of Transportation

PORTABLE SIGN SUPPORT ASSEMBLY

D-704-50




Notes:

- ① The maximum weight of the assembly is 250 pounds.
- ② Use a 14" wheel and tire.
- ③ Automotive and equipment axle assemblies may not be used for trailer-mounted sign supports.
- ④ Other NCHRP 350 crash tested assemblies are acceptable.


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
11-23-10	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by
Roger Weigel
Registration Number
PE- 2930 ,
on 11/23/10 and the original document is stored at the
North Dakota Department
of Transportation


EROSION AND SILTATION CONTROLS
MEDIAN OR DITCH INLET PROTECTION




FIBER ROLL PROTECTION
(MEDIAN OR DITCH INLET)




FIBER ROLL PROTECTION
(INLET OF CULVERT)




SILT FENCE PROTECTION
(MEDIAN OR DITCH INLET)



GRAVEL INLET PROTECTION
(MEDIAN OR DITCH INLET)




SANDBAG PROTECTION
(LOW POINT)



SANDBAG PROTECTION
(ON SLOPE)


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION		This document was originally issued and sealed by Roger Weigel Registration Number PE- 2930 , on 10-17-2017 and the original document is stored at the North Dakota Department of Transportation
10-03-13		
REVISIONS		
DATE	CHANGE	
06-26-14	Updated reference to standard drawing number for fiber roll staking details,	
10-01-14	Updated reference to standard drawing number for silt fence,	
10-17-17	Updated to active voice,	

REINFORCED CONCRETE PIPE CULVERTS AND END SECTIONS
(Round Pipe)



REINFORCED CONCRETE PIPE - FLARED END SECTION
Reinforcement to be equivalent to Class III RCP

TRAVERSABLE END SECTION							
DIA	B	C	D	E	F	R	S
15"	4"	9"	4'-9"	1'-7½"	2½"	3"	6
18"	5'-9"	9"	6'-6"	1'-11"	2½"	3"	6
24"	6"	1'	7"	2'-6"	3"	3"	4
30"	7'-6"	1'	8'-6"	3'-1"	3½"	3½"	4
36"	7'-3"	15"	8'-6"	3'-8"	4"	3"	4




NOTES (Traversable End Section):

1. Manufactured in accordance with applicable portions of ASTM C76/AASHTO M170.
2. Reinforcement per Class III RCP with double reinforcement in the upper 120° of the full barrel portion.

FLARED END SECTION						
TERMINAL DIMENSIONS						
DIA	A	B	C	D	E	U
12	0'-4"	2'-0"	4'-0⅞"	6'-0⅞"	2'-0"	2"
15	0'-6"	2'-3"	3'-10"	6'-1"	2'-6"	2½"
18	0'-9"	2'-3"	3'-10"	6'-1"	3'-0"	2½"
21	0'-9"	3'-0"	3'-1"	6'-1"	3'-6"	2½"
24	0'-9½"	3'-7½"	2'-6"	6'-1½"	4'-0"	3"
27	0'-10½"	4'-0"	2'-1½"	6'-1½"	4'-6"	3½"
30	1'-0"	4'-6"	1'-7¾"	6'-1¾"	5'-0"	3½"
36	1'-3"	5'-3"	2'-9"	8'-0"	6'-0"	4"
42	1'-9"	5'-3"	2'-9"	8'-0"	6'-6"	4½"
48	2'-0"	6'-0"	2'-0"	8'-0"	7'-0"	5"
54	2'-3"	5'-5"	2'-9¼"	8'-2¼"	7'-6"	5½"
60	2'-11"	5'-0"	3'-3"	8'-3"	8'-0"	5"
66	2'-6"	6'-0"	2'-3"	8'-3"	8'-6"	5½"
72	3'-0"	6'-6"	1'-9"	8'-3"	9'-0"	6"
78	3'-0"	7'-6"	1'-9"	9'-3"	9'-6"	6½"
84	3'-0"	7'-6½"	1'-9"	9'-3½"	10'-0"	6½"
90	3'-5"	7'-3½"	2'-0"	9'-3½"	11'-0"	6½"

REINFORCED CONCRETE PIPE - TRAVERSABLE END SECTION
Reinforcement to be equivalent to Class III RCP



All Classifications of Round Concrete Pipe						
Internal Dia. of Pipe in Inches	Cross-Sectional Water Area	Weight per Lin. Foot of Pipe Std. Wall	Joint J Groove End Min./Max.	Joint K Tongue Min.	Minimum Wall Thickness (T)	
Dia	Sq. ft.	Lbs.	In.	In.	In.	
12	0.79	92	1⅞-2⅝	¾	2	
15	1.23	127	1¾-2¾	⅞	2½	
18	1.77	168	1⅞-2⅞	1	2½	
21	2.40	214	1⅞-3⅝	1⅞	2½	
24	3.14	265	2¾-3¾	1⅞	3	
27	3.98	322	2¾-4	1¼	3½	
30	4.91	384	3¼-4¼	1¼	3½	
33	5.94	452	3¼-4¼	1½	3¾	
36	7.07	524	3¼-4¼	1½	4	
42	9.62	685	3¾-4¾	1¾	4½	
48	12.57	685	3¾-4¾	1⅞	5	
54	15.90	1070	4½-5½	2	5½	
60	19.63	1296	4½-5½	2¼	6	
66	23.76	1542	5-6	2⅞	6½	
72	28.27	1810	5½-6¾	2⅞	7	
78	33.18	2098	6¼-7¼	2⅞	7½	
84	38.48	2410	5½-7¾	3⅞	8	
90	44.18	2793	6¾-8½	3⅞	8½	
96	50.27	3092	7-8¼	3½	9	
102	56.75	3466	7-8¼	3½	9½	
108	63.62	3864	7¼-8½	3¾	10	


- NOTES:
1. All reinforcing steel shall meet AASHTO M170 requirements.
 2. All circular, longitudinal, and elliptical reinforcement shall be assembled and securely fastened in cage fashion so as to maintain reinforcement in exact shape and correct positions within the forms.
 3. Laying length of pipe: 12" to 66" (incl.) = not less than 4 feet 66" to 108" (incl.) = not less than 6 feet
 4. Joints shall be sealed with rubber gaskets or with sealer approved by the engineer whenever pipe are specified for storm drain or sanitary sewers.
 5. For Class IV and Class V reinforced concrete pipe and end section sizes which do not have reinforcement specified by AASHTO M170, shop drawings and design calculations shall be prepared and sealed by a Professional Engineer and submitted for the Engineer's review.

SEE STANDARD DRAWING D-714-22 FOR DETAILS OF CONCRETE PIPE TIES (TIE BOLTS).



NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
05-12-14	
REVISIONS	
DATE	CHANGE
01-21-15 11-21-16	Revised Note 5 Revised End Section Dimensions

This document was originally issued and sealed by
Jon Ketterling
Registration Number
PE- 4684,
on 11/21/16 and the original document is stored at the
North Dakota Department
of Transportation


JACKED AND BORED PIPE



JACKED AND BORED PAY LENGTH



STANDARD COUPLER FOR JOINING
SMOOTH WALL STEEL PIPE TO REINFORCED
CONCRETE PIPE



STANDARD CONNECTING BAND FOR JOINING SMOOTH
WALL STEEL PIPE TO CORRUGATED PIPE

Table of Minimum Wall Thicknesses for Smooth Walled Steel Pipe Through Roadway Embankment	
Diameter of Pipe	Minimum Wall Thickness
24 Inches	0.312 Inch
30 Inches	0.406 Inch
36 Inches	0.469 Inch
42 Inches	0.500 Inch
48 Inches	0.563 Inch
54 Inches	0.656 Inch
60 Inches	0.719 Inch
66 Inches	0.813 Inch
72 Inches	0.875 Inch

NOTES:

1. The method used to install the pipe indicated as jacked on the plans shall be left to the discretion of the contractor. The boring or jacked methods are acceptable. If the boring method is used, the contractor may use smooth wall steel pipe in lieu of RCP. Jacked concrete pipe sections shall be the class required for the height of fill, but concrete compressive strength shall be a minimum of 6,000 psi or greater. If smooth walled steel pipe is to be used, this material shall be welded steel pipe of new material, meeting ASTM Specifications A-139, Grade B with minimum yield strength of 35,000 psi. The Table of Minimum Wall Thicknesses for Smooth Walled Steel Pipe Through Roadway Embankment shall be used.
2. Pipe culverts that are bored or jacked shall conform to section 714 and section 830 of the standard specifications.
3. Pipe culverts shall be installed using equipment that encases the hole as the earth is removed. Boring or jacking without the concurrent installation of the pipe will not be permitted.
4. Pipe shall extend through the undisturbed fill and shall be installed so as not to disrupt traffic nor damage roadway grade and surface. Contractor shall ensure proper traffic control and traffic safety measures are put into place to protect the traveling public throughout the jacking or boring process.
5. The encased hole shall not be more than 0.1 foot greater than the outside diameter of the pipe.
6. Use of water in the process of boring or jacking is prohibited.
7. Temporary removal and replacement of embankment shall be included in price bid for Pipe Conduit – Jacked or Bored. Temporary removal of embankment may be allowed up to a maximum of 2:1, and shall not be into the existing pavement section (base, pavement, etc). Contractor is responsible for protection and stability of the slope throughout the jacking or boring process.
8. Proper cushioning material shall be inserted between the jack and pipe. Damaged ends that result in an unsatisfactory joint when the additional sections of pipe are placed, shall be rejected and removed, and a new section shall be installed.
9. The boring or jacking shall start from the low or downstream end, be made in straight lines, to the grade and alignment as shown on the plans. The flow line elevation at the starting point for boring or jacking shall be within 0.1 ft. of staked grade; the flow line shall not be reversed at any point; and the line and grade at any point within the pipe shall not vary by more than 0.5 ft. from the line and grade designated.
10. Openings more than 1/4 inch (5 mm) in width between adjacent sections of concrete pipe shall be filled with 1:2 cement/sand mortar. All concrete pipe sections and end sections shall be tied in accordance with standard drawing D-714-22. All steel sections shall be welded continuously around their periphery in accordance with Standard Specification 830.02 F & 714.04 C.
11. Once the pipe jacking has begun, proceed with the operation without interruption to prevent the pipe from becoming firmly set in the embankment.
12. The culvert consists of separate bid items for each portion: "Pipe Conduit XXIn – Jacked or Bored" and "Pipe Conduit XXIn". The pay lengths of the pipe bid items are as shown for the type and size specified per linear foot. Connecting bands or Couplers shall be included in the unit price bid for "Pipe Conduit XXIn – Jacked or Bored". The required materials, labor, and equipment to complete the work shall be included in the price bid for the above bid items.




Note: This Standard Drawing only applies to jacked and bored pipe under a roadway embankment. Additional coordination and design is needed for railroad embankments.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
02-28-2014	
REVISIONS	
DATE	CHANGE
07-07-2014	Revise Notes

This document was originally
issued and sealed by
Roger Weigel
Registration Number
PE-2930,
on 7/7/14 and the original
document is stored at the
North Dakota Department
of Transportation

CONCRETE PIPE, CATTLE PASS, OR
PRECAST CONCRETE BOX CULVERT TIES




D-714-22






SECTION A-A

REQUIRED SIZE OF TIE BOLTS		
Pipe Size	Thread ϕ	XXS Pipe Sleeve Inner ϕ
18" - 24"	$\frac{5}{8}$ " See note 2	$\frac{3}{4}$ "
30" - 66"	$\frac{3}{4}$ "	1"
72" - 78"	1"	1 $\frac{1}{4}$ "
RCB/Cattle Pass		


- NOTES:
- The pipe size listed is the inside diameter of round pipe or the equivalent diameter of pipe arch.
 - Cattle Pass and Jacked and Bored pipes shall have pipe ties inserted from the inside of the pipes and grouted into place. Jacked and bored pipes with a diameter of 24" or less do not require pipe ties.
 - Nuts and washers are not required on Jacked and Bored pipes or pipes with a 24" diameter or less. Where nuts and washers are not used, the tie bars shall be inserted and grouted into place.
 - Ties are only for holding pipe or RCB sections together, not for pulling sections tight.
 - Tie bolt assembly shall be hot dip galvanized in accordance with AASHTO M232.
 - Holes in pipes to accommodate tie bolts can be precast or drilled. Tapered holes are permitted when precast. Holes shall have a diameter $\frac{1}{4}$ " larger than the diameter of the thread. Holes in precast RCB's shall contain cast-in bolt sleeves with an inside diameter of 1 $\frac{1}{4}$ ".
 - The contractor has the option of selecting the type of tie bolt used from those shown.
 - The cost of precasting or drilling the required holes and furnishing and installing the tie bolts shall be included in the price bid for the appropriate conduit or RCB pay item.
 - All centerline and approach RCP culvert joints shall be tied. Storm drain systems shall have the first three joints including the end section of all free ends tied. Free ends are defined as any storm drain end which does not terminate at an inlet or manhole. Outfall culverts with end sections which drain adjacent ditches are examples of free ends.
 - Place joint wrap prior to installing ties. Overlap the joint by 12" in both directions.
 - Tie bolts shall conform to ASTM A 36. Nuts shall be heavy hex and conform to ASTM A 563. Washers shall conform to ASTM F 436, Type 1. Welded pipe sleeves and cast-in bolt sleeves shall conform to ASTM A 53, Grade B.
 - RCB tie locations shall be as shown on the plans.





DETAIL A




DETAIL B



PLAN VIEW



END VIEW







NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
3-18-14	
REVISIONS	
DATE	CHANGE
7-21-15 6-6-17	Note 8 Notes 2-11, Table, Title, Labels

This document was originally issued and sealed by Jonathan David Ketterling, Registration Number PE-4684, on 6/6/2017 and the original document is stored at the North Dakota Department of Transportation


OBJECT MARKERS - CULVERTS

D-754-83



Notes:

- Installation: Construction requirements shall meet 754.04D. Each end of culverts crossing the roadway within the right-of-way shall be marked with a post as shown. Posts are to be installed in front of the culvert in the direction of travel along the side of the culvert and one foot from the culvert opening unless shown otherwise on the plans.
- Posts: Posts shall conform to section 894.04A of the Standard Specifications with the exception that the post may or may not have holes drilled.
- Basis of Payment: The quantity will be measured by the number of object markers each installed. All costs for furnishing and installing the markers shall be included in the price bid for the item "Object Markers - Culverts".



NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-05-13	
REVISIONS	
DATE	CHANGE
7-7-14	Revised Notes

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 7/7/2014 and the original document is stored at the North Dakota Department of Transportation