


JOB # 6
NORTH DAKOTA
DEPARTMENT OF TRANSPORTATION


	STATE	PROJECT NO.	PCN	SECTION NO.	SHEET NO.
	ND	H-8-999(041)	22174	1	1

GOVERNING SPECIFICATIONS:
2014 Standard Specifications adopted by the North Dakota
Department of Transportation and the Supplemental Specifications
effective on the date the project is advertised.


PROJECT NUMBER \ DESCRIPTION NET MILES GROSS MILES
H-8-999(041) Weigh Station Flashing Beacons and Signs



Site 1
I - 94 Westbound
RP 342



Site 2
I - 29 North and Southbound
RP 24.06



STATE COUNTY MAP

DESIGNERS

Lyle Landstrom /s/

APPROVED DATE 06/04/2018

Robert Walton Jr /s/
FARGO DISTRICT ENGINEER
ND DEPARTMENT OF TRANSPORTATION

I hereby certify that the attached plans were
prepared by me or under my direct supervision
and that I am a duly registered professional
engineer under the laws of the state of ND.



APPROVED DATE 6/04/2018

Lyle Landstrom /s/
NDDOT FARGO DISTRICT

This document was originally
issued and sealed by
Lyle Landstrom
Registration Number
PE- 4079,
on 06/04/2018 and the original
document is stored at the
North Dakota Department
of Transportation

TABLE OF CONTENTS						STATE	PROJECT NO.	SECTION NO.	SHEET NO.
						ND	H-8-999(041)	2	1
PLAN SECTIONS					LIST OF STANDARD DRAWINGS				
Section	Page(s)	Description	Number	Description					
1	1	Title Sheet	D-101-1	NDDOT Abbreviations					
2	1	Table of Contents	D-101-2	NDDOT Abbreviations					
4	1	Scope of Work	D-101-3	NDDOT Abbreviations					
6	1	Notes	D-101-10	NDDOT Utility Company and Organization Abbreviations					
8	1	Quantities	D-101-20	Line Styles					
100	1	Work Zone Traffic Control	D-101-21	Line Styles					
110	1 - 6	Signing	D-101-30	Symbols					
150	1 - 9	Signals	D-101-31	Symbols					
			D-101-32	Symbols					
			D-704-11	Construction Sign Details - Warning Signs					
			D-704-24	Shoulder Closures And Bridge Painting Layouts					
			D-754-1	Pipe Or W-Shape Assembly Details					
			D-754-12	Breakaway Coupler System - Structural Details For W-Shape Supports					
			D-754-13	Breakaway System Structural Details For W-Shape Supports					
			D-754-14	Wind Beams And Anchor Plates For W-Shape Supports					
			D-770-3	Pull Box Details					

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	H-8-999(041)	004	1



This document was originally issued and sealed by
Lyle Landstrom /s/
Registration Number
PE- 4079,
on 06/04/2018 and the original document is stored at the
North Dakota Department
of Transportation

Scope of Work

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	H-8-999(041)	006	1

100-P01
COORDINATION WITH CONTRACTOR: There is a Prepass project at Site 2 in both directions which involves Electrical, Trenching, and New Signage. The contractor is to coordinate their activities with the Prepass contractor.

772-P02
EXISTING WEIGH STATION SWITCH: The existing switch inside the weigh station that operates the existing electronic OPEN / CLOSED signs shall be rewired to turn the power on and off to the Flash Cabinet. The Flash Cabinet shall be wired so the flashing beacons become activated once the switch inside the weigh station is turned on.

772-P03
FLASHING BEACON: This pay item is for the installation of the new Flashing Beacons and all related conduit, conductor, hardware, confirmation light, and other items mounted to the new sign structure. It also includes the removal of the existing electronic OPEN / CLOSED signs from the existing static sign assembly at Sites 1,2, and 3, and for the removal of the existing WEIGH STATION NEXT LEFT signs and posts at Site 2 northbound and southbound. The foundations for these will be paid for seperately.

This document was originally issued and sealed by
Lyle Landstrom /s/
Registration Number
PE- 4079,
on 06/04/2018 and the original document is stored at the
North Dakota Department
of Transportation

Notes

ESTIMATE OF QUANTITIES

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	H-8-999(041)	8	1

SPEC CODE	ITEM DESCRIPTION	UNIT	MAINLINE	TOTAL
-----	-----	----	-----	-----
103	0100 CONTRACT BOND	L SUM	1	1
702	0100 MOBILIZATION	L SUM	1	1
704	1000 TRAFFIC CONTROL SIGNS	UNIT	315	315
754	0214 GALV STEEL POSTS-W-SHAPE POSTS(TWO OR MORE)	LF	190	190
754	0534 PANEL FOR SIGNS-TYPE IV REFLECTIVE SHEETING	SF	230	230
754	1104 REMOVE SIGN FOUNDATION	EA	4	4
772	0101 STRUCTURAL SPLICE BOX	EA	3	3
772	0110 PULL BOX PVC WITH METAL FRAME & COVER	EA	6	6
772	0240 2IN DIAMETER RIGID CONDUIT	LF	5,037	5,037
772	0401 NO12 AWG 3 CONDUCTOR CABLE	LF	4,983	4,983
772	0403 NO12 AWG 5 CONDUCTOR CABLE	LF	281	281
772	0520 FEED POINT-FLASHING BEACON	EA	3	3
772	2160 FLASHING BEACON	EA	3	3

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	H-8-999(041)	100	1

SIGN NUMBER	SIGN SIZE	DESCRIPTION	AMOUNT REQUIRED	UNITS PER AMOUNT	UNITS SUB TOTAL
D3-36	36"x6"	STREET NAME SIGN (Sign and installation only)		6	
G20-1-60	60"x24"	ROAD WORK NEXT ___ MILES		34	
G20-1b-60	60"x24"	WORK IN PROGRESS/ NO WORK IN PROGRESS (Sign and installation only)		26	
G20-2-48	48"x24"	END ROAD WORK		19	
G20-4-36	36"x18"	PILOT CAR FOLLOW ME (Mounted to back of pilot car)		18	
G20-10-108	108"x48"	CONTRACTOR SIGN		64	
G20-50a-72	72"x36"	ROAD WORK NEXT ___ MILES RT & LT ARROWS		37	
G20-52a-72	72"x24"	ROAD WORK NEXT ___ MILES RT or LT ARROW		30	
G20-55-96	96"x48"	SPEED LIMIT ENFORCED - MINIMUM FEE \$80 WHEN WORKERS PRESENT		59	
M1-1-36	36"x36"	INTERSTATE ROUTE MARKER (Post and installation only)		10	
M1-4-24	24"x24"	U.S. ROUTE MARKER (Post and installation only)		10	
M1-5-24	24"x24"	STATE ROUTE MARKER (Post and installation only)		10	
M3-1-24	24"x12"	NORTH (Mounted on route marker post)		7	
M3-2-24	24"x12"	EAST (Mounted on route marker post)		7	
M3-3-24	24"x12"	SOUTH (Mounted on route marker post)		7	
M3-4-24	24"x12"	WEST (Mounted on route marker post)		7	
M4-8-24	24"x12"	DETOUR (Mounted on route marker post)		7	
M4-9-30	30"x24"	DETOUR ARROW RIGHT or LEFT/AHD AND RT or LT		15	
M4-10-48	48"x18"	DETOUR ARROW RIGHT or LEFT		23	
M5-1-21	21"x15"	ARROW AHD AND RT or LT (Mounted on route marker post)		7	
M5-2-21	21"x15"	ARROW AHD UP & RT or LT (Mounted on route marker post)		7	
M6-1-21	21"x15"	ARROW RT or LT (Mounted on route marker post)		7	
M6-2-21	21"x15"	ARROW UP & RT or LT (Mounted on route marker post)		7	
M6-3-21	21"x15"	ARROW AHD (Mounted on route marker post)		7	
R1-1-48	48"x48"	STOP		32	
R1-1a-18	18"x18"	STOP and SLOW PADDLE Back to Back		5	
R1-2-60	60"x60"	YIELD		29	
R2-1-48	48"x60"	SPEED LIMIT ___		39	
R2-1a-24	24"x18"	MINIMUM FEE \$80 (Mounted on Speed Limit post)		10	
R3-7-48	48"x48"	LEFT or RIGHT LANE MUST TURN LEFT or RIGHT		35	
R4-1-48	48"x60"	DO NOT PASS		39	
R4-7-48	48"x60"	KEEP RIGHT SYMBOL		39	
R5-1-48	48"x48"	DO NOT ENTER		35	
R6-1-36	36"x12"	ONE WAY RIGHT or LEFT		13	
R7-1-12	12"x18"	NO PARKING		11	
R10-6-24	24"x36"	STOP HERE ON RED		16	
R11-2-48	48"x30"	ROAD CLOSED		28	
R11-2a-48	48"x30"	STREET CLOSED		28	
R11-3a-60	60"x30"	ROAD CLOSED ___ MILES AHEAD LOCAL TRAFFIC ONLY		31	
R11-3c-60	60"x30"	STREET CLOSED ___ MILES AHEAD LOCAL TRAFFIC ONLY		31	
R11-4a-60	60"x30"	STREET CLOSED TO THRU TRAFFIC		31	
W1-3-48	48"x48"	RIGHT or LEFT SHARP REVERSE CURVE ARROW		35	
W1-4-48	48"x48"	RIGHT or LEFT REVERSE CURVE ARROW		35	
W1-4b-48	48"x48"	DOUBLE RIGHT or LEFT REVERSE CURVE ARROW		35	
W1-6-48	48"x24"	LARGE ARROW		26	
W3-1-48	48"x48"	STOP AHEAD SYMBOL		35	
W3-3-48	48"x48"	SIGNAL AHEAD SYMBOL		35	
W3-4-48	48"x48"	BE PREPARED TO STOP		35	
W3-5-48	48"x48"	SPEED REDUCTION AHEAD		35	
W4-2-48	48"x48"	RIGHT or LEFT LANE TRANSITION SYMBOL		35	
W5-1-48	48"x48"	ROAD NARROWS		35	
W5-8-48	48"x48"	THRU TRAFFIC RIGHT LANE		35	
W5-9-48	48"x48"	ROAD WORK TRAFFIC ONLY DOWN & LT or RT ARROW		35	
W6-3-48	48"x48"	TWO WAY TRAFFIC SYMBOL		35	
W8-1-48	48"x48"	BUMP		35	
W8-3-48	48"x48"	PAVEMENT ENDS		35	
W8-7-48	48"x48"	LOOSE GRAVEL		35	
W8-9a-48	48"x48"	SHOULDER DROP-OFF		35	
W8-11-48	48"x48"	UNEVEN LANES		35	
W8-12-48	48"x48"	NO CENTER STRIPE		35	
W8-53-48	48"x48"	TRUCKS ENTERING HIGHWAY		35	
W8-54-48	48"x48"	TRUCKS ENTERING AHEAD or ___ FT.		35	
W8-55-48	48"x48"	TRUCKS CROSSING AHEAD or ___ FT.		35	
W8-56-48	48"x48"	TRUCKS EXITING HIGHWAY		35	
W9-3a-48	48"x48"	CENTER LANE CLOSED SYMBOL		35	
W12-2-48	48"x48"	LOW CLEARANCE SYMBOL		35	
W13-1-24	24"x24"	___ MPH ADVISORY SPEED PLATE (Mounted on warning sign post)		11	
W13-4-48	48"x60"	RAMP ARROW		39	
W14-3-48	48"x36"	NO PASSING ZONE		23	
W20-1-48	48"x48"	ROAD WORK AHEAD or ___ FT or ___ MILE	3	35	105
W20-2-48	48"x48"	DETOUR AHEAD or ___ FT		35	
W20-3-48	48"x48"	ROAD or STREET CLOSED AHEAD or ___ FT.		35	

[illegible][illegible]

SPEC & CODE			
704-1000	TRAFFIC CONTROL SIGNS	TOTAL UNITS	315

SPEC & CODE	DESCRIPTION	UNIT	QUANTITY
704-0100	FLAGGING	MHR	
704-1041	ATTENUATION DEVICE-TYPE B-55	EACH	
704-1043	ATTENUATION DEVICE-TYPE B-65	EACH	
704-1044	ATTENUATION DEVICE-TYPE B-70	EACH	
704-1050	TYPE I BARRICADES	EACH	
704-1051	TYPE II BARRICADES	EACH	
704-1052	TYPE III BARRICADES	EACH	
704-1060	DELINEATOR DRUMS	EACH	
704-1065	TRAFFIC CONES	EACH	30
704-1067	TUBULAR MARKERS	EACH	
704-1070	DELINEATOR	EACH	
704-1072	FLEXIBLE DELINEATORS	EACH	
704-1081	VERTICAL PANELS - BACK TO BACK	EACH	
704-1085	SEQUENCING ARROW PANEL - TYPE A	EACH	
704-1086	SEQUENCING ARROW PANEL - TYPE B	EACH	
704-1087	SEQUENCING ARROW PANEL - TYPE C	EACH	
704-1088	SEQUENCING ARROW PANEL - TYPE C - CROSSOVER	EACH	
704-1095	TYPE B FLASHERS	EACH	
704-1500	OBLITERATION OF PVMT MK	SF	
704-3501	PORTABLE PRECAST CONCRETE MED BARRIER	LF	
704-3510	PRECAST CONCRETE MED BARRIER - STATE FURNISHED	EACH	
762-0200	RAISED PAVEMENT MARKERS	EACH	
762-0420	SHORT TERM 4IN LINE - TYPE R	LF	
762-0430	SHORT TERM 4IN LINE - TYPE NR	LF	
772-2110	FLASHING BEACON - POST MOUNTED	EACH	


NOTE:
If additional signs are required, units will be calculated using the formula from Section III-19.06 of the Design Manual.
<http://www.dot.nd.gov/>

This document was
originally issued
and sealed by
Lyle Landstrom,
Registration Number
PE-4079,
on 6/4/18 and the
original document
is stored at the North Dakota
Department of Transportation.

Traffic Control Devices List

																					STATE	PROJECT NO.				SECTION NO.	SHEET NO.	
																					N.D.	H-8-999(041)				110	1	
	Sign / Assembly	Flat Sheet For Signs		Panel For Signs		Overlay Panel		Vert Clear-ance	Galv Steel Sheet			Galv Steel Post W-Shape Posts			Max Post Len	Post Space	Revise Fuse Joint	Std Pipe Fdn			W-Shape Pile	Remove Sign Fdns		Reset Sign Panel	Reset Sign Support	Stub Post	Multi Dir Base	
Station / RP	No.	IV SF	XI SF	IV SF	XI SF	IV SF	XI SF	FT	1st	2nd	Size	1st LF	2nd LF	3rd LF	LF	FT	EA	FT	FT	Vol CY	LF	Conc Fdn	W-Shape Pile	EA	EA	EA	EA	Comments
I-94 342.155 Lt	SN 1			76.5				5.0			W6x20	17.6	17.6		25.6	4.5					28							
I-29 23.871 Rt	SN 2			76.5				5.0			W6x20	17.6	17.6		25.6	4.5					28							
I-29 24.873 Lt	SN 2			76.5				5.0			W6x20	17.6	17.6		25.6	4.5					28							
I-29 23.871 Rt																							2					
I-29 24.873 Lt																							2					
Sub Total				229.5				Total		0.0		Total	105.6							0.0	84	0	4	0	0	0	0	
Grand Total				229.5				Total		0.0		Total	105.6							0.0	84	0	4	0	0	0	0	

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	H-8-999(041)	110	2





Note, The electronic OPEN / CLOSED sign shall be removed from the existing sign structure. All electrical cabling shall be disconnected and terminated below grade and within the Scalehouse building. Removed sign shall be delivered to the Fargo District in operational condition.

The remaining Weigh Station sign shall remain in place.

This document was originally issued and sealed by
Lyle Landstrom /s/
Registration Number
PE- 4079,
on 06/04/2018 and the original document is stored at the
North Dakota Department
of Transportation

Sign Layout
Site 1
I-94 West Bound

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	H-8-999(041)	110	3





Note, The electronic OPEN / CLOSED sign shall be removed from the existing sign structure. All electrical cabling shall be disconnected and terminated below grade and within the Scalehouse building. Removed sign shall be delivered to the Fargo District in operational condition. The remaining Weigh Station sign shall remain in place.

This document was originally issued and sealed by
Lyle Landstrom /s/
Registration Number
PE- 4079,
on 06/04/2018 and the original document is stored at the
North Dakota Department
of Transportation

Sign layout
Site 2
I-29 Northbound
RP 23.871 to 24.155

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	H-8-999(041)	110	4





Note, The electronic OPEN / CLOSED sign shall be removed from the existing sign structure. All electrical cabling shall be disconnected and terminated below grade and within the Scalehouse building. Removed sign shall be delivered to the Fargo District in operational condition.

The remaining Weigh Station sign shall remain in place.

This document was originally issued and sealed by
LyleLandstrom /s/
Registration Number
PE- 4079,
on 06/04/2018 and the original document is stored at the
North Dakota Department
of Transportation

Sign Layout
Site 2
I-29
RR 24.465 to 24.665


	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	H-8-999(041)	110	5



This document was originally issued and sealed by
Lyle Landstrom /s/
Registration Number
PE- 4079,
on 06/04/2018 and the original document is stored at the
North Dakota Department
of Transportation

Sign Layout
Site 2
I-29
RP 24.465 to 24.873

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	H-8-999(041)	150	1




Note:
The new conductor shall enter the Scale house building in the same location as the existing conductor.
Remove all existing conductors from the new pullbox to the breaker panel located inside the building.
The exact location of the new PB 1 will be determined when the existing conductor is excavated and the end of the conduit is discovered.
New conductor shall be unspliced the entire length from the Scale Building to the Flashing Beacon Location. Pullboxes are for pulling purposes only.

This document was originally issued and sealed by
Lyle ~~perman~~ /s/
Registration Number
PE- ~~1079~~,
on ~~06/04/2018~~ and the original document is stored at the
North Dakota Department of Transportation

Site 1
I-94 West bound
Rp 341.726



	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	H-8-999(041)	150	2



This document was originally issued and sealed by
Lyle Landstrom /s/
Registration Number
PE- 4079,
on 06/04/2018 and the original document is stored at the
North Dakota Department
of Transportation

Site 1
I-94 West Bound



	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	H-8-999(041)	150	4



This document was originally issued and sealed by
Lyle Landstrom /s/
Registration Number
PE- 4079,
on 06/04/2018 and the original document is stored at the
North Dakota Department
of Transportation

Site 2
I-29 Northbound
RP 24.155 to 24.465



	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	H-8-999(041)	150	5



This document was originally issued and sealed by
Lyle Landstrom /s/
Registration Number
PE- 4079,
on 06/04/2018 and the original document is stored at the
North Dakota Department
of Transportation

Site 2
I-29
RR 24.465 to 24.665

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	H-8-999(041)	150	6



This document was originally
issued and sealed by
Lyle Landstrom /s/
Registration Number
PE- 4079,
on 06/04/2018 and the original
document is stored at the
North Dakota Department
of Transportation

Site 2
I-29
RP 24.465 to 24.873

Site 1, I-94 Westbound RP 341.726

STATION	CONDUIT	RUNS	CABLE TRENCH	CABLE	RUNS
	LF	DIA	LF	LF	TYPE
Inside Scalehouse				100	No 12 AWG 3
Existing Scalehouse to PB 1, RP 341.730 - 222' Lt				51	No. 12 AWG 3
PB 1, RP 341.730 - 222' Lt. to PB 2, 341.730 - 296' Lt.	36	2"		42	No. 12 AWG 3
PB 2, 341.730 - 296' Lt. to RP 341.868 - 296' Lt.	728	2"		728	No. 12 AWG 3
RP 341.868 - 296' Lt. to RP 341.888 - 196' Lt.	148	2"		148	No. 12 AWG 3
RP 341.888 196' Lt. to Flash Cabinet RP 342.155 - 196' Lt	1461	2"		1465	No. 12 AWG 3
Flash Cabinet RP 342.155 - 196' Lt to Flashing Beacon RP 342.155 - 114' Lt	82	2"		90	No. 12 AWG 5

Site 2, I-29 Northbound RP 23.871

STATION	CONDUIT	RUNS	CABLE TRENCH	CABLE	RUNS
	LF	DIA	LF	LF	TYPE
Flasher Cabinet RP 871 - 140' Rt to SN 2 RP 23.871 - 72' Rt	68	2"		76	No. 12 AWG 5
Flasher Cabinet RP 871 - 140' Rt to PB 4 RP 23.871 - 22' Lt	162	2"		170	No 12 AWG 3
PB 4 RP 23.871 - 22' Lt to PB 3 RP 24.066 - 22 ft. Lt	980	2"		992	No 12 AWG 3

Site 2, I-29 Southbound RP 24.465

STATION	CONDUIT	RUNS	CABLE TRENCH	CABLE	RUNS
	LF	DIA	LF	LF	TYPE
PB 5 RP 24.665 - 38.5 Rt. To PB 6 RP 24.873 - 22 Ft. Rt.	1098	2"		1110	No 12 AWG 3
PB 6 RP 24.873 - 22 Ft. Rt. To Flasher Cabinet RP 24.873 - 145 Ft. Lt	167	2"		177	No 12 AWG 3
Flasher Cabinet RP 24.873 - 145 Ft. Lt to SN 2 RP 24.873 - 38 ft Lt.	107	2"		115	No. 12 AWG 5

QUANTITIES (A)													
		Remove Electronic OPEN / CLOSED SIGN (A)	Remove Weigh Station Next Left Sign	2" Dia. Rigid Conduit	No. 12 AWG 3 Conductor Cable	No. 12 AWG 5 Conductor Cable	Structural Splice Box	Feed Point - Flashing Beacon	Concrete Pad (B)	PVC Pullbox			
Site 1		1		2455	2534	90	1	1	1	2			
Site 2 NB		1	1	1210	1162	76	1	1	1	2			
Site 2 SB		1	1	1372	1287	115	1	1	1	2			


(A) These items shall not be bid seperately but shall be included in the item Flashing Beacon

(B) These items shall not be bid seperately but shall be included In the Item Feed Point - Flashing Beacon

This document was originally issued and sealed by
Lyle Landstrom /s/
Registration Number
PE- 4079,
on 06/04/2018and the original document is stored at the
North Dakota Department
of Transportation

I-94 West bound
Rp 341.726
Flashing Beacon Cable Runs and Quantities



	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	8-8-999(041)	150	8



This document was originally issued and sealed by
Lyle Landstrom /s/
Registration Number
PE- 4079,
on 06/04/2018 and the original document is stored at the
North Dakota Department
of Transportation

Flashing Beacon
Assembly Details
Site 1, Site 2, Site 3

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	H-8-999(041)	150	9



Note:
Mount as close to the Right of
Way fence as possible.

All costs to install Flasher Cabinet
including concrete foundation
shall be included in the Pay Item
Feed Point - Flashing Beacon

This document was originally
issued and sealed by
Lyle Landstrom /s/
Registration Number
PE- 4079,
on 06/04/2018 and the original
document is stored at the
North Dakota Department
of Transportation

Flashing Beacon Post Mounted

Flasher Cabinet Pipe Stand Mounted Detail

?	This is a special text character used in the labeling of existing features. It indicates a feature that has an unknown characteristic, potentially based on: lack of description, location accuracy or purpose.	Bldg	building	CSP	corrugated steel pipe	EDM	electronic distance meter
Abn	abandoned	BV	butterfly valve	CSTES	corrugated steel traversable end section	Elev or El	elevation
Abut	abutment	Byp	bypass	C	coulomb	Ellipt	elliptical
Ac	acres	C Gdrl	cable guardrail	Co	County	Emb	embankment
Adj	adjusted	Calc	calculate	Crse	course	Emuls	emulsion/emulsified
Aggr	aggregate	Cd	candela	Ct	Court	ES	end section
Ahd	ahead	CIP	cast iron pipe	Xarm	cross arm	Engr	engineer
ARV	air release valve	CB	catch basin	Xbuck	cross buck	ESS	environmental sensor station
Align	alignment	CRS	cationic rapid setting	Xsec	cross sections	Eq	equal
Al	alley	C Gd	cattle guard	Xing	crossing	Eq	equation
Alt	alternate	C To C	center to center	Xrd	Crossroad	Evgr	evergreen
Alum	aluminum	Cl or \varnothing	centerline	Crn	crown	Exc	excavation
ADA	Americans with Disabilities Act	Cm	centimeter	CF	cubic feet	Exst	existing
A	ampere	Ch	chain	M3	cubic meter	Exp	expansion
&	and	Chnlk	chain-link	M3/s	cubic meters per second	Expy	Expressway
Appr	approach	Ch Blk	channel block	CY	cubic yard	E	external of curve
Approx	approximate	Ch Ch	channel change	Cy/mi	cubic yards per mile	Extru	extruded
ACP	asbestos cement pipe	Chk	check	Culv	culvert	FOS	factor of safety
Asph	asphalt	Chsld	chiseled	C&G	curb & gutter	F	Fahrenheit
AC	asphalt cement	Cir	circle	CI	curb inlet	FS	far side
Assmd	assumed	Cl	class	CR	curb ramp	F	farad
@	at	Cl	clay	CS	curve to spiral	Fed	Federal
Atten	attenuation	Cl F	clay fill	C	cut	FP	feed point
ATR	automatic traffic recorder	Cl Hvy	clay heavy	Dd Ld	dead load	Ft	feet/foot
Ave	Avenue	Cl Lm	clay loam	Defl	deflection	Fn	fence
Avg	average	Clnt	clean-out	Defm	deformed	Fn P	fence post
ADT	average daily traffic	Clr	clear	Deg or D	degree	FO	fiber optic
Az	azimuth	Cl&gr	clearing & grubbing	DInt	delineate	FB	field book
Bk	back	Co S	coal slack	DIntr	delineator	FD	field drive
BF	back face	C Gr	coarse gravel	Depr	depression	F	fill
Bs	backsight	CS	coarse sand	Desc	description	FAA	fine aggregate angularity
Balc	balcony	Comb.	combination	Det	detail	FS	fine sand
B Wire	barbed wire	Coml	commercial	DWP	detectable warning panel	FH	fire hydrant
Barr	barricade	Compr	compression	Dtr	detour	Fl	flange
Btry	battery	CADD	computer aided drafting & design	Dia or \varnothing	diameter	Flrd	flared
Brg	bearing	Conc	concrete	Dir	direction	FES	flared end section
BI	beehive inlet	CECB	concrete erosion control blanket	Dist	distance	F Bcn	flashing beacon
Beg	begin	Cond	conductor	DM	disturbed material	FA	flight auger sample
BM	bench mark	Const	construction	DB	ditch block	FL	flow line
Bkwy	bikeway	Cont	continuous	DG	ditch grade	Ftg	footing
Bit	bituminous	CSB	continuous split barrel sample	Dbl	double	FM	force main
Blk	block	Contr	contraction	Dn	down	Fs	foresight
Bd Ft	board feet	Contr	contractor	Dwg	drawing		
BH	bore hole	CP	control point	Dr	drive		
BS	both sides	Coord	coordinate	Drwy	driveway		
Bot	bottom	Cor	corner	DI	drop inlet		
Blvd	Boulevard	Corr	corrected	D	dry density		
Bndry	boundary	CAES	corrugated aluminum end section	Ea	each		
BC	brass cap	CAP	corrugated aluminum pipe	Esmt	easement		
Brkwy	breakaway	CMES	corrugated metal end section	E	East		
Br	bridge	CMP	corrugated metal pipe	EB	Eastbound		
		CPVCP	corrugated poly-vinyl chloride pipe	Elast	elastomeric		
		CSES	corrugated steel end section	EL	electric locker		
		CSFES	corrugated steel flared end section	E Mtr	electric meter		
				Elec	electric/al		

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
04-23-18	General Revisions

This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930 , on 04/23/18 and the original document is stored at the North Dakota Department of Transportation

NDDOT ABBREVIATIONS

D-101-2

Fnd	found	ID	inside diameter	Mkg	marking	PMT	pad mounted transformer
Fdn	foundation	Inst	instrument	MA	mast arm	Pg	pages
Frac	fractional	Intchg	interchange	Matl	material	Pntd	painted
Frwy	freeway	Intmdt	intermediate	Max	maximum	Pr	pair
Frt	front	Intscn	intersection	MC	meander corner	Pnl	panel
FF	front face	Inv	invert	Meas	measure	Pk	park
F Disp	fuel dispenser	IM	iron monument	Mdn	median	PK	Parker-Kalon nail
FFP	fuel filler pipes	I Pn	Iron Pin	MD	median drain	Pa	pascal
FLS	fuel leak sensor	IP	iron Pipe	MC	medium curing	PSD	passing sight distance
Furn	furnish/ed	Jt	joint	M	mega	Pvmt	pavement
Gal	gallon	J	joule	Mer	meridian	Ped	pedestal
Galv	galvanized	Jct	junction	M	meter	Ped	pedestrian
Gar	garage	K	kelvin	M/s	meters per second	PPP	pedestrian pushbutton post
Gs L	gas line	Kn	kilo newton	M	mid ordinate of curve	Pen.	penetration
G Reg	gas line regulator	Kpa	kilo pascal	MGS	Midwest Guardrail System	Perf	perforated
GMV	gas main valve	Kg	kilogram	Mi	mile	Per.	perimeter
G Mtr	gas meter	Kg/m3	kilogram per cubic meter	MM	mile marker	PL	pipeline
GSV	gas service valve	Km	kilometer	MP	mile post	PI	place
GVP	gas vent pipe	K	Kip(s)	MI	milliliter	P&P	plan & profile
GV	gate valve	LS	Land Surveyor (licensed)	Mm	millimeter	PL	plastic limit
Ga	gauge	LSIT	Land Surveyor In Training	Mm/hr	millimeters per hour	P Cap	plastic cap
Geod	geodetic	Ln	lane	Min	minimum	PI or \overline{P}	plate
GIS	Geographical Information System	Lg	large	Misc	miscellaneous	Pt	point
G	giga	Lat	latitude	Mon	monument	PCC	point of compound curve
GPS	Global Positioning System	Lt	left	Mnd	mound	PC	point of curve
Gov	government	L	length of curve	Mtbl	mountable	PI	point of intersection
Grd	graded/grade	Lens	lenses	Mtd	mounted	PRC	point of reverse curvature
Gr	gravel	Lvl	level	Mtg	mounting	PT	point of tangent
Grnd	ground	LB	level book	Mk	muck	POC	point on curve
GWM	ground water monitor	Lvng	leveling	Mun	municipal	POT	point on tangent
Gdrl	guardrail	Lht	light	N	nano	PE	polyethylene
Gtr	gutter	LP	light pole	NGS	National Geodetic Survey	PVC	polyvinyl chloride
H Plg	H piling	Ltg	lighting	NS	near side	PCC	Portland Cement concrete
Hdwl	headwall	Lig Co	lignite coal	Neop	neoprene	Lb or #	pounds
Ha	hectare	Lig Sl	lignite slack	Ntwk	network	PP	power pole
Ht	height	LF	linear foot	N	newton	Preempt	preemption
HI	height of instrument	Liq	liquid	N	North	Prefab	prefabricated
Hel	helical	LL	liquid limit	NE	North East	Prfmd or Pref	preformed
H	henry	L	litre	NW	North West	Prep	preperation
Hz	hertz	Lm	loam	NB	Northbound	Press.	pressure
HDPE	high density polyethylene	Loc	location	No. or #	number		
HM	high mast	LC	long chord	Obsc	obscure(d)		
HP	high pressure	Long.	longitude	Obsn	observation		
HPS	high pressure sodium	Lp	loop	Ocpd	occupied		
Hwy	highway	LD	loop detector	Ocpy	occupy		
Hor	horizontal	Lm	lumen	Off Loc	office location		
HBP	hot bituminous pavement	Lum	luminaire	O/s	offset		
HMA	hot mix asphalt	L Sum	lump sum	OC	on center		
Hr	hour(s)	Lx	lux	C	one dimensional consolidation		
Hyd	hydrant	Mb	mailbox	OC	organic content		
Ph	hydrogen ion content	ML	main line	Orig	original		
Id	identification	M Hr	man hour	O To O	out to out		
In or "	inch	MH	manhole	OD	outside diameter		
Incl	inclinometer tube	Mkd	marked	OH	overhead		
IMH	inlet manhole	Mkr	marker				

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
08-03-15 04-23-18	General Revisions General Revisions

This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930 , on 04/23/18 and the original document is stored at the North Dakota Department of Transportation

NDDOT ABBREVIATIONS

D-101-3

PRV	pressure relief valve	Sc	scoria	St	street	Vert	vertical
Prestr	prestressed	Sec	seconds	SPP	structural plate pipe	VC	vertical curve
Pvt	private	Sec	section	SPPA	structural plate pipe arch	VCP	vitrified clay pipe
PD	private drive	SL	section line	Str	structure	V	volt
Prod.	production/produce	Sep	separation	Subd	subdivision	Vol	volume
Prog	programmed	Seq	sequence	Sub	subgrade	Wkwy	walkway
Prop.	property	Serv	service	Sub Prep	subgrade preperation	W	water content
Prop Ln	property line	Sh	shale	Ss	subsoil	WGV	water gate valve
Ppsd	proposed	Sht	sheet	SE	superelevation	WL	water line
PB	pull box	Shtng	sheeting	SS	supplement specification	WM	water main
Qty	quantity	Shldr	shoulder	Supp	supplemental	WMV	water main valve
Qtr	quarter	Sw or Sdwk	sidewalk	Surf	surfacing	W Mtr	water meter
Rad or R	radius	S	siemens	Surv	survey	WSV	water service valve
RR	railroad	SD	sight distance	Sym	symmetrical	WW	water well
Rlwy	railway	SN	sign number	SI	systems international	W	watt
Rsd	raised	Sig	signal	Tan	tangent	Wrng	wearing
RTP	random traverse point	Si Cl	silt clay	T	tangent (semi)	Wb	weber
Rge or R	range	Si Cl Lm	silty clay loam	TS	tangent to spiral	WIM	weigh in motion
RC	rapid curing	Si Lm	silty loam	Tel	telephone	W	west
Rec	record	Sgl	single	Tel B	Telephone Booth	WB	westbound
Rcy	recycle	SRCP	slotted reinforced concrete pipe	Tel P	telephone pole	Wrng	wiring
RAP	recycled asphalt pavement	SC	slow curing	Tv	television	W/	with
RPCC	recycled portland cement concrete	SS	slow setting	Temp	temperature	W/o	without
Ref	reference	Sm	small	Temp	temporary	WC	witness corner
R Mkr	reference marker	S	South	TBM	temporary bench mark	WGS	world geodetic system
RM	reference monument	SE	South East	T	tesla	Z	zenith
RP	reference point	SW	South West	T	thinwall tube sample		
Refl	reflectorized	SB	Southbound	T/mi	tons per mile		
RCB	reinforced concrete box	Sp	spaces	Ts	topsoil		
RCES	reinforced concrete end section	Spcl	special	Twp or T	township		
RCFES	reinforced concrete flared end section	SA	special assembly	Traf	traffic		
RCTES	reinforced concrete traversable end section	SP	special provisions	TSCB	traffic signal control box		
RCP	reinforced concrete pipe	G	specific gravity	Tr	trail		
RCPS	reinforced concrete pipe sewer	Spk	spike	Transf	transformer		
Reinf	reinforcement	SC	spiral to curve	TB	transit book		
Res	reservation	ST	spiral to tangent	Trans	transition		
Rs	residence	SB	split barrel sample	TT	transmission tower		
Ret	retaining	SH	sprinkler head	TES	traversable end section		
Rev	reverse	SV	sprinkler valve	Trans	transverse		
Rt	right	Sq	square	Trav	traverse		
R/W	right of way	SF	square feet	TP	traverse point		
Riv	river	Km2	square kilometer	Trtd	treated		
Rd	road	M2	square meter	Trmt	treatment		
Rdbd	road bed	SY	square yard	Qc	triaxial compression		
Rdwy	roadway	Stk	stake	TERO	tribal employment rights ordinance		
RWIS	roadway weather information system	Std	standard	Tpl	triple		
Rk	rock	N	standard penetration test	TP	turning point		
Rt	route	Std Specs	standard specifications	Typ	typical		
Salv	salvage(d)	Sta	station	Qu	unconfined compressive strength		
Sd	sand	Sta Yd	station yards	Ugrnd	underground		
Sdy Cl	sandy clay	Stm L	steam line	USC&G	US Coast & Geodetic Survey		
Sdy Cl Lm	sandy clay loam	SEC	steel encased concrete	USGS	US Geologic Survey		
Sdy Fl	sandy fill	SMA	stone matrix asphalt	Util	utility		
Sdy Lm	sandy loam	SSD	stopping sight distance	VG	valley gutter		
San	sanitary sewer line	SD	storm drain	Vap	vapor		

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
08-03-15 04-23-18	General Revisions General Revisions

This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930 , on 04/23/18 and the original document is stored at the North Dakota Department of Transportation

NDDOT UTILITY COMPANY AND ORGANIZATION ABBREVIATIONS

D-101-10
























702COM	702 Communications	GT PLNS NAT GAS	Great Plains Natural Gas Company	RED RIV TEL	Red River Rural Telephone
ACCENT	Accent Communications	HALS TEL	Halstad Telephone Company	RESVTN TEL	Reservation Telephone
AGASSIZ WU	Agassiz Water Users Incorporated	IDEA1	Idea1	ROBRTS TEL	Roberts Company Telephone
AGC	Associated General Contractors of America	INT-COMM TEL	Inter-Community Telephone Company	R-RIDER ELEC	Roughrider Electric Cooperative
AI PI	Alliance Pipeline	KANEB PL	Kaneb Pipeline Company	RRVW	Red River Valley & Western Railroad
ALL SEAS WU	All Seasons Water Users Association	KEM ELEC	Kem Electric Cooperative Incorporated	S CENT REG WD	South Central Regional Water District
AMOCO PI	Amoco Pipeline Company	KOCH GATH SYS	Koch Gathering Systems Incorporated	S E W U	South East Water Users Incorporated
AMRDA HESS	Amerada Hess Corporation	LKHD PL	Lakehead Pipeline Company	SCOTT CABLE	Scott Cable Television Dickinson
AT&T	AT&T Corporation	LNGDN RWU	Langdon Rural Water Users Incorporated	SHERDN ELEC	Sheridan Electric Cooperative
B PAW	Bear Paw Energy Incorporated	LWR YELL R ELEC	Lower Yellowstone Rural Electric	SHEYN VLY ELEC	Sheyenne Valley Electric Cooperative
BAKER ELEC	Baker Electric	MCKNZ CON	McKenzie Consolidated Telcom	SKYTECH	Skyland Technologies Incorporated
BASIN ELEC	Basin Electric Cooperative Incorporated	MCKNZ ELEC	McKenzie Electric Cooperative	SLOPE ELEC	Slope Electric Cooperative Incorporated
BEK TEL	Bek Communications Cooperative	MCKNZ WRD	McKenzie County Water Resource District	SOURIS RIV TELCOM	Souris River Telecommunications
BELLE PL	Belle Fourche Pipeline Company	MCLEOD	McLeod USA	ST WAT COMM	State Water Commission
BLM	Bureau of Land Management	MCLN ELEC	McLean Electric Cooperative	STATE LN WATER	State Line Water Cooperative
BNSF	Burlington Northern Santa Fe Railway	MCLN-SHRDN R WAT	McLean-Sheridan Rural Water	STER ENG	Sterling Energy
BOEING	Boeing	MDU	Montana-dakota Utilities	STUT RWU	Stutsman Rural Water Users
BRNS RWD	Barnes Rural Water District	MID-CONT CABLE	Mid-Continent Cable	SW PL PRJ	Southwest Pipeline Project
BURK-DIV ELEC	Burke-Divide Electric Cooperative	MIDSTATE TEL	Midstate Telephone Company	T M C	Turtle Mountain Communications
BURL WU	Burleigh Water Users	MINOT CABLE	Minot Cable Television	TCI	TCI of North Dakota
Cable One	Cable One	MINOT TEL	Minot Telephone Company	TESORO HGH PLNS PL	Tesoro High Plains Pipeline
CABLE SERV	Cable Services	MISS VALL COMM	Missouri Valley Communications	TRI-CNTY WU	Tri-County Water Users Incorporated
CAP ELEC	Capital Electric Cooperative Incorporat	MISS W W S	Missouri West Water System	TRL CO RWU	Traill County Rural Water Users
CASS CO ELEC	Cass County Electric Cooperative	MNKOTA PWR	Minnkota Power	UNTD TEL	United Telephone
CASS RWU	Cass Rural Water Users Incorporated	MOR-GRAN-SOU ELEC	Mor-gran-sou Electric Cooperative	UPPR SOUR WUA	Upper Souris Water Users Association
CAV ELEC	Cavalier Rural Electric Cooperative	MOUNT-WILLI ELEC	Mountrail-williams Electric Cooperative	US SPRINT	U.S. Sprint
CBLCOM	Cablecom Of Fargo	MRE LBTY TEL	Moore & Liberty Telephone	USAF MSL CABLE	U.S.A.F. Missile Cable
CENEX PL	Cenex Pipeline	MUNICIPAL	City Water And Sewer	USFWS	US Fish and Wildlife Service
CENT PL WATER DIST	Central Pipe Line Water District	MUNICIPAL	City Of '.....'	USW COMM	U.S. West Communications
CENT PWR ELEC	Central Power Electric Cooperative	N CENT ELEC	North Central Electric Cooperative	VRNDRY ELEC	Verendrye Electric Cooperative
COE	Corps of Engineers	N VALL W DIST	North Valley Water District	W RIV TEL	West River Telephone Incorporated
CONS TEL	Consolidated Telephone	ND PKS & REC	North Dakota Parks And Recreation	WEB	W. E. B. Water Development Association
CONT RES	Continental Resource Inc	ND TEL	North Dakota Telephone Company	WILLI RWA	Williams Rural Water Association
CPR	Canadian Pacific Railway	NDDOT	North Dakota Department of Transportation	WILSTN BAS PL	Williston Basin Interstate Pipeline Company
D O E	Department Of Energy	NDSU SOIL SCI DEPT	NDSU Soil Science Department	WLSH RWD	Walsh Water Rural Water District
DAK CARR	Dakota Carrier Network	NEMONT TEL	Nemont Telephone	WOLVRTN TEL	Wolverton Telephone
DAK CENT TEL	Dakota Central Telephone	NODAK R ELEC	Nodak Rural Electric Cooperative	XLENER	Xcel Energy
DAK RWD	Dakota Rural Water District	NOON FRMS TEL	Noonan Farmers Telephone Company	YSVR	Yellowstone Valley Railroad
DGC	Dakota Gasification Company	NPR	Northern Plains Railroad		
DICKEY R NET	Dickey Rural Networks	NSP	Northern States Power		
DICKEY RWU	Dickey Rural Water Users Association	NTH PRAIR RW	Northern Prairie Rural Water Association		
DICKEY TEL	Dickey Telephone	NTHN BRDR PL	Northern Border Pipeline		
DNRR	Dakota Northern Railroad	NTHN PLNS ELEC	Northern Plains Electric Cooperative Incorporated		
DO ME PL	Dome Pipeline Company	NTHWSTRN REF	Northwestern Refinery Company		
DVELEC	Dakota Valley Electric Cooperative	NW COMM	Northwest Communication Cooperation		
DVMW	Dakota, Missouri Valley & Western	ONEOK	Oneok gas		
ENBRDG	Enbridge Pipelines Incorporated	OSHA	Occupational Safety and Health Administration		
ENVENTIS	Enventis Telephone	OTTR TL PWR	Otter Tail Power Company		
FALK MNG	Falkirk Mining Company	P L E M	Prairielands Energy Marketing		
FHWA	Federal Highway Administration	POLAR COM	Polar Communications		
G FKS-TRL WD	Grand Forks-trail Water District	PVT ELEC	Private Electric		
GETTY TRD & TRAN	Getty Trading & Transportation	QWEST	Qwest Communications		
GLDN W ELEC	Golden West Electric Cooperative	R&T W SUPPLY	R & T Water Supply Association		
GRGS CO TEL	Griggs County Telephone	RAMSEY R SEW	Ramsey Rural Sewer Association		
		RAMSEY RW	Ramsey Rural Water Association		
		RAMSEY UTIL	Ramsey County Rural Utilities		













NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
04-23-18	General Revisions

This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930 , on 04/23/18 and the original document is stored at the North Dakota Department of Transportation








Line Styles

Existing Topography























	Existing Ground Void
	Existing Cemetary Boundary
	Existing Box Culvert Bridge
	Existing Concrete Surface
	Existing Drainage Structure
	Existing Gravel Surface
	Existing Riprap
	Existing Dirt Surface
	Existing Asphalt Surface
	Existing Tie Point Line
	Existing Railroad Centerline
	Existing Guardrail Cable
	Existing Guardrail Metal
	Existing Edge of Water
	Existing Fence
	Existing Railroad
	Existing Field Line
	Exst Flow
	Existing Curb
	Existing Valley Gutter
	Existing Driveway Gutter
	Existing Curb and Gutter
	Existing Mountable Curb and Gutter

	Existing 3-Cable w Posts
	Site Boundary
	Existing Berm, Dike, Pit, or Earth Dam
	Existing Ditch Block
	Existing Tree Boundary
	Existing Brush or Shrub Boundary
	Existing Retaining Wall
	Existing Planter or Wall
	Existing W-Beam Guardrail with Posts
	Existing Railroad Switch
	Gravel Pit - Borrow Area
	Existing Wet Area-Vegetation Break





Proposed Topography

	3-Cable w Posts
	Flow
	Fence
	Remove Line
	Wall
	Retaining Wall (Plan View)
	W-Beam w Posts










Existing Utilities

	Existing Electrical
	Existing Fiber Optic Line
	Existing TV Fiber Optic
	Existing Gas Pipe
	Existing Overhead Utility Line
	Existing Power
	Existing Fuel Pipeline
	Existing Undefined Above Ground Pipe Line
	Existing Sanitary Sewer
	Existing Sanitary Force Main
	Existing Storm Drain
	Existing Storm Drain Force Main
	Existing Culvert
	Existing Telephone Line
	Existing TV Line
	Existing Water or Steam Line
	Existing Under Drain
	Existing Slotted Drain
	Existing Conduit
	Existing Conductor
	Existing Down Guy Wire Down Guy
	Existing Underground Vault or Lift Station




Proposed Utilities

	24 Inch Pipe
	Reinforced Concrete Pipe
	Under Drain
	Edge Drain

Traffic Utilities

	Conductor
	Fiber Optic
	Existing Loop Detector
	Existing Double Micro Loop Detector
	Micro Loop Detector Double
	Existing Micro Loop Detector
	Micro Loop Detector
	Signal Head with Mast Arm
	Existing Signal Head with Mast Arm

Sign Structures














	Existing Overhead Sign Structure
	Existing Overhead Sign Structure Cantilever
	Overhead Sign Structure Cantilever

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
09-23-16	Added and Revised Items, Organized by Functional Groups










This document was originally issued and sealed by
Roger Weigel,
Registration Number
PE-2930,
on 09/23/16 and the original document is stored at the
North Dakota Department
of Transportation

Line Styles









Right Of Way

	Easement
	Existing Easement
	Right of Way
	Existing Right of Way
	Existing Right of Way Railroad
	Existing Right of Way Not State Owned
	Existing Government Lot Line
	Existing Adjacent Block Lines
	Existing Adjacent Lot Lines
	Existing Adjacent Property Line
	Existing Adjacent Subdivision Lines
	Sight Distance Triangle Line
	Dimension Leader







Boundary Control



	Existing City Corporate Limits or Reservation Boundary
	Existing State or International Line
	Existing Township
	Existing County
	Existing Section Line
	Existing Quarter Section Line
	Existing Sixteenth Section Line
	Existing Centerline
	Tangent Line

Cross Sections and Typicals



	Existing Ground
	Existing Topsoil (Cross Section View)
	Existing Ground Void (Not Surveyed)
	Existing Concrete
	Existing Aggregate (Cross Section View)
	Existing Curb and Gutter (Cross Section View)
	Existing Asphalt (Cross Section View)
	Existing Reinforcement Rebar

Geotechnical



	Geotextile Fabric Type D
	Geogrid
	Geotextile Fabric Type R
	Geotextile Fabric Type R1
	Geotextile Fabric Type RR
	Geotextile Fabric Type S

	Subgrade Reinforcement
	Failure Line







Countours

	Depression Contours
	Supplemental Contour





Profile

	Subgrade, Subcut or Ditch Grade
	Topsoil Profile










Striping

	Centerline Pavement Marking
	Barrier with Centerline Pavement Marking
	Barrier Pavement Marking
	Stripe 4 IN Dotted Extension White
	Stripe 8 IN Dotted Extension White
	Stripe 8 IN Lane Drop








Pavement Joints

	Doweled Joint
	Tie Bar 30 Inch 4 Foot Center to Center
	Tie Bar 18 Inch 3 Foot Center to Center
	Tie Bar at Random Spacing






Bridge Details

	Hidden Object
	Small Hidden Object
	Large Hidden Object
	Phantom Object
	Centerline Main
	Centerline
	Existing Ground (Details)
	Existing Conditions
	Sheet Piling

Erosion Control

	Limits of Const Transition Line
	Bale Check
	Rock Check
	Floating Silt Curtain
	Silt Fence
	Excavation Limits
	Fiber Rolls

Environmental

	Wetland Mitigation
	Existing Wetland Easement USFWS
	Existing Wetland Jurisdictional
	Existing Wetland
	Tree Row

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
09-23-16	Added and Revised Items, Organized by Functional Groups



















































































This document was originally issued and sealed by
Roger Weigel,
Registration Number
PE-2930 ,
on 09/23/16 and the original document is stored at the
North Dakota Department
of Transportation

Symbols

	North Arrow (Half Scale)		Attenuation Device		Existing Railroad Battery Box		Existing Delineator Type E										
	Truck Mounted Attenuator		Diamond Grade Delineator Type A		Existing Bush or Shrub		Existing EFB Misc										
	Type I Barricade		Diamond Grade Delineator Type B		Existing Gas Cap or Stub		Existing Flashing Beacon										
	Type II Barricade		Diamond Grade Delineator Type C		Existing Sanitary Cap or Stub		Existing Pipe Mounted Flasher										
	Type III Barricade		Diamond Grade Delineator Type D		Existing Storm Drain Cap or Stub		Existing Pad Mounted Feed Point										
	Catch Basin		Diamond Grade Delineator Type E		Existing Water Cap or Stub		Existing Pipe Mounted Feed Point with Pad										
	Cairn or Stone Circle		Flexible Delineator		Existing Sanitary Cleanout		Existing Pole Mounted Feed Point										
	Video Detection Camera		Flexible Delineator Type A		Existing Concrete Foundation		Existing Railroad Frog										
	Storm Drain Cap or Stub		Flexible Delineator Type B		Existing Traffic Signal Controller		Existing Snow Gate 18										
	Corrugated Metal End Section 18 Inch		Flexible Delineator Type C		Existing Pad Mounted Signal Controller		Existing Snow Gate 28										
	Corrugated Metal End Section 24 Inch		Flexible Delineator Type D		Existing Sixteenth Section Corner		Existing Snow Gate 40										
	Corrugated Metal End Section 30 Inch		Flexible Delineator Type E		Existing Quarter Section Corner		Existing Headwall										
	Corrugated Metal End Section 36 Inch		Delineator Type A		Existing Section Corner		Existing Pedestrian Head with Number										
	Corrugated Metal End Section 42 Inch		Delineator Type A Reset		Existing Railroad Crossbuck		Existing Signal Head										
	Corrugated Metal End Section 48 Inch		Delineator Type B		Existing Satellite Dish		Existing Sprinkler Head										
	Concrete Foundation		Delineator Type B Reset		Existing Fuel Dispensers		Existing Fire Hydrant										
	Ground Connection Conductor		Delineator Type C		Existing Flexible Delineator Type A		Existing Catch Basin Drop Inlet										
	Neutral Connection Conductor		Delineator Type D		Existing Flexible Delineator Type B		Existing Curb Inlet										
	Phase 1 Connection Conductor		Delineator Type E		Existing Flexible Delineator Type C		Existing Manhole Inlet										
	Phase 2 Connection Conductor		Delineator Drums		Existing Flexible Delineator Type D		Existing Junction Box										
	Traffic Cone		Spot Elevation		Existing Flexible Delineator Type E	<table><tr><th colspan="2">NORTH DAKOTA DEPARTMENT OF TRANSPORTATION</th></tr><tr><th colspan="2">07-01-14</th></tr><tr><th colspan="2">REVISIONS</th></tr><tr><th>DATE</th><th>CHANGE</th></tr><tr><td></td><td></td></tr></table>		NORTH DAKOTA DEPARTMENT OF TRANSPORTATION		07-01-14		REVISIONS		DATE	CHANGE		
NORTH DAKOTA DEPARTMENT OF TRANSPORTATION																	
07-01-14																	
REVISIONS																	
DATE	CHANGE																
	Signal Controller		Existing Access Control Arrow		Existing Delineator Type A												
	Pad Mounted Signal Controller		Existing Artifact		Existing Delineator Type B												
	Alignment Data Point		Existing Flashing Beacon		Existing Delineator Type C												
	Emergency Vehicle Detector		Existing Benchmark		Existing Delineator Type D												

Symbols

D-101-31

	Existing Light Standard		Existing Manhole with Valve Water		Existing Telephone Pole		Existing Undefined Manhole
	Existing High Mast Light Standard 10 Luminaire		Existing Water Manhole		Existing Wood Pole		Existing Undefined Pull Box
	Existing High Mast Light Standard 3 Luminaire		Existing Mile Post Type A		Existing Post		Existing Undefined Pedestal
	Existing High Mast Light Standard 4 Luminaire		Existing Mile Post Type B		Existing Pedestrian Push Button Post		Existing Undefined Valve
	Existing High Mast Light Standard 5 Luminaire		Existing Mile Post Type C		Existing Control Point CP		Existing Undefined Pipe Vent
	Existing High Mast Light Standard 6 Luminaire		Existing Reference Marker		Existing Control Point GPS-RTK		Existing Gas Valve
	Existing High Mast Light Standard 7 Luminaire		Existing RW Marker		Existing Control Point TRI		Existing Water Valve
	Existing High Mast Light Standard 8 Luminaire		Existing Utility Marker		Existing Reference Marker Point NGS		Existing Fuel Pipe Vent
	Existing High Mast Light Standard 9 Luminaire		Iron Monument Found		Existing Pull Box		Existing Gas Pipe Vent
	Existing Overhead Sign Structure Load Center		Iron Pin R/W Monument		Existing Intelligent Transportation Pull Box		Existing Sanitary Pipe Vent
	Existing Luminaire		Existing Object Marker Type I		Existing Water Pump		Existing Storm Drain Pipe Vent
	Existing Light Standard Luminaire		Existing Object Marker Type II		Existing Slotted Reinforced Concrete Pipe		Existing Water Pipe Vent
	Existing Federal Mailbox		Existing Object Marker Type III		Existing RR Profile Spot		Existing Weather Station
	Existing Private Mailbox		Existing Electrical Pedestal		Existing Fuel Leak Sensors		Existing Ground Water Well Bore Hole
	Existing Meander Section Corner		Existing Telephone Pedestal		Existing Highway Sign		Existing Windmill or Tower
	Existing Meter		Existing Fiber Optic Telephone Pedestal		Existing Miscellaneous Spot		Existing Witness Corner
	Existing Electrical Manhole		Existing TV Pedestal		Existing Lighting Standard Pole		Flashing Beacon
	Existing Gas Manhole		Existing Fiber Optic TV Pedestal		Existing Traffic Signal Standard		Flagger
	Existing Sanitary Manhole		Existing Fuel Filler Pipes		Existing Transformer		Pipe Mounted Flasher
	Existing Sanitary Force Main Manhole		Existing Traverse PI Aerial Panel		Existing Large Evergreen Tree		Sanitary Force Main with Valve
	Existing Sanitary Manhole with Valve		Existing Pole		Existing Small Evergreen Tree		
	Existing Storm Drain Manhole		Existing Power Pole		Existing Large Tree		
	Existing Force Main Storm Drain Manhole		Existing Power Pole with Transformer		Existing Small Tree		
	Existing Force Main Storm Drain Manhole with Valve				Existing Tree Trunk		
	Existing Telephone Manhole				Existing Pad Mounted Traffic Signal Control Box		

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 07/01/14 and the original document is stored at the North Dakota Department of Transportation

Symbols



Pad Mounted Feed Point



Pipe Mounted Feed Point with Pad



Pole Mounted Feed Point



Headwall



Double Headwall with Vegetation Barrier



Single Headwall with Vegetation Barrier



Pole Mounted Head



Sprinkler Head



Fire Hydrant



Inlet Type 1



Inlet Type 2



Double Inlet Type 2



Inlet Grate Type 2



Junction Box



High Mast Light Standard 10 Luminaire



High Mast Light Standard 3 Luminaire



High Mast Light Standard 4 Luminaire



High Mast Light Standard 5 Luminaire



High Mast Light Standard 6 Luminaire



High Mast Light Standard 7 Luminaire



High Mast Light Standard 8 Luminaire



High Mast Light Standard 9 Luminaire



Relocate Light Standard



Overhead Sign Structure Load Center



Light Standard 100 Watt High Pressure Sodium Vapor Luminaire



Light Standard 1000 Watt High Pressure Sodium Vapor Luminaire



Light Standard 150 Watt High Pressure Sodium Vapor Luminaire



Light Standard 175 Watt High Pressure Sodium Vapor Luminaire



Light Standard 200 Watt High Pressure Sodium Vapor Luminaire



Light Standard 250 Watt High Pressure Sodium Vapor Luminaire



Light Standard 310 Watt High Pressure Sodium Vapor Luminaire



Light Standard 35 Watt High Pressure Sodium Vapor Luminaire



Light Standard 400 Watt High Pressure Sodium Vapor Luminaire



Light Standard 50 Watt High Pressure Sodium Vapor Luminaire



Light Standard 70 Watt High Pressure Sodium Vapor Luminaire



Light Standard 700 Watt High Pressure Sodium Vapor Luminaire



Manhole



Manhole 48 Inch



Sanitary Force Main Manhole



Sanitary Sewer Manhole



Storm Drain Manhole



Storm Drain Manhole with Inlet



Reset Mile Post



Mile Post Type A



Mile Post Type B



Mile Post Type C



Right of Way Marker



Tubular Marker



Alignment Monument



Iron Pin Reference Monument



Object Marker Type I



Object Marker Type II



Object Marker Type III



Caution Mode Arrow Panel



Back to Back Vertical Panel Sign



Double Direction Arrow Panel



Left Directional Arrow Panel



Right Directional Arrow Panel



Sequencing Arrow Panel



Truck Mounted Arrow Panel



Power Pole



Wood Pole



Pedestrian Push Button Post



Property Corner



Pull Box



Intelligent Transportation Pull Box



Sanitary Pump



Storm Drain Pump



Reinforced Pavement



Reinforced Concrete End Section 15 Inch



Reinforced Concrete End Section 18 Inch



Reinforced Concrete End Section 24 Inch



Reinforced Concrete End Section 30 Inch



Reinforced Concrete End Section 36 Inch



Reinforced Concrete End Section 42 Inch



Reinforced Concrete End Section 48 Inch



Reinforced Concrete End Section 54 Inch



Reset Right of Way Marker



Reset USGS Marker



Right of Way Markers



Riser 30 Inch



Continuous Split Barrel Sample



Flight Auger Sample



Split Barrel Sample



Thinwall Tube Sample



Highway Sign



SNOW GATE 18 FT



SNOW GATE 28 FT



SNOW GATE 40 FT



Standard Penetration Test



Transformer



Inclinometer Tube



Underdrain Cleanout



Excavation Unit




Water Valve

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 07/01/14 and the original document is stored at the North Dakota Department of Transportation


CONSTRUCTION SIGN DETAILS
WARNING SIGNS

D-704-11




W5-8-48

Legend: black (non-refl)
Background: orange




W8-54-48

Legend: black (non-refl)
Background: orange



W20-51-48

Legend: black (non-refl)
Background: orange




W21-51-48

Legend: black (non-refl)
Background: orange


WORD	LETTER SPACING
AHEAD	Standard
200 FT	Standard
350 FT	Standard
500 FT	Standard
1000 FT	Reduce 40%
1500 FT	Reduce 40%
1/2 MILE	Reduce 50%
1 MILE	Standard

* DISTANCE MESSAGES




W5-9-48

Legend: black (non-refl)
Background: orange




W8-55-48

Legend: black (non-refl)
Background: orange




W20-52P-54

Legend: black (non-refl)
Background: orange




W22-8-48

Legend: black (non-refl)
Background: orange




W5-9-48

ARROW DETAILS




W8-53-48

Legend: black (non-refl)
Background: orange



W8-56-48

Legend: black (non-refl)
Background: orange







W21-50-48

Legend: black (non-refl)
Background: orange



NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-13-13	
REVISIONS	
DATE	CHANGE
8-17-17	Updated sign number

This document was originally issued and sealed by
Roger Weigel,
Registration Number
PE- 2930,
on 8/17/17 and the original document is stored at the
North Dakota Department
of Transportation

SHOULDER CLOSURES AND BRIDGE PAINTING LAYOUTS



- Notes
- Variables
 - S = Numerical value of speed limit or 85th percentile.
 - W = The width of the taper in feet.
 - L = Minimum length of taper, $S \times W$ for freeways, expressways, and all other roads with speeds of 45 mph or greater, or $W \times S^2 / 60$ for urban, residential, and other streets with speeds of 40 mph or less.
 - Space delineator drums for tapering traffic at dimension "S". Space delineator drums or tubular markers for tangents at 2 times "S".
 - Sequencing Arrow Panels
 - Use Type A on roadways with slow moving traffic speeds and low volume (25 mph or less and 750 ADT or less).
 - Use Type B on roadways with moderate traffic speeds and volumes (40 mph or less and 5000 ADT or less).
 - Use Type C on roadways with high traffic speeds and volumes (over 40 mph or over 5000 ADT).
 - Re-establish speed limit. Determine exact speed limit in the field, dependent on location and conditions.
 - Determine the reduced speed limit based on the in-place speed limit before construction. Where speed reductions exceed 30 MPH, install a second speed limit sign with the desired speed reduction (not to exceed 30 mph.) Place the second speed limit sign at 1/2 B.
 - Install flags on warning signs in urban areas when signs are not portable. Mount 24 inch square flags perpendicular to the edges of the sign, and at such a distance above the edge that the flag does not touch the sign when limp.
 - Cover existing speed limit signs within a reduced speed zone.
 - As an option, use portable sign supports in lieu of post mounted signs in accordance with NDDOT Standard Specifications.
 - Recommend 40 mph speed limit in vicinity of workers, unless location and conditions dictate otherwise.



KEY

- Sign
- Delineator Drum
- Sequencing Arrow Panel (Caution Mode)
- Work area
- Tubular Marker

ADVANCE WARNING SIGN SPACING				
Road Type	Distance Between Signs Min. (ft)			
	A	B	C	
Urban - Low Speed (30 mph or less)	150	150	150	
Urban - Low Speed (over 30 to 40 mph)	280	280	280	
Urban - High Speed (over 40 mph to 50 mph)	360	360	360	
Rural - High Speed (over 50 mph to 65 mph)	720	720	720	
Urban Expressway and Freeway (55 mph to 60 mph)	850	1350	2200	
Rural Expressway and Freeway (70 mph to 75 mph)	1000	1500	2640	
Interstate/4-Lane Divided (Maintenance and Surveying)	750	1000	1500	


Longitudinal Buffer Space	
Speed (mph)	Length Min (feet)
20	115
25	155
30	200
35	250
40	305
45	360
50	425
55	495
60	570
65	645
70	730
75	820

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-27-13	
REVISIONS	
DATE	CHANGE
8-17-17	Updated notes & revised signs

This document was originally issued and sealed by Roger Weigel Registration Number PE- 2930, on 08/17/17 and the original document is stored at the North Dakota Department of Transportation

PIPE OR W-SHAPE ASSEMBLY DETAILS

D-754-1




NOTES:

MINIMUM VERTICAL CLEARANCE:
Signs installed at the side of the road in rural districts shall be at least 5 feet measured from the bottom of the sign to the edge of driving lane, or Auxiliary Lane. Where parking or pedestrian movements occur, the clearance to the bottom of the sign shall be at least 7 feet.

Signs on freeways, expressways, and multi-lane conventional roadways shall be installed with a minimum height of 7 feet.

Where signs are placed at least 30 feet or more from the edge of the traveled way, the height to the bottom of such sign shall be 5 feet above the edge of driving lane.

Signs may be placed a maximum of 6" above the vertical clearance specified above.




NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
12-1-10	
REVISIONS	
DATE	CHANGE
7-18-14	Modify notes and update reflective sheeting for object marker. Add correct section number for object marker post.


This document was originally issued and sealed by
Roger Weigel,
Registration Number
PE- 2930,
on 7/18/14 and the original document is stored at the
North Dakota Department
of Transportation

Breakaway Coupler System
Structural Details
for W-Shape Supports


- Notes:
- In lieu of the breakaway base system shown on standard D-754-13 the breakaway coupling system may be used. The breakaway coupling system shall be manufactured from material meeting the requirements of ASTM A325 fasteners with the special requirements as specified by DENT BREAKAWAY IND., INC. which meets the requirements of NCHRP Report 350.
 - Structural steel shall conform to Sec. 894.03 B.6. High strength bolts shall conform to ASTM - A325. Refer to "Sign Summary" sheet for specific data on each individual sign installation.
 - Assembly procedure according to the manufacturer's recommendations.



Sign Post and Stub Post
Elevation




Section A - A Section B - B
(See Table for Dimensions)




Section C - C

Max. protection of the stub post is 4" above a 60" chord aligned radially to the center line of the highway and connecting any point, within the length of the chord, on the ground surface on one side of the support to a point in the ground surface on the other side.




Shim Detail

Furnish 2 - .012"± thick and 2 - .032"± thick shims per post. Shims shall be fabricated from brass shim stock or strip conforming to ASTM B36.



Stiffener Plate Detail
(See Table for Dimensions)

Sections shown are for installations on right shoulder and in gore. Plate slot bevels are opposite hand from that shown for installations on left shoulder.




W-Shape - Pile Footing


W-Shape Post & Pile Size	Base Connection Data										Footing Data
	Bolt Size	A	B	C	D	E	t ₁	t ₂	W	F	W-Shape Pile Post "P"
W4X13	3/4" x 5 1/4"	6"	2 1/2"	1 1/2"	3 1/2"	1 1/4"	1"	1/2"	1/4"	13/16"	14'
W5X16											14'
W6X20	7/8" x 5 1/4"	8"	3"	1 3/4"	4"	2"	1 1/4"	1/2"	1/4"	15/16"	14'
W8X24											14'
W8X28	1" x 5 1/4"	8"	3"	2"	4"	2"	1 1/2"	3/4"	5/16"	1 1/16"	14'

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION		This document was originally issued and sealed by Roger Weigel Registration Number PE- 2930 , on 7/8/14 and the original document is stored at the North Dakota Department of Transportation
10-4-2013		
REVISIONS		
DATE	CHANGE	
7-8-14	Revised notes 2 and 3	


Breakaway System Structural Details for W-Shape Supports




Typical Panel Mounting on W-shape Sign Posts



Fuse Joint
(Side View)




Base Connection Detail



Section A-A


Sections shown are for installations on right shoulder. Installations on the left shoulder shall have the plate slot bevels reversed.

Section B-B




Shim Detail


Furnish 2 each .012"± thick and 2 each .032"± thick shims per post. Shims shall be fabricated from brass shim stock or strip conforming to ASTM B36.




Perforated Fuse Plate




Hinge Plate




Keeper Plate



Stiffener Plate




Section E-E




Section F-F

Post clips shall be installed on both sides of each post at each panel joint as indicated.



Flat Washer Detail

W-Shape Post and Pile Size	Base Connection Dimensions										Fuse and Hinge Plate Dimensions									
	Bolt Size and Torque	A	B	C	D	E	t ₁	t ₂	W	R	G	H	J	K	L	M	d ₁	d ₂	t ₃	Bolt dia.
W4x13	$\frac{3}{4}" \text{ } \phi \times 3\frac{1}{2}"$ Torque = 600 in-lb	6"	2½"	1½"	3½"	1¼"	1"	½"	¼"	$\frac{13}{32}"$	2"	1¼"	4"	2¼"	⅞"	1"	$\frac{11}{16}"$	¾"	⅜"	⅝"
W5x16	$\frac{3}{4}" \text{ } \phi \times 3\frac{1}{2}"$ Torque = 600 in-lb	6"	2½"	1½"	3½"	1¼"	1"	½"	¼"	$\frac{13}{32}"$	2½"	1¼"	5"	2¾"	1⅝"	1⅝"	$\frac{13}{16}"$	⅞"	⅜"	¾"
W6x20	$\frac{7}{8}" \text{ } \phi \times 4\frac{1}{4}"$ Torque = 800 in-lb	8"	3"	1¾"	4"	2"	1¼"	½"	¼"	$\frac{15}{32}"$	2½"	1¼"	6"	3½"	1¼"	1⅜"	$\frac{13}{16}"$	1⅝"	⅜"	¾"
W8x24	$\frac{7}{8}" \text{ } \phi \times 4\frac{1}{4}"$ Torque = 800 in-lb	8"	3"	1¾"	4"	2"	1¼"	½"	¼"	$\frac{15}{32}"$	2½"	1½"	6½"	3½"	1½"	1½"	$\frac{15}{16}"$	1¼"	½"	⅞"
W8x28	1" $\phi \times 5"$ Torque = 1000 in-lb	8"	3"	2"	4"	2"	1½"	¾"	$\frac{5}{16}"$	$\frac{17}{32}"$	2½"	1½"	6½"	3½"	1½"	1⅝"	$\frac{11}{16}"$	1⅝"	½"	1"
W8x31	1⅝" $\phi \times 5"$ Torque = 1200 in-lb	9"	3½"	2"	5"	2"	1½"	¾"	$\frac{5}{16}"$	$\frac{19}{32}"$	3"	1¾"	8"	5½"	1¼"	2"	$\frac{11}{16}"$	1½"	½"	1"
W10x39	1⅝" $\phi \times 5"$ Torque = 1200 in-lb	9"	3½"	2"	5"	2"	1½"	¾"	$\frac{5}{16}"$	$\frac{19}{32}"$	3"	1¾"	8"	5½"	1¼"	1⅝"	$\frac{13}{16}"$	1⅝"	½"	1¼"



Section D-D

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
2-28-14	
REVISIONS	
DATE	CHANGE
7-18-14	Revised first note

This document was originally
issued and sealed by
Roger Weigel,
Registration Number
PE- 2930,
on 7/18/14 and the original
document is stored at the
North Dakota Department
of Transportation

Notes:

Structural steel shall conform to Section 894.03 B.6 of the Standard Specifications. High strength bolts shall conform to ASTM A325.

Refer to Sign Summary sheet for specific data on each individual sign installation.


Perforated fuse plate shall be installed on side of post facing traffic.

All posts shall be saw cut. Plates may be sheared or flame cut using a mechanically guided cutting torch in accordance with Section 754.04 D.4.b of the Standard Specifications. Edge preparation shall be in accordance with Section 754.04 D.4.c of the Standard Specifications.

Assembly Procedure:

1. Assemble base plates together with bolts and with one flat washer between top base plate and the keeper plate.
2. Shim as required to plumb post.
3. Tighten all base connection bolts the maximum possible with 12" to 15" wrench to bed washers and shims and to clean bolt threads.
4. Loosen each bolt in turn and retighten in a systematic order to the prescribed torque (see table).
5. Assemble perforated fuse and hinge plates to post with bolts and with one flat washer and lock washer under nut.

WIND BEAMS AND ANCHOR PLATES FOR W-SHAPE SUPPORTS




ASSEMBLY DETAIL FOR WIND BEAMS AND ANCHOR PLATES

Notes:


The B distance is calculated by the following formula, $B=A/4$.

The wind beam shall conform to Section 894.03 B.6 of the Standard Specifications.


The bolts shall conform to requirements of ASTM A307 and galvanized according to ASTM A153.



W4-13 & W5-16




W6-20, W8-24 & W8-28




W8-31 & W10-39


ANCHOR PLATE DETAILS




End View
W4-13 & W5-16




End View
W6-20, W8-24 and W8-28



End View
W8-31



End View
W10-39
WIND BEAM CONNECTION DETAILS









ASSEMBLY DETAIL FOR EXIT NUMBER SIGNS

Note: Two aluminum angles required on each sign. The distance between angles varies depending on post spacing of sign in place. Angles shall be placed as near as possible to posts. The Engineer shall determine the exact location.



NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-3-13	
REVISIONS	
DATE	CHANGE
7-8-14	Revised second note

This document was originally issued and sealed by
Roger Weigel
Registration Number
PE-2930,
on 7/8/14 and the original document is stored at the
North Dakota Department
of Transportation

PULL BOX DETAILS




Cast Iron Frame and Cover





Polymer Concrete Pull Box


Note: Polymer concrete reinforced by a heavy weave fiberglass



- Polymer Concrete Pull Box Notes:
- Place top of pull box flush with surfaced area and approximately one inch above earth or sodded areas on level surfaces.
 - Provide at least one knockout per side in pull box.
 - Provide Polymer Concrete pull box meeting Tier 22 as per ANSI / SCTE 77.



PVC Pull Box



Typical Pull Box in Rural Section

- PVC Pull Box Notes:
- Attach split 24" nominal diameter PVC cover support ring with four 3/8" dia. x 2" long stainless steel hex head bolts with nuts at 90 degrees apart.
 - Two type 2 shoulder eye bolts, 3/8" dia. x 1 1/4" shank length with hex nuts 180 degrees apart (for lifting pull box and supporting electric cable).
 - Four 1/4" x 1 1/4" long galvanized lag screws. Screw assembly together.
 - Attach split 24" nominal diameter PVC cover support extension ring with four 3/8" dia. x 2" long stainless steel hex head bolts with nuts at 90 degrees apart.
 - Bolt assembly together.
 - Size conduit holes in barrel section a maximum of 1" larger than size of conduit being used.
 - After pull box and conduit installation, make inside walls and cover water tight to the satisfaction of the Engineer.
 - PVC pipe to meet requirements of ASTM F679T-1 or equal.
 - Use austenitic stainless steel hex head bolts and nuts. Galvanize other fasteners as per AASHTO M-232.
 - Coat concrete cover on top and sides with an approved epoxy coating. Apply light gray, clear, or neutral color epoxy protective coating as recommended by the manufacturer. Clean the surfaces of concrete receiving the epoxy protective coating by wire brush and dry before application.
 - Cast Iron Cover castings shall be gray iron as per AASHTO M 105, Class 35B.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION		This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 10-17-2017 and the original document is stored at the North Dakota Department of Transportation
10-8-13		
REVISIONS		
DATE	CHANGE	
7-8-14 10-17-17	Added Note 3 Updated to active voice.	