STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	SS-8-018(088)064	6	1

NOTES

105-200 UTILITY COORDINATION: A utility coordination meeting is required.

105-P01 UTILITIES: Coordinate work activities with utility companies to address utility conflicts as needed for the proposed cut. Adjust operations adjacent to the water main valve to protect it until its relocation.

Utility Company Name & Address	Contact Name	Phone Number	Email
Cass Rural Water District 131 Maple St. Kindred, ND 58051	Brent Brinkman	(701) 428-3139	brent.brinkman@cassruralwaterdistrict.com
Cass County Electric Coop.Inc. 3312 42nd St. S., Suite 200, Fargo, ND 58104	Chuck Ames	(701) 356-4479	cames@kwh.com
Midco 50 22nd St E, West Fargo, ND 58078	Tony Geffre	(701) 552-2585	Tony.geffre@midco.com
CenturyLink 302 29th St N, Fargo ND 58502	Charles Grummons	(701) 580-8460	Charles.Grummons@centurylink.com

105-P02 CONTROL OF WORK: The adjacent landowner is responsible for fence removal prior to beginning excavation and for fence placement after completion of the project. Notify landowner in writing with a copy to the Engineer, a minimum of 30 days in advance of starting earthwork operations.

203-P01 COMMON EXCAVATION-WASTE: Include removal of any existing riprap encountered within the work area in the unit price bid for “Common Excavation-Waste”.

256-P01 RIPRAP GRADE II: Make the top surface of the riprap flush with the ground adjacent to it.

704-P01 TRAFFIC CONTROL: Place Road Work Ahead sign 750’ before the project beginning. Place End Road Work sign 750’ after the project end.

REGISTERED PROFESSIONAL ENGINEER
Aaron Derman
Derman, Aaron J.
PE-27165
05/30/18
NORTH DAKOTA