

NORTH DAKOTA
DEPARTMENT OF TRANSPORTATION
REQUEST FOR PROPOSAL
STATE FEDERAL AID PROJECT NO. HEU-6-081(094)940 (PCN-21884)

1.712 Miles

TRAFFIC SIGNALS AND TURN LANES

BUS 81 (32ND AVE S), GRAND FORKS - I-29 E TO 20TH STREET S

GRAND FORKS COUNTY

DBE Race Neutral Goal - 0%

BID OPENING: The bidder's proposal will be accepted via the Bid Express on-line bidding exchange at www.bidx.com until **09:30AM Central Time on November 13, 2020.**

Prior to submitting a Proposal, the Bidder shall complete all applicable sections and properly execute the Proposal Form in accordance with the specifications.

Proposal Form of:

(Firm Name)

(Address, City, State, Zipcode)

(For official use only)

PAGE INTENTIONALLY LEFT BLANK

Project: HEU-6-081(094)940 (PCN-21884)

The company, firm, corporation, or individual hereby acknowledges that it has designated a responsible person or persons as having the authority to obligate the company, firm, or individual, through electronic or paper submittal, to the terms and conditions described herein and in the contract documents. The designated responsible person submitting this proposal shall be hereafter known as the bidder. By submitting this proposal, the bidder fully accepts and agrees to all the provisions of the proposal. The bidder also certifies that the information given in this proposal is true and the certifications made in this proposal are correct.

The bidder acknowledges that they have thoroughly examined the plans, proposal form, specifications, supplemental specifications, special provisions and agrees that they constitute essential parts of this proposal.

The bidder acknowledges that all line items which contain a quantity shall have a unit price bid. Any line item which is bid lump sum shall contain a lump sum bid price.

The bidder acknowledges that they understand that the quantities of work required by the plans and specifications are approximate only and are subject to increases and decreases; the bidder understands that all quantities of work actually required must be performed and that payment therefore shall be at the prices stipulated herein; that the bidder proposes to timely furnish the specified materials in the quantities required and to furnish the machinery, equipment, labor and expertise necessary to competently complete the proposed work in the time specified.

NON-COLLUSION AND DEBARMENT CERTIFICATION

The bidder certifies that neither he/she, nor any official, agent or employee of the bidder has entered into any agreement, participated in any collusion, or otherwise taken any action which is in restraint of free competitive bidding in connection with this bid.

By submitting this proposal, the bidder certifies to the best of his/her knowledge and belief that he/she and his/her principles:

- a. Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from covered transactions by any Federal Department or agency;
- b. Have not within a three-year period preceding this proposal been convicted of or had a civil judgment rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or perform a public (Federal, State or Local) transaction or contract under a public transaction; violation of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records; making false statements; or receiving stolen property

Project: HEU-6-081(094)940 (PCN-21884)

-
- c. Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State or Local) with commission of any of the offenses enumerated in paragraph b. of the certification; and
 - d. Have not within a three-year period preceding this proposal had one or more public transactions (Federal, State or Local) terminated for cause or default

Where the prospective bidder is unable to certify to any of the statements in this certification, the bidder shall submit an explanation in the blanks provided herein. The explanation will not necessarily result in denial of participation in a contract:

Explanation: _____

If the prequalified bidder's status changes, he/she shall immediately submit a new fully executed non-collusion affidavit and debarment certification with an explanation of the change to the Contract Office prior to submitting the bid.

Failure to furnish a certification or an explanation will be grounds for rejection of a bid.

BID LIMITATION (Optional)

The bidder who desires to bid on more than one project on which bids are to be opened on the same date, and who also desires to avoid receiving an award of more projects than the bidder is equipped to handle, may bid on multiple projects and limit the total amount of work awarded to the bidder on selected projects by completing the "Bid Limitation".

The Bid Limitation must be filled in on each proposal form for which the Bidder desires protection. Each such proposal must be covered by a proposal guaranty.

The bid limitation can be made by declaring the total dollar value of work OR total number of projects a bidder is willing to perform.

The Bidder desires to disqualify all of his/her bids on this bid opening that exceed a total dollar value of \$ _____

OR

that exceed a total number of _____ projects.

The Bidder hereby authorizes the Department to determine which bids shall be disqualified.

Project: HEU-6-081(094)940 (PCN-21884)

PERMISSIBLE DISCOUNT (optional)

Only when invited to do so in the Request for Proposal by Special Provision, Bidders are permitted to offer a discount on a specific project (discount project) if they are awarded the contract on one or more additional projects bid at the same bid opening time and date. The bidder must present the proposal so that it can be considered with or without the discount. The bid or discount offered on the "discount project" will not affect the determination of the low bid of any other project.

When discounts are offered, they must be presented as a reduction in the unit price for one or more items of work in the specified proposal (discount project).

Space for Offering Discounts:

Item No: _____

Description: _____

Unit: _____

Proposal Quantity: _____ Unit Price Reduction: \$ _____ Discount: \$ _____

Item No: _____

Description: _____

Unit: _____

Proposal Quantity: _____ Unit Price Reduction: \$ _____ Discount: \$ _____

Item No: _____

Description: _____

Unit: _____

Proposal Quantity: _____ Unit Price Reduction: \$ _____ Discount: \$ _____

TOTAL DISCOUNT _____

It is understood that the discount will only apply if awarded under the conditions as listed above and signed by the bidder.

Project: HEU-6-081(094)940 (PCN-21884)

RECEIPT OF ADDENDA ACKNOWLEDGEMENT

We hereby acknowledge receipt of the following addenda:

Addendum # _____ Dated _____

Addendum # _____ Dated _____

Addendum # _____ Dated _____

Addendum # _____ Dated _____

Addendum # _____ Dated _____

Addendum # _____ Dated _____

PROPOSAL GUARANTY

A proposal guaranty is required. The proposal guaranty must comply with Section 102.09, "Proposal Guarantee" of the Standard Specifications.

TYPE OF PROPOSAL GUARANTY APPLIED TO THIS PROJECT (Check one):

_____ Annual Bid Bond*

_____ Single Project Bid Bond

_____ Certified or Cashier's Check

*Annual Bid Bond is required when submitting proposals electronically

BID ITEMS

Project: HEU-6-081(094)940 (PCN-21884)

Bidder must type or neatly print unit prices in numerals, make extensions for each item, and total. Do not carry unit prices further than three (3) decimal places.

Item No.	Spec No.	Code No.	Description	Unit	Approx. Quantity	Unit Price		Amount	
						\$\$\$\$	000	\$\$\$\$	00
001	103	0100	CONTRACT BOND	L SUM	1.				
002	201	0370	REMOVAL OF TREES 10IN	EA	2.				
003	201	0395	STUMP REMOVAL	EA	1.				
004	202	0114	REMOVAL OF CONCRETE PAVEMENT	SY	3,449.				
005	202	0130	REMOVAL OF CURB & GUTTER	LF	8,289.				
006	202	0230	REMOVAL OF INLETS	EA	2.				
007	203	0103	COMMON EXCAVATION-TYPE C	CY	4,921.				
008	203	0109	TOPSOIL	CY	1,202.				
009	261	0112	FIBER ROLLS 12IN	LF	623.				
010	261	0113	REMOVE FIBER ROLLS 12IN	LF	623.				
011	261	0200	WEIGHTED FIBER ROLLS	LF	95.				
012	261	0201	REMOVE WEIGHTED FIBER ROLLS	LF	95.				
013	302	0100	SALVAGED BASE COURSE	TON	8,212.				
014	550	0300	8IN NON-REINF CONCRETE PVMT CL AE-DOWELED	SY	1,845.				
015	550	0305	9IN NON-REINF CONCRETE PVMT CL AE-DOWELED	SY	2,238.				
016	550	0310	10IN NON REINF CONCRETE PVMT CL AE-DOWELED	SY	3,871.				

BID ITEMS

Project: HEU-6-081(094)940 (PCN-21884)

Bidder must type or neatly print unit prices in numerals, make extensions for each item, and total. Do not carry unit prices further than three (3) decimal places.

Item No.	Spec No.	Code No.	Description	Unit	Approx. Quantity	Unit Price		Amount	
						\$\$\$\$	000	\$\$\$\$	00
017	702	0100	MOBILIZATION	L SUM	1.				
018	704	0100	FLAGGING	MHR	850.				
019	704	1000	TRAFFIC CONTROL SIGNS	UNIT	4,597.				
020	704	1035	ATTENUATION DEVICE-TYPE B-25	EA	1.				
021	704	1052	TYPE III BARRICADE	EA	78.				
022	704	1054	SIDEWALK BARRICADE	EA	17.				
023	704	1056	PEDESTRIAN CHANNELIZATION	LF	360.				
024	704	1060	DELINEATOR DRUMS	EA	349.				
025	704	1067	TUBULAR MARKERS	EA	97.				
026	704	1087	SEQUENCING ARROW PANEL-TYPE C	EA	8.				
027	704	1500	OBLITERATION OF PAVEMENT MARKING	SF	5,319.				
028	704	2108	TEMPORARY CURB RAMP	EA	2.				
029	704	3501	PORTABLE PRECAST CONCRETE MED BARRIER	LF	210.				
030	704	4011	PORTABLE CHANGEABLE MESSAGE SIGN	EA	3.				
031	706	0400	FIELD OFFICE	EA	1.				
032	708	1540	INLET PROTECTION-SPECIAL	EA	18.				

BID ITEMS

Project: HEU-6-081(094)940 (PCN-21884)

Bidder must type or neatly print unit prices in numerals, make extensions for each item, and total. Do not carry unit prices further than three (3) decimal places.

Item No.	Spec No.	Code No.	Description	Unit	Approx. Quantity	Unit Price		Amount	
						\$\$\$\$	000	\$\$\$\$	00
033	708	1541	REMOVE INLET PROTECTION-SPECIAL	EA	18.				
034	709	0100	GEOSYNTHETIC MATERIAL TYPE G	SY	9,192.				
035	714	9006	ADJUST 6IN SEWER CLEANOUT	EA	1.				
036	714	9720	UNDERDRAIN PIPE PVC PERFORATED 4IN	LF	20.				
037	722	3450	MANHOLE RELOCATE	EA	1.				
038	722	3510	INLET-TYPE 2	EA	2.				
039	722	6140	ADJUST GATE VALVE BOX	EA	3.				
040	722	6160	ADJUST INLET	EA	1.				
041	722	6200	ADJUST MANHOLE	EA	7.				
042	722	6240	ADJUST UTILITY APPURTENANCE	EA	1.				
043	724	0427	ADJUST HYDRANT	EA	1.				
044	748	0140	CURB & GUTTER-TYPE I	LF	7,446.				
045	748	0520	CURB-TYPE I	LF	67.				
046	750	0020	PIGMENTED CONCRETE	SY	1,029.				
047	750	0115	SIDEWALK CONCRETE 4IN	SY	777.				
048	750	0140	SIDEWALK CONCRETE 6IN	SY	400.				

BID ITEMS

Project: HEU-6-081(094)940 (PCN-21884)

Bidder must type or neatly print unit prices in numerals, make extensions for each item, and total. Do not carry unit prices further than three (3) decimal places.

Item No.	Spec No.	Code No.	Description	Unit	Approx. Quantity	Unit Price		Amount	
						\$\$\$\$	000	\$\$\$\$	00
049	750	0210	CONCRETE MEDIAN NOSE PAVING	SY	44.				
050	750	2115	DETECTABLE WARNING PANELS	SF	487.				
051	754	0110	FLAT SHEET FOR SIGNS-TYPE XI REFL SHEETING	SF	619.500				
052	754	0112	FLAT SHEET FOR SIGNS-TYPE IV REFL SHEETING	SF	371.				
053	754	0206	STEEL GALV POSTS-TELESCOPING PERFORATED TUBE	LF	149.800				
054	754	0592	RESET SIGN PANEL	EA	8.				
055	762	0112	EPOXY PVMT MK MESSAGE	SF	496.				
056	762	0115	EPOXY PVMT MK 8IN LINE	LF	4,981.				
057	762	0117	EPOXY PVMT MK 24IN LINE	LF	1,022.				
058	762	1305	PREFORMED PATTERNED PVMT MK 4IN LINE-GROOVED	LF	20.				
059	762	1307	PREFORMED PATTERNED PVMT MK 6IN LINE-GROOVED	LF	200.				
060	762	1309	PREFORMED PATTERNED PVMT MK 8IN LINE-GROOVED	LF	6,444.				
061	770	4540	RELOCATE LIGHT STANDARD	EA	1.				
062	772	2906	REVISE TRAFFIC SIGNAL SYSTEM-SITE 1	EA	1.				
063	772	2907	REVISE TRAFFIC SIGNAL SYSTEM-SITE 2	EA	1.				
064	772	2913	REVISE TRAFFIC SIGNAL SYSTEM-SITE 7	EA	1.				

BID ITEMS

Project: HEU-6-081(094)940 (PCN-21884)									
<p>Bidder must type or neatly print unit prices in numerals, make extensions for each item, and total. Do not carry unit prices further than three (3) decimal places.</p>									
Item No.	Spec No.	Code No.	Description	Unit	Approx. Quantity	Unit Price		Amount	
						\$\$\$\$\$	000	\$\$\$\$\$	00
065	772	9200	IT SYSTEM	EA	1.				
066	772	9813	TRAFFIC SIGNAL SYSTEM - SITE 3	EA	1.				
067	772	9814	TRAFFIC SIGNAL SYSTEM - SITE 4	EA	1.				
068	772	9815	TRAFFIC SIGNAL SYSTEM - SITE 5	EA	1.				
069	772	9816	TRAFFIC SIGNAL SYSTEM - SITE 6	EA	1.				
070	772	9818	TRAFFIC SIGNAL SYSTEM - SITE 8	EA	1.				
071	970	0008	LANDSCAPE PREPARATION	SY	3,363.				
072	970	1000	TREES	EA	2.				
			TOTAL SUM BID						

Project: HEU-6-081(094)940 (PCN-21884)

Type of Work: TRAFFIC SIGNALS AND TURN LANES

County: GRAND FORKS

Length: 1.7120 Miles

TIME FOR COMPLETION:

The undersigned Bidder agrees, if awarded the contract, to prosecute the work with sufficient forces and equipment to complete the contract work within the allowable time specified as follows:

WORKING DAY CONTRACT: NA working days are provided. The Department will begin charging working days beginning NA or the date work begins on the project site, whichever is earlier.

CALENDAR DAY CONTRACT: NA calendar days are provided. The completion date will be determined by adding NA calendar days to NA or the date work begins on the project site, whichever is earlier.

COMPLETION DATE CONTRACT The project completion date is 10/15/2021. The Department provides a minimum of NA working days. The Department will begin charging working days beginning NA or the date work begins on the project site, whichever is earlier.

PROPOSAL FORM

North Dakota Department of Transportation

BID OPENING: November 13, 2020**Job 006**

Page 11 of 11

Project: HEU-6-081(094)940 (PCN-21884)**Type of Work:** TRAFFIC SIGNALS AND TURN LANES**County:** GRAND FORKS**Length:** 1.7120 Miles**CONTRACT EXECUTION:**

The undersigned Bidder agrees, if awarded the contract, to execute the contract form and furnish a contract bond within fifteen calendar days, as determined by NDCC Section 1-02-15, after date of notice of award, in accordance with the provisions of Sections 103.05 and 103.06 of the Standard Specifications.

AFFIDAVIT:

STATE OF _____)
) **ss.**
COUNTY OF _____)

The undersigned bidder, being duly sworn, does depose and say that they are an authorized representative of _____

CONTRACTOR NAME

of _____, a

MAILING ADDRESS

☐ Individual ☐ Partnership ☐ Joint Venture ☐ Corporation

and that they have read, understand, acknowledge, and accept the entire proposal form; and that all statements made by said bidder are true and correct.

BIDDER MUST SIGN ON THIS LINE

_____, TITLE _____

TYPE OR PRINT SIGNATURE ON THIS LINE

Subscribed and sworn to before me this day.

COUNTY

(Seal)

STATE_____
DATE_____
NOTARY PUBLIC

My commission expires _____

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION

Job # 06, HEU-6-081(094)940

Traffic Signals and Turn Lanes

INDEX OF PROVISIONS

Road Restriction Permits

Hot Line Notice

Price Schedule for Miscellaneous Items dated October 1, 2014 (PS-1)

SP DBE Program - Race Neutral dated February 1, 2018

E.E.O. Affirmative Action Requirements dated March 15, 2014

Appendix A of the Title VI Assurances dated September 8, 2020

Appendix E of the Title VI Assurances dated September 8, 2020

SP Cargo Preference Act

Required Contract Provisions Federal Aid Construction Contracts
(Form FHWA 1273 Rev. May 1, 2012)

SP Certified Payrolls, dated 9-6-17

SP DBE Project Payment Reporting, dated 10-3-17

NOTICE - Electrician

Labor Rates from U.S. Department of Labor dated August 28, 2020 (Mod. No. 5)

On-The-Job Training Program dated October 1, 2016

SSP 1 Temporary Erosion & Sediment Best Management Practices

SSP 5 Limitations of Operations

SSP 8 Federal Prohibition on Certain Technological Hardware

SP 90(20) Utility Coordination

INDEX OF PROVISIONS

Page 2 of 2

SP 91(20) Drilled Shaft Foundations for Highway Signals and Highway Lighting

SP 92(20) Video Detection System

SP 93(20) Interconnect Cable

SP Fuel Cost Adjustment Clause dated September 8, 2006

NOTICE

TO: All prospective bidders on all North Dakota Department of Transportation Highway Construction Projects.

Contractors moving construction equipment to NDDOT highway construction projects are subject to the Road Restriction Policy with the following modifications:

- A. The contractor may purchase up to 10 single trip permits for each NDDOT highway construction project at a cost ranging from \$20 to \$70 each. These permits must be purchased from the Motor Carrier Division of the Highway Patrol at the central office of the NDDOT in Bismarck, North Dakota.
- B. The \$1 per mile fee will not be charged for Gross Vehicle Weights (GVW) exceeding 105,500 pounds, 105,500 pounds, and 105,000 pounds for highways Restricted by Legal Weights, 8 Ton, and 7 Ton highways respectively.
- C. The \$5 per ton per mile fee will be charged only for loads exceeding a GVW of 130,000 pounds, 120,000 pounds, 110,000 pounds and 80,000 pounds for highways Restricted by Legal Weights, 8 Ton, 7 Ton, and 6 Ton highways respectively.
- D. The maximum weights per axle for each of the class restrictions still apply. If it is shown that more axles cannot be added, movement may be authorized; however, a \$1 per ton per mile fee will be charged for all weight in excess of the restricted axle limits.
- E. These construction equipment single trip permits apply to State and US Highways only.
- F. The District Engineers and Highway Patrol will select the route of travel.
- G. Contractors moving equipment to other than NDDOT highway construction projects are subject to all fees as shown in the Road Restriction Permit Policy.
- H. Contractors must call the Highway Patrol prior to movement of all overweight loads on all State and US Highways.

NDDOT ROAD AND VEHICLE RESTRICTIONS

Date Revised 05-22-10

ROAD RESTRICTION PERMITS

Permits shall be issued for the movement of non-divisible vehicles and loads on state highways which exceed the weight limits during spring road restrictions. The issuance of permits may be stopped or posted weights changed at any time based on the varying conditions of the roadways. Permits can be obtained from the Highway Patrol.

RESTRUCTION CLASSIFICATIONS WITH ALLOWABLE AXLE WEIGHTS AND GROSS VEHICLE WEIGHTS	PERMIT AND TON/MILE FEES
<p>Highways Restricted by Legal Weight</p> <p>Single Axle -- 20,000 lbs. Tandem Axle -- 34,000 lbs. Triple Axle -- 48,000 lbs. 4 Axles or more -- 15,000 lbs. per axle</p> <p>Gross Vehicle Weight -- 105,500 lbs.</p> <p>Note: The above weights apply to state highways restricted by legal weights, other than interstate highways, in areas where road restrictions are in force. When the gross weight of an axle grouping exceeds 48,000 pounds, the \$1 per ton per mile shall apply to all weight in excess of 15,000 pounds per axle.</p>	<p>Permit Fee: \$20-\$70 per trip</p> <p>Ton Mile Fee:</p> <p>105,501 lbs. to 130,000 lbs. GVW -- \$1 per mile</p> <p>Over 130,000 lbs. GVW -- \$1 per mile plus \$5 per ton per mile for that weight exceeding 130,000 lbs. GVW</p> <p>Exceeding axle limits -- \$1 per ton per mile</p>
<p>8-Ton:</p> <p>Single Axle -- 16,000 lbs. Tandem Axle -- 32,000 lbs. 3 Axles or more -- 14,000 lbs. per axle</p> <p>Gross Vehicle Weight -- 105,500 lbs.</p>	<p>Permit Fee: \$20-\$70 per trip</p> <p>Ton Mile Fee:</p> <p>105,501 lbs. to 120,000 lbs. GVW -- \$1 per mile</p> <p>Over 120,000 lbs. GVW -- \$1 per mile plus \$5 per ton per mile for that weight exceeding 120,000 lbs. GVW</p> <p>Exceeding restricted axle limits -- \$1 per ton per mile</p>
<p>7-Ton:</p> <p>Single Axle -- 14,000 lbs. Tandem Axle -- 28,000 lbs. 3 Axles or more -- 12,000 lbs. per axle</p> <p>Gross Vehicle Weight -- 105,500 lbs.</p>	<p>Permit Fee: \$20-\$70 per trip</p> <p>Ton Mile Fee:</p> <p>105,500 lbs. to 110,000 lbs. GVW -- \$1 per mile</p> <p>Over 110,000 lbs. GVW -- \$1 per mile plus \$5 per ton per mile for that weight exceeding 110,000 lbs. GVW</p> <p>Exceeding restricted axle limits -- \$1 per ton per mile</p>
<p>6-Ton:</p> <p>Single Axle -- 12,000 lbs. Tandem Axle -- 24,000 lbs. 3 Axles or more -- 10,000 lbs. per axle</p> <p>Gross Vehicle Weight -- 80,000 lbs.</p>	<p>Permit Fee: \$20-\$70 per trip</p> <p>Ton Mile Fee:</p> <p>\$5 per ton per mile for all weight exceeding 80,000 lbs. GVW</p> <p>Exceeding restricted axle limits -- \$1 per ton per mile</p>
<p>5-Ton:</p> <p>Single Axle -- 10,000 lbs. Tandem Axle -- 20,000 lbs. 3 Axles or more -- 10,000 lbs. per axle</p> <p>Gross Vehicle Weight -- 80,000 lbs.</p>	<p>No overweight movement allowed</p>

SINGLE UNIT FIXED LOAD VEHICLES SUCH AS TRUCK CRANES AND WORKOVER RIGS

A. Permit Fee and Ton Mile Fee for Self-Propelled Fixed Load Vehicles .

1. Permit Fee: \$25 per trip
2. \$1 per ton per mile for all weight in excess of restricted axle limits or in excess of legal limits on state highways in areas where road restrictions are in force. When the gross weight of an axle grouping exceeds 48,000 pounds, the \$1 per ton per mile shall apply to all weight in excess of 15,000 pounds per axle (see weight classification chart in section C.)
3. **\$5 per ton per mile** for all movements exceeding the following gross vehicle weight limits:
 - a. 105,500 lbs. GVW on unrestricted state highways, other than interstate highways, in areas where road restrictions are in force.
 - b. 105,500 lbs. GVW on 8-ton highways.
 - c. 105,500 lbs. GVW on 7-ton highways.
 - d. 80,000 lbs. GVW on 6-ton highways.
 - e. No overweight movement allowed on 5-ton highways

B. Permit Fees for Work-Over Rigs and Special Mobile Equipment Exceeding 650 but not 670 Pounds Per Inch Width of Tire.

1. Permit Fee:
 - a. \$50 per trip on work-over rigs up to 650 pounds per inch width.
 - b. \$75 per trip on work -over rigs that exceed 650 but not 670 pounds per inch width of tire.
2. The work-over rig shall be stripped to the most minimum weights.
3. A minimal number of state highway miles shall be used.
4. District engineer approval shall be obtained prior to movement when vehicle exceeds restricted axle weights by more than 5,000 pounds.
5. A validation number ending in TM must be obtained from the Highway Patrol prior to using a self-issue single trip movement approval form.
6. The ton mile shall be waived .

NOTICE

U.S. DEPARTMENT OF TRANSPORTATION

"HOT LINE"

As part of its continuing investigation into Highway Construction Contract Bid Rigging and abuses in the Disadvantaged Business Enterprise Program, the Inspector General for the Department of Transportation (DOT) has established a "HOT LINE" to receive information from contractors, suppliers, or anyone with knowledge of such activities.

The toll-free "HOT LINE" telephone number is 1-800-424-9071 and will be manned during normal working hours (8 a.m. to 5 p.m. EST). This operation is under the direction of DOT's Inspector General. All information will be treated confidentially and anonymity will be respected.

CALL

Inspector General's 'HOT LINE'
Toll Free 1-800-424-9071
Washington, DC Area:
202-366-1461
Fax: 202-366-7749

WRITE

Inspector General
Post Office Box 23178
Washington, DC 20026-0178

Email: hotline@oig.dot.gov

The field office address and telephone number for NORTH DAKOTA is:

CHICAGO REGIONAL OFFICE

Special Agent-in-Charge
Commercial: 312-353-0106
111 N. Canal St., Suite 677
Chicago, Illinois 60606

10/1/2014

**NORTH DAKOTA DEPARTMENT OF TRANSPORTATION
PRICE SCHEDULE FOR MISCELLANEOUS ITEMS (PS-1)**

The Contractor agrees to accept the following unit prices for each listed item of work and or material when no project contract unit price exists for that item. Each price listed will be full compensation for the cost of labor, material and equipment necessary to provide the item of work and/or material, complete in place, including (but not limited to) royalty, disposal of unsuitable material, equipment rental, sales tax, use tax, overhead, profit, and incidentals.

Each listed item is referenced to the Standard Specifications by Section number and Section name.

SECTION NO.	SECTION NAME	ITEM NAME	PRICE PER ITEM
107.08	Haul Roads	Water	\$27 per M Gal
107.08	Haul Roads	Bitumen for Mix	Invoice Price ¹ + 10%
107.08	Haul Roads	Bituminous Mix	\$42 per Ton ²
107.08	Haul Roads	Aggregate Base	\$17 per Ton ²
203.01 B	Rock Excavation	Rock Excavation	\$11 per CY
203.01 C	Shale Excavation	Shale Excavation	Common Excavation Price + \$1.00 per CY
203.01 D	Muck Excavation	Muck Excavation	\$9 per CY
203.05 H.3	Embankment	Overhaul	\$1.40 per CY - Mile
260	Silt Fence	Mucking Silt Fence	\$3.90 per LF
260	Silt Fence	Removal of Silt Fence ³	\$4.25 per LF
261	Fiber Rolls	Mucking of Fiber Rolls	\$3.90 per LF
261	Fiber Rolls	Removal of Fiber Rolls ³	\$4.25 per LF
420.04 E	Bituminous Seal Coat	Blotter Sand	\$27 per Ton ²
430.04 G	Hot Mix Asphalt (Exc. Material Hauled to Disposal Area)	Bituminous Mixture	Machine Placed: Bid or Invoice Price + \$31 per ton Hand Placed: Bid or Invoice Price + \$48 per Ton
704	Temporary Traffic Control	Flagging	\$32 per MHR

¹Price paid for bituminous material will be invoice price plus freight costs.

²Price Includes haul up to 10 miles. Payment for haul exceeding 10 miles will be according to Section 109.03 E, "Force Account." The haul distance for aggregate base and bituminous mix will be based on the average haul. The haul distance for blotter sand will be from the point where the haul begins to the point where it enters the project.

³This is only for pre-existing items that were not installed under the Contract.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION SPECIAL PROVISION: DISADVANTAGED BUSINESS ENTERPRISE (DBE) PROGRAM

PROJECT HEU-6-081(094)940 (PCN-21884)

RACE/GENDER NEUTRAL GOAL: 0%

NDDOT Contact Information	
Contractor Sign In & Submit Advertisements https://apps.nd.gov/dot/cr/csi/login.htm	Amy Conklin, DBE Program Administrator 701-328-3116 - or - aconklin@nd.gov
Submit quotes and post-bid documentation to: subquotes@nd.gov or Fax: 701-328-0343	Ramona Bernard, Civil Rights Division Director 701-328-2576 - or - rbernard@nd.gov
DBE Directory https://dotnd.diversitycompliance.com/	All times are stated in Central Time. The day of the bid opening is not counted as one of the business days.

PURPOSE

These provisions:

1. Provide an explanation of the federal law and outline the obligations to comply with the Federal DBE requirements applicable to this contract,
2. Explain the process NDDOT will follow to evaluate bidders' efforts to obtain DBE participation
3. Provide the standards NDDOT will use to measure compliance with the requirements
4. Identify sanctions for failing to comply with DBE program requirements.

QUOTES:

All bidders and all subcontractors over \$500,000 (regardless of whether they are apparent low bidder or their quote was used on a project in this bid opening) should submit a completed [SFN 52013-List of Businesses Submitting Quotes](#) by 4:00 pm CST, within 5 business days after the bid opening. **(Copies of quotes are no longer accepted).** This process is necessary in identifying "ready, willing, and able" contractors upon which to base the NDDOT Triennial DBE Goal. The number of contractors and the types of work they have bid/quoted will be used in the calculation of the DBE goal for each goal setting period.

All subcontractors, suppliers, manufacturers, regular dealers, vendors, and brokers should fax or email quotes to the Department no later than 9 PM the day before each bid opening.

All DBEs quoting on this project should submit all quotes and a list of contractors they quoted to NDDOT no later than 9 PM the day before each bid opening.

Prime contractors preparing to bid on NDDOT highway projects have requested that quotes be sent to them the day before the bid opening by:

- 2 PM Central - Suppliers (brokers/regular dealers), vendors, & manufacturers
- 5 PM Central - Subcontractors under \$500,000
- 8 PM Central - Subcontractors over \$500,000

REQUIREMENTS FOR ALL BIDDERS:

- ALL BIDDERS are strongly encouraged to submit all documentation at the time of bid opening.
- Must submit Form A with bid package at the time of bid opening.
- Must submit [Form C \(Notification of Intent to use\)](#) for DBE (if used) by 4:00 pm CST, within 2 business days after the bid opening. If no DBE's are used, Form C is not required.
- Completed [Form B](#), or a spreadsheet containing all the information on Form B, should be submitted by 4:00 pm, CST within 5 business days after the bid opening.
- Prime contractors are strongly encouraged to submit their bid documentation in one electronic file. Forms incorrectly submitted could result in a technicality, forcing the Department to award to the next responsive bidder.

To maximize subcontracting opportunities the following actions are encouraged.

ADVERTISE

All DBE and Non-DBE prime contractors and all subcontractors (over/under \$500,000), vendors, regular dealers/suppliers, and manufacturers, are encouraged to advertise using one of the two options:

OPTION 1: Place an advertisement soliciting DBE participation using the electronic [DBE Advertisement System](#).

- Submit the required information online at <https://apps.nd.gov/dot/cr/csi/login.htm> no later than noon, 15 calendar days before the bid opening.

OPTION 2: Directly contact by email or fax, all DBEs certified in the specific work type (NAICS) required for the job.

- Make contact with DBEs no later than 5 PM 7 calendar days before the bid opening.
- Use the DBE Directory to determine the DBE firms certified in the work to be subcontracted.

Either method of advertisement should:

- Provide the name, email address, telephone, and fax number of the company contact who will be available to discuss and/or receive quotes.
- Offer assistance to DBEs in interpreting plans; quantities; expected overtime; project scheduling; pit and batch plan locations, length of haul, type of road; method of measurement (seeding by the mile or acre, hauling by hour or by ton-mile) or other issues that may affect a price quote.

Indicate your intention to bid and/or receive quotes on specific jobs by using the Department's Bid Opening Sign in System

- The **[Bid Opening Sign-In](#)** web application located at <https://apps.nd.gov/dot/cr/csi/login.htm>.
Sign-In opens at 8 AM 7 calendar days prior to the bid opening and closes at 11 AM the day before the bid opening.
- Fill in the online form fields as required.
- Log in to download the "Bid Opening Contact Report" at <https://apps.nd.gov/dot/cr/csi/public/listBidOpenings.htm>

RECEIVE & EVALUATE ALL QUOTES GIVEN

All prime contractors and all subcontractors over \$500,000 should receive and evaluate all quotes offered.

All quotes given for each job should be faxed or emailed to prime contractors or subcontractors no later than the day before the bid opening. Subcontractors interested in work on the advertised jobs are encouraged to quote all contractors on the Sign-In report.

POST-AWARD REQUIREMENTS

FEDERAL AUTHORITY

The following paragraph must be included in all subcontracts of all tiers in accordance with 49 CFR § 26.13(b):

The contractor or all tiers of subcontractors shall not discriminate on the basis of race, color, national origin, or sex in the performance of this contract. The contractor shall carry out applicable requirements of 49 CFR § 26.13 in the award and administration of DOT-assisted contracts. Failure by the contractor to carry out these requirements is a material breach of this contract, which may result in the termination of this contract or such other remedy as NDDOT deems appropriate which may include, but is not limited to:

- (1) Withholding monthly progress payments;
- (2) Assessing sanctions;
- (3) Liquidated damages; and/or
- (4) Disqualifying the contractor from future bidding as non-responsible

It is the prime contractors' responsibility to ensure all tiers of subcontractors, brokers, manufacturers, suppliers, vendors, and regular dealers comply with the requirements of this special provision. In addition, the prime contractor has the responsibility to monitor DBE performance on the project, and to ensure that the DBE performs a commercially useful function (CUF).

PRIME CONTRACTOR'S MONITORING, RESPONSIBILITIES, REPORTING

For the life of the project, the prime contractor is responsible for the DBEs listed on Form C and for the specific spec/code items or products that the prime committed to during the award process.

The prime contractor is responsible to:

- Report payments to DBEs used to meet the project goal. **Payments on the contract must be entered and stored in the CCS. Use of CCS on the project eliminates the requirement to submit SFN 60638 and SFN 14268.**
- Invite and encourage all subcontractors and all DBEs listed on [Form C](#) to the pre-construction conference.
- Provide minutes to any DBE not in attendance at the pre-construction conference.
- Ensure their firm as well as any subcontractors, manufacturers, and regular dealers/suppliers comply with the requirements of this special provision.
- Provide all subcontractors with Proposed Project Schedules and any necessary updates.
- Monitor DBE performance on the project.
 - Submit [SFN 60597, DBE Performance – Commercially Useful Function \(CUF\)](#) Certification to the project engineer with [SFN 5682, Prime Contractor's Request to Sublet](#). Project engineers will not approve Requests to Sublet without the CUF Certification.
- Maintain project records and documentation of payments to DBEs for three years following acceptance of the final payment from NDDOT (per FHWA-1273, Section II Nondiscrimination #11).
 - This reporting requirement also applies to any certified DBE.
 - NDDOT may perform interim audits of contract payments to DBEs to ensure that the actual amount paid to DBEs equals or exceeds the dollar amount stated on Form C.
 - Make these records available for inspection, upon request, by an authorized representative of the NDDOT or USDOT.

If SFN 60597, and reports of payment are not received in a timely manner, progress payments will be withheld from the prime until submitted.

NDDOT MONITORING AND ENFORCEMENT MECHANISMS

The Department will bring any false, fraudulent, or dishonest conduct in connection with the DBE program to the attention of USDOT. USDOT may pursue action as provided in 49 CFR § 26.107. Actions include referral to the Department of Justice for criminal prosecution or referral to the USDOT Inspector General for action under suspension and debarment, or Program Fraud and Civil Remedies rules. The Department will also consider similar action under its own legal authority, including responsibility determination in future contracts.

COMMERCIALLY USEFUL FUNCTION

DBEs are required to perform a commercially useful function (CUF). CUF refers to those services the DBE is certified to perform. Certified services for each DBE are listed in the online DBE Directory. It is a DBE's responsibility to immediately notify the prime contractor in writing if the DBE is unable to perform a CUF or the services indicated on [Form C](#).

The contractor must certify that DBEs working on the prime's contract are performing a commercially useful function. Submit [SFN 60597, DBE Performance – Commercially Useful Function Certification](#) to the project engineer with [SFN 5682 -Contractor's Request to Sublet](#). Project engineers will not approve the Requests to Sublet without the CUF Certification. A review of the certification must be performed by the project engineer to determine whether the contract dollar value of the DBE's work may be counted toward the project goal.

The Department counts participation to a DBE contractor toward DBE goals only if the DBE is performing a CUF on that contract.

- A. A DBE performs a CUF when it is responsible for execution of the work of the contract and is carrying out its responsibilities by actually performing, managing, and supervising the work involved. To perform a CUF, the DBE must also be responsible, with respect to materials and supplies used on the contract, for negotiating price, determining quality and quantity, ordering the material, installation and paying for the material itself. 49 CFR § 26.55(c)(1)
- B. A DBE does not perform a CUF if its role is limited to that of an extra participant in a transaction, contract, or project through which funds are passed in order to obtain the appearance of DBE participation. 49 CFR § 26.55(c)(2)
- C. If a DBE does not perform or exercise responsibility for at least 30 percent of the total cost of its contract with its own work force, the Department must presume that it is not performing a CUF. 49 CFR § 26.55(c)(3)
- D. When a DBE is presumed not to be performing a CUF as provided in paragraph C (above), the DBE may present evidence to rebut this presumption. 49 CFR § 26.55(c)(4)
- E. The Department's decisions on CUF matters are subject to review by Federal Highway Administration, but are not administratively appealable to USDOT. 49 CFR § 26.55(c)(5)

COUNTING RACE/GENDER NEUTRAL DBE PARTICIPATION - 49 CFR § 26.55

The Department does not count the participation of a DBE subcontractor toward a contractor's final compliance with its DBE obligations on a contract until the amount being counted has actually been paid to the DBE. 49 CFR § 26.55 (h)

The Department will count DBE participation toward our overall annual goal as provided in 49 CFR § 26.55 as noted below.

- 1. The Department will use the following factors in counting DBE trucking participation.
 - A. For purposes of this section, a lease must indicate that the DBE has exclusive use of and control over the truck. This does not preclude the leased truck from working for others during the term of the lease with the consent of the DBE, so long as the lease gives the DBE absolute priority for use of the leased truck. Leased trucks must display the name and identification number of the DBE. 49 CFR § 26.55(d)(7)

- B. The DBE must be responsible for the management and supervision of the entire trucking operation for which it is responsible on a particular contract. 49 CFR § 26.55(d)(1)
- C. The DBE must itself own and operate at least one fully licensed, insured, and operational truck used on the contract and receives credit for the total value of the transportation services it provides on the contract using trucks it owns, insures, and operates using drivers it employs. 49 CFR § 26.55(d)(2-3)
- D. The DBE may lease trucks and drivers from another DBE firm and receives credit for the total value of the transportation services the lessee DBE provides. 49 CFR § 26.55(d)(4)
- E. The DBE may also lease trucks with drivers and is entitled to credit for the total value of transportation services provided by non-DBE leased trucks equipped with drivers not to exceed the services under items 1C and 1D. Additional participation by non-DBE owned trucks equipped with drivers receives credit only for the fee or commission it receives as a result of the lease arrangement. 49 CFR § 26.55(d)(5)

Example to 1D: DBE Firm X uses two of its own trucks on a contract. It leases two trucks with drivers from DBE Firm Y and six trucks with drivers from non-DBE Firm Z. DBE credit would be awarded for the total value of transportation services provided by Firm X and Firm Y, and may also be awarded for the total value of transportation services provided by four of the six trucks provided by Firm Z. In all, full credit would be allowed for the participation of eight trucks. DBE credit could be awarded only for the fees or commissions pertaining to the remaining trucks Firm X receives as a result of the lease with Firm Z.

- F. The DBE may lease trucks without drivers from a non-DBE truck leasing company and if the DBE uses its own employees as drivers, it is entitled to credit for the total value of these hauling services.

Example to paragraph 1F: DBE Firm X uses two of its own trucks and drivers on a contract. It leases two additional trucks and drivers from non-DBE Firm Z. Firm X uses its own employees to drive the trucks leased from Firm Z. DBE credit would be awarded for the total value of the transportation services provided by all four trucks. 49 § 26.55(d)(6)

- 2. Only the value of the work actually performed by the DBE counts toward the project goal when a DBE participates in a contract provided the DBE is certified in this work.
 - A. The Department counts the entire amount of that portion of a construction contract, or other contract not covered by item 2. B, that is performed by the DBE's own forces. Included are the cost of supplies and materials obtained by the DBE for the work of the contract, including supplies purchased or equipment leased by the DBE (except supplies and equipment the DBE subcontractor purchases or leases from the prime contractor or its affiliate). 49 CFR § 26.55 (a)(1)
 - B. The Department counts the entire amount of fees or commissions charged by a DBE firm for providing a bona fide service for which they are certified, such as professional, technical, consultant, or managerial services, or for providing bonds or insurance specifically required for the performance of a USDOT-assisted contract, toward DBE goals, if the Department determines the fee to be reasonable and not excessive. 49 CFR § 26.55 (a)(2)
 - C. When a DBE subcontracts part of the work of its contract to another firm, the value of the subcontracted work may be counted toward DBE goals only if the DBE's subcontractor is also a DBE. 49 CFR § 26.55 (a)(3)
- 3. The Department counts expenditures with DBEs for materials or supplies toward DBE goals as provided in the following:
 - A. If the materials or supplies are obtained from a DBE manufacturer, count 100% of the cost of the materials or supplies toward DBE goals. 49 CFR § 26.55 (e)(1)(i)
 - B. If the materials or supplies are purchased from a DBE regular dealer, count 60 percent of the cost of the materials or supplies toward DBE goals. 49 CFR § 26.55 (e)(2)(i)
 - C. Packagers, brokers, manufacturers' representatives, or other persons who arrange or expedite transactions are not regular dealers within the meaning of 3B (above) 49 CFR § 26.55 (e)(2)(ii)(C)
 - D. With respect to materials or supplies purchased from a DBE which is neither a manufacturer nor a regular dealer, count the entire amount of fees or commissions charged for assistance in the procurement of the materials and supplies, or fees or transportation charges for the delivery of materials or supplies required on a job site, toward DBE goals, if the Department determines the fees to be reasonable and not excessive. Do not count any portion of the cost of the materials and supplies themselves toward DBE goals, however.

49 CFR § 26.55 (e) (3)

- E. The Department determines the amount of credit awarded to a firm for the provisions of materials and supplies (e.g., whether a firm is acting as a regular dealer or a transaction expeditor) on a contract-by-contract basis. 49 CFR § 26.55 (e)(4)
4. If a firm is not currently certified in ND at the time of the execution of the contract, the Department does not count the firm's participation toward any DBE goal. 49 CFR § 26.55 (f)
5. The Department does not count the dollar value of work performed under a contract with a firm after it has ceased to be certified toward the Department's overall annual goal. 49 CFR § 26.55 (g)

DEFINITIONS

The definitions specified below apply only to this Special Provision and may contain differences from NDDOT Standard Specifications.

Achievement means any DBE certified service dollar amount committed to at the time of award. Any achievement must be supported by a request to sublet and Monthly DBE Payment Records for each DBE.

Aggregate providers are considered subcontractors rather than regular dealers/suppliers, regardless of the amount of their quote.

Apparent low bidder (ALB) means the bidder whose bid is read as low bid at the bid opening.

Bid Opening Sign-In System means the Department's online system to which all prime contractors and subcontractors must register to indicate their interest in quoting or bidding prior to each bid opening.

Bidder means a contractor intending to serve as the prime contractor for highway construction projects.

Blanket quote means when a business provides the same quote, for all projects, at a bid opening, using the same price at one rate, which is not project specific. Blanket quotes for the construction season are not allowed, i.e. trucking, striping, signing, construction supplies, etc.

Commercially Useful Function (CUF) describes a DBE's responsibilities and involvement in a project, see section Commercially Useful Function of this SP.

Commitment means the dollar amount of work the DBE will complete as stated in the bidder's proposal.

Contractor means all DBE and non-DBE firms, including prime contractors, brokers, vendors, regular dealers/suppliers, and manufacturers at any tier.

DBE Goal means a percentage of the total contract targeted for the hiring of DBE subcontractors to do specific bid items for which the DBE has been certified to perform. Project goals are set by assessing the project's bid items, location, whether DBEs are available to do the work.

DBE Participation means the percentage achieved when the dollar amount committed to the DBE is divided by the dollar amount of all contract items.

DBE Participation Review summarizes the prime's participation at the time of award. A replacement approval request must be submitted to substitute a firm for any DBEs reported as being used at the time of award.

Department means the project owner regardless of whether the owner is NDDOT, a city or a county project.

Disadvantaged business enterprise or DBE means a for-profit small business concern that is certified by the Department and listed in the DBE Directory available on the Department's web site. DBEs must first be certified in the work intended before any DBE achievement may be counted toward the project goal.

Equipment supplier is a firm which provides equipment for sale or lease, without operators, and whose primary business function is equipment sales or leasing.

Manufacturer means a firm that operates or maintains a factory or establishment that produces, on the premises, the materials, supplies, articles, or equipment required under the contract and of the general character described by the specifications. 49 CFR § 26.55 (e) (1) (ii)

Materials means aggregate, steel, petroleum products, concrete, asphalt, and other construction supplies.

NAICS Codes means industry codes assigned by North American Industry Classification System. When certified, DBE businesses are assigned NAICS codes which are identified in the DBE Directory.

NDDOT Certification & Compliance System (CCS) refers to the online compliance reporting system whereby contractors report/submit job related payments, commitments, and Utilization Plan documentation.

Positive Contact means active and documented solicitation of DBE and other subcontractors. Advertising the prime's intention to bid, using the Contractor sign in to notify DBEs and other subcontractors of the jobs the prime is interested in, and contacting individual DBEs is deemed positive contact.

Prime contractor means bidders who are submitting proposals on this project, regardless of the size of the project.

Project owner means any political subdivision such as a city or county which provides match to federal highway funds and uses NDDOT's electronic bidding system to let their projects to bid. The Department "owns" state projects.

Quoter means DBE or a non-DBE subcontractors, brokers, vendors, regular dealers/suppliers, and manufacturers at any tier who submits quotes to another contractor.

Race/Gender Neutral (RGN) means a zero (0) percent goal that is used to assist all small businesses. Please note, NDDOT intends to achieve its overall DBE goals via RGN means; 3.47 percent is the Department's RGN goal.

Responsible Bid Proposal means a bidder's proposal in which the project goal has been achieved, or the bidder demonstrates Good Faith Efforts (GFE) as outlined in this Special Provision timely.

Subcontractor means any firm intending to perform work, or intending to perform work and supply the materials, which were intended for their work on the project. All subcontractors must attach a list of DBE subcontractors intended for use to their quote when submitting it to the prime contractor.

Supplier means a party providing goods, services, and supplies on the project.

Broker means an agent who, without having custody of the property, a) negotiates contracts of purchase, work, lease, or sale; b) buys and sells goods; or c) negotiates between buyers and sellers. See Counting DBE Participation section.

Regular Dealer means a DBE firm that owns, operates, or maintains a store, warehouse, or other establishment in which the materials supplies, articles, or equipment of the general character described by the specifications and required under the contract are bought, kept in stock, and regularly sold or leased to the public in the usual course of business. See Counting DBE Participation section.

Tier means various levels of contractors on the job. For example a prime contractor's subcontractor (B) is referred to as the second tier. When B subcontracts with C, C becomes the third tier, etc.

Tied quote means the quote will be considered only if all of the bid items are included.

Untied quote means that any item or group of items quoted may be used for price noted on the quote whether one or all are used.

**NORTH DAKOTA DEPARTMENT OF TRANSPORTATION
EEO AFFIRMATIVE ACTION REQUIREMENTS**

March 15, 2014

Bidders shall become familiar with the following requirements and be prepared to comply in good faith with all of them:

APPENDIX A

Notice or Requirement for Affirmative Action to Ensure Equal Employment Opportunity (Executive Order 11246).

1. The Bidder's attention is called to the "Equal Opportunity Clause" and the "Standard Federal Equal Employment Opportunity Construction Contract Specifications" set forth herein.
2. The goals and timetables for minority and female participation, expressed in percentage terms for the Contractor's aggregate work force in each trade on all construction work in the covered area, are as follows:
 - a. Goals for Female Participation in Each Trade – Statewide6.9%
 - b. Goals for Minority Participation in Each Trade by County:
Barnes, Cass, Dickey, Eddy, Foster, Griggs, LaMoure, Logan,
McIntosh, Ransom, Richland, Sargent, Steele, Stutsman, Traill0.7%

Grand Forks1.2%

Benson, Cavalier, Nelson, Pembina, Ramsey, Towner, Walsh2.0%

Burleigh, Morton0.4%

Adams, Billings, Bowman, Dunn, Emmons, Golden Valley, Grant,
Hettinger, Kidder, Mercer, Oliver, Sheridan, Sioux, Slope, Stark, Wells . . .1.3%

Bottineau, Burke, Divide, McHenry, McKenzie, McLean, Mountrail,
Pierce, Renville, Rolette, Ward, Williams4.4%

These goals are applicable to all the Contractor's construction work (whether or not it is Federal or federally assisted) performed in the covered area. If the contractor performs construction work in a geographical area located outside the covered area, it shall apply the goals established for such geographical area where the work is actually performed. With regard to this second area, the contractor also is subject to the goals for both federally involved and nonfederally involved construction.

The Contractor's compliance with the Executive Order and the regulations in 41 CFR 60-4 shall be based on its implementation of the Equal Opportunity Clause specific affirmative action obligations required by the specifications set forth in 41 CFR 60-4.3 (a),

and its efforts to meet the goals established for the geographical area where the contract resulting from this solicitation is to be performed. The hours of minority and female employment and training must be substantially uniform throughout the length of the contract, and in each trade, and the Contractor shall make a good faith effort to employ minorities and women evenly on each of its projects. The transfer of minority or female employees or trainees from Contractor to Contractor or from project to project for the sole purpose of meeting the Contractor's goals shall be a violation of the contract, the Executive Order, and the regulations in 41 CFR part 60-4. Compliance with the goals will be measured against the total work hours performed.

3. The Contractor shall notify the Office of Federal Contract Compliance Programs, in writing, within ten working days of award of any subcontract in excess of \$10,000. The notification shall include the name, address, and telephone number of the subcontractor and their employer identification number; dollar amount of the contract, estimated starting and completion dates of the contract; the contract number; and geographical area in which the contract is to be performed.

Notification should be sent to:

U.S. Department of Labor/ESA
OFCCP
Denver District Office
1244 Speer Boulevard
Denver, Colorado 80202
Phone: 720-264-3200
Fax: 720-264-3211

4. As used in this "Notice" and in the contract for this project, the "covered area" is the State of North Dakota.

APPENDIX B

Standard Federal Equal Employment Opportunity Construction Contract Specifications
(Executive Order 11246)

1. As used in these specifications:
 - a. "Covered area" means the geographical area described in the proposal from which this contract resulted.
 - b. "Director" means Director, Office of Federal Contract Compliance Programs, United States Department of Labor, or any person to whom the Director delegates authority.
 - c. "Employer identification number" means the Federal Social Security number used on the Employer's Quarterly Federal Tax Return, U.S. Treasury Department Form 941.
 - d. "Minority" includes:

- (1) Black (all persons having origins in any of the Black African racial groups, not of Hispanic origin);
 - (2) Hispanic (all persons of Mexican, Puerto Rican, Cuban, Central or South American, or other Spanish Culture or origin, regardless of race);
 - (3) Asian and Pacific Islander (all persons having origins in any of the original peoples of the Far East, Southeast Asia, the Indian Subcontinent, or the Pacific Islands); and
 - (4) American Indian or Alaskan Native (all persons having origins in any of the original peoples of North America and maintaining identifiable tribal affiliations through membership and participation of community identification).
2. Whenever the Contractor, or any Subcontractor at any tier, subcontracts a portion of the work involving any construction trade, it shall physically include in each subcontract in excess of \$10,000 the provisions of these specifications and the Notice which contains the applicable goals for minority and female participation and which is set forth in the proposal from which this contract resulted.
3. If the Contractor is participating (pursuant to 41 CFR 60-4.5) in a Hometown Plan approved by the U.S. Department of Labor in the covered area either individually or through an association, its affirmative action obligations on all work in the Plan area (including goals and timetables) shall be in accordance with that Plan for those trades which have unions participating in the Plan. Contractors must be able to demonstrate their participation in and compliance with the provisions of any such Hometown Plan. Each Contractor or Subcontractor participating in an approved Plan is individually required to comply with its obligations under the EEO clause, and to make a good faith effort to achieve each goal under the Plan in each trade in which it has employees. The overall good faith performance by other Contractors or Subcontractors toward a goal in an approved Plan does not excuse any covered Contractor's or Subcontractor's failure to take good faith efforts to achieve the Plan goals and timetables.
4. The Contractor shall implement the specific affirmative action standards provided in paragraphs 7a through p of these specifications. The goals set forth in the solicitation from which this contract resulted are expressed as percentages of the total hours of employment and training of minority and female utilization the Contractor should reasonably be able to achieve in each construction trade in which it has employees in the covered area. The Contractor is expected to make substantially uniform progress toward its goals in each craft.
5. Neither the provisions of any collective bargaining agreement, nor the failure by a union with whom the Contractor has a collective bargaining agreement, to refer either minorities or women shall excuse the Contractor's obligations under these specifications, Executive Order 11246, or the regulations promulgated pursuant thereto.
6. In order for the nonworking training hours of apprentices and trainees to be counted

in meeting the goals, such apprentices and trainees must be employed by the Contractor during the training period, and the Contractor must have made a commitment to employ the apprentices and trainees at the completion of their training, subject to the availability of employment opportunities. Trainees must be trained pursuant to training programs approved by the U.S. Department of Labor. (Training programs approved by the North Dakota Department of Transportation are recognized by the U.S. Department of Labor.)

7. The Contractor shall take specific affirmative actions to ensure equal employment opportunity. The evaluation of the Contractor's compliance with these specifications shall be based upon its effort to achieve maximum results from its actions. The Contractor shall document these efforts fully, and shall implement affirmative action steps at least as extensive as the following:
 - a. Ensure and maintain a working environment free of harassment, intimidation, and coercion at all sites, and in all facilities at which the Contractor's employees are assigned to work. The Contractor, where possible, will assign two or more women to each construction project. The Contractor shall specifically ensure that all Foremen, Superintendents, and other on-site supervisory personnel are aware of and carry out the Contractor's obligation to maintain such a working environment, with specific attention to minority or female individuals working at such sites or in such facilities.
 - b. Establish and maintain a current list of minority and female recruitment sources; provide written notification to minority and female recruitment sources and to community organizations when the Contractor or its union have employment opportunities available, and maintain a record of the organization's responses.
 - c. Maintain a current file of the names, addresses, and telephone numbers of each minority and female off-the-street applicant and minority or female referral from a union, a recruitment source or community organization and of what action was taken with respect to each individual. If such individual was sent to the union hiring hall for referral and was not referred back to the Contractor by the union, or if referred, not employed by the Contractor, this shall be documented in the file with the reason therefore, along with whatever additional actions the Contractor may have taken.
 - d. Provide immediate written notification to the Director when the union with which the Contractor has a collective bargaining agreement has not referred to the Contractor a minority or woman sent by the Contractor, or when the Contractor has other information that the union referral process has impeded the Contractor's efforts to meet its obligations.
 - e. Develop on-the-job training opportunities and/or participate in training programs for the area which expressly include minorities and women, including upgrading programs and apprenticeship and trainee programs relevant to the Contractor's employment needs, especially those programs funded or approved by the Department of Labor. The Contractor shall provide notice of these programs to

the sources compiled under 7b above.

- f. Disseminate the Contractor's EEO policy by providing notice of the policy to unions and training programs and requesting their cooperation in assisting the Contractor in meeting its EEO obligations; by including it in any policy manual and collective bargaining agreement; by publicizing it in the Company newspaper, annual report, etc., by specific review of the policy with all management personnel and with all minority and female employees at least once a year; and by posting the Company EEO policy on bulletin boards accessible to all employees at each location where construction work is performed.
- g. Review, at least annually, the Company's EEO policy and affirmative action obligations under these specifications with all employees having any responsibility for hiring, assignment, layoff, termination, or other employment decisions including specific review of these items with on-site supervisory personnel such as Superintendents, General Foremen, etc., prior to the initiation of construction work at any job site. A written record shall be made and maintained identifying the time and place of these meetings, persons attending, subject matter discussed, and disposition of the subject matter.
- h. Disseminate the Contractor's EEO policy externally by including it in any advertising in the news media, specifically including minority and female news media, and providing written notification to and discussing it with the Contractors and Subcontractors with whom the Contractor does or anticipates doing business.
- i. Direct its recruitment efforts, both oral and written, to minority, female, and community organizations, to schools with minority and female students, and to minority and female recruitment and training organizations serving the Contractor's recruitment area and employment needs. Not later than one month prior to the date for the acceptance of applications for apprenticeship or other training by any recruitment source, the Contractor shall send written notification to organizations such as the above, describing the openings, screening procedures, and tests to be used in the selection process.
- j. Encourage present minority and female employees to recruit other minorities and women, and where reasonable, provide after school, summer, and vacation employment to minority and female youth both on the site and in other areas of the Contractor's work force.
- k. Validate all tests and other selection requirements where there is an obligation to do so under 41 CFR Part 60-3.
- l. Conduct, at least annually, an inventory and evaluation at least of all minority and female personnel for promotional opportunities and encourage these to seek or to prepare for, through appropriate training, etc., such opportunities.
- m. Ensure that seniority practices, job classifications, work assignments, and other personnel practices do not have a discriminatory effect by continually monitoring

- all personnel and employment related activities to ensure that the EEO policy and the Contractor's obligations under these specifications are being carried out.
- n. Ensure that all facilities and Company activities are non-segregated except that separate or single-user toilet and necessary changing facilities shall be provided to assure privacy between the sexes.
 - o. Document and maintain a record of all solicitations of offers for subcontracts from minority and female construction Contractors and Suppliers, including circulation of solicitations to minority and female Contractor associations and other business associations.
 - p. Conduct a review, at least annually, of all Supervisors' adherence to and performance under the Contractor's EEO policies and affirmative action obligation.
8. Contractors are encouraged to participate in voluntary associations which assist in fulfilling one or more of their affirmative action obligations (7a through p). The efforts of a Contractor association, joint Contractor- union, Contractor-community, or other similar group of which the Contractor is a member and participant, may be asserted as fulfilling any one or more of its obligations under 7a through p of these Specifications provided that the Contractor actively participates in the group, makes every effort to assure that the group has a positive impact on the employment of minorities and women in the industry, ensures that the concrete benefits of the program are reflected in the Contractor's minority and female work force participation, makes a good faith effort to meet its individual goals and timetables, and can provide access to documentation which demonstrates the effectiveness of actions taken on behalf of the Contractor. The obligation to comply, however, is the Contractor's, and failure of such a group to fulfill an obligation shall not be a defense for the Contractor's noncompliance.
9. Goals for minorities and a separate single goal for women have been established. The Contractor, however, is required to provide equal employment opportunity and to take affirmative action for all minorities, both male and female, and all women, both minority and non-minority. Consequently, the Contractor may be in violation of the Executive Order if a particular group is employed in a substantially disparate manner (for example, even though the Contractor has achieved its goals for women generally, the Contractor may be in violation of the Executive Order if a specific minority group of women is underutilized).
10. The Contractor shall not use the goals and timetables or affirmative action standards to discriminate against any person because of race, color, religion, sex, or national origin.
11. The Contractor shall not enter into any subcontract with any person or firm debarred from Government contracts pursuant to Executive Order 11246.
12. The Contractor shall carry out such sanctions and penalties for violation of these specifications and of the Equal Opportunity Clause, including suspension, termina-

tion, and cancellation of existing subcontracts as may be imposed or ordered pursuant to Executive Order 11246, as amended, and its implementing regulations, by the Office of Federal Contract Compliance Programs. Any Contractor who fails to carry out such sanctions and penalties shall be in violation of these specifications and Executive Order 11246, as amended.

13. The Contractor, in fulfilling its obligations under these specifications, shall implement specific affirmative action steps, at least as extensive as those standards prescribed in paragraph 7 of these specifications, so as to achieve maximum results from its efforts to ensure equal employment opportunity. If the Contractor fails to comply with the requirements of the Executive Order, the implementing regulations, or these specifications, the Director shall proceed in accordance with 41 CFR 60-4.8.
14. The Contractor shall designate a responsible official to monitor all employment-related activity to ensure that the Company EEO policy is being carried out, to submit reports relating to the provisions hereof as may be required by the Government, and to keep records. Records shall at least include for each employee the name, address, telephone numbers, construction trade, union affiliation, if any, employee identification number when assigned, social security number, race, sex, status (e.g., mechanic, apprentice, trainee, helper, or laborer), dates of changes in status, hours worked per week in the indicated trade, rate of pay, and locations at which the work was performed. Records shall be maintained in an easily understandable and retrievable form, however, to the degree that existing records satisfy this requirement, Contractors shall not be required to maintain separate records.
15. Nothing herein provided shall be construed as a limitation upon the application of other laws which establish different standards of compliance or upon application of requirements for the hiring of local or other area residents (e.g., those under the Public Works Employment Act of 1977 and the Community Development Block Grant Program).

**NORTH DAKOTA DEPARTMENT OF TRANSPORTATION
APPENDIX A OF THE TITLE VI ASSURANCES**

During the performance of this contract, the Contractor, for itself, its assignees, and successors in interest (hereinafter referred to as the Contractor) agrees as follows:

1. Compliance with Regulations: The Contractor (hereinafter includes consultants) will comply with the Acts and the Regulations relative to Non-discrimination in Federally-assisted programs of the U.S. Department of Transportation, the Federal Highway Administration, as they may be amended from time to time, which are herein incorporated by reference and made a part of this contract.

2. Non-discrimination: The Contractor, with regard to the work performed by it during the contract, will not discriminate on the grounds of race, color, or national origin in the selection and retention of subcontractors, including procurements of materials and leases of equipment. The Contractor will not participate directly or indirectly in the discrimination prohibited by the Acts and the Regulations, including employment practices when the contract covers any activity, project, or program set forth in Appendix B of 49 CFR Part 21.

3. Solicitations for Subcontracts, Including Procurements of Materials and Equipment: In all solicitations, either by competitive bidding, or negotiation made by the Contractor for work to be performed under a subcontract, including procurements of materials, or leases of equipment, each potential subcontractor or supplier will be notified by the Contractor of the Contractor's obligations under this contract and the Acts and the Regulations relative to Non-discrimination on the grounds of race, color, or national origin.

4. Information and Reports: The Contractor will provide all information and reports required by the Acts, the Regulations, and directives issued pursuant thereto and will permit access to its books, records, accounts, other sources of information, and its facilities as may be determined by the Recipient or the Federal Highway Administration to be pertinent to ascertain compliance with such Acts, Regulations, and instructions. Where any information required of a Contractor is in the exclusive possession of another who fails or refuses to furnish the information, the Contractor will so certify to the Recipient or the Federal Highway Administration as appropriate, and will set forth what efforts it has made to obtain the information.

5. Sanctions for Noncompliance: In the event of a contractor's noncompliance with the Non-discrimination provisions of this contract, the Recipient will impose such contract sanctions as it or the Federal Highway Administration may determine to be appropriate, including, but not limited to:

- a. withholding payments to the Contractor under the contract until the Contractor complies; and/or
- b. cancelling, terminating, or suspending a contract, in whole or in part.

6. Incorporation of Provisions: The Contractor will include the provisions of paragraphs one through six in every subcontract, including procurements of materials and leases of equipment, unless exempt by the Acts, the Regulations and directives issued pursuant thereto. The Contractor will take action with respect to any subcontract or procurement as the Recipient or the Federal Highway Administration may direct as a means of enforcing such provisions including sanctions for noncompliance. Provided, that if the Contractor becomes involved in, or is threatened with litigation by a subcontractor, or supplier because of such direction, the Contractor may request the Recipient to enter into any litigation to protect the interests of the Recipient. In addition, the Contractor may request the United States to enter into the litigation to protect the interests of the United States.

**NORTH DAKOTA DEPARTMENT OF TRANSPORTATION
APPENDIX E OF THE TITLE VI ASSURANCES**

During the performance of this contract, the contractor, for itself, its assignees, and successors in interest (hereinafter referred to as the Contractor) agrees to comply with the following non-discrimination statutes and authorities; including but not limited to:

Pertinent Non-Discrimination Authorities:

- Title VI of the Civil Rights Act of 1964 (42 U.S.C. § 2000d *et seq.*, 78 stat. 252), (prohibits discrimination on the basis of race, color, national origin); and 49 CFR Part 21.
- The Uniform Relocation Assistance and Real Property Acquisition Policies Act of 1970, (42 U.S.C. § 4601), (prohibits unfair treatment of persons displaced or whose property has been acquired because of Federal or Federal-aid programs and projects);
- Federal-Aid Highway Act of 1973, (23 U.S.C. § 324 *et seq.*), (prohibits discrimination on the basis of sex);
- Section 504 of the Rehabilitation Act of 1973, (29 U.S.C. § 794 *et seq.*), as amended, (prohibits discrimination on the basis of disability); and 49 CFR Part 27;
- The Age Discrimination Act of 1975, as amended, (42 U.S.C. § 6101 *et seq.*), (prohibits discrimination on the basis of age);
- Airport and Airway Improvement Act of 1982, (49 USC § 471, Section 47123), as amended, (prohibits discrimination based on race, creed, color, national origin, or sex);
- The Civil Rights Restoration Act of 1987, (PL 100-209), (Broadened the scope, coverage and applicability of Title VI of the Civil Rights Act of 1964, The Age Discrimination Act of 1975 and Section 504 of the Rehabilitation Act of 1973, by expanding the definition of the terms "programs or activities" to include all of the programs or activities of the Federal-aid recipients, sub-recipients and contractors, whether such programs or activities are Federally funded or not);
- Titles II and III of the Americans with Disabilities Act, which prohibit discrimination on the basis of disability in the operation of public entities, public and private transportation systems, places of public accommodation, and certain testing entities (42 U.S.C. §§ 12131-12189) as implemented by Department of Transportation regulations at 49 C.F.R. parts 37 and 38;
- The Federal Aviation Administration's Non-discrimination statute (49 U.S.C. § 47123) (prohibits discrimination on the basis of race, color, national origin, and sex);
- Executive Order 12898, Federal Actions to Address Environmental Justice in Minority Populations and Low-Income Populations, which ensures non-discrimination against minority populations by discouraging programs, policies, and activities with disproportionately high and adverse human health or environmental effects on minority and low-income populations;
- Executive Order 13166, Improving Access to Services for Persons with Limited English Proficiency, and resulting agency guidance, national origin discrimination includes discrimination because of limited English proficiency (LEP). To ensure compliance with Title VI, you must take reasonable steps to ensure that LEP persons have meaningful access to your programs (70 Fed. Reg. at 74087 to 74100);
- Title IX of the Education Amendments of 1972, as amended, which prohibits you from discriminating because of sex in education programs or activities (20 U.S.C. 1681 *et seq.*).

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION

CARGO PREFERENCE ACT (CPA)

DESCRIPTION

The Federal Highway Administration (FHWA) in partnership with the Federal Maritime Administration (MARAD) has mandated the implementation of 46 CFR 381 making the cargo preference requirements applicable to the Federal Aid Highway Program.

The requirements of this Special Provision apply to items transported by ocean vessel.

CONTRACT REQUIREMENTS

A. General

Utilize privately owned United States-flag commercial vessels to ship at least 50 percent of the gross tonnage whenever shipping any equipment, material, or commodities pursuant to this contract, to the extent such vessels are available at fair and reasonable rates for United States-flag commercial vessels. Gross tonnage is computed separately for dry bulk carriers, dry cargo liners, and tankers.

Furnish a legible, English language copy of a rated 'on-board' commercial ocean bill-of-lading for each shipment of cargo described in the previous paragraph. Furnish the bill-of-lading within 20 days following the date of loading for shipments originating in the United States and within 30 working days following the date of loading from shipments originating outside the United States.

Furnish bills-of-lading to the Engineer and to the following:

Division of National Cargo
Office of Market Development
Maritime Administration
Washington, DC 20590

B. Subcontracts

Include the language in Section "A, General" of this Special Provision in all subcontracts issued pursuant to this contract.

REQUIRED CONTRACT PROVISIONS FEDERAL-AID CONSTRUCTION CONTRACTS

- I. General
- II. Nondiscrimination
- III. Nonsegregated Facilities
- IV. Davis-Bacon and Related Act Provisions
- V. Contract Work Hours and Safety Standards Act Provisions
- VI. Subletting or Assigning the Contract
- VII. Safety: Accident Prevention
- VIII. False Statements Concerning Highway Projects
- IX. Implementation of Clean Air Act and Federal Water Pollution Control Act
- X. Compliance with Governmentwide Suspension and Debarment Requirements
- XI. Certification Regarding Use of Contract Funds for Lobbying

ATTACHMENTS

A. Employment and Materials Preference for Appalachian Development Highway System or Appalachian Local Access Road Contracts (included in Appalachian contracts only)

I. GENERAL

1. Form FHWA-1273 must be physically incorporated in each construction contract funded under Title 23 (excluding emergency contracts solely intended for debris removal). The contractor (or subcontractor) must insert this form in each subcontract and further require its inclusion in all lower tier subcontracts (excluding purchase orders, rental agreements and other agreements for supplies or services).

The applicable requirements of Form FHWA-1273 are incorporated by reference for work done under any purchase order, rental agreement or agreement for other services. The prime contractor shall be responsible for compliance by any subcontractor, lower-tier subcontractor or service provider.

Form FHWA-1273 must be included in all Federal-aid design-build contracts, in all subcontracts and in lower tier subcontracts (excluding subcontracts for design services, purchase orders, rental agreements and other agreements for supplies or services). The design-builder shall be responsible for compliance by any subcontractor, lower-tier subcontractor or service provider.

Contracting agencies may reference Form FHWA-1273 in bid proposal or request for proposal documents, however, the Form FHWA-1273 must be physically incorporated (not referenced) in all contracts, subcontracts and lower-tier subcontracts (excluding purchase orders, rental agreements and other agreements for supplies or services related to a construction contract).

2. Subject to the applicability criteria noted in the following sections, these contract provisions shall apply to all work performed on the contract by the contractor's own organization and with the assistance of workers under the contractor's immediate superintendence and to all work performed on the contract by piecework, station work, or by subcontract.

3. A breach of any of the stipulations contained in these Required Contract Provisions may be sufficient grounds for withholding of progress payments, withholding of final payment, termination of the contract, suspension / debarment or any other action determined to be appropriate by the contracting agency and FHWA.

4. Selection of Labor: During the performance of this contract, the contractor shall not use convict labor for any purpose within the limits of a construction project on a Federal-aid highway unless it is labor performed by convicts who are on parole, supervised release, or probation. The term Federal-aid highway does not include roadways functionally classified as local roads or rural minor collectors.

II. NONDISCRIMINATION

The provisions of this section related to 23 CFR Part 230 are applicable to all Federal-aid construction contracts and to all related construction subcontracts of \$10,000 or more. The provisions of 23 CFR Part 230 are not applicable to material supply, engineering, or architectural service contracts.

In addition, the contractor and all subcontractors must comply with the following policies: Executive Order 11246, 41 CFR 60, 29 CFR 1625-1627, Title 23 USC Section 140, the Rehabilitation Act of 1973, as amended (29 USC 794), Title VI of the Civil Rights Act of 1964, as amended, and related regulations including 49 CFR Parts 21, 26 and 27; and 23 CFR Parts 200, 230, and 633.

The contractor and all subcontractors must comply with: the requirements of the Equal Opportunity Clause in 41 CFR 60-1.4(b) and, for all construction contracts exceeding \$10,000, the Standard Federal Equal Employment Opportunity Construction Contract Specifications in 41 CFR 60-4.3.

Note: The U.S. Department of Labor has exclusive authority to determine compliance with Executive Order 11246 and the policies of the Secretary of Labor including 41 CFR 60, and 29 CFR 1625-1627. The contracting agency and the FHWA have the authority and the responsibility to ensure compliance with Title 23 USC Section 140, the Rehabilitation Act of 1973, as amended (29 USC 794), and Title VI of the Civil Rights Act of 1964, as amended, and related regulations including 49 CFR Parts 21, 26 and 27; and 23 CFR Parts 200, 230, and 633.

The following provision is adopted from 23 CFR 230, Appendix A, with appropriate revisions to conform to the U.S. Department of Labor (US DOL) and FHWA requirements.

1. Equal Employment Opportunity: Equal employment opportunity (EEO) requirements not to discriminate and to take affirmative action to assure equal opportunity as set forth under laws, executive orders, rules, regulations (28 CFR 35, 29 CFR 1630, 29 CFR 1625-1627, 41 CFR 60 and 49 CFR 27) and orders of the Secretary of Labor as modified by the provisions prescribed herein, and imposed pursuant to 23 U.S.C. 140 shall constitute the EEO and specific affirmative action standards for the contractor's project activities under

this contract. The provisions of the Americans with Disabilities Act of 1990 (42 U.S.C. 12101 et seq.) set forth under 28 CFR 35 and 29 CFR 1630 are incorporated by reference in this contract. In the execution of this contract, the contractor agrees to comply with the following minimum specific requirement activities of EEO:

a. The contractor will work with the contracting agency and the Federal Government to ensure that it has made every good faith effort to provide equal opportunity with respect to all of its terms and conditions of employment and in their review of activities under the contract.

b. The contractor will accept as its operating policy the following statement:

"It is the policy of this Company to assure that applicants are employed, and that employees are treated during employment, without regard to their race, religion, sex, color, national origin, age or disability. Such action shall include: employment, upgrading, demotion, or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship, pre-apprenticeship, and/or on-the-job training."

2. EEO Officer: The contractor will designate and make known to the contracting officers an EEO Officer who will have the responsibility for and must be capable of effectively administering and promoting an active EEO program and who must be assigned adequate authority and responsibility to do so.

3. Dissemination of Policy: All members of the contractor's staff who are authorized to hire, supervise, promote, and discharge employees, or who recommend such action, or who are substantially involved in such action, will be made fully cognizant of, and will implement, the contractor's EEO policy and contractual responsibilities to provide EEO in each grade and classification of employment. To ensure that the above agreement will be met, the following actions will be taken as a minimum:

a. Periodic meetings of supervisory and personnel office employees will be conducted before the start of work and then not less often than once every six months, at which time the contractor's EEO policy and its implementation will be reviewed and explained. The meetings will be conducted by the EEO Officer.

b. All new supervisory or personnel office employees will be given a thorough indoctrination by the EEO Officer, covering all major aspects of the contractor's EEO obligations within thirty days following their reporting for duty with the contractor.

c. All personnel who are engaged in direct recruitment for the project will be instructed by the EEO Officer in the contractor's procedures for locating and hiring minorities and women.

d. Notices and posters setting forth the contractor's EEO policy will be placed in areas readily accessible to employees, applicants for employment and potential employees.

e. The contractor's EEO policy and the procedures to implement such policy will be brought to the attention of employees by means of meetings, employee handbooks, or other appropriate means.

4. Recruitment: When advertising for employees, the contractor will include in all advertisements for employees the notation: "An Equal Opportunity Employer." All such advertisements will be placed in publications having a large circulation among minorities and women in the area from which the project work force would normally be derived.

a. The contractor will, unless precluded by a valid bargaining agreement, conduct systematic and direct recruitment through public and private employee referral sources likely to yield qualified minorities and women. To meet this requirement, the contractor will identify sources of potential minority group employees, and establish with such identified sources procedures whereby minority and women applicants may be referred to the contractor for employment consideration.

b. In the event the contractor has a valid bargaining agreement providing for exclusive hiring hall referrals, the contractor is expected to observe the provisions of that agreement to the extent that the system meets the contractor's compliance with EEO contract provisions. Where implementation of such an agreement has the effect of discriminating against minorities or women, or obligates the contractor to do the same, such implementation violates Federal nondiscrimination provisions.

c. The contractor will encourage its present employees to refer minorities and women as applicants for employment. Information and procedures with regard to referring such applicants will be discussed with employees.

5. Personnel Actions: Wages, working conditions, and employee benefits shall be established and administered, and personnel actions of every type, including hiring, upgrading, promotion, transfer, demotion, layoff, and termination, shall be taken without regard to race, color, religion, sex, national origin, age or disability. The following procedures shall be followed:

a. The contractor will conduct periodic inspections of project sites to insure that working conditions and employee facilities do not indicate discriminatory treatment of project site personnel.

b. The contractor will periodically evaluate the spread of wages paid within each classification to determine any evidence of discriminatory wage practices.

c. The contractor will periodically review selected personnel actions in depth to determine whether there is evidence of discrimination. Where evidence is found, the contractor will promptly take corrective action. If the review indicates that the discrimination may extend beyond the actions reviewed, such corrective action shall include all affected persons.

d. The contractor will promptly investigate all complaints of alleged discrimination made to the contractor in connection with its obligations under this contract, will attempt to resolve such complaints, and will take appropriate corrective action within a reasonable time. If the investigation indicates that the discrimination may affect persons other than the complainant, such corrective action shall include such other persons. Upon completion of each investigation, the contractor will inform every complainant of all of their avenues of appeal.

6. Training and Promotion:

a. The contractor will assist in locating, qualifying, and increasing the skills of minorities and women who are

applicants for employment or current employees. Such efforts should be aimed at developing full journey level status employees in the type of trade or job classification involved.

b. Consistent with the contractor's work force requirements and as permissible under Federal and State regulations, the contractor shall make full use of training programs, i.e., apprenticeship, and on-the-job training programs for the geographical area of contract performance. In the event a special provision for training is provided under this contract, this subparagraph will be superseded as indicated in the special provision. The contracting agency may reserve training positions for persons who receive welfare assistance in accordance with 23 U.S.C. 140(a).

c. The contractor will advise employees and applicants for employment of available training programs and entrance requirements for each.

d. The contractor will periodically review the training and promotion potential of employees who are minorities and women and will encourage eligible employees to apply for such training and promotion.

7. Unions: If the contractor relies in whole or in part upon unions as a source of employees, the contractor will use good faith efforts to obtain the cooperation of such unions to increase opportunities for minorities and women. Actions by the contractor, either directly or through a contractor's association acting as agent, will include the procedures set forth below:

a. The contractor will use good faith efforts to develop, in cooperation with the unions, joint training programs aimed toward qualifying more minorities and women for membership in the unions and increasing the skills of minorities and women so that they may qualify for higher paying employment.

b. The contractor will use good faith efforts to incorporate an EEO clause into each union agreement to the end that such union will be contractually bound to refer applicants without regard to their race, color, religion, sex, national origin, age or disability.

c. The contractor is to obtain information as to the referral practices and policies of the labor union except that to the extent such information is within the exclusive possession of the labor union and such labor union refuses to furnish such information to the contractor, the contractor shall so certify to the contracting agency and shall set forth what efforts have been made to obtain such information.

d. In the event the union is unable to provide the contractor with a reasonable flow of referrals within the time limit set forth in the collective bargaining agreement, the contractor will, through independent recruitment efforts, fill the employment vacancies without regard to race, color, religion, sex, national origin, age or disability; making full efforts to obtain qualified and/or qualifiable minorities and women. The failure of a union to provide sufficient referrals (even though it is obligated to provide exclusive referrals under the terms of a collective bargaining agreement) does not relieve the contractor from the requirements of this paragraph. In the event the union referral practice prevents the contractor from meeting the obligations pursuant to Executive Order 11246, as amended, and these special provisions, such contractor shall immediately notify the contracting agency.

8. Reasonable Accommodation for Applicants / Employees with Disabilities: The contractor must be familiar

with the requirements for and comply with the Americans with Disabilities Act and all rules and regulations established there under. Employers must provide reasonable accommodation in all employment activities unless to do so would cause an undue hardship.

9. Selection of Subcontractors, Procurement of Materials and Leasing of Equipment: The contractor shall not discriminate on the grounds of race, color, religion, sex, national origin, age or disability in the selection and retention of subcontractors, including procurement of materials and leases of equipment. The contractor shall take all necessary and reasonable steps to ensure nondiscrimination in the administration of this contract.

a. The contractor shall notify all potential subcontractors and suppliers and lessors of their EEO obligations under this contract.

b. The contractor will use good faith efforts to ensure subcontractor compliance with their EEO obligations.

10. Assurance Required by 49 CFR 26.13(b):

a. The requirements of 49 CFR Part 26 and the State DOT's U.S. DOT-approved DBE program are incorporated by reference.

b. The contractor or subcontractor shall not discriminate on the basis of race, color, national origin, or sex in the performance of this contract. The contractor shall carry out applicable requirements of 49 CFR Part 26 in the award and administration of DOT-assisted contracts. Failure by the contractor to carry out these requirements is a material breach of this contract, which may result in the termination of this contract or such other remedy as the contracting agency deems appropriate.

11. Records and Reports: The contractor shall keep such records as necessary to document compliance with the EEO requirements. Such records shall be retained for a period of three years following the date of the final payment to the contractor for all contract work and shall be available at reasonable times and places for inspection by authorized representatives of the contracting agency and the FHWA.

a. The records kept by the contractor shall document the following:

(1) The number and work hours of minority and non-minority group members and women employed in each work classification on the project;

(2) The progress and efforts being made in cooperation with unions, when applicable, to increase employment opportunities for minorities and women; and

(3) The progress and efforts being made in locating, hiring, training, qualifying, and upgrading minorities and women;

b. The contractors and subcontractors will submit an annual report to the contracting agency each July for the duration of the project, indicating the number of minority, women, and non-minority group employees currently engaged in each work classification required by the contract work. This information is to be reported on [Form FHWA-1391](#). The staffing data should represent the project work force on board in all or any part of the last payroll period preceding the end of July. If on-the-job training is being required by special provision, the contractor

will be required to collect and report training data. The employment data should reflect the work force on board during all or any part of the last payroll period preceding the end of July.

III. NONSEGREGATED FACILITIES

This provision is applicable to all Federal-aid construction contracts and to all related construction subcontracts of \$10,000 or more.

The contractor must ensure that facilities provided for employees are provided in such a manner that segregation on the basis of race, color, religion, sex, or national origin cannot result. The contractor may neither require such segregated use by written or oral policies nor tolerate such use by employee custom. The contractor's obligation extends further to ensure that its employees are not assigned to perform their services at any location, under the contractor's control, where the facilities are segregated. The term "facilities" includes waiting rooms, work areas, restaurants and other eating areas, time clocks, restrooms, washrooms, locker rooms, and other storage or dressing areas, parking lots, drinking fountains, recreation or entertainment areas, transportation, and housing provided for employees. The contractor shall provide separate or single-user restrooms and necessary dressing or sleeping areas to assure privacy between sexes.

IV. DAVIS-BACON AND RELATED ACT PROVISIONS

This section is applicable to all Federal-aid construction projects exceeding \$2,000 and to all related subcontracts and lower-tier subcontracts (regardless of subcontract size). The requirements apply to all projects located within the right-of-way of a roadway that is functionally classified as Federal-aid highway. This excludes roadways functionally classified as local roads or rural minor collectors, which are exempt. Contracting agencies may elect to apply these requirements to other projects.

The following provisions are from the U.S. Department of Labor regulations in 29 CFR 5.5 "Contract provisions and related matters" with minor revisions to conform to the FHWA-1273 format and FHWA program requirements.

1. Minimum wages

a. All laborers and mechanics employed or working upon the site of the work, will be paid unconditionally and not less often than once a week, and without subsequent deduction or rebate on any account (except such payroll deductions as are permitted by regulations issued by the Secretary of Labor under the Copeland Act (29 CFR part 3)), the full amount of wages and bona fide fringe benefits (or cash equivalents thereof) due at time of payment computed at rates not less than those contained in the wage determination of the Secretary of Labor which is attached hereto and made a part hereof, regardless of any contractual relationship which may be alleged to exist between the contractor and such laborers and mechanics.

Contributions made or costs reasonably anticipated for bona fide fringe benefits under section 1(b)(2) of the Davis-Bacon Act on behalf of laborers or mechanics are considered wages paid to such laborers or mechanics, subject to the provisions

of paragraph 1.d. of this section; also, regular contributions made or costs incurred for more than a weekly period (but not less often than quarterly) under plans, funds, or programs which cover the particular weekly period, are deemed to be constructively made or incurred during such weekly period. Such laborers and mechanics shall be paid the appropriate wage rate and fringe benefits on the wage determination for the classification of work actually performed, without regard to skill, except as provided in 29 CFR 5.5(a)(4). Laborers or mechanics performing work in more than one classification may be compensated at the rate specified for each classification for the time actually worked therein: Provided, That the employer's payroll records accurately set forth the time spent in each classification in which work is performed. The wage determination (including any additional classification and wage rates conformed under paragraph 1.b. of this section) and the Davis-Bacon poster (WH-1321) shall be posted at all times by the contractor and its subcontractors at the site of the work in a prominent and accessible place where it can be easily seen by the workers.

b. (1) The contracting officer shall require that any class of laborers or mechanics, including helpers, which is not listed in the wage determination and which is to be employed under the contract shall be classified in conformance with the wage determination. The contracting officer shall approve an additional classification and wage rate and fringe benefits therefore only when the following criteria have been met:

(i) The work to be performed by the classification requested is not performed by a classification in the wage determination; and

(ii) The classification is utilized in the area by the construction industry; and

(iii) The proposed wage rate, including any bona fide fringe benefits, bears a reasonable relationship to the wage rates contained in the wage determination.

(2) If the contractor and the laborers and mechanics to be employed in the classification (if known), or their representatives, and the contracting officer agree on the classification and wage rate (including the amount designated for fringe benefits where appropriate), a report of the action taken shall be sent by the contracting officer to the Administrator of the Wage and Hour Division, Employment Standards Administration, U.S. Department of Labor, Washington, DC 20210. The Administrator, or an authorized representative, will approve, modify, or disapprove every additional classification action within 30 days of receipt and so advise the contracting officer or will notify the contracting officer within the 30-day period that additional time is necessary.

(3) In the event the contractor, the laborers or mechanics to be employed in the classification or their representatives, and the contracting officer do not agree on the proposed classification and wage rate (including the amount designated for fringe benefits, where appropriate), the contracting officer shall refer the questions, including the views of all interested parties and the recommendation of the contracting officer, to the Wage and Hour Administrator for determination. The Wage and Hour Administrator, or an authorized representative, will issue a determination within 30 days of receipt and so advise the contracting officer or

will notify the contracting officer within the 30-day period that additional time is necessary.

(4) The wage rate (including fringe benefits where appropriate) determined pursuant to paragraphs 1.b.(2) or 1.b.(3) of this section, shall be paid to all workers performing work in the classification under this contract from the first day on which work is performed in the classification.

c. Whenever the minimum wage rate prescribed in the contract for a class of laborers or mechanics includes a fringe benefit which is not expressed as an hourly rate, the contractor shall either pay the benefit as stated in the wage determination or shall pay another bona fide fringe benefit or an hourly cash equivalent thereof.

d. If the contractor does not make payments to a trustee or other third person, the contractor may consider as part of the wages of any laborer or mechanic the amount of any costs reasonably anticipated in providing bona fide fringe benefits under a plan or program. Provided, That the Secretary of Labor has found, upon the written request of the contractor, that the applicable standards of the Davis-Bacon Act have been met. The Secretary of Labor may require the contractor to set aside in a separate account assets for the meeting of obligations under the plan or program.

2. Withholding

The contracting agency shall upon its own action or upon written request of an authorized representative of the Department of Labor, withhold or cause to be withheld from the contractor under this contract, or any other Federal contract with the same prime contractor, or any other federally-assisted contract subject to Davis-Bacon prevailing wage requirements, which is held by the same prime contractor, so much of the accrued payments or advances as may be considered necessary to pay laborers and mechanics, including apprentices, trainees, and helpers, employed by the contractor or any subcontractor the full amount of wages required by the contract. In the event of failure to pay any laborer or mechanic, including any apprentice, trainee, or helper, employed or working on the site of the work, all or part of the wages required by the contract, the contracting agency may, after written notice to the contractor, take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds until such violations have ceased.

3. Payrolls and basic records

a. Payrolls and basic records relating thereto shall be maintained by the contractor during the course of the work and preserved for a period of three years thereafter for all laborers and mechanics working at the site of the work. Such records shall contain the name, address, and social security number of each such worker, his or her correct classification, hourly rates of wages paid (including rates of contributions or costs anticipated for bona fide fringe benefits or cash equivalents thereof of the types described in section 1(b)(2)(B) of the Davis-Bacon Act), daily and weekly number of hours worked, deductions made and actual wages paid. Whenever the Secretary of Labor has found under 29 CFR 5.5(a)(1)(iv) that the wages of any laborer or mechanic include the amount of any costs reasonably anticipated in providing benefits under a plan or program described in section 1(b)(2)(B) of the Davis-

Bacon Act, the contractor shall maintain records which show that the commitment to provide such benefits is enforceable, that the plan or program is financially responsible, and that the plan or program has been communicated in writing to the laborers or mechanics affected, and records which show the costs anticipated or the actual cost incurred in providing such benefits. Contractors employing apprentices or trainees under approved programs shall maintain written evidence of the registration of apprenticeship programs and certification of trainee programs, the registration of the apprentices and trainees, and the ratios and wage rates prescribed in the applicable programs.

b. (1) The contractor shall submit weekly for each week in which any contract work is performed a copy of all payrolls to the contracting agency. The payrolls submitted shall set out accurately and completely all of the information required to be maintained under 29 CFR 5.5(a)(3)(i), except that full social security numbers and home addresses shall not be included on weekly transmittals. Instead the payrolls shall only need to include an individually identifying number for each employee (e.g., the last four digits of the employee's social security number). The required weekly payroll information may be submitted in any form desired. Optional Form WH-347 is available for this purpose from the Wage and Hour Division Web site at <http://www.dol.gov/esa/whd/forms/wh347instr.htm> or its successor site. The prime contractor is responsible for the submission of copies of payrolls by all subcontractors. Contractors and subcontractors shall maintain the full social security number and current address of each covered worker, and shall provide them upon request to the contracting agency for transmission to the State DOT, the FHWA or the Wage and Hour Division of the Department of Labor for purposes of an investigation or audit of compliance with prevailing wage requirements. It is not a violation of this section for a prime contractor to require a subcontractor to provide addresses and social security numbers to the prime contractor for its own records, without weekly submission to the contracting agency..

(2) Each payroll submitted shall be accompanied by a "Statement of Compliance," signed by the contractor or subcontractor or his or her agent who pays or supervises the payment of the persons employed under the contract and shall certify the following:

(i) That the payroll for the payroll period contains the information required to be provided under §5.5 (a)(3)(ii) of Regulations, 29 CFR part 5, the appropriate information is being maintained under §5.5 (a)(3)(i) of Regulations, 29 CFR part 5, and that such information is correct and complete;

(ii) That each laborer or mechanic (including each helper, apprentice, and trainee) employed on the contract during the payroll period has been paid the full weekly wages earned, without rebate, either directly or indirectly, and that no deductions have been made either directly or indirectly from the full wages earned, other than permissible deductions as set forth in Regulations, 29 CFR part 3;

(iii) That each laborer or mechanic has been paid not less than the applicable wage rates and fringe benefits or cash equivalents for the classification of work performed, as specified in the applicable wage determination incorporated into the contract.

(3) The weekly submission of a properly executed certification set forth on the reverse side of Optional Form WH-347 shall satisfy the requirement for submission of the "Statement of Compliance" required by paragraph 3.b.(2) of this section.

(4) The falsification of any of the above certifications may subject the contractor or subcontractor to civil or criminal prosecution under section 1001 of title 18 and section 231 of title 31 of the United States Code.

c. The contractor or subcontractor shall make the records required under paragraph 3.a. of this section available for inspection, copying, or transcription by authorized representatives of the contracting agency, the State DOT, the FHWA, or the Department of Labor, and shall permit such representatives to interview employees during working hours on the job. If the contractor or subcontractor fails to submit the required records or to make them available, the FHWA may, after written notice to the contractor, the contracting agency or the State DOT, take such action as may be necessary to cause the suspension of any further payment, advance, or guarantee of funds. Furthermore, failure to submit the required records upon request or to make such records available may be grounds for debarment action pursuant to 29 CFR 5.12.

4. Apprentices and trainees

a. Apprentices (programs of the USDOL).

Apprentices will be permitted to work at less than the predetermined rate for the work they performed when they are employed pursuant to and individually registered in a bona fide apprenticeship program registered with the U.S. Department of Labor, Employment and Training Administration, Office of Apprenticeship Training, Employer and Labor Services, or with a State Apprenticeship Agency recognized by the Office, or if a person is employed in his or her first 90 days of probationary employment as an apprentice in such an apprenticeship program, who is not individually registered in the program, but who has been certified by the Office of Apprenticeship Training, Employer and Labor Services or a State Apprenticeship Agency (where appropriate) to be eligible for probationary employment as an apprentice.

The allowable ratio of apprentices to journeymen on the job site in any craft classification shall not be greater than the ratio permitted to the contractor as to the entire work force under the registered program. Any worker listed on a payroll at an apprentice wage rate, who is not registered or otherwise employed as stated above, shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed. In addition, any apprentice performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed. Where a contractor is performing construction on a project in a locality other than that in which its program is registered, the ratios and wage rates (expressed in percentages of the journeyman's hourly rate) specified in the contractor's or subcontractor's registered program shall be observed.

Every apprentice must be paid at not less than the rate specified in the registered program for the apprentice's level of progress, expressed as a percentage of the journeymen hourly

rate specified in the applicable wage determination. Apprentices shall be paid fringe benefits in accordance with the provisions of the apprenticeship program. If the apprenticeship program does not specify fringe benefits, apprentices must be paid the full amount of fringe benefits listed on the wage determination for the applicable classification. If the Administrator determines that a different practice prevails for the applicable apprentice classification, fringes shall be paid in accordance with that determination.

In the event the Office of Apprenticeship Training, Employer and Labor Services, or a State Apprenticeship Agency recognized by the Office, withdraws approval of an apprenticeship program, the contractor will no longer be permitted to utilize apprentices at less than the applicable predetermined rate for the work performed until an acceptable program is approved.

b. Trainees (programs of the USDOL).

Except as provided in 29 CFR 5.16, trainees will not be permitted to work at less than the predetermined rate for the work performed unless they are employed pursuant to and individually registered in a program which has received prior approval, evidenced by formal certification by the U.S. Department of Labor, Employment and Training Administration.

The ratio of trainees to journeymen on the job site shall not be greater than permitted under the plan approved by the Employment and Training Administration.

Every trainee must be paid at not less than the rate specified in the approved program for the trainee's level of progress, expressed as a percentage of the journeyman hourly rate specified in the applicable wage determination. Trainees shall be paid fringe benefits in accordance with the provisions of the trainee program. If the trainee program does not mention fringe benefits, trainees shall be paid the full amount of fringe benefits listed on the wage determination unless the Administrator of the Wage and Hour Division determines that there is an apprenticeship program associated with the corresponding journeyman wage rate on the wage determination which provides for less than full fringe benefits for apprentices. Any employee listed on the payroll at a trainee rate who is not registered and participating in a training plan approved by the Employment and Training Administration shall be paid not less than the applicable wage rate on the wage determination for the classification of work actually performed. In addition, any trainee performing work on the job site in excess of the ratio permitted under the registered program shall be paid not less than the applicable wage rate on the wage determination for the work actually performed.

In the event the Employment and Training Administration withdraws approval of a training program, the contractor will no longer be permitted to utilize trainees at less than the applicable predetermined rate for the work performed until an acceptable program is approved.

c. Equal employment opportunity. The utilization of apprentices, trainees and journeymen under this part shall be in conformity with the equal employment opportunity requirements of Executive Order 11246, as amended, and 29 CFR part 30.

d. Apprentices and Trainees (programs of the U.S. DOT).

Apprentices and trainees working under apprenticeship and skill training programs which have been certified by the Secretary of Transportation as promoting EEO in connection with Federal-aid highway construction programs are not subject to the requirements of paragraph 4 of this Section IV. The straight time hourly wage rates for apprentices and trainees under such programs will be established by the particular programs. The ratio of apprentices and trainees to journeymen shall not be greater than permitted by the terms of the particular program.

5. Compliance with Copeland Act requirements. The contractor shall comply with the requirements of 29 CFR part 3, which are incorporated by reference in this contract.

6. Subcontracts. The contractor or subcontractor shall insert Form FHWA-1273 in any subcontracts and also require the subcontractors to include Form FHWA-1273 in any lower tier subcontracts. The prime contractor shall be responsible for the compliance by any subcontractor or lower tier subcontractor with all the contract clauses in 29 CFR 5.5.

7. Contract termination: debarment. A breach of the contract clauses in 29 CFR 5.5 may be grounds for termination of the contract, and for debarment as a contractor and a subcontractor as provided in 29 CFR 5.12.

8. Compliance with Davis-Bacon and Related Act requirements. All rulings and interpretations of the Davis-Bacon and Related Acts contained in 29 CFR parts 1, 3, and 5 are herein incorporated by reference in this contract.

9. Disputes concerning labor standards. Disputes arising out of the labor standards provisions of this contract shall not be subject to the general disputes clause of this contract. Such disputes shall be resolved in accordance with the procedures of the Department of Labor set forth in 29 CFR parts 5, 6, and 7. Disputes within the meaning of this clause include disputes between the contractor (or any of its subcontractors) and the contracting agency, the U.S. Department of Labor, or the employees or their representatives.

10. Certification of eligibility.

a. By entering into this contract, the contractor certifies that neither it (nor he or she) nor any person or firm who has an interest in the contractor's firm is a person or firm ineligible to be awarded Government contracts by virtue of section 3(a) of the Davis-Bacon Act or 29 CFR 5.12(a)(1).

b. No part of this contract shall be subcontracted to any person or firm ineligible for award of a Government contract by virtue of section 3(a) of the Davis-Bacon Act or 29 CFR 5.12(a)(1).

c. The penalty for making false statements is prescribed in the U.S. Criminal Code, 18 U.S.C. 1001.

V. CONTRACT WORK HOURS AND SAFETY STANDARDS ACT

The following clauses apply to any Federal-aid construction contract in an amount in excess of \$100,000 and subject to the overtime provisions of the Contract Work Hours and Safety Standards Act. These clauses shall be inserted in addition to the clauses required by 29 CFR 5.5(a) or 29 CFR 4.6. As used in this paragraph, the terms laborers and mechanics include watchmen and guards.

1. Overtime requirements. No contractor or subcontractor contracting for any part of the contract work which may require or involve the employment of laborers or mechanics shall require or permit any such laborer or mechanic in any workweek in which he or she is employed on such work to work in excess of forty hours in such workweek unless such laborer or mechanic receives compensation at a rate not less than one and one-half times the basic rate of pay for all hours worked in excess of forty hours in such workweek.

2. Violation; liability for unpaid wages; liquidated damages. In the event of any violation of the clause set forth in paragraph (1.) of this section, the contractor and any subcontractor responsible therefor shall be liable for the unpaid wages. In addition, such contractor and subcontractor shall be liable to the United States (in the case of work done under contract for the District of Columbia or a territory, to such District or to such territory), for liquidated damages. Such liquidated damages shall be computed with respect to each individual laborer or mechanic, including watchmen and guards, employed in violation of the clause set forth in paragraph (1.) of this section, in the sum of \$10 for each calendar day on which such individual was required or permitted to work in excess of the standard workweek of forty hours without payment of the overtime wages required by the clause set forth in paragraph (1.) of this section.

3. Withholding for unpaid wages and liquidated damages. The FHWA or the contracting agency shall upon its own action or upon written request of an authorized representative of the Department of Labor withhold or cause to be withheld, from any moneys payable on account of work performed by the contractor or subcontractor under any such contract or any other Federal contract with the same prime contractor, or any other federally-assisted contract subject to the Contract Work Hours and Safety Standards Act, which is held by the same prime contractor, such sums as may be determined to be necessary to satisfy any liabilities of such contractor or subcontractor for unpaid wages and liquidated damages as provided in the clause set forth in paragraph (2.) of this section.

4. Subcontracts. The contractor or subcontractor shall insert in any subcontracts the clauses set forth in paragraph (1.) through (4.) of this section and also a clause requiring the subcontractors to include these clauses in any lower tier subcontracts. The prime contractor shall be responsible for compliance by any subcontractor or lower tier subcontractor with the clauses set forth in paragraphs (1.) through (4.) of this section.

VI. SUBLETTING OR ASSIGNING THE CONTRACT

This provision is applicable to all Federal-aid construction contracts on the National Highway System.

1. The contractor shall perform with its own organization contract work amounting to not less than 30 percent (or a greater percentage if specified elsewhere in the contract) of the total original contract price, excluding any specialty items designated by the contracting agency. Specialty items may be performed by subcontract and the amount of any such specialty items performed may be deducted from the total original contract price before computing the amount of work required to be performed by the contractor's own organization (23 CFR 635.116).

a. The term "perform work with its own organization" refers to workers employed or leased by the prime contractor, and equipment owned or rented by the prime contractor, with or without operators. Such term does not include employees or equipment of a subcontractor or lower tier subcontractor, agents of the prime contractor, or any other assignees. The term may include payments for the costs of hiring leased employees from an employee leasing firm meeting all relevant Federal and State regulatory requirements. Leased employees may only be included in this term if the prime contractor meets all of the following conditions:

(1) the prime contractor maintains control over the supervision of the day-to-day activities of the leased employees;

(2) the prime contractor remains responsible for the quality of the work of the leased employees;

(3) the prime contractor retains all power to accept or exclude individual employees from work on the project; and

(4) the prime contractor remains ultimately responsible for the payment of predetermined minimum wages, the submission of payrolls, statements of compliance and all other Federal regulatory requirements.

b. "Specialty Items" shall be construed to be limited to work that requires highly specialized knowledge, abilities, or equipment not ordinarily available in the type of contracting organizations qualified and expected to bid or propose on the contract as a whole and in general are to be limited to minor components of the overall contract.

2. The contract amount upon which the requirements set forth in paragraph (1) of Section VI is computed includes the cost of material and manufactured products which are to be purchased or produced by the contractor under the contract provisions.

3. The contractor shall furnish (a) a competent superintendent or supervisor who is employed by the firm, has full authority to direct performance of the work in accordance with the contract requirements, and is in charge of all construction operations (regardless of who performs the work) and (b) such other of its own organizational resources (supervision, management, and engineering services) as the contracting officer determines is necessary to assure the performance of the contract.

4. No portion of the contract shall be sublet, assigned or otherwise disposed of except with the written consent of the contracting officer, or authorized representative, and such consent when given shall not be construed to relieve the contractor of any responsibility for the fulfillment of the contract. Written consent will be given only after the contracting agency has assured that each subcontract is

evidenced in writing and that it contains all pertinent provisions and requirements of the prime contract.

5. The 30% self-performance requirement of paragraph (1) is not applicable to design-build contracts; however, contracting agencies may establish their own self-performance requirements.

VII. SAFETY: ACCIDENT PREVENTION

This provision is applicable to all Federal-aid construction contracts and to all related subcontracts.

1. In the performance of this contract the contractor shall comply with all applicable Federal, State, and local laws governing safety, health, and sanitation (23 CFR 635). The contractor shall provide all safeguards, safety devices and protective equipment and take any other needed actions as it determines, or as the contracting officer may determine, to be reasonably necessary to protect the life and health of employees on the job and the safety of the public and to protect property in connection with the performance of the work covered by the contract.

2. It is a condition of this contract, and shall be made a condition of each subcontract, which the contractor enters into pursuant to this contract, that the contractor and any subcontractor shall not permit any employee, in performance of the contract, to work in surroundings or under conditions which are unsanitary, hazardous or dangerous to his/her health or safety, as determined under construction safety and health standards (29 CFR 1926) promulgated by the Secretary of Labor, in accordance with Section 107 of the Contract Work Hours and Safety Standards Act (40 U.S.C. 3704).

3. Pursuant to 29 CFR 1926.3, it is a condition of this contract that the Secretary of Labor or authorized representative thereof, shall have right of entry to any site of contract performance to inspect or investigate the matter of compliance with the construction safety and health standards and to carry out the duties of the Secretary under Section 107 of the Contract Work Hours and Safety Standards Act (40 U.S.C.3704).

VIII. FALSE STATEMENTS CONCERNING HIGHWAY PROJECTS

This provision is applicable to all Federal-aid construction contracts and to all related subcontracts.

In order to assure high quality and durable construction in conformity with approved plans and specifications and a high degree of reliability on statements and representations made by engineers, contractors, suppliers, and workers on Federal-aid highway projects, it is essential that all persons concerned with the project perform their functions as carefully, thoroughly, and honestly as possible. Willful falsification, distortion, or misrepresentation with respect to any facts related to the project is a violation of Federal law. To prevent any misunderstanding regarding the seriousness of these and similar acts, Form FHWA-1022 shall be posted on each Federal-aid highway project (23 CFR 635) in one or more places where it is readily available to all persons concerned with the project:

18 U.S.C. 1020 reads as follows:

"Whoever, being an officer, agent, or employee of the United States, or of any State or Territory, or whoever, whether a person, association, firm, or corporation, knowingly makes any false statement, false representation, or false report as to the character, quality, quantity, or cost of the material used or to be used, or the quantity or quality of the work performed or to be performed, or the cost thereof in connection with the submission of plans, maps, specifications, contracts, or costs of construction on any highway or related project submitted for approval to the Secretary of Transportation; or

Whoever knowingly makes any false statement, false representation, false report or false claim with respect to the character, quality, quantity, or cost of any work performed or to be performed, or materials furnished or to be furnished, in connection with the construction of any highway or related project approved by the Secretary of Transportation; or

Whoever knowingly makes any false statement or false representation as to material fact in any statement, certificate, or report submitted pursuant to provisions of the Federal-aid Roads Act approved July 1, 1916, (39 Stat. 355), as amended and supplemented;

Shall be fined under this title or imprisoned not more than 5 years or both."

IX. IMPLEMENTATION OF CLEAN AIR ACT AND FEDERAL WATER POLLUTION CONTROL ACT

This provision is applicable to all Federal-aid construction contracts and to all related subcontracts.

By submission of this bid/proposal or the execution of this contract, or subcontract, as appropriate, the bidder, proposer, Federal-aid construction contractor, or subcontractor, as appropriate, will be deemed to have stipulated as follows:

1. That any person who is or will be utilized in the performance of this contract is not prohibited from receiving an award due to a violation of Section 508 of the Clean Water Act or Section 306 of the Clean Air Act.

2. That the contractor agrees to include or cause to be included the requirements of paragraph (1) of this Section X in every subcontract, and further agrees to take such action as the contracting agency may direct as a means of enforcing such requirements.

X. CERTIFICATION REGARDING DEBARMENT, SUSPENSION, INELIGIBILITY AND VOLUNTARY EXCLUSION

This provision is applicable to all Federal-aid construction contracts, design-build contracts, subcontracts, lower-tier subcontracts, purchase orders, lease agreements, consultant contracts or any other covered transaction requiring FHWA approval or that is estimated to cost \$25,000 or more – as defined in 2 CFR Parts 180 and 1200.

1. Instructions for Certification – First Tier Participants:

a. By signing and submitting this proposal, the prospective first tier participant is providing the certification set out below.

b. The inability of a person to provide the certification set out below will not necessarily result in denial of participation in this

covered transaction. The prospective first tier participant shall submit an explanation of why it cannot provide the certification set out below. The certification or explanation will be considered in connection with the department or agency's determination whether to enter into this transaction. However, failure of the prospective first tier participant to furnish a certification or an explanation shall disqualify such a person from participation in this transaction.

c. The certification in this clause is a material representation of fact upon which reliance was placed when the contracting agency determined to enter into this transaction. If it is later determined that the prospective participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the contracting agency may terminate this transaction for cause of default.

d. The prospective first tier participant shall provide immediate written notice to the contracting agency to whom this proposal is submitted if any time the prospective first tier participant learns that its certification was erroneous when submitted or has become erroneous by reason of changed circumstances.

e. The terms "covered transaction," "debarred," "suspended," "ineligible," "participant," "person," "principal," and "voluntarily excluded," as used in this clause, are defined in 2 CFR Parts 180 and 1200. "First Tier Covered Transactions" refers to any covered transaction between a grantee or subgrantee of Federal funds and a participant (such as the prime or general contract). "Lower Tier Covered Transactions" refers to any covered transaction under a First Tier Covered Transaction (such as subcontracts). "First Tier Participant" refers to the participant who has entered into a covered transaction with a grantee or subgrantee of Federal funds (such as the prime or general contractor). "Lower Tier Participant" refers any participant who has entered into a covered transaction with a First Tier Participant or other Lower Tier Participants (such as subcontractors and suppliers).

f. The prospective first tier participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency entering into this transaction.

g. The prospective first tier participant further agrees by submitting this proposal that it will include the clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transactions," provided by the department or contracting agency, entering into this covered transaction, without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions exceeding the \$25,000 threshold.

h. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A participant is responsible for ensuring that its principals are not suspended, debarred, or otherwise ineligible to participate in covered transactions. To verify the eligibility of its principals, as well as the eligibility of any lower tier prospective participants, each participant may, but is not required to, check the Excluded Parties List System website (<https://www.epls.gov/>), which is compiled by the General Services Administration.

i. Nothing contained in the foregoing shall be construed to require the establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of the prospective participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.

j. Except for transactions authorized under paragraph (f) of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the department or agency may terminate this transaction for cause or default.

* * * * *

2. Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion – First Tier Participants:

a. The prospective first tier participant certifies to the best of its knowledge and belief, that it and its principals:

(1) Are not presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participating in covered transactions by any Federal department or agency;

(2) Have not within a three-year period preceding this proposal been convicted of or had a civil judgment rendered against them for commission of fraud or a criminal offense in connection with obtaining, attempting to obtain, or performing a public (Federal, State or local) transaction or contract under a public transaction; violation of Federal or State antitrust statutes or commission of embezzlement, theft, forgery, bribery, falsification or destruction of records, making false statements, or receiving stolen property;

(3) Are not presently indicted for or otherwise criminally or civilly charged by a governmental entity (Federal, State or local) with commission of any of the offenses enumerated in paragraph (a)(2) of this certification; and

(4) Have not within a three-year period preceding this application/proposal had one or more public transactions (Federal, State or local) terminated for cause or default.

b. Where the prospective participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal.

2. Instructions for Certification - Lower Tier Participants:

(Applicable to all subcontracts, purchase orders and other lower tier transactions requiring prior FHWA approval or estimated to cost \$25,000 or more - 2 CFR Parts 180 and 1200)

a. By signing and submitting this proposal, the prospective lower tier is providing the certification set out below.

b. The certification in this clause is a material representation of fact upon which reliance was placed when this transaction was entered into. If it is later determined that the prospective lower tier participant knowingly rendered an erroneous certification, in addition to other remedies available to the Federal Government, the department, or agency with which

this transaction originated may pursue available remedies, including suspension and/or debarment.

c. The prospective lower tier participant shall provide immediate written notice to the person to which this proposal is submitted if at any time the prospective lower tier participant learns that its certification was erroneous by reason of changed circumstances.

d. The terms "covered transaction," "debarred," "suspended," "ineligible," "participant," "person," "principal," and "voluntarily excluded," as used in this clause, are defined in 2 CFR Parts 180 and 1200. You may contact the person to which this proposal is submitted for assistance in obtaining a copy of those regulations. "First Tier Covered Transactions" refers to any covered transaction between a grantee or subgrantee of Federal funds and a participant (such as the prime or general contract). "Lower Tier Covered Transactions" refers to any covered transaction under a First Tier Covered Transaction (such as subcontracts). "First Tier Participant" refers to the participant who has entered into a covered transaction with a grantee or subgrantee of Federal funds (such as the prime or general contractor). "Lower Tier Participant" refers any participant who has entered into a covered transaction with a First Tier Participant or other Lower Tier Participants (such as subcontractors and suppliers).

e. The prospective lower tier participant agrees by submitting this proposal that, should the proposed covered transaction be entered into, it shall not knowingly enter into any lower tier covered transaction with a person who is debarred, suspended, declared ineligible, or voluntarily excluded from participation in this covered transaction, unless authorized by the department or agency with which this transaction originated.

f. The prospective lower tier participant further agrees by submitting this proposal that it will include this clause titled "Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion-Lower Tier Covered Transaction," without modification, in all lower tier covered transactions and in all solicitations for lower tier covered transactions exceeding the \$25,000 threshold.

g. A participant in a covered transaction may rely upon a certification of a prospective participant in a lower tier covered transaction that is not debarred, suspended, ineligible, or voluntarily excluded from the covered transaction, unless it knows that the certification is erroneous. A participant is responsible for ensuring that its principals are not suspended, debarred, or otherwise ineligible to participate in covered transactions. To verify the eligibility of its principals, as well as the eligibility of any lower tier prospective participants, each participant may, but is not required to, check the Excluded Parties List System website (<https://www.epls.gov/>), which is compiled by the General Services Administration.

h. Nothing contained in the foregoing shall be construed to require establishment of a system of records in order to render in good faith the certification required by this clause. The knowledge and information of participant is not required to exceed that which is normally possessed by a prudent person in the ordinary course of business dealings.

i. Except for transactions authorized under paragraph e of these instructions, if a participant in a covered transaction knowingly enters into a lower tier covered transaction with a person who is suspended, debarred, ineligible, or voluntarily excluded from participation in this transaction, in addition to other remedies available to the Federal Government, the

department or agency with which this transaction originated may pursue available remedies, including suspension and/or debarment.

* * * * *

Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion--Lower Tier Participants:

1. The prospective lower tier participant certifies, by submission of this proposal, that neither it nor its principals is presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participating in covered transactions by any Federal department or agency.

2. Where the prospective lower tier participant is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal.

* * * * *

XI. CERTIFICATION REGARDING USE OF CONTRACT FUNDS FOR LOBBYING

This provision is applicable to all Federal-aid construction contracts and to all related subcontracts which exceed \$100,000 (49 CFR 20).

1. The prospective participant certifies, by signing and submitting this bid or proposal, to the best of his or her knowledge and belief, that:

a. No Federal appropriated funds have been paid or will be paid, by or on behalf of the undersigned, to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with the awarding of any Federal contract, the making of any Federal grant, the making of any Federal loan, the entering into of any cooperative agreement, and the extension, continuation, renewal, amendment, or modification of any Federal contract, grant, loan, or cooperative agreement.

b. If any funds other than Federal appropriated funds have been paid or will be paid to any person for influencing or attempting to influence an officer or employee of any Federal agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with this Federal contract, grant, loan, or cooperative agreement, the undersigned shall complete and submit Standard Form-LLL, "Disclosure Form to Report Lobbying," in accordance with its instructions.

2. This certification is a material representation of fact upon which reliance was placed when this transaction was made or entered into. Submission of this certification is a prerequisite for making or entering into this transaction imposed by 31 U.S.C. 1352. Any person who fails to file the required certification shall be subject to a civil penalty of not less than \$10,000 and not more than \$100,000 for each such failure.

3. The prospective participant also agrees by submitting its bid or proposal that the participant shall require that the language of this certification be included in all lower tier subcontracts, which exceed \$100,000 and that all such recipients shall certify and disclose accordingly.

**ATTACHMENT A - EMPLOYMENT AND MATERIALS
PREFERENCE FOR APPALACHIAN DEVELOPMENT
HIGHWAY SYSTEM OR APPALACHIAN LOCAL ACCESS
ROAD CONTRACTS**

This provision is applicable to all Federal-aid projects funded under the Appalachian Regional Development Act of 1965.

1. During the performance of this contract, the contractor undertaking to do work which is, or reasonably may be, done as on-site work, shall give preference to qualified persons who regularly reside in the labor area as designated by the DOL wherein the contract work is situated, or the subregion, or the Appalachian counties of the State wherein the contract work is situated, except:

a. To the extent that qualified persons regularly residing in the area are not available.

b. For the reasonable needs of the contractor to employ supervisory or specially experienced personnel necessary to assure an efficient execution of the contract work.

c. For the obligation of the contractor to offer employment to present or former employees as the result of a lawful collective bargaining contract, provided that the number of nonresident persons employed under this subparagraph (1c) shall not exceed 20 percent of the total number of employees employed by the contractor on the contract work, except as provided in subparagraph (4) below.

2. The contractor shall place a job order with the State Employment Service indicating (a) the classifications of the laborers, mechanics and other employees required to perform the contract work, (b) the number of employees required in each classification, (c) the date on which the participant estimates such employees will be required, and (d) any other pertinent information required by the State Employment Service to complete the job order form. The job order may be placed with the State Employment Service in writing or by telephone. If during the course of the contract work, the information submitted by the contractor in the original job order is substantially modified, the participant shall promptly notify the State Employment Service.

3. The contractor shall give full consideration to all qualified job applicants referred to him by the State Employment Service. The contractor is not required to grant employment to any job applicants who, in his opinion, are not qualified to perform the classification of work required.

4. If, within one week following the placing of a job order by the contractor with the State Employment Service, the State Employment Service is unable to refer any qualified job applicants to the contractor, or less than the number requested, the State Employment Service will forward a certificate to the contractor indicating the unavailability of applicants. Such certificate shall be made a part of the contractor's permanent project records. Upon receipt of this certificate, the contractor may employ persons who do not normally reside in the labor area to fill positions covered by the certificate, notwithstanding the provisions of subparagraph (1c) above.

5. The provisions of 23 CFR 633.207(e) allow the contracting agency to provide a contractual preference for the use of mineral resource materials native to the Appalachian region.

6. The contractor shall include the provisions of Sections 1 through 4 of this Attachment A in every subcontract for work which is, or reasonably may be, done as on-site work.

**CONTRACT SPECIAL PROVISION
MANDATORY USE OF
AUTOMATED CERTIFIED
PAYROLL**

All contractors on NDDOT federal-aid projects, including city/county projects, must file weekly Certified Payrolls, as required under Davis-Bacon and Related Acts (DBRA). **The NDDOT requires the use of LCPtracker, a paperless online system for entering and filing these certified payrolls. Certified payrolls in paper form will no longer be accepted, and all contractors must file their payroll electronically.**

After award, the Prime Contractor (Prime) must:

1. Designate an individual as Prime Approver for the project. The Prime Approver will oversee DBRA payroll for all subcontractors of all tiers on the project. A contractor may inform the NDDOT Civil Rights Division (CRD) that the same individual will be Prime Approver on all projects. CRD will set up the Prime Approver Account for the project. Thereafter, the Prime Approver will have the responsibility to use the Account to approve all payroll on the project. Until payroll is approved by the Prime Approver, it cannot be viewed by the NDDOT and it is not deemed submitted to the NDDOT.
2. The prime contractor has the responsibility to assign subcontractors within the LCPtracker system to the project and to ensure that all subcontractors are aware of the necessity to file payrolls electronically and are set up within the system. Any subcontractor not on Approved Subcontractor List or the Qualified Contractor List must register and be placed on one of these lists before entry of the subcontractor into LCPtracker. These lists may be found at <https://www.dot.nd.gov/pacer/qualified.htm> and <https://www.dot.nd.gov/pacer/registered.htm>. Only Prime Approvers or the CRD may enter subcontractors into LCPtracker.
3. The prime contractor has the responsibility to see that all required payrolls are filed by subcontractors of all tiers. If payroll is rejected or project staff otherwise requests a correction of payroll by any subcontractor on the project, the prime contractor has a responsibility to see that corrected payroll is submitted.
4. For further information on certified payroll, go to the NDDOT Labor Compliance/LCPtracker page at <https://www.dot.nd.gov/divisions/civilrights/laborcompliance.htm>. On this page, contractors will find a Getting Started on LCPtracker Guide and a Prime Approver Guide. Recorded trainings are also available on this page for both contractors and prime approvers. Contractors can obtain an LCPtracker user name and password by calling the NDDOT Civil Rights Division at (701) 328-2605 or (701) 328-2576.

09/06/2017

**CONTRACT SPECIAL PROVISION
MANDATORY USE OF ONLINE
DBE PROJECT PAYMENT REPORTING**

Payments made to all tiers of subcontractors must be reported electronically using the B2GNow system. Paper forms (Monthly Record of DBE Project Payments – SFN 60638) will no longer be accepted.

After award, the Prime Contractor (Prime) must:

1. Create a new account if not already in the system. Create a user for each employee who will use the system. If there is no account already set up, you can email Customer Support directly from the Account Lookup page. Your email address will be your user ID. Customer Support will email you with the information you need to log in.
2. Once the project has been awarded and the Utilization Plan (UP) has been created in the system and assigned to the contractor it must be filled out and submitted. An automated email message will be sent to a designated individual within the company alerting them that a UP is pending. Log into the system using the link provided in the email. For each contract the Prime must add all DBE and non-DBE subs being used on the project. When all information has been provided submit the UP. Civil Rights will review the UP and if everything is in order it will be approved. If changes need to be made the UP will be returned to the contractor and they will have 7 days to make the necessary adjustments and resubmit. If DBE or non-DBE subcontractors are added after the initial UP is set up the Prime can submit a request for them to be added.
3. Once the UP is submitted the project is “locked in” after Financial Management has processed the project in their system. After a UP is locked in payments from NDDOT to the Prime are reported through the system. The Prime must start reporting DBE and non-DBE subcontractor payments through the system in accordance with prompt pay guidelines outlined in the contract.
4. A user manual for UP’s and recording project payments is available to the contractors within the system. After login they can go to View>>My Utilization Plans and they will find the guide on the top of the Utilization Plan screen. They do not have to have a current UP assigned to them to see this guide. The guide is also on the actual UP page when a UP is assigned to them.
5. For further information on the Certification and Compliance System, go to the NDDOT Civil Rights page at <https://www.dot.nd.gov/divisions/civilrights/civilrights.htm>. There is various training available on a regular basis, to sign up for training go to the main Certification and Compliance System page and click the “Training and Events” box. Contractors that need to obtain an account or need subcontractors set up within the system should call the NDDOT Civil Rights Division at (701) 328-3116 or email civilrights@nd.gov

10/3/2017

NOTICE:

Electrical work done outdoors on highway construction projects is covered by the Line Construction rates rather than Electrician rates. When electrical work is performed on or within a commercial building only, such as a rest area, the job classification Electrician is to be used. Any other electrical work on a federal-aid highway construction project in North Dakota is covered by the line construction rates. The minimum wage and fringe amount stated in the attached wage determination within this proposal is required for such classification.

Apprentices in Line Construction: Apprentices in Line Construction must be classified and paid as Apprentice Linemen with a percentage of journeyman's pay that reflects the apprentice's progress level of training. Additionally, they must be enrolled in a bona fide lineman Apprentice Program regardless if they are also enrolled in an indoor Electrical Apprentice Program.

Electrical work may not be done by any Laborer classification under the ND Century Code. The Group 2 Laborer, Conduit Layer may only handle low voltage data or telephone lines and may not install or handle electrical conduit.

For assistance or questions concerning Davis-Bacon Wages and Requirements, go to:

<https://www.dot.nd.gov/manuals/civilrights/davisbacon.pdf>

Or contact:

Civil Rights Division
North Dakota Department of Transportation
608 East Boulevard Avenue
Bismarck, ND 58505-0700
Phone: 701-328-2605 Email: civilrights.nd.gov

NDDOT's *Davis-Bacon Wage and Payroll Requirements Handbook* is available at:
www.dot.nd.gov/manuals/civilrights/davisbacon.pdf

U.S.DEPARTMENT OF LABOR

STATE	COUNTY	20200037	Page 1
NORTH DAKOTA	STATEWIDE	DATE OF DECISION 1-3-20	
		Revised 2-07-2020 (Mod. No. 1) Revised 2-28-2020 (Mod. No. 2) Revised 3-05-2020 (Mod. No. 3) Revised 3-20-2020 (Mod. No. 4) Revised 8-28-2020 (Mod. No. 5)	

	Basic Hourly Rates	Fringe Benefits Payments			
		H & W/Pensions	Vacation	App. Tr.	Others
CARPENTERS	\$29.85	\$ 7.35			
CEMENT MASONS/FINISHERS	29.85	7.35			
LINE CONSTRUCTION:					
Lineman	43.50	5.75 + 29%			
Cable Splicer	43.50	5.75 + 29%			
Line Equipment Operator	36.93	5.75 + 29%			
Groundman	24.62	5.75 + 29%			
ELECTRICIANS:					
Electrician	34.92	11.40 + 11.5%			
Cable Splicer	36.67	11.40 + 11.5%			
(Adams, Billings, Bottineau, Bowman, Burke, Divide, Dunn, Emmons, Golden Valley, Grant, Hettinger, McHenry, McKenzie, Mclean, Mercer, Mountrail, Oliver, Pierce, Renville, Rolette, Sheridan, Sioux, Slope, Ward and Williams Counties)					
Electrician	36.36	10.80 + 11.5%			
Cable Splicer	37.94	10.80 + 11.5%			
(Barnes, Benson, Cavalier, Dickey, Eddy, Foster, Grand Forks, Griggs, Kidder, La-Moure, Logan, McIntosh, Nelson, Pembina, Ramsey, Ransom, Richland, Sargent, Steele, Stutsman, Towner, Traill, Walsh, and Wells Counties)					
Electrician	34.70	11.40 + 11.5%			
Cable Splicer	34.64	11.40 + 11.5%			
(Burleigh, Morton and Stark Counties)					
Electrician					
(Cass County)	14.72	3.40			
WELDERS:					
Receive rate prescribed for craft performing operation to which welding is incidental					
LABORERS:					
Group 1					
General Construction Laborers :Sack Shaker (cement and mineral filler), pipe handler, drill runner tender, salamander heater and blower tender, light truck, pickup driver, flaggers and pilot car drivers	21.90	2.90			

LABOR RATES

Page 4 of 4

01-03-2020

Revised 2-07-2020 (Mod. No. 1)

Revised 2-28-2020 (Mod. No. 2)

Revised 3-05-2020 (Mod. No. 3)

Revised 3-20-2020 (Mod. No. 4)

Revised 8-28-2020 (Mod. No. 5)

ND20200037

Page

	Basic Hourly Rates	Fringe Benefits Payments			
		H & W/Pensions	Vacation	App. Tr.	Others
POWER EQUIP. OPERATORS: (CONT.)					
Group 4 (cont.)					
Packer with Dozer Attachment 100 H.P. and over; Shouldering Machine; Slip Form, Curb and Gutter Operator, Slurry Seal Machine; Tamping Machine Operator; Tie Tamper and Ballast Machine; Trenching Machine Operator, 46 H.P. up to and including 99 H.P.; Truck Mechanic; Tub Grinder; Well Points; Fuel/Lube Operator	28.65	\$17.20			
Group 5					
Boom Truck, A-Frame or Hydraulic 2 tons up to and including 7 tons; Broom Self-Propelled; Concrete Saw (power operated); Cure Bridge Operator; Front End Loader Operator, less than 1-1/2 CY; Mobile Cement Mixer; Power Actuated Auger and Horizontal Boring Machine Operator, up to and including 5"; Roller (on other than hot mix asphalt paving); Oilers; Vibrating Packer Operator (Pad Type) (Self-Propelled); Water Spraying Equipment, Self-Propelled; Skidsteer Operator with attachments	27.80	17.20			
Group 6					
Brakeman or Switchman; Curb Machine Operator (Manual); Dredge or Tugboat Deckhand; Drill Truck Gravel/Testing Operator; Form Trench Digger (Power); Gunite Operator; Gunall; Paint Machine Striping Operator; Pickup Sweeper, 1 CY and over Hopper Capacity; Scissor Jack (Self-Propelled) Platform Lift; Straw Mulcher and Blower; Stump Chipper Operator; Tractor Pulling Compaction or Aerating Equipment; Trenching Machine Operator, up to and including 45 H.P.; Assistant/Apprentice Operator	26.50	17.20			
TRUCK DRIVERS:					
Single-Axle Truck	28.82	13.85			
Tandem- and Tri-Axle Truck	28.94	13.85			
Tandem- and Tri-Axle Semi	29.25	13.85			
Lowboy	29.25	13.85			
Off Road Heavy Duty End Dumps, 20 Yards and Under	29.25	13.85			
Euclid, Over 20 Yards	30.77	13.85			

Unlisted classifications needed for work not included within the scope of the classifications listed may be added alter award only as provided in the labor standards contract clauses [29 CFR, 5.5 (a) (1) (ii)].

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION (NDDOT)

2017 ON-THE-JOB TRAINING PROGRAM SPECIAL PROVISION

The bidder's signature on the proposal sheet indicates the bidder agrees to take part in the On-the-Job Training (OJT) Program and to follow the OJT Program Manual and Special Provision. Contractors that fail to do so will be subject to suspension of progress payments or sanctions up to and including revocation of bidding privileges.

OJT is training conducted in a highway construction work environment designed to enable minority, female, and economically disadvantaged individuals to learn a bona fide skill and qualify for a specific occupation through demonstration and practice.

After a training program and trainee candidate have been approved, the contractor begins training its regular employee according to the approved program. The goal of this training is to retain the trainee as a permanent employee. OJT involves individuals at the entry level. Training is designed to help participants reach their fullest potential and become self-sufficient in the job.

I. POLICY STATEMENT

The purpose of the OJT Program is to provide training in the highway construction industry for minority, female, and economically disadvantaged individuals, from this time known as the targeted group. Pursuant to 23 Code of Federal Regulations Part 230, Subpart A, Appendix B - Training Special Provisions, this program provides for on-the-job training aimed at developing journey-level workers in skilled trades.

The Contractor shall take all necessary and reasonable steps to ensure that minorities and women have the opportunity to compete for and participate as trainees or apprentices and to develop as journey-level workers employed in the skilled trades.

Contractors should select a training program(s) based on their company's employment/staffing needs as stated in the OJT Program Manual.

II. INTRODUCTION/PROGRAM BACKGROUND

The OJT Program was originally prepared through the cooperative efforts of the Associated General Contractors of North Dakota (AGC); the Federal Highway Administration (FHWA); the North Dakota Department of Transportation (Department); and, other program stakeholders.

Successful operation of the OJT Program requires contractors to follow uniform and basic training procedures, keep records of trainee progress, and report each trainee's completion or termination.

III. ASSIGNED OJT POSITIONS

A. Trainee positions are assigned contractors based only on federal highway dollars awarded from October 1 to September 30. Trainee assignments are not project specific; that means the contractor may train program participants on any project where training opportunities exist.

The number of trainee positions assigned will be determined by formula based on calculations involving particular project specification numbers on applicable projects. The types of projects NOT applicable in the calculation to assign trainee positions are:

- County-only or state-only funded projects
- Emergency relief, concrete pavement repair (CPR), electrical, rest area, signing, striping projects
- Projects subject to Tribal Employment Rights Ordinances (TERO)
- Projects not let through NDDOT bid openings

- B. Contractors will receive the number of positions assigned and links to resources necessary for completion of program requirements via email.
- C. The number of trainee positions assigned to each contractor will increase proportionately, as shown below, for any applicable federally funded projects awarded to them.

For all federal highway dollars awarded from October 1 to September 30:

6,000,000 to 15,000,000	1	trainee
15,000,001 to 23,000,000	2	trainees
22,000,001 to 31,000,000	3	trainees
31,000,001 and above	4	trainees

A maximum of four (4) trainee positions in a federal fiscal year will be assigned to any prime contractor regardless of dollar amount. Carryover positions from a prior construction season are not included in the four trainee maximum, e.g., a contractor with one carryover and four assigned positions may have a total five trainees.

Failure to follow this OJT Special Provision and the accompanying OJT Program Manual may result in suspension of progress payments or sanctions up to and including revocation of bidding privileges.

IV. FUNDING

The Department will establish an OJT fund annually from which contractors may bill the Department directly for eligible trainee hours. The funds for payment of trainee hours on federal-aid projects will be made available based on 23 USC 504(e) to a maximum of \$100,000. The funds for payment of trainee hours on state-aid only projects will be allocated to a maximum of \$10,000.

V. ONLINE RESOURCES

OJT Program Manual: Includes program requirements, wage rates, and curriculum:
<https://www.dot.nd.gov/divisions/civilrights/docs/ojtprogram.pdf>

SFN 60226 Request for On-the-Job Training Program and Trainee Approval:
<http://www.dot.nd.gov/forms/sfn60226.pdf>

SFN 51023 Voucher for On-the-Job Training Program Hourly Reimbursement:
<http://www.dot.nd.gov/forms/sfn51023.pdf>

Davis-Bacon and Related Acts (DBRA) Handbook: <https://www.dot.nd.gov/manuals/civilrights/davisbacon.pdf>

VI. APPROVALS REQUIRED

- A. Requests for Training Programs and Trainee Approvals must be submitted to Civil Rights Division (CRD). Contractors must request and receive program and trainee candidate approval in order to pay trainees less than the established Davis-Bacon wage for the job classification concerned. No training program hours will count toward the fulfillment of an assigned trainee position or be eligible for reimbursement without prior approval. No retroactive approval will be granted.
 - 1. Submit *SFN 60226 Request for On-the-Job Training Program and Trainee Approval* with each trainee's employment application. <http://www.dot.nd.gov/forms/sfn60226.pdf> and the pre-approved training curriculum for each trainee position assigned by April 1 or within fifteen (15) calendar days of notification of any additional position assignments.
 - 2. Submit *SFN 7857 Application for Eligibility*, Job Service North Dakota (JSND) approval of an economically disadvantaged individual for participation in the OJT Program.

- B. Pre-approved curriculum: NDDOT's OJT Program Manual contains pre-approved training curriculum for a number of skilled trade positions. Contractors should select a training program(s) based on their company's employment/staffing needs.
- C. Customized curriculum: To request a training curriculum not included in the pre-approved curriculum, submit a written request for approval by NDDOT and FHWA.

The request must include:

- A training curriculum, including the classification requested, minimum number of hours required, and type of training the individual will receive to achieve journey-level worker status.
- A minimum wage scale.

If approved, each new classification must comply with the provisions specified in the OJT Program Manual. No hours worked prior to approval will be credited toward completion of the customized training program. Training programs for classifications not covered by the Davis-Bacon and Related Acts (DBRA) will be considered on a limited basis.

The contractor may commence its "customized" training as of the date of the written approval.

- D. Union apprenticeship and on-the-job training programs registered with the Bureau of Apprenticeship and Training (BAT), U.S. Department of Labor, may be used for trainee positions assigned under the OJT Program, provided the trainees or apprentices are minority, female, or economically disadvantaged. Nonminority males not certified as economically disadvantaged may only be used when the contractor has requested and received approval, from the Department, for additional trainee positions. The apprenticeship indenture agreements serve as the trainee's job application and must be provided prior to any hours being credited toward OJT Program completion.
- E. Power Equipment Operators:

The contractor may train an individual on a combination of equipment if each piece of equipment falls within the same groups of power equipment operators identified in the training curricula (groups 1-3 and groups 4-6). These power equipment operator groups are referenced to the federal DBRA wage rates contained in the contract proposal. As an example, a "utility operator" may receive training on a broom, a front-end loader less than 1½ cubic yards, or other piece of equipment that is used around a paver if each piece falls within either groups 1-3 or groups 4-6. When multiple wage rates apply, the trainee's wage will be based on the equipment being operated at the time or on the highest of the applicable wage rates.

Use of the classification "pickup machine operator (asphalt dump-person)" as a group 4 power equipment operator is considered standard industry practice. The classification is defined as: "Operates the controls on the pickup machine that runs in front of the paver, trips the levers on the dump trucks, and balances the loads for the paver. The pickup machine operates on similar principles as a shouldering machine."

- F. Contractors not qualifying for the OJT Program, or contractors desiring to train more than the allotted number of trainees, may apply to the Department for additional trainee positions. Approval of additional positions will be at the sole discretion of the Department. The Department will take into consideration whether there is enough work for the trainee to successfully complete the curriculum and whether the contractor will be exceeding the allowable ratio of trainees to journey-workers (generally considered to be one trainee or apprentice to every three to five journey-workers).

The additional positions may be filled by individuals outside of the targeted groups. The contractor may pay the reduced training rates to additional trainees outside of the targeted groups, but will not receive hourly reimbursement for any individuals who are outside the targeted groups.

VII. NDDOT'S RESPONSIBILITIES

- A. The NDDOT OJT supportive services (OJTSS) consultant will monitor excerpts from the weekly certified payrolls submitted with the monthly vouchers for reimbursement. This includes weekly payrolls from

contractors working on state funded only projects. On contracts where certified payrolls are not required and not available for supporting documentation, contractors may enter trainee wages, hours in training, and the project control number(s) (PCN) in a spreadsheet to support their reimbursement vouchers. In this case, contractors should work with OJTSS to assure that all information required for payment is provided. The OJTSS consultant will assess when the trainees have completed the specified number of hours and their wages are increased accordingly. The OJTSS consultant will also assure that applicable fringe benefits are paid either directly to the trainees or for the trainee into approved plans, funds, or programs.

- B. The OJTSS consultant is charged with visiting trainees and monitoring their progress under the OJT Program. To facilitate the on-site visits, the OJTSS consultant will contact contractors for the location of the trainees weekly.

VIII. CONTRACTOR'S RESPONSIBILITIES

- A. Consistently demonstrate efforts to recruit, hire, and train candidates for the OJT Program.
- B. Assign each trainee to a particular person—either a supervisor or an employee proficient in the skills to be trained—who shall see that the trainee is given timely, instructional experience. This person must be familiar with the OJT Program, keep proper records, and ensure completion of the required training hours in accordance with the training curriculum.
- C. Appoint a company employee who will be available and responsive to weekly contacts by the OJTSS consultant. OJTSS monitors the status of assigned trainee positions (e.g., program and trainee approvals, trainees' progress, etc.). The OJTSS consultant will contact the individual listed on the company's approved SFN 60226 Request for OJT Trainee Approval. This person must reply to communications from the Department and the OJTSS consultant in a timely manner.
- D. Make trainees available to the OJTSS consultant for at least two on-site visits during the construction season.
- E. Make the trainer and project superintendent available to the OJTSS consultant for at least two on-site visits each construction season.
- F. Make trainees aware they are formally enrolled in the OJT program.
- G. Identify trainees on the payroll excerpts, for example: "grp. 4 roller operator trainee." This includes trainees in job classifications not covered by DBRA. Handwritten notes are appropriate for identification.
- H. Notify the Department when a trainee completes the number of hours required to graduate from the OJT Program. The Department will issue the trainee a certificate of completion and a wallet-sized card as proof of the graduate's successful training program completion.
- I. Notify the Department to "propose graduation" or discontinue the training period of a trainee who has completed 90% or more of their hours and thereafter advance the trainee to journey-worker status.
- J. Elect to upgrade proficient trainees from one power equipment operator group or truck driver group to another, with the approval of CRD. Fewer hours are required to complete the upgraded position.

Minimum number of hours required:

Power Equipment Operator Groups 4-6 to Groups 1-3 = 400 hrs.
Class C Truck Driver to Class B = 200 hrs.
Class B Truck Driver to Class A = 200 hrs.

Depending on the variety of experience the trainee has gained under the previous curriculum, the difference in the hours may be deducted from the actual operation of the piece of equipment or truck. The contractor will need to review the trainee's past performance in order to make this determination.

- K. May hire commercial driver's license (CDL) holders as truck driver trainees. Those having over-the-road driving experience, with little or no highway construction experience, may be considered to have completed

the Class C truck driver training curriculum and, therefore, are eligible to be upgraded to a Class B truck driver trainee, with the approval CRD.

- L. May transfer trainees from one project to another in order to complete the OJT Program. If transfers are made, CRD must be notified and provided with the name of the trainer. The training hours will count toward overall OJT Program completion.
- M. May train trainees on municipal, private, out-of-state projects or other non-highway work. These training hours must be paid at the OJT minimum wage scale to count toward their OJT Program completion; however, no program reimbursement will be made for those hours.
- N. May delegate or reassign trainee positions to subcontractors, with the acceptance of the subcontractors and the approval of CRD. The prime contractor must verify that the trainee will be able to accumulate enough hours to complete his or her training program. If approved, the subcontractor must obtain training program and trainee approval from CRD before the trainee begins work under the OJT program. Program reimbursement will be made directly to the prime contractor. The trainee position will remain the responsibility of the prime contractor.
- O. May use trainees on projects subject to TERO requirements as part of the core crew or as part of the skilled labor supplied by the contractor. The training hours will count toward overall OJT Program completion; however, no program reimbursement will be made for those hours unless it is a NDDOT let project.
- P. May not use one trainee to simultaneously fill multiple trainee positions
- Q. May use a trainee on a piece of equipment in groups 1-3 or groups 4-6 for one assigned trainee position, then once that trainee has completed the program, the trainee may be trained on a different piece of equipment in groups 1-3 or groups 4-6 to fulfill a second assigned trainee position. When a trainee is used for a second time within a group, the contractor must pay that trainee at the higher wage rate as described in paragraph B under Wage Rates (page 8).

IX. CLASSROOM TRAINING

- A. Classroom training may be used to train employees. Each classroom training curriculum must be pre-approved by CRD if the contractor wishes to count the classroom hours as training hours and be reimbursed.

Submit a proposed classroom training curriculum to CRD for approval. Define the type of training the individual will receive, classroom training curriculum, and the minimum number of hours required. The Department will determine the number of hours of credit each trainee will receive toward their training. No retroactive approval will be granted.
- B. Contractors will be reimbursed for classroom training hours after the trainee has completed 80 hours of work on highway construction projects.
- C. Reimbursement for classroom training will be limited to 60 hours per trainee per construction season. Reimbursement for classroom training required under the NDDOT Transportation Technician Qualification Program will be at the NDDOT discretion.
- D. The minimum wage scale to be used for classroom training will be that of the first federal-aid highway construction project on which the trainee will be employed. If the trainee is already employed on a federal-aid highway construction project, the trainee will be paid in accordance with the minimum wage scale applicable to that project. However, if the first project on which the trainee will be employed is a state funded only contract, the minimum wage scale to be used for the classroom training will be that of the appropriate DBRA wage in effect at the time of award of the state funded contract.

X. WAGE RATES

- A. When the contractor is submitting the trainee's hours toward training program, wages paid shall in no case

be less than that of those stated in the approved curriculum. A trainee working on a state funded only project, must be paid the DBRA wage rate in effect at the time of award for the type of work the trainee is performing as a trainee.

- B. The minimum wage rates shall not be less than 80% of the journey-worker rate for the first two quarters of training, 85% of the journey-worker rate for the third quarter, and 90% of the journey-worker rate for the fourth quarter.
- Under the power equipment operator training curricula only, once a trainee has completed a training curriculum in either groups 1-3 or groups 4-6, the contractor may enroll the trainee in another training curriculum on a different piece of equipment in either groups 1-3 or groups 4-6.
 - The minimum wage rate under the trainee's second program shall not be less than 85% of the journey-worker rate for the first two quarters of training, 90% of the journey-worker rate for the third quarter, and 95% of the journey-worker rate for the fourth quarter.
 - For the purpose of the OJT Program, a quarter is 25% of the hours the trainee works toward completion of their approved program. The first two quarters of a 550-hour training curriculum would end after 275 hours, the third quarter after 138 hours, and the fourth after 137 hours.
- C. At any time hours are being attributed toward the completion of the approved training program, trainees shall be paid full fringe benefit amounts, where applicable, in accordance to DBRA requirements.
- D. At the completion of the OJT Program, the trainee shall receive the wages of a skilled journey-worker.

XI. RECRUITMENT AND SELECTION

- A. Prerequisites:
- Trainees must possess basic physical fitness for the work to be performed, dependability, willingness to learn, ability to follow instructions, and an aptitude to maintain a safe work environment.
- B. Licenses:
- Truck driver trainees must possess appropriate driver permits or licenses for the operation of Class A, B, and C trucks. When an instructional permit is used in lieu of a license, the trainee must be accompanied by an operator who:
1. Holds a license corresponding to the vehicle being operated;
 2. Has had at least one year of driving experience; and
 3. Is occupying the seat next to the driver.
- C. Recruitment:
1. Place notices and posters setting forth the contractor's Equal Employment Opportunity (EEO) Policy and the availability of the OJT Program in areas readily accessible to employees, applicants for employment, and potential employees.
 2. Employ members of the targeted group (minority, female, or economically disadvantaged individuals) for all trainee positions assigned in accordance with the OJT Program. Additional positions requested by the contractor may be filled by individuals outside of the targeted groups.
 3. Conduct systematic and direct recruitment through public and private employee referral sources.
 4. Screen present employees for upgrading to higher skilled crafts. A present employee may qualify as a trainee; however, no work hours will be reimbursed or counted toward program completion prior to training program and trainee approval by CRD.
- D. Selection:
1. Hire and enroll OJT trainee candidates who qualify as an individual in the targeted group.

2. Select a training program(s) based on their company's employment/staffing needs.
3. Individuals in the targeted group having experience in the selected curriculum may be eligible to participate in the OJT Program providing they:
 - Are not or have not been journey-workers in the selected curriculum, and/or
 - Have not been previously trained in the selected curriculum.
4. Non-minority males who are economically disadvantaged must obtain written certification from Job Service North Dakota (JSND) to qualify for the OJT Program. Contractors wishing to hire and enroll economically disadvantaged candidates must provide JSND's certification along with SFN 60226 and the employment application when requesting trainee approval.
 - JSND is the only agency that may certify an individual as economically disadvantaged. If JSND refers the candidate to the contractor, written certification under this category will be provided to the contractor at the time of the interview.
 - Any person wishing to obtain this certification must apply to JSND and complete the Workforce Investment Act Program's Application for Eligibility (SFN 7857). A contractor recruiting a candidate who may qualify must contact the Workforce Investment Act Program Manager at JSND. JSND contacts are also online:
<http://www.dot.nd.gov/divisions/civilrights/docs/jobservice-workforce-invest-contacts.pdf>

XII. BASIS OF PAYMENT

- A. Contractors will be paid \$4.00 for each hour of training in accordance with the OJT Program Manual.
 - B. Reimbursement will be made directly to the contractor. Complete SFN 51023 Voucher for On-the-Job Training Program Hourly Reimbursement for each trainee. Attach excerpts from the weekly certified payrolls showing the trainee's hours, rate of pay, and how applicable fringe benefits were paid. Excerpts from weekly payrolls are also required for state funded only projects. Vouchers without excerpts from payrolls will not be paid until the excerpts are provided. If the excerpts from the payrolls are not provided within one week, the voucher will not be paid and the trainee's hours will not be credited toward completion.
<http://www.dot.nd.gov/forms/sfn51023.pdf>
 - C. On contracts where certified payrolls are not required and not available for supporting documentation, contractors may enter trainee wages, hours in training, and the project control number(s) (PCN) in a spreadsheet to support their reimbursement vouchers. In this case, contractors should work with OJTSS to assure that all information required for payment is provided.
 - D. Submit completed vouchers to CRD for approval and processing by the fifteenth (15th) calendar day of every following month the trainee is employed under the OJT Program.
- Regardless, all vouchers for trainee hours worked on state funded only projects from July 1 to June 30 must be received by CRD no later than July 15 in order to be reimbursed. All vouchers for trainee hours worked on federally funded projects from October 1 to September 30 must be received by CRD no later than October 15 in order to be reimbursed. This is due to state and federal end-of-the-year budget fiduciary requirements.

XIII. FAILURE TO PROVIDE THE TRAINING OR HIRE THE TRAINEE AS A JOURNEY-WORKER

- A. The contractor is required to consistently demonstrate efforts to recruit, hire, and train candidates for the OJT Program.
- B. If the contractor does not show in a timely manner good faith efforts to recruit, hire, and train candidates in the targeted group, the Department may withhold progress payments
- C. If payments have been made, the Department will deduct the amount paid from the contractor's progress

payment.

- D. No payment shall be made to a contractor for failure to provide the required training or failure to hire the trainee as a journey-worker when such failure is caused by the contractor and evidences a lack of good faith on the part of the contractor in meeting the requirements of this OJT Program Special Provision.
- E. Hiring a trainee to begin training as soon as feasible after start of work is evidence of a contractor's good faith efforts to comply with the OJT Program requirements. Additional evidence supporting a contractor's good faith efforts would be to keep the trainee employed as long as training opportunities exist in the approved work classification or until the trainee has completed his or her training program.
- F. It is not required that all trainees be employed for the entire length of the construction season. A contractor will have fulfilled its responsibilities under this OJT Special Provision if it has provided acceptable training to the number of trainees assigned.

XIV. UNFILLED OR INCOMPLETE TRAINEE POSITIONS

- A. By October 1, provide written explanation of the firm's good faith efforts for unfilled or incomplete trainee assignments to CRD. CRD will decide, on a case-by-case basis, whether to carry the assigned positions over to the next construction season.
- B. Positions carried over from the previous construction season must be among the first positions filled at season startup. To notify CRD of the trainee's rehiring, submit *SFN 60226 Request for On-the-Job Trainee Approval*, marking 'Check if Carryover Trainee' in the Approved Training Program section of the form. There is no need for the training position or a returning trainee to be re-approved.
- C. Sanctions, up to and including revocation of bidding privileges, may be imposed on the contractor for failure to provide sufficient explanation and documentation for reasons assigned trainee positions when unfilled or incomplete.

XV. DEFINITIONS

Carryover Position: Incomplete trainee position carried forward from a prior program year.

Carryover Trainee: Trainee scheduled to continue training hours under prior year's approved program.

CRD: NDDOT's Civil Rights Division administers the NDDOT On-the-Job Training Program.

Good Faith Efforts: Documentation supporting a contractor's efforts to fulfill the program requirements, e.g., new hires list, advertising examples/locations, current employees reviewed for upgrades, etc.

Journey-worker: A worker employed in a trade or craft who has attained a level of skill, abilities, and competencies recognized within the industry.

OJT Supportive Services (OJTSS): Department contractor providing in-person oversight, support, and guidance to contractors and trainees to increase the effectiveness of approved training programs.

Trainee: A person who receives training through an apprenticeship program or other FHWA approved program.

Trainer/Supervisor: Contractor's employee assigned to train, supervise, and support a trainee.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION

TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES

1. GENERAL

Install, maintain and remove appropriate Temporary Erosion and Sediment Control Measures (ESCMs).

Definitions:

A. Temporary Erosion and Sediment Control Measures are to be installed and maintained before and during the term of the land disturbance activity. These items are removed when permanent erosion and sediment ESCMs are installed.

B. Permanent Erosion and Sediment Control Measures are to be installed and maintained once the project is completed so that the applicable permits can be terminated.

In some instances, individual temporary and permanent erosion and sediment ESCMs for a site may consist of identical ESCMs. In these cases, the temporary erosion and sediment ESCMs may be used as the permanent erosion and sediment ESCMs if they meet the following criteria:

1. The ESCM was installed correctly,
2. Is in a functional condition,
3. Has had all accumulated sediment removed.

C. The Stormwater Pollution Prevention Plan (SWPPP) is the document that identifies potential sources of sediment or other pollution from construction activity and ensures practices are used to reduce the contribution of pollutants from construction site runoff.

D. Contractor Controlled Areas are project areas not included in the contract, but are obtained and solely controlled by the Contractor (e.g., concrete or asphalt batch plants, concrete washout areas, equipment staging yards, material storage areas, excavated material disposal areas, Contractor furnished borrow areas, etc.).

E. Maintenance is any action taken to keep an ESCM in working condition. These actions may consist of repairing failures of the ESCM itself.

F. Noncompliance is any action or inaction that violates the regulations imposed by the applicable permits or the requirements of this special provision and other contract documents. Failure of an ESCM does not necessarily constitute noncompliance as long as the ESCM is repaired, replaced or supplemented within the timelines established in the applicable permits and no sediment is discharged from the site or into a water of the state.

2. CONSTRUCTION REQUIREMENTS

Develop a SWPPP specific to the project. The creation of the SWPPP is a cooperative effort between the NDDOT who creates the project plan sheets and the Contractor who creates a complete SWPPP which incorporates the plan sheets and the Contractor's means and methods. The project plan sheets by themselves do not meet the requirements of a complete SWPPP and should not be considered as such. The Contractor has the flexibility to modify the design and implementation of the temporary erosion and sediment controls to match the Contractor's means and methods and/or field conditions. These changes must be documented in the SWPPP and meet all regulatory requirements.

Obtain appropriate permit coverage for the activities conducted in Contractor Controlled Areas. A permit will be required for these areas regardless of their size. The NDDOT will have no responsibility for these areas. Provide copies of the completed and signed Notice of Intent submitted for permit coverage to the Engineer before activities in these areas commence. Do not commence activities in these areas until after permit coverage has begun. Provide copies of Permit Coverage Letters for these areas to the Engineer within 7 days of receiving them from the regulating agency.

Install perimeter erosion and sediment ESCMs according to the plans/SWPPP prior to site disturbance.

Change the location of temporary erosion and sediment ESCMs to fit the field conditions.

Update the SWPPP as work progresses, or as directed by the Engineer. Update the SWPPP to show changes due to revisions in work schedules or sequence of construction. Update the site map to reflect erosion and sediment ESCMs that have been installed, changed, or removed.

Do not rely on perimeter ESCMs as the sole method of controlling erosion. As the project progresses, install temporary erosion and sediment ESCMs within the perimeter ESCMs to control erosion resulting from the construction of the project.

Use temporary erosion and sediment ESCMs to prevent contamination of adjacent streams or other watercourses, lakes, ponds or other areas of water impoundment.

Coordinate temporary erosion and sediment ESCMs with the construction of permanent erosion and sediment ESCMs to provide continuous erosion control. Do not install temporary erosion and sediment ESCMs when permanent erosion and sediment ESCMs are able to be installed. Once the permit is terminated or transferred to the Department, the maintenance of the permanent erosion and sediment ESCMs becomes the responsibility of the NDDOT.

Install stabilization ESCMs (mulch, seeding and mulch, etc.) in areas that have been disturbed where work has temporarily or permanently ceased following the timelines established in the applicable permits. If implementation of stabilization is precluded by snow cover, undertake such measures as soon as conditions allow.

Maintain the effectiveness of the temporary erosion and sediment ESCMs as long as required to contain sediment runoff. Inspect the temporary erosion and sediment ESCMs and complete the inspection and maintenance reports every 14 days and within 24 hours of a rainfall event of 0.25 inch or more. During prolonged rainfall (more than 1 day), conduct an inspection within 24 hours of the first day of the event and within 24 hours after the end of the event. Inspections are required only during normal business hours. Install a rain gauge to monitor rainfall amounts as required by the appropriate permit.

Correct any deficiencies in the ESCMs within the timelines established in the applicable permits. If conditions do not permit access to the ESCM, corrective actions can be taken by installing additional ESCMs. Correct the original deficiencies as soon as conditions allow access to their location without causing additional damage to the slopes. In the inspection logs, document the conditions that prohibit access.

Provide copies of all inspections, documentation, record keeping, maintenance, remedial actions, and repairs required by the applicable permits to the Engineer. Provide inspection and maintenance reports within 3 working days after an inspection has been conducted.

Provide, at the preconstruction conference, documentation of any Subcontractor hired for erosion control showing that the Subcontractor's on site supervisor is certified through the NDDOT Erosion & Sediment Control Construction Certification Training. This certification must be maintained by the Subcontractor's onsite supervisor through the term of the contract. The Engineer will provide a verification of their certification through the NDDOT Erosion & Sediment Control Construction Certification Training at the preconstruction conference and will maintain that certification through the term of the contract.

Provide immediate written notification to the Engineer of proposed changes to the erosion control plan or SWPPP. The Engineer will review the proposed changes and determine if they are adequate. Documentation of maintenance and inspections that does not affect the erosion control plan or SWPPP does not require approval by the Engineer.

Remove the temporary devices when directed by the Engineer or when permanent erosion and sediment controls are installed.

3. Erosion and Sediment Control Supervisor.

A. General. Designate an erosion and sediment control supervisor. Provide the name and contact information for the supervisor at the preconstruction meeting. If this erosion and sediment control supervisor becomes unavailable on the project, designate a replacement supervisor. Notify the Engineer if this supervisor changes and provide the contact information for the new supervisor.

B. Qualifications. The supervisor shall be:

1. An employee of the Prime Contractor;
2. Familiar with installation, maintenance and removal of ESCMs and the requirements of the erosion and sediment control plans, applicable permit requirements, specifications, plans and this provision; and
3. Competent to supervise personnel in erosion and sediment control operations.
4. Certified through the NDDOT Erosion & Sediment Control Construction Certification Training and maintain that training throughout the term of the contract.

C. Duties. The supervisor shall:

1. Provide erosion and sediment control as required by the SWPPP, Plans, and Specifications.
2. Be on the site to supervise the installation, operation, inspection, maintenance, and removal of the erosion and sediment ESCMs.
3. Update the SWPPP as work progresses to show changes due to revisions in work schedules or sequence of construction, or as directed by the Engineer. Update the site map to reflect erosion and sediment ESCMs that have been installed, changed, or removed.
4. Propose changes to improve erosion and sediment control.
5. Be accessible to the job site within 24-hours.
6. Provide the Engineer with documentation of all erosion and sediment control activities and inspections as required above.

4. PERFORMANCE

Correct all areas of noncompliance within 24 hours after notification of noncompliance. If corrective actions are not taken within 24 hours, the Engineer may:

1. Assess a contract price reduction of \$500 per day per instance;
2. Have deficiencies corrected by another Contractor and deduct the cost of the work from the monies due or to become due to the Contractor;
3. Suspend all work; or
4. Withhold payment on other contract items/pay estimates.

These actions will be applied until deficiencies have been corrected.

5. BASIS OF PAYMENT

ESCM installation will be paid for at the contract unit price for erosion and sediment control for the appropriate items and sections. The plans will detail the required ESCMs for temporary and permanent installations. The same bid items may be used for temporary and permanent ESCMs.

ESCM items will be measured as specified in the "Method of Measurement" portion of the appropriate section of the specifications.

ESCM item removal will be paid for at the contract unit price for "Remove _____" in the appropriate section of the specifications.

Include the costs for labor, materials, maintenance, equipment, disposal, adherence to the permit, and SWPPP modifications in the respective pay items.

When the Engineer directs the replacement of temporary erosion and sediment ESCMs that are no longer functional because of deterioration or functional incapacity and those items were installed as specified in the Contract or as directed by the Engineer, the Department will pay for replacement ESCMs

No payment will be made for replacing temporary erosion and sediment ESCMs that the Engineer determines are ineffective because of improper installation, lack of maintenance, or the Contractor's failure to pursue timely installation of permanent erosion and sediment ESCMs as required in the Contract.

No payment will be made for replacing temporary erosion and sediment ESCMs due to contractor operations. Include the cost to move Flotation Silt Curtain as work progresses in the price bid for "Flotation Silt Curtain".

Erosion and sediment controls for Contractor Controlled Areas are the responsibility of the Contractor and will not be paid for by the Department.

Removal of sediment from silt fence and fiber rolls will be paid for at the price listed in the "Price Schedule PS-1."

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION

LIMITATIONS OF OPERATIONS

DESCRIPTION

Section 108.05, "Limitations of Operations" is no longer valid. Use this Special Provision in its place.

108.05 LIMITATION OF OPERATIONS

A. General.

Perform the work in a manner and sequence that minimizes interference to traffic, and with due regard to the location of detours and provisions for handling traffic. Do not begin work to the prejudice or detriment of work already started; the contract may require a section of roadway to be finished before starting additional sections if the opening of the section is essential to public convenience.

If the prosecution of the work is discontinued, provide the Engineer at least 24-hours notice before resuming operations.

B. Holidays.

Unless the contract allows work on holidays, perform work on holidays only with the Engineer's prior written approval. Submit a written request to the Engineer by noon 2 business days before the requested holiday.

C. Night-time Operations and Extended Hours.

1. General.

When performing work in low light conditions, implement proper safety precautions and provide adequate lighting for the performance and inspection of the work.

2. Nighttime Operations.

Unless the contract allows for nighttime operations, perform work at night only with the Engineer's prior written approval.

Submit a written request to the Engineer a minimum of 7 calendar days before anticipated nighttime operations. The Engineer may deny the request or delay approval if it would require additional staffing considerations. If nighttime operations requires the Engineer to hire additional forces, nighttime operations may not be allowed for up to 30 days from the receipt of the request.

When requesting to perform nighttime operations, include a plan to ensure the safety of all individuals on the project site, including the Contractor's and subcontractor's workers, Department representatives, and the traveling public.

The Department bears no liability for costs or delays resulting from the Engineer's approval, rejection, or delay for staffing purposes of a request to perform nighttime operations.

3. Extended Hours.

Extended hours are allowed before sunrise with verbal notice given to the Engineer the previous day. Extended hours are allowed after sunset with verbal notice given to the Engineer that same day.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION

FEDERAL PROHIBITION ON CERTAIN TECHNOLOGICAL HARDWARE

DESCRIPTION

This Special Provision details technological items that are prohibited from use on Department contracts. The contents of this SP take precedent over requirements regarding affected equipment in all other contract documents.

CONTRACT REQUIREMENTS

A. Technological Equipment Prohibitions.

Equipment, services, and systems using telecommunications equipment or services are prohibited from containing equipment produced by:

- Huawei Technologies Company;
- ZTE Corporation; and
- Any subsidiary or affiliate of the named entities.

Video surveillance and telecommunications equipment are prohibited from containing equipment produced by:

- Hytera Communications Corporation;
- Hangzhou Hikvision Digital Technology Company;
- Dahua Technology Company; and
- Any subsidiary or affiliate of the named entities.

B. Contractor Certification.

The Prime Contractor must complete the information below, sign this Special Provision, and submit the signed document to the Engineer at the preconstruction conference. This signature affirms that no prohibited products will be used in the project.

Project Number(s): _____

PCN(s): _____

Company Name: _____

Signatory Name (printed): _____

Signature: _____

Date: _____

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION

UTILITY COORDINATION

PROJECT HEU-6-081(094)940 – PCN 21884

DESCRIPTION

This work consists of coordinating the construction schedule with third party utility companies owning facilities within the project limits, verifying the location of those facilities during construction, and resolving issues with those utilities.

The requirements in this Special Provision replace the requirements of Section 105.03, "Cooperation With Utility Owners".

ATTACHMENTS

Appendix A – Utility Coordination Table

Appendix B – Utility Exhibits

DEFINITIONS

Conflict: A utility in need of relocation or adjustment for the construction to proceed in that area.

Protect in Place (PIP): A utility that does not need relocation, but needs precautions to protect the utility during construction activities.

Utility Encounter (UE): A Conflict or Protect in Place situation involving an existing third party owned utility.

CONTRACTOR RESPONSIBILITIES

A. Responsibilities.

The responsibilities for utility coordination include the following:

- Conduct the preconstruction utility coordination meeting;
- Main a point of contact for all utility companies;
- Maintain a schedule for utility activities;
- Hold weekly utility meetings in addition to the weekly planning and reporting meeting and report on the utility meetings at the weekly planning and reporting meeting;
- Follow up with any utility companies that do not show up to construction meetings;
- Coordinate work efforts of the utility companies, revise work schedules and traffic control as necessary to ensure adequate cooperation between UE and construction work;
- Develop and update the utility coordination plan;
- Provide a weekly written summary for contacts and meetings to the Engineer; and
- Coordinate with all of the other parties to update the project schedule specified in Section 108.03, "Progress Schedule".

B. Utility Coordination Plan.

Develop a utility coordination plan with each utility company that includes the phasing and scheduling requirements for UE.

C. Record of Utility Outage Notifications.

Request a copy of notifications that utility companies provide to customers for service outages. Maintain copies of all notifications until the Contractor signs the final estimate.

D. Utility Coordination Schedule.

Create and maintain a construction schedule that includes timelines for the phasing of utility coordination work. Include information contained in the contract documents and information obtained during coordination discussions with utility owners. Written agreements between the Contractor and a utility company will govern over information contained in contract documents; however, the agreements must be signed by the NDDOT, Contractor and Utility Company to be effective. Written agreements are considered contract revisions, however they are not eligible for additional compensation or additional time unless agreed to separately by the Engineer.

The Utility Coordination Table contains information related to the utility coordination requirements at each area designated as a UE. The timelines included on the Table may be longer than shown if the Contractor requests multiple resolutions simultaneously. Adjust work schedules as required to accommodate utility resolutions.

Revisions to the construction schedule due to a utility company or companies non-conformance with agreed upon schedules or failure to reasonably coordinate work efforts with the Contractor will be considered excusable, non-compensable delays as specified in Section 108.06, "Determination of and Extensions to the Contract Time".

Failure by the Contractor to reasonably coordinate schedules with a utility company or companies for UE identified in the contract, or failure to document coordination efforts will be considered non-excusable delays as specified in Section 108.06, "Determination of and Extensions to the Contract Time".

CONSTRUCTION REQUIREMENTS

A. General.

The vertical and horizontal utility locations shown in the plans are approximate. Plan locations should not be interpreted as exact for bidding or construction purposes.

Utility facilities shown on the plans, if any, are for reference purposes only and may not constitute an exhaustive representation of all utility facilities within the project. Notify the North Dakota One Call System (811) before starting the work, so they may locate and mark all utility facilities within the project. Receive utility locates for Department-owned, publicly-owned, and privately-owned utility facilities, whether on or off the One Call System.

Comply with Chapter 49-23 of the NDCC in determining the location of underground utilities.

B. Utilities Identified in Plans.

Coordinate UE work with the affected utility owners. Maintain continuous communication with the Engineer, affected subcontractors, and affected utility owners until UE will no longer affect or be affected by the Contractor.

Cooperate with utility owners in relocating and adjusting utility facilities to minimize interruption to service and duplication of work by utility owners.

The Contract documents show all known UE for the project.

If a UE identified as a Protect in Place is determined to be a Conflict during construction, the Engineer will make necessary revisions to the Contract as specified in Section 104.02, "Contract Revisions". These types of changes will be considered excusable, compensable delays as specified in Section 108.06, "Determination of and Extensions to the Contract Time".

C. Utilities Encountered During Work.

1. General

Neither of the cases discussed in this subsection relieve the Contractor of liability that may arise under provisions of the NDCC.

2. Unidentified Utility Encounters

The Department will bear costs associated with revisions to the work as specified in Section 104.02 B, "Differing Site Conditions" only if the Engineer determines that all of the following conditions exist:

- a UE exists that was not designated in the plans; and
- the UE is in a location that affects the prosecution of the work to construct the project as designed.

3. Utility Encounters Created Due to Actions Performed by the Contractor

If a new UE is created due to actions performed by the Contractor for the Contractor's convenience; the Contractor shall account for and protect the affected facilities. Before performing these actions, the Contractor shall coordinate with the utility owner. The Department will not make additional payments to the Contractor nor the utility owner for UE created in this manner and will not provide additional time to the Contractor for completing the work.

If utility companies incur costs, the Department will not participate in those costs and will not make payment to the Contractor for those costs.

D. Utility Coordination Meetings.

1. Preconstruction Utility Meeting.

Arrange the meeting with the utility owners, the Contractor and affected subcontractors, local agency representatives, and the Engineer to occur no later than two weeks after the preconstruction meeting. At the meeting, provide an agenda and a tentative construction schedule for planning UE work; after the meeting, publish minutes and distribute a copy to all meeting attendees within 48 hours of the conclusion of the meeting.

2. Weekly Utility Coordination Meeting.

Organize a weekly meeting to discuss utility coordination efforts with utility companies and affected subcontractors, local authorities, the Engineer and others who may have an

interest in utility coordination efforts. Hold the weekly utility coordination meeting immediately before the weekly planning and reporting meeting. Publish minutes and distribute copies to all meeting attendees within 48 hours of the conclusion of the meeting.

The intent of this meeting is to disseminate information regarding ongoing and upcoming UE work and to ensure that all affected parties are collaborating and sharing information related to that work.

Provide a summary of the discussion at the weekly planning and reporting meeting.

E. Fire Hydrants.

Before starting work that affects a fire hydrant, coordinate with the local fire authority to determine if provisions need to be in place before starting the work. If provisions are necessary, obtain the approval of the local fire authority before beginning the work affecting the fire hydrant.

F. Damage and Interruptions.

If the Contractor causes damage to utility facilities, the Contractor is responsible for the costs of restoring or repairing the damaged utility facility to a condition equal to or better than the condition existing before the damage occurred. Immediately notify the utility owner of the damage or, if the owner is unknown, the One Call System. Do not conceal, attempt to conceal, or make repairs to the utility facilities until approved by the utility owner. If this damage causes interruption to utility service, continuously coordinate with the utility owner until the service is fully restored.

The Department will not pay the Contractor for the cost to restore utility facilities or repair damage to utility facilities and will consider any delays resulting from this damage to be non-excusable in accordance with Section 108.06, "Determination of and Extensions to the Contract Time."

G. Utility Criteria.

The Utility Coordination Table and Utility Exhibits contain specific information related to each UE location.

APPENDIX A

Utility Coordination Table Appendix A of SP 1014(14) HEU-6-081(094)940 PCN 21884 Sorted By Station																			Not Reimbursable (NR) - Reimbursable (R)	Additional Potholing to be performed by Utility company (Information of pothole will be added to comments in table).			LOCATION OUT = outside existing NDDOT RW IN = in Existing NDDOT RW	
UE ID #	Utility Coordina tion Exhibits	Approx. Sta From		Approx. Sta To	LT/RT or Crossing or Point Location	Approx. Qty	Unit	Max Excavation Cut (-) / Fill (+) Feet	Encounter Level	Resolution Criteria / Comments (The following information for the Contractor is based on early coordination with utilities. Information is approximate. Details for the schedule and construction phasing will need to be finalized between the Contractor and Utility	Utility Company	Type of Facility	After Notification - Time For Utility to Mobilize (D = Working Day, W = Week)	Estimated Time to Complete Relocation (D = Working Day, W = Week)	UTILITY ENCOUNTER TYPE (UE)		Quantity of Pothole Utility	Pot Hole ID#						
															Protect in Place	Conflict								
																				NO	YES	If Yes, How many ?		
																							IN	OUT
CGF-1	3	2125+59	to	2125+59	Crossing	23	LF	-2.5	Level 1	Utility encounter with proposed pavement and existing pavement removal.	City of Grand Forks	Storm Drain	-	-	X		0	-	NR	X			X	
CGF-2	4	2128+43	to	2128+43	Crossing	11	LF	-2.5	Level 1	Utility encounter with proposed pavement and existing pavement removal.	City of Grand Forks	Water Line	-	-	X		0	-	NR	X			X	
XCEENE-3	4	2128+53	to	2128+86	LT	33	LF	> -10	Level 2	Utility encounter with proposed proposed conduit and existing foundation removal. Carefully excavate.	Xcel Energy	Gas Line	-	-	X		0	-	NR	X			X	
CGF-196	4	2128+61	to	2128+99	LT	56	LF	> -10	Level 2	Utility encounter with proposed conduit, sidewalk installation and existing traffic signal foundation removal. Carefully excavate.	City of Grand Forks	Interconnect	-	-	X		0	-	NR	X			X	
CENLINK-4	4	2128+65	to	2129+16	RT	62	LF	-2.0	Level 2	Utility encounter with existings pavement and pull box removal. Carefully Excavate.	Century Link	Telephone Line	-	-	X		0	-	NR	X			X	
CENLINK-5	4	2128+65	to	2128+67	Crossing	13	LF	-2.5	Level 2	Utility encounter with proposed pavement and existing pavement removal. Carefully excavate.	Century Link	Telephone Line	-	-	X		0	-	NR	X			X	
MIDCAB-6	4	2128+72	to	2128+73	RT	11	LF	-4	Level 2	Utility encounter with proposed pull box installation. Carefully excavate.	Mid-Continent Cable	TV Line	-	-	X		0	-	NR	X			X	
XCEENE-7	4	2128+72	to	2129+16	RT	44	LF	-2.5	Level 2	Utility encounter with proposed pavement and existing pavement removal. Carefully excavate.	Xcel Energy	Gas Line	-	-	X		0	-	NR	X			X	
CENLINK-8	4	2128+72	to	2129+16	RT	44	LF	-3	Level 2	Utility encounter with existing pavement removal and proposed conduit, pedestrian push button post installation. Carefully excavate.	Century Link	Fiber Optic Line	-	-	X		0	-	NR	X			X	
MIDCAB-9	4	2128+73	to	2128+74	LT	8	LF	-2.5	Level 2	Utility encounter with proposed sidewalk. Carefully excavate.	Mid-Continent Cable	TV Line	-	-	X		0	-	NR	X			X	
CENLINK-10	4	2128+74	to	2128+82	LT	23	LF	-2.5	Level 2	Utility encounter with existing pavement removal and proposed pull box installation. Carefully excavate.	Century Link	Telephone Line	-	-	X		0	-	NR	X			X	
MIDCAB-11	4	2128+76	to	2128+76	Crossing	13	LF	-2.5	Level 2	Utility encounter with proposed pavement and existing pavement removal. Carefully excavate.	Mid-Continent Cable	TV Line	-	-	X		0	-	NR	X			X	

Utility Coordination Table Appendix A of SP 1014(14) HEU-6-081(094)940 PCN 21884 Sorted By Station																			Not Reimbursable (NR) - Reimbursable (R)	Additional Potholing to be performed by Utility company (information of pothole will be added to comments in table).			LOCATION OUT = outside existing NDDOT RW IN = in Existing NDDOT RW	
UE ID #	Utility Coordina tion Exhibits	Approx. Sta From		Approx. Sta To	LT/RT or Crossing or Point Location	Approx. Qty	Unit	Max Excavation Cut (-) / Fill (+) Feet	Encounter Level	Resolution Criteria / Comments (The following information for the Contractor is based on early coordination with utilities. Information is approximate. Details for the schedule and construction phasing will need to be finalized between the Contractor and Utility	Utility Company	Type of Facility	After Notification - Time For Utility to Mobilize (D = Working Day, W = Week)	Estimated Time to Complete Relocation (D = Working Day, W = Week)	UTILITY ENCOUNTER TYPE (UE)		Quantity of Pothole Utility	Pot Hole ID#		NO	YES	If Yes, How many ?	IN	OUT
															Protect in Place	Conflict								
CGF-12	4	2128+77	to	2129+16	RT	39	LF	-2.5	Level 1	Utility encounter with existing pavement removal.	City of Grand Forks	Storm Drain	-	-	X		0	-	NR	X			X	
CENLINK-13	4	2128+79	to	2129+16	RT	37	LF	> -10	Level 4	Utility line will need to be adjusted due to proposed signal pole foundation installation. Additional Utility encounter with existing foundation removal. Give 2 weeks notice to Century Link for relocation. Coordinate and identify safe area for relocations.	Century Link	Fiber Optic Line	-	-		X	0	-	NR	X			X	
CGF-14	4	2128+93	to	2129+01	RT	10	LF	-2.5	Level 1	Utility encounter with existing pavement removal.	City of Grand Forks	Storm Drain	-	-	X		0	-	NR	X			X	
CGF-15	4	2129+01	to	2129+01	RT	9	LF	-2.5	Level 1	Utility encounter with existing pavement removal.	City of Grand Forks	Storm Drain	-	-	X		0	-	NR	X			X	
CGF-16	4	2129+04	to	2129+05	LT	5	LF	-2.5	Level 2	Utility encounter with proposed conduit installation. Carefully excavate.	City of Grand Forks	Storm Drain	-	-	X		0	-	NR	X			X	
CGF-17	4	2129+10	to	-	RT	1	EA	-2.5	Level 2	Utility encounter with existing pavement removal. Carefully excavate.	City of Grand Forks	Light Pole	-	-	X		0	-	NR	X			X	
MIDCAB-18	4	2129+12	to	2129+15	RT	3	LF	-2.5	Level 2	Utility encounter with existing pavement removal. Carefully excavate.	Mid-Continent Cable	TV Line	-	-	X		0	-	NR	X			X	
CGF-19	4	2129+65	to	2129+80	LT	15	LF	-2.5	Level 1	Utility encounter with existing pavement removal.	City of Grand Forks	Sanitary Sewer	-	-	X		0	-	NR	X			X	
CGF-197	4	2129+70	to	2129+82	LT	11	LF	-2.5	Level 2	Utility encounter with proposed pavement installation. Carefully excavate.	City of Grand Forks	Interconnect	-	-	X		0	-	NR	X			X	
CGF-20	4	2129+70	to	2129+82	LT	12	LF	-2.5	Level 1	Utility encounter with existing pavement removal.	City of Grand Forks	Water Line	-	-	X		0	-	NR	X			X	
XCEENE-21	4	2129+71	to	2130+43	LT	73	LF	-2.5	Level 2	Utility encounter with proposed conduit installation and existing pavement removal. Carefully excavate.	Xcel Energy	Gas Line	-	-	X		0	-	NR	X			X	
CENLINK-22	4	2129+85	to	2130+14	RT	39	LF	-2.5	Level 2	Utility encounter with proposed conduit and sidewalk installation. Carefully excavate.	Century Link	Fiber Optic Line	-	-	X		0	-	NR	X			X	
CENLINK-23	4	2129+86	to	2130+19	RT	33	LF	-2.5	Level 2	Utility encounter with proposed conduit and sidewalk installation. Carefully excavate.	Century Link	Telephone Line	-	-	X		0	-	NR	X			X	

Utility Coordination Table Appendix A of SP 1014(14) HEU-6-081(094)940 PCN 21884 Sorted By Station																			Not Reimbursable (NR) - Reimbursable (R)	Additional Potholing to be performed by Utility company (information of pothole will be added to comments in table).			LOCATION OUT = outside existing NDDOT RW IN = in Existing NDDOT RW	
UE ID #	Utility Coordina tion Exhibits	Approx. Sta From		Approx. Sta To	LT/RT or Crossing or Point Location	Approx. Qty	Unit	Max Excavation Cut (-) / Fill (+) Feet	Encounter Level	Resolution Criteria / Comments (The following information for the Contractor is based on early coordination with utilities. Information is approximate. Details for the schedule and construction phasing will need to be finalized between the Contractor and Utility	Utility Company	Type of Facility	After Notification - Time For Utility to Mobilize (D = Working Day, W = Week)	Estimated Time to Complete Relocation (D = Working Day, W = Week)	UTILITY ENCOUNTER TYPE (UE)		Quantity of Pothole Utility	Pot Hole ID#						
															Protect in Place	Conflict								
																				NO	YES	If Yes, How many ?		
																							IN	OUT
XCEENE-24	4	2129+88	to	2130+18	RT	30	LF	-2.5	Level 2	Utility encounter with proposed conduit installation. Carefully excavate.	Xcel Energy	Gas Line	-	-	X		0	-	NR	X			X	
CGF-25	4	2130+00	to	2130+39	RT	39	LF	> -10	Level 2	Utility encounter with proposed conduit and signal pole foundation installation. Carefully excavate.	City of Grand Forks	Storm Drain	-	-	X		0	-	NR	X			X	
CENLINK-26	4	2130+08	to	2130+14	RT	10	LF	-2.5	Level 2	Utility encounter with proposed conduit installation. Carefully excavate.	Century Link	Telephone Line	-	-	X		0	-	NR	X			X	
XCEENE-27	4	2130+13	to	2130+14	RT	13	LF	-2.5	Level 2	Utility encounter with proposed conduit installation. Carefully excavate.	Xcel Energy	Gas Line	-	-	X		0	-	NR	X			X	
CENLINK-28	4	2130+16	to	2130+19	RT	10	LF	-2.5	Level 2	Utility encounter with proposed conduit installation. Carefully excavate.	Century Link	Telephone Line	-	-	X		0	-	NR	X			X	
CGF-29	4	2133+77	to	2133+77	Crossing	23	LF	-2.5	Level 2	Utility encounter with existing pavement removal. Carefully excavate.	City of Grand Forks	Storm Drain	-	-	X		0	-	NR	X			X	
CGF-30	6	2140+22	to	2140+22	Crossing	11	LF	-2.5	Level 2	Utility encounter with existing pavement removal. Carefully excavate.	City of Grand Forks	Storm Drain	-	-	X		0	-	NR	X			X	
CGF-31	6	2141+64	to	2142+52	RT	89	LF	-2.5	Level 2	Utility encounter with proposed pavement and existing pavement removal. Carefully excavate.	City of Grand Forks	Storm Drain	-	-	X		0	-	NR	X			X	
MIDCAB-32	6	2141+64	to	2142+28	RT	71	LF	> -10	Level 2	Utility encounter with proposed pavement and existing pavement, signal foundation removal. Carefully excavate.	Mid-Continent Cable	TV Line	-	-	X		0	-	NR	X			X	
XCEENE-33	6	2141+64	to	2142+52	RT	89	LF	-2.5	Level 2	Utility encounter with proposed pavement and existing pavement removal. Carefully excavate.	Xcel Energy	Gas Line	-	-	X		0	-	NR	X			X	
CENLINK-34	6	2141+72	to	2142+52	RT	81	LF	> -10	Level 2	Utility encounter with existing pavement , and signal foundation removal. Carefully excavate.	Century Link	Fiber Optic Line	-	-	X		0	-	NR	X			X	

Utility Coordination Table Appendix A of SP 1014(14) HEU-6-081(094)940 PCN 21884 Sorted By Station																		Not Reimbursable (NR) - Reimbursable (R)	Additional Potholing to be performed by Utility company (Information of pothole will be added to comments in table).			LOCATION OUT = outside existing NDDOT RW IN = in Existing NDDOT RW		
UE ID #	Utility Coordina tion Exhibits	Approx. Sta From		Approx. Sta To	LT/RT or Crossing or Point Location	Approx. Qty	Unit	Max Excavation Cut (-) / Fill (+) Feet	Encounter Level	Resolution Criteria / Comments (The following information for the Contractor is based on early coordination with utilities. Information is approximate. Details for the schedule and construction phasing will need to be finalized between the Contractor and Utility	Utility Company	Type of Facility	After Notification - Time For Utility to Mobilize (D = Working Day, W = Week)	Estimated Time to Complete Relocation (D = Working Day, W = Week)	UTILITY ENCOUNTER TYPE (UE)		Quantity of Pothole Utility		Pot Hole ID#	NO	YES	If Yes, How many ?	IN	OUT
															Protect in Place	Conflict								
CENLINK-35	6	2141+85	to	2142+26	RT	62	LF	> -10	Level 4	Utility line will need to be adjusted due to the Fiber Optic Vault being impacted. Additional utility encounter with proposed conduit, sidewalk, and existing pavement removal. Give 2 weeks notice to Century Link for relocation. Coordinate and identify safe area for relocations.	Century Link	Fiber Optic Line	-	-		X	0	-	NR	X			X	
CENLINK-36	6	2141+87	to	2141+87	Crossing	11	LF	-2.5	Level 2	Utility encounter with proposed pavement and existing pavement removal.	Century Link	Fiber Optic Line	-	-	X		0	-	NR	X			X	
NORUEC-37	6	2142+03	to	2142+27	LT	23	LF	-1	Level 2	Utility encounter with proposed sidewalk. Carefully excavate.	Nodak Rural Electric Cooperative	Electric Line	-	-	X		0	-	NR	X			X	
CENLINK-38	6	2142+07	to	2142+07	RT	45	LF	-2.5	Level 2	Utility encounter with proposed conduit, sidewalk installation and existing pavement removal. Carefully excavate.	Century Link	Telephone Line	-	-	X		0	-	NR	X			X	
CENLINK-39	6	2142+07	to	2142+31	RT	28	LF	-1	Level 2	Utility encounter with proposed sidewalk. Carefully excavate.	Century Link	Telephone Line	-	-	X		0	-	NR	X			X	
CENLINK-40	6	2142+08	to	2142+53	RT	46	LF	-2.5	Level 2	Utility encounter with proposed sidewalk and existing pavement removal. Carefully excavate.	Century Link	Telephone Line	-	-	X		0	-	NR	X			X	
CENLINK-41	6	2142+08	to	2142+08	Crossing	12	LF	-2.5	Level 2	Utility encounter with proposed pavement and existing pavement removal. Carefully excavate.	Century Link	Telephone Line	-	-	X		0	-	NR	X			X	
MIDCAB-42	6	2142+08	to	2142+08	LT	9	LF	-2.5	Level 2	Utility encounter with proposed pavement and existing pavement removal. Carefully excavate.	Mid-Continent Cable	TV Line	-	-	X		0	-	NR	X			X	
CENLINK-43	6	2142+09	to	2142+53	RT	45	LF	-2.5	Level 2	Utility encounter with proposed pavement, sidewalk and existing pavement removal. Carefully excavate.	Century Link	Telephone Line	-	-	X		0	-	NR	X			X	
MIDCAB-44	6	2142+17	to	2142+17	LT	11	LF	-2.5	Level 2	Utility encounter with proposed pavement and existing pavement removal. Carefully excavate.	Mid-Continent Cable	Telephone Line	-	-	X		0	-	NR	X			X	

Utility Coordination Table Appendix A of SP 1014(14) HEU-6-081(094)940 PCN 21884 Sorted By Station																		Not Reimbursable (NR) - Reimbursable (R)	Additional Potholing to be performed by Utility company (information of pothole will be added to comments in table).			LOCATION OUT = outside existing NDDOT RW IN = in Existing NDDOT RW		
UE ID #	Utility Coordina tion Exhibits	Approx. Sta From		Approx. Sta To	LT/RT or Crossing or Point Location	Approx. Qty	Unit	Max Excavation Cut (-) / Fill (+) Feet	Encounter Level	Resolution Criteria / Comments (The following information for the Contractor is based on early coordination with utilities. Information is approximate. Details for the schedule and construction phasing will need to be finalized between the Contractor and Utility	Utility Company	Type of Facility	After Notification - Time For Utility to Mobilize (D = Working Day, W = Week)	Estimated Time to Complete Relocation (D = Working Day, W = Week)	UTILITY ENCOUNTER TYPE (UE)		Quantity of Pothole Utility		Pot Hole ID#					
															Protect in Place	Conflict								
																				NO	YES	If Yes, How many ?		
																						IN	OUT	
CENLINK-45	6	2142+18	to	2142+35	LT	17	LF	-4	Level 2	Utility encounter with proposed sidewalk and existing pull box removal. Carefully excavate.	Century Link	Telephone Line	-	-	X		0	-	NR	X			X	
MIDCAB-46	6	2142+19	to	2142+27	RT	42	LF	-2.5	Level 2	Utility encounter with proposed pavement, sidewalk and existing pavement removal. Carefully excavate.	Mid-Continent Cable	TV Line	-	-	X		0	-	NR	X			X	
MIDCAB-47	6	2142+19	to	2142+52	RT	33	LF	-1	Level 2	Utility encounter with proposed sidewalk. Carefully excavate.	Mid-Continent Cable	TV Line	-	-	X		0	-	NR	X			X	
NORUEC-48	6	2142+21	to	2142+28	RT	34	LF	-1	Level 2	Utility encounter with proposed sidewalk. Carefully excavate.	Nodak Rural Electric Cooperative	Electric Line	-	-	X		0	-	NR	X			X	
CENLINK-49	6	2142+22	to	2142+33	LT	12.0	LF	-1	Level 2	Utility encounter with propopsed sidewalk. Carefully excavate.	Century Link	Telephone Line	-	-	X		0	-	NR	X			X	
CENLINK-50	6	2142+25	to	2142+27	RT	7	LF	> -10	Level 4	Utility line will need to be adjusted due to the Fiber Optic Vault being impacted. Additional utility encounter with existing pavement and signal foundation removal. Give 2 weeks notice to Century Link for relocation. Coordinate and identify safe area for relocations.	Century Link	Fiber Optic Line	-	-		X	0	-	NR	X			X	
XCEENE-51	6	2142+26	to	2142+29	RT	73	LF	> -10	Level 2	Utility encounter with propsed pavement, sidewalk, and existing pavement , signal foundation removal. Carefully excavate.	Xcel Energy	Gas Line	-	-	X		0	-	NR	X			X	
CENLINK-52	6	2142+28	to	-	RT	1	EA	-2.5	Level 4	Utility line will need to be adjusted due to proposed sidewalk.	Century Link	Fiber Optic Ped	-	-		X	0	-	NR	X			X	
CENLINK-53	6	2142+28	to	2142+28	RT	51	LF	-1	Level 4	Utility line will need to be adjusted due to the Fiber Optic Vault being impacted. Additional utility encounter with proposed sidewalk. Give 2 weeks notice to Century Link for relocation. Coordinate and identify safe area for relocations.	Century Link	Fiber Optic Line	-	-		X	0	-	NR	X			X	

Utility Coordination Table Appendix A of SP 1014(14) HEU-6-081(094)940 PCN 21884 Sorted By Station																			Not Reimbursable (NR) - Reimbursable (R)	Additional Potholing to be performed by Utility company (Information of pothole will be added to comments in table).			LOCATION OUT = outside existing NDDOT RW IN = in Existing NDDOT RW	
UE ID #	Utility Coordina tion Exhibits	Approx. Sta From		Approx. Sta To	LT/RT or Crossing or Point Location	Approx. Qty	Unit	Max Excavation Cut (-) / Fill (+) Feet	Encounter Level	Resolution Criteria / Comments (The following information for the Contractor is based on early coordination with utilities. Information is approximate. Details for the schedule and construction phasing will need to be finalized between the Contractor and Utility	Utility Company	Type of Facility	After Notification - Time For Utility to Mobilize (D = Working Day, W = Week)	Estimated Time to Complete Relocation (D = Working Day, W = Week)	UTILITY ENCOUNTER TYPE (UE)		Quantity of Pothole Utility	Pot Hole ID#						
															Protect in Place	Conflict								
																				NO	YES	If Yes, How many ?		
																							IN	OUT
CENLINK-54	6	2142+29	to	-	RT	1	EA	> -10	Level 4	Utility line will need to be adjusted due to existing pavement removal. Additional utility encounter with existing signal foundation removal. Give 2 weeks notice to Century Link for relocation. Coordinate and identify safe area for relocations.	Century Link	Fiber Optic Vault	-	-		X	0	-	NR	X			X	
MIDCAB-55	6	2142+29	to	2142+29	RT	57	LF	-1	Level 2	Utility encounter with proposed sidewalk. Carefully excavate.	Mid-Continent Cable	TV Line	-	-	X		0	-	NR	X			X	
CGF-56	6	2142+31	to	2142+33	LT	16	LF	-1	Level 1	Utility encounter with proposed sidewalk.	City of Grand Forks	Sanitary Sewer	-	-	X		0	-	NR	X			X	
CGF-198	6	2142+33	to	2142+50	LT	18	LF	-4	Level 2	Utility encounter with proposed pull box and conduit installation. Carefully excavate.	City of Grand Forks	Interconnect	-	-	X		0	-	NR	X			X	
CGF-57	6	2142+34	to	2142+53	RT	19	LF	-2.5	Level 1	Utility encounter with proposed pavement and existing pavement removal.	City of Grand Forks	Sanitary Sewer	-	-	X		0	-	NR	X			X	
DACANE-58	6	2142+36	to	2142+55	LT	19	LF	-2.5	Level 2	Utility encounter with proposed conduit installation. Carefully excavate.	Dakota Carrier Network	Telephone Line	-	-	X		0	-	NR	X			X	
CGF-59	6	2142+38	to	2142+41	LT	25	LF	-3	Level 1	Utility encounter with proposed conduit and pedestrian push button installation.	City of Grand Forks	Sanitary Sewer	-	-	X		0	-	NR	X			X	
XCEENE-60	6	2142+40	to	2142+64	LT	24	LF	-3	Level 2	Utility encounter with proposed conduit and pedestrian push button installation. Carefully excavate.	Xcel Energy	Gas Line	-	-	X		0	-	NR	X			X	
CGF-61	6	2142+41	to	-	LT	1	EA	-2.5	Level 2	Utility encounter with proposed conduit installation. Carefully excavate.	City of Grand Forks	Sanitary Manhole	-	-	X		0	-	NR	X			X	
CGF-62	6	2142+41	to	2142+41	Crossing	12	LF	-2.5	Level 1	Utility encounter with proposed pavement and existing pavement removal. Carefully excavate.	City of Grand Forks	Sanitary Sewer	-	-	X		0	-	NR	X			X	
CGF-63	6	2142+42	to	2142+43	RT	31	LF	-2.5	Level 1	Utility encounter with proposed pavement and existing pavement removal. Carefully excavate.	City of Grand Forks	Sanitary Sewer	-	-	X		0	-	NR	X			X	
CGF-64	6	2142+43	to	2142+51	RT	150	LF	-2.5	Level 1	Utility encounter with proposed pavement and existing pavement removal. Carefully excavate.	City of Grand Forks	Water Line	-	-	X		0	-	NR	X			X	

Utility Coordination Table Appendix A of SP 1014(14) HEU-6-081(094)940 PCN 21884 Sorted By Station																			Not Reimbursable (NR) - Reimbursable (R)	Additional Potholing to be performed by Utility company (information of pothole will be added to comments in table).			LOCATION OUT = outside existing NDDOT RW IN = in Existing NDDOT RW	
UE ID #	Utility Coordina tion Exhibits	Approx. Sta From		Approx. Sta To	LT/RT or Crossing or Point Location	Approx. Qty	Unit	Max Excavation Cut (-) / Fill (+) Feet	Encounter Level	Resolution Criteria / Comments (The following information for the Contractor is based on early coordination with utilities. Information is approximate. Details for the schedule and construction phasing will need to be finalized between the Contractor and Utility	Utility Company	Type of Facility	After Notification - Time For Utility to Mobilize (D = Working Day, W = Week)	Estimated Time to Complete Relocation (D = Working Day, W = Week)	UTILITY ENCOUNTER TYPE (UE)		Quantity of Pothole Utility	Pot Hole ID#						
															Protect in Place	Conflict								
																				NO	YES	If Yes, How many ?		
																							IN	OUT
CGF-65	6	2142+46	to	2142+47	LT	15	LF	-3	Level 1	Utility encounter with proposed conduit and pedestrian push button installation. Carefully excavate.	City of Grand Forks	Water Line	-	-	X		0	-	NR	X			X	
CGF-199	6	2142+92	to	2143+71	LT	78	LF	-3	Level 2	Utility encounter with proposed pavement and conduit installation. Carefully excavate. Portions of the line is going to be adjusted due to the Pull Box being relocated as part of the plans.	City of Grand Forks	Interconnect	-	-	X		0	-	NR	X			X	
DACANE-66	6	2142+93	to	2143+71	LT	78	LF	-2.5	Level 2	Utility encounter with proposed conduit, pavement installation and existing pavement removal. Carefully excavate.	Dakota Carrier Network	Telephone Line	-	-	X		0	-	NR	X			X	
XCEENE-67	6	2142+93	to	2143+57	LT	64	LF	-2.5	Level 2	Utility encounter with proposed conduit, pavement installation and existing pavement removal. Carefully excavate.	Xcel Energy	Gas Line	-	-	X		0	-	NR	X			X	
NORUEC-68	6	2142+93	to	2143+43	LT	54	LF	> -10	Level 2	Utility encounter with proposed conduit installation and existing signal cabinet foundation, pavement, signal foundation removal. Carefully excavate.	Nodak Rural Electric Cooperative	Electric Line	-	-	X		0	-	NR	X			X	
CGF-69	6	2142+93	to	2143+10	LT	17	LF	-2.5	Level 1	Utility encounter with proposed pavement and existing pavement removal. Carefully excavate.	City of Grand Forks	Water Line	-	-	X		0	-	NR	X			X	
CENLINK-70	6	2142+93	to	2143+10	LT	17	LF	-2.5	Level 2	Utility encounter with proposed pavement and existing pavement removal. Carefully excavate.	Century Link	Telephone Line	-	-	X		0	-	NR	X			X	
XCEENE-71	6	2143+06	to	2143+09	LT	45	LF	> -10	Level 2	Utility encounter with proposed pavement, conduit installation, existing pavement, signal foundation removal. Carefully excavate.	Xcel Energy	Gas Line	-	-	X		0	-	NR	X			X	
XCEENE-72	6	2143+09	to	2143+36	RT	27	LF	-2.5	Level 2	Utility encounter with proposed conduit installation. Carefully excavate.	Xcel Energy	Gas Line	-	-	X		0	-	NR	X			X	

Utility Coordination Table Appendix A of SP 1014(14) HEU-6-081(094)940 PCN 21884 Sorted By Station																			Not Reimbursable (NR) - Reimbursable (R)	Additional Potholing to be performed by Utility company (Information of pothole will be added to comments in table).			LOCATION OUT = outside existing NDDOT RW IN = in Existing NDDOT RW	
UE ID #	Utility Coordina tion Exhibits	Approx. Sta From		Approx. Sta To	LT/RT or Crossing or Point Location	Approx. Qty	Unit	Max Excavation Cut (-) / Fill (+) Feet	Encounter Level	Resolution Criteria / Comments (The following information for the Contractor is based on early coordination with utilities. Information is approximate. Details for the schedule and construction phasing will need to be finalized between the Contractor and Utility	Utility Company	Type of Facility	After Notification - Time For Utility to Mobilize (D = Working Day, W = Week)	Estimated Time to Complete Relocation (D = Working Day, W = Week)	UTILITY ENCOUNTER TYPE (UE)		Quantity of Pothole Utility	Pot Hole ID#						
															Protect in Place	Conflict								
																				NO	YES	If Yes, How many ?		
IN	OUT																							
CGF-73	6	2143+16	to	2143+61	RT	45	LF	> -10	Level 2	Utility encounter with proposed conduit, signal pole foundation installation, and existing signal pole foundation removal. Carefully excavate.	City of Grand Forks	Storm Drain	-	-	X		0	-	NR	X			X	
CGF-74	6	2143+13	to	2143+13	RT	10	LF	-4	Level 1	Utility encounter with proposed conduit and pull box installation.	City of Grand Forks	Sanitary Sewer	-	-	X		0	-	NR	X			X	
CGF-75	6	2143+13	to	-	RT	1	EA	-2.5	Level 2	Utility encounter with proposed conduit installation. Carefully excavate.	City of Grand Forks	Sanitary Manhole	-	-	X		0	-	NR	X			X	
CGF-76	6	2143+13	to	2143+23	RT	10	LF	-2.5	Level 1	Utility encounter with proposed conduit installation.	City of Grand Forks	Sanitary Sewer	-	-	X		0	-	NR	X			X	
XCEENE-77	6	2143+28	to	2143+28	RT	5	LF	-2.5	Level 2	Utility encounter with proposed conduit installation. Carefully excavate.	Xcel Energy	Gas Line	-	-	X		0	-	NR	X			X	
XCEENE-78	6	2143+44	to	2143+59	LT	11	LF	-4	Level 4	Utility line will need to be adjusted due to pull box installation. Additional utility encounter with proposed conduit installation. Give 2 weeks' notice to Xcel Energy for adjustment/relocation. Coordinate and identify safe area for relocations.	Xcel Energy	Electric Line	-	-		X	0	-	R	X			X	
CGF-79	6	2145+72	to	2145+72	Crossing	23	LF	-2.5	Level 2	Utility encounter with proposed pavement and existing pavement removal. Carefully excavate.	City of Grand Forks	Storm Drain	-	-	X		0	-	NR	X			X	
CGF-80	8	2152+21	to	2152+21	Crossing	11	LF	-2.5	Level 2	Utility encounter with proposed pavement and existing pavement removal. Carefully excavate.	City of Grand Forks	Storm Drain	-	-	X		0	-	NR	X			X	
CGF-81	8	2152+41	to	2153+03	RT	62	LF	-3	Level 1	Utility encounter with proposed pavement and conduit installation.	City of Grand Forks	Sanitary Sewer	-	-	X		0	-	NR	X			X	
CGF-82	8	2152+48	to	2152+49	Crossing	12	LF	-2.5	Level 2	Utility encounter with proposed pavement and existing pavement removal. Carefully excavate.	City of Grand Forks	Storm Drain	-	-	X		0	-	NR	X			X	
CGF-83	8	2152+49	to	2153+03	RT	54	LF	-4	Level 2	Utility encounter with proposed pavement, conduit installation and existing pavement, pull box removal. Carefully excavate.	City of Grand Forks	Storm Drain	-	-	X		0	-	NR	X			X	

Utility Coordination Table Appendix A of SP 1014(14) HEU-6-081(094)940 PCN 21884 Sorted By Station																		Not Reimbursable (NR) - Reimbursable (R)	Additional Potholing to be performed by Utility company (Information of pothole will be added to comments in table).			LOCATION OUT = outside existing NDDOT RW IN = in Existing NDDOT RW		
UE ID #	Utility Coordina tion Exhibits	Approx. Sta From		Approx. Sta To	LT/RT or Crossing or Point Location	Approx. Qty	Unit	Max Excavation Cut (-) / Fill (+) Feet	Encounter Level	Resolution Criteria / Comments (The following information for the Contractor is based on early coordination with utilities. Information is approximate. Details for the schedule and construction phasing will need to be finalized between the Contractor and Utility	Utility Company	Type of Facility	After Notification - Time For Utility to Mobilize (D = Working Day, W = Week)	Estimated Time to Complete Relocation (D = Working Day, W = Week)	UTILITY ENCOUNTER TYPE (UE)		Quantity of Pothole Utility		Pot Hole ID#	NO	YES	If Yes, How many ?	IN	OUT
															Protect in Place	Conflict								
MIDCAB-84	8	2152+49	to	2153+03	RT	72	LF	-2.5	Level 2	Utility encounter with proposed pavement, sidewalk, conduit installation and existing pavement removal. Carefully excavate.	Mid-Continent Cable	Telephone Line	-	-	X		0	-	NR	X			X	
CGF-85	8	2152+55	to	2152+70	LT	15	LF	-1	Level 1	Utility encounter with existing signal cabinet foundation removal and proposed foundation installation.	City of Grand Forks	Water Line	-	-	X		0	-	NR	X			X	
XCEENE-209	8	2152+56	to	-	LT	1	EA	0	Level 4	This supplies power to the signal cabinet, but is outside the current RW. A new pedestal will have to be installed within the existing RW by Xcel Energy. Give Xcel Energy 1 month notice to install a new electrical pedestal to provide power to the signal system. Give notice for installation between April 15th and September 1st. Coordinate and identify safe area for adjustments.	Xcel Energy	Electric Vault	-	-		X	0	-	R	X			X	
CGF-86	8	2152+56	to	2152+74	LT	18	LF	-2.5	Level 2	Utility encounter with proposed conduit installation. Carefully excavate.	City of Grand Forks	Electric Line	-	-	X		0	-	NR	X			X	
CGF-200	8	2152+56	to	2152+74	LT	19	LF	> -10	Level 2	Utility encounter with proposed traffic signal foundation, conduit, and sidewalk installation. Carefully excavate.	City of Grand Forks	Interconnect	-	-	X		0	-	NR	X			X	
DACANE-87	8	2152+57	to	2152+75	LT	18	LF	-2.5	Level 2	Utility encounter with proposed conduit installation. Carefully excavate.	Dakota Carrier Network	Fiber Optic Line	-	-	X		0	-	NR	X			X	
XCEENE-88	8	2152+57	to	2152+75	LT	18	LF	-2.5	Level 2	Utility encounter with proposed conduit installation. Carefully excavate.	Xcel Energy	Gas Line	-	-	X		0	-	NR	X			X	
CGF-89	8	2152+59	to	2152+60	LT	8	LF	-1	Level 2	Utility encounter with proposed sidewalk. Carefully excavate.	City of Grand Forks	Electric Line	-	-	X		0	-	NR	X			X	
CENLINK-90	8	2152+72	to	2153+03	RT	31	LF	-2.5	Level 2	Utility encounter with proposed pavement, conduit installation and existing pavement removal. Carefully excavate.	Century Link	Telephone Line	-	-	X		0	-	NR	X			X	

Utility Coordination Table Appendix A of SP 1014(14) HEU-6-081(094)940 PCN 21884 Sorted By Station																		Not Reimbursable (NR) - Reimbursable (R)	Additional Potholing to be performed by Utility company (information of pothole will be added to comments in table).			LOCATION OUT = outside existing NDDOT RW IN = in Existing NDDOT RW		
UE ID #	Utility Coordina tion Exhibits	Approx. Sta From		Approx. Sta To	LT/RT or Crossing or Point Location	Approx. Qty	Unit	Max Excavation Cut (-) / Fill (+) Feet	Encounter Level	Resolution Criteria / Comments (The following information for the Contractor is based on early coordination with utilities. Information is approximate. Details for the schedule and construction phasing will need to be finalized between the Contractor and Utility	Utility Company	Type of Facility	After Notification - Time For Utility to Mobilize (D = Working Day, W = Week)	Estimated Time to Complete Relocation (D = Working Day, W = Week)	UTILITY ENCOUNTER TYPE (UE)		Quantity of Pothole Utility		Pot Hole ID#					
															Protect in Place	Conflict								
																				NO	YES	If Yes, How many ?		
																						IN	OUT	
CENLINK-91	8	2152+73	to	2153+03	RT	30	LF	-2.5	Level 2	Utility encounter with proposed pavement, conduit installation and existing pavement removal. Carefully excavate.	Century Link	Telephone Line	-	-	X		0	-	NR	X			X	
CENLINK-92	8	2152+75	to	2153+03	RT	28	LF	-2.5	Level 2	Utility encounter with proposed pavement, conduit installation and existing pavement removal. Carefully excavate.	Century Link	Telephone Line	-	-	X		0	-	NR	X			X	
CGF-93	8	2152+76	to	2153+03	RT	27	LF	-2.5	Level 1	Utility encounter with proposed sidewalk, pavement, and existing pavement removal. Carefully excavate.	City of Grand Forks	Water Line	-	-	X		0	-	NR	X			X	
CGF-94	8	2152+90	to	2152+90	RT	28	LF	-2.5	Level 1	Utility encounter with proposed pavement and existing pavement removal. Carefully excavate.	City of Grand Forks	Sanitary Sewer	-	-	X		0	-	NR	X			X	
CGF-201	8	2153+47	to	2154+16	LT	69	LF	-3	Level 2	Utility encounter with proposed pavement, pedestrian push button, and conduit installation. Carefully excavate.	City of Grand Forks	Interconnect	-	-	X		0	-	NR	X			X	
DACANE-95	8	2153+47	to	2154+16	LT	69	LF	-2.5	Level 2	Utility encounter with proposed pavement, conduit installation and existing pavement removal. Carefully excavate.	Dakota Carrier Network	Fiber Optic Line	-	-	X		0	-	NR	X			X	
XCEENE-96	8	2153+47	to	2154+16	LT	69	LF	-2.5	Level 2	Utility encounter with proposed pavement, conduit installation and existing pavement removal. Carefully excavate.	Xcel Energy	Gas Line	-	-	X		0	-	NR	X			X	
CGF-97	8	2153+47	to	2154+16	LT	70	LF	-3	Level 2	Utility encounter with proposed pavement, conduit, pedestrian push button installation and existing pavement removal. Carefully excavate.	City of Grand Forks	Electric Line	-	-	X		0	-	NR	X			X	
CGF-98	8	2153+47	to	2154+16	LT	69	LF	> -10	Level 2	Utility encounter with proposed conduit, pull box installation, and existing signal foundation removal. Carefully excavate.	City of Grand Forks	Electric Line	-	-	X		0	-	NR	X			X	
CGF-99	8	2153+47	to	2153+74	LT	27	LF	-2.5	Level 1	Utility encounter with proposed pavement and existing pavement removal. Carefully excavate.	City of Grand Forks	Water Line	-	-	X		0	-	NR	X			X	

Utility Coordination Table Appendix A of SP 1014(14) HEU-6-081(094)940 PCN 21884 Sorted By Station																		Not Reimbursable (NR) - Reimbursable (R)	Additional Potholing to be performed by Utility company (Information of pothole will be added to comments in table).			LOCATION OUT = outside existing NDDOT RW IN = in Existing NDDOT RW		
UE ID #	Utility Coordina tion Exhibits	Approx. Sta From		Approx. Sta To	LT/RT or Crossing or Point Location	Approx. Qty	Unit	Max Excavation Cut (-) / Fill (+) Feet	Encounter Level	Resolution Criteria / Comments (The following information for the Contractor is based on early coordination with utilities. Information is approximate. Details for the schedule and construction phasing will need to be finalized between the Contractor and Utility	Utility Company	Type of Facility	After Notification - Time For Utility to Mobilize (D = Working Day, W = Week)	Estimated Time to Complete Relocation (D = Working Day, W = Week)	UTILITY ENCOUNTER TYPE (UE)		Quantity of Pothole Utility		Pot Hole ID#					
															Protect in Place	Conflict								
																				NO	YES	If Yes, How many ?		
																						IN	OUT	
CGF-100	8	2153+58	to	2154+10	RT	52	LF	-4	Level 2	Utility encounter with proposed conduit and pull box installation. Carefully excavate.	City of Grand Forks	Storm Drain	-	-	X		0	-	NR	X			X	
CGF-101	8	2153+62	to	2153+64	RT	24	LF	-3	Level 2	Utility encounter with proposed sidewalk and pedestrian push button installation. Carefully excavate.	City of Grand Forks	Storm Drain	-	-	X		0	-	NR	X			X	
CGF-102	8	2153+64	to	2154+07	RT	43	LF	> -10	Level 2	Utility encounter proposed sidewalk, pedestrian signal foundation, signal foundation, and conduit, installation. Carefully excavate.	City of Grand Forks	Storm Drain	-	-	X		0	-	NR	X			X	
CGF-103	8	2153+86	to	2153+96	RT	10	LF	> -10	Level 2	Utility encounter proposed signal foundation installation. Carefully excavate.	City of Grand Forks	Sanitary Sewer	-	-	X		0	-	NR	X			X	
XCEENE-104	8	2153+95	to	2153+95	LT	15	LF	-3	Level 2	Utility encounter with proposed pavement, conduit installation, and existing pavement removal. Carefully excavate.	Xcel Energy	Gas Line	-	-	X		0	-	NR	X			X	
XCEENE-105	8	2153+97	to	2153+98	RT	20	LF	-2.5	Level 2	Utility encounter with proposed conduit and sidewalk installation. Carefully excavate.	Xcel Energy	Gas Line	-	-	X		0	-	NR	X			X	
XCEENE-106	8	2153+97	to	2153+97	Crossing	13	LF	-2.5	Level 2	Utility encounter with proposed pavement and existing pavement removal. Carefully excavate.	Xcel Energy	Gas Line	-	-	X		0	-	NR	X			X	
CGF-107	8	2154+12	to	2154+12	Crossing	11	LF	-2.5	Level 1	Utility encounter with proposed pavement and existing pavement removal. Carefully excavate.	City of Grand Forks	Water Line	-	-	X		0	-	NR	X			X	
CGF-108	9	2158+20	to	2158+20	Crossing	25	LF	-4	Level 2	Utility encounter with proposed pavement and existing pavement removal. Carefully excavate.	City of Grand Forks	Storm Drain	-	-	X		0	-	NR	X			X	
CGF-202	10	2167+98	to	2168+13	LT	15	LF	-3	Level 2	Utility encounter with proposed conduit installation. Carefully excavate.	City of Grand Forks	Interconnect	-	-	X		0	-	NR	X			X	
CENLINK-109	10	2168+00	to	2168+02	RT	13	LF	-2.5	Level 2	Utility encounter with proposed signal cabinet foundation, conduit installation, and existing signal cabinet foundation removal. Carefully excavate.	Century Link	Telephone Line	-	-	X		0	-	NR	X			X	

Utility Coordination Table Appendix A of SP 1014(14) HEU-6-081(094)940 PCN 21884 Sorted By Station																			Not Reimbursable (NR) - Reimbursable (R)	Additional Potholing to be performed by Utility company (Information of pothole will be added to comments in table).			LOCATION OUT = outside existing NDDOT RW IN = in Existing NDDOT RW	
UE ID #	Utility Coordina tion Exhibits	Approx. Sta From		Approx. Sta To	LT/RT or Crossing or Point Location	Approx. Qty	Unit	Max Excavation Cut (-) / Fill (+) Feet	Encounter Level	Resolution Criteria / Comments (The following information for the Contractor is based on early coordination with utilities. Information is approximate. Details for the schedule and construction phasing will need to be finalized between the Contractor and Utility	Utility Company	Type of Facility	After Notification - Time For Utility to Mobilize (D = Working Day, W = Week)	Estimated Time to Complete Relocation (D = Working Day, W = Week)	UTILITY ENCOUNTER TYPE (UE)		Quantity of Pothole Utility	Pot Hole ID#						
															Protect in Place	Conflict								
																				NO	YES	If Yes, How many ?		
																		IN	OUT					
CENLINK-110	10	2168+00	to	-	RT	1	EA	-2.5	Level 2	Utility encounter with proposed foundation, conduit installation, and existing signal cabinet foundation removal. Carefully excavate.	Century Link	Telephone Ped	-	-	X		0	-	NR	X			X	
XCEENE-111	10	2168+04	to	2168+53	LT	49	LF	-2.5	Level 2	Utility encounter with proposed sidewalk, conduit and pedetrian push button installation. Carefully excavate.	Xcel Energy	Gas Line	-	-	X		0	-	NR	X			X	
DACANE-112	10	2168+05	to	2168+27	LT	24	LF	> -10	Level 2	Utility encounter with proposed sidewalk, conduit, and signal pole foundation installation. Carefully excavate.	Dakota Carrier Network	Fiber Optic Line	-	-	X		0	-	NR	X			X	
CGF-113	10	2168+10	to	2168+67	RT	57	LF	-4	Level 2	Utility encounter with proposed pavement, sidewalk, pedestrian signal foundation, conduit installation, and existing pavement removal. Carefully excavate.	City of Grand Forks	Storm Drain	-	-	X		0	-	NR	X			X	
CENLINK-114	10	2168+12	to	2168+67	RT	56	LF	-1	Level 2	Utility encounter with existing pavement and sidewalk removal. Carefully excavate.	Century Link	Telephone Line	-	-	X		0	-	NR	X			X	
CGF-203	10	2168+19	to	2168+19	Crossing	11	LF	-3.5	Level 2	Utility encounter with proposed pavement installation. Carefully excavate.	City of Grand Forks	Interconnect	-	-	X		0	-	NR	X			X	
XCEENE-115	10	2168+20	to	2168+20	LT	10	LF	-2.5	Level 2	Utility encounter with proposed conduit installation. Carefully excavate.	Xcel Energy	Gas Line	-	-	X		0	-	NR	X			X	
CGF-204	10	2168+20	to	2170+00	RT	208	LF	> -10	Level 2	Utility encounter with proposed traffic signal foundation, pedestrian signal foundation, pavement, and conduit installation. Carefully excavate. Portions of the line is going to be adjusted due to the Pull Box being relocated as part of the plans.	City of Grand Forks	Interconnect	-	-	X		0	-	NR	X			X	
CGF-116	10	2168+25	to	2168+35	LT	10	LF	-2.5	Level 1	Utility encounter with proposed conduit installation. Carefully excavate.	City of Grand Forks	Water Line	-	-	X		0	-	NR	X			X	
DACANE-117	10	2168+29	to	2168+30	LT	32	LF	-4	Level 2	Utility encounter with proposed conduit and pedestrian signal foundation installation. Carefully excavate.	Dakota Carrier Network	Fiber Optic Line	-	-	X		0	-	NR	X			X	

Utility Coordination Table Appendix A of SP 1014(14) HEU-6-081(094)940 PCN 21884 Sorted By Station																		Not Reimbursable (NR) - Reimbursable (R)	Additional Potholing to be performed by Utility company (Information of pothole will be added to comments in table).			LOCATION OUT = outside existing NDDOT RW IN = in Existing NDDOT RW		
UE ID #	Utility Coordina tion Exhibits	Approx. Sta From		Approx. Sta To	LT/RT or Crossing or Point Location	Approx. Qty	Unit	Max Excavation Cut (-) / Fill (+) Feet	Encounter Level	Resolution Criteria / Comments (The following information for the Contractor is based on early coordination with utilities. Information is approximate. Details for the schedule and construction phasing will need to be finalized between the Contractor and Utility	Utility Company	Type of Facility	After Notification - Time For Utility to Mobilize (D = Working Day, W = Week)	Estimated Time to Complete Relocation (D = Working Day, W = Week)	UTILITY ENCOUNTER TYPE (UE)		Quantity of Pothole Utility		Pot Hole ID#	NO	YES	If Yes, How many ?	IN	OUT
															Protect in Place	Conflict								
DACANE-118	10	2168+30	to	2168+51	LT	21	LF	-4	Level 2	Utility encounter with proposed pedestrian signal foundation installation. Carefully excavate.	Dakota Carrier Network	Fiber Optic Line	-	-	X		0	-	NR	X			X	
CGF-119	10	2168+31	to	2168+33	RT	44	LF	-4	Level 2	Utility encounter with proposed pavement, sidewalk, pedestrian push button, conduit installation, and existing pavement removal. Carefully excavate.	City of Grand Forks	Storm Drain	-	-	X		0	-	NR	X			X	
DACANE-120	10	2168+31	to	2168+31	Crossing	11	LF	-4	Level 2	Utility encounter with proposed pavement and existing pavement removal. Carefully excavate.	Dakota Carrier Network	Fiber Optic Line	-	-	X		0	-	NR	X			X	
CENLINK-121	10	2168+31	to	2168+67	RT	36	LF	-1	Level 2	Utility encounter with existing pavement and sidewalk removal. Carefully excavate.	Century Link	Telephone Line	-	-	X		0	-	NR	X			X	
CENLINK-122	10	2168+32	to	2168+60	RT	42	LF	-1	Level 2	Utility encounter with existing sidewalk removal. Carefully excavate.	Century Link	Telephone Line	-	-	X		0	-	NR	X			X	
CGF-123	10	2168+34	to	2168+34	Crossing	11	LF	-4	Level 2	Utility encounter with proposed pavement and existing pavement removal. Carefully excavate.	City of Grand Forks	Storm Drain	-	-	X		0	-	NR	X			X	
CGF-124	10	2168+34	to	2168+44	RT	61	LF	> -10	Level 2	Utility encounter with proposed pavement, sidewalk, signal foundation, and existing pavement removal. Carefully excavate.	City of Grand Forks	Water Line	-	-	X		0	-	NR	X			X	
CGF-125	10	2168+34	to	2168+35	LT	51	LF	-4	Level 2	Utility encounter with proposed conduit and pedestrian signal foundation installation. Carefully excavate.	City of Grand Forks	Storm Drain	-	-	X		0	-	NR	X			X	
CENLINK-126	10	2168+37	to	2168+68	RT	31	LF	-1	Level 2	Utility encounter with existing sidewalk removal. Carefully excavate.	Century Link	Telephone Line	-	-	X		0	-	NR	X			X	
MINPOW-195	10	2168+56	to	2168+57	RT	10	LF	0	Level 1	Utility encounter with proposed signal pole.	Minnkota Power	Overhead Utility	-	-	X		0	-	NR	X			X	
CGF-127	10	2168+94	to	2169+17	RT	23	LF	-4	Level 2	Utility encounter with proposed pavement and existing pavement removal. Carefully excavate.	City of Grand Forks	Storm Drain	-	-	X		0	-	NR	X			X	
CENLINK-128	10	2168+94	to	2169+17	RT	23	LF	-4	Level 2	Utility encounter with proposed pavement and existing pavement removal. Carefully excavate.	Century Link	Telephone Line	-	-	X		0	-	NR	X			X	

Utility Coordination Table Appendix A of SP 1014(14) HEU-6-081(094)940 PCN 21884 Sorted By Station																		Not Reimbursable (NR) - Reimbursable (R)	Additional Potholing to be performed by Utility company (Information of pothole will be added to comments in table).			LOCATION OUT = outside existing NDDOT RW IN = in Existing NDDOT RW		
UE ID #	Utility Coordina tion Exhibits	Approx. Sta From		Approx. Sta To	LT/RT or Crossing or Point Location	Approx. Qty	Unit	Max Excavation Cut (-) / Fill (+) Feet	Encounter Level	Resolution Criteria / Comments (The following information for the Contractor is based on early coordination with utilities. Information is approximate. Details for the schedule and construction phasing will need to be finalized between the Contractor and Utility	Utility Company	Type of Facility	After Notification - Time For Utility to Mobilize (D = Working Day, W = Week)	Estimated Time to Complete Relocation (D = Working Day, W = Week)	UTILITY ENCOUNTER TYPE (UE)		Quantity of Pothole Utility		Pot Hole ID#					
															Protect in Place	Conflict								
																				NO	YES	If Yes, How many ?		
																						IN	OUT	
CENLINK-129	10	2168+94	to	2169+18	RT	23	LF	-4	Level 2	Utility encounter with proposed pavement and existing pavement removal. Carefully excavate.	Century Link	Telephone Line	-	-	X		0	-	NR	X			X	
CENLINK-130	10	2168+95	to	2169+18	RT	23	LF	-4	Level 2	Utility encounter with proposed pavement and existing pavement removal. Carefully excavate.	Century Link	Telephone Line	-	-	X		0	-	NR	X			X	
CGF-131	10	2169+13	to	2169+24	LT	10	LF	-4	Level 1	Utility encounter with proposed pavement and existing pavement removal. Carefully excavate.	City of Grand Forks	Water Line	-	-	X		0	-	NR	X			X	
DACANE-132	10	2169+13	to	2169+24	LT	10	LF	-4	Level 2	Utility encounter with proposed pavement and existing pavement removal. Carefully excavate.	Dakota Carrier Network	Fiber Optic Line	-	-	X		0	-	NR	X			X	
XCEENE-133	10	2169+14	to	2169+24	LT	10	LF	-4	Level 2	Utility encounter with proposed pavement and existing pavement removal. Carefully excavate.	Xcel Energy	Gas Line	-	-	X		0	-	NR	X			X	
CGF-134	10	2169+51	to	2169+90	LT	39	LF	-4	Level 1	Utility encounter with proposed pavement, sidewalk, and conduit installation. Carefully excavate.	City of Grand Forks	Water Line	-	-	X		0	-	NR	X			X	
DACANE-135	10	2169+52	to	2170+13	LT	61	LF	> -10	Level 2	Utility encounter with proposed pavement, sidewalk, conduit, signal foundation installation. Carefully excavate.	Dakota Carrier Network	Fiber Optic Line	-	-	X		0	-	NR	X			X	
XCEENE-136	10	2169+52	to	2170+12	LT	60	LF	> -10	Level 2	Utility encounter with proposed conduit installation and existing signal foundation removal. Carefully excavate.	Xcel Energy	Gas Line	-	-	X		0	-	NR	X			X	
XCEENE-137	10	2169+67	to	2169+67	LT	38	LF	-4	Level 2	Utility encounter with proposed pavement and conduit installation. Carefully excavate.	Xcel Energy	Gas Line	-	-	X		0		NR	X			X	
CGF-138	10	2169+72	to	2169+99	RT	27	LF	> -10	Level 2	Utility encounter with proposed conduit, pedestrian push button, and signal pole foundation installation. Carefully excavate.	City of Grand Forks	Storm Drain	-	-	X		0		NR	X			X	
CGF-139	10	2169+81	to	2169+82	RT	31	LF	-4	Level 2	Utility encounter with proposed conduit and pedestrian signal foundation installation. Carefully excavate.	City of Grand Forks	Storm Drain	-	-	X		0		NR	X			X	

Utility Coordination Table Appendix A of SP 1014(14) HEU-6-081(094)940 PCN 21884 Sorted By Station																			Not Reimbursable (NR) - Reimbursable (R)	Additional Potholing to be performed by Utility company (information of pothole will be added to comments in table).			LOCATION OUT = outside existing NDDOT RW IN = in Existing NDDOT RW	
UE ID #	Utility Coordina tion Exhibits	Approx. Sta From		Approx. Sta To	LT/RT or Crossing or Point Location	Approx. Qty	Unit	Max Excavation Cut (-) / Fill (+) Feet	Encounter Level	Resolution Criteria / Comments (The following information for the Contractor is based on early coordination with utilities. Information is approximate. Details for the schedule and construction phasing will need to be finalized between the Contractor and Utility	Utility Company	Type of Facility	After Notification - Time For Utility to Mobilize (D = Working Day, W = Week)	Estimated Time to Complete Relocation (D = Working Day, W = Week)	UTILITY ENCOUNTER TYPE (UE)		Quantity of Pothole Utility	Pot Hole ID#						
															Protect in Place	Conflict								
																				NO	YES	If Yes, How many ?		
IN	OUT																							
XCEENE-140	10	2169+84	to	2169+85	RT	20	LF	> -10	Level 2	Utility encounter with proposed conduit, pull box installation and existing signal foundation removal. Carefully excavate.	Xcel Energy	Electric Line	-	-	X		0		NR	X			X	
XCEENE-141	10	2169+87	to	2169+87	Crossing	23	LF	-4	Level 2	Utility encounter with proposed pavement and existing pavement removal. Carefully excavate.	Xcel Energy	Electric Line	-	-	X		0	-	NR	X			X	
CENLINK-142	10	2169+88	to	2170+08	RT	38	LF	-2.5	Level 2	Utility encounter with proposed conduit and pull box installation. Carefully excavate.	Century Link	Telephone Line	-	-	X		0	-	NR	X			X	
XCEENE-143	10	2169+88	to	2169+90	LT	41	LF	-4	Level 2	Utility encounter with proposed pavement, conduit installation, and existing pavement removal. Carefully excavate.	Xcel Energy	Electric Line	-	-	X		0	-	NR	X			X	
CENLINK-144	10	2169+89	to	2170+08	RT	37	LF	-2.5	Level 2	Utility encounter with proposed conduit and pull box installation. Carefully excavate.	Century Link	Telephone Line	-	-	X		0	-	NR	X			X	
CGF-145	11	2173+28	to	2173+29	Crossing	33	LF	-4	Level 2	Utility encounter with proposed pavement and existing pavement removal. Carefully excavate.	City of Grand Forks	Storm Drain	-	-	X		0	-	NR	X			X	
CGF-146	12	2181+42	to	2181+92	RT	50	LF	-4	Level 2	Utility encounter with proposed pavement and existing pavement removal. Carefully excavate.	City of Grand Forks	Storm Drain	-	-	X		0	-	NR	X			X	
CGF-205	12	2181+59	to	2182+87	RT	145	LF	-4	Level 2	Utility encounter with proposed pavement, sidewalk, pull box and conduit installation. Carefully excavate.	City of Grand Forks	Interconnect	-	-	X		0	-	NR	X			X	
XCEENE-147	12	2181+72	to	2182+24	RT	54	LF	-4	Level 2	Utility encounter with proposed pavement, median, pull box installation, and existing pavement removal. Carefully excavate.	Xcel Energy	Electric Line	-	-	X		0	-	NR	X			X	
XCEENE-148	12	2181+76	to	2182+24	RT	67	LF	-4	Level 2	Utility encounter with proposed pavement, median, pull box, and existing pavement removal. Carefully excavate.	Xcel Energy	Electric Line	-	-	X		0	-	NR	X			X	
CENLINK-149	12	2181+81	to	2181+92	RT	11	LF	-4	Level 2	Utility encounter with proposed pavement and existing pavement removal. Carefully excavate.	Century Link	Telephone Line	-	-	X		0	-	NR	X			X	

Utility Coordination Table Appendix A of SP 1014(14) HEU-6-081(094)940 PCN 21884 Sorted By Station																		Not Reimbursable (NR) - Reimbursable (R)	Additional Potholing to be performed by Utility company (Information of pothole will be added to comments in table).			LOCATION OUT = outside existing NDDOT RW IN = in Existing NDDOT RW		
UE ID #	Utility Coordina tion Exhibits	Approx. Sta From		Approx. Sta To	LT/RT or Crossing or Point Location	Approx. Qty	Unit	Max Excavation Cut (-) / Fill (+) Feet	Encounter Level	Resolution Criteria / Comments (The following information for the Contractor is based on early coordination with utilities. Information is approximate. Details for the schedule and construction phasing will need to be finalized between the Contractor and Utility	Utility Company	Type of Facility	After Notification - Time For Utility to Mobilize (D = Working Day, W = Week)	Estimated Time to Complete Relocation (D = Working Day, W = Week)	UTILITY ENCOUNTER TYPE (UE)		Quantity of Pothole Utility		Pot Hole ID#					
															Protect in Place	Conflict								
																				NO	YES	If Yes, How many ?		
																						IN	OUT	
CENLINK-150	12	2181+81	to	2181+92	RT	11	LF	-4	Level 2	Utility encounter with proposed pavement and existing pavement removal. Carefully excavate.	Century Link	Telephone Line	-	-	X		0	-	NR	X			X	
CENLINK-151	12	2181+82	to	2181+92	RT	9	LF	-4	Level 2	Utility encounter with proposed pavement and existing pavement removal. Carefully excavate.	Century Link	Telephone Line	-	-	X		0	-	NR	X			X	
XCEENE-152	12	2181+84	to	2181+92	RT	7	LF	-4	Level 2	Utility encounter with proposed pavement and existing pavement removal. Carefully excavate.	Xcel Energy	Electric Line	-	-	X		0	-	NR	X			X	
XCEENE-153	12	2181+85	to	2181+92	RT	7	LF	-4	Level 2	Utility encounter with proposed pavement and existing pavement removal. Carefully excavate.	Xcel Energy	Gas Line	-	-	X		0	-	NR	X			X	
DACANE-154	12	2182+71	to	2182+72	RT	20	LF	-1	Level 2	Utility encounter with proposed sidewalk Installation. Carefully excavate.	Dakota Carrier Network	Fiber Optic Line	-	-	X		0	-	NR	X			X	
CGF-155	12	2182+73	to	2183+13	RT	40	LF	-3	Level 2	Utility encounter with proposed pedestrian push button, signal cabinet foundation installation and existing signal cabinet foundation removal. Carefully excavate.	City of Grand Forks	Storm Drain	-	-	X		0	-	NR	X			X	
XCEENE-156	12	2182+79	to	2182+87	RT	8	LF	-1	Level 2	Utility encounter with proposed foundation installation, and existing signal cabinet foundation removal. Carefully excavate.	Xcel Energy	Electric Line	-	-	X		0	-	NR	X			X	
XCEENE-157	12	2182+79	to	2182+99	RT	20	LF	-1	Level 2	Utility encounter with proposed foundation installation, and existing signal cabinet foundation removal. Carefully excavate.	Xcel Energy	Gas Line	-	-	X		0	-	NR	X			X	
CENLINK-158	12	2182+81	to	2182+96	RT	20	LF	-1	Level 2	Utility encounter with proposed foundation installation, and existing signal cabinet foundation removal. Carefully excavate.	Century Link	Telephone Line	-	-	X		0	-	NR	X			X	
XCEENE-159	12	2182+89	to	2182+93	RT	5	LF	-1	Level 2	Utility encounter with proposed signal cabinet foundation installation, and existing foundation removal. Carefully excavate.	Xcel Energy	Electric Line	-	-	X		0	-	NR	X			X	

Utility Coordination Table Appendix A of SP 1014(14) HEU-6-081(094)940 PCN 21884 Sorted By Station																			Not Reimbursable (NR) - Reimbursable (R)	Additional Potholing to be performed by Utility company (Information of pothole will be added to comments in table).			LOCATION OUT = outside existing NDDOT RW IN = in Existing NDDOT RW	
UE ID #	Utility Coordina tion Exhibits	Approx. Sta From		Approx. Sta To	LT/RT or Crossing or Point Location	Approx. Qty	Unit	Max Excavation Cut (-) / Fill (+) Feet	Encounter Level	Resolution Criteria / Comments (The following information for the Contractor is based on early coordination with utilities. Information is approximate. Details for the schedule and construction phasing will need to be finalized between the Contractor and Utility	Utility Company	Type of Facility	After Notification - Time For Utility to Mobilize (D = Working Day, W = Week)	Estimated Time to Complete Relocation (D = Working Day, W = Week)	UTILITY ENCOUNTER TYPE (UE)		Quantity of Pothole Utility	Pot Hole ID#		NO	YES	If Yes, How many ?	IN	OUT
															Protect in Place	Conflict								
XCEENE-160	12	2182+90	to	2182+92	RT	5	LF	-1	Level 2	Utility encounter with proposed foundation installation, and existing signal cabinet foundation removal. Carefully excavate.	Xcel Energy	Electric Line	-	-	X		0	-	NR	X			X	
XCEENE-161	12	2182+90	to	2182+99	RT	9	LF	-1	Level 2	Utility encounter with proposed foundation installation, and existing signal cabinet foundation removal. Carefully excavate.	Xcel Energy	Electric Line	-	-	X		0	-	NR	X			X	
XCEENE-162	12	2182+93	to	2182+94	RT	5	LF	-1	Level 2	Utility encounter with proposed foundation installation, and existing signal cabinet foundation removal. Carefully excavate.	Xcel Energy	Electric Line	-	-	X		0	-	NR	X			X	
XCEENE-163	12	2183+01	to	2183+04	RT	5	LF	-1	Level 2	Utility encounter with proposed foundation installation, and existing signal cabinet foundation removal. Carefully excavate.	Xcel Energy	Electric Line	-	-	X		0	-	NR	X			X	
XCEENE-164	12	2183+01	to	2183+04	RT	5	LF	-1	Level 2	Utility encounter with proposed foundation installation, and existing signal cabinet foundation removal. Carefully excavate.	Xcel Energy	Electric Line	-	-	X		0	-	NR	X			X	
XCEENE-165	12	2183+02	to	2183+04	RT	5	LF	-1	Level 2	Utility encounter with proposed foundation installation, and existing signal cabinet foundation removal. Carefully excavate.	Xcel Energy	Electric Line	-	-	X		0	-	NR	X			X	
CGF-166	13	2194+58	to	2195+32	RT	106	LF	> -10	Level 2	Utility encounter with proposed pavement, conduit installation, and existing pavement, signal foundation removal. Carefully excavate.	City of Grand Forks	Electric Line	-	-	X		0	-	NR	X			X	
CGF-167	13	2194+77	to	2195+39	RT	62	LF	-4	Level 2	Utility encounter with proposed pavement, pedestrian signal foundation, conduit installation and existing pavement removal. Carefully excavate. Note: There is a raised vertical pipe approximately 3' below the ground at the intersection of the storm drain pipes. Impacts 167 & 177.	City of Grand Forks	Storm Drain	-	-	X		0	-	NR	X			X	

Utility Coordination Table Appendix A of SP 1014(14) HEU-6-081(094)940 PCN 21884 Sorted By Station																		Not Reimbursable (NR) - Reimbursable (R)	Additional Potholing to be performed by Utility company (information of pothole will be added to comments in table).			LOCATION OUT = outside existing NDDOT RW IN = in Existing NDDOT RW		
UE ID #	Utility Coordination Exhibits	Approx. Sta From		Approx. Sta To	LT/RT or Crossing or Point Location	Approx. Qty	Unit	Max Excavation Cut (-) / Fill (+) Feet	Encounter Level	Resolution Criteria / Comments (The following information for the Contractor is based on early coordination with utilities. Information is approximate. Details for the schedule and construction phasing will need to be finalized between the Contractor and Utility	Utility Company	Type of Facility	After Notification - Time For Utility to Mobilize (D = Working Day, W = Week)	Estimated Time to Complete Relocation (D = Working Day, W = Week)	UTILITY ENCOUNTER TYPE (UE)		Quantity of Pothole Utility		Pot Hole ID#					
															Protect in Place	Conflict								
																				NO	YES	If Yes, How many ?		
																		IN	OUT					
XCEENE-168	13	2194+80	to	2195+39	RT	59	LF	-2.5	Level 2	Utility encounter with proposed pavement and existing pavement removal. Carefully excavate.	Xcel Energy	Gas Line	-	-	X		0	-	NR	X			X	
CGF-169	13	2194+88	to	2195+39	RT	64	LF	> -10	Level 2	Utility encounter with proposed pavement and existing pavement, signal foundation removal. Carefully excavate.	City of Grand Forks	Electric Line	-	-	X		0	-	NR	X			X	
CGF-206	13	2194+89	to	2195+39	RT	66	LF	-3	Level 2	Utility encounter with proposed pavement installation. Carefully excavate. Portions of the line is going to be adjusted due to the Pull Box being relocated as part of the plans.	City of Grand Forks	Interconnect	-	-	X		0	-	NR	X			X	
CGF-170	13	2194+97	to	2195+39	RT	59	LF	> -10	Level 2	Utility encounter with proposed pavement and existing pavement, signal foundation removal. Carefully excavate.	City of Grand Forks	Electric Line	-	-	X		0	-	NR	X			X	
CENLINK-171	13	2194+89	to	2195+39	RT	50	LF	-4	Level 2	Utility encounter with proposed conduit, pull box installation and existing pavement removal. Carefully excavate.	Century Link	Telephone Line	-	-	X		0	-	NR	X			X	
CENLINK-172	13	2194+89	to	2195+19	RT	69	LF	-3	Level 2	Utility encounter with proposed pavement, conduit installation and existing pavement removal. Carefully excavate.	Century Link	Telephone Line	-	-	X		0	-	NR	X			X	
CGF-173	13	2195+01	to	2195+11	LT	10	LF	> -10	Level 2	Utility encounter with existing signal foundation removal. Carefully excavate.	City of Grand Forks	Electric Line	-	-	X		0	-	NR	X			X	
CENLINK-174	13	2195+13	to	2195+29	RT	16	LF	-2.5	Level 2	Utility encounter with proposed pavement, sidewalk, and existing pavement removal. Carefully excavate.	Century Link	Telephone Line	-	-	X		0	-	NR	X			X	
CENLINK-175	13	2195+14	to	2195+30	RT	16	LF	-2.5	Level 2	Utility encounter with proposed pavement, sidewalk, and existing pavement removal. Carefully excavate.	Century Link	Telephone Line	-	-	X		0	-	NR	X			X	

Utility Coordination Table Appendix A of SP 1014(14) HEU-6-081(094)940 PCN 21884 Sorted By Station																		Not Reimbursable (NR) - Reimbursable (R)	Additional Potholing to be performed by Utility company (information of pothole will be added to comments in table).			LOCATION OUT = outside existing NDDOT RW IN = in Existing NDDOT RW		
UE ID #	Utility Coordina tion Exhibits	Approx. Sta From		Approx. Sta To	LT/RT or Crossing or Point Location	Approx. Qty	Unit	Max Excavation Cut (-) / Fill (+) Feet	Encounter Level	Resolution Criteria / Comments (The following information for the Contractor is based on early coordination with utilities. Information is approximate. Details for the schedule and construction phasing will need to be finalized between the Contractor and Utility	Utility Company	Type of Facility	After Notification - Time For Utility to Mobilize (D = Working Day, W = Week)	Estimated Time to Complete Relocation (D = Working Day, W = Week)	UTILITY ENCOUNTER TYPE (UE)		Quantity of Pothole Utility		Pot Hole ID#	NO	YES	If Yes, How many ?	IN	OUT
															Protect in Place	Conflict								
XCEENE-176	13	2195+16	to	2195+16	RT	10	LF	-	Level 4	Utility line will need to be adjusted due to proposed signal mast arm installation. Give Xcel Energy 1 week notice for de-energizing the lines, and 1 month notice for the adjustment to the utility. Coordinate and identify safe area for adjustment.	Xcel Energy	Overhead Utility	-	-		X	0	-	NR	X			X	
CGF-177	13	2195+16	to	2195+16	RT	41	LF	-2.5	Level 2	Utility encounter with proposed pavement, sidewalk, and conduit installation. Carefully excavate. Note: There is a raised vertical pipe approximately 3' below the ground at the intersection of the storm drain pipes. Impacts 167 & 177.	City of Grand Forks	Storm Drain	-	-	X		0	-	NR	X			X	
CENLINK-178	13	2195+20	to	2195+20	Crossing	13	LF	-2.5	Level 2	Utility encounter with proposed pavement and existing pavement removal. Carefully excavate.	Century Link	Telephone Line	-	-	X		0	-	NR	X			X	
CENLINK-179	13	2195+21	to	2195+21	LT	10	LF	-2.5	Level 2	Utility encounter with proposed conduit installation. Carefully excavate.	Century Link	Telephone Line	-	-	X		0	-	NR	X			X	
CGF-180	13	2195+28	to	2195+28	RT	63	LF	> -10	Level 2	Utility encounter with proposed conduit installation and existing pavement, signal foundation removal. Carefully excavate.	City of Grand Forks	Water Line	-	-	X		0	-	NR	X			X	
CGF-181	13	2195+28	to	2195+28	Crossing	13	LF	-2.5	Level 1	Utility encounter with proposed pavement and existing pavement removal. Carefully excavate.	City of Grand Forks	Water Line	-	-	X		0	-	NR	X			X	
CENLINK-182	13	2195+30	to	2195+39	RT	9	LF	-2.5	Level 2	Utility encounter with proposed pavement and existing pavement removal. Carefully excavate.	Century Link	Telephone Line	-	-	X		0	-	NR	X			X	

Utility Coordination Table Appendix A of SP 1014(14) HEU-6-081(094)940 PCN 21884 Sorted By Station																		Not Reimbursable (NR) - Reimbursable (R)	Additional Potholing to be performed by Utility company (information of pothole will be added to comments in table).			LOCATION OUT = outside existing NDDOT RW IN = in Existing NDDOT RW		
UE ID #	Utility Coordina tion Exhibits	Approx. Sta From		Approx. Sta To	LT/RT or Crossing or Point Location	Approx. Qty	Unit	Max Excavation Cut (-) / Fill (+) Feet	Encounter Level	Resolution Criteria / Comments (The following information for the Contractor is based on early coordination with utilities. Information is approximate. Details for the schedule and construction phasing will need to be finalized between the Contractor and Utility	Utility Company	Type of Facility	After Notification - Time For Utility to Mobilize (D = Working Day, W = Week)	Estimated Time to Complete Relocation (D = Working Day, W = Week)	UTILITY ENCOUNTER TYPE (UE)		Quantity of Pothole Utility		Pot Hole ID#	NO	YES	If Yes, How many ?	IN	OUT
															Protect in Place	Conflict								
CENLINK-183	13	2195+31	to	-	RT	1	EA	-2.5	Level 4	Utility will need to be adjusted due to proposed pavement. Give 2 weeks notice to Century Link for relocation. Coordinate and identify safe area for relocations.	Century Link	Telephone Ped	-	-		X	0	-	NR	X			X	
CENLINK-184	13	2195+31	to	2195+39	RT	8	LF	-2.5	Level 2	Utility encounter with proposed pavement and existing pavement removal. Carefully excavate.	Century Link	Telephone Line	-	-	X		0	-	NR	X			X	
CGF-210	13,14	2195+67	to	2196+07	RT	64	LF	> -10	Level 2	Utility encounter with proposed conduit and traffic signal foundation installation. Carefully excavate.	City of Grand Forks	Electric Line	-	-	X		0	-	NR	X			X	
CGF-185	13,14	2195+79	to	2196+07	LT	28	LF	-2.5	Level 1	Utility encounter with proposed pavement, sidewalk and existing pavement removal. Carefully excavate.	City of Grand Forks	Water Line	-	-	X		0	-	NR	X			X	
CGF-186	13,14	2195+79	to	2196+34	LT	55	LF	-2.5	Level 2	Utility encounter with proposed pavement and existing pavement removal. Carefully excavate.	City of Grand Forks	Electric Line	-	-	X		0	-	NR	X			X	
CGF-187	13,14	2195+90	to	2195+90	Crossing	12	LF	-2.5	Level 1	Utility encounter with proposed pavement and existing pavement removal. Carefully excavate.	City of Grand Forks	Sanitary Sewer	-	-	X		0	-	NR	X			X	
CGF-188	13,14	2195+91	to	2195+92	LT	49	LF	> -10	Level 2	Utility encounter with proposed pavement and existing pavement, signal foundation removal. Carefully excavate.	City of Grand Forks	Sanitary Sewer	-	-	X		0	-	NR	X			X	
CENLINK-189	13,14	2196+03	to	2196+13	RT	10	LF	-4	Level 2	Utility encounter with proposed conduit installation and existing pull box removal. Carefully excavate.	Century Link	Telephone Line	-	-	X		0	-	NR	X			X	
MIDCAB-190	13,14	2196+04	to	2196+04	Crossing	13	LF	-2.5	Level 2	Utility encounter with proposed pavement and existing pavement removal. Carefully excavate.	Mid-Continent Cable	TV Line	-	-	X		0	-	NR	X			X	
CGF-207	4	2196+05	to	2196+14	RT	15	LF	-4	Level 2	Utility encounter with proposed pull box and conduit installation. Carefully excavate.	City of Grand Forks	Interconnect	-	-	X		0	-	NR	X			X	

Utility Coordination Table Appendix A of SP 1014(14) HEU-6-081(094)940 PCN 21884 Sorted By Station																		Not Reimbursable (NR) - Reimbursable (R)	Additional Potholing to be performed by Utility company (information of pothole will be added to comments in table).			LOCATION OUT = outside existing NDDOT RW IN = in Existing NDDOT RW			
UE ID #	Utility Coordina tion Exhibits	Approx. Sta From		Approx. Sta To	LT/RT or Crossing or Point Location	Approx. Qty	Unit	Max Excavation Cut (-) / Fill (+) Feet	Encounter Level	Resolution Criteria / Comments (The following information for the Contractor is based on early coordination with utilities. Information is approximate. Details for the schedule and construction phasing will need to be finalized between the Contractor and Utility	Utility Company	Type of Facility	After Notification - Time For Utility to Mobilize (D = Working Day, W = Week)	Estimated Time to Complete Relocation (D = Working Day, W = Week)	UTILITY ENCOUNTER TYPE (UE)		Quantity of Pothole Utility		Pot Hole ID#	NO	YES	If Yes, How many ?	IN	OUT	
															Protect in Place	Conflict									
MIDCAB-191	13,14	2196+05	to	2196+75	LT	95	LF	-3	Level 2	Utility encounter with proposed pavement, sidewalk, conduit, pedestrian push button installation and existing pavement removal. Carefully excavate.	Mid-Continent Cable	TV Line	-	-	X		0	-	NR	X			X		
MIDCAB-192	13,14	2196+07	to	-	LT	1	EA	-1	Level 4	Utility will need to be adjusted due to proposed sidewalk installation. Give 2 weeks notice to Midco for relocation. Coordinate and identify safe area for relocations.	Mid-Continent Cable	Fiber Optic Vault	-	-		X	0	-	NR	X			X		
CGF-193	14	2196+19	to	2196+29	RT	10	LF	> -10	Level 2	Utility encounter with proposed signal foundation installation. Carefully excavate.	City of Grand Forks	Storm Drain	-	-	X		0	-	NR	X			X		
CGF-208	4	2196+34	to	2196+45	RT	12	LF	-3	Level 2	Utility encounter with proposed conduit installation. Carefully excavate.	City of Grand Forks	Interconnect	-	-	X		0	-	NR	X			X		
CGF-194	14	2197+21	to	2197+21	Crossing	11	LF	-2.5	Level 2	Utility encounter with proposed pavement and existing pavement removal. Carefully excavate.	City of Grand Forks	Storm Drain	-	-	X		0	-	NR	X			X		
Totals:															199	11	0				210	0		210	

Utility Company Information			
Utility Company	Contact Name	Phone Number	Email
Century Link	Timothy Armstrong		Timothy.Armstrong@CenturyLink.com
	Charles Grummons	701-241-3141	Charles.Grummons@CenturyLink.com
	Paul Lane		Paul.Lane@CenturyLink.com
	Brendan Christenson		Brendan.Christenson@CenturyLink.com
City of Grand Forks (Electric)	Rick Hanson	701-738-8796	Rhanson@grandforksgov.com
City of Grand Forks (Engineering)	Matt Yavarow	701-746-2612	myavarow@grandforksgov.com
Dakota Carrier Network	Mike Mack	701-361-0551	mmack@dakotacarrier.com
Midcontinent Communications	Robert Johnson	701-335-4228	Kyle.Christenson@midco.com
	Kyle Christenson	701-335-4243	Robert.Johnson@midco.com
	Marc Hogenson	Office: 701-335-4233	Marc.Hogenson@midco.com
Minnkota Power Cooperative	Wayne Lembke	701-795-4342	wlembke@minnkota.com
Nodak Rural Electric Cooperative	Steve Breidenbach	701-795-6759	sbreidenbach@nodakelectric.com
Xcel Energy (Electric)	Deb Thompson	Office: 701-795-5229 Cell: 218-791-0525	debora.l.thompson@xcelenergy.com
Xcel Energy (Gas)	Brennen Wilkens	701-795-5218	brennen.wilkens@xcelenergy.com

Utility Conflict Level Designations	
(Disclaimer: the Following conflict levels were designated based on information provided by utility companies and surveyed located locations.)	
Level 1	Utility not exposed by proposed improvements, no impacts.
Level 2	Utility exposed by proposed improvements but no permanent
Level 3	Utility permanently impacted by proposed improvements and
Level 4	Utility permanently impacted by proposed improvements and

APPENDIX B

DESIGN DATA

Traffic	Average Daily			
Current	Pass:	Trucks:	Total:	
Forecast	Pass:	Trucks:	Total:	
Clear Zone Distance:		Design Speed:		
Minimum Sight Dist. for Stopping:		Bridges:		
Limited Access Control				
Pavement Design Life (years)				
Design Accumulated One-way		ESALs:		

JOB # XX

NORTH DAKOTA

DEPARTMENT OF TRANSPORTATION

HEU-6-081(094)940

Grand Forks County

US Highway 81 (32nd Ave S) from I-29 to S 20th Street

Grand Forks, ND


Safety, Signal and Turn Lanes

STATE	PROJECT NO.	PCN	SECTION NO.	SHEET NO.
ND	HEU-6-081(094)940	21884	1	1

GOVERNING SPECIFICATIONS:
2014 Standard Specifications adopted by the North Dakota
Department of Transportation and the Supplemental Specifications
effective on the date the project is advertised.


PROJECT NUMBER \ DESCRIPTION	NET MILES	GROSS MILES
HEU-6-081(094)940 \ Safety, Signal and Turn Lanes	X.X	X.X

Begin Project
C of US 81 / 32nd Ave S
RP 939.875
Station 2109+84.73



End Project
C of US 81 / 32nd Ave S
RP 941.587
Station 2200+21.50

DESIGNERS



STATE COUNTY MAP

DISTRICT REVIEW

DISTRICT NAME

APPROVED DATE

OFFICE OF PROJECT DEVELOPMENT
ND DEPARTMENT OF TRANSPORTATION

I hereby certify that the attached plans were prepared by me or under my direct supervision and that I am a duly registered professional engineer under the laws of the state of ND.

APPROVED DATE

NDDOT DIV-DIST OR CONSULTANT FIRM

This document
is preliminary
and not for
construction or
implementation
purposes.

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	HEU-6-081(094)940	4	1



Legend

Signal System Revisions & Replacements

Turn Lane / Median / Radii / Sidewalk / ADA Revisions

This document is preliminary and not for construction or implementation purposes.

Scope of Work
US Hwy 81 Safety, Signal and Turn Lanes
I-29 to 20th Street

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	HEU-6-081(094)940	4	2




Legend


Signal System Revisions & Replacements

Turn Lane / Median / Radial / Sidewalk / ADA Revisions

This document is preliminary and not for construction or implementation purposes.

Scope of Work
US Hwy 81 Safety, Signal and Turn Lanes
I-29 to 20th Street











This document is preliminary and not for construction or implementation purposes.

Utility Plan and Profile
US Hwy 81 Signal and Turn Lanes
I-29 to 20th Street
Sta 2122+00 to Sta 2128+00











	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	HEU-6-081(094)940	60	9



This document
is preliminary
and not for
construction or
implementation
purposes.


Utility Plan and Profile
US Hwy 81 Signal and Turn Lanes
I-29 to 20th Street
Sta 2158+00 to Sta 2164+00

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	HEU-6-081(094)940	60	11



This document
is preliminary
and not for
construction or
implementation
purposes.

Utility Plan and Profile
US Hwy 81 Signal and Turn Lanes
I-29 to 20th Street
Sta 2173+00 to Sta 2179+00



NORTH DAKOTA DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION

**DRILLED SHAFT FOUNDATIONS FOR TRAFFIC SIGNALS AND HIGHWAY
LIGHTING**

PROJECT HEU-6-081(094)940 – PCN 21884

DESCRIPTION

This work is constructing reinforced concrete shafts cast in cylindrically excavated holes that extend into soil or rock to support the structure and externally applied loads at the locations and to the lines and grades shown in the plans.

EQUIPMENT

Item	Section
Concrete Equipment	155

MATERIALS

A. General.

Item	Section
Portland Cement Concrete	802
Water	812
Grade 60 Concrete Reinforcement	836.02

B. Portland Cement Concrete Mix Design.

Develop concrete mix designs for Class AE concrete from Table 802-01 with materials conforming to Section 802.01, "Mix Design", but with the following revisions and additions:

- Mix will consist of 25-35% fly ash.
- Maintain a concrete slump of 4-7 inches throughout placement of concrete for the entire Drilled Shaft.
- Provide water reducing and/or retarding concrete admixtures Types A, B or D, as classified under ASTM C494 that meet the requirements of AASHTO M 194 to achieve the required concrete workability and slump throughout concrete placement.

C. Steel Reinforcing Bar Cage Centralizers, Boots and Base Plates.

Provide non-corrosive commercially manufactured devices for properly aligning, centering and supporting steel rebar cages in Drilled Shaft excavations.

Use feet (bottom supports) made of plastic or concrete. Skids or chairs constructed of steel or other corrosive materials will not be allowed.

D. Casing.

Permanent Casing is not allowed unless it is called out in the plans.

If temporary casing is used, ensure that it meets the following requirements:

- Clean
- Watertight
- Smooth wall
- Steel
- Cylindrical
- Strong enough to resist damage and deformation from transportation and handling, installation and extraction stresses, and all pressures and forces acting on the casing.

Sono-tube or paper tube concrete forms are not allowed to be left in place permanently.

F. Slurry.

If slurry is used it must meet the following requirements:

1. General.

Use water meeting the requirements of Section 812, "Water".

Use Slurry samples with temperature of at least 40 degrees when performing tests indicated in Table 1, Table 2, or Table 3.

2. Mineral Slurry

Provide a manufactured mineral slurry that is predominantly clay minerals and water. Prepare and maintain the slurry according to the manufacturer's recommendations, Table 1, and the quality control plan specified in the construction Requirements A., "Drilled Shaft Construction Submittal".

Table 1		
Quality Requirements for Mineral Slurry		
Property	Test	Requirement
Density (pcf)	Mud Weight (Density) American Petroleum Institute (API) 13B-1, Section 1	63 to 75
Viscosity (seconds/quart)	Marsh Funnel and Cup API 13B-1, Section 2.2	28 to 50
pH	Glass Electrode, pH Meter, or pH Paper	8 to 11
Sand Content (percent) immediately prior to placing concrete	Sand Content API 13B-1, Section 5	4.0 max

3. Synthetic Slurry.

Prepare and maintain synthetic slurry according to the manufacturer's recommendations, Table 2, and the quality control plan specified in the construction Requirements A., "Drilled Shaft Construction Submittal".

Table 2		
Quality Requirements for Synthetic Slurry		
Property	Test	Requirement
Density (pcf)	Mud Weight (Density)	≥ 64

	American Petroleum Institute (API) 13B-1, Section 1	
Viscosity (seconds/quart)	Marsh Funnel and Cup API 13B-1, Section 2.2	32 to 135
pH	Glass Electrode, pH Meter, or pH Paper	8 to 11.5
Sand Content (percent) immediately prior to placing concrete	Sand Content API 13B-1, Section 5	1.0 max

4. Water Slurry.

Use Water without site soils when the drilled shaft is cased the entire length of the hole and there is no upward flow that could affect basal stability of the shaft excavation. Prepare and maintain the slurry according to the requirements of Table 3.

Table 3 Quality Requirements for Water Slurry		
Property	Test	Requirement
Density (pcf)	Mud Weight (Density) API 13B-1, Section 1	65 max
Sand Content (percent)	Sand Content API 13B-1, Section 5	1.0 max

CONSTRUCTION REQUIREMENTS

A. Drilled Shaft Construction Submittal.

Provide a Drilled Shaft Construction Submittal, for Engineer's review, comprised of the following components:

- Construction Experience;
- Concrete Mix Designs;
- Drilled Shaft Installation Plan; and
- Slurry Manufacturer's Technical Representative (if slurry is proposed)

Submit the document according to Section 105.08, "Work Drawings".

1. Contractor Personnel

Provide the name and experience record of the Contractor, Superintendent, and driller(s)/operators that will be performing the Drilled Shaft work.

2. Concrete Mix Design

- Meet the requirements of 802.01
- Batch Plant Qualifications
 - Use a National Ready Mixed Concrete Association (NRMCA) certified plant for concrete operations.
 - Provide the following information:
 - Plant's name
 - Address
 - Phone Number

- (d) Distance and travel time to site
- (3) Do not change concrete mix designs and supplier unless new batch plant qualifications and mix designs are submitted to Engineer.

3. Drilled Shaft Installation Plan

Develop a Drilled Shaft Installation Plan with the following information:

- a. Proposed overall construction operation sequence.
- b. Description, size, and capacities of proposed drilling equipment, including but not limited to cranes, drills, auger, bailing buckets, final cleaning equipment, and drilling unit. Describe equipment suitability to the anticipated site conditions and work methods. Include a project history of the drilling equipment demonstrating the successful use of the equipment on drilled shafts of equal or greater hole size in similar soil/rock conditions. Include specific details of drilled shaft excavation and cleanout methods.
- c. Contingency plan that addresses methods to complete the drilled shafts in the event of equipment breakdowns, potential problems related to the subsurface conditions at the site.
- d. Details of the method(s) proposed to ensure drilled shaft stability (i.e., prevention of caving or bottom heave using temporary casing, slurry, or other means) during excavation (including pauses and stoppages during excavation), reinforcing steel cage placement and concrete placement.
- e. Description and details of the storage and disposal plan for excavated material.
- f. Details of concrete placement, including proposed operational procedures for pumping methods, and a sample uniform yield form for plotting the approximate volume of concrete placed versus the depth of shaft for all shaft concrete placement (except for concrete placement in the dry).
- g. Copies of all permits, agreements, and manifests.
- h. Temporary Casing Plan
If temporary casing is proposed, provide a Temporary Casing Plan that includes the following information:
 - (1) Casing dimensions.
 - (2) Method of installation.
 - (3) Method of extracting the temporary casing and maintaining shaft reinforcement in proper alignment and location.
 - (4) Means for maintaining workable concrete (slump) during casing extraction.
- i. Slurry Work Plan
If slurry is proposed, provide a Slurry Work Plan that includes the following information:
 - (1) Slurry mix design, listing and describing all additives and their specific purpose in the slurry mix, with a discussion of their suitability to the anticipated subsurface conditions along with the procedures for mixing, using, and maintaining the slurry.
 - (2) Description and details of the storage and disposal plan for drilling slurry. Include permit applications and approved permits required for slurry storage and disposal.
 - (3) Description of methods to be used to control and contain slurry within the NDDOT right-of-way.
 - (4) The name(s) of the Contractor's personnel assigned to the project and trained by

the slurry manufacturer in the proper use of the slurry. Include a copy of a signed training certification letter from the slurry manufacturer for each trained Contractor's employee listed, including the date of the training.

- (5) Detailed plan for quality control of the selected slurry including:
- (a) Tests to be performed and methods to be followed.
 - (b) Tester's name and qualifications.
 - (c) Minimum and/or maximum slurry material property requirements that ensure the slurry functions as intended, with consideration of the anticipated subsurface conditions and shaft construction methods, and in accordance with the slurry manufacturer's recommendations and these Special Provisions.
 - (d) Include the following tests in the slurry quality control plan:
 - Mineral Slurry: See Table 1
 - Synthetic Slurry: See Table 2
 - Water Slurry: See Table 3

4. Slurry Manufacturer's Technical Representative

If slurry other than Water Slurry is proposed, provide or arrange for technical assistance in the use of the slurry. Submit the following to the Engineer:

- a. The name and contact information for the Slurry Manufacturer's Technical Representative assigned to the project
- b. The frequency of scheduled visits to the project site by the Slurry Manufacturer's Technical Representative.

B. Suspension of Work.

The Engineer will suspend drilled shaft construction if methods listed and described on the approved Drilled shaft Construction Submittal are substituted or changed without resubmittal of an updated Drilled Shaft Construction Submittal. The Contractor is fully liable for the additional costs resulting from the suspension of work, and no adjustments in contract time resulting from the suspension of work will be allowed.

C. Drilled Shaft Excavation.

1. Drilled Shaft Excavation Operations

a. General

- (1) Excavate the drilled shaft shafts to the required depth as shown in the Plans and in conformance with the approved Drilled Shaft Construction Submittal. Check the plumbness, alignment and dimensions of the shaft during drilling or excavation of the shaft. Correct any deviation exceeding the allowable Construction Tolerances with a procedure approved by the Engineer.
- (2) Construct shafts so that the center at the top of the shaft is within 6 inches horizontally of the plan position in the horizontal plane unless approved by the Engineer.
- (3) Construct shafts at the plan elevation for the top of the shaft, unless the Engineer approves alternate elevation.
- (4) Vertical alignment of shafts to be within 1.5 percent measured from vertical plane.
- (5) Perform drilled shaft excavation operations, including casing installation and

removal, such that the soil adjacent to the shaft is not disturbed for the full height of the shaft. Disturbed soil is defined as soil whose geotechnical properties have been changed from those of the original in situ soil, and whose altered condition adversely affects the structural integrity of the drilled shaft or the interface between the drilled shaft and the soil.

- (6) Excavate in a continuous operation until the excavation of the shaft is completed, except for pauses and stops as noted below, using approved equipment.
- (7) Pauses are not allowed during this excavation operation, except for casing splicing, tooling changes, slurry maintenance, and removal of obstructions. Stops are shaft excavation operation interruptions not conforming to this definition.
- (8) Notify the Geotechnical Section of significant variations, changes, revisions and updates to the Drilled Shaft Construction Submittal, as they are approved by the Engineer.

b. Stops in shaft excavation

- (1) Do not exceed stops longer than 16 hours for uncased or partially cased excavations.
- (2) Do not exceed stops longer than 65 hours for fully cased excavations, excavations in rock or excavations with casing seated into rock.
- (3) For stops exceeding the time durations specified above in excavations where mineral or synthetic slurry is not present, stabilize the excavation using one or more of the following methods:

(a) Uncased Excavations

- Install casing in the hole to the depth of the excavation before the end of the work day. The outside diameter of the casing shall not be smaller than 6 inches less than either the plan diameter of the shaft or the actual excavated diameter of the hole, whichever is greater.
- Sound the annular space between the casing and excavation prior to removing the casing and resuming shaft excavation. If the sounding operation indicates that caving has occurred, do not remove the casing nor resume shaft excavation until stabilizing the excavation in conformance with the Drilled Shaft Installation Plan.
- Backfill the hole with granular material to the ground surface

(b) Cased Excavations

- Backfill the hole with granular material to a minimum of 5 feet above the bottom of temporary casing.

- (4) During stops, stabilize the shaft excavation to prevent bottom heave, caving, head-loss, and loss of ground. The Contractor bears full responsibility for selection and execution of the method(s) for stabilizing and maintaining the shaft excavation. Stabilize the shaft in conformance to the Drilled Shaft Installation Plan.
- (5) If slurry is present in the shaft excavation, maintain the minimum level of drilling slurry throughout the stoppage to the greater of the following elevations:
 - No lower than water level outside the drilled shaft.
 - Elevation necessary to maintain a stable hole.Prior to recommencing shaft excavation operations, recondition the slurry to the required slurry properties.

c. Collect and dispose of excavated soil and drilled shaft spoils without allowing erosion

or runoff to disperse soil outside the NDDOT right-of-way, and in accordance with Sections 107.01, "Laws to be Observed", and 107.17, "Removed Materials". Provide copies of all documentation of the transport and final disposal of the soils and drilled shaft spoils to the Engineer.

- d. Contain all water, including water slurry, for disposal outside of NDDOT Right-of-Way.

2. Bottom of Shaft Excavation

- a. Use appropriate means such as a cleanout bucket or air lift to clean the bottom of the excavation of all shafts. Ensure that no more than 2 inches of loose or disturbed material is present at the bottom of the shaft prior to placing concrete.
- b. Sound the bottom of the excavated shaft with an airlift pipe, a steel tape with a heavy weight of at least 1 pound attached to the end of the tape, or other means acceptable to the Engineer to determine that the shaft bottom is at the depth shown in the plans.
- c. After observing the Contractor inspecting each shaft for acceptable cleanliness and depth, the Engineer will approve each shaft prior to the Contractor proceeding with construction.

D. Casing.

Temporary Casing may be furnished and installed to maintain a stable excavation or to facilitate construction. Provide a casing with an outside diameter that is equal to or greater than the specified diameter of the shaft. Completely remove temporary casing after shaft construction is complete without deforming and causing damage to the completed shaft and without disturbing the surrounding soil. As the temporary casing is withdrawn, maintain the concrete and slurry (if used) inside the casing at a level sufficient to balance the hydrostatic pressure outside the casing.

E. Slurry Installation Requirements.

- 1. General
Use slurry, in accordance with this Special Provision, to maintain a stable excavation during excavation and concrete placement operations.
- 2. Slurry Technical Assistance
 - a. Slurry Manufacturer's Technical Representative does the following:
 - (1) Provides technical assistance and training for the use of the slurry
 - (2) Be at the site prior to addition of the slurry into the first drilled hole requiring slurry
 - (3) Remain at the site during the construction of at least the first shaft excavated to adjust the slurry mix to the specific site conditions
 - b. After the Slurry Manufacturer's Technical Representative is no longer present at the site, the Contractor's employee(s) who received training by the slurry manufacturer will provide technical assistance for testing, mixing, maintaining and adjusting the slurry mix in accordance with the manufacturer's requirements and this Special Provision throughout the remainder of shaft slurry operations.
- 3. Minimum Level of Slurry in Excavation
Use of slurry in a shaft excavation requires the following:

- a. Sustain the height of the slurry as required to provide and maintain a stable hole to prevent bottom heave, caving, or sloughing of all unstable zones.
 - b. Maintain a slurry level in the shaft above the groundwater level equal to or greater than the following:
 - (1) 5 feet or more for mineral slurries
 - (2) 10 feet or more for synthetic slurries
 - (3) 10 feet or more for water slurries
4. Slurry Sampling and Testing
- a. When synthetic slurry is used, keep a written record of all additives and concentrations of the additives in the synthetic slurry. Provide these records to the Engineer once the slurry system has been established in the first concrete on the project. Provide revised data to the Engineer if changes are made to the type or concentration of additives during construction.
 - b. Sample and test all slurry in the presence of the Engineer, unless otherwise directed. Record the date, time, names of the persons sampling and testing the slurry, and the results of the tests. Submit a copy of the recorded slurry test results to the Engineer at the completion of each shaft. Provide a copy of the recorded slurry test results during construction of each shaft when requested by the Engineer. To verify that the slurry conforms to the specified slurry material properties, collect and test slurry samples at the frequency specified in Table 4.
 - c. Do not place concrete until the slurry samples taken at mid-height and within 2 feet of the bottom of the drilled shaft excavation conform to the specified slurry material properties.
 - d. Table 4 below summarizes the slurry sampling and testing requirements at different stages of drilled shaft construction.
5. Maintain the slurry properties by doing the following:
- a. Cleaning
 - b. Recirculating
 - c. Removing sand
 - d. Replacing slurry
6. Maintenance of a Stable Drilled Shaft Excavation with Slurry
- Demonstrate to the satisfaction of the Engineer that stable conditions are being maintained. If the Engineer determines that stable conditions are not being maintained, take immediate action to stabilize the shaft. Submit a revised Drilled Shaft Installation Plan within 2 days, which addresses the problem and prevents future instability. The Engineer will review the revised Drilled Shaft Installation Plan within 10 days. Do not continue with shaft construction until the damage that has occurred is repaired and until receiving the Engineer's approval of the revised Drilled Shaft Installation Plan narrative.
7. Disposal of Slurry and Slurry Contaminated Spoils
- Dispose of the slurry and slurry-contaminated spoils off-site as specified in the Drilled Shaft Installation Plan submittal, and in accordance with Sections 107.01, "Laws to be Observed", and 107.17, "Removed Materials". Provide copies of all documentation of the transport and final disposal of the slurry and slurry contaminated spoils.

F. Assembly and Placement of Reinforcing Steel.

1. Steel Reinforcing Bar Cage Assembly

- a. Rigidly brace the reinforcing cage to retain its configuration during handling and construction. No individual or loose bars will be permitted. Support shaft reinforcing bar cages on a continuous surface to the extent possible. Locate all rigging connections at primary handling bars. Internal bracing is required at each support and lift point.
- b. Position and securely fasten the reinforcement to provide the minimum clearances as shown on the Plans, and to ensure no displacement of the reinforcing steel bars in position throughout the concrete placement operation.

2. Steel Reinforcing Bar Cage Centralizers

Place reinforcing steel centralizers at each longitudinal space plane at the quarter points around the circumference of the steel reinforcing bar cage, and at a maximum longitudinal spacing of either 2.5 times the shaft diameter or 20 feet, whichever is less. Position and securely fasten the centralizers to provide the minimum concrete cover as shown on the Plans, and to maintain proper positioning of the cage during placement of the concrete.

3. Steel Reinforcing Cage Bottom Supports

Install prefabricated feet (bottom supports) to maintain the clearance shown on the Plans.

G. Placing Concrete.

1. Concrete Placement Requirements

a. General

- (1) Notify the Engineer 24 hours before placing concrete. Do not give the notice until all preparations are complete.
- (2) Begin concrete placement as soon as possible after completion of drilled shaft excavation, testing slurry (if applicable), placement of the reinforcing steel cage, and inspection and approval by the Engineer to proceed.
- (3) Place concrete in one continuous operation to the top of the shaft.
- (4) During concrete placement, monitor and minimize the difference in the level of concrete inside and outside of the steel reinforcing bar cage so that the difference is no greater than 1 foot.
- (5) Remove excess concrete and contaminated concrete above the top elevation of the shaft to expose fresh concrete and smooth any high spots.
- (6) After the shaft concrete is placed, the top of the reinforcing steel cage will be no more than 6 inches above and no more than 3 inches below plan position.
- (7) The top elevation of the shaft will be no more than 1 inch above or 3 inches below the plan elevation.

b. Concrete Placement in Dry Hole

A hole will be considered dry if there is less than 3 inches of water in the hole at the time of concrete placement.

Deposit the concrete through the center of the reinforcement cage by a method that prevents segregation of aggregates and splashing of concrete on the reinforcement cage. Place the concrete such that the free-fall is vertical down the center of the shaft without hitting the sides of the excavation, the steel reinforcing bars, or the steel reinforcing bar cage bracing.

c. Concrete Vibration Requirements

For concrete placed in the dry, vibrate the upper 5 feet of the drilled shaft in accordance with Section 602.04 C.2, "Vibration".

If temporary casing is used, remove it before vibration.

d. Concrete Placement in Wet Hole (Tremie Method)

A hole will be considered wet when there are more than 3 inches of water in the bottom of the hole at the time of concrete placement. Place the concrete at the bottom of the shaft by pressure feed using a concrete pump and a watertight tremie pipe having a minimum diameter of 4 inches.

Concrete placement by gravity feed is not allowed.

Include a device to seal out water at the discharge end of the tube on the tremie pipe while it is first filled with concrete. Alternatively, use a plug or pig manufactured for use in concrete tremie pipes that is inserted at the top of the tremie pipe and travels through the tremie to keep the concrete separated from the water and slurry.

Completely fill the tremie pipe and hopper with concrete prior to allowing the plug or pig to discharge from the end of the tremie pipe.

Keep tremies full of concrete during placement. Keep the lower end of the tremie at least 5 feet into the concrete throughout the pour.

Over-pump the concrete in the shaft until uniform concrete (visually free from slurry, soil and laitance) reaches the top elevation of the shaft.

If the underwater concrete placement operation is interrupted, the Engineer may require the Contractor to prove by core drilling or other tests that the shaft contains no voids or horizontal joints.

If testing reveals voids or joints, repair or replace the shaft at no expense to the Department. Responsibility for coring costs, and calculation of time extension, will be in accordance with Section 109.03, "Compensation for Contract Revisions".

2. Protection of Fresh and Curing Concrete from Vibration

Do not operate heavy equipment within 15 feet of a newly poured shaft for 24 hours, or until the concrete has reached a minimum compressive strength of 1800 psi.

3. Rejection of Shafts and Revisions to Concrete Placement Operations

If the Engineer determines that the concrete placed for a given shaft is structurally

inadequate (e.g., results of compressive strength testing), the shaft will be rejected. Suspend subsequent placement of concrete until submitting written changes to the methods of shaft construction needed to prevent future structurally inadequate shafts to the Engineer, and receiving the Engineer's written approval of the submittal.

H. Concrete Field Testing.

Concrete sampling, frequency, and testing procedures will be made by the Engineer in accordance with Section 602 of the NDDOT "Field Sampling and Testing Manual".

I. Coring Drilled Shaft and Remedial Action Plan.

1. At the Engineer's request, drill a core hole in any questionable quality shaft, determined by observation of the Engineer, to explore the shaft condition.
2. Prior to beginning of coring, submit the method and equipment that will be used to drill and remove cores from the shaft concrete, and receive the Engineer's written approval. Use either a conventional double-tube, swivel-type core barrel with split liners or wireline barrel with slit inner liners. Use a new diamond coring bit. Replace the coring bit and core barrel as necessary to achieve a high percentage of core recovery. Obtain core samples in accordance with ASTM D 2113 to 5 feet below the bottom elevation of the possible defect or as directed by the Engineer. Obtain core samples with a minimum diameter of 3.0 inches. Preserve all core in wooden core boxes, identified as to location and depth, and make available for inspection by the Engineer.
3. If a flaw or defect is confirmed, submit a proposed remedial action plan with supporting calculations and work drawings for correcting the shafts. Submit all remedial correction procedures and designs to the Engineer for approval. Do not begin repair operations until receiving the Engineer's approval of the remedial action plan
4. If no defect is encountered, the Department will pay for all coring and grouting costs.
5. All materials and work necessary, including engineering analysis, testing, evaluations and redesign, to investigate and affect corrections for shaft flaws, defects or to replace the shaft shall be furnished to the Engineer's satisfaction at no additional cost to the Department.

METHOD OF MEASUREMENT AND BASIS OF PAYMENT

Drilled Shafts will not be measured separately and will be based on Plan Quantities.

BASIS OF PAYMENT

The accepted quantities will be paid for at the contract bid price for:

Item No.	Pay Item	Pay Unit
772-981X	Traffic Signal System – Site X	Each
772-981X	Traffic Signal System – Site X	Each
772-981X	Traffic Signal System – Site X	Each

Commented [GEN2]: Revise Name and Bid Items

Commented [GEN1]: Revise Name and Bid Items

Such payment is full compensation for furnishing all materials, equipment, labor, and incidentals to complete the work as specified.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION

VIDEO VEHICLE DETECTION SYSTEM

PROJECT HEU-6-081(094)940 – PCN 21884

1. DESCRIPTION

This provision sets forth the minimum requirements for work, which consists of furnishing, installing, and placing into operation select vehicle detection system components at each intersection, which detects vehicles by processing video images and providing detection outputs to a traffic signal controller. This equipment shall meet the NEMA environmental, power, and surge ratings as set forth in NEMA TS1 and TS2 specifications.

2. ITEMS COVERED & SYSTEM COMPONENTS

The video detection and monitoring system includes the following components:

1. Provide video detection cameras that are Autoscope Vision Processor devices as manufactured by Econolite Control Products Inc. or City approved equal with current software. Include all necessary mounting brackets and the Comm Manager Board.
2. With each camera installation, include an Econolite Autoscope Vision compatible cable (Econolite part #1175-011) branch cable (cable, round, 3-conductor, 18 AWG w/polyethylene jacket) connection to the traffic signal controller cabinet.
3. For the SITE 1, 2, 4, 5, 7, and 8 traffic signal controller cabinets, provide a RuggedComm Ethernet Switch, model RS-900G-HI-P-2LC10. Use two RS-900G-HI-P-2LC10 switches when the fiber branches to a third direction at the cabinet, or as shown in the plans. For the SITE 3 and 6 traffic signal controller cabinets, provide a RuggedComm Ethernet Switch, model RS-2228 rack mounted with 4 LC fiber ports. Include the appropriate type of Ethernet Switch in each controller cabinet an Econolite Cobalt RM with Transit Key/2M Series NEMA TS2/NTCIP. The Ethernet Switches are included in the contract unit price for "IT SYSTEM".
4. Attach mounting risers to the mast arms. Extend risers 5 feet above the mast arms. Riser height may vary if approved by the City of Grand Forks.
5. Provide one spare camera per intersection as additional equipment to the satisfaction of the City.

Provide all cable connections, camera aiming and system set-up, including programming detection zones, counting zones, bicycle zones, and verification of reliable operation with the manufacturer's representative. Perform all cable and camera installations. Video detection camera locations in the plans are for guidance only.

Install the Autoscope cameras on mast arms at the location as shown in the plans, in accordance with the manufacturer's guidelines; and to the satisfaction of the City. Label Autoscope camera locations and corresponding to correlate with indications shown in the plan.

Aim and secure the cameras in an aimed position. Employ a Field Service representative approved by the Autoscope supplier. Aim the cameras so that the field of view is as directed by the City.

Install all Autoscope equipment and cameras using personnel with proper training and certified for Autoscope installation by the equipment manufacturer.

Include services of field service representative of the Autoscope supplier within the cost of this item.

3. TRAINING

Provide on-site training to representatives of the NDDOT, the City of Grand Forks, and anyone on invitation by either. Include one 8 hour training session, covering all aspects of the detector system reasonable for full operation of the system by Owner.

4. WARRANTY, MAINTENANCE, AND SUPPORT

Warranty the video detection system components by its supplier for six (6) years after final inspection and acceptance.

Provide ongoing software support by the supplier including updates of the MVP sensor, modular cabinet interface unit and supervisor computer applications. Provide these updates free of charge during the warranty period. Maintain a program for technical support and software updates following expiration of the warranty period.

Coordinate delivery of spare cameras to the City of Grand Forks Electrician Rick Hanson (701-738-8796) at 714 South 47th Street, Grand Forks, ND.

5. METHOD OF MEASUREMENT

Provide all labor and equipment necessary for the video detection system to be fully operational. Do not measure video vehicle detection system components separately. Include the cost for labor, materials and equipment necessary for furnishing and installing the video vehicle detection system in the contract unit price for "REVISE TRAFFIC SIGNAL SYSTEM – SITE 1, 2, and 7" and "TRAFFIC SIGNAL SYSTEM – SITE 3, 4, 5, 6, and 8".

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION

INTERCONNECT CABLE

PROJECT HEU-6-081(094)940 – PCN 21884

DESCRIPTION

This provision sets forth the minimum requirements for a fiber optic interconnection system to establish communication between ITS equipment as specified.

GENERAL

The bid shall include all necessary labor, equipment and material to install two interconnect cables (12 pair single-mode, 12 pair multi-mode) and connections such that the communication links are complete and fully operational.

The fiber optic cables shall be optical cables suitable for outside plant operations.

The Contractor shall use two single-mode fibers for traffic signal controller interconnection and two single-mode fibers for the entire video detection system.

A. Fiber Optic Cable Specification

1. The fiber optic interconnect cables shall include fibers for aerial and duct application, compatible with daisy-chain operation, for the purpose of controlling traffic in a coordinated system.
2. Cable Specification
The optical cables shall be:
 - a. Dielectric
 - b. Single-Mode: Loose-tube
 - c. Dry Block or totally dry cable (no grease or gel)
 - d. Jacket:
 - Single-Mode cable: Single polyethylene jacket (high or medium density)
 - Multi-mode cable: PVC jacket
 - e. Reinforced with aramid yarn (Kevlar)
 - f. Suitable for duct installation*
*(If the cable is direct burial, it shall be double jacketed)
3. Optical Specifications shall meet RUS 7 CFR 1755.900 (PE-90) and Telcordia GR-20 standards for single-mode cable. The cable shall also meet the following criteria:
Single-mode Fiber
 - a. 62.5 or 50 micrometer, zero water peak.
 - b. Attenuation shall be:
 - Less than or equal to 0.4 dB/km at 1310 nm;
 - Less than or equal to 0.40 dB/km at 1383 nm; and
 - Less than or equal to 0.3 dB/km at 1550 nm.

Multi-mode Fiber

- a. 62.5/125 micrometer, zero water peak
- b. Attenuation shall be:
 - Less than or equal to 3.5 dB/km at 850 nm; and
 - Less than or equal to 1.5 dB/km at 1300 nm.
4. Mechanical Specifications
 - a. The maximum tensile load rating shall not be greater than 2700 Newtons (600 lbf).
 - b. The minimum bend radius shall be 40 times the cable diameter, but not less than 18 inches in diameter under load. The minimum bend radius shall be 20 times the cable diameter under no load.
 - c. The temperature range shall be -40oC to +70oC (single-mode) and -40oC to +75oC (multi-mode).
5. Documentation

The cable manufacturer shall provide documentation indicating the attenuation and bandwidth for individual fibers on each reel within five (5) business days after delivery of the cable. The Contractor shall test the fibers prior to placement with an Optical Time Domain Reflectometer (OTDR).

B. Splicing requirements – No splicing allowed

Fibers shall be terminated in a fiber splice box/enclosure within the signal controller cabinet

C. Fiber Optic Connectors

The purpose of this specification is to describe fiber optic connectors for mating the ends of the fiber with other fiber optic devices.

1. The fiber optic connectors for all multi-mode fiber shall be connectors of “ST” Type.
2. Connectors for all single-mode fiber shall be connectors of “LC” type.
3. The ITS device locations shall be provided with a wall or rack mounted patch panel frame with capacity to terminate all fibers entering or exiting the location.

The distribution unit shall be adequate for the number of fibers, proper winding areas and splices. All ST type connectors for multi-mode and all LC type connectors for single-mode shall be provided for each signal controller cabinet. The distribution unit enclosure shall be mounted on a EIA 19” rack in an area that does not interfere with the normal maintenance of the cabinet electronics and shall have maximum dimensions of 3.5”H x 18.5”W x 11.25”D. The distribution unit enclosure shall be of a slide out drawer type for easy front access with removable rear tray cover to provide easy rear access. The distribution unit shall provide for side cable entries and be capable to accommodate up to 12 ST multi-mode and 12 LC single-mode adapters.

All fibers connected to equipment and the remaining fibers in the bundle shall be terminated at a Fiber Patch Panel which shall have a label for each individual fiber.

WORK DRAWINGS

Work drawings shall be submitted in accordance with specification 105.08 “Plans and Work Drawings.” Additionally, the work drawings shall be complete, indexed, and shall include but not be limited to the following:

- A. Complete details of all components and sections showing all materials.
- B. A listing of all applicable North Dakota DOT, UL and AASHTO specification.
- C. Name of the manufacturer and supplier.

- D. The cable manufacturer shall provide the Engineer with documentation indicating the attenuation and bandwidth for individual fibers on each reel within five business days after delivery of the cable.

TESTING

End-To-End Conformance Testing using Optical Time Domain Reflectometer (OTDR) using a certified Level III cable tester using fiber modules – Fluke DTX1800 or equal. The Contractor shall test each fiber of each cable run and provide results of the test and the reel packing label test results from the manufacturer to the engineer. The test result format shall be computer-based and both hard and electronic copies shall be included with final submittal. The test should include the breakout cable. If the individual cable runs do not match the test results of the packing label test results less the connection and splice losses, the cable shall be replaced at the Contractor's expense. The cable shall again be tested after connectors are installed.

INSTALLATION REQUIREMENTS

- A. Interconnect shall be installed per the manufacturers recommendation with orange warning tape placed 12 inches above the cables.
- B. The Contractor shall include a No.14 AWG 1 unspliced, insulated copper conductor running the full length and parallel to any fiber that is not installed in an existing conduit system with the tracer wire already installed. The purpose of this conductor is for locating the fiber. The cost for the insulated copper conductor shall be included in the price bid for the fiber optic cable.
- C. The Contractor shall identify the foot mark of the cable of the incoming and outgoing cable of each hand-hole. The identifying mark shall be recorded and a label shall be placed in the hand-hole. A summary of all identifying marks shall be provided to City of Grand Forks.
- D. The Contractor shall leave a minimum of 15 feet of each cable slack in each hand-hole. At Splice Enclosure locations, a minimum of 50 feet of each cable slack shall be left at each cable end. At strategic locations, additional cable length may be needed; this information will be provided on a case-by-case basis.

METHOD OF MEASUREMENT

The Interconnect Cable shall be included in the item "IT System" and will not be measured for payment. All labor, materials and equipment necessary for fiber optic interconnection shall be included in the price bid for "IT SYSTEM."

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION
SPECIAL PROVISION

FUEL COST ADJUSTMENT CLAUSE
Revision Date: 9/8/2006

Introduction

This Special Provision provides for price adjustments to the Contract when significant changes in the cost of motor fuels and burner fuels occur while completing the Contract work. Participation in fuel cost adjustment program is not mandatory. A Contractor is not required to notify the Department at the time of submitting bids whether the Contractor will or will not participate in the fuel cost adjustment provision.

The North Dakota Department of Transportation (NDDOT) will send the low responsible bidder a "Fuel Cost Adjustment Affidavit" (SFN 58393) with the proposed Contract. The Contractor shall return a completed Fuel Adjustment Affidavit with the signed Contract as specified in Standard Specification Section 103.06, Execution and Approval of the Contract. The affidavit shall be returned on all Contracts with this provision even if the Contractor elects not to participate in the provision.

Compensation adjustments for motor fuels and burner fuels consumed in prosecuting the Contract shall be determined by the Engineer in accordance with the provisions set forth herein. Compensation adjustments will be assessed monthly for the cost of the motor fuels and burner fuels whenever the Current Fuel Index (CFI) is outside the given threshold of the Base Fuel Index (BFI) for the Contract.

If the Contractor has a fixed price for fuel for motor or burner fuels to complete the work, no fuel cost adjustments will be made for that fuel type. If there is no fixed fuel price for motor or burner fuels, participation in the Fuel Adjustment provision is the decision of the prime Contractor.

If the prime Contractor decides not to participate, no fuel cost adjustments will be made to the Contract for the Contractor or any subcontractors. If the prime Contractor elects to participate in the fuel cost adjustment provision, the prime Contractor shall include the anticipated fuel cost of subcontractors who wish to participate. If fuel cost adjustments are made to the Contract, the prime Contractor shall ensure that participating subcontractors including second and lower tier, are included in the adjustments in proportion to the percentage of work and anticipated fuel cost by that subcontractor.

Fuel Indexes

Each month, NDDOT will record the average wholesale price for No. 2 diesel fuel and the average wholesale price for unleaded gasoline (87 octane). The monthly average will be the average of the daily rack prices for the month as reported by DTN Energy for Fargo ND.

The burner fuel index will be the No. 2 diesel fuel index regardless of the type of burner fuel actually used.

The Base Fuel Index (BFI) price for motor fuels and burner fuel to be used in the Contract will be the average wholesale price for the month prior to the bid opening.

The Current Fuel Index (CFI) price for motor fuels and burner fuel to be used for each monthly adjustment will be the average wholesale price for the month prior to the adjustment month.

Fuel Ratio

For motor fuels diesel and unleaded gas, the fuel ratio of the Contract will be determined by dividing the Contractor's affidavit costs for each motor fuel by the original Contract amount.

For burner fuels, the fuel ratio of the contract will be determined by dividing the Contractor's affidavit cost for burner fuels by the original Contract amount of plant-mixed hot bituminous pavement paid by the ton. Asphalt cement, binders and other miscellaneous bituminous items shall not be included.

The fuel ratio of the contract for motor and burner fuels will remain the same throughout the length of the contract. The sum of the affidavit fuel costs shall not exceed 15% of the original Contract amount.

The fuel ratio for the three fuel types will be determined by the following equation:

Fuel Ratio_(x, y, z) = Affidavit Cost_(x, y, z) / Original Contract Amount_(x, y, z)		
(x)	=	Motor Fuel (Diesel)
(y)	=	Motor Fuel (Unleaded)
(z)	=	Burner Fuel
Fuel Ratio _(x, y, z)	=	Fuel ratio of the contract for each respective fuel type
Affidavit Cost _(x, y, z)	=	Fuel costs from Fuel Adjustment Affidavit (SFN 58393)
Original Contract Amount _(x, y)	=	Total of the original contract amount excluding lane rental, and Part B of the bid (when A+B bidding is used), if applicable.
Original Contract Amount _(z)	=	Total original contract amount for all hot bituminous pavement bid items combined, excluding bid items for asphalt cement, sawing and sealing joints, coring, etc. Only hot bituminous pavement bid items measured by the Ton will be included in the calculation.

Cost Change

The monthly change in fuel costs will be determined by the following equation:

Cost Change_(x, y, z) = (CFI_(x, y, z) - BFI_(x, y, z)) / BFI_(x, y, z)		
(x)	=	Motor Fuel (Diesel)
(y)	=	Motor Fuel (Unleaded)
(z)	=	Burner Fuel (use diesel prices)
Cost Change _(x, y, z)	=	The relative change in the current CFI and the BFI for each fuel type
CFI _(x, y, z)	=	Current Fuel Index for each fuel type
BFI _(x, y, z)	=	Base Fuel Index for each fuel type

Contract Adjustments

Contract adjustments will be made for the cost of motor and burner fuels whenever the cost change exceeds a ±0.10 threshold. No fuel cost adjustment will be made for work done under liquidated damages. Adjustments will be determined for Motor Fuel (diesel), Motor Fuel (unleaded), and Burner Fuel (burner) separately and shall be computed on a monthly basis.

When the cost change is greater than 0.10, the rebate to the Contractor for each fuel type shall be computed according to the following formulas:

$FCA_{(x, y, z)} = \text{Fuel Ratio}_{(x, y, z)} \times \text{Estimate}_{(x, y, z)} \times (\text{Cost Change}_{(x, y, z)} - 0.10)$		
(x)	=	Motor Fuel (Diesel)
(y)	=	Motor Fuel (Unleaded)
(z)	=	Burner Fuel
$FCA_{(x, y, z)}$	=	Fuel Cost Adjustment for each of the fuel types
$\text{Fuel Ratio}_{(x, y, z)}$	=	Fuel Ratio for each of the fuel types
$\text{Estimate}_{(x, y)}$	=	The monthly total of work done on estimates issued in the current month excluding incentive or disincentive payments, pay factor adjustments and any work completed under liquidated damages.
$\text{Estimate}_{(z)}$	=	The monthly total of hot bituminous pavement work done on estimates issued in the current month, excluding bid items for asphalt cement, sawing and sealing joints, coring, etc. Only hot bituminous pavement bid items measured by the Ton will be included in the calculation. Hot bituminous pavement work completed under liquidated damages will not be included.
$\text{Cost Change}_{(x, y, z)}$	=	The monthly change in fuel costs for each of the fuel types

When the cost change is less than -0.10, the credit to the Department for each fuel type shall be computed according to the following formulas:

$FCA_{(x, y, z)} = \text{Fuel Ratio}_{(x, y, z)} \times \text{Estimate}_{(x, y, z)} \times (\text{Cost Change}_{(x, y, z)} + 0.10)$		
(x)	=	Motor Fuel (Diesel)
(y)	=	Motor Fuel (Unleaded)
(z)	=	Burner Fuel
$FCA_{(x, y, z)}$	=	Fuel Cost Adjustment for each of the fuel types
$\text{Fuel Ratio}_{(x, y, z)}$	=	Fuel Ratio for each of the fuel types
$\text{Estimate}_{(x, y)}$	=	The monthly total of work done on estimates issued in the current month excluding any incentive or disincentive payments, pay factor adjustments and any work completed under liquidated damages.
$\text{Estimate}_{(z)}$	=	The monthly total of hot bituminous pavement work done on estimates issued in the current month, excluding bid items for asphalt cement, sawing and sealing joints, coring, etc. Only hot bituminous pavement bid items measured by the Ton will be included in the calculation. Hot bituminous pavement work completed under liquidated damages will not be included.
$\text{Cost Change}_{(x, y, z)}$	=	The monthly change in fuel costs for each of the fuel types

Payments

Adjustments will be determined by the Engineer monthly. Adjustments will be made under the following spec and code for each fuel type:

109 0100	Motor Fuels (Diesel)
109 0200	Motor Fuels (Unleaded)
109 0300	Burner Fuel

When significant payment adjustments are made on final estimates to account for final in-place measured quantities, the Engineer may prorate the adjustments back to the months when the work was done.

Attachments

For informational purposes, a 'Fuel Cost Adjustment Affidavit' (SFN 58393) is included as Attachment A.

FUEL COST ADJUSTMENT AFFIDAVIT

North Dakota Department of Transportation, Construction Services
SFN 58393 (8-2017)

SP Fuel Cost Adjustment Clause
6 of 6

Attachment A

PCN	Project Number		
The Contractor is not required to notify the Department at the time of submitting bids whether he will or will not participate in the fuel cost adjustment program. The Contractor shall return the affidavit on all Contracts with this Provision even if the Contractor elects not to participate.			
Check the box for each fuel type that has a fixed price. No adjustments in fuel price will be made for the boxes that are checked. <input type="checkbox"/> Diesel <input type="checkbox"/> Unleaded <input type="checkbox"/> Burner			
Does your company elect to participate in a fuel adjustment for this contract for the fuels that do not have a fixed price? No adjustments in fuel prices will be made if No is checked. <input type="checkbox"/> Yes <input type="checkbox"/> No			
If yes, provide the total dollars for each of the applicable fuels:			
Diesel (D)			
Unleaded (U)			
Burner Fuel (B)			
Sum (D+U+B)			
		% of Original Contract Amount *	
*The sum of the D, U, and B may not exceed 15% of the original contract amount.			
Under the penalty of law for perjury of falsification, the undersigned,			
Name (print or type)		Title (print or type)	
Contractor (print or type)			
hereby certifies that the documentation is submitted in good faith, that the information provided is accurate and complete to the best of their knowledge and belief, and that the monetary amount identified accurately reflects the cost for fuel, and that they are duly authorized to certify the above documentation on behalf of the company.			
I hereby agree that the Department or its authorized representative shall have the right to examine and copy all Contractor records, documents, work sheets, bid sheets and other data pertinent to the justification of the fuel costs shown above.			
Signature			Date

Acknowledgement

State of	
County of	
Signed and sworn to (or affirmed) before me on this day _____ (month, day, year)	
Name of Notary Public or other Authorized Officer (Type or Print)	Affix Notary Stamp
Signature of Notary Public or other Authorized Officer	
Commission Expiration Date (if not listed on stamp)	