

JOB # 21
NORTH DAKOTA
DEPARTMENT OF TRANSPORTATION



	STATE	PROJECT NO.	PCN	SECTION NO.	SHEET NO.
	ND	ROM-0300(144)	22747	1	1

GOVERNING SPECIFICATIONS:
2020 Standard Specifications adopted by the North Dakota
Department of Transportation and the Supplemental Specifications
effective on the date the project is advertised.

PROJECT NUMBER \ DESCRIPTION	NET MILES	GROSS MILES
ROM-0300(144) Aggregate Surfacing	48.393	48.393

Federal Aid Project ROM-0300(144)

Renville, Ward, Mountrail, Bottineau, McHenry, McLean
Various Locations
Aggregate Surfacing



STATE COUNTY MAP

DESIGNER Dustin Fanfulik, PE /s/
DESIGNER Dean Anderson /s/
DESIGNER Ryan Berg /s/

OTHER REVIEW	
Approval Name	Date Signed
ND DEPARTMENT OF TRANSPORTATION OFFICE OF PROJECT DEVELOPMENT	
Approval Name	Date Signed

Widseth

This document was originally
issued and sealed by
Dustin R. Fanfulik
Registration Number
PE- 27243,
on 08/31/20 and the original
document is stored at the
North Dakota Department
of Transportation

TABLE OF CONTENTS


Plan Sections		
Section	Page(s)	Description
1	1	Title Sheet
2	1	Table of Contents
4	1-12	Scope of Work
6	1	Notes
8	1	Quantities
10	1-2	Basis of Estimate
20	1-2	General Details
30	1	Typical Sections
100	1	Traffic Control Devices List

List of Standard Drawings	
Section	Description
D-101-1, 2, 3	NDDOT Abbreviations
D-101-10	NDDOT Utility Company and Organization Abbreviations
D-101-20, 21	Line Styles
D-101-30, 31, 32	Symbols
D-704-7	Breakaway Systems for Construction Zone Signs - Perforated Tube
D-704-8	Breakaway Systems for Construction Zone Signs - U-Channel Post
D-704-9	Construction Sign Details - Terminal and Guide Signs
D-704-10	Construction Sign Details - Regulatory Signs
D-704-11	Construction Sign Details - Warning Signs
D-704-13	Barricade and Channelizing Device Details
D-704-14	Construction Sign Punching and Mounting Details
D-704-15	Road Closure Layouts
D-704-20	Terminal and Seal Coat Sign Layouts
D-704-22	Construction Truck and Temporary Detour Layouts
D-704-30	Windrow Marking
D-704-50	Portable Sign Support Assembly


Table of Contents
Renville, Ward, Mountrail, Bottineau,
McHenry, McLean Counties
Various Locations

Aggregate Surfacing

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	ROM-0300(144)	4	1



	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	ROM-0300(144)	4	3



LEGEND

 3" Aggregate Surfacing




This document was originally issued and sealed by
Dustin R. Fanfulk
Registration Number
PE- 27243,
on 08/31/20 and the original document is stored at the
North Dakota Department
of Transportation


Scope of Work
Site 2A
J-10, 62nd Ave NW, Mountrail Co

Aggregate Surfacing

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	ROM-0300(144)	4	4




LEGEND

 3" Aggregate Surfacing

This document was originally issued and sealed by
Dustin R. Fanfulk
Registration Number
PE- 27243,
on 08/31/20 and the original document is stored at the
North Dakota Department
of Transportation

Scope of Work
Site 2B
J-02, 51st AVE NW
M-06, 75th St NW
M-07(b), 352nd St NW
Ward County, Renville County
Aggregate Surfacing

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	ROM-0300(144)	4	5



LEGEND


 3" Aggregate Surfacing



This document was originally issued and sealed by
Dustin R. Fanfulk
Registration Number
PE- 27243,
on 08/31/20 and the original document is stored at the
North Dakota Department
of Transportation

Scope of Work
Site 2C
M-08, CR26, Ward County
M-05, CR26, Renville County
Aggregate Surfacing

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	ROM-0300(144)	4	6



LEGEND

 3" Aggregate Surfacing




This document was originally issued and sealed by
Dustin R. Fanfulk
Registration Number
PE- 27243,
on 08/31/20 and the original document is stored at the
North Dakota Department
of Transportation

Scope of Work
Site 3A
H-02(b), 71st Ave NW, Mountrail County

Aggregate Surfacing

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	ROM-0300(144)	4	7



LEGEND

 3" Aggregate Surfacing




This document was originally issued and sealed by
Dustin R. Fanfulk
Registration Number
PE- 27243,
on 08/31/20 and the original document is stored at the
North Dakota Department
of Transportation


Scope of Work
Site 3B
J-06, 61st Ave NW Mountrail County

Aggregate Surfacing

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	ROM-0300(144)	4	8



	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	ROM-0300(144)	4	9



LEGEND

 3" Aggregate Surfacing



This document was originally issued and sealed by
Dustin R. Fanfulk
Registration Number
PE- 27243,
on 08/31/20 and the original document is stored at the
North Dakota Department
of Transportation

Scope of Work
Site 4B
D-08, CR15, McLean County


Aggregate Surfacing

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	ROM-0300(144)	4	10

R84W
R83W

LEGEND

 3" Aggregate Surfacing




This document was originally issued and sealed by
Dustin R. Fanfulk
Registration Number
PE- 27243,
on 08/31/20 and the original document is stored at the
North Dakota Department
of Transportation

Scope of Work
Site 4C
D-09, CR15, McLean County

Aggregate Surfacing

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	ROM-0300(144)	4	11



LEGEND

 3" Aggregate Surfacing



This document was originally issued and sealed by
Dustin R. Fanfulk
Registration Number
PE- 27243,
on 08/31/20 and the original document is stored at the
North Dakota Department
of Transportation

**Scope of Work
Site 5A**
A-01, Central Ave, McHenry County
A-09S, 4th Ave N, McHenry County
A-11, 43rd St N, McHenry County
Aggregate Surfacing

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	ROM-0300(144)	6	1

NOTES

- 100-P01 Military traffic will not be delayed at any time due to the manner and sequence of work. Complete work in progress before starting other work which may interfere with it. The US Air Force point of contact is Dan Lewis 701-723-4834.
- 105-P01 UTILITIES: No utility relocations or adjustments are planned. All utilities on the project need to be protected and remain in existing location.
- 107-112 RAILROAD PROTECTIVE LIABILITY INSURANCE: This project crosses the Canadian Pacific Railway at DOT 693233J Milepost 472.920, DOT 698843J Milepost 434.423, DOT 698837F Milepost 429.934, and DOT 698852H Milepost 442.631.423. All of these locations are off not on the state system and no RP is available. The type of work that will be performed within the railroad right of way is Aggregate Surfacing. Direct inquiries regarding protective liability insurance to:
- Jim Krieger, PE
Manager Public Works – Southern Region
Canadian Pacific Railroad
120 South 6th Street, Suite 900
Minneapolis, MN 55402
612-330-4555 off.
jim_krieger@cpr.ca
- Obtain information regarding the crossing numbers as listed above from the Federal Railroad Administration website: <http://safetydata.fra.dot.gov/Officeofsafety/>
- 203-P01 SUBCUT FOR SUBGRADE REINFORCEMENT: The bid item “Common Excavation-Subcut” includes all costs to excavate the subcut, haul and disposal of material. Subcut areas as directed by the Engineer.
- 230-P01 RESHAPING ROADWAY: Remove all sod from that portion of the existing roadbed which will be between the shoulder lines of the completed roadbed. Reshape roadway top to a crowned section with a 0.040 ‘/’ cross slope (see typical sections). Portions of the roadway have inslopes requiring reshaping to eliminate a false shoulder. Bring the false shoulder up onto the roadway as directed by the engineer and work the aggregate into the existing roadway (see typical sections). Mow and disk the area of the inslope to be pulled up, prior to pulling the material up. Use a disk that is a manufactured shoulder material reclaimer. (Other methods to minimize roots and foreign matter may be proposed for consideration by the engineer). Remove and dispose of all soft and spongy material and rocks larger than 2 inches brought to the surface. Minimize the roots and other foreign matter brought to the surface. Fill all holes and depressions with approved material. Smooth, moisten, or dry the subgrade as necessary, and compact as directed by the engineer. Correct defects in the subgrade (as evidence by sponginess or rutting) with “Aggregate Surface Course-Cl 13” and subcut if required.
- 302-P01 AGGREGATE FOR SUBGRADE REINFORCEMENT: 560 Tons of Class 13 Aggregate have been provided for subgrade reinforcement and will be used as

directed by the Engineer. Include all costs to place and provide this aggregate in the unit price bid for “Aggregate Surface Course Cl. 13.”

- 302-P02 NOXIOUS WEEDS: Provide aggregate from a Contractor optioned pit. Prior to production of the aggregate, furnish the Engineer with a weed certification from the respective County Weed Control Officers allowing the material to be removed from the pit.
- 302-P03 SPOT REPAIRS: Aggregate depths will vary. In most cases, place more aggregate on hilltops. Place aggregate as direct by the Engineer.
- 302-P04 AGGREGATE SURFACE COURSE CL 13: Provide a Class 13 Aggregate with a Plasticity Index (PI) ranging from 4 to 9 and meets the requirements of Section 816.02, “Miscellaneous Aggregates.” The PI is to be determined in accordance with test ND T 90, “Determining the Plastic Limit and Plasticity Index.

A contract adjustment will be administered if the PI is not within the specified range. The Engineer will determine the PI adjustment factor if the limits for PI are exceeded, as calculated:
$$\text{PI Adjustment Factor} = 5 \text{ percent} \times (\text{Average of 3 samples} - \text{Allowable PI})$$

If the PI is determined to be greater than 12, the material will be rejected.

- 704-P01 TRAFFIC CONTROL: Provide traffic control consisting of the following layouts:
1. Standard D-704-15, Layout Type A;
 2. Standard D-704-20, Layout G;
 3. Standard D-704-22, Layouts K & L;
 4. Standard D-704-30, for Gravel Operations providing for 2 miles of windrow.
- Includes all costs to provide the necessary Traffic Control Devices to complete this work in the price bid for “Traffic Control.”

This document was originally issued and sealed by Dustin R. Fanfulik, Registration Number PE-27243, on 8/31/2020 and the original document is stored at the North Dakota Department of Transportation.

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	ROM-0300(142)	8	1

ESTIMATE OF QUANTITIES				
SPEC	CODE	ITEM DESCRIPTION	UNIT	QUANTITY
103	100	CONTRACT BOND	L SUM	1
203	138	COMMON EXCAVATION-SUBCUT	CY	300
216	100	WATER	M GAL	2,547
230	106	RESHAPING ROADWAY	MILE	48.067
302	356	AGGREGATE SURFACE COURSE CL 13	TON	127,901
702	100	MOBILIZATION	L SUM	1
704	100	FLAGGING	MHR	600
704	1081	VERTICAL PANELS - BACK TO BACK	EACH	40
704	1000	TRAFFIC CONTROL SIGNS	UNIT	850
709	151	GEOSYNTHETIC MATERIAL TYPE R1	SY	2700

Estimated Quantities
Renville, Ward, Mountrail, Bottineau,
McHenry, McLean Counties
Various Locations

Aggregate Surfacing

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	ROM-0300(144)	10	1

SITE	ROAD NAME	STATION	EXISTING AGGREGATE DEPTH (FT)	LENGTH	AGGREGATE SURFACING AREA	AGGREGATE DEPTH	WATER	RESHAPE ROADWAY	AGGREGATE SURFACE COURSE CL 13 (1.875 TONS/CY)		WATER	TYPE OF WORK
				MILES	SY	INCHES	GAL/TON	MILES	SURFACING CY	SURFACING TONS	M GAL	
MIAB-M-11	55th Ave. NW	0+21	0.15	3.010	36,099	4	20	3.010	4,011	7,521	150	4" Aggregate Surfacing
		26+42	0.12									
		52+81	0.13									
		79+22	0.17									
		105+55	0.08									
		131+86	0.18									
		158+36	0.11									
MIAB-N-10 (C)	49th Ave. NW	0+64	0.14	1.599	19,293	3	20	1.599	1,608	3,015	60	3" Aggregate Surfacing
		10+76	0.20									
		37+51	0.21									
		63+69	0.17									
		90+06	0.17									
MIAB-N-02	39th Ave. NW	0+70	0.10	1.738	21,434	4	20	1.738	2,382	4,465	89	3" Aggregate Surfacing
		26+39	0.06									
		52+73	0.09									
		79+20	0.11									
		105+60	0.10									
MIAB-O-10	102nd St. NW	0+00	0.11	1.823	21,780	4	20	1.823	2,420	4,538	91	4" Aggregate Surfacing
		26+67	0.24									
		52+84	0.11									
		79+33	0.07									
		105+59	0.17									
MIAB-J-10	62nd Ave. NW	0+66	0.28	4.544	74,210	3	20	4.544	6,184	11,595	232	3" Aggregate Surfacing
		26+32	0.43									
		52+77	0.20									
		91+37	0.27									
		118+90	0.33									
		145+13	0.34									
		171+89	0.35									
		198+29	0.21									
		224+62	0.22									
		251+03	0.10									
MIAB-M-07 (B)	352nd St. NW	0+00	0.24	1.238	18,894	3	20	1.238	1,575	2,952	59	3" Aggregate Surfacing
		26+61	0.10									
		52+94	0.20									
		79+45	0.11									
MIAB-J-02	51st Ave. NW	16+94	0.27	1.894	24,319	3	20	1.894	2,027	3,800	76	3" Aggregate Surfacing
		40+26	0.15									
		69+55	0.19									
MIAB-M-06	75th St. NW	101+00	0.21	1.284	15,420	3	20	1.284	1,285	2,409	48	3" Aggregate Surfacing
		0+00	0.19									
		26+34	0.23									
		53+28	0.31									
MIAB-M-08	CR4	77+97	0.57	2.221	32,398	4	20	2.221	3,600	6,750	135	4" Aggregate Surfacing
		0+99	0.19									
		4+77	0.24									
		31+25	0.14									
		57+60	0.15									
		84+09	0.07									
MIAB-M-05	CR26	109+19	0.15	4.594	75,641	4	20	4.594	8,405	15,759	315	4" Aggregate Surfacing
		135+73	0.09									
		0+00	0.15									
		26+57	0.11									
		52+91	0.11									
		79+25	0.14									
		105+72	0.15									
		131+96	0.17									
		158+66	0.33									
		185+06	0.14									
		211+39	0.16									
		237+76	0.12									
		263+28	0.19									

Aggregate Surface Course, Class 13 @ 1.875 ton/CY
Water for reshaping roadway @ 20 gal/ton

ESTIMATED QUANTITIES FOR APPROACH

Private drive / Field drive 5 ton / Approach - 94 Total (470 TONS)
Adjust roadway 10 ton / Approach - 41 Total (410 TONS)

This document was originally
issued and sealed by
Dustin R. Fanfulik
Registration Number
PE- 27243,
on 08/31/20 and the original
document is stored at the
North Dakota Department
of Transportation

Basis of Estimate
Renville, Ward, Mountrail, Bottineau,
McHenry, McLean Counties
Various Locations

Aggregate Surfacing

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	ROM-0300(144)	10	2


SITE	ROAD NAME	STATION	EXISTING AGGREGATE DEPTH (FT)	LENGTH	AGGREGATE SURFACING AREA	AGGREGATE DEPTH	WATER	RESHAPE ROADWAY	AGGREGATE SURFACE COURSE CL 13 (1.875 TONS/CY)		WATER	TYPE OF WORK
				MILES	SY	INCHES	GAL/TON	MILES	SURFACING CY	SURFACING TONS	M GAL	
MIAB-H-02 (B)	71st Ave. NW	1+82	0.17	3.109	46,489	4	20	3.109	5,165	9,685	194	4" Aggregate Surfacing
		26+48	0.09									
		52+80	0.17									
		76+65	0.24									
		100+13	0.20									
		128+00	0.05									
		159+43	0.14									
		177+56	0.11									
MIAB-J-06	61st Ave. NW	0+00	0.31	2.631	46,412	3	20	2.631	3,868	7,252	145	3" Aggregate Surfacing
		26+21	0.38									
		52+65	0.24									
		79+05	0.16									
		105+15	0.21									
		131+55	0.31									
		146+00	0.24									
MIAB-D-07 (A)	40th Ave. NW	1+39	0.33	1.019	17,146	3	20	1.019	1,429	2,679	54	3" Aggregate Surfacing
		27+43	0.39									
		53+86	0.40									
MIAB-D-07 (B)	17th St. NW	80+28	0.26	0.187	2,738	3	20	0.187	228	428	9	3" Aggregate Surfacing
MIAB-D-08	CR15	1+93	0.39	7.164	126,279	3	20	7.164	10,523	19,731	395	3" Aggregate Surfacing
		26+49	0.37									
		52+90	0.34									
		79+23	0.28									
		105+63	0.28									
		132+28	0.02									
		158+66	0.42									
		185+03	0.33									
		211+49	0.41									
		237+36	0.33									
		264+39	0.31									
		290+85	0.26									
		317+14	0.39									
		343+82	0.27									
		370+20	0.43									
MIAB-D-09	CR15	396+48	0.30	4.823	82,620	3	20	4.823	6,885	12,909	258	3" Aggregate Surfacing
		422+87	0.41									
		449+17	0.35									
		475+95	0.36									
		502+22	0.33									
		528+81	0.31									
		555+13	0.41									
		581+90	0.41									
		608+26	0.35									
		633+63	0.31									
MIAB-A-09S	4th Ave. N	0+72	0.14	1.213	14,485	3	20	1.213	1,207	2,263	45	3" Aggregate Surfacing
		2+41	0.52									
		31+96	0.43									
		55+05	0.49									
		68+28	0.32									
MIAB-A-01	Central Ave.	1+14	0.45	0.258	2,800	3	20	0.258	233	438	9	3" Aggregate Surfacing
		11+03	0.43									
		26+94	0.28									
MIAB-A-11	43rd St. N	0+72	0.41	1.718	19,890	3	20	1.718	1,658	3,108	62	3" Aggregate Surfacing
		26+41	0.49									
		52+69	0.68									
		79+15	0.38									
		105+60	0.50									
MIAB-B-02S	CR2540	0+24	0.66	2.000	29,473	3	20	2.000	2,456	4,605	92	3" Aggregate Surfacing
		26+38	0.35									
		52+92	0.54									
		79+36	0.19									
		105+28	0.40									
PRIVATE DRIVE / FIELD DRIVE / ADJUST ROADWAY / SUBCUT							20			1,440	29	
TOTAL =				48	727,820			48.067	67,147	127,341	2,547	

This document was originally issued and sealed by
Dustin R. Fanfulik
Registration Number
PE- 27243,
on 08/31/20 and the original document is stored at the
North Dakota Department
of Transportation


Basis of Estimate
Renville, Ward, Mountrail, Bottineau,
McHenry, McLean Counties
Various Locations

Aggregate Surfacing


	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	ROM-0300(144)	20	1




1. Reshape Roadway



2. Aggregate Surfacing



Section A-A
(Not to Scale)



Section B-B
(Not to Scale)


1. Actual Aggregate Surfacing locations may vary in the field, as approved by the Engineer.
2. Quantity totals have been included in the bid items of the "Estimate of Quantities" of the plans.

This document was originally issued and sealed by
Dustin R. Fanfulk
Registration Number
PE- 27243,
on 08/31/20 and the original document is stored at the
North Dakota Department
of Transportation

General Details

Approach Paving Details, Existing Rural Approaches
(No Approach Grading)
Renville, Ward, Mountrail, Bottineau,
McHenry, McLean Counties
Various Locations

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	ROM-0300(144)	20	2




Transition

NOTE:
Transitions will be used at the beginning and end of project limits. When project limits start or end at a missile site entrance approach will be full depth and transition will follow beyond the approach.

This document was originally issued and sealed by
Dustin R. Fanfulik
Registration Number
PE- 27243,
on 08/31/20 and the original document is stored at the
North Dakota Department
of Transportation


General Details
Gravel Surfacing Transitions
Renville, Ward, Mountrail, Bottineau,
McHenry, McLean Counties
All Locations
Aggregate Surfacing

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	ROM-0300(144)	30	1




EXISTING ROADWAY

All Sites



RESHAPE ROADWAY

All Sites



TYPICAL AGGREGATE SURFACE SECTION

All Sites

NOTES:

- * Adjust to match existing road width as approved. Taper at a rate of 25:1 between widths.
- ** Included in Reshape Roadway.
- *** The sloughs shall not be steeper than the existing inslope.

This document was originally issued and sealed by
Dustin R. Fanfulik
Registration Number
PE- 27243,
on 08/31/20 and the original document is stored at the
North Dakota Department
of Transportation

Typical Sections
Existing and Proposed
Renville, Ward, Mountrail, Bottineau,
McHenry, McLean Counties
Various Locations
Aggregate Surfacing

?

This is a special text character used in the labeling of existing features. It indicates a feature that has an unknown characteristic, potentially based on: lack of description, location accuracy or purpose.

Abn abandoned
Abut abutment
Ac acres
Adj adjusted
Aggr aggregate
Ahd ahead
ARV air release valve
Align alignment
Al alley
Alt alternate
Alum aluminum
ADA Americans with Disabilities Act
A ampere
& and
Appr approach
Approx approximate
ACP asbestos cement pipe
Asph asphalt
AC asphalt cement
Assmd assumed
@ at
Atten attenuation
ATR automatic traffic recorder
Ave Avenue
Avg average
ADT average daily traffic
Az azimuth
Bk back
BF back face
Bs backsight
Balc balcony
B Wire barbed wire
Barr barricade
Btry battery
Brg bearing
BI beehive inlet
Beg begin
BG below grade
BM bench mark
Bkwy bikeway
Bit bituminous
Blk block
Bd Ft board feet
BH bore hole
BS both sides
Bot bottom
Blvd Boulevard
Bndry boundary
BC brass cap
Brkwy breakaway
Br bridge

Bldg building
BV butterfly valve
Byp bypass
C Gdrl cable guardrail
Calc calculate
Cd candela
CIP cast iron pipe
CB catch basin
CRS cationic rapid setting
C Gd cattle guard
C To C center to center
Cl or C centerline
Cm centimeter
Ch chain
Chnlk chain-link
Ch Blk channel block
Ch Ch channel change
Chk check
Chsld chiseled
Cir circle
Cl class
Cl clay
Cl F clay fill
Cl Hvy clay heavy
Cl Lm clay loam
Clnt clean-out
Clr clear
Cl&gr clearing & grubbing
Co S coal slack
C Gr coarse gravel
CS coarse sand
Comb. combination
Coml commercial
Compr compression
CADD computer aided drafting & design
Conc concrete
CECB concrete erosion control blanket
Cond conductor
Const construction
Cont continuous
CSB continuous split barrel sample
Contr contraction
Contr contractor
CP control point
Coord coordinate
Cor corner
Corr corrected
CAES corrugated aluminum end section
CAP corrugated aluminum pipe
CMES corrugated metal end section
CMP corrugated metal pipe
CPVCP corrugated poly-vinyl chloride pipe
CSES corrugated steel end section
CSFES corrugated steel flared end section

CSP corrugated steel pipe
CSTES corrugated steel traversable end section
C coulomb
Co County
Crse course
Ct Court
Xarm cross arm
Xbuck cross buck
Xsec cross sections
Xing crossing
Xrd Crossroad
Crn crown
CF cubic feet
M3 cubic meter
M3/s cubic meters per second
CY cubic yard
Cy/mi cubic yards per mile
Culv culvert
C&G curb & gutter
CI curb inlet
CR curb ramp
CS curve to spiral
C cut
Dd Ld dead load
Defl deflection
Defm deformed
Deg or D degree
DInt delineate
DIntr delineator
Depr depression
Desc description
Det detail
DWP detectable warning panel
Dtr detour
Dia or \varnothing diameter
Dir direction
Dist distance
DM disturbed material
DB ditch block
DG ditch grade
Dbl double
Dn down
Dwg drawing
Dr drive
Drwy driveway
DI drop inlet
D dry density
DSDS dynamic speed display sign
Ea each
Esmt easement
E East
EB Eastbound
Elast elastomeric
EL electric locker
E Mtr electric meter
Elec electric/al

EDM electronic distance meter
Elev or El elevation
Ellipt elliptical
Emb embankment
Emuls emulsion/emulsified
ES end section
Engr engineer
ESS environmental sensor station
Eq equal
Eq equation
Evgr evergreen
Exc excavation
Exst existing
Exp expansion
Expy Expressway
E external of curve
Extru extruded
FOS factor of safety
F Fahrenheit
FS far side
F farad
Fed Federal
FP feed point
Ft feet/foot
Fn fence
Fn P fence post
FO fiber optic
FB field book
FD field drive
F fill
FAA fine aggregate angularity
FS fine sand
FH fire hydrant
Fl flange
Flrd flared
FES flared end section
F Bcn flashing beacon
FA flight auger sample
FL flow line
Ftg footing
FM force main
Fs foresight

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
04-23-18 09-20-18	General Revisions General Revisions

This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930 , on 09/20/18 and the original document is stored at the North Dakota Department of Transportation

NDDOT ABBREVIATIONS

D-101-2

Fnd	found	ID	inside diameter	Mkg	marking	PMT	pad mounted transformer
Fdn	foundation	Inst	instrument	MA	mast arm	Pg	pages
Frac	fractional	Intchg	interchange	Matl	material	Pntd	painted
Frwy	freeway	Intmdt	intermediate	Max	maximum	Pr	pair
Frt	front	Intscn	intersection	MC	meander corner	Pnl	panel
FF	front face	Inv	invert	Meas	measure	Pk	park
F Disp	fuel dispenser	IM	iron monument	Mdn	median	PK	Parker-Kalon nail
FFP	fuel filler pipes	I Pn	Iron Pin	MD	median drain	Pa	pascal
FLS	fuel leak sensor	IP	iron Pipe	MC	medium curing	PSD	passing sight distance
Furn	furnish/ed	Jt	joint	M	mega	Pvmt	pavement
Gal	gallon	J	joule	Mer	meridian	Ped	pedestal
Galv	galvanized	Jct	junction	M	meter	Ped	pedestrian
Gar	garage	K	kelvin	M/s	meters per second	PPP	pedestrian pushbutton post
Gs L	gas line	Kn	kilo newton	M	mid ordinate of curve	Pen.	penetration
G Reg	gas line regulator	Kpa	kilo pascal	MGS	Midwest Guardrail System	Perf	perforated
GMV	gas main valve	Kg	kilogram	Mi	mile	Per.	perimeter
G Mtr	gas meter	Kg/m3	kilogram per cubic meter	MM	mile marker	PL	pipeline
GSV	gas service valve	Km	kilometer	MP	mile post	PI	place
GVP	gas vent pipe	K	Kip(s)	MI	milliliter	P&P	plan & profile
GV	gate valve	LS	Land Surveyor (licensed)	Mm	millimeter	PL	plastic limit
Ga	gauge	LSIT	Land Surveyor In Training	Mm/hr	millimeters per hour	P Cap	plastic cap
Geod	geodetic	Ln	lane	Min	minimum	PI or \overline{P}	plate
GIS	Geographical Information System	Lg	large	Misc	miscellaneous	Pt	point
G	giga	Lat	latitude	Mon	monument	PCC	point of compound curve
GPS	Global Positioning System	Lt	left	Mnd	mound	PC	point of curve
Gov	government	L	length of curve	Mtbl	mountable	PI	point of intersection
Grd	graded/grade	Lens	lenses	Mtd	mounted	PRC	point of reverse curvature
Gr	gravel	Lvl	level	Mtg	mounting	PT	point of tangent
Grnd	ground	LB	level book	Mk	muck	POC	point on curve
GWM	ground water monitor	Lvng	leveling	Mun	municipal	POT	point on tangent
Gdrl	guardrail	Lht	light	N	nano	PE	polyethylene
Gtr	gutter	LP	light pole	NGS	National Geodetic Survey	PVC	polyvinyl chloride
H Plg	H piling	Ltg	lighting	NS	near side	PCC	Portland Cement concrete
Hdwl	headwall	Lig Co	lignite coal	Neop	neoprene	Lb or #	pounds
Ha	hectare	Lig Sl	lignite slack	Ntwk	network	PP	power pole
Ht	height	LF	linear foot	N	newton	Preempt	preemption
HI	height of instrument	Liq	liquid	N	North	Prefab	prefabricated
Hel	helical	LL	liquid limit	NE	North East	Prfmd or Pref	preformed
H	henry	L	litre	NW	North West	Prep	preperation
Hz	hertz	Lm	loam	NB	Northbound	Press.	pressure
HDPE	high density polyethylene	Loc	location	No. or #	number		
HM	high mast	LC	long chord	Obsc	obscure(d)		
HP	high pressure	Long.	longitude	Obsn	observation		
HPS	high pressure sodium	Lp	loop	Ocpd	occupied		
Hwy	highway	LD	loop detector	Ocpy	occupy		
Hor	horizontal	Lm	lumen	Off Loc	office location		
HBP	hot bituminous pavement	Lum	luminaire	O/s	offset		
HMA	hot mix asphalt	L Sum	lump sum	OC	on center		
Hr	hour(s)	Lx	lux	C	one dimensional consolidation		
Hyd	hydrant	Mb	mailbox	OC	organic content		
Ph	hydrogen ion content	ML	main line	Orig	original		
Id	identification	M Hr	man hour	O To O	out to out		
In or "	inch	MH	manhole	OD	outside diameter		
Incl	inclinometer tube	Mkd	marked	OH	overhead		
IMH	inlet manhole	Mkr	marker				

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
08-03-15 04-23-18	General Revisions General Revisions

This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930 , on 04/23/18 and the original document is stored at the North Dakota Department of Transportation

NDDOT ABBREVIATIONS

D-101-3

PRV	pressure relief valve	Sc	scoria	St	street	Vert	vertical
Prestr	prestressed	Sec	seconds	SPP	structural plate pipe	VC	vertical curve
Pvt	private	Sec	section	SPPA	structural plate pipe arch	VCP	vitrified clay pipe
PD	private drive	SL	section line	Str	structure	V	volt
Prod.	production/produce	Sep	separation	Subd	subdivision	Vol	volume
Prog	programmed	Seq	sequence	Sub	subgrade	Wkwy	walkway
Prop.	property	Serv	service	Sub Prep	subgrade preperation	W	water content
Prop Ln	property line	Sh	shale	Ss	subsoil	WGV	water gate valve
Ppsd	proposed	Sht	sheet	SE	superelevation	WL	water line
PB	pull box	Shtng	sheeting	SS	supplement specification	WM	water main
Qty	quantity	Shldr	shoulder	Supp	supplemental	WMV	water main valve
Qtr	quarter	Sw or Sdwk	sidewalk	Surf	surfacing	W Mtr	water meter
Rad or R	radius	S	siemens	Surv	survey	WSV	water service valve
RR	railroad	SD	sight distance	Sym	symmetrical	WW	water well
Rlwy	railway	SN	sign number	SI	systems international	W	watt
Rsd	raised	Sig	signal	Tan	tangent	Wrng	wearing
RTP	random traverse point	Si Cl	silt clay	T	tangent (semi)	Wb	weber
Rge or R	range	Si Cl Lm	silty clay loam	TS	tangent to spiral	WIM	weigh in motion
RC	rapid curing	Si Lm	silty loam	Tel	telephone	W	west
Rec	record	Sgl	single	Tel B	Telephone Booth	WB	westbound
Rcy	recycle	SRCP	slotted reinforced concrete pipe	Tel P	telephone pole	Wrng	wiring
RAP	recycled asphalt pavement	SC	slow curing	Tv	television	W/	with
RPCC	recycled portland cement concrete	SS	slow setting	Temp	temperature	W/o	without
Ref	reference	Sm	small	Temp	temporary	WC	witness corner
R Mkr	reference marker	S	South	TBM	temporary bench mark	WGS	world geodetic system
RM	reference monument	SE	South East	T	tesla	Z	zenith
RP	reference point	SW	South West	T	thinwall tube sample		
Refl	reflectorized	SB	Southbound	T/mi	tons per mile		
RCB	reinforced concrete box	Sp	spaces	Ts	topsoil		
RCES	reinforced concrete end section	Spcl	special	Twp or T	township		
RCFES	reinforced concrete flared end section	SA	special assembly	Traf	traffic		
RCTES	reinforced concrete traversable end section	SP	special provisions	TSCB	traffic signal control box		
RCP	reinforced concrete pipe	G	specific gravity	Tr	trail		
RCPS	reinforced concrete pipe sewer	Spk	spike	Transf	transformer		
Reinf	reinforcement	SC	spiral to curve	TB	transit book		
Res	reservation	ST	spiral to tangent	Trans	transition		
Rs	residence	SB	split barrel sample	TT	transmission tower		
Ret	retaining	SH	sprinkler head	TES	traversable end section		
Rev	reverse	SV	sprinkler valve	Trans	transverse		
Rt	right	Sq	square	Trav	traverse		
R/W	right of way	SF	square feet	TP	traverse point		
Riv	river	Km2	square kilometer	Trtd	treated		
Rd	road	M2	square meter	Trmt	treatment		
Rdbd	road bed	SY	square yard	Qc	triaxial compression		
Rdwy	roadway	Stk	stake	TERO	tribal employment rights ordinance		
RWIS	roadway weather information system	Std	standard	Tpl	triple		
Rk	rock	N	standard penetration test	TP	turning point		
Rt	route	Std Specs	standard specifications	Typ	typical		
Salv	salvage(d)	Sta	station	Qu	unconfined compressive strength		
Sd	sand	Sta Yd	station yards	Ugrnd	underground		
Sdy Cl	sandy clay	Stm L	steam line	USC&G	US Coast & Geodetic Survey		
Sdy Cl Lm	sandy clay loam	SEC	steel encased concrete	USGS	US Geologic Survey		
Sdy Fl	sandy fill	SMA	stone matrix asphalt	Util	utility		
Sdy Lm	sandy loam	SSD	stopping sight distance	VG	valley gutter		
San	sanitary sewer line	SD	storm drain	Vap	vapor		

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
08-03-15 04-23-18	General Revisions General Revisions

This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930 , on 04/23/18 and the original document is stored at the North Dakota Department of Transportation

NDDOT UTILITY COMPANY AND ORGANIZATION ABBREVIATIONS

D-101-10

702COM
ACCENT
AGASSIZ WU
AGC
All PI
ALL SEAS WU
AMOCO PI
AMRDA HESS
AT&T
B PAW
BAKER ELEC
BASIN ELEC
BEK TEL
BELLE PL
BLM
BNSF
BOEING
BRNS RWD
BURK-DIV ELEC
BURL WU
Cable One
CABLE SERV
CAP ELEC
CASS CO ELEC
CASS RWU
CAV ELEC
CBLCOM
CENEX PL
CENT PL WATER DIST
CENT PWR ELEC
COE
CONS TEL
CONT RES
CPR
D O E
DAK CARR
DAK CENT TEL
DAK RWD
DGC
DICKY R NET
DICKY RWU
DICKY TEL
DNRR
DOME PL
DVELEC
DVMW
ENBRDG
ENVENTIS
FALK MNG
FHWA
G FKS-TRL WD
GETTY TRD & TRAN
GLDN W ELEC
GRGS CO TEL
GTR RAMSEY WD

702 Communications
Accent Communications
Agassiz Water Users Incorporated
Associated General Contractors of America
Alliance Pipeline
All Seasons Water Users Association
Amoco Pipeline Company
Amerada Hess Corporation
AT&T Corporation
Bear Paw Energy Incorporated
Baker Electric
Basin Electric Cooperative Incorporated
Bek Communications Cooperative
Belle Fourche Pipeline Company
Bureau of Land Management
Burlington Northern Santa Fe Railway
Boeing
Barnes Rural Water District
Burke-Divide Electric Cooperative
Burleigh Water Users
Cable One
Cable Services
Capital Electric Cooperative Incorporat
Cass County Electric Cooperative
Cass Rural Water Users Incorporated
Cavalier Rural Electric Cooperative
Cablecom Of Fargo
Cenex Pipeline
Central Pipe Line Water District
Central Power Electric Cooperative
Corps of Engineers
Consolidated Telephone
Continental Resource Inc
Canadian Pacific Railway
Department Of Energy
Dakota Carrier Network
Dakota Central Telephone
Dakota Rural Water District
Dakota Gasification Company
Dickey Rural Networks
Dickey Rural Water Users Association
Dickey Telephone
Dakota Northern Railroad
Dome Pipeline Company
Dakota Valley Electric Cooperative
Dakota, Missouri Valley & Western
Enbridge Pipelines Incorporated
Enventis Telephone
Falkirk Mining Company
Federal Highway Administration
Grand Forks-trail Water District
Getty Trading & Transportation
Golden West Electric Cooperative
Griggs County Telephone
Greater Ramsey Water District

GT PLNS NAT GAS
HALS TEL
IDEA1
INT-COMM TEL
KANEB PL
KEM ELEC
KOCH GATH SYS
LKHD PL
LNGDN RWU
LWR YELL R ELEC
MCKNZ CON
MCKNZ ELEC
MCKNZ WRD
MCLEOD
MCLN ELEC
MCLN-SHRDN R WAT
MDU
MID-CONT CABLE
MIDSTATE TEL
MINOT CABLE
MINOT TEL
MISS VALL COMM
MISS W W S
MNKOTA PWR
MOR-GRAN-SOU ELEC
MOUNT-WILLI ELEC
MRE LBTY TEL
MUNICIPAL
MUNICIPAL
N CENT ELEC
N VALL W DIST
ND PKS & REC
ND TEL
NDDOT
NDSU SOIL SCI DEPT
NEMONT TEL
NODAK R ELEC
NOON FRMS TEL
NPR
NSP
NTH PRAIR RW
NTHN BRDR PL
NTHN PLNS ELEC
NTHWSTRN REF
NW COMM
NWRWD
ONEOK
OSHA
OTTR TL PWR
P L E M
POLAR COM
PVT ELEC
QWEST
R&T W SUPPLY

Great Plains Natural Gas Company
Halstad Telephone Company
Idea1
Inter-Community Telephone Company
Kaneb Pipeline Company
Kem Electric Cooperative Incorporated
Koch Gathering Systems Incorporated
Lakehead Pipeline Company
Langdon Rural Water Users Incorporated
Lower Yellowstone Rural Electric
McKenzie Consolidated Telcom
McKenzie Electric Cooperative
McKenzie County Water Resource District
McLeod USA
McLean Electric Cooperative
McLean-Sheridan Rural Water
Montana-dakota Utilities
Mid-Continent Cable
Midstate Telephone Company
Minot Cable Television
Minot Telephone Company
Missouri Valley Communications
Missouri West Water System
Minnkota Power
Mor-gran-sou Electric Cooperative
Mountrail-williams Electric Cooperative
Moore & Liberty Telephone
City Water And Sewer
City Of '.....'
North Central Electric Cooperative
North Valley Water District
North Dakota Parks And Recreation
North Dakota Telephone Company
North Dakota Department of Transportation
NDSU Soil Science Department
Nemont Telephone
Nodak Rural Electric Cooperative
Noonan Farmers Telephone Company
Northern Plains Railroad
Northern States Power
Northern Prairie Rural Water Association
Northern Border Pipeline
Northern Plains Electric Cooperative Incorporated
Northwestern Refinery Company
Northwest Communication Cooperation
Northwest Rural Water District
Oneok gas
Occupational Safety and Health Administration
Otter Tail Power Company
Prairielands Energy Marketing
Polar Communications
Private Electric
Qwest Communications
R & T Water Supply Association
























RED RIV TEL
RESVTN TEL
ROBRTS TEL
R-RIDER ELEC
RRVW
S CENT REG WD
S E W U
SCOTT CABLE
SHERDN ELEC
SHEYN VLY ELEC
SKYTECH
SLOPE ELEC
SOURIS RIV TELCOM
ST WAT COMM
STATE LN WATER
STER ENG
STUT RWU
SW PL PRJ
T M C
TCI
TESORO HGH PLNS PL
TRI-CNTY WU
TRL CO RWU
UNTD TEL
UPPR SOUR WUA
US SPRINT
USAF MSL CABLE
USFWS
USW COMM
VRNDRY ELEC
W RIV TEL
WEB
WILLI RWA
WILSTN BAS PL
WLSH RWD
WOLVRTN TEL
XLENER
YSVR













Red River Rural Telephone
Reservation Telephone
Roberts Company Telephone
Roughrider Electric Cooperative
Red River Valley & Western Railroad
South Central Regional Water District
South East Water Users Incorporated
Scott Cable Television Dickinson
Sheridan Electric Cooperative
Sheyenne Valley Electric Cooperative
Skyland Technologies Incorporated
Slope Electric Cooperative Incorporated
Souris River Telecommunications
State Water Commission
State Line Water Cooperative
Sterling Energy
Stutsman Rural Water Users
Southwest Pipeline Project
Turtle Mountain Communications
TCI of North Dakota
Tesoro High Plains Pipeline
Tri-County Water Users Incorporated
Traill County Rural Water Users
United Telephone
Upper Souris Water Users Association
U.S. Sprint
U.S.A.F. Missile Cable
US Fish and Wildlife Service
U.S. West Communications
Verendrye Electric Cooperative
West River Telephone Incorporated
W. E. B. Water Development Association
Williams Rural Water Association
Williston Basin Interstate Pipeline Company
Walsh Water Rural Water District
Wolverton Telephone
Xcel Energy
Yellowstone Valley Railroad

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
04-23-18 09-20-18	General Revisions General Revisions








This document was originally
issued and sealed by
Roger Weigel,
Registration Number
PE- 2930 ,
on 09/20/18 and the original
document is stored at the
North Dakota Department
of Transportation

Existing Topography























	Existing Ground Void
	Existing Cemetary Boundary
	Existing Box Culvert Bridge
	Existing Concrete Surface
	Existing Drainage Structure
	Existing Gravel Surface
	Existing Riprap
	Existing Dirt Surface
	Existing Asphalt Surface
	Existing Tie Point Line
	Existing Railroad Centerline
	Existing Guardrail Cable
	Existing Guardrail Metal
	Existing Edge of Water
	Existing Fence
	Existing Railroad
	Existing Field Line
	Exst Flow
	Existing Curb
	Existing Valley Gutter
	Existing Driveway Gutter
	Existing Curb and Gutter
	Existing Mountable Curb and Gutter

	Existing 3-Cable w Posts
	Site Boundary
	Existing Berm, Dike, Pit, or Earth Dam
	Existing Ditch Block
	Existing Tree Boundary
	Existing Brush or Shrub Boundary
	Existing Retaining Wall
	Existing Planter or Wall
	Existing W-Beam Guardrail with Posts
	Existing Railroad Switch
	Gravel Pit - Borrow Area
	Existing Wet Area-Vegetation Break





Proposed Topography

	3-Cable w Posts
	Flow
	Fence
	Remove Line
	Wall
	Retaining Wall (Plan View)
	W-Beam w Posts










Existing Utilities

	Existing Electrical
	Existing Fiber Optic Line
	Existing TV Fiber Optic
	Existing Gas Pipe
	Existing Overhead Utility Line
	Existing Power
	Existing Fuel Pipeline
	Existing Undefined Above Ground Pipe Line
	Existing Sanitary Sewer
	Existing Sanitary Force Main
	Existing Storm Drain
	Existing Storm Drain Force Main
	Existing Culvert
	Existing Telephone Line
	Existing TV Line
	Existing Water or Steam Line
	Existing Under Drain
	Existing Slotted Drain
	Existing Conduit
	Existing Conductor
	Existing Down Guy Wire Down Guy
	Existing Underground Vault or Lift Station




Proposed Utilities

	24 Inch Pipe
	Reinforced Concrete Pipe
	Under Drain
	Edge Drain

Traffic Utilities

	Conductor
	Fiber Optic
	Existing Loop Detector
	Existing Double Micro Loop Detector
	Micro Loop Detector Double
	Existing Micro Loop Detector
	Micro Loop Detector
	Signal Head with Mast Arm
	Existing Signal Head with Mast Arm

Sign Structures














	Existing Overhead Sign Structure
	Existing Overhead Sign Structure Cantilever
	Overhead Sign Structure Cantilever

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
09-23-16	Added and Revised Items, Organized by Functional Groups










This document was originally issued and sealed by
Roger Weigel,
Registration Number
PE-2930,
on 09/23/16 and the original document is stored at the
North Dakota Department
of Transportation

Line Styles









Right Of Way

	Easement
	Existing Easement
	Right of Way
	Existing Right of Way
	Existing Right of Way Railroad
	Existing Right of Way Not State Owned
	Existing Government Lot Line
	Existing Adjacent Block Lines
	Existing Adjacent Lot Lines
	Existing Adjacent Property Line
	Existing Adjacent Subdivision Lines
	Sight Distance Triangle Line
	Dimension Leader







Boundary Control



	Existing City Corporate Limits or Reservation Boundary
	Existing State or International Line
	Existing Township
	Existing County
	Existing Section Line
	Existing Quarter Section Line
	Existing Sixteenth Section Line
	Existing Centerline
	Tangent Line

Cross Sections and Typicals



	Existing Ground
	Existing Topsoil (Cross Section View)
	Existing Ground Void (Not Surveyed)
	Existing Concrete
	Existing Aggregate (Cross Section View)
	Existing Curb and Gutter (Cross Section View)
	Existing Asphalt (Cross Section View)
	Existing Reinforcement Rebar

Geotechnical



	Geotextile Fabric Type D
	Geogrid
	Geotextile Fabric Type R
	Geotextile Fabric Type R1
	Geotextile Fabric Type RR
	Geotextile Fabric Type S

	Subgrade Reinforcement
	Failure Line







Countours

	Depression Contours
	Supplemental Contour



Profile

	Subgrade, Subcut or Ditch Grade
	Topsoil Profile










Striping

	Centerline Pavement Marking
	Barrier with Centerline Pavement Marking
	Barrier Pavement Marking
	Stripe 4 IN Dotted Extension White
	Stripe 8 IN Dotted Extension White
	Stripe 8 IN Lane Drop








Pavement Joints

	Doweled Joint
	Tie Bar 30 Inch 4 Foot Center to Center
	Tie Bar 18 Inch 3 Foot Center to Center
	Tie Bar at Random Spacing






Bridge Details

	Hidden Object
	Small Hidden Object
	Large Hidden Object
	Phantom Object
	Centerline Main
	Centerline
	Existing Ground (Details)
	Existing Conditions
	Sheet Piling

Erosion Control

	Limits of Const Transition Line
	Bale Check
	Rock Check
	Floating Silt Curtain
	Silt Fence
	Excavation Limits
	Fiber Rolls

Environmental

	Wetland Mitigation
	Existing Wetland Easement USFWS
	Existing Wetland Jurisdictional
	Existing Wetland
	Tree Row

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
09-23-16	Added and Revised Items, Organized by Functional Groups

















































































This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930 , on 09/23/16 and the original document is stored at the North Dakota Department of Transportation

Symbols

	North Arrow (Half Scale)		Attenuation Device		Existing Railroad Battery Box		Existing Delineator Type E										
	Truck Mounted Attenuator		Diamond Grade Delineator Type A		Existing Bush or Shrub		Existing EFB Misc										
	Type I Barricade		Diamond Grade Delineator Type B		Existing Gas Cap or Stub		Existing Flashing Beacon										
	Type II Barricade		Diamond Grade Delineator Type C		Existing Sanitary Cap or Stub		Existing Pipe Mounted Flasher										
	Type III Barricade		Diamond Grade Delineator Type D		Existing Storm Drain Cap or Stub		Existing Pad Mounted Feed Point										
	Catch Basin		Diamond Grade Delineator Type E		Existing Water Cap or Stub		Existing Pipe Mounted Feed Point with Pad										
	Cairn or Stone Circle		Flexible Delineator		Existing Sanitary Cleanout		Existing Pole Mounted Feed Point										
	Video Detection Camera		Flexible Delineator Type A		Existing Concrete Foundation		Existing Railroad Frog										
	Storm Drain Cap or Stub		Flexible Delineator Type B		Existing Traffic Signal Controller		Existing Snow Gate 18										
	Corrugated Metal End Section 18 Inch		Flexible Delineator Type C		Existing Pad Mounted Signal Controller		Existing Snow Gate 28										
	Corrugated Metal End Section 24 Inch		Flexible Delineator Type D		Existing Sixteenth Section Corner		Existing Snow Gate 40										
	Corrugated Metal End Section 30 Inch		Flexible Delineator Type E		Existing Quarter Section Corner		Existing Headwall										
	Corrugated Metal End Section 36 Inch		Delineator Type A		Existing Section Corner		Existing Pedestrian Head with Number										
	Corrugated Metal End Section 42 Inch		Delineator Type A Reset		Existing Railroad Crossbuck		Existing Signal Head										
	Corrugated Metal End Section 48 Inch		Delineator Type B		Existing Satellite Dish		Existing Sprinkler Head										
	Concrete Foundation		Delineator Type B Reset		Existing Fuel Dispensers		Existing Fire Hydrant										
	Ground Connection Conductor		Delineator Type C		Existing Flexible Delineator Type A		Existing Catch Basin Drop Inlet										
	Neutral Connection Conductor		Delineator Type D		Existing Flexible Delineator Type B		Existing Curb Inlet										
	Phase 1 Connection Conductor		Delineator Type E		Existing Flexible Delineator Type C		Existing Manhole Inlet										
	Phase 2 Connection Conductor		Delineator Drums		Existing Flexible Delineator Type D		Existing Junction Box										
	Traffic Cone		Spot Elevation		Existing Flexible Delineator Type E	<table><tr><th colspan="2">NORTH DAKOTA DEPARTMENT OF TRANSPORTATION</th></tr><tr><th colspan="2">07-01-14</th></tr><tr><th colspan="2">REVISIONS</th></tr><tr><th>DATE</th><th>CHANGE</th></tr><tr><td></td><td></td></tr></table>		NORTH DAKOTA DEPARTMENT OF TRANSPORTATION		07-01-14		REVISIONS		DATE	CHANGE		
NORTH DAKOTA DEPARTMENT OF TRANSPORTATION																	
07-01-14																	
REVISIONS																	
DATE	CHANGE																
	Signal Controller		Existing Access Control Arrow		Existing Delineator Type A												
	Pad Mounted Signal Controller		Existing Artifact		Existing Delineator Type B												
	Alignment Data Point		Existing Flashing Beacon		Existing Delineator Type C												
	Emergency Vehicle Detector		Existing Benchmark		Existing Delineator Type D												

Symbols

D-101-31

	Existing Light Standard		Existing Manhole with Valve Water		Existing Telephone Pole		Existing Undefined Manhole
	Existing High Mast Light Standard 10 Luminaire		Existing Water Manhole		Existing Wood Pole		Existing Undefined Pull Box
	Existing High Mast Light Standard 3 Luminaire		Existing Mile Post Type A		Existing Post		Existing Undefined Pedestal
	Existing High Mast Light Standard 4 Luminaire		Existing Mile Post Type B		Existing Pedestrian Push Button Post		Existing Undefined Valve
	Existing High Mast Light Standard 5 Luminaire		Existing Mile Post Type C		Existing Control Point CP		Existing Undefined Pipe Vent
	Existing High Mast Light Standard 6 Luminaire		Existing Reference Marker		Existing Control Point GPS-RTK		Existing Gas Valve
	Existing High Mast Light Standard 7 Luminaire		Existing RW Marker		Existing Control Point TRI		Existing Water Valve
	Existing High Mast Light Standard 8 Luminaire		Existing Utility Marker		Existing Reference Marker Point NGS		Existing Fuel Pipe Vent
	Existing High Mast Light Standard 9 Luminaire		Iron Monument Found		Existing Pull Box		Existing Gas Pipe Vent
	Existing Overhead Sign Structure Load Center		Iron Pin R/W Monument		Existing Intelligent Transportation Pull Box		Existing Sanitary Pipe Vent
	Existing Luminaire		Existing Object Marker Type I		Existing Water Pump		Existing Storm Drain Pipe Vent
	Existing Light Standard Luminaire		Existing Object Marker Type II		Existing Slotted Reinforced Concrete Pipe		Existing Water Pipe Vent
	Existing Federal Mailbox		Existing Object Marker Type III		Existing RR Profile Spot		Existing Weather Station
	Existing Private Mailbox		Existing Electrical Pedestal		Existing Fuel Leak Sensors		Existing Ground Water Well Bore Hole
	Existing Meander Section Corner		Existing Telephone Pedestal		Existing Highway Sign		Existing Windmill or Tower
	Existing Meter		Existing Fiber Optic Telephone Pedestal		Existing Miscellaneous Spot		Existing Witness Corner
	Existing Electrical Manhole		Existing TV Pedestal		Existing Lighting Standard Pole		Flashing Beacon
	Existing Gas Manhole		Existing Fiber Optic TV Pedestal		Existing Traffic Signal Standard		Flagger
	Existing Sanitary Manhole		Existing Fuel Filler Pipes		Existing Transformer		Pipe Mounted Flasher
	Existing Sanitary Force Main Manhole		Existing Traverse PI Aerial Panel		Existing Large Evergreen Tree		Sanitary Force Main with Valve
	Existing Sanitary Manhole with Valve		Existing Pole		Existing Small Evergreen Tree		
	Existing Storm Drain Manhole		Existing Power Pole		Existing Large Tree		
	Existing Force Main Storm Drain Manhole		Existing Power Pole with Transformer		Existing Small Tree		
	Existing Force Main Storm Drain Manhole with Valve				Existing Tree Trunk		
	Existing Telephone Manhole				Existing Pad Mounted Traffic Signal Control Box		

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 07/01/14 and the original document is stored at the North Dakota Department of Transportation

Symbols



Pad Mounted Feed Point



Pipe Mounted Feed Point with Pad



Pole Mounted Feed Point



Headwall



Double Headwall with Vegetation Barrier



Single Headwall with Vegetation Barrier



Pole Mounted Head



Sprinkler Head



Fire Hydrant



Inlet Type 1



Inlet Type 2



Double Inlet Type 2



Inlet Grate Type 2



Junction Box



High Mast Light Standard 10 Luminaire



High Mast Light Standard 3 Luminaire



High Mast Light Standard 4 Luminaire



High Mast Light Standard 5 Luminaire



High Mast Light Standard 6 Luminaire



High Mast Light Standard 7 Luminaire



High Mast Light Standard 8 Luminaire



High Mast Light Standard 9 Luminaire



Relocate Light Standard



Overhead Sign Structure Load Center



Light Standard 100 Watt High Pressure Sodium Vapor Luminaire



Light Standard 1000 Watt High Pressure Sodium Vapor Luminaire



Light Standard 150 Watt High Pressure Sodium Vapor Luminaire



Light Standard 175 Watt High Pressure Sodium Vapor Luminaire



Light Standard 200 Watt High Pressure Sodium Vapor Luminaire



Light Standard 250 Watt High Pressure Sodium Vapor Luminaire



Light Standard 310 Watt High Pressure Sodium Vapor Luminaire



Light Standard 35 Watt High Pressure Sodium Vapor Luminaire



Light Standard 400 Watt High Pressure Sodium Vapor Luminaire



Light Standard 50 Watt High Pressure Sodium Vapor Luminaire



Light Standard 70 Watt High Pressure Sodium Vapor Luminaire



Light Standard 700 Watt High Pressure Sodium Vapor Luminaire



Manhole



Manhole 48 Inch



Sanitary Force Main Manhole



Sanitary Sewer Manhole



Storm Drain Manhole



Storm Drain Manhole with Inlet



Reset Mile Post



Mile Post Type A



Mile Post Type B



Mile Post Type C



Right of Way Marker



Tubular Marker



Alignment Monument



Iron Pin Reference Monument



Object Marker Type I



Object Marker Type II



Object Marker Type III



Caution Mode Arrow Panel



Back to Back Vertical Panel Sign



Double Direction Arrow Panel



Left Directional Arrow Panel



Right Directional Arrow Panel



Sequencing Arrow Panel



Truck Mounted Arrow Panel



Power Pole



Wood Pole



Pedestrian Push Button Post



Property Corner



Pull Box



Intelligent Transportation Pull Box



Sanitary Pump



Storm Drain Pump



Reinforced Pavement



Reinforced Concrete End Section 15 Inch



Reinforced Concrete End Section 18 Inch



Reinforced Concrete End Section 24 Inch



Reinforced Concrete End Section 30 Inch



Reinforced Concrete End Section 36 Inch



Reinforced Concrete End Section 42 Inch



Reinforced Concrete End Section 48 Inch



Reinforced Concrete End Section 54 Inch



Reset Right of Way Marker



Reset USGS Marker



Right of Way Markers



Riser 30 Inch



Continuous Split Barrel Sample



Flight Auger Sample



Split Barrel Sample



Thinwall Tube Sample



Highway Sign



SNOW GATE 18 FT



SNOW GATE 28 FT



SNOW GATE 40 FT



Standard Penetration Test



Transformer



Inclinometer Tube



Underdrain Cleanout



Excavation Unit






Water Valve

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by
Roger Weigel,
Registration Number
PE-2930,
on 07/01/14 and the original document is stored at the
North Dakota Department
of Transportation

Perforated Tube

- Notes:
1. Torque slip base bolts as specified by manufacturer.
 2. Use anchor with 43.9 KSI yield strength and 59.3 KSI tensile strength.
 3. Provide 4" vertical clearance for anchor or breakaway base. Measure the 4"x60" measurement above and below post location and back and ahead of post.
 4. In concrete sidewalk, use same anchor without wings.
 5. Provide more than 7' between the first and fourth posts of a four post sign.





Telescoping Perforated Tube						
Number of Posts	Post Size in.	Wall Thick-ness Gauge	Sleeve Size in.	Wall Thick-ness Gauge	Slip Base	Anchor Size without Slip Base in.
1	2	12			No	2 1/4
1	2 1/4	12			No	2 1/2
1	2 1/2	12			(A)	3
1	2 1/2	10			Yes	
1	2 1/4	12	2	12	Yes	
1	2 1/2	12	2 1/4	12	Yes	
2	2	12			No	2 1/4
2	2 1/4	12			No	2 1/2
2	2 1/2	12			Yes	
2	2 1/2	12			Yes	
2	2 1/4	10	2	12	Yes	
2	2 1/2	12	2 1/4	12	Yes	
3 & 4	2 1/2	12			Yes	
3 & 4	2 1/2	10			Yes	
3 & 4	2 1/2	12	2 1/4	12	Yes	
3 & 4	2 1/4	12	2	12	Yes	
3 & 4	2 1/2	10	2 3/16	10	Yes	

Properties of Telescoping Perforated Tube						
Tube Size in.	Wall Thickness in.	U.S. Standard Gauge	Weight per Foot lbs.	Moment of Inertia in. ⁴	Cross Sec. Area in. ²	Section Modulus in. ³
1 1/2 x 1 1/2	0.105	12	1.702	0.129	0.380	0.172
2 x 2	0.105	12	2.416	0.372	0.590	0.372
2 1/4 x 2 1/4	0.105	12	2.773	0.561	0.695	0.499
2 3/8 x 2 3/8	0.135	10	3.432	0.605	0.841	0.590
2 1/2 x 2 1/2	0.105	12	3.141	0.804	0.803	0.643
2 1/2 x 2 1/2	0.135	10	4.006	0.979	1.010	0.785






Top Post Receiver Data Table						
Square Post Sizes (B)	A	B	C	D	E	F
2 3/16"x10 ga.	1 5/16"	2 1/2"	3 1/2"	2 5/32"	1 33/64"	1 7/8"
2 1/2"x10 ga.	1 3/32"	2 1/2"	3 5/16"	5/8"	1 21/32"	1 3/4"

- (A) Use breakaway base when support is placed in weak soils. Engineer determines if soils are weak.
- (B) For additional wind load, insert the 2 3/8"x10 ga. into 2 1/2"x10 ga.



NORTH DAKOTA DEPARTMENT OF TRANSPORTATION		This document was originally issued and sealed by Kirk J Hoff, Registration Number PE- 4683, on 10/03/19 and the original document is stored at the North Dakota Department of Transportation
2-28-14		
REVISIONS		
DATE	CHANGE	
9-27-17 10-03-19	Updated to active voice New Design Engr PE Stamp	

U-Channel Post



Alternate A Steps of Installation:


- a) Drive anchor unit to within 12" of ground level.
b) Establish proper assembly by lining up bottom hole of retainer strap with 6th hole from the top of the anchor unit.
c) Assemble strap to back of anchor unit using 5/16"x2" bolt, lock washer and nut.
d) Rotate strap 90° to left.
- a) Drive anchor unit to 4" above ground.
b) Rotate strap to vertical position.
- a) Place 5/16"x2" bolt, lock washer and nut in bottom of sign post to facilitate alignment of sign post with proper hole in anchor unit.
b) Alternately tighten two connector bolts.
- Complete assembly by tightening 5/16"x2" bolt (this fastens sign post to retainer strap).
- Properly nest base post, strap, and sign post. Proper nesting occurs when all flat surfaces of the base post, strap, and sign post at the bolts have full contact across the entire width.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
2-28-14	
REVISIONS	
DATE	CHANGE
9-27-17 10-03-19	Updated to active voice New Design Engr PE Stamp


This document was originally issued and sealed by
Kirk J Hoff,
Registration Number
PE- 4683,
on 10/03/19 and the original document is stored at the
North Dakota Department
of Transportation

CONSTRUCTION SIGN DETAILS
TERMINAL AND GUIDE SIGNS


D-704-9



G20-1-60
Legend: black (non-refl)
Background: orange




G20-1b-60
Legend: black (non-refl)
Background: orange




G20-2-48
Legend: black (non-refl)
Background: orange




G20-4b-36
Legend: black (non-refl)
Background: orange




G20-50a-72
Legend: black (non-refl)
Background: orange




G20-52a-72
Legend: black (non-refl)
Background: orange




G20-55-96
Legend: black (non-refl)
Background: orange




E5-1(L or R)-48
Legend: white
Background: green (orange optional)




M4-8-36
Legend: black (non-refl)
Background: orange




M4-9(L or R)-30 & M4-9-30
Legend: black (non-refl)
Background: orange




E5-1-48




G20-50a-72
G20-52a-72



M4-9(L or R)-30
Right or Left



M4-9(L or R)-30
Advanced Right or Left



M4-9-30
Straight

ARROW DETAILS


NOTES:
(A) Arrow may be right or left of the legend to indicate construction to the right or left.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-13-13	
REVISIONS	
DATE	CHANGE
8-17-17 10-03-19	Added sign & background color New Design Engineer PE Stamp

This document was originally issued and sealed by
Kirk J Hoff,
Registration Number
PE- 4683,
on 10/03/19 and the original document is stored at the
North Dakota Department
of Transportation


CONSTRUCTION SIGN DETAILS
REGULATORY SIGNS

D-704-10




R1-50P-24

Legend: black (non-refl)
Background: white




R11-3c-60

Legend: black (non-refl)
Background: white




R2-1aP-24

Legend: black (non-refl)
Background: white



R11-4a-60

Legend: black (non-refl)
Background: white



R11-2a-48


Legend: black (non-refl)
Background: white

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-13-13	
REVISIONS	
DATE	CHANGE
8-17-17 10-03-19	Revised sign number New Design Engineer PE Stamp

This document was originally
issued and sealed by
Kirk J Hoff,
Registration Number
PE- 4683,
on 10/03/19 and the original
document is stored at the
North Dakota Department
of Transportation


CONSTRUCTION SIGN DETAILS
WARNING SIGNS

D-704-11




W5-8-48

Legend: black (non-refl)
Background: orange




W8-53-48

Legend: black (non-refl)
Background: orange




W8-56-48

Legend: black (non-refl)
Background: orange




W5-9-48

Legend: black (non-refl)
Background: orange




W8-54-48

Legend: black (non-refl)
Background: orange




W9-3a-48

Legend: black (non-refl)
Background: orange



W8-9a-48

Legend: black (non-refl)
Background: orange





W8-55-48

Legend: black (non-refl)
Background: orange

WORD	LETTER SPACING
AHEAD	Standard
200 FT	Standard
350 FT	Standard
500 FT	Standard
1000 FT	Reduce 40%
1500 FT	Reduce 40%
1/2 MILE	Reduce 50%
1 MILE	Standard

* DISTANCE MESSAGES




ARROW DETAILS

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-13-13	
REVISIONS	
DATE	CHANGE
8-17-17	Updated sign number
5-31-18	Revised sign and arrow details
10-03-19	New Design Engineer PE Stamp

This document was originally
issued and sealed by
Kirk J Hoff,
Registration Number
PE- 4683,
on 10/03/19 and the original
document is stored at the
North Dakota Department
of Transportation

BARRICADE AND CHANNELIZING DEVICE DETAILS




DELINEATOR DRUM

VERTICAL PANEL

STACKABLE
Molded rubber base (min weight 30 lbs)


Provide horizontal, circumferential, alternating orange and white retroreflective stripes 4" to 6" wide for drum markings. Use a minimum of two orange and two white stripes with the top stripe being orange for each drum. Do not exceed 3" nonretroreflectORIZED spaces between the horizontal orange and white stripes. Avoid placement of stripes on drum ribs or indentations. Use closed top drums that will not allow collection of debris. Do not place ballast on the top of drum.

Provide alternating orange and white retroreflective stripes, sloping downward in direction vehicular traffic is to pass. Place retroreflective sheeting on both sides of panel with a minimum of 270 square inches of retroreflective area facing vehicular traffic. Where the height of the retroreflective material on the vertical panel is 36 inches or more, use a stripe width of 6 inches.




TRAFFIC CONE

Provide retroreflectORIZATION of cones more than 36" in height by alternating orange and white retroreflective stripes. Use a minimum of two orange and two white stripes for each cone with the top stripe being orange. Use maximum 3" nonretroreflectORIZED space between the orange and white stripes.




TUBULAR MARKER

Provide retroreflectORIZATION of tubular markers more than 42" in height by alternating four 4" to 6" wide orange and white stripes with the top stripe being orange.



FLEXIBLE DELINEATOR

- INSTALLATION NOTES:
1. Drill installation holes to diameter and depth required by manufacturer's specifications.
 2. For removal, remove anchors and fill installation hole with an epoxy designed to bond to pavement surface.
 3. In lieu of bolted down base, use an 8" x 8" butyl pad or hot melt butyl. Remove butyl as close as possible to pavement surface.




BARRICADE BLADE DETAIL

ELEVATION VIEW

BARRICADE ASSEMBLY DETAIL
(Aluminum Barricade Rails)


NOTE: For barricade markings use alternating orange and white retroreflective stripes, sloping downward in the direction traffic is to pass. Place retroreflective sheeting on both sides of the rails with a minimum of 270 square inches of visible retroreflective area facing vehicular traffic. When the barricade length is less than 36", use a rail stripe width of 4".




TYPE I BARRICADE

TYPE II BARRICADE


BARRICADE RAIL DETAILS



SIDE VIEW




TYPE III BARRICADE



ELEVATION VIEW

BARRICADE ASSEMBLY DETAIL
(Wood or Plastic Rails)

SIDE VIEW



REFLECTOR DETAIL

ELEVATION

DELINEATORS

MINIMUM BALLAST
(For each side of barricade support)

Without Sign	4 - 25 lb sandbags
With Sign	6 - 25 lb sandbags


Note: Number of sandbags based on a wind speed of 55 MPH. Sandbags assumed to be placed at or near the ends of the skids.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-3-13	
REVISIONS	
DATE	CHANGE
9-27-17 11-01-19	Updated to active voice Revised details for Flexible Delineator


This document was originally issued and sealed by
Kirk J Hoff,
Registration Number
PE- 4683,
on 11/1/19 and the original document is stored at the North Dakota Department of Transportation

CONSTRUCTION SIGN PUNCHING AND MOUNTING DETAILS


Note: In curb sections, place signs a minimum horizontal distance of 2' from face of the curb to near edge of the sign.




TYPICAL SECTION
(48" x 48" diamond warning sign shown)




24" x 24"
ROUTE MARKER
ASSEMBLY




36" x 36"
ROUTE MARKER
ASSEMBLY




18" x 18"
DIAMOND SIGN




108" x 48" SIGN




48" x 48" DIAMOND SIGN
(with 30" x 30" secondary sign)




48" x 48" DIAMOND SIGN
(with 30" x 24" secondary sign)




R1-2-60 - YIELD SIGN




W14-3-64 - PENNANT SIGN




R1-1-48 - STOP SIGN
(with R6-1-54 sign as required)




R1-1-48 - STOP SIGN
(with R1-50P-24 sign as required)




48" x 48" SIGN
(with R6-1-54 sign as required)




48" x 48" SIGN
(with R2-1aP-24 sign as required)




24" x 36" SIGN




30" x 24" SIGN




72" x 36" SIGN




72" x 24" SIGN




60" x 24" SIGN



48" x 24" SIGN



PORTABLE SIGN SUPPORT
LOW-MOUNTING HEIGHT



PORTABLE SIGN SUPPORT
HIGH-MOUNTING HEIGHT

NOTES:

1. Sign Supports: Galvanize or paint supports. Minimum post sizes are 2.5 lb/ft u-channel or 2" x 2" x 12 gauge steel perforated tube, except where noted. When installing signs on u-channel, minimum post size for assemblies containing a secondary sign is 3.0 lb/ft. Post sizes based on a wind speed of 55 MPH.

Place signs over 50 square feet on 2½" x 2½" perforated tube supports as a minimum.

Do not attach guy wires to sign supports. Attach wind beams behind sign panels when used with u-posts.
2. Sign Panels: Provide sign panels made of 0.100" aluminum, ½" plywood, or other approved material, except where noted. Punch all holes round for ⅝" bolts.
3. Alternate Messages: Install and remove alternate message signs on reflectorized plate (without borders) as required. (i.e. "Left" and "Right" message on lane closure sign)
4. Route Marker Auxiliary Signs: Provide route marker auxiliary signs, such as the cardinal direction and directional arrows, with a background and legend that match the route marker they are used with:

Interstate - white legend on blue background
Interstate Business Loop - white legend on green background
US and State - black legend on white background
County - yellow legend on blue background

5. Vertical Clearance: Install signs with a vertical clearance of 5'-0" (see TYPICAL SECTION). In areas where parking or pedestrian movements are likely or the view of the sign may be obstructed, install signs with a vertical clearance of 7'-0" from the top of the curb or from the near edge of the driving lane in absence of a curb.

The vertical clearance to secondary signs is 1'-0" less than the vertical clearance stated above.

Provide a minimum clearance of 7'-0" from the ground at the post for signs with an area exceeding 50 square feet.

6. Portable Signs: Provide portable signs that meet the vertical clearance stated above when it is necessary to place signs within the pavement surface.

Use of low-mounting height (minimum 12" vertical clearance) portable signs for 5 days or less, is allowed as long as the view of the sign is not obstructed. Time delays caused by unforeseen circumstances, such as equipment breakdown, rain, subgrade failures, etc., will not accrue towards the 5 day period. Use of R9-8 through R9-11a series, W1-6 through W1-8 series, M4-10, and E5-1 is allowed for longer than 5 days.

Restrict signs mounted on portable sign supports shown in the LOW-MOUNTING HEIGHT and HIGH-MOUNTING HEIGHT details to a maximum surface area of 16 square feet.

MINIMUM BALLAST
(For each side of sign support base)

Sign Panel Mounting Height (ft)	Number of 25 lb sandbags for 4' x 4' sign panel
1'	6
5'	8
7'	10

Note: The number of sandbags are based on a wind speed of 55 MPH. Place sandbags at or near the ends of skids.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-4-13	
REVISIONS	
DATE	CHANGE
11-14-13	Revised Note 6
9-27-17	Updated to active voice
11-01-19	Revised 60"x24" sign detail

This document was originally issued and sealed by

Kirk J Hoff,
Registration Number
PE-4683,
on 11/1/19 and the original document is stored at the North Dakota Department of Transportation


ROAD CLOSURE LAYOUTS

- Notes
1. Variables
- S = Numerical value of speed limit or 85th percentile.
W = The width of taper in feet.
L = Minimum length of taper, S x W for freeways, expressways, and other roads with speeds of 45 mph or greater, or $W \times S^2/60$ for urban, residential, and other streets with speeds of 40 mph or less.
2. Place barricades on moveable assemblies and signs on portable assemblies when located on roadway.
3. Place delineator drums, barricades or cones for tapering traffic at dimension "S" and for tangents space at 2 times dimension "S".
4. Place Sequencing Arrow Panels at the beginning of the taper when possible. Where shoulder width does not provide sufficient room, move the panel closer to the work area and place on roadway surface. See Shoulder Closure Standard Drawing.
- Use Type A on roadways with slow moving traffic speeds and low volume (25 mph or less and 750 ADT or less).
Use Type B on roadways with moderate traffic speeds and volumes (40 mph or less and 5000 ADT or less).
Use Type C on roadways with high traffic speeds and volumes (over 40 mph or over 5000 ADT).
5. Re-establish speed. Determine exact speed limit in the field, dependent on location and conditions.
6. Determine the reduced speed limit based on the in-place speed limit before construction. Where speed reductions exceed 30 mph, install a second speed limit sign with the desired speed reduction (not to exceed 30 mph.) Place the second speed limit sign at $\frac{1}{2}$ B.
7. Install flags on warning signs in urban areas when signs are not portable.
8. Cover existing speed limit signs within reduced speed zones.
9. Where necessary, engineer will determine safe speed.
10. As an option, use portable sign supports in lieu of post mounted signs in accordance with NDDOT Standard Drawing D-704-14.
11. Sign G20-55-96 is not required if this standard is part of other traffic control, or the work is less than 15 days.
12. Recommend using 40 mph speed limit in vicinity of workers, unless location and conditions dictate otherwise.

ADVANCE WARNING SIGN SPACING			
Road Type	Distance Between Signs Min. (ft)		
	A	B	C
Urban - Low Speed (30 mph or less)	150	150	150
Urban - Low Speed (over 30 to 40 mph)	280	280	280
Urban - High Speed (over 40 mph to 50 mph)	360	360	360
Rural - High Speed (over 50 mph to 65 mph)	720	720	720
Urban Expressway and Freeway (55 mph to 60 mph)	850	1350	2200
Rural Expressway and Freeway (70 mph to 75 mph)	1000	1500	2640
Interstate/4-Lane Divided (Maintenance and Surveying)	750	1000	1500

KEY	
	Type III barricade
	Sign
	Delineator drum
	Tubular markers
	Work area
	Flagger
	Sequencing arrow panel
	Vertical panels back to back

Longitudinal Buffer Space	
Speed (mph)	Length Min (feet)
20	115
25	155
30	200
35	250
40	305
45	360
50	425
55	495
60	570
65	645
70	730
75	820



TYPE A
TEMPORARY ROAD CLOSURE
Sign R2-1aP-24 not needed on project using pilot car.

TYPE B
ROAD CLOSURE WITH A DIVERSION
Two lane highway where roadway is closed and detour provided (signing shown for one direction only). Use on bridge and culvert installation with $\frac{1}{2}$ mile or less closure.


TYPE C
HALF ROAD CLOSURE ON A MULTI-LANE, HIGH SPEED HIGHWAY
4 lane undivided highway with half the roadway closed.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-27-13	
REVISIONS	
DATE	CHANGE
8-17-17	Updated notes & Speed Limit signs
11-01-19	Sign, Notes, and Pmnt Mkg updates

This document was originally issued and sealed by
Kirk J Hoff,
Registration Number
PE- 4683,
on 11/01/19 and the original document is stored at the
North Dakota Department
of Transportation

TERMINAL AND SEAL COAT SIGN LAYOUTS

D-704-20



1. Place barricades on moveable assemblies and signs on portable assemblies when located on roadway.
 2. Determine the exact speed limit in the field, based on location and conditions.
 3. Determine the reduced speed limit based on the in place speed limit before construction. Where speed limit reductions exceed 30 MPH, install a second speed limit sign with the desired speed reduction (not to exceed 30 MPH.) Place the second speed limit sign at ½ B.
 4. Install flags on warning signs in urban areas when signs are not portable. Mount 24 inch square flags perpendicular to the edges of the sign, and at such a distance above the edge that the flag does not touch the sign when limp.
 5. Cover existing speed limit signs within a reduced speed zone.
 6. On seal coat projects, place signs R2-1-48, R2-1aP-24, R4-1-48, W22-8-48 and W20-52P-54 after all important intersections and at five mile intervals. Place sign W8-12-48 after all important intersections and at 2 mile intervals until short term center line pavement marking is placed.
 7. As an option, use portable sign supports in lieu of post mounted signs in accordance with the NDDOT Standard Drawing D-704-14.
 8. Cover or remove speed limit signs from layout Type H when loose aggregate is removed.
 9. Install sign G20-1b-60 when work is suspended for winter.
 10. Use other traffic control layouts in immediate work areas. Place sign R2-1aP-24 below speed limit signs in reduced speed limit work areas.
 11. Sign G20-55-96 is not required if work is less than 15 days.
 12. Recommend using 40 mph speed limit in vicinity of workers, unless location and conditions dictate otherwise.


ADVANCE WARNING SIGN SPACING			
Road Type	Distance Between Signs Min. (ft)		
	A	B	C
Urban - Low Speed (30 mph or less)	150	150	150
Urban - Low Speed (over 30 to 40 mph)	280	280	280
Urban - High Speed (over 40 mph to 50 mph)	360	360	360
Rural - High Speed (over 50 mph to 65 mph)	720	720	720
Urban Expressway and Freeway (55 mph to 60 mph)	850	1350	2200
Rural Expressway and Freeway (70 mph to 75 mph)	1000	1500	2640
Interstate/4-Lane Divided (Maintenance and Surveying)	750	1000	1500

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-27-13	
REVISIONS	
DATE	CHANGE
8-17-17 11-01-19	Updated notes & sign numbers. Note & sign updates.

This document was originally issued and sealed by
 Kirk J Hoff,
 Registration Number
 PE- 4683,
 on 11/1/19 and the original document is stored at the
 North Dakota Department
 of Transportation

CONSTRUCTION TRUCK AND TEMPORARY DETOUR LAYOUTS

D-704-22




Notes

- Place barricades on a moveable assemblies and signs on portable assemblies when located on roadway.
- Where necessary, safe speed to be determined by the Engineer.
- Determine the reduced speed limit based on the in-place speed limit before construction. Where speed reductions exceed 30 mph, install a second speed limit sign with the desired speed reduction (not to exceed 30 mph.) Place the second speed limit sign at $\frac{1}{2}$ B.
- Install flags on warning signs in urban areas when signs are not portable. Mount 24 inch square flags perpendicular to the edges of the sign, and at such a distance above the edge that the flag does not touch the sign when limp.
- Cover existing speed limit signs within a reduced speed zone.
- Covered (when approved by engineer) or obliterated pavement marking measured as Obliteration of Pavement Marking.
- As an option, use portable sign supports in lieu of post mounted signs in accordance with NDDOT Standard Drawing D-704-14.
- Install sign G20-1b-60 when work is suspended for winter.
- If existing stop sign is in place, a 48" stop sign is not required.
- Sign G20-55-96 is not required if layout is part of other traffic control or if work is less than 15 days.
- Recommend using 40 mph speed limit in vicinity of workers, unless location and conditions dictate otherwise.

ADVANCE WARNING SIGN SPACING			
Road Type	Distance Between Signs		
	A	B	C
Urban - Low Speed (30 mph or less)	150	150	150
Urban - Low Speed (over 30 to 40mph)	280	280	280
Urban - High Speed (over 40 mph to 50 mph)	360	360	360
Rural - High Speed (over 50 mph to 65 mph)	720	720	720
Urban Expressway and Freeway (55 mph to 60 mph)	850	1350	2200
Rural Expressway and Freeway (70 mph to 75 mph)	1000	1500	2640
Interstate/4-Lane Divided (Maintenance and Surveying)	750	1000	1500

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-27-13	
REVISIONS	
DATE	CHANGE
8-17-17 11-01-19	Update notes & sign numbers Revised sign numbers & note 7

This document was originally issued and sealed by
Kirk J Hoff,
Registration Number
PE- 4683,
on 11/1/19 and the original document is stored at the North Dakota Department of Transportation



Notes:
As an option, use portable sign supports in lieu of post mounted sign in accordance with NDDOT Standard Drawing D-704-14.


ADVANCE WARNING SIGN SPACING			
Road Type	Distance Between Signs Min. (ft)		
	A	B	C
Urban - Low Speed (30 mph or less)	150	150	150
Urban - Low Speed (over 30 to 40 mph)	280	280	280
Urban - High Speed (over 40 mph to 50 mph)	360	360	360
Rural - High Speed (over 50 mph to 65 mph)	720	720	720
Urban Expressway and Freeway (55 mph to 60 mph)	850	1350	2200
Rural Expressway and Freeway (55 mph to 60 mph)	1000	1500	2640
Interstate/4-Lane Divided (Maintenance and Surveying)	750	1000	1500

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-27-13	
REVISIONS	
DATE	CHANGE
6-24-14 8-17-17 11-01-19	Revised Note Updated notes & sign support Revised note

This document was originally issued and sealed by
Kirk J Hoff,
Registration Number
PE- 4683,
on 11/1/19 and the original document is stored at the
North Dakota Department
of Transportation

PORTABLE SIGN SUPPORT ASSEMBLY

D-704-50



- Notes:
- ① The maximum weight of the assembly is 250 pounds.
 - ② Use a 14" wheel and tire.
 - ③ Automotive and equipment axle assemblies may not be used for trailer-mounted sign supports.
 - ④ Other NCHRP 350 crash tested assemblies are acceptable.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
11-23-10	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by
Roger Weigel
Registration Number
PE- 2930 ,
on 11/23/10 and the original document is stored at the
North Dakota Department
of Transportation