

JOB # 24
NORTH DAKOTA
DEPARTMENT OF TRANSPORTATION

NH-2-003(024)032



Mc Intosh County
General Location Line 1

Deck Overlay, Erail Retrofit and Spall Repair

	STATE	PROJECT NO.	PCN	SECTION NO.	SHEET NO.
	ND	NH-2-003(024)032	22488	1	1

GOVERNING SPECIFICATIONS:
2020 Standard Specifications adopted by the North Dakota
Department of Transportation and the Supplemental Specifications
effective on the date the project is advertised.

PROJECT NUMBER \ DESCRIPTION	NET MILES	GROSS MILES
NH-2-003(024)032	NA	N/A



STATE COUNTY MAP

ND DEPARTMENT OF TRANSPORTATION
BRIDGE DIVISION

Don Ketterling

09/10/20

DocuSign



DocuSign

TABLE OF CONTENTS						STATE	PROJECT NO.	SECTION NO.	SHEET NO.
						ND	NH-2-003(024)032	2	1
PLAN SECTIONS			LIST OF STANDARD DRAWINGS						
Section	Page(s)	Description	Number	Description					
1	1	Title Sheet	D-101-1, 2,3	NDDOT Abbreviations					
2	1	Table of Contents	D-101-10	NDDOT Utility Company and Organization Abbreviations					
6	1	Environmental Notes	D-101-20, 21	Line Styles					
8	1	Quantities	D-101-30, 31,32	Symbols					
20	1	General Details	D-704-1	Attenuation Device					
100	1 - 5	Work Zone Traffic Control	D-704-5	Construction Sign Detail					
130	1	Guardrail	D-704-7	Breakaway Systems For Construction Zone Signs - Perforated Tube					
170	1 - 3	Bridges and Box Culverts	D-704-8	Breakaway Systems For Construction Zone Signs - U-Channel Post					
			D-704-9	Construction Sign Details - Terminal And Guide Signs					
			D-704-10	Construction Sign Details - Regulatory Signs					
			D-704-11, 11A	Construction Sign Details - Warning Signs					
			D-704-13	Barricade And Channelizing Device Details					
			D-704-14	Construction Sign Punching And Mounting Details					
			D-704-16	Lane Closure On A Two Lane Road Using Traffic Control Signals					
			D-704-17	Sign Layout For One Lane Closure Two Lane Roadway					
			D-704-20	Terminal And Seal Coat Sign Layouts					
			D-704-50	Portable Sign Support Assembly					
			D-704-51	Portable Precast Concrete Median Barrier (Temporary Usage)					
			D-762-4	Pavement Marking					
			D-764-1	W-Beam Guardrail General Details					
			D-764-10	Thrie Beam Transition To Double Box Beam Retrofit					
			D-764-22	Typical Grading At Bridge Ends With W-Beam Guardrail					
SPECIAL PROVISIONS									
Number	Description								
SP 69(20)	Commercial Grade Asphalt								

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	NH-2-003(024)032	6	1

NOTES

704-200 PRECAST CONCRETE MEDIAN BARRIERS – STATE FURNISHED: Obtain 25 – 2’ barriers from Steele (3840 25th Ave SE). Return barriers to Steele.

Install any missing markers on the barriers before traffic use. Include the cost of the markers in the contract unit price for "Precast Concrete Median Barrier – State Furnished".

Some 4 inch x 4 inch boards are available at the return location. Provide any additional 4 inch x 4 inch boards necessary to stack barriers. The boards will become property of the Department. Include the cost for boards in the contract unit price for "Precast Concrete Median Barrier - State Furnished".

704-450 LANE CLOSURE - SIGNAL CONTROL/FLAGGING CONTROL: Install either the signal controlled lane closure on Standard D-704-16 or the flagging controlled lane closure on Standard D-704-17.

Obtain an electrical source for traffic signals. Solar powered signals may be used. Place generators a minimum of 60 feet from the roadway centerline, unless the generator and signal are part of a trailer mounted unit.

Place utility poles and equipment a minimum of 60 feet from the roadway centerline and place power conductors a minimum of 6 inches below the ground surface. Remove poles after they are no longer necessary.

The Engineer will measure individual traffic control devices, other than the signal system and flaggers, shown on the standards. Payment will be made at the respective contract unit price.

Include the cost of either a traffic signal system or flaggers in the contract unit price for "Lane Closure – Signal Control/Flagging Control".

704-500 PORTABLE RUMBLE STRIPS (PRS): Use PRS made of rubber or engineered polymers.

Install PRS as part of the temporary traffic control when the following signs are also part of the required traffic control set up:

- "Be Prepared to Stop" (W3-4); and
- "Flagger" symbol (W20-7)

Install PRS that meet the following criteria:

- Have no adhesives or fasteners required for placement;
- Have a manufacture's speed rating that meets or exceeds the posted speed limit; and
- Each strip in the array must weigh a minimum of 100 pounds.

Use individual PRS constructed in one of the following manners:

- A single piece;
- Interlocking segments; or
- Two pieces hinged at the midpoint.

An installed array of PRS consists of a minimum of 3 individual strips.

Move rumble strips with the flagging operation. Do not place rumble strips on horizontal curves.

The Engineer will count and measure each array as one unit. Include the cost of providing, installing, maintaining, and relocating PRS in the unit price bid for "Portable Rumble Strips".

704-P01 TRAFFIC CONTROL DEVICES: The traffic control devices list has been developed using the traffic control layout sheets and the list below:


D-704-16, Sign layout for Lane Closure on a Two Lane Road Using Traffic Control Signals;



ESTIMATE OF QUANTITIES

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	NH-2-003(024)032	8	1


SPEC CODE	ITEM DESCRIPTION	UNIT	MAINLINE	TOTAL
-----	-----	----	-----	-----
103	0100 CONTRACT BOND	L SUM	1	1
202	0130 REMOVAL OF CURB & GUTTER	LF	16	16
411	0105 MILLING PAVEMENT SURFACE	SY	378	378
430	0500 COMMERCIAL GRADE HOT MIX ASPHALT	TON	42	42
602	1250 PENETRATING WATER REPELLENT TREATMENT	SY	202	202
624	3001 DOUBLE BOX BEAM RAIL RETROFIT-FREE STANDING	LF	90	90
650	0704 OVERLAY CONCRETE	CY	7.4	7.4
650	0707 DECK CONCRETE	CY	3	3
650	0710 CLASS 1-H REMOVAL	SY	170	170
650	0711 CLASS 2-H REMOVAL	SY	34	34
650	0712 CLASS 3-H REMOVAL	SY	2	2
702	0100 MOBILIZATION	L SUM	1	1
704	0100 FLAGGING	MHR	150	150
704	1000 TRAFFIC CONTROL SIGNS	UNIT	1,579	1,579
704	1018 LANE CLOSURE-SIGNAL CONTROL/FLAGGING CONTROL	EA	1	1
704	1041 ATTENUATION DEVICE-TYPE B-55	EA	2	2
704	1048 PORTABLE RUMBLE STRIPS	EA	2	2
704	1052 TYPE III BARRICADE	EA	2	2
704	1060 DELINEATOR DRUMS	EA	10	10
704	1500 OBLITERATION OF PAVEMENT MARKING	SF	25	25
704	3510 PRECAST CONCRETE MED BARRIER-STATE FURNISHED	EA	25	25
762	0420 SHORT TERM 4IN LINE-TYPE R	LF	3,424	3,424
762	0426 SHORT TERM 24IN LINE-TYPE R	LF	24	24
762	1104 PVMT MK PAINTED 4IN LINE	LF	252	252
764	0150 REMOVE & RESET GUARDRAIL	LF	233	233
930	9612 SPALL REPAIR	SF	143	143



Milling Transition: Bridge 3-032.215

X	Begin Station	Y	End Station	YY
50 ft.	1039+97.5	2 in.	1040+47.5	1 in.
50 ft.	1040+92.5	1 in.	1041+42.5	2 in.

SPEC	CODE	BID ITEM	UNIT	Quantity
411	0105	Milling Pavement Surface		
		Sta 1039+97.5 to Sta 1040+47.5	SY	189
		Sta 1040+92.5 to Sta 1041+42.5	SY	189
		Total	SY	378



Paving Transition: Bridge 3-032.215

X	Begin Station	Y	End Station	YY
50 ft.	1039+97.5	2 in.	1040+47.5	2 in.
50 ft.	1040+92.5	2 in.	1041+42.5	2 in.

SPEC	CODE	BID ITEM	UNIT	Quantity
430	0500	Commercial Grade Hot Mix Asphalt		
		Sta 1039+97.5 to Sta 1040+47.5	TON	21
		Sta 1040+92.5 to Sta 1041+42.5	TON	21
		Total	TON	42

*Drawing is not to scale.








Milling and Paving Transitions

Bridge Deck Overlay, Rail Retrofit




ND Hwy 3

West of Wishek

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	NH-2-003(024)032	100	2



Traffic Control Typical Sections
Bridge Deck Overlay, Rail Retrofit
ND Hwy 3
West of Wishek



PORTABLE RUMBLE STRIPS ARRAY
TYPES OF MOVEMENT AND MAXIMUM ALLOWANCES

- Notes:
1. Number of devices were calculated using 40 mph. Speed determined in the field based on location and conditions.
 2. Re-establish the speed limit. Determine the exact speed limit in the field, dependent on location and conditions.
 3. Sign R2-1aP-24 is not required when pilot car operation is used.
 4. Rumble strips are not used on a non paved surface or in a pre-construction speed zone of 25 mph or less.

ADVANCE WARNING SIGN SPACING			
Road Type	Distance Between Signs Min. (ft)		
	A	B	C
Urban - Low Speed (30 mph or less)	150	150	150
Urban - Low Speed (over 30 to 40 mph)	280	280	280
Urban - High Speed (over 40 mph to 50 mph)	360	360	360
Rural - High Speed (over 50 mph to 65 mph)	720	720	720


KEY

Work area

Flagger

Sign

S = Numerical value of speed limit or 85th percentile.




TWO-LANE PORTABLE RUMBLE STRIPS

Bridge Deck Overlay, Rail Retrofit

ND Hwy 3

West of Wishek




PORTABLE RUMBLE STRIPS ARRAY DETAIL

PORTABLE RUMBLE STRIPS
AT TEMPORARY ROAD CLOSURE

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	NH-2-003(024)032	130	1

23 USC § 409 Documents
NDDOT Reserves All Objections



SPEC CODE	BID ITEM	QTY	UNIT
764 0150	REMOVE & RESET GUARDRAIL		
	Sta 1039+91.11 to 1040+49.25 Lt	58.1	LF
	Sta 1039+91.11 to 1040+49.25 Rt	58.1	LF
	Sta 1040+90.75 to 1041+48.89 Lt	58.1	LF
	Sta 1040+90.75 to 1041+48.89 Rt	58.1	LF
	Total	232.4	LF

- (A) Thrie beam rail section (double thickness)
(B) Thrie beam rail section




Thrie/W-Beam Guardrail Layout
At Both Ends of Bridge

Creek West of Wishek
RP 32.215


ND 3




STATE	PROJECT NUMBER	SECTION NO.	SHEET NO.
ND	NH-2-003(024)032	170	1




PLAN




(SPALL REPAIR)
A-A



Hatched area indicates existing double box beam steel rail retrofit to be removed. Include the removal of the existing rail retrofit in the contract unit price for "Double Box Beam Rail Retrofit-Free Standing."



Hatched area indicates curb spall.



DECK DRAIN DETAIL

NOTES:

- 100 SCOPE OF WORK: Work at this site consists of placing a concrete deck overlay, removing the existing rail retrofit and installing double box beam rail retrofit, and barrier repair to the existing curb
- 624 DOUBLE BOX BEAM RAIL RETROFIT: Remove the existing railing and posts and cut all existing anchor bolts flush with the top of the concrete and cover with silicone. Include the cost to remove existing rail retrofit in the bid item "Double Box Beam Rail Retrofit - Free Standing."
- Include all cost for furnishing and installing the guardrail connection plates and for sawing and removing portions of the curb in the contract unit price for "Double Box Beam Rail Retrofit - Free Standing."

- 930 SPALL REPAIR: The curb has spalling as shown in the A-A views in multiple locations.
- Remove all unsound concrete and replace it with new concrete material. Use a 15 pound maximum size chipping hammer on any unsound concrete. Provide sharp, neat lines at least 1 inch deep at the edges of the repair areas. Produce these sharp, neat lines by saw cutting or other means approved by the Engineer.
- Sand blast clean the existing concrete and exposed reinforcing steel. Repair any damaged epoxy coating on the reinforcing steel according to Section 612.04 E. Clean the existing concrete surface by high pressure water blasting. After the surface has dried and just before the patching material is placed, coat the surface with an epoxy bonding agent.
- Use a concrete material that is specifically intended for patching concrete. This patching material may be SikaTop 123 Plus (Sika Corporation), Duraltop Gel (Euclid Chemical Company), ThoRoc HB2 (BASF Corporation), or an approved equal repair mortar. Cure the material as recommended by the manufacturer.
- The curb spall repair quantity is based on the assumption that the area to be repaired is to the dimensions shown in the elevation. The actual limits of the repair are to be determined by the Engineer in the field. It is also assumed that the spall repair area is approximately 3" deep. Include all labor, equipment and materials needed to repair the spall areas in the bid item "Spall Repair."

BRIDGE BID ITEMS

SPEC	CODE	ITEM DESCRIPTION	UNIT	QUANTITY
602	1250	PENETRATING WATER REPELLENT TREATMENT	SY	202.0
624	3001	DOUBLE BOX BEAM RAIL RETROFIT-FREE STANDING	LF	90.0
650	0704	OVERLAY CONCRETE	CY	7.4
650	0707	DECK CONCRETE	CY	3
650	0710	CLASS 1-H REMOVAL	SY	170
650	0711	CLASS 2-H REMOVAL	SY	34
650	0712	CLASS 3-H REMOVAL	SY	2
930	9612	SPALL REPAIR	SF	143



CREEK WEST OF WISHEK

BRIDGE LAYOUT

ND DEPARTMENT OF TRANSPORTATION
BRIDGE DIVISION




08/28/20
Jon Ketterhohn

DocuSign

	STATE	PROJECT NUMBER	SECTION NO.	SHEET NO.
	ND	NH-2-003(024)032	170	2

NOTE:

- 650 OVERLAY CONCRETE CRACK SEALING: After the bridge deck overlay has cured, the Engineer will perform a visual inspection of the bridge deck to determine the need for crack sealing. Repair all cracks designated by the Engineer.
- Wash the deck surface with a minimum water pressure of 3,000 psi. Perform a visual inspection of the bridge deck surface and mark all visible cracks appearing on the top surface 0.007" or greater in width at its widest segment or as directed by the Engineer. Air dry the wet deck a minimum of 72 hours before applying the sealer.
- Immediately before applying the sealer, clean the cracks by removing all dust and debris with compressed air. Seal the cracks with a two-part epoxy in accordance to the manufacturer's recommendations. Chase crack with the sealant application to limits of crack, including those portions that are narrower than 0.007" wide. The epoxy sealer may be Paulco TE-2501 (Viking Paints, Inc.), Dural 50 LM (Euclid Chemical Co.), TK-9000 or TK-2110 (TK Products), or an approved equal. Include all work and materials associated with the deck crack sealing in the bid item "Overlay Concrete."




CREK WEST OF WISHEK

DECK OVERLAY DETAILS

?	This is a special text character used in the labeling of existing features. It indicates a feature that has an unknown characteristic, potentially based on: lack of description, location accuracy or purpose.		Bldg	building	CSP	corrugated steel pipe	EDM	electronic distance meter
Abn	abandoned		BV	butterfly valve	CSTES	corrugated steel traversable end section	Elev or El	elevation
Abut	abutment		ByP	bypass	C	coulomb	Ellipt	elliptical
Ac	acres		C Gdrl	cable guardrail	Co	County	Emb	embankment
Adj	adjusted		Calc	calculate	Crse	course	Emuls	emulsion/emulsified
Aggr	aggregate		Cd	candela	Ct	Court	ES	end section
Ahd	ahead		CIP	cast iron pipe	Xarm	cross arm	Engr	engineer
ARV	air release valve		CB	catch basin	Xbuck	cross buck	ESS	environmental sensor station
Align	alignment		CRS	cationic rapid setting	Xsec	cross sections	Eq	equal
Al	alley		C Gd	cattle guard	Xing	crossing	Eq	equation
Alt	alternate		C To C	center to center	Xrd	Crossroad	Evgr	evergreen
Alum	aluminum		Cl or \varnothing	centerline	Crn	crown	Exc	excavation
ADA	Americans with Disabilities Act		Cm	centimeter	CF	cubic feet	Exst	existing
A	ampere		Ch	chain	M3	cubic meter	Exp	expansion
&	and		Chnlk	chain-link	M3/s	cubic meters per second	Expy	Expressway
Appr	approach		Ch Blk	channel block	CY	cubic yard	E	external of curve
Approx	approximate		Ch Ch	channel change	Cy/mi	cubic yards per mile	Extru	extruded
ACP	asbestos cement pipe		Chk	check	Culv	culvert	FOS	factor of safety
Asph	asphalt		Chsld	chiseled	C&G	curb & gutter	F	Fahrenheit
AC	asphalt cement		Cir	circle	CI	curb inlet	FS	far side
Assmd	assumed		Cl	class	CR	curb ramp	F	farad
@	at		Cl	clay	CS	curve to spiral	Fed	Federal
Atten	attenuation		Cl F	clay fill	C	cut	FP	feed point
ATR	automatic traffic recorder		Cl Hvy	clay heavy	Dd Ld	dead load	Ft	feet/foot
Ave	Avenue		Cl Lm	clay loam	Defl	deflection	Fn	fence
Avg	average		Clnt	clean-out	Defm	deformed	Fn P	fence post
ADT	average daily traffic		Clr	clear	Deg or D	degree	FO	fiber optic
Az	azimuth		Cl&gr	clearing & grubbing	DInt	delineate	FB	field book
Bk	back		Co S	coal slack	DIntr	delineator	FD	field drive
BF	back face		C Gr	coarse gravel	Depr	depression	F	fill
Bs	backsight		CS	coarse sand	Desc	description	FAA	fine aggregate angularity
Balc	balcony		Comb.	combination	Det	detail	FS	fine sand
B Wire	barbed wire		Coml	commercial	DWP	detectable warning panel	FH	fire hydrant
Barr	barricade		Compr	compression	Dtr	detour	FI	flange
Btry	battery		CADD	computer aided drafting & design	Dia or \varnothing	diameter	Flrd	flared
Brg	bearing		Conc	concrete	Dir	direction	FES	flared end section
BI	beehive inlet		CECB	concrete erosion control blanket	Dist	distance	F Bcn	flashing beacon
Beg	begin		Cond	conductor	DM	disturbed material	FA	flight auger sample
BG	below grade		Const	construction	DB	ditch block	FL	flow line
BM	bench mark		Cont	continuous	DG	ditch grade	Ftg	footing
Bkwy	bikeway		CSB	continuous split barrel sample	Dbl	double	FM	force main
Bit	bituminous		Contr	contraction	Dn	down	Fs	foresight
Blk	block		Contr	contractor	Dwg	drawing		
Bd Ft	board feet		CP	control point	Dr	drive		
BH	bore hole		Coord	coordinate	Drwy	driveway		
BS	both sides		Cor	corner	DI	drop inlet		
Bot	bottom		Corr	corrected	D	dry density		
Blvd	Boulevard		CAES	corrugated aluminum end section	DSDS	dynamic speed display sign		
Bndry	boundary		CAP	corrugated aluminum pipe	Ea	each		
BC	brass cap		CMES	corrugated metal end section	Esmt	easement		
Brkwy	breakaway		CMP	corrugated metal pipe	E	East		
Br	bridge		CPVCP	corrugated poly-vinyl chloride pipe	EB	Eastbound		
			CSES	corrugated steel end section	Elast	elastomeric		
			CSFES	corrugated steel flared end section	EL	electric locker		
					E Mtr	electric meter		
					Elec	electric/al		

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
04-23-18 09-20-18	General Revisions General Revisions

This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930 , on 09/20/18 and the original document is stored at the North Dakota Department of Transportation

Fnd	found	ID	inside diameter	Mkg	marking	PMT	pad mounted transformer
Fdn	foundation	Inst	instrument	MA	mast arm	Pg	pages
Frac	fractional	Intchg	interchange	Matl	material	Pntd	painted
Frwy	freeway	Intmdt	intermediate	Max	maximum	Pr	pair
Frt	front	Intscn	intersection	MC	meander corner	Pnl	panel
FF	front face	Inv	invert	Meas	measure	Pk	park
F Disp	fuel dispenser	IM	iron monument	Mdn	median	PK	Parker-Kalon nail
FFP	fuel filler pipes	I Pn	Iron Pin	MD	median drain	Pa	pascal
FLS	fuel leak sensor	IP	iron Pipe	MC	medium curing	PSD	passing sight distance
Furn	furnish/ed	Jt	joint	M	mega	Pvmt	pavement
Gal	gallon	J	joule	Mer	meridian	Ped	pedestal
Galv	galvanized	Jct	junction	M	meter	Ped	pedestrian
Gar	garage	K	kelvin	M/s	meters per second	PPP	pedestrian pushbutton post
Gs L	gas line	Kn	kilo newton	M	mid ordinate of curve	Pen.	penetration
G Reg	gas line regulator	Kpa	kilo pascal	MGS	Midwest Guardrail System	Perf	perforated
GMV	gas main valve	Kg	kilogram	Mi	mile	Per.	perimeter
G Mtr	gas meter	Kg/m3	kilogram per cubic meter	MM	mile marker	PL	pipeline
GSV	gas service valve	Km	kilometer	MP	mile post	PI	place
GVP	gas vent pipe	K	Kip(s)	MI	milliliter	P&P	plan & profile
GV	gate valve	LS	Land Surveyor (licensed)	Mm	millimeter	PL	plastic limit
Ga	gauge	LSIT	Land Surveyor In Training	Mm/hr	millimeters per hour	P Cap	plastic cap
Geod	geodetic	Ln	lane	Min	minimum	PI or 	plate
GIS	Geographical Information System	Lg	large	Misc	miscellaneous	Pt	point
G	giga	Lat	latitude	Mon	monument	PCC	point of compound curve
GPS	Global Positioning System	Lt	left	Mnd	mound	PC	point of curve
Gov	government	L	length of curve	Mtbl	mountable	PI	point of intersection
Grd	graded/grade	Lens	lenses	Mtd	mounted	PRC	point of reverse curvature
Gr	gravel	Lvl	level	Mtg	mounting	PT	point of tangent
Grnd	ground	LB	level book	Mk	muck	POC	point on curve
GWM	ground water monitor	Lvng	leveling	Mun	municipal	POT	point on tangent
Gdrl	guardrail	Lht	light	N	nano	PE	polyethylene
Gtr	gutter	LP	light pole	NGS	National Geodetic Survey	PVC	polyvinyl chloride
H Plg	H piling	Ltg	lighting	NS	near side	PCC	Portland Cement concrete
Hdwl	headwall	Lig Co	lignite coal	Neop	neoprene	Lb or #	pounds
Ha	hectare	Lig Sl	lignite slack	Ntwk	network	PP	power pole
Ht	height	LF	linear foot	N	newton	Preempt	preemption
HI	height of instrument	Liq	liquid	N	North	Prefab	prefabricated
Hel	helical	LL	liquid limit	NE	North East	Prfmd or Pref	preformed
H	henry	L	litre	NW	North West	Prep	preperation
Hz	hertz	Lm	loam	NB	Northbound	Press.	pressure
HDPE	high density polyethylene	Loc	location	No. or #	number		
HM	high mast	LC	long chord	Obsc	obscure(d)		
HP	high pressure	Long.	longitude	Obsn	observation		
HPS	high pressure sodium	Lp	loop	Ocpd	occupied		
Hwy	highway	LD	loop detector	Ocpy	occupy		
Hor	horizontal	Lm	lumen	Off Loc	office location		
HBP	hot bituminous pavement	Lum	luminaire	O/s	offset		
HMA	hot mix asphalt	L Sum	lump sum	OC	on center		
Hr	hour(s)	Lx	lux	C	one dimensional consolidation		
Hyd	hydrant	Mb	mailbox	OC	organic content		
Ph	hydrogen ion content	ML	main line	Orig	original		
Id	identification	M Hr	man hour	O To O	out to out		
In or "	inch	MH	manhole	OD	outside diameter		
Incl	inclinometer tube	Mkd	marked	OH	overhead		
IMH	inlet manhole	Mkr	marker				

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
08-03-15 04-23-18	General Revisions General Revisions

This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930 , on 04/23/18 and the original document is stored at the North Dakota Department of Transportation

NDDOT ABBREVIATIONS

D-101-3

PRV	pressure relief valve	Sc	scoria	St	street	Vert	vertical
Prestr	prestressed	Sec	seconds	SPP	structural plate pipe	VC	vertical curve
Pvt	private	Sec	section	SPPA	structural plate pipe arch	VCP	vitrified clay pipe
PD	private drive	SL	section line	Str	structure	V	volt
Prod.	production/produce	Sep	separation	Subd	subdivision	Vol	volume
Prog	programmed	Seq	sequence	Sub	subgrade	Wkwy	walkway
Prop.	property	Serv	service	Sub Prep	subgrade preperation	W	water content
Prop Ln	property line	Sh	shale	Ss	subsoil	WGV	water gate valve
Ppsd	proposed	Sht	sheet	SE	superelevation	WL	water line
PB	pull box	Shtng	sheeting	SS	supplement specification	WM	water main
Qty	quantity	Shldr	shoulder	Supp	supplemental	WMV	water main valve
Qtr	quarter	Sw or Sdwk	sidewalk	Surf	surfacing	W Mtr	water meter
Rad or R	radius	S	siemens	Surv	survey	WSV	water service valve
RR	railroad	SD	sight distance	Sym	symmetrical	WW	water well
Rlwy	railway	SN	sign number	SI	systems international	W	watt
Rsd	raised	Sig	signal	Tan	tangent	Wrng	wearing
RTP	random traverse point	Si Cl	silt clay	T	tangent (semi)	Wb	weber
Rge or R	range	Si Cl Lm	silty clay loam	TS	tangent to spiral	WIM	weigh in motion
RC	rapid curing	Si Lm	silty loam	Tel	telephone	W	west
Rec	record	Sgl	single	Tel B	Telephone Booth	WB	westbound
Rcy	recycle	SRCP	slotted reinforced concrete pipe	Tel P	telephone pole	Wrng	wiring
RAP	recycled asphalt pavement	SC	slow curing	Tv	television	W/	with
RPCC	recycled portland cement concrete	SS	slow setting	Temp	temperature	W/o	without
Ref	reference	Sm	small	Temp	temporary	WC	witness corner
R Mkr	reference marker	S	South	TBM	temporary bench mark	WGS	world geodetic system
RM	reference monument	SE	South East	T	tesla	Z	zenith
RP	reference point	SW	South West	T	thinwall tube sample		
Refl	reflectorized	SB	Southbound	T/mi	tons per mile		
RCB	reinforced concrete box	Sp	spaces	Ts	topsoil		
RCES	reinforced concrete end section	Spcl	special	Twp or T	township		
RCFES	reinforced concrete flared end section	SA	special assembly	Traf	traffic		
RCTES	reinforced concrete traversable end section	SP	special provisions	TSCB	traffic signal control box		
RCP	reinforced concrete pipe	G	specific gravity	Tr	trail		
RCPS	reinforced concrete pipe sewer	Spk	spike	Transf	transformer		
Reinf	reinforcement	SC	spiral to curve	TB	transit book		
Res	reservation	ST	spiral to tangent	Trans	transition		
Rs	residence	SB	split barrel sample	TT	transmission tower		
Ret	retaining	SH	sprinkler head	TES	traversable end section		
Rev	reverse	SV	sprinkler valve	Trans	transverse		
Rt	right	Sq	square	Trav	traverse		
R/W	right of way	SF	square feet	TP	traverse point		
Riv	river	Km2	square kilometer	Trtd	treated		
Rd	road	M2	square meter	Trmt	treatment		
Rdbd	road bed	SY	square yard	Qc	triaxial compression		
Rdwy	roadway	Stk	stake	TERO	tribal employment rights ordinance		
RWIS	roadway weather information system	Std	standard	Tpl	triple		
Rk	rock	N	standard penetration test	TP	turning point		
Rt	route	Std Specs	standard specifications	Typ	typical		
Salv	salvage(d)	Sta	station	Qu	unconfined compressive strength		
Sd	sand	Sta Yd	station yards	Ugrnd	underground		
Sdy Cl	sandy clay	Stm L	steam line	USC&G	US Coast & Geodetic Survey		
Sdy Cl Lm	sandy clay loam	SEC	steel encased concrete	USGS	US Geologic Survey		
Sdy Fl	sandy fill	SMA	stone matrix asphalt	Util	utility		
Sdy Lm	sandy loam	SSD	stopping sight distance	VG	valley gutter		
San	sanitary sewer line	SD	storm drain	Vap	vapor		
























NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
08-03-15 04-23-18	General Revisions General Revisions













This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930 , on 04/23/18 and the original document is stored at the North Dakota Department of Transportation

702COM	702 Communications	GT PLNS NAT GAS	Great Plains Natural Gas Company	RED RIV TEL	Red River Rural Telephone
ACCENT	Accent Communications	HALS TEL	Halstad Telephone Company	RESVTN TEL	Reservation Telephone
AGASSIZ WU	Agassiz Water Users Incorporated	IDEA1	Idea1	ROBRTS TEL	Roberts Company Telephone
AGC	Associated General Contractors of America	INT-COMM TEL	Inter-Community Telephone Company	R-RIDER ELEC	Roughrider Electric Cooperative
AI PI	Alliance Pipeline	KANEB PL	Kaneb Pipeline Company	RRVW	Red River Valley & Western Railroad
ALL SEAS WU	All Seasons Water Users Association	KEM ELEC	Kem Electric Cooperative Incorporated	S CENT REG WD	South Central Regional Water District
AMOCO PI	Amoco Pipeline Company	KOCH GATH SYS	Koch Gathering Systems Incorporated	S E W U	South East Water Users Incorporated
AMRDA HESS	Amerada Hess Corporation	LKHD PL	Lakehead Pipeline Company	SCOTT CABLE	Scott Cable Television Dickinson
AT&T	AT&T Corporation	LNGDN RWU	Langdon Rural Water Users Incorporated	SHERDN ELEC	Sheridan Electric Cooperative
B PAW	Bear Paw Energy Incorporated	LWR YELL R ELEC	Lower Yellowstone Rural Electric	SHEYN VLY ELEC	Sheyenne Valley Electric Cooperative
BAKER ELEC	Baker Electric	MCKNZ CON	McKenzie Consolidated Telcom	SKYTECH	Skyland Technologies Incorporated
BASIN ELEC	Basin Electric Cooperative Incorporated	MCKNZ ELEC	McKenzie Electric Cooperative	SLOPE ELEC	Slope Electric Cooperative Incorporated
BEK TEL	Bek Communications Cooperative	MCKNZ WRD	McKenzie County Water Resource District	SOURIS RIV TELCOM	Souris River Telecommunications
BELLE PL	Belle Fourche Pipeline Company	MCLEOD	McLeod USA	ST WAT COMM	State Water Commission
BLM	Bureau of Land Management	MCLN ELEC	McLean Electric Cooperative	STATE LN WATER	State Line Water Cooperative
BNSF	Burlington Northern Santa Fe Railway	MCLN-SHRDN R WAT	McLean-Sheridan Rural Water	STER ENG	Sterling Energy
BOEING	Boeing	MDU	Montana-dakota Utilities	STUT RWU	Stutsman Rural Water Users
BRNS RWD	Barnes Rural Water District	MID-CONT CABLE	Mid-Continent Cable	SW PL PRJ	Southwest Pipeline Project
BURK-DIV ELEC	Burke-Divide Electric Cooperative	MIDSTATE TEL	Midstate Telephone Company	T M C	Turtle Mountain Communications
BURL WU	Burleigh Water Users	MINOT CABLE	Minot Cable Television	TCI	TCI of North Dakota
Cable One	Cable One	MINOT TEL	Minot Telephone Company	TESORO HGH PLNS PL	Tesoro High Plains Pipeline
CABLE SERV	Cable Services	MISS VALL COMM	Missouri Valley Communications	TRI-CNTY WU	Tri-County Water Users Incorporated
CAP ELEC	Capital Electric Cooperative Incorporat	MISS W W S	Missouri West Water System	TRL CO RWU	Traill County Rural Water Users
CASS CO ELEC	Cass County Electric Cooperative	MNKOTA PWR	Minnkota Power	UNTD TEL	United Telephone
CASS RWU	Cass Rural Water Users Incorporated	MOR-GRAN-SOU ELEC	Mor-gran-sou Electric Cooperative	UPPR SOUR WUA	Upper Souris Water Users Association
CAV ELEC	Cavalier Rural Electric Cooperative	MOUNT-WILLI ELEC	Mountrail-williams Electric Cooperative	US SPRINT	U.S. Sprint
CBLCOM	Cablecom Of Fargo	MRE LBTY TEL	Moore & Liberty Telephone	USAF MSL CABLE	U.S.A.F. Missile Cable
CENEX PL	Cenex Pipeline	MUNICIPAL	City Water And Sewer	USFWS	US Fish and Wildlife Service
CENT PL WATER DIST	Central Pipe Line Water District	MUNICIPAL	City Of '.....'	USW COMM	U.S. West Communications
CENT PWR ELEC	Central Power Electric Cooperative	N CENT ELEC	North Central Electric Cooperative	VRNDRY ELEC	Verendrye Electric Cooperative
COE	Corps of Engineers	N VALL W DIST	North Valley Water District	W RIV TEL	West River Telephone Incorporated
CONS TEL	Consolidated Telephone	ND PKS & REC	North Dakota Parks And Recreation	WEB	W. E. B. Water Development Association
CONT RES	Continental Resource Inc	ND TEL	North Dakota Telephone Company	WILLI RWA	Williams Rural Water Association
CPR	Canadian Pacific Railway	NDDOT	North Dakota Department of Transportation	WILSTN BAS PL	Williston Basin Interstate Pipeline Company
D O E	Department Of Energy	NDSU SOIL SCI DEPT	NDSU Soil Science Department	WLSH RWD	Walsh Water Rural Water District
DAK CARR	Dakota Carrier Network	NEMONT TEL	Nemont Telephone	WOLVRTN TEL	Wolverton Telephone
DAK CENT TEL	Dakota Central Telephone	NODAK R ELEC	Nodak Rural Electric Cooperative	XLENER	Xcel Energy
DAK RWD	Dakota Rural Water District	NOON FRMS TEL	Noonan Farmers Telephone Company	YSVR	Yellowstone Valley Railroad
DGC	Dakota Gasification Company	NPR	Northern Plains Railroad		
DICKEY R NET	Dickey Rural Networks	NSP	Northern States Power		
DICKEY RWU	Dickey Rural Water Users Association	NTH PRAIR RW	Northern Prairie Rural Water Association		
DICKEY TEL	Dickey Telephone	NTHN BRDR PL	Northern Border Pipeline		
DNRR	Dakota Northern Railroad	NTHN PLNS ELEC	Northern Plains Electric Cooperative Incorporated		
DO ME PL	Dome Pipeline Company	NTHWSTRN REF	Northwestern Refinery Company		
DVELEC	Dakota Valley Electric Cooperative	NW COMM	Northwest Communication Cooperation		
DVMW	Dakota, Missouri Valley & Western	NWRWD	Northwest Rural Water District		
ENBRDG	Enbridge Pipelines Incorporated	ONEOK	Oneok gas		
ENVENTIS	Enventis Telephone	OSHA	Occupational Safety and Health Administration		
FALK MNG	Falkirk Mining Company	OTTR TL PWR	Otter Tail Power Company		
FHWA	Federal Highway Administration	P L E M	Prairielands Energy Marketing		
G FKS-TRL WD	Grand Forks-trail Water District	POLAR COM	Polar Communications		
GETTY TRD & TRAN	Getty Trading & Transportation	PVT ELEC	Private Electric		
GLDN W ELEC	Golden West Electric Cooperative	QWEST	Qwest Communications		
GRGS CO TEL	Griggs County Telephone	R&T W SUPPLY	R & T Water Supply Association		
GTR RAMSEY WD	Greater Ramsey Water District				








NORTH DAKOTA DEPARTMENT OF TRANSPORTATION		This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930 , on 09/20/18 and the original document is stored at the North Dakota Department of Transportation
07-01-14		
REVISIONS		
DATE	CHANGE	
04-23-18 09-20-18	General Revisions General Revisions	

Existing Topography























	Existing Ground Void
	Existing Cemetary Boundary
	Existing Box Culvert Bridge
	Existing Concrete Surface
	Existing Drainage Structure
	Existing Gravel Surface
	Existing Riprap
	Existing Dirt Surface
	Existing Asphalt Surface
	Existing Tie Point Line
	Existing Railroad Centerline
	Existing Guardrail Cable
	Existing Guardrail Metal
	Existing Edge of Water
	Existing Fence
	Existing Railroad
	Existing Field Line
	Exst Flow
	Existing Curb
	Existing Valley Gutter
	Existing Driveway Gutter
	Existing Curb and Gutter
	Existing Mountable Curb and Gutter

	Existing 3-Cable w Posts
	Site Boundary
	Existing Berm, Dike, Pit, or Earth Dam
	Existing Ditch Block
	Existing Tree Boundary
	Existing Brush or Shrub Boundary
	Existing Retaining Wall
	Existing Planter or Wall
	Existing W-Beam Guardrail with Posts
	Existing Railroad Switch
	Gravel Pit - Borrow Area
	Existing Wet Area-Vegetation Break





Proposed Topography

	3-Cable w Posts
	Flow
	Fence
	Remove Line
	Wall
	Retaining Wall (Plan View)
	W-Beam w Posts










Existing Utilities

	Existing Electrical
	Existing Fiber Optic Line
	Existing TV Fiber Optic
	Existing Gas Pipe
	Existing Overhead Utility Line
	Existing Power
	Existing Fuel Pipeline
	Existing Undefined Above Ground Pipe Line
	Existing Sanitary Sewer
	Existing Sanitary Force Main
	Existing Storm Drain
	Existing Storm Drain Force Main
	Existing Culvert
	Existing Telephone Line
	Existing TV Line
	Existing Water or Steam Line
	Existing Under Drain
	Existing Slotted Drain
	Existing Conduit
	Existing Conductor
	Existing Down Guy Wire Down Guy
	Existing Underground Vault or Lift Station




Proposed Utilities

	24 Inch Pipe
	Reinforced Concrete Pipe
	Under Drain
	Edge Drain

Traffic Utilities

	Conductor
	Fiber Optic
	Existing Loop Detector
	Existing Double Micro Loop Detector
	Micro Loop Detector Double
	Existing Micro Loop Detector
	Micro Loop Detector
	Signal Head with Mast Arm
	Existing Signal Head with Mast Arm

Sign Structures














	Existing Overhead Sign Structure
	Existing Overhead Sign Structure Cantilever
	Overhead Sign Structure Cantilever

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
09-23-16	Added and Revised Items, Organized by Functional Groups










This document was originally issued and sealed by
Roger Weigel,
Registration Number
PE-2930,
on 09/23/16 and the original document is stored at the
North Dakota Department
of Transportation

Line Styles









Right Of Way

	Easement
	Existing Easement
	Right of Way
	Existing Right of Way
	Existing Right of Way Railroad
	Existing Right of Way Not State Owned
	Existing Government Lot Line
	Existing Adjacent Block Lines
	Existing Adjacent Lot Lines
	Existing Adjacent Property Line
	Existing Adjacent Subdivision Lines
	Sight Distance Triangle Line
	Dimension Leader







Boundary Control



	Existing City Corporate Limits or Reservation Boundary
	Existing State or International Line
	Existing Township
	Existing County
	Existing Section Line
	Existing Quarter Section Line
	Existing Sixteenth Section Line
	Existing Centerline
	Tangent Line

Cross Sections and Typicals



	Existing Ground
	Existing Topsoil (Cross Section View)
	Existing Ground Void (Not Surveyed)
	Existing Concrete
	Existing Aggregate (Cross Section View)
	Existing Curb and Gutter (Cross Section View)
	Existing Asphalt (Cross Section View)
	Existing Reinforcement Rebar

Geotechnical



	Geotextile Fabric Type D
	Geogrid
	Geotextile Fabric Type R
	Geotextile Fabric Type R1
	Geotextile Fabric Type RR
	Geotextile Fabric Type S

	Subgrade Reinforcement
	Failure Line







Countours

	Depression Contours
	Supplemental Contour





Profile

	Subgrade, Subcut or Ditch Grade
	Topsoil Profile










Striping

	Centerline Pavement Marking
	Barrier with Centerline Pavement Marking
	Barrier Pavement Marking
	Stripe 4 IN Dotted Extension White
	Stripe 8 IN Dotted Extension White
	Stripe 8 IN Lane Drop








Pavement Joints

	Doweled Joint
	Tie Bar 30 Inch 4 Foot Center to Center
	Tie Bar 18 Inch 3 Foot Center to Center
	Tie Bar at Random Spacing






Bridge Details

	Hidden Object
	Small Hidden Object
	Large Hidden Object
	Phantom Object
	Centerline Main
	Centerline
	Existing Ground (Details)
	Existing Conditions
	Sheet Piling

Erosion Control

	Limits of Const Transition Line
	Bale Check
	Rock Check
	Floating Silt Curtain
	Silt Fence
	Excavation Limits
	Fiber Rolls

Environmental

	Wetland Mitigation
	Existing Wetland Easement USFWS
	Existing Wetland Jurisdictional
	Existing Wetland
	Tree Row

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
09-23-16	Added and Revised Items, Organized by Functional Groups

























































































This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930 , on 09/23/16 and the original document is stored at the North Dakota Department of Transportation

Symbols

	North Arrow (Half Scale)		Attenuation Device		Existing Railroad Battery Box		Existing Delineator Type E										
	Truck Mounted Attenuator		Diamond Grade Delineator Type A		Existing Bush or Shrub		Existing EFB Misc										
	Type I Barricade		Diamond Grade Delineator Type B		Existing Gas Cap or Stub		Existing Flashing Beacon										
	Type II Barricade		Diamond Grade Delineator Type C		Existing Sanitary Cap or Stub		Existing Pipe Mounted Flasher										
	Type III Barricade		Diamond Grade Delineator Type D		Existing Storm Drain Cap or Stub		Existing Pad Mounted Feed Point										
	Catch Basin		Diamond Grade Delineator Type E		Existing Water Cap or Stub		Existing Pipe Mounted Feed Point with Pad										
	Cairn or Stone Circle		Flexible Delineator		Existing Sanitary Cleanout		Existing Pole Mounted Feed Point										
	Video Detection Camera		Flexible Delineator Type A		Existing Concrete Foundation		Existing Railroad Frog										
	Storm Drain Cap or Stub		Flexible Delineator Type B		Existing Traffic Signal Controller		Existing Snow Gate 18										
	Corrugated Metal End Section 18 Inch		Flexible Delineator Type C		Existing Pad Mounted Signal Controller		Existing Snow Gate 28										
	Corrugated Metal End Section 24 Inch		Flexible Delineator Type D		Existing Sixteenth Section Corner		Existing Snow Gate 40										
	Corrugated Metal End Section 30 Inch		Flexible Delineator Type E		Existing Quarter Section Corner		Existing Headwall										
	Corrugated Metal End Section 36 Inch		Delineator Type A		Existing Section Corner		Existing Pedestrian Head with Number										
	Corrugated Metal End Section 42 Inch		Delineator Type A Reset		Existing Railroad Crossbuck		Existing Signal Head										
	Corrugated Metal End Section 48 Inch		Delineator Type B		Existing Satellite Dish		Existing Sprinkler Head										
	Concrete Foundation		Delineator Type B Reset		Existing Fuel Dispensers		Existing Fire Hydrant										
	Ground Connection Conductor		Delineator Type C		Existing Flexible Delineator Type A		Existing Catch Basin Drop Inlet										
	Neutral Connection Conductor		Delineator Type D		Existing Flexible Delineator Type B		Existing Curb Inlet										
	Phase 1 Connection Conductor		Delineator Type E		Existing Flexible Delineator Type C		Existing Manhole Inlet										
	Phase 2 Connection Conductor		Delineator Drums		Existing Flexible Delineator Type D		Existing Junction Box										
	Traffic Cone		Spot Elevation		Existing Flexible Delineator Type E	<table><tr><th colspan="2">NORTH DAKOTA DEPARTMENT OF TRANSPORTATION</th></tr><tr><th colspan="2">07-01-14</th></tr><tr><th colspan="2">REVISIONS</th></tr><tr><th>DATE</th><th>CHANGE</th></tr><tr><td></td><td></td></tr></table>		NORTH DAKOTA DEPARTMENT OF TRANSPORTATION		07-01-14		REVISIONS		DATE	CHANGE		
NORTH DAKOTA DEPARTMENT OF TRANSPORTATION																	
07-01-14																	
REVISIONS																	
DATE	CHANGE																
	Signal Controller		Existing Access Control Arrow		Existing Delineator Type A												
	Pad Mounted Signal Controller		Existing Artifact		Existing Delineator Type B												
	Alignment Data Point		Existing Flashing Beacon		Existing Delineator Type C												
	Emergency Vehicle Detector		Existing Benchmark		Existing Delineator Type D												

Symbols
































































































D-101-31

	Existing Light Standard		Existing Manhole with Valve Water		Existing Telephone Pole		Existing Undefined Manhole
	Existing High Mast Light Standard 10 Luminaire		Existing Water Manhole		Existing Wood Pole		Existing Undefined Pull Box
	Existing High Mast Light Standard 3 Luminaire		Existing Mile Post Type A		Existing Post		Existing Undefined Pedestal
	Existing High Mast Light Standard 4 Luminaire		Existing Mile Post Type B		Existing Pedestrian Push Button Post		Existing Undefined Valve
	Existing High Mast Light Standard 5 Luminaire		Existing Mile Post Type C		Existing Control Point CP		Existing Undefined Pipe Vent
	Existing High Mast Light Standard 6 Luminaire		Existing Reference Marker		Existing Control Point GPS-RTK		Existing Gas Valve
	Existing High Mast Light Standard 7 Luminaire		Existing RW Marker		Existing Control Point TRI		Existing Water Valve
	Existing High Mast Light Standard 8 Luminaire		Existing Utility Marker		Existing Reference Marker Point NGS		Existing Fuel Pipe Vent
	Existing High Mast Light Standard 9 Luminaire		Iron Monument Found		Existing Pull Box		Existing Gas Pipe Vent
	Existing Overhead Sign Structure Load Center		Iron Pin R/W Monument		Existing Intelligent Transportation Pull Box		Existing Sanitary Pipe Vent
	Existing Luminaire		Existing Object Marker Type I		Existing Water Pump		Existing Storm Drain Pipe Vent
	Existing Light Standard Luminaire		Existing Object Marker Type II		Existing Slotted Reinforced Concrete Pipe		Existing Water Pipe Vent
	Existing Federal Mailbox		Existing Object Marker Type III		Existing RR Profile Spot		Existing Weather Station
	Existing Private Mailbox		Existing Electrical Pedestal		Existing Fuel Leak Sensors		Existing Ground Water Well Bore Hole
	Existing Meander Section Corner		Existing Telephone Pedestal		Existing Highway Sign		Existing Windmill or Tower
	Existing Meter		Existing Fiber Optic Telephone Pedestal		Existing Miscellaneous Spot		Existing Witness Corner
	Existing Electrical Manhole		Existing TV Pedestal		Existing Lighting Standard Pole		Flashing Beacon
	Existing Gas Manhole		Existing Fiber Optic TV Pedestal		Existing Traffic Signal Standard		Flagger
	Existing Sanitary Manhole		Existing Fuel Filler Pipes		Existing Transformer		Pipe Mounted Flasher
	Existing Sanitary Force Main Manhole		Existing Traverse PI Aerial Panel		Existing Large Evergreen Tree		Sanitary Force Main with Valve
	Existing Sanitary Manhole with Valve		Existing Pole		Existing Small Evergreen Tree		
	Existing Storm Drain Manhole		Existing Power Pole		Existing Large Tree		
	Existing Force Main Storm Drain Manhole		Existing Power Pole with Transformer		Existing Small Tree		
	Existing Force Main Storm Drain Manhole with Valve				Existing Tree Trunk		
	Existing Telephone Manhole				Existing Pad Mounted Traffic Signal Control Box		



NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 07/01/14 and the original document is stored at the North Dakota Department of Transportation

Symbols

	Pad Mounted Feed Point		Light Standard 1000 Watt High Pressure Sodium Vapor Luminaire		Object Marker Type I		Reinforced Concrete End Section 48 Inch										
	Pipe Mounted Feed Point with Pad		Light Standard 150 Watt High Pressure Sodium Vapor Luminaire		Object Marker Type II		Reinforced Concrete End Section 54 Inch										
	Pole Mounted Feed Point		Light Standard 175 Watt High Pressure Sodium Vapor Luminaire		Object Marker Type III		Reset Right of Way Marker										
	Headwall		Light Standard 200 Watt High Pressure Sodium Vapor Luminaire		Caution Mode Arrow Panel		Reset USGS Marker										
	Double Headwall with Vegetation Barrier		Light Standard 250 Watt High Pressure Sodium Vapor Luminaire		Back to Back Vertical Panel Sign		Right of Way Markers										
	Single Headwall with Vegetation Barrier		Light Standard 310 Watt High Pressure Sodium Vapor Luminaire		Double Direction Arrow Panel		Riser 30 Inch										
	Pole Mounted Head		Light Standard 35 Watt High Pressure Sodium Vapor Luminaire		Left Directional Arrow Panel		Continuous Split Barrel Sample										
	Sprinkler Head		Light Standard 400 Watt High Pressure Sodium Vapor Luminaire		Right Directional Arrow Panel		Flight Auger Sample										
	Fire Hydrant		Light Standard 50 Watt High Pressure Sodium Vapor Luminaire		Sequencing Arrow Panel		Split Barrel Sample										
	Inlet Type 1		Light Standard 70 Watt High Pressure Sodium Vapor Luminaire		Truck Mounted Arrow Panel		Thinwall Tube Sample										
	Inlet Type 2		Light Standard 700 Watt High Pressure Sodium Vapor Luminaire		Power Pole		Highway Sign										
	Double Inlet Type 2		Manhole		Wood Pole		SNOW GATE 18 FT										
	Inlet Grate Type 2		Manhole 48 Inch		Pedestrian Push Button Post		SNOW GATE 28 FT										
	Junction Box		Sanitary Force Main Manhole		Property Corner		SNOW GATE 40 FT										
	High Mast Light Standard 10 Luminaire		Sanitary Sewer Manhole		Pull Box		Standard Penetration Test										
	High Mast Light Standard 3 Luminaire		Storm Drain Manhole		Intelligent Transportation Pull Box		Transformer										
	High Mast Light Standard 4 Luminaire		Storm Drain Manhole with Inlet		Sanitary Pump		Inclinometer Tube										
	High Mast Light Standard 5 Luminaire		Reset Mile Post		Storm Drain Pump		Underdrain Cleanout										
	High Mast Light Standard 6 Luminaire		Mile Post Type A		Reinforced Pavement		Excavation Unit										
	High Mast Light Standard 7 Luminaire		Mile Post Type B		Reinforced Concrete End Section 15 Inch		Water Valve										
	High Mast Light Standard 8 Luminaire		Mile Post Type C		Reinforced Concrete End Section 18 Inch	<table><tr><th colspan="2">NORTH DAKOTA DEPARTMENT OF TRANSPORTATION</th></tr><tr><td colspan="2">07-01-14</td></tr><tr><th colspan="2">REVISIONS</th></tr><tr><th>DATE</th><th>CHANGE</th></tr><tr><td></td><td></td></tr></table>	NORTH DAKOTA DEPARTMENT OF TRANSPORTATION		07-01-14		REVISIONS		DATE	CHANGE			
NORTH DAKOTA DEPARTMENT OF TRANSPORTATION																	
07-01-14																	
REVISIONS																	
DATE	CHANGE																
	High Mast Light Standard 9 Luminaire		Right of Way Marker		Reinforced Concrete End Section 24 Inch												
	Relocate Light Standard		Tubular Marker		Reinforced Concrete End Section 30 Inch												
	Overhead Sign Structure Load Center		Alignment Monument		Reinforced Concrete End Section 36 Inch												
	Light Standard 100 Watt High Pressure Sodium Vapor Luminaire		Iron Pin Reference Monument		Reinforced Concrete End Section 42 Inch												


ATTENUATION DEVICE



Outer Containers




Cones



Typical Assembly

Typical Module Construction Detail




Reflective Sheet Detail

Note:
Apply Type IV reflective sheeting (as specified in the NDDOT Standard Specifications) directly to the outer container of the last attenuation device facing traffic, following the details above.
Or apply the sheet to a metallic sheet and attach it to the container with approved fasteners.


(A) Use 3" orange sheeting for temporary installations, and 3" yellow sheeting for permanent installations.

Fill Chart					
	Module Weights (LBS)				
	200	400	700	1400	2100
Distance from top edge	8½"	5"	4"	3"	0"



Type B Layout

Note:
Angle attenuation devices 10 degrees towards traffic when placed at piers offset from roadway.



Section A-A
(Type B Layout)

Type B Attenuation Device											
Module Number	Dash Number										
	75	70	65	60	55	50	45	40	35	30	25
	Module Weights (LBS)										
B1	2100										
B2	2100										
B3	2100	2100	2100	2100	2100	2100	2100	2100	2100		
B4	2100	2100	2100	2100	2100	2100	2100	2100	2100		
B5	1400	1400	1400	1400	1400	1400	1400	1400	1400	1400	1400
B6	1400	1400	1400	1400	1400	1400	1400	1400	1400	1400	1400
B7	1400	1400	1400	1400	1400	1400	1400	1400	1400	1400	1400
B8	1400	1400	1400	1400	1400	1400	1400	1400	1400	1400	1400
B9	700	700	700	700	700	700	700	700	700	700	700
B10	700	700	700	700	700	700	700	700	700	700	700
B11	700	700	700	700	700	700	700	700	700	700	700
B12	700	700	700	700	700	700	700	700	700	700	700
B13	700	700	700	700	700	700	700	700	700	700	700
B14	400	400	400	400	400	400	400	400	400	400	400
B15	400	400	400	400	400	400	400	400	400	400	400
B16	200	200	200	200	200	200	200	200	200	200	200
Length (L)	34.2'	30.7'	30.7'	30.7'	30.7'	30.7'	30.7'	30.7'	30.7'	27.2'	27.2'
Module Weights (LBS)	Replacement Module										
	2100	1	1	1	1	1	1	1	1		
	1400	1	1	1	1	1	1	1	1	1	1
	700	2	2	2	2	2	2	2	2	2	2
	400	1	1	1	1	1	1	1	1	1	1
	200	2	2	2	1	1	1	1	1	1	1

Notes:

- Materials
 - Use modules manufactured from frangible polyethylene material which shatters upon impact.
 - Fill modules with class 43 aggregate meeting NDDOT Standard Specifications aggregate requirements. Use fill with a unit weight of at least 100 pounds per cubic foot. Use fill with a moisture content of 2% or less when left over winter.
- Modules
 - Provide three components for 2, 4, or 7 cubic foot module containers:
 - A 14 C.F., yellow outer container.
 - A black lid securely locking over the top lip of the container.
 - A variable cone-shaped supporting insert capable of supporting 200, 400, or 700 pounds of sand mass to allow for three sizes of modules. Place cone inserts inside the 14 cubic foot container.
 - Provide two components for the 14 cubic foot module container:
 - A 14 C.F., yellow outer container.
 - A black lid securely locking over the top lip of the container.
 - Provide two components for the 21 cubic foot module container:
 - A 36" height X 36" width yellow outer container.
 - A black lid which locks securely over the top of the container.
- For temporary installations use Energite or Fitch attenuation barrels manufactured by Energy Absorption Systems of Chicago, IL, TrafFix barrels manufactured by TrafFix Devices, Inc. of San Clemente, CA, or approved equal modules. As an option, place attenuation devices on 3½" maximum thickness pallets to facilitate maintenance.
- For permanent installations use Barrel Attenuation Device consisting of one-piece outer sand container modules with separate detachable lid. Energite attenuation barrels manufactured by Energy Absorption Systems of Chicago, IL, TrafFix barrels manufactured by TrafFix Devices, Inc. of San Clemente, CA, or approved equal meet these requirements.
- The Typical Module Construction Detail and Type B Layout are based on the Energite Crash Cushion manufactured by Energy Absorption. Provide any required layouts and details from other sand filled attenuation module manufacturers which differ from those shown here.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-25-12	
REVISIONS	
DATE	CHANGE
7-18-14	Revised sheeting in reflective sheet detail
9-27-17	Update to active voice
10-03-19	New Design Engr PE Stamp

This document was originally issued and sealed by
Kirk J Hoff,
Registration Number
PE- 4683,
on 10/03/19 and the original document is stored at the
North Dakota Department
of Transportation

SIGN NUMBER	G20-10-108
WIDTH x HEIGHT	9'-0" x 4'-0"
BORDER WIDTH	1.25" (inset 0.75")
CORNER RADIUS	3"
MOUNTING	Ground
BACKGROUND	TYPE: IV Reflective
	COLOR: Fluorescent Orange
LEGEND/BORDER	TYPE: Non-Refl
	COLOR: Black

SYMBOL	X	Y	WID	HT	ANGLE
	42.1	6.2	24	4	0

STATION(S):

AREA: 36.0 Sq.Ft.

Dimensions are in inches.tenthsLetter locations are panel edge to lower left corner

LETTER POSITION (X)																		LENGTH	SIZE	SERIES
C	O	N	S	T	R	U	C	T	E	D		B	Y					69.7	6	D 2000
19.2	24.5	30	35.1	39.7	44.3	49.4	54.8	59.7	64.3	69	73.1	79.1	83.7							
Y	O	U	R		C	O	M	P	A	N	Y		N	A	M	E		91.5	6	D 2000
8.3	14.2	19.8	25.3	29.4	35.4	40.7	46.2	52.4	56.8	62.8	67.8	72.9	78.9	83.9	89.9	96				
Y	O	U	R		T	O	W	N	,		N	D						64.6	6	D 2000
21.7	27.6	33.2	38.7	42.8	48.8	53.3	58.4	64.6	69.6	70.7	76.7	82.2								

Advance Warning Sign Spacing (A)			
Road Type	Distance between signs min. (ft)		
	A	B	C
Urban - Low Speed (30 mph or less)	150	150	150
Urban - Low Speed (over 30 to 40 mph)	280	280	280
Urban - High Speed (over 40 mph to 50 mph)	360	360	360
Rural - High Speed (over 50 mph to 65 mph)	720	720	720
Urban Expressway and Freeway (55 mph to 60 mph)	850	1350	2200
Rural Expressway and Freeway (70 mph to 75 mph)	1000	1500	2640
Interstate/4-Lane Divided (Maintenance and Surveying)	750	1000	1500

- Notes:
- Post mount sign a distance of ½A following the End Road Work (G20-2-48) sign (maximum 2 signs per project.)
 - Use sign on rural projects with a 30 day or longer duration (not required on seal coats or other short duration projects.)
 - Do not place sign in urban areas or within city limits.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-22-12	
REVISIONS	
DATE	CHANGE
7-18-14 9-27-17 8-30-18 10-03-19	Revise sheeting to type IV. Updated to active voice. Updated sign number in note 1. New Design Engineer PE Stamp.

This document was originally issued and sealed by

Kirk J Hoff,

Registration Number




PE- 4683 ,

on 10/03/19 and the original document is stored at the

North Dakota Department of Transportation

Perforated Tube

- Notes:
1. Torque slip base bolts as specified by manufacturer.
 2. Use anchor with 43.9 KSI yield strength and 59.3 KSI tensile strength.
 3. Provide 4" vertical clearance for anchor or breakaway base. Measure the 4"x60" measurement above and below post location and back and ahead of post.
 4. In concrete sidewalk, use same anchor without wings.
 5. Provide more than 7' between the first and fourth posts of a four post sign.





Telescoping Perforated Tube						
Number of Posts	Post Size in.	Wall Thick-ness Gauge	Sleeve Size in.	Wall Thick-ness Gauge	Slip Base	Anchor Size without Slip Base in.
1	2	12			No	2 1/4
1	2 1/4	12			No	2 1/2
1	2 1/2	12			(A)	3
1	2 1/2	10			Yes	
1	2 1/4	12	2	12	Yes	
1	2 1/2	12	2 1/4	12	Yes	
2	2	12			No	2 1/4
2	2 1/4	12			No	2 1/2
2	2 1/2	12			Yes	
2	2 1/2	12			Yes	
2	2 1/4	10	2	12	Yes	
2	2 1/2	12	2 1/4	12	Yes	
3 & 4	2 1/2	12			Yes	
3 & 4	2 1/2	10			Yes	
3 & 4	2 1/2	12	2 1/4	12	Yes	
3 & 4	2 1/4	12	2	12	Yes	
3 & 4	2 1/2	10	2 3/16	10	Yes	

Properties of Telescoping Perforated Tube						
Tube Size in.	Wall Thickness in.	U.S. Standard Gauge	Weight per Foot lbs.	Moment of Inertia in. ⁴	Cross Sec. Area in. ²	Section Modulus in. ³
1 1/2 x 1 1/2	0.105	12	1.702	0.129	0.380	0.172
2 x 2	0.105	12	2.416	0.372	0.590	0.372
2 1/4 x 2 1/4	0.105	12	2.773	0.561	0.695	0.499
2 3/8 x 2 3/8	0.135	10	3.432	0.605	0.841	0.590
2 1/2 x 2 1/2	0.105	12	3.141	0.804	0.803	0.643
2 1/2 x 2 1/2	0.135	10	4.006	0.979	1.010	0.785






Top Post Receiver Data Table						
Square Post Sizes (B)	A	B	C	D	E	F
2 3/16"x10 ga.	1 5/16"	2 1/2"	3 1/2"	2 5/32"	1 33/64"	1 7/8"
2 1/2"x10 ga.	1 3/32"	2 1/2"	3 5/16"	5/8"	1 21/32"	1 3/4"

- (A) Use breakaway base when support is placed in weak soils. Engineer determines if soils are weak.
- (B) For additional wind load, insert the 2 3/8"x10 ga. into 2 1/2"x10 ga.



NORTH DAKOTA DEPARTMENT OF TRANSPORTATION		This document was originally issued and sealed by Kirk J Hoff, Registration Number PE- 4683, on 10/03/19 and the original document is stored at the North Dakota Department of Transportation
2-28-14		
REVISIONS		
DATE	CHANGE	
9-27-17 10-03-19	Updated to active voice New Design Engr PE Stamp	

U-Channel Post



Alternate A Steps of Installation:


- a) Drive anchor unit to within 12" of ground level.
b) Establish proper assembly by lining up bottom hole of retainer strap with 6th hole from the top of the anchor unit.
c) Assemble strap to back of anchor unit using 5/16"x2" bolt, lock washer and nut.
d) Rotate strap 90° to left.
- a) Drive anchor unit to 4" above ground.
b) Rotate strap to vertical position.
- a) Place 5/16"x2" bolt, lock washer and nut in bottom of sign post to facilitate alignment of sign post with proper hole in anchor unit.
b) Alternately tighten two connector bolts.
- Complete assembly by tightening 5/16"x2" bolt (this fastens sign post to retainer strap).
- Properly nest base post, strap, and sign post. Proper nesting occurs when all flat surfaces of the base post, strap, and sign post at the bolts have full contact across the entire width.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
2-28-14	
REVISIONS	
DATE	CHANGE
9-27-17 10-03-19	Updated to active voice New Design Engr PE Stamp


This document was originally issued and sealed by
Kirk J Hoff,
Registration Number
PE- 4683,
on 10/03/19 and the original document is stored at the
North Dakota Department
of Transportation

CONSTRUCTION SIGN DETAILS
TERMINAL AND GUIDE SIGNS


D-704-9




G20-1-60
Legend: black (non-refl)
Background: orange




G20-50a-72
Legend: black (non-refl)
Background: orange




G20-1b-60
Legend: black (non-refl)
Background: orange




G20-52a-72
Legend: black (non-refl)
Background: orange




G20-2-48
Legend: black (non-refl)
Background: orange




G20-55-96
Legend: black (non-refl)
Background: orange




E5-1(L or R)-48
Legend: white
Background: green (orange optional)




M4-8-36
Legend: black (non-refl)
Background: orange




E5-1-48




G20-50a-72
G20-52a-72



M4-9(L or R)-30
Right or Left



M4-9(L or R)-30
Advanced Right or Left




M4-9-30
Straight

ARROW DETAILS

NOTES:
(A) Arrow may be right or left of the legend to indicate construction to the right or left.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-13-13	
REVISIONS	
DATE	CHANGE
8-17-17 10-03-19	Added sign & background color New Design Engineer PE Stamp


This document was originally issued and sealed by
Kirk J Hoff,
Registration Number
PE- 4683,
on 10/03/19 and the original document is stored at the
North Dakota Department
of Transportation




M4-9(L or R)-30 &
M4-9-30
Legend: black (non-refl)
Background: orange

CONSTRUCTION SIGN DETAILS
REGULATORY SIGNS


D-704-10




R1-50P-24
Legend: black (non-refl)
Background: white



R11-3c-60
Legend: black (non-refl)
Background: white



R2-1aP-24
Legend: black (non-refl)
Background: white



R11-4a-60
Legend: black (non-refl)
Background: white




R11-2a-48
Legend: black (non-refl)
Background: white

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-13-13	
REVISIONS	
DATE	CHANGE
8-17-17 10-03-19	Revised sign number New Design Engineer PE Stamp


This document was originally
issued and sealed by
Kirk J Hoff,
Registration Number
PE- 4683,
on 10/03/19 and the original
document is stored at the
North Dakota Department
of Transportation

CONSTRUCTION SIGN DETAILS
WARNING SIGNS


D-704-11




W5-8-48
Legend: black (non-refl)
Background: orange




W8-53-48
Legend: black (non-refl)
Background: orange




W8-56-48
Legend: black (non-refl)
Background: orange




W5-9-48
Legend: black (non-refl)
Background: orange




W8-54-48
Legend: black (non-refl)
Background: orange



W9-3a-48
Legend: black (non-refl)
Background: orange





W8-9a-48
Legend: black (non-refl)
Background: orange



W8-55-48
Legend: black (non-refl)
Background: orange

WORD	LETTER SPACING
AHEAD	Standard
200 FT	Standard
350 FT	Standard
500 FT	Standard
1000 FT	Reduce 40%
1500 FT	Reduce 40%
1/2 MILE	Reduce 50%
1 MILE	Standard

* DISTANCE MESSAGES



ARROW DETAILS


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-13-13	
REVISIONS	
DATE	CHANGE
8-17-17	Updated sign number
5-31-18	Revised sign and arrow details
10-03-19	New Design Engineer PE Stamp

This document was originally issued and sealed by
Kirk J Hoff,
Registration Number
PE- 4683,
on 10/03/19 and the original document is stored at the
North Dakota Department
of Transportation

CONSTRUCTION SIGN DETAILS
WARNING SIGNS


WORD	LETTER SPACING
AHEAD	Standard
200 FT	Standard
350 FT	Standard
500 FT	Standard
1000 FT	Reduce 40%
1500 FT	Reduce 40%
½ MILE	Reduce 50%
1 MILE	Standard

* DISTANCE MESSAGES




W16-7aP-18

Legend: black (non-refl)
Background: orange




W21-50-48

Legend: black (non-refl)
Background: orange




W21-53-48

Legend: black (non-refl)
Background: orange




W20-51-48

Legend: black (non-refl)
Background: orange




W21-51-48

Legend: black (non-refl)
Background: orange




W22-8-48

Legend: black (non-refl)
Background: orange




W16-7aP-18



W20-52P-54

Legend: black (non-refl)
Background: orange




W21-52-48

Legend: black (non-refl)
Background: orange


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION		This document was originally issued and sealed by Kirk J Hoff, Registration Number PE- 4683, on 11/1/19 and the original document is stored at the North Dakota Department of Transportation
5-31-18		
REVISIONS		
DATE	CHANGE	
11-01-19	Added details for sign W16-7aP-18.	

BARRICADE AND CHANNELIZING DEVICE DETAILS




DELINEATOR DRUM

Provide horizontal, circumferential, alternating orange and white retroreflective stripes 4" to 6" wide for drum markings. Use a minimum of two orange and two white stripes with the top stripe being orange for each drum. Do not exceed 3' nonretroreflectORIZED spaces between the horizontal orange and white stripes. Avoid placement of stripes on drum ribs or indentations. Use closed top drums that will not allow collection of debris. Do not place ballast on the top of drum.




TRAFFIC CONE

Provide retroreflectorization of cones more than 36" in height by alternating orange and white retroreflective stripes. Use a minimum of two orange and two white stripes for each cone with the top stripe being orange. Use maximum 3" nonretroreflectorized space between the orange and white stripes.



TUBULAR MARKER


Provide retroreflectorization of tubular markers more than 42" in height by alternating four 4" to 6" wide orange and white stripes with the top stripe being orange.



FLEXIBLE DELINEATOR


INSTALLATION NOTES:

1. Drill installation holes to diameter and depth required by manufacturer's specifications.
2. For removal, remove anchors and fill installation hole with an epoxy designed to bond to pavement surface.
3. In lieu of bolted down base, use an 8" x 8" butyl pad or hot melt butyl. Remove butyl as close as possible to pavement surface.




BARRICADE BLADE DETAIL

NOTE: For barricade markings use alternating orange and white retroreflective stripes, sloping downward in the direction traffic is to pass. Place retroreflective sheeting on both sides of the rails with a minimum of 270 square inches of visible retroreflective area facing vehicular traffic. When the barricade length is less than 36", use a rail stripe width of 4".




TYPE | BARRICADE




ELEVATION VIEW

BARRICADE ASSEMBLY DETAIL (Aluminum Barricade Rails)




TYPE II BARRICADE


BARRICADE RAIL DETAILS



TYPE III BARRICADE



DELINEATORS



ELEVATION VIEW

BARRICADE ASSEMBLY DETAIL (Wood or Plastic Rails)

SIDE VIEW

MINIMUM BALLAST
(For each side of barricade support)

Without Sign	4 - 25 lb sandbags
With Sign	6 - 25 lb sandbags


Note: Number of sandbags based on a wind speed of 55 MPH. Sandbags assumed to be placed at or near the ends of the skids.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-3-13	
REVISIONS	
DATE	CHANGE
9-27-17 11-01-19	Updated to active voice Revised details for Flexible Delineator


This document was originally
issued and sealed by
Kirk J Hoff,
Registration Number
PE-4683,
on 11/1/19 and the original
document is stored at the
North Dakota Department
of Transportation

CONSTRUCTION SIGN PUNCHING AND MOUNTING DETAILS


Note: In curb sections, place signs a minimum horizontal distance of 2' from face of the curb to near edge of the sign.




TYPICAL SECTION
(48" x 48" diamond warning sign shown)




24" x 24"
ROUTE MARKER
ASSEMBLY




36" x 36"
ROUTE MARKER
ASSEMBLY




18" x 18"
DIAMOND SIGN




108" x 48" SIGN




48" x 48" DIAMOND SIGN
(with 30" x 30" secondary sign)




48" x 48" DIAMOND SIGN
(with 30" x 24" secondary sign)




R1-2-60 - YIELD SIGN




W14-3-64 - PENNANT SIGN




R1-1-48 - STOP SIGN
(with R6-1-54 sign as required)




R1-1-48 - STOP SIGN
(with R1-50P-24 sign as required)




48" x 48" SIGN
(with R6-1-54 sign as required)




48" x 48" SIGN
(with R2-1aP-24 sign as required)




24" x 36" SIGN




30" x 24" SIGN




72" x 36" SIGN




72" x 24" SIGN




60" x 24" SIGN



48" x 24" SIGN



PORTABLE SIGN SUPPORT
LOW-MOUNTING HEIGHT



PORTABLE SIGN SUPPORT
HIGH-MOUNTING HEIGHT

NOTES:

1. Sign Supports: Galvanize or paint supports. Minimum post sizes are 2.5 lb/ft u-channel or 2" x 2" x 12 gauge steel perforated tube, except where noted. When installing signs on u-channel, minimum post size for assemblies containing a secondary sign is 3.0 lb/ft. Post sizes based on a wind speed of 55 MPH.

Place signs over 50 square feet on 2½" x 2½" perforated tube supports as a minimum.

Do not attach guy wires to sign supports. Attach wind beams behind sign panels when used with u-posts.
2. Sign Panels: Provide sign panels made of 0.100" aluminum, ½" plywood, or other approved material, except where noted. Punch all holes round for ⅝" bolts.
3. Alternate Messages: Install and remove alternate message signs on reflectorized plate (without borders) as required. (i.e. "Left" and "Right" message on lane closure sign)
4. Route Marker Auxiliary Signs: Provide route marker auxiliary signs, such as the cardinal direction and directional arrows, with a background and legend that match the route marker they are used with:

Interstate - white legend on blue background
Interstate Business Loop - white legend on green background
US and State - black legend on white background
County - yellow legend on blue background

5. Vertical Clearance: Install signs with a vertical clearance of 5'-0" (see TYPICAL SECTION.). In areas where parking or pedestrian movements are likely or the view of the sign may be obstructed, install signs with a vertical clearance of 7'-0" from the top of the curb or from the near edge of the driving lane in absence of a curb.

The vertical clearance to secondary signs is 1'-0" less than the vertical clearance stated above.

Provide a minimum clearance of 7'-0" from the ground at the post for signs with an area exceeding 50 square feet.

6. Portable Signs: Provide portable signs that meet the vertical clearance stated above when it is necessary to place signs within the pavement surface.

Use of low-mounting height (minimum 12" vertical clearance) portable signs for 5 days or less, is allowed as long as the view of the sign is not obstructed. Time delays caused by unforeseen circumstances, such as equipment breakdown, rain, subgrade failures, etc., will not accrue towards the 5 day period. Use of R9-8 through R9-11a series, W1-6 through W1-8 series, M4-10, and E5-1 is allowed for longer than 5 days.

Restrict signs mounted on portable sign supports shown in the LOW-MOUNTING HEIGHT and HIGH-MOUNTING HEIGHT details to a maximum surface area of 16 square feet.

MINIMUM BALLAST
(For each side of sign support base)

Sign Panel Mounting Height (ft)	Number of 25 lb sandbags for 4' x 4' sign panel
1'	6
5'	8
7'	10

Note: The number of sandbags are based on a wind speed of 55 MPH. Place sandbags at or near the ends of skids.


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-4-13	
REVISIONS	
DATE	CHANGE
11-14-13	Revised Note 6
9-27-17	Updated to active voice
11-01-19	Revised 60"x24" sign detail

This document was originally issued and sealed by

Kirk J Hoff,
Registration Number
PE-4683,
on 11/1/19 and the original document is stored at the North Dakota Department of Transportation

LANE CLOSURE ON A TWO LANE ROAD USING TRAFFIC CONTROL SIGNALS

D-704-16



SPEED LIMIT ENFORCED
MINIMUM FEE \$80
WHEN WORKERS PRESENT
G20-55-96
Post mounted

SPEED LIMIT ENFORCED
MINIMUM FEE \$80
WHEN WORKERS PRESENT
G20-55-96
Post mounted

KEY	
	Work Area
	Type III Barricade
	Sign
	Delineator Drum
	Wood Pole

Notes

- Span conductor overhead between poles except on bridges, where it may alternately be attached and supported by the bridge structure. When conductor is supported by the bridge structure, attach conductor to avoid interference with bridge construction. Attach conductor on either side of bridge as determined by field personnel.
- Locate controller on a wood pole in the cable run between signal heads for through traffic movements.
- The timing schedule is suggested trial setting. Check signals in operation frequently to obtain the most efficient timing schedule.
- Place wood poles a minimum of 16 feet from edge of driving lane. Provide a minimum 16 to 19 feet clearance from the center line of the roadway to the bottom of traffic signal heads suspended over the roadway.
- Place traffic signal heads with 12 inch red, yellow and green lenses and 5 inch louvered backplates.
- See standard drawing "Span Wire Mounted Traffic Signals" for interim traffic construction details.
- Re-establish speed limit. Determine exact speed limit in the field, dependent on location and conditions.
- Determine the reduced speed limit based on the in-place speed limit before construction. Where speed reductions exceed 30 MPH, install a second speed limit sign with the desired speed reduction (not to exceed 30 MPH.) Place the second speed limit sign at 1/2 B.
- Install flags on warning signs in urban areas when signs are not portable. Mount 24 inch square flags perpendicular to the edges of the sign, and at such a distance above the edge that the flag does not touch the sign when limp.
- Cover existing speed limit signs within a reduced speed zone.
- Place barricades on moveable assemblies and signs on portable assemblies when located on roadway.
- As an option, use portable sign supports in lieu of post mounted signs in accordance with NDDOT Standard Drawing D-704-14.
- Continue double yellow centerline thru private drives.
- Sign G20-55-96 is not required if layout is part of other traffic control or if work is less than 15 days.
- Recommend using 40 mph speed limit in vicinity of workers, unless location and conditions dictate otherwise.
- As an option, use solar powered signals instead of wood pole signal system.

ADVANCE WARNING SIGN SPACING			
Road Type	Distance Between Signs Min. (ft)		
	A	B	C
Urban - Low Speed (30 mph or less)	150	150	150
Urban - Low Speed (over 30 to 40 mph)	280	280	280
Urban - High Speed (over 40 mph to 50 mph)	360	360	360
Rural - High Speed (over 50 mph to 65 mph)	720	720	720
Urban Expressway and Freeway (55 mph to 60 mph)	850	1350	2200
Rural Expressway and Freeway (70 mph to 75 mph)	1000	1500	2640
Interstate/4-Lane Divided (Maintenance and Surveying)	750	1000	1500


SUGGESTED TIMING AND SIGNAL SEQUENCE						
Heads 1 & 2	Green	Yellow	Red			
Heads 3 & 4	Red		Green	Yellow	Red	
Time						
Cycle = 90 seconds	18.0	4.5	22.5	18.0	4.5	22.5
Percent of Cycle	20	5	25	20	5	25

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-27-13	
REVISIONS	
DATE	CHANGE
11-20-15	Revised Note 6. Renumbered Minimum Fee plaque.
8-17-17 11-01-19	Revised notes & added note Revise sign Nos & pvmt mkg type

This document was originally issued and sealed by
Kirk J Hoff,
Registration Number
PE- 4683,
on 11/1/19 and the original document is stored at the North Dakota Department of Transportation

SIGN LAYOUT FOR ONE LANE CLOSURE TWO LANE ROADWAY

D-704-17



Notes

1. Place barricades on moveable assemblies and signs on portable assemblies when located on roadway.
2. Remove existing striping as required. Use back to back delineators when inslope is 4:1 or flatter and roadway alignment is visible to approaching vehicles. Place back to back vertical panels when roadways have steep slopes and alignment is not visible to approaching traffic.
3. Re-establish speed limit. Determine exact speed limit in the field, dependent on location and conditions.
4. Determine the reduced speed limit based on the in-place speed limit before construction. Where speed reductions exceed 30 MPH, install a second speed limit sign with the desired speed reduction (not to exceed 30 MPH.) Place the second speed limit sign at 1/2 B.
5. Install flags on warning signs in urban areas when signs are not portable. Mount 24 inch square flags perpendicular to the edges of the sign, and at such a distance above the edge that the flag does not touch the sign when limp.
6. As an option, use portable sign supports in lieu of post mounted signs in accordance with NDDOT Standard Drawing D-704-14.
7. Cover existing speed limit signs within a reduced speed zone.
8. Sign G20-55-96 is not required if layout is part of other traffic control or if work is less than 15 days.
9. Recommend using 40 mph speed limit in vicinity of workers, unless location and conditions dictate otherwise.


ADVANCE WARNING SIGN SPACING			
Road Type	Distance Between Signs Min. (ft)		
	A	B	C
Urban - Low Speed (30 mph or less)	150	150	150
Urban - Low Speed (over 30 to 40 mph)	280	280	280
Urban - High Speed (over 40 mph to 50 mph)	360	360	360
Rural - High Speed (over 50 mph to 65 mph)	720	720	720
Urban Expressway and Freeway (55 mph to 60 mph)	850	1350	2200
Rural Expressway and Freeway (70 mph to 75 mph)	1000	1500	2640
Interstate/4-Lane Divided (Maintenance and Surveying)	750	1000	1500

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-27-13	
REVISIONS	
DATE	CHANGE
8-17-17 11-01-19	Note update & sign numbers Removed signs & revised note

This document was originally issued and sealed by
Kirk J Hoff,
Registration Number
PE- 4683,
on 11/1/19 and the original document is stored at the North Dakota Department of Transportation

TERMINAL AND SEAL COAT SIGN LAYOUTS

D-704-20



1. Place barricades on moveable assemblies and signs on portable assemblies when located on roadway.
 2. Determine the exact speed limit in the field, based on location and conditions.
 3. Determine the reduced speed limit based on the in place speed limit before construction. Where speed limit reductions exceed 30 MPH, install a second speed limit sign with the desired speed reduction (not to exceed 30 MPH.) Place the second speed limit sign at ½ B.
 4. Install flags on warning signs in urban areas when signs are not portable. Mount 24 inch square flags perpendicular to the edges of the sign, and at such a distance above the edge that the flag does not touch the sign when limp.
 5. Cover existing speed limit signs within a reduced speed zone.
 6. On seal coat projects, place signs R2-1-48, R2-1aP-24, R4-1-48, W22-8-48 and W20-52P-54 after all important intersections and at five mile intervals. Place sign W8-12-48 after all important intersections and at 2 mile intervals until short term center line pavement marking is placed.
 7. As an option, use portable sign supports in lieu of post mounted signs in accordance with the NDDOT Standard Drawing D-704-14.
 8. Cover or remove speed limit signs from layout Type H when loose aggregate is removed.
 9. Install sign G20-1b-60 when work is suspended for winter.
 10. Use other traffic control layouts in immediate work areas. Place sign R2-1aP-24 below speed limit signs in reduced speed limit work areas.
 11. Sign G20-55-96 is not required if work is less than 15 days.
 12. Recommend using 40 mph speed limit in vicinity of workers, unless location and conditions dictate otherwise.


ADVANCE WARNING SIGN SPACING			
Road Type	Distance Between Signs Min. (ft)		
	A	B	C
Urban - Low Speed (30 mph or less)	150	150	150
Urban - Low Speed (over 30 to 40 mph)	280	280	280
Urban - High Speed (over 40 mph to 50 mph)	360	360	360
Rural - High Speed (over 50 mph to 65 mph)	720	720	720
Urban Expressway and Freeway (55 mph to 60 mph)	850	1350	2200
Rural Expressway and Freeway (70 mph to 75 mph)	1000	1500	2640
Interstate/4-Lane Divided (Maintenance and Surveying)	750	1000	1500

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-27-13	
REVISIONS	
DATE	CHANGE
8-17-17 11-01-19	Updated notes & sign numbers. Note & sign updates.

This document was originally issued and sealed by
 Kirk J Hoff,
 Registration Number
 PE- 4683,
 on 11/1/19 and the original document is stored at the
 North Dakota Department
 of Transportation

PORTABLE SIGN SUPPORT ASSEMBLY

D-704-50



Notes:


- ① The maximum weight of the assembly is 250 pounds.
- ② Use a 14" wheel and tire.
- ③ Automotive and equipment axle assemblies may not be used for trailer-mounted sign supports.
- ④ Other NCHRP 350 crash tested assemblies are acceptable.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
11-23-10	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by
Roger Weigel
Registration Number
PE- 2930 ,
on 11/23/10 and the original document is stored at the
North Dakota Department
of Transportation

PORTABLE PRECAST CONCRETE MEDIAN BARRIER
(TEMPORARY USAGE)


D-704-51




Plan View




End View




Connecting Bolt Detail
(One per 10 Ft section)




Bolt Connection Detail



C1 Bar Detail




Dap Detail




U3 Bar Detail

Notes:


1. Galvanize all exposed hardware as per ASTM A153, except for the loop inserts.
2. Use AAE-3 Concrete.
3. Provide steel in accordance with Section 612 of NDDOT Standard Specifications.
4. Imprint barrier ends A and B as shown with 4 inch letters. Field match A end with B end.
5. Place barrier markers at the center of the barrier at 20' centers.
6. Connect barrier sections with 1 1/4" Dia A-307 double hex connecting bolt. Maintain bottom nut and washer connection for duration of barrier installation.
7. Place barrier to minimize openings between individual sections.




U1 Bar Detail



U2 Bar Detail



Side View



Barrier Marker Detail

Use same color reflective faces as the edge line along barrier edge. Two way reflective on Surface 1 & 2.

Marker Body
Use high impact, weatherable engineering thermo-plastic material conforming to the following:

Property	Result	ASTM Test Method
Thickness (min)	.090"	—
Tensile strength (min psi) @ yield	5,500	D638
Impact strength @ -20°F (ft-lbs/in of notch)	3.2	D256 Method A
Impact strength @ 73°F (ft-lbs/in of notch)	14.0	D256 Method A
Flexural strength, PSI 1/4" @ 73°F	8,000	D790
Flexural modulus, PSI 1/4" @ 73°F	300,000	D790
Elongation @ yield	30%	D638

Reflective Tape
Use retroreflective, acrylic microprism material with acrylic backing. 3" wide, providing the following minimum optical performance with an observation angle of 0.1° measured in candlepower for the reflector:

Entrance Angle	Specific Intensity
Yellow - 4"	136
White - 4"	200

Adhesive
Use factory applied solid butyl rubber 1/8" thick, 2" wide on 2 1/4" wide release paper on surface 3 to temporarily mount markers to portable concrete barrier.

Bar List				
Mark	Size	No.	Length	Shape
C1	4	6	9'- 4"	Straight
U1	4	2	4'- 8"	Bent
U2	4	2	4'- 10 1/4"	Bent
U3	4	15	5'- 4"	Bent


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-20-12	
REVISIONS	
DATE	CHANGE
9-27-17 11-01-19	Updated to active voice New Design Engr PE Stamp

This document was originally issued and sealed by
Kirk J Hoff,
Registration Number
PE- 4683,
on 11/1/19 and the original document is stored at the
North Dakota Department
of Transportation


PAVEMENT MARKING

D-762-4


- NOTES:
- 1. Continue edge lines through private drives and field drives. Break edge lines for intersections.




Two Lane Two Way
RURAL ROADWAY




Two Lane Roadway
INTERSTATE HIGHWAY
Concrete Section




RURAL FIVE LANE ROADWAY
Concrete Section




Two Lane Divided
Rural Roadway
PRIMARY HIGHWAY
Asphalt Section




RURAL FIVE LANE ROADWAY
Asphalt Section




URBAN FIVE LANE SECTION
Concrete Section




Two Lane Roadway
PRIMARY HIGHWAY
Concrete Section




URBAN FIVE LANE SECTION
Asphalt Section




RURAL FOUR LANE ROADWAY
Asphalt Section




Two Lane Roadway
INTERSTATE HIGHWAY
Asphalt Section




RURAL FOUR LANE ROADWAY
Concrete Section



URBAN FOUR LANE SECTION
Asphalt Section



URBAN FOUR LANE SECTION
Concrete Section






CENTERLINE PAVEMENT MARKING SKIP SPACING DETAIL

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
12-1-10	
REVISIONS	
DATE	CHANGE
10-17-17 08-27-19	Updated to active voice. New Design Engineer PE Stamp.

This document was originally issued and sealed by
Kirk J Hoff,
Registration Number
PE-4683,
on 8/27/19 and the original document is stored at the
North Dakota Department
of Transportation



W-BEAM GUARDRAIL GENERAL DETAILS

- NOTES:
- Place reflector plates at the first post and spaced at 25' centers on guardrail less than 250' in length and at 50' centers for guardrail over 250' in length. Use reflector the same color as the pavement marking adjacent to that reflector unless noted otherwise on the plans.
 - Dispose of excess earth from excavations for guard posts as directed by the engineer. Replace bituminous material where guardrail is installed after mat is placed. Include cost of excavation and replacing of bituminous material in the price bid for other items.
 - Place Object Marker within the vertical edges of the Impact Plate. Use type XI retroreflective sheeting meeting the requirements of Section 894.02.B of the standard specifications. Apply sheeting to 0.100 Aluminum sheeting meeting the requirements Section 894.01.A. Attach the Object Marker to the Impact Head Plate with non-rust rivets or some other non-rust attachment device. Slope stripes downward toward the roadway side.
 - Guardrail installation height tolerance = - 1/4" , + 1".
 - Standard W-Beam rail post bolt slot spacing is 6'-3". Post bolt slot spacing of 3'-1 1/2" is acceptable.




REFLECTORIZED PLATE DETAIL


Additional reflectors are added to the W-beam guardrail quantities for placement on end treatment.




W BEAM TERMINAL CONNECTOR




TYPICAL POST ATTACHMENT DETAIL




C6x8 RUB RAIL AND SPLICE PLATE




5/8" Diameter Guardrail Bolt	
L	Thread Length
1 1/4"	Full length thread
2"	1 3/4" Min thread length
9 1/2"	4" Min thread length
18"	4" Min thread length
20"	4" Min thread length
22"	4" Min thread length
25"	4" Min thread length




5/8" GUARDRAIL BOLT & RECESS NUT




5/8" Diameter Carriage Bolt	
L	Thread Length
1 1/2"	Full length thread
3"	1 1/2" Min thread length
11"	1 3/4" Min thread length
13"	1 3/4" Min thread length




5/8" CARRIAGE BOLT & NUT



SPLICE DETAIL



IMPACT HEAD OBJECT MARKER



W-BEAM CROSS SECTION

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-11-13	
REVISIONS	
DATE	CHANGE
10-25-19	Updated notes to active voice and added Note 5.

This document was originally issued and sealed by

Kirk J Hoff,

Registration Number

PE- 4683,

on 10/25/19 and the original document is stored at the North Dakota Department of Transportation

D-764-10




NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-11-13	
REVISIONS	
DATE	CHANGE


This document was originally
issued and sealed by
Roger Weigel,
Registration Number
PE- 2930 ,
on 10/11/13 and the original
document is stored at the
North Dakota Department
of Transportation

TYPICAL GRADING AT BRIDGE ENDS
WITH W-BEAM GUARDRAIL


D-764-22




TYPICAL SECTION



PLAN LAYOUT
FLARED GUARDRAIL WITH END TERMINAL



PLAN LAYOUT
NON-FLARED GUARDRAIL WITH TANGENT END TERMINAL



PLAN LAYOUT
NON-FLARED GUARDRAIL WITH FLARED END TERMINAL

NOTES:

- (A) Slope flatter than 10:1 may be required to provide proper guardrail height.
- (B) Where normal inslope is 4:1 the added fill shall be 4:1. Where normal inslope is 6:1 the added fill shall be 6:1.
- (C) Measured from top of guardrail to top of surfacing at front face of guardrail.
- (D) Dimension at end terminals may vary per Plan Layouts shown on this sheet.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-3-13	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by
Roger Weigel,
Registration Number
PE-2930,
on 10-3-13 and the original document is stored at the
North Dakota Department
of Transportation