

1

# **TABLE OF CONTENTS**

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	BRJ-0030(50)	2	1


LIST OF STANDARD DRAWINGS


## **PLAN SECTIONS**

Section	Page(s)	Description	Number	Description
1	1	Title Sheet	D-101-1, 2,3,4	NDDOT Abbreviations
2	1	Table of Contents	D-101-10	NDDOT Utility Company and Organization Abbreviations
4	1 - 2	Scope of Work	D-101-20, 21	Line Styles
6	1	Notes	D-101-30, 31,32,33	Symbols
6	2	Environmental Notes	D-260-1	Erosion And Siltation Controls - Silt Fence
8	1	Quantities	D-261-1	Erosion Control - Fiber Roll Placement Details
10	1	Basis of Estimate	D-704-7	Breakaway Systems For Construction Zone Signs - Perforated Tube
20	1 - 4	General Details	D-704-8	Breakaway Systems For Construction Zone Signs - U-Channel Post
30	1	Typical Sections	D-704-9	Construction Sign Details - Terminal And Guide Signs
60	1 - 2	Plan & Profile	D-704-10	Construction Sign Details - Regulatory Signs
75	1 - 2	Wetland Impacts	D-704-11	Construction Sign Details - Warning Signs
76	1 - 2	Temporary Erosion Control	D-704-13	Barricade And Channelizing Device Details
77	1 - 2	Permanent Erosion Control	D-704-14	Construction Sign Punching And Mounting Details
81	1	Survey Coordinate and Curve Data	D-704-15	Road Closure Layouts
100	1 - 3	Work Zone Traffic Control	D-704-19	Road Closure And Lane Closure On A Two Way Road Layouts
170	1 - 6	Bridges and Box Culverts	D-704-50	Portable Sign Support Assembly
200	1 - 7	Cross Sections	D-714-22	Concrete Pipe, Cattle Pass, or Precast Concrete Box Culvert Ties
			D-752-1	Standard Barbed Wire Fence
			D-754-82	Object Markers
			D-754-82	Object Markers

### **SPECIAL PROVISIONS**

Number	Description
PSP 69(24)	Permits and Environmental Considerations
SP 417(24)	Structural and Channel Excavation, Foundation Fill and Preparation
SP 418(24)	Temporary Water Diversion
SSP 1	Temporary Erosion and Sediment Best Management Practices
SSP 2	Federal Migratory Bird Treaty Act
SSP 3	Local Agency Contracts
SSP 6	Gravel Road Specifications






STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	BRJ-0030(50)	6	1

#### **GENERAL NOTES**

- 105-P01 UTILITIES: The horizontal utility locations shown in the plans are approximate. Plan locations should not be interpreted as exact for bidding purposes.
- 203-010 SHRINKAGE: 25 Percent additional volume is included for shrinkage in earth embankment.
- 203-P01 TOPSOIL: Topsoil will be paid at plan quantity.
- 203-P02 COMMON EXCAVATOIN TYPE B: Measurement of "Common Excavation Type B" will be paid at plan quantity. Excess excavation must be disposed of by the Contractor. Furnish the Engineer copies of all agreements with property owners. Include all costs associated with disposing the excess excavation in the price bid for "Common Excavation-Type B".
- 203-P03 CHANNEL EXCAVATION: Excavation required to shape the channel shall be included in the Lump Sum Bid item "Channel Excavation." There is an estimated quantity of 1,701 CY of Channel Excavation at Bridge No. 30-152-35.0 and 334 CY of Channel Excavation at Bridge No. 30-158-27.0.
- 251-P01 SEEDING & COVER CROP: Measurements for seeding and cover crop will be paid at plan quantity.
- 253-P01 MULCH: Mulch will be paid at plan quantity.
- 704-P01 TRAFFIC CONTROL: The traffic control devices list has been developed using the following layout on the Standard Drawing for traffic Control.
  - 1. Standard D-704-19, Type E for Road Closed.
- 752-P01 TEMPORARY FENCE: Temporary fence to be installed as Barbed Wire 3 Strand fence as specified in Section 752, "Fencing". Install temporary fence in conjuncture with permanent fence to preserve the continuity of existing fence lines during construction. The cost to install and remove temporary fencing is included in the price bid for "Temporary Fence".



<b>ENVIRONMEN</b>	TAL NOTES
-------------------	-----------

ENVIRONMENTAL NOTES (EN): Morton County, the North Dakota Department of Transportation, and the Federal Highway Administration has made environmental commitments to secure approval of this project. The following environmental notes are requirements to comply with these commitments:

EN-1 THREATENED AND ENDANGERED SPECIES: The project is located near/within suitable habitat for the species listed in the following table

<u>SPECIES</u>	<u>HABITAT</u>	PRESENCE
Northern Long- Eared Bat	Forested/Wooded Areas/Bridges/Box Culverts/Caves/Mines	Active Season: April 1 - October 31* Inactive Season: November 1 - March 31*

<sup>\*</sup>Time frames can differ slightly, depending on the year

If any of the above species are identified within 1 mile of the project, the Contractor will notify the Engineer immediately and cease construction activities in the vicinity until an avoidance area is established. The Engineer will establish an avoidance area that is at least a 0.5 mile and immediately coordinate with the USFWS (701-355-8513), FHWA (701-221-9464), and NDDOT Environmental and Transportation Services (701-328-2592). The Contractor will not resume work within the avoidance area until the Engineer has confirmed with the agencies that work may proceed (either the species have left the area, or approved avoidance/minimization measures have been implemented).

EN-2 AQUATIC NUISANCE SPECIES (ANS): Equipment that was last used outside of North Dakota or within a Class I infested waterbody (identified on the North Dakota Game and Fish Department (NDGFD) website) requires an inspection by NDGFD. Notify the NDGFD at least 10 business days prior to pumps, watercraft, or any equipment entering a public water to allow the NDGFD sufficient time to inspect any and all such equipment for ANS. Contact the NDGFD ANS Coordinator, Ben Holen by e-mail - bholen@nd.gov for equipment inspections. Supply one of the following to the engineer as proof of compliance prior to work taking place in the water: (1) the NDGFD inspection report, (2) documented NDGFD correspondence (email or signed letter).

<u>EN-3 TEMPORARY WETLAND IMPACT:</u> Temporary impact areas within wetlands and or other waters are incorporated into the plans for this project. Remove temporary fill placed and sedimentation in wetlands or other waters. Restore these wetlands to preconstruction contours.


<u>EN-4 WETLAND MITIGATION</u>: Wetland mitigation is required for unavoidable permanent wetland impacts. The wetland mitigation plan is incorporated into the plans for this project. After completion of the mitigation area, the Engineer will complete the Onsite Mitigation Certification Form SFN 61042. Any sedimentation occurring within the mitigation area will be removed.

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	BRJ-0030(50)	6	2

### PERMITS REQUIRED:

United States Army Corp of Engineers – Section 404 Permit Status: Has been obtained for the project.

North Dakota Department of Environmental Quality – NDPDES Permits Status: To be obtained by the Contractor prior to construction, owner to be listed as Morton County on the permit.



# **Estimated Quantities**

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
,	ND	BRJ-0030(50)	8	1

Mainline:	<b>BRJ</b>
-----------	------------

SPEC	CODE	ITEM DESCRIPTION	UNIT	Mailline. Div	TOTAL
103	0100	CONTRACT BOND	L SUM	1	
202	0104	REMOVAL OF STRUCTURE	EA	2	2
202	0312	REMOVE EXISTING FENCE	LF	679	679
203	0102	COMMON EXCAVATION-TYPE B	CY	1376	1376
203	0109	TOPSOIL	CY	959	959
210	0050	BOX CULVERT EXCAVATION	EA	2	2
210	0128	CHANNEL EXCAVATION-SITE 1	L SUM	1	1
210	0129	CHANNEL EXCAVATION-SITE 2	L SUM	1	1
210	0210	FOUNDATION FILL	CY	320	320
210	0250	BOX CULVERT FOUNDATION AGGREGATE	CY	370	370
210	0405	FOUNDATION PREPARATION-BOX CULVERT	EA	2	2
216	0100	WATER	M GAL	54	54
251	0200	SEEDING CLASS II	ACRE	0.92	0.92
251	1000	WETLAND SEED	ACRE	0.27	0.27
251	2000	TEMPORARY COVER CROP	ACRE	1.19	1.19
253	0101	STRAW MULCH	ACRE	2.11	2.11
256	0200	RIPRAP GRADE II	CY	280	280
260	0200	SILT FENCE SUPPORTED	LF	630	630
260	0201	REMOVE SILT FENCE SUPPORTED	LF	630	630
261	0112	FIBER ROLLS 12IN	LF	480	480
261	0113	REMOVE FIBER ROLLS 12IN	LF	280	280
262	0100	FLOTATION SILT CURTAIN	LF	95	95
262	0101	REMOVE FLOTATION SILT CURTAIN	LF	95	95
350	0500	GRAVEL SURFACING	TON	799	799
606	1007	10FT X 7FT PRECAST RCB CULVERT	LF	60	60
606	3007	DBL 10FT X 7FT PRECAST RCB CULVERT	LF	60	60
606	3304	DBL 13FT X 4FT PRECAST RCB CULVERT	LF	120	120
606	7007	DBL 10FT X 7FT PRECAST RCB END SECTION	EA	2	2
606	7304	DBL 13FT X 4FT PRECAST RCB END SECTION	EA	2	2
702	0100	MOBILIZATION	L SUM	1	1
704	1000	TRAFFIC CONTROL SIGNS	UNIT	353	353
704	1052	TYPE III BARRICADE	EA	16	16
709	0100	GEOSYNTHETIC MATERIAL TYPE G	SY	740	740
709	0155	GEOSYNTHETIC MATERIAL TYPE RR	SY	420	420
752	0100	FENCE BARBED WIRE 3 STRAND	LF	651	651
752	0905	TEMPORARY FENCE	LF	553	553
752	2100	VEHICLE GATE	EA	2	2
752	2120	REMOVE VEHICLE GATE	EA	2	2
752	2995	CORNER ASSEMBLY-WOOD POST	EA	10	10
754	0803	OBJECT MARKERS - TYPE III	EA	8	8
900	1000	TEMPORARY STREAM DIVERSION	EA	2	2

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	BRJ-0030(050)	10	1

#### Basis of Estimate

#### <u>Materials</u>

350 0500 GRAVEL SURFACING @ 1.875 TON/CY


	216 0100 WA	TER	
Material	Basis	Basis Quantity	Quantity (MGAL)
Dust Palliative	25 Mgal/Mile	1 Mile	25
Aggregates	20 Gal/Ton	509 Ton	10
Embankment	10 Gal/CY	1,851 CY	19
·		Total	54

Earthwork Summary							
	203 0102	-			203 0109		
Location	COMMON EXCAVATION-TYPE B (CY)	Channel Excavation (CY)	Embankment (CY)	Waste (CY)	TOPSOIL (CY)		
Bridge No. 30-152-35	45	1,053	547	551	298		


		Earthwork Summary			
	203 0102				203 0109
Location	COMMON EXCAVATION-TYPE B (CY)	Channel Excavation (CY)	Embankment (CY)	Waste (CY)	TOPSOIL (CY)
Bridge No. 30-158-27	1,331	334	1,304	361	661

Morton County Bridge Replacement

Basis of Estimate



STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	BRJ-0030(050)	20	1



Carrier Float -Variable length curtain fabric Water Surface Anchor cable - Underwater Anchor SECTION X-X FLOTATION SILT CURTAINS

Note: Maximum water velocity for moving water = 5 ft/sec

Steel Tension Cable


#### PLAN VIEW FLOTATION SILT CURTAIN - TYPE HERRING BONE PATTERN

DESIGN GUIDELINES:


When temporary work encroaches more than  $\mbox{\ensuremath{\%}}$  width of the stream Or where stream width doesn't allow use of Type Moving Water

Morton County Bridge Replacement

Temporary Erosion Control - Flotation Silt Curtain



	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
	ND	BRJ-0030(050)	20	2




#### Notes:


- Windrow the existing topsoil from the foreslope to create a berm at the grading tie line.
- 2. 3.
- Stabilize berms in accordance with the Construction General Permit.


  Place weirs intermittently throughout the length of the berm to allow stormwater to drain through the berm. Avoid placing weirs adjacent to waterbodies.
- Install fiber rolls as the weirs are created in the topsoil berm.
- Include costs to create, stabilize, maintain, and dismantle the berm in the unit price bid for "Topsoil". Include costs for fiber rolls in the unit price bid for "Fiber Rolls 12IN".


Morton County Bridge Replacement

Temporary Topsoil Berm and Weir Detail











ExstR/W




Existing Typical Section Bridge No. 30-152-35.0




Morton County Bridge Replacement

Typical Sections



- <u>Exst™</u>





SECTION NO.

60

SHEET NO.

ENGINEER






Mitigation Summary Table										
WetlandWetlandWetlandOtherOther#1a#1b#1eWater #1cWater #1dTotal										
Onsite	0.004	0.009	0.004	0.090	0.102	0.209				
Onsite Ditch Shift										


						Other Wat	ers Imp	act Table	Э					
						Impa	cts to O	ther Wat	ers			Other	Waters Mitigation	
11			F t	USACE		Acres			Linear Feet		Mitigation	Proposed		
Number	Location	Туре	Feature	Jurisdictional	Temp.	Perm. (Fill/Drain)	Perm.	Temp.	Perm. (Fill/Drain)	Perm.	USACE	EO 1990	Mitigation Location; ratio	Onsite Acre(s)
1c	Sec 28 T-135-N R-82-W	Stream	Natural	Υ	0.078	0.045		71	50		Υ	Y	Site 1; 2:1	0.090
1d	Sec 29 T-135-N R-82-W	Stream	Natural	Y	0.044	0.051		49	50		Υ	Υ	Site 1; 2:1	0.102
				Totals	0.122	0.096	0.000	120	100	0				0.192


Morton County Bridge Replacement


Wetland Impacts


Bridge No. 30-152-35.0














2

# PRELIMINARY SURVEY COORDINATE AND CURVE DATA - Morton County Structure Replacement Bridge No. 30-152-35.0 & Bridge No. 30-158-27.0

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	BRJ-0030(050)	81	1

												,		
	HORIZON	ITAL ALIGNMEN	IT	CURVE DATA	U	S PUBLIC	LAND SURVEY	DATA		SUR	EY CON	TROL F	POINTS	
PNT	STATION	NORTHING	EASTING	ARC DEFINITION	CORNER	IRN	NORTHING	EASTING	PNT		EASTING		STATION	OFFSET
CR 82 (Chai	in: OCL_MOR1)				T-135-N R 82-V	V				M	ONUMENT DES	CRIPTION		
Begin	0+00.00	337079.107	1872707.573		NW Cor Sec 28	5-J	299,709.82	1,841,037.36		DDIM		ITDOL		
PI	2+50.00	337329.094	1872710.132		W Qtr Sec 28	5-K	297,067.86	1,841,024.72		PRIIV	ARY CON	NIROL		
End	5+00	337579.081	1872712.691		SW Cor Sec 28	5-L	294,429.03	1,841,012.21	GPS 50	338146.88	1872700.87	1804.40	10+67.64	18' Lt
									# 5 Reb	ar w/ 1.5" Alum Ca <sub>l</sub>	Stamped "GPS	50"	OCL_MOR1	
22nd Avenue	e (Chain: OCL_MOR2)				T-136-N R 81-V	V			GPS 51	336779.47	1872680.33	1817.03	-2+99.64	24' Lt
Begin	100+00.00	295532.486	1841017.215		NW Cor Sec 16	5-E	341,792.28	1,872,746.32	# 5 Reb	ar w/ 1.5" Alum Ca <sub>l</sub>	Stamped "GPS	51"	OCL_MOR1	
PI	102+50.00	295782.478	1841019.190		SW Cor Sec 16	5-G	336,486.88'	1,872,696.98'	GPS 52	296512.80	1841001.76	2015.11	109+80.17	23' Lt
End	105+00.00	296032.470	1841021.165						# 5 Reb	ar w/ 1.5" Alum Ca <sub>l</sub>	Stamped "GPS	52"	OCL_MOR2	
									GPS 53	294934.56	1841031.49	2014.81	94+20.07	19' Rt
									# 5 Reb	ar w/ 1.5" Alum Ca <sub>l</sub>	Stamped "GPS	53"	OCL_MOR2	
									-					
														_
										coordinates and me this document deriv			OFF SHOW	A Sha
										International Foot		1 (Q)	BRETA	18
					Assumed (	Coordinate -				INITIALIZING BENG	CH MARK	REGISTERED	ZELTING	ER 31 (STORY OF OFFICE OFFICE OF OFFICE OF
										BSMK		SS	LS-273	31
NOTES: Shee	et 1 of 1				All coordina County gro	and coordinates.				IAVD-88		1/2/	DATE 2025.07.1 15:29:51	6.05'00'
				Date Survey Completed 06/09/2023	reference f	erived from the Name; North Dako	ota North Zone			GEOID12A		\i	Op	(A)
					Combinatio	n Factor (cf) = 0.	9998485		_	GEOID18		`	ORTH DA	(0)

ı	ND	BRJ-0030(50)	100	1
ı	SIAIE	PROJECT NO.	NO.	NO.
٦	STATE	PROJECT NO.	SECTION	SHEET

SIGN NUMBER	SIGN SIZE	DESCRIPTION	AMOUNT REQUIRED	UNITS PER AMOUNT	UNITS SUB TOTAL
E5-1-48	48"x48"	EXIT GORE		35	
G20-1-60	60"x24"	ROAD WORK NEXT MILES		28	
G20-1b-60 G20-2-48	60"x24"	NO WORK IN PROGRESS (Sign and installation only)		18	
G20-2-48 G20-4-36	48"x24" 36"x18"	END ROAD WORK   PILOT CAR FOLLOW ME (Mounted to back of pilot car)		26 18	
G20-4-30 G20-4b-36	36"x30"	WAIT FOR PILOT CAR		18	
G20-50a-72	72"x36"	ROAD WORK NEXT MILES RT & LT ARROWS		43	
G20-52a-72	72"x24"	ROAD WORK NEXT MILES RT or LT ARROW		36	
G20-55-96	96"x48"	SPEED LIMIT ENFORCED - MINIMUM FEE \$80 WHEN WORKERS PRESENT		59	
M1-1-36	36"x36"	INTERSTATE ROUTE MARKER (Post and installation only)		11	
M1-4-24	24"x24"	U.S. ROUTE MARKER (Post and installation only)		10	
M1-5-24 M3-1-24	24"x24" 24"x12"	STATE ROUTE MARKER (Post and installation only)  NORTH (Mounted on route marker post)		10 7	
M3-2-24	24 X12 24"x12"	EAST (Mounted on route marker post)		7	
M3-3-24	24"x12"	SOUTH (Mounted on route marker post)		7	
M3-4-24	24"x12"	WEST (Mounted on route marker post)		7	
M4-8-24	24"x12"	DETOUR (Mounted on route marker post)		7	
M4-9-30	30"x24"	DETOUR ARROW RIGHT or LEFT/AHD AND RT or LT		15	
M4-10-48	48"x18"	DETOUR (INSIDE ARROW) RIGHT or LEFT (Mounted on barricade)		7	
M5-1-21	21"x15"	ADVANCE TURN ARROW RT or LT(Mounted on route marker post)		7	
M5-1-30	30"x21"	ADVANCE TURN ARROW RT or LT (Mounted on route marker post)		9	
M6-1-21 M6-1-30	21"x15" 30"x21"	DIRECTIONAL ARROW RT or LT (Mounted on route marker post)  DIRECTIONAL ARROW RT or LT (Mounted on route marker post)		9	
M6-3-21	21"x15"	DIRECTIONAL ARROW RT of ET (Mounted on route marker post)		7	
R1-1-48	48"x48"	STOP		32	
R1-2-60	60"x60"	YIELD		29	
R2-1-36	36"x48"	SPEED LIMIT (Portable only)		30	
R2-1-48	48"x60"	SPEED LIMIT		39	
R2-1aP-24	24"x18"	MINIMUM FEE \$80 (Mounted on Speed Limit post)		10	
R3-2-48 R4-1-48	48"x48"	NO LEFT TURN		35 39	
R4-1-46 R4-7-48	48"x60" 48"x60"	DO NOT PASS  KEEP RIGHT		39	
R5-1-48	48"x48"	DO NOT ENTER		35	
R6-1-54	54"x18"	ONE WAY RIGHT or LEFT (Mounted on STOP or DO NOT ENTER post)		14	
R7-1-12	12"x18"	NO PARKING ANY TIME		11	
R10-6-24	24"x36"	STOP HERE ON RED		16	
R11-2-48	48"x30"	ROAD CLOSED (Mounted on barricade)	4	12	48
R11-2a-48	48"x30"	STREET CLOSED (Mounted on barricade)		12	
R11-3a-60	60"x30"	ROAD CLOSEDMILES AHEAD LOCAL TRAFFIC ONLY (Mtd on barricade)	4	15	60
R11-3c-60 R11-4a-60	60"x30" 60"x30"	STREET CLOSED MILES AHEAD LOCAL TRAFFIC ONLY (Mtd on barricade)  STREET CLOSED TO THRU TRAFFIC (Mounted on barricade)		15 15	
W1-3-48	48"x48"	REVERSE TURN RIGHT or LEFT		35	
W1-4-48	48"x48"	REVERSE CURVE RIGHT or LEFT		35	
W1-4b-48	48"x48"	TWO LANE REVERSE CURVE RIGHT or LEFT		35	
W1-6-48	48"x24"	ONE DIRECTION LARGE ARROW		26	
W3-1-48	48"x48"	STOP AHEAD		35	
W3-3-48	48"x48"	SIGNAL AHEAD		35	
W3-4-48	48"x48"	BE PREPARED TO STOP		35	
W3-5-48	48"x48"	SPEED REDUCTION AHEAD  LANE ENDS RIGHT or LEFT		35	
W4-2-48 W5-1-48	48"x48" 48"x48"	ROAD NARROWS		35 35	
W5-8-48	48"x48"	THRU TRAFFIC RIGHT LANE		35	
W5-9-48	48"x48"	ROAD WORK TRAFFIC ONLY DOWN & LT or RT ARROW		35	
W6-3-48	48"x48"	TWO WAY TRAFFIC		35	
W8-1-48	48"x48"	BUMP		35	
W8-3-48	48"x48"	PAVEMENT ENDS		35	
W8-7-48	48"x48"	LOOSE GRAVEL		35	
W8-11-48	48"x48"	UNEVEN LANES		35	
W8-12-48 W8-17-48	48"x48" 48"x48"	NO CENTER LINE SHOULDER DROP-OFF SYMBOL		35 35	
W8-53-48	48"x48"	TRUCKS ENTERING HIGHWAY		35	
W8-54-48	48"x48"	TRUCKS ENTERING AHEAD or FT or MILE		35	
W8-55-48	48"x48"	TRUCKS CROSSING AHEAD or FT or MILE		35	
W8-56-48	48"x48"	TRUCKS EXITING HIGHWAY		35	
W9-3a-48	48"x48"	CENTER LANE CLOSED SYMBOL		35	
W13-1P-30	30"x30"	MPH ADVISORY SPEED PLAQUE (Mounted on warning sign post)		14	
W14-3-64	64"x48"	NO PASSING ZONE		28	
W16-2P-30 W20-1-48	30"x24"	FEET PLAQUE (Mounted on warning sign post)		10	
W20-1-48 W20-2-48	48"x48" 48"x48"	ROAD WORK AHEAD or _FT or _MILE  DETOUR AHEAD or _FT or _MILE		35 35	
W20-2-46 W20-3-48	48"x48"	ROAD or STREET CLOSED AHEAD or FT or _ MILE	7	35	245
W20-4-48	48"x48"	ONE LANE ROAD AHEAD OF FT OF MILE	,	35	240
W20-5-48	48"x48"	RIGHT or CENTER or LEFT LANE CLOSED AHEAD or FT or _ MILE		35	
W20-7-48	48"x48"	FLAGGER		35	
W20-8-18	18"x18"	STOP - SLOW PADDLE Back to Back		5	
W20-52P-54		NEXT MILES (Mounted on warning sign post)		12	
W21-1-48	48"x48"	WORKERS		35	
W21-2-48	48"x48"	FRESH OIL		35	
W21-3-48	48"x48"	ROAD MACHINERY AHEAD or FT or _ MILE		35	
W21-5-48	48"x48"	SHOULDER WORK RIGHT or LEFT SHOULDER CLOSED		35 35	
W21-5a-48	48"x48"				


SIGN NUMBER	SIGN SIZE	DESCRIPTION	AMOUNT REQUIRED	UNITS PER AMOUNT	UNITS SUB TOTAL
W21-6-48	48"x48"	SURVEY CREW		35	
W21-50-48	48"x48"	BRIDGE PAINTING AHEAD or FT		35	
W21-51-48	48"x48"	MATERIAL ON ROADWAY		35	
W21-52-48	48"x48"	PAVEMENT BREAKS		35	
W21-53-48	48"x48"	RUMBLE STRIPS AHEAD		35	
W22-8-48	48"x48"	FRESH OIL LOOSE ROCK		35	
W24-1-48	48"x48"	DOUBLE REVERSE CURVE		35	


SPECIAL SIGNS						

SPEC & CODE


704-1000 TRAFFIC CONTROL SIGNS TOTAL UNITS 353


NOTE:
If additional signs are
required, units will be
calculated using the formula
from Section III-18.06 of the
Design Manual.
http://www.dot.nd.gov/





Traffic Control Devices List







23 U.S.C. 407 NDDOT Reserves All Objections

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	BRJ-0030(050)	170	1







BRIDGE BID ITEMS

Drainage Area	24.8	sq mi	SPEC	CODE	ITEM DESCRIPTION	UNIT	QUANTITY
Stream Gradient	0.0015	ft/ft					
Design Frequency	25	yr	202	0104	REMOVAL OF STRUCTURE	EA	1
Design Discharge	814	cfs	210	0050	BOX CULVERT EXCAVATION	EA	1
Design Headwater Stage	1983.20	ft	210	0210	FOUNDATION FILL	CY	215
Design Tailwater Stage	1982.72	ft	210	0250	BOX CULVERT FOUNDATION AGGREGATE	CY	150
Velocity Through Culvert	4.5	fps	210	0405	FOUNDATION PREPARATION-BOX CULVERT	EA	1
100-Year Frequency Discharge	1296	cfs	256	0200	RIPRAP GRADE II	CY	120
100-Year Frequency Headwater	1984.59	ft	606	1007	10FT X 7FT PRECAST RCB CULVERT	LF	60
Overtopping Stage	1985.55	ft	606	3007	DBL 10FT X 7FT PRECAST RCB CULVERT	LF	60
Overtopping Discharge	1598	cfs	606	7007	DBL 10FT X 7FT PRECAST RCB END SECTION	EA	2
			709	0100	GEOSYNTHETIC MATERIAL TYPE G	SY	300
			709	0155	GEOSYNTHETIC MATERIAL TYPE RR	SY	180
			900	1000	TEMPORARY STREAM DIVERSION	EA	1



	<u>Q</u> Box □ □ □ □ □ □ □ □ □ □ □ □ □ □ □ □ □ □ □
0-,6	Finished Channel (typ)  The state of the sta
	(SHOWING FINISHED SECTION)  END VIEW

OTANDADD DDAWNOO					
SP 418(24)	STRUC EXCAVATION AND BACKFILL TEMPORARY WATER DIVERSION				
SP 417(24)					
SSP 2	MIGRATORY BIRD TREATY ACT				
SPECIAL PROVISIONS					

STANDARD DRAWINGS

D-714-22

#### HL-93 DESIGN LOADING

EAST BRANCH CHANTA PETA CREEK 1 MI N AND 10 MI E OF FLASHER

CLEAR SPAN 3 X 10' MIN FILL 2' MAX FILL 6' CLEAR HEIGHT 7' STATION: 102+35.07

PRECAST CONCRETE
TRIPLE BOX CULVERT LAYOUT

**HYDRAULIC DATA:** 

ERJ

# **NOTES**

23 U.S.C. 407	STATE	
NDDOT Reserves All Objections	ND	

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	BRJ-0030(050)	170	2

SCOPE OF WORK: Work at this site consists of removing an existing structure and building a new triple barrel 10' x 7' x 60'-0" precast concrete box culvert.

202 REMOVAL OF STRUCTURE: The existing structure is a 1-span timber stringer bridge, 32'-3" long with a clear roadway width of 23'-0". The deck and substructures are also made of timber. Include all work required to remove the bridge in the contract unit price for "Removal of Structure."

ORDINARY BACKFILL: Compact material as specified in Section 203.04 G.2.a, "ND T 180."

DESIGN AND LOAD RATING: Design the box culvert and box culvert end sections in accordance with the AASHTO LRFD Bridge Design Specifications, 10th Edition. Design for HL-93 live load and a fill height range from 2 ft to 6ft over the box culvert.

Load rate the box culvert in accordance with both the NDDOT Load Rating Manual and the AASHTO Manual for Bridge Evaluation, 2018 Edition, incorporating the latest Interim Revisions. Provide a box culvert design to achieve a rating factor greater than or equal to 1.0 for the design, legal, and permit trucks over the specified fill range. Include BrR Load Rating Summaries for 1 ft incremental fill depths throughout the fill range in the load rating report. Populate the NDDOT Load Rating Summary for the actual fill depth at the time of construction.

Include with the work drawing submittals a Load Rating Report sealed by a ND registered PE, and an AASHTOWare BrR Model of the structure in XML format.

PRECAST SECTION: Do not install lifting holes in walls or floor of box culvert sections. Plug lifting holes in roof with tapered concrete plugs or another method approved by the Engineer.

Tie the barrel sections together with 1"φ tie bolts as shown on Standard Drawing D-714-22. Place two ties per exterior wall joint, located at third points of the wall clear height.

A 1 EA payment for "Dbl 10Ft X 7Ft Precast RCB End Section" will be made at each end of the box for the apron, cutoff wall, parapet and wingwalls. Attach the apron to the last barrel section, the wingwalls and the cutoff wall. Attach the wingwalls to the last barrel section. Provide a welded tie type system for the connections of the apron to the box and wingwalls. Connect the wingwalls to the last barrel section by the use of tie bolts, steel-bolted plates or other approved method so the inside corner surface is smooth.

Use ASTM A36 steel for bolts, plates, angles, and studs. Use heavy hex nuts meeting the requirements of ASTM A563 and washers meeting ASTM F436, Type 1. Provide welded pipe sleeves meeting the requirements of ASTM A53, Grade B. Galvanize hardware and structural steel according to Section 854.

Welders are to meet the requirements of Section 105.06 D. Galvanize field welds according to Section 854.02.

Cast holes at 3'-0" centers through the apron and into the cutoff wall to receive \(^3\lambda''\) diameter reinforcing bars. Cast holes in the last barrel section at 1'-0" centers for \(^1\lambda''\) diameter reinforcing bars to attach the parapet. Cast parapet against the section. Install the bars according to the manufacturer's recommendations, with a high strength adhesive specifically intended for concrete anchorage, in accordance with Section 806.02.

Provide a distance of 1'-0" between separate precast units. Fill this gap with a controlled density backfill. Use a controlled density backfill consisting of cement, water, pozzolanic materials, and fillers. Use a material that is fluid on placement to flow around and fill voids in the backfill area. Use a material that is able to support normal loads after 6 hours and have a compressive strength in the range of 75 psi to 125 psi at 28 days. If the mix design shown is used, no further testing will be required. The mix design yields approximately one cubic yard of flowable mortar.

#### MIX DESIGNS

Mix Design 1		Mix Design 2 (No	Mix Design 2 (No Fly Ash)		
Cement	100 lbs	Cement	165 lbs		
Fly Ash	300 lbs	Fly Ash	NA		
Fine Aggregate	2600 lbs	Fine Aggregate	2600 lbs		
Water	70 gals	Water	50 gals		

For the 12" cap, use a weatherproof and freeze/thaw resistant, non-shrink cement grout material such as SikaGrout® 212, BASF Masterflow® 928, Euclid NS Grout, or an approved equal which complies with ASTM C1107.


Include the controlled density backfill and material used for the 12" cap in the price bid for "DbI 10Ft X 7Ft Precast RCB Culvert."

JOINTS: Provide joints in accordance with Section 606.04 E.3, with the exception that a 12" minimum width waterproof membrane is allowable around the exterior surfaces of the box culvert walls and roof.



23 U.S.C. 407 NDDOT Reserves All Objections

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	BRJ-0030(050)	170	3




#### (SHOWING SECTION ALONG € ROADWAY) GEOSYNTHETIC GEOGRID PLACEMENT AND FOUNDATION FILL THROUGH EXISTING EMBANKMENT

#### NOTES:

The intent of this detail is to show only the placement of the controlled density backfill between adjacent barrels. The representation of the size of barrels is arbitrary.


Embed the #4 bar 6" into the side of one of the box culvert end sections maintaining a 3" minimum clearance from the other box culvert. Spacing measured 1'-0" from bottom of box and spaced at 1'-0" up the front face.

Install the #4 bars according to the manufacturer's recommendations, with a high strength adhesive specifically intended for concrete anchorage and that meets the requirements of Section 806.02.



#### NOTES:


1) Extend the geosynthetic, bedding material and box culvert foundation aggregate material below the box culvert to the end of the apron.



EAST BRANCH CHANTA PETA CREEK 1 MI N AND 10 MI E OF FLASHER

**EXCAVATION & BACKFILL DETAIL** 

ERJ



# **NOTES**

23 U.S.C. 407	S
NDDOT Reserves All Objections	1

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	BRJ-0030(050)	170	5

SCOPE OF WORK: Work at this site consists of removing an existing structure and building a new quadruple barrel 13' x 4' x 60'-0" precast concrete box culvert.

202 REMOVAL OF STRUCTURE: The existing structure is a 1-span timber stringer bridge, 40'-0" long with a clear roadway width of 23'-4". The deck and substructures are also made of timber. Include all work required to remove the bridge in the contract unit price for "Removal of Structure."

ORDINARY BACKFILL: Compact material as specified in Section 203.04 G.2.a, "ND T 180."

DESIGN AND LOAD RATING: Design the box culvert and box culvert end sections in accordance with the AASHTO LRFD Bridge Design Specifications, 10th Edition. Design for HL-93 live load and a fill height range from 2 ft to 7ft over the box culvert.

Load rate the box culvert in accordance with both the NDDOT Load Rating Manual and the AASHTO Manual for Bridge Evaluation, 2018 Edition, incorporating the latest Interim Revisions. Provide a box culvert design to achieve a rating factor greater than or equal to 1.0 for the design, legal, and permit trucks over the specified fill range. Include BrR Load Rating Summaries for 1 ft incremental fill depths throughout the fill range in the load rating report. Populate the NDDOT Load Rating Summary for the actual fill depth at the time of construction.

Include with the work drawing submittals a Load Rating Report sealed by a ND registered PE, and an AASHTOWare BrR Model of the structure in XML format.

PRECAST SECTION: Do not install lifting holes in walls or floor of box culvert sections. Plug lifting holes in roof with tapered concrete plugs or another method approved by the Engineer.

Tie the barrel sections together with 1"φ tie bolts as shown on Standard Drawing D-714-22. Place two ties per exterior wall joint, located at third points of the wall clear height.

A 1 EA payment for "Dbl 13Ft X 4Ft Precast RCB End Section" will be made at each end of the box for the apron, cutoff wall, parapet and wingwalls. Attach the apron to the last barrel section, the wingwalls and the cutoff wall. Attach the wingwalls to the last barrel section. Provide a welded tie type system for the connections of the apron to the box and wingwalls. Connect the wingwalls to the last barrel section by the use of tie bolts, steel-bolted plates or other approved method so the inside corner surface is smooth.

Use ASTM A36 steel for bolts, plates, angles, and studs. Use heavy hex nuts meeting the requirements of ASTM A563 and washers meeting ASTM F436, Type 1. Provide welded pipe sleeves meeting the requirements of ASTM A53, Grade B. Galvanize hardware and structural steel according to Section 854.

Welders are to meet the requirements of Section 105.06 D. Galvanize field welds according to Section 854.02.

Cast holes at 3'-0" centers through the apron and into the cutoff wall to receive 3/4" diameter reinforcing bars. Cast holes in the last barrel section at 1'-0" centers for 1/2" diameter reinforcing bars to attach the parapet. Cast parapet against the section. Install the bars according to the manufacturer's recommendations, with a high strength adhesive specifically intended for concrete anchorage, in accordance with Section 806.02.

Provide a distance of 1'-0" between separate precast units. Fill this gap with a controlled density backfill. Use a controlled density backfill consisting of cement, water, pozzolanic materials, and fillers. Use a material that is fluid on placement to flow around and fill voids in the backfill area. Use a material that is able to support normal loads after 6 hours and have a compressive strength in the range of 75 psi to 125 psi at 28 days. If the mix design shown is used, no further testing will be required. The mix design yields approximately one cubic yard of flowable mortar.


#### MIX DESIGNS

Mix Design 1		Mix Design 2 (No Fly Ash)		
Cement	100 lbs	Cement	165 lbs	
Fly Ash	300 lbs	Fly Ash	NA	
Fine Aggregate	2600 lbs	Fine Aggregate	2600 lbs	
Water	70 gals	Water	50 gals	

For the 12" cap, use a weatherproof and freeze/thaw resistant, non-shrink cement grout material such as SikaGrout<sup>®</sup> 212, BASF Masterflow<sup>®</sup> 928, Euclid NS Grout, or an approved equal which complies with ASTM C1107.


Include the controlled density backfill and material used for the 12" cap in the price bid for "DbI 13Ft X 4Ft Precast RCB Culvert."

JOINTS: Provide joints in accordance with Section 606.04 E.3, with the exception that a 12" minimum width waterproof membrane is allowable around the exterior surfaces of the box culvert walls and roof.



23 U.S.C. 407 NDDOT Reserves All Objections

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	BRJ-0030(050)	170	6



#### (SHOWING SECTION ALONG € ROADWAY)

# GEOSYNTHETIC GEOGRID PLACEMENT AND FOUNDATION FILL THROUGH EXISTING EMBANKMENT

#### NOTES:


1) Extend the geosynthetic, bedding material and box culvert foundation aggregate material below the box culvert to the end of the apron.


#### NOTES:

The intent of this detail is to show only the placement of the controlled density backfill between adjacent barrels. The representation of the size of barrels is arbitrary.

Embed the #4 bar 6" into the side of one of the box culvert end sections maintaining a 3" minimum clearance from the other box culvert. Spacing measured 1'-0" from bottom of box and spaced at 1'-0" up the front face.

Install the #4 bars according to the manufacturer's recommendations, with a high strength adhesive specifically intended for concrete anchorage and that meets the requirements of Section 806.02.








SE BRANCH LITTLE HEART RIVER 2 MI S AND 1 MI E OF ST. ANTHONY


EXCAVATION & BACKFILL DETAIL

ERJ









SECTION NO. STATE PROJECT NO. BRJ-0030(050) 5 ND 200 Sta 2+50.00 Sta 2+25.00 -140 Sta 2+00.00 -140 Sta 1+75.00

