

DESIGN DATA			
Traffic	Average Daily		
Current 2024	Pass: 915	Trucks: 204	Total: 1,119

Preventive Maintenance

STATE	PROJECT NO.	PCN	SECTION NO.	HEET NO.
ND	SS-6-018(094)198	24711	1	1



# NORTH DAKOTA DEPARTMENT OF TRANSPORTATION

SS-6-018(094)198

Walsh County  
N JCT 17 to CO LN  
Milling and HMA

GOVERNING SPECIFICATIONS	Date Published and Adopted by the North Dakota Department of Transportation
Standard Specifications	7/1/2025
Supplemental Specifications	NONE

PROJECT NUMBER \ DESCRIPTION    NET MILES    GROSS MILES  
SS-6-018(094)198    9.135    9.135



STATE COUNTY MAP

DESIGNER
Adam Gorecki
DESIGNER
DESIGNER

ND DEPARTMENT OF TRANSPORTATION  
GRAND FORKS DISTRICT

*John S. Johnson* 1/29/25







TABLE OF CONTENTS			STATE	PROJECT NO.	SECTION NO.	SHEET NO.
			ND	SS-6-018(094)198	2	1
PLAN SECTIONS			LIST OF STANDARD DRAWINGS			
Section	Page(s)	Description	Number	Description		
1	1 - 1	Title Sheet	D-101-1, 2,3,4	NDDOT Abbreviations		
2	1 - 1	Table of Contents	D-101-10	NDDOT Utility Company and Organization Abbreviations		
4	1 - 1	Scope of Work	D-101-20, 21	Line Styles		
6	1 - 2	Notes	D-101-30, 31,32,33	Symbols		
8	1 - 1	Quantities	D-704-2	Traffic Control For Coring Of Hot Bituminous Pavement		
10	1 - 2	Basis of Estimate	D-704-7	Breakaway Systems For Construction Zone Signs - Perforated Tube		
20	1 - 4	General Details	D-704-8	Breakaway Systems For Construction Zone Signs - U-Channel Post		
30	1 - 2	Typical Sections	D-704-9	Construction Sign Details - Terminal And Guide Signs		
90	1 - 1	Paving Layouts	D-704-10	Construction Sign Details - Regulatory Signs		
100	1 - 2	Work Zone Traffic Control	D-704-11, 11A	Construction Sign Details - Warning Signs		
120	1 - 1	Pavement Marking	D-704-13	Barricade And Channelizing Device Details		
			D-704-14	Construction Sign Punching And Mounting Details		
			D-704-15	Road Closure Layouts		
			D-704-17	Sign Layout For One Lane Closure Two Lane Roadway		
			D-704-20	Terminal And Seal Coat Sign Layouts		
			D-704-22	Construction Truck And Temporary Detour Layouts		
			D-704-26	Miscellaneous Sign Layouts		
			D-704-27	Mobile Operation (Pavement Marking)		
			D-704-33	Two-Lane Roadway Portable Rumble Strips		
			D-704-50	Portable Sign Support Assembly		
			D-704-56	Mobile Operation - Grinding Shoulder Rumble Strips		
			D-706-1	Bituminous Laboratory		
			D-760-3	Rumble Strips Undivided Highways (Shoulders 4' Or Greater)		
			D-760-4	Rumble Strips Undivided Highways (Shoulders Less Than 4')		
			D-762-1	Pavement Marking Message Details		
			D-762-4	Pavement Marking		
			D-762-5	Pavement Marking for Standard 90 Degree Flared Intersection-(No Center Left Turn Lane on Major Road)		
			D-762-11	Short-Term Pavement Marking		
SPECIAL PROVISIONS						
Number	Description					
PSP 25(25)	Permits and Environmental Considerations					
SP 184(25)	E-ticketing (Mandatory)					
SP 210(25)	Railroad Requirements					
SSP 4	Longitudinal Joint Density					

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	SS-6-018(094)198	4	1	



Scope of Work

Milling and HMA  
N JCT 17 to CO LN



STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	SS-6-018(094)198	6	1

## NOTES

100-P01 COORDINATION OF PROJECTS: Another project in the vicinity of this project is under contract during the 2026 construction season. This project is SS-6-066(038)112-Chip Seal and is located from Crystal E to N Jct 81-St. Thomas.

107-P03 MAINTAINING TRAFFIC - DROP-OFFS: If, at the end of the workday, drop-offs greater than 2 inches and less than 18 inches or slopes steeper than 4:1 exist between the edge of a traffic lane and the outside edge of the proposed roadway, perform one of the following actions:

- Construct a traversable wedge in the area of the drop-off or steep slope; or
- Close the lane adjacent to the drop-off or steep slope and provide 24-hour flagging operations.

When constructing a wedge, construct a wedge composed of aggregate or earthen materials with a 4:1 or flatter slope along the entire length of the area. Compact materials using Type C compaction, as specified in 203.04 G.4, "Compaction Control Type C".

Install stackable vertical panels that meet the requirements of Section 704.03 H, "Stackable Vertical Panels", along the edge of the driving lane closest to the wedge.

The Engineer will measure stackable vertical panels as specified in Section 704.05, "Method of Measurement" and will pay for panels as specified in Section 704.06, "Basis of Payment".

The Engineer will not measure material used to construct the wedge. Include the cost of materials, equipment, labor, and incidentals required for this operation in the price bid for other pay items.

If a 4:1 or flatter wedge is not installed, provide 24-hour flagging operations and associated traffic control at no additional cost to the Department.

The requirements of Section 704.04 O, "Traffic Control for Uneven Pavement" apply to drop-offs created by milling or the placement of hot mix asphalt.

302-P01 AGGREGATE BASE COURSE CL 5: Use a road widening/shouldering machine for the placement of the "AGGREGATE BASE COURSE CL 5" on the shoulders. Placement of the aggregate material by motor grader will not be allowed. Equipment and method to be approved by the Engineer. Include all costs for furnishing materials, equipment, labor and incidentals in the contract unit price for "AGGREGATE BASE COURSE CL 5".

Complete final shape and compaction of shoulder material within 21 working days after mainline paving is completed on SS-6-018(094)198. Liquidated Damages for failure to complete the shouldering within 21 working days will be charged according to Section 108.07.

302-P02 AGGREGATE BASE COURSE CL 5: 350 tons Aggregate Base Course CL 5 has been provided in the quantities to fill in around the radii of approaches. This material will be required when sloughs are steeper than 4:1.

302-P03 SALVAGED BASE COURSE:

Use one of the following Materials:

- Salvage material produced by uniformly blending the existing hot mix asphalt pavement, bituminous base, and aggregate from the project
- Class 5 aggregates meeting the requirements of section 816.

Use the same type of material throughout the project.

If salvage material is used, the following additional requirements apply:


- Produce material with a maximum particle size of 1.5 inches.

Such payment is full compensation for furnishing all materials, equipment, labor, and incidentals to complete such work as specified.

411-P01 TEMPORARY ASPHALT WEDGES: Place temporary asphalt wedges at the beginning and end of the project and paved approaches to allow smooth passage of vehicles at these milled locations. Place wedges at these milled areas prior to the traffic being allowed back on the milled roadway section. Millings may be used instead of asphalt for all wedges. Include all costs associated with labor, materials, and equipment for the installation, maintenance, and removal of the wedges in the contract price bid for "MILLING PAVEMENT SURFACE".

411-P02 MILLED MATERIAL: Stockpile all remaining milled material at the NDDOT Cavalier Maintenance Yard in Cavalier. Notify the Section Supervisor (701-741-1519) 72 hours prior to delivery of any millings. Stockpile material with a front-end loader. Do not operate on the milled material while stockpiling. Include all costs for labor and equipment to mill, haul, and stockpile the material in the contract price for "MILLING PAVEMENT SURFACE".

430-200 FOG SEAL: Apply a fog seal at a rate of 0.05 Gal/SY to the final surface of the hot mix asphalt if the ND T 113 "Lightweight Pieces in Virgin Aggregate" test results exceeds 3.0% during mix design or production of the hot mix asphalt. Apply the fog seal behind the finish roller before the mat temperature drops below 130 degrees Fahrenheit. Use the same emulsion material as the Tack Coat. Apply the fog seal at no additional cost to the Department.



STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	SS-6-018(094)198	6	2

## NOTES

704-500 PORTABLE RUMBLE STRIPS (PRS): Use PRS made of rubber or engineered polymers.

Install PRS as part of the temporary traffic control when the following signs are also part of the required traffic control set up:

- "Be Prepared to Stop" (W3-4); and
- "Flagger" symbol (W20-7)

Install PRS that meet the following criteria:

- Have no adhesives or fasteners required for placement.
- Have a manufacturer's speed rating that meets or exceeds the posted speed limit; and
- Each strip in the array must weigh a minimum of 100 pounds.

Use individual PRS constructed in one of the following manners:

- A single piece.
- Interlocking segments; or
- Two pieces hinged at the midpoint.

An installed array of PRS consists of a minimum of 3 individual strips.

Move rumble strips with the flagging operation. Do not place rumble strips on horizontal curves.

The Engineer will count and measure each array as one unit. Include the cost of providing, installing, maintaining, and relocating PRS in the unit price bid for "Portable Rumble Strips".


704-P01 TRAFFIC CONTROL FOR MILLING, HMA, AND PATCHING: Provide traffic control consisting of a temporary lane closure, flagging, and a pilot car.

Traffic control device quantities are based on a 6-mile lane closure and the list below. The Department will pay for all necessary deployed devices, regardless of the length of the lane closure.

1. Standard D-704-15, Type A;
2. Standard D-704-20, Type G – signing will be required at junctions;
3. Standard D-704-22, Types K and L;
4. Standard D-704-26, Types CC, EE, and GG; and
5. Standard D-704-33.

Place flaggers and traffic control devices as shown on Standard D-704-15, Type A at the following intersections when the lane closure spans across them:

1. Walsh County 9 West;
2. Walsh County 9 East; and
3. Walsh County 1.



# ESTIMATE OF QUANTITIES

STATE	PROJECT NO.	SECTION NO.	HEET NO.
ND	SS-6-018(094)198	8	1

SPEC CODE	ITEM DESCRIPTION	UNIT	MAINLINE	TOTAL
103 0100	CONTRACT BOND	L SUM	0.52	0.52
107 0100	RAILWAY PROTECTION INSURANCE	L SUM	1	1
107 0141	RAILROAD COORDINATION - COMPANY A	L SUM	1	1
109 1000	E-TICKETING	L SUM	0.52	0.52
302 0101	RESCUED BASE COURSE	CY	141	141
302 0120	AGGREGATE BASE COURSE CL 5	TON	3,659	3,659
401 0050	TACK COAT	GAL	12,085	12,085
411 0105	MILLING PAVEMENT SURFACE	SY	161,019	161,019
430 0143	RAP - SUPERPAVE FAA 43	TON	17,754	17,754
430 1000	CORED SAMPLE	EA	154	154
430 2000	PATCHING	TON	226	226
430 5815	PG 58S-34 ASPHALT CEMENT	TON	931	931
702 0100	MOBILIZATION	L SUM	0.52	0.52
704 0100	FLAGGING	MHR	648	648
704 1000	TRAFFIC CONTROL SIGNS	UNIT	2,572	2,572
704 1048	PORTABLE RUMBLE STRIPS	EA	3	3
704 1067	TUBULAR MARKERS	EA	240	240
704 1080	STACKABLE VERTICAL PANELS	EA	20	20
704 1185	PILOT CAR	HR	180	180
706 0550	BITUMINOUS LABORATORY	EA	0.52	0.52
706 0600	CONTRACTOR'S LABORATORY	EA	0.52	0.52
709 0100	GEOSYNTHETIC MATERIAL TYPE G	SY	1,014	1,014
760 0025	SINUSOIDAL RUMBLE STRIP - ASPHALT SHOULDER	MILE	17.362	17.362
760 0027	SINUSOIDAL RUMBLE STRIP - ASPHALT CENTERLINE	MILE	8.681	8.681
762 0103	PVMT MK PAINTED-MESSAGE	SF	265	265
762 0432	SHORT TERM 6IN LINE-TYPE NR	LF	79,447	79,447
762 1106	PVMT MK PAINTED 6IN LINE	LF	118,834	118,834
762 1112	PVMT MK PAINTED 12IN LINE	LF	358	358
762 1124	PVMT MK PAINTED 24IN LINE	LF	102	102

## BASIS OF ESTIMATE


STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	SS-6-018(094)198	10	1

Design Calculations			
	Unit	Width	Quantity
<b>Typical Section 1 (0.024 Miles)</b>			
Milling Pavement Surface (34.4 ft x 5280 LF/Mi ÷ 9 SF/SY = 20182 SY/Mi)	SY	34.4'	484
RAP - Superpave FAA 43 (5.6038 SF x 5280 LF ÷ 27 CF/CY x 2 Ton/CY= 2192 Ton/Mi)	Ton	34.4'	53
PG 58S-34 Asphalt Cement @ 5.2 % (0.052 x 2192 Ton/Mi = 114 Ton/Mi)	Ton	34.4'	3
Tack @ 0.075 Gal/SY (34.4 ft x 5280 LF/Mi ÷ 9 SF/SY x 0.075 Gal/SY = 1514 Gal/Mi)	Gal	34.4'	37
Aggregate Base Course CL 5 (Shoulders) (0.2386 SF x 5280 LF ÷ 27 CF/CY x 1.875 Ton/CY= 88 Ton/Mi)	Ton	3' RT	3
<b>Typical Section 2 (3.735 Miles)</b>			
Milling Pavement Surface (30.4 ft x 5280 LF/Mi ÷ 9 SF/SY = 17835 SY/Mi)	SY	30.4'	66,614
RAP - Superpave FAA 43 (5.0386 SF x 5280 LF ÷ 27 CF/CY x 2 Ton/CY= 1971 Ton/Mi)	Ton	30.4'	7,362
PG 58S-34 Asphalt Cement @ 5.2 % (0.052 x 1971 Ton/Mi = 103 Ton/Mi)	Ton	30.4'	385
Tack @ 0.075 Gal/SY (30.4 ft x 5280 LF/Mi ÷ 9 SF/SY x 0.075 Gal/SY = 1338 Gal/Mi)	Gal	30.4'	4,998
Aggregate Base Course CL 5 (Shoulders) (0.4602 SF x 5280 LF ÷ 27 CF/CY x 1.875 Ton/CY= 169 Ton/Mi)	Ton	3' LT/RT	632
<b>Typical Section 3 (4.853 Miles)</b>			
Milling Pavement Surface (28.8 ft x 5280 LF/Mi ÷ 9 SF/SY = 16896 SY/Mi)	SY	28.8'	81,997
RAP - Superpave FAA 43 (4.7248 SF x 5280 LF ÷ 27 CF/CY x 2 Ton/CY= 1848 Ton/Mi)	Ton	28.8'	8,969
PG 58S-34 Asphalt Cement @ 5.2 % (0.052 x 1848 Ton/Mi = 98 Ton/Mi)	Ton	28.8'	471
Tack @ 0.075 Gal/SY (28.8 ft x 5280 LF/Mi ÷ 9 SF/SY x 0.075 Gal/SY = 1268 Gal/Mi)	Gal	28.8'	6,154
Aggregate Base Course CL 5 (Shoulders) (1.2376 SF x 5280 LF ÷ 27 CF/CY x 1.875 Ton/CY= 454 Ton/Mi)	Ton	7.8' LT/RT	2,204
<b>Typical Section 4 (0.054 Miles)</b>			
Milling Pavement Surface (28.8 ft x 5280 LF/Mi ÷ 9 SF/SY = 16896 SY/Mi)	SY	28.8'	913
RAP - Superpave FAA 43 (4.7248 SF x 5280 LF ÷ 27 CF/CY x 2 Ton/CY= 1848 Ton/Mi)	Ton	28.8'	100
PG 58S-34 Asphalt Cement @ 5.2 % (0.052 x 1848 Ton/Mi = 97 Ton/Mi)	Ton	28.8'	6
Tack @ 0.075 Gal/SY (28.8 ft x 5280 LF/Mi ÷ 9 SF/SY x 0.075 Gal/SY = 1268 Gal/Mi)	Gal	28.8'	69
Aggregate Base Course CL 5 (Shoulders) (1.0476 SF x 5280 LF ÷ 27 CF/CY x 1.875 Ton/CY= 385 Ton/Mi)	Ton	7.8' LT/RT	21

Additional Quantities			
Description	Unit	Basis	Quantity
<b>Approaches</b>			
Aggregate Base Course CL 5	Ton		799
Milling Pavement Surface	SY		7,250
Tack Coat 0.075 Gal/SY	Gal		545
RAP Superpave FAA 43 @ 2 Tons/CY	Ton		852
PG 58S-34 Asphalt Cement @ 5.2%	Ton		44
<b>Patches</b>			
Patching @ 2 Tons/CY	Ton		226
Salvaged Base Course	CY		141
Geosynthetic Material Type G	SY		1,014
<b>Truck Inspection Turnout</b>			
Milling Pavement Surface	SY		3,761
Tack Coat 0.075 Gal/SY	Gal		282
RAP Superpave FAA 43 @ 2 Tons/CY	Ton		418
PG 58S-34 Asphalt Cement @ 5.2%	Ton		22

Estimated Available Milled Material Quantities			
Milled Material Available	Milled Area (SF)	Length	Tons (1.875 Ton/CY)
Typical 1	5.6244	0.024	49
Typical 2	5.0732	3.735	6,948
Typical 3	4.7800	4.853	8,506
Typical 4	4.8006	0.054	94
Approaches	See Sec 20 Sheet 1		755
Additional Quantities	See Sec 90 Sheet 1		392
<b>Total (Less 10% for losses)</b>			<b>15,070</b>

Estimated Required & Remaining Milled Material Quantities	% RAP by Mix Design
Milled Material required for production of RAP - Superpave FAA 43 (17,754 tons RAP-Superpave FAA 43)	10% Min      25% Max
	1,776      4,439
Milled Material to become the property of the NDDOT	13,294      10,631



## BASIS OF ESTIMATE

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	SS-6-018(094)198	10	2

Temporary Pavement Marking		
Location	Basis	Quantity
<b>RP 198.812 to RP 207.582 (8.770 Mi) (3 Applications)</b>		
Short Term 6IN Line - Type NR Yellow Skip Line (10' Line, 30' Skip)	1,320 LF/Mi	34,730 LF
Short Term 6IN Line - Type NR Yellow Single Barrier Line	5,280 LF/Mi	23,586 LF
Short Term 6IN Line - Type NR Yellow Double Barrier Line	10,560 LF/Mi	21,131 LF

Permanent Pavement Marking		
Location	Basis	Quantity
<b>RP 198.486 to RP 207.582 (9.096 Mi)</b>		
Pvmt Mk Painted 6IN Yellow Skip Line (10' Line, 30' Skip)	1,320 LF/Mi	11,127 LF
Pvmt Mk Painted 6IN Yellow Single Barrier Line	5,280 LF/Mi	7,862 LF
Pvmt Mk Painted 6IN Yellow Double Barrier Line	10,560 LF/Mi	2,891 LF
Pvmt Mk Painted 6IN White Edge Lines	10,560 LF/Mi	96,054 LF


Additional Quantities		
Location	Basis	Quantity
<b>JCT ND 17 &amp; ND 18 N</b>		
Pvmt Mk Painted 24IN White STOP Bar		42 LF
<b>Dakota Northern Railroad</b>		
Pvmt Mk Painted Message - White (RR Cross, 2 R's, 3 Bands on Each approach of track)	See D-762-1	265 SF
<b>Truck Inspection Turnout</b>		
Pvmt Mk Painted 12IN White Channel Line	5,280 LF/Mi	358 LF
<b>JCT Walsh Co Rd 11 East - Pvmt Mk for Flared Intersection, No Hatching</b>		
Pvmt Mk Painted 6IN Line White Edge Lines		180 LF
Pvmt Mk Painted 24IN White (STOP Bar)		12 LF
<b>JCT Walsh Co Rd 9 East - Pvmt Mk for Flared Intersection, No Hatching</b>		
Pvmt Mk Painted 6IN Line White Edge Lines		180 LF
Pvmt Mk Painted 24IN White (STOP Bar)		12 LF
<b>JCT Walsh Co Rd 9 West - Pvmt Mk for Flared Intersection, No Hatching</b>		
Pvmt Mk Painted 6IN Line White Edge Lines		180 LF
Pvmt Mk Painted 24IN White (STOP Bar)		12 LF
<b>JCT Walsh Co Rd 1B - Pvmt Mk for Flared Intersection, No Hatching</b>		
Pvmt Mk Painted 6IN Line White Edge Lines		180 LF
Pvmt Mk Painted 24IN White (STOP Bar)		12 LF
<b>JCT Walsh Co Rd 1A - Pvmt Mk for Flared Intersection, No Hatching</b>		
Pvmt Mk Painted 6IN Line White Edge Lines		180 LF
Pvmt Mk Painted 24IN White (STOP Bar)		12 LF

Sec 120,  
Sheet 1

Total Pavement Marking		
	White	Yellow
Short Term 6IN Line - Type NR		79,447 LF
Pvmt Mk Painted 6IN Line	96,954 LF	21,880 LF
Pvmt Mk Painted 12IN Line	358 LF	
Pvmt Mk Painted 24IN Line	102 LF	
Pvmt Mk Painted Message	265 SF	

Barrier Striping Locations		
From RP to RP	Single Barrier (Mi)	Double Barrier (Mi)
198.486	198.667	0.181
199.435	199.888	0.453
200.394	200.520	0.126
200.520	200.595	0.075
200.623	200.651	0.028
200.651	200.754	0.103
200.754	200.902	0.148
202.424	202.584	0.160
202.584	202.728	0.144
204.441	204.582	0.141
204.582	204.734	0.152
205.590	205.720	0.130
205.720	205.849	0.129
206.484	206.589	0.105
206.589	206.799	0.210
206.873	206.979	0.106
206.979	207.165	0.186
207.450	207.585	0.135
	1.489	0.667

Sinusoidal Rumble Strips - Asphalt Shoulder and Centerline		
Location	Basis	Quantity
<b>RP 198.812 to RP 207.582 (0.089 Mi of rumble strip exceptions for Bridge # 0018-203.479)</b>		
Sinusoidal Rumble Strips - Asphalt Centerline	1 Mi/mi	8.681
Sinusoidal Rumble Strips - Asphalt Shoulder	2 Mi/mi	17.362






STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	SS-6-018(094)198	10	3

## BASIS OF ESTIMATE

Estimated Flagging & Pilot Car Hours			
Operation	Basis	Flagging	Pilot Car
Milling Pavement	6 days x 12 Hr/Day x 4 Flaggers 6 days x 12 Hr/Day x 1 pilot car	288 MHR	72 HR
Patching	3 days x 12 Hr/Day x 2 flaggers 3 days x 12 Hr/Day x 1 pilot car	72 MHR	36 HR
HMA	6 days x 12 Hr/Day x 4 Flaggers 6 days x 12 Hr/Day x 1 pilot car	288 MHR	72 HR







HMA Cored Samples							
	A	B		C			
Specification Section	Distance (Ft) ÷ 1000	Lanes	Joints	Lifts	Quantity (A x B x C)	Quantity (1 per mile)	Unit
430.04 I.2.b(1), "General"	46	2	N/A	1	92	N/A	EA
SSP4 Longitudinal Joint Density in HMA Pavements (Centerline)	46	N/A	1	1	46	N/A	EA
430.04 I.2.b(2) "Pavement Thickness Determination Cores"	N/A	N/A	N/A	N/A	N/A	N/A	EA
Patching							
430.04 I.2.b(1), "General"	3	2		2	12	N/A	EA
SSP4 Longitudinal Joint Density in HMA Pavements (Centerline)	2	NA	1	2	4	N/A	EA
430.04 I.2.b(2) "Pavement Thickness Determination Cores"	N/A	N/A	N/A	N/A	N/A	N/A	EA
		Total		154	N/A	EA	





Notes:


1. Actual HMA paving and aggregate base course locations may vary in the field, as approved by the Engineer.
2. Quantity totals have been included in the bid items of the "Estimate of Quantities" of the plans.
3. 350 tons Aggregate base course has been provided in the quantities to fill in around the radii. This material will be required when sloughs are steeper than 4:1 (see section C-C)



BASIS OF ESTIMATE		(1)	(2)	(3)	(4)	
ITEM	UNIT	Paved Section Line	Gravel Section Line	Gravel Private Drive	Field Drive	TOTALS
Number of Locations	#	4	14	27	33	78
Aggregate Base Course CL 5	TON	N/A	6.0	8.0	4.5	449
Milling Pavement Surface	SY	420.1	193.5	67.1	44.5	7,250
Tack Coat	GAL	31.5	14.5	5.1	3.3	545
RAP Superpave FAA 43	TON	46.7	21.5	7.5	4.9	852
PG 58S-34 Asphalt Cement	TON	2.4	1.1	0.4	0.3	44

Approach Details

Milling and HMA  
N JCT 17 to CO LN




	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
		ND		

SS-6-018(094)198 Approach Locations								
198.816	LT	Gravel Private Drive	201.440	RT	Gravel Private Drive	205.092	LT	Gravel Field Approach
198.906	RT	Gravel Field Approach	201.527	LT	Gravel Section Line	205.386	LT	Gravel Field Approach
198.906	LT	Gravel Private Drive	201.527	LT	Gravel Section Line	205.400	LT	Gravel Private Drive
199.062	LT	Gravel Private Drive	201.807	LT	Gravel Field Approach	205.440	RT	Gravel Private Drive
199.062	RT	Gravel Field Approach	201.807	RT	Gravel Field Approach	205.465	LT	Gravel Private Drive
199.216	RT	Gravel Private Drive	202.118	LT	Gravel Private Drive	205.495	LT	Gravel Private Drive
199.350	LT	Gravel Private Drive	202.214	LT	Gravel Field Approach	205.495	RT	Gravel Private Drive
199.475	LT	Gravel Private Drive	202.214	RT	Gravel Field Approach	205.535	RT	Gravel Private Drive
199.550	LT	Gravel Section Line	202.404	LT	Gravel Field Approach	205.586	LT	Gravel Section Line
199.550	RT	Gravel Section Line	202.529	RT	Gravel Field Approach	205.586	RT	Gravel Section Line
199.744	RT	Gravel Section Line	202.569	LT	Gravel Section Line	205.620	LT	Gravel Private Drive
199.992	LT	Gravel Field Approach	202.569	RT	Paved Section Line	205.655	LT	Gravel Private Drive
200.054	RT	Gravel Field Approach	202.784	LT	Gravel Private Drive	205.745	RT	Gravel Private Drive
200.161	LT	Gravel Field Approach	202.959	RT	Gravel Field Approach	205.829	LT	Gravel Field Approach
200.282	RT	Gravel Field Approach	203.083	RT	Gravel Section Line	205.849	RT	Gravel Private Drive
200.367	RT	Gravel Private Drive	203.430	LT	Gravel Private Drive	205.954	RT	Gravel Private Drive
200.367	LT	Gravel Field Approach	203.580	LT	Gravel Section Line	206.304	RT	Gravel Field Approach
200.511	LT	Gravel Section Line	203.580	RT	Gravel Section Line	206.459	RT	Gravel Private Drive
200.576	LT	Gravel Field Approach	203.649	RT	Gravel Private Drive	206.459	LT	Gravel Field Approach
200.576	RT	Gravel Field Approach	203.714	LT	Gravel Field Approach	206.594	LT	Paved Section Line
200.744	LT	Gravel Field Approach	203.853	LT	Gravel Field Approach	206.594	RT	Gravel Section Line
200.744	RT	Paved Section Line	204.082	RT	Gravel Field Approach	206.884	RT	Gravel Private Drive
200.996	RT	Gravel Field Approach	204.082	LT	Gravel Field Approach	207.258	RT	Gravel Private Drive
201.116	LT	Gravel Field Approach	204.587	RT	Gravel Section Line	207.295	LT	Gravel Field Approach
201.237	RT	Gravel Field Approach	204.587	LT	Paved Section Line	207.326	RT	Gravel Private Drive
201.318	LT	Gravel Field Approach	205.021	RT	Gravel Field Approach	207.346	RT	Gravel Field Approach

Approach Locations


Milling and HMA  
N JCT 17 to CO LN





1. The exact locations, lengths and widths to be patched will be determined by the Engineer in the field.
2. Broken or unstable bituminous surfacing will be removed and replaced according to Section 430.04 G.
3. Remove existing base and subgrade material to the depth required to obtain a stable subgrade. Replace removed base and subgrade material with salvaged base course and compact.
4. The patching must meet specified density. The requirements of Section 430.04 I.2 apply.
5. Include all costs to remove & dispose of unstable material, cut vertical edges, apply tack oil, the cost for aggregate and asphalt cement to produce HMA, and placement in the contract price for PATCHING. Include all costs to haul, place and compact salvaged base course in the contract unit price for SALVAGED BASE COURSE.

Basis of Estimate						
Location				Patching (Ton) 4" Typical	Salvaged Base Course (CY) 5" Typical	Geosynthetic Material Type G (SY)
Begin RP	End RP	Length (FT)	Width (FT)			
203.490	203.511	111	32	88	55	395
205.700	205.718	95	32	75	47	338
205.720	205.735	79	32	63	39	281
Totals				226	141	1,014



Patching



Salvaged Base Course







Typical Milling Pavement Surface & HMA

Patching Details

Milling and HMA  
N JCT 17 to CO LN



	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	SS-6-018(094)198	20	4	







Milling & Paving Transitions

Milling and HMA  
N JCT 17 to CO LN



	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	SS-6-018(094)198	30	1	




Typical Section 1




Milling and HMA  
N JCT 17 to CO LN



	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	SS-6-018(094)198	30	2	



2" Recycled HBP-Superpave FAA 43  
1" Hot Bituminous Pavement  
1.5" Maintenance Patch  
1.5" Hot Bituminous Pavement  
2" Hot Bituminous Pavement  
5" Bituminous Base





Typical Section 2




Milling and HMA  
N JCT 17 to CO LN



	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	SS-6-018(094)198	30	3	




	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	SS-6-018(094)198	30	4	





\*Detail and quantities for PATCHING, SALVAGED BASE COURSE, and GEOSYNTHETIC MATERIAL TYPE G on Section 20 Sheet 3.

Typical Section 4

Milling and HMA  
N JCT 17 to CO LN




	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	SS-6-018(094)198	90	1	



#### Basis of Estimate

Milling Pavement Surface	3,761 SY
RAP - Superpave FAA 43 @ 2 Tons/CY	418 Tons
PG 58S-34 Asphalt Cement @ 5.2%	22 Tons
Tack Coat @ 0.075 Gals/SY	282 Gals



2" Milling & 2" HMA (Additional Quantity)



Typical Section 2

Milling & Paving Layout  
Additional Quantities  
Truck Inspection Turnout



Milling and HMA  
N JCT 17 to CO LN




SIGN NUMBER	SIGN SIZE	DESCRIPTION	AMOUNT REQUIRED	UNITS PER AMOUNT	UNITS SUB TOTAL
E5-1-48	48"x48"	EXIT GORE		35	
G20-1-60	60"x24"	ROAD WORK NEXT __ MILES		28	
G20-1b-60	60"x24"	NO WORK IN PROGRESS (Sign and installation only)		18	
<b>G20-2-48</b>	<b>48"x24"</b>	<b>END ROAD WORK</b>	<b>2</b>	<b>26</b>	<b>52</b>
<b>G20-4-36</b>	<b>36"x18"</b>	<b>PILOT CAR FOLLOW ME (Mounted to back of pilot car)</b>	<b>1</b>	<b>18</b>	<b>18</b>
G20-4b-36	36"x30"	WAIT FOR PILOT CAR		18	
<b>G20-50a-72</b>	<b>72"x36"</b>	<b>ROAD WORK NEXT __ MILES RT &amp; LT ARROWS</b>	<b>5</b>	<b>43</b>	<b>215</b>
<b>G20-52a-72</b>	<b>72"x24"</b>	<b>ROAD WORK NEXT __ MILES RT or LT ARROW</b>	<b>2</b>	<b>36</b>	<b>72</b>
<b>G20-55-96</b>	<b>96"x48"</b>	<b>SPEED LIMIT ENFORCED - MINIMUM FEE \$150 WHEN WORKERS PRESENT</b>	<b>1</b>	<b>59</b>	<b>59</b>
M1-1-36	36"x36"	INTERSTATE ROUTE MARKER (Post and installation only)		11	
M1-4-24	24"x24"	U.S. ROUTE MARKER (Post and installation only)		10	
M1-5-24	24"x24"	STATE ROUTE MARKER (Post and installation only)		10	
M3-1-24	24"x12"	NORTH (Mounted on route marker post)		7	
M3-2-24	24"x12"	EAST (Mounted on route marker post)		7	
M3-3-24	24"x12"	SOUTH (Mounted on route marker post)		7	
M3-4-24	24"x12"	WEST (Mounted on route marker post)		7	
M4-8-24	24"x12"	DETOUR (Mounted on route marker post)		7	
M4-9-30	30"x24"	DETOUR ARROW RIGHT or LEFT/AHD AND RT or LT		15	
M4-10-48	48"x18"	DETOUR (INSIDE ARROW) RIGHT or LEFT (Mounted on barricade)		7	
M5-1-21	21"x15"	ADVANCE TURN ARROW RT or LT(Mounted on route marker post)		7	
M5-1-30	30"x21"	ADVANCE TURN ARROW RT or LT(Mounted on route marker post)		9	
M6-1-21	21"x15"	DIRECTIONAL ARROW RT or LT (Mounted on route marker post)		7	
M6-1-30	30"x21"	DIRECTIONAL ARROW RT or LT (Mounted on route marker post)		9	
M6-3-21	21"x15"	DIRECTIONAL ARROW UP (Mounted on route marker post)		7	
R1-1-48	48"x48"	STOP		32	
R1-2-60	60"x60"	YIELD		29	
R2-1-36	36"x48"	SPEED LIMIT __ (Portable only)	10	30	300
R2-1-48	48"x60"	SPEED LIMIT __		39	
<b>R2-1aP-24</b>	<b>24"x18"</b>	<b>MINIMUM FEE \$150 (Mounted on Speed Limit post)</b>	<b>6</b>	<b>10</b>	<b>60</b>
R3-2-48	48"x48"	NO LEFT TURN		35	
<b>R4-1-48</b>	<b>48"x60"</b>	<b>DO NOT PASS</b>	<b>4</b>	<b>39</b>	<b>156</b>
R4-7-48	48"x60"	KEEP RIGHT		39	
R5-1-48	48"x48"	DO NOT ENTER		35	
R6-1-54	54"x18"	ONE WAY RIGHT or LEFT (Mounted on STOP or DO NOT ENTER post)		14	
R7-1-12	12"x18"	NO PARKING ANY TIME		11	
R10-6-24	24"x36"	STOP HERE ON RED		16	
R11-2-48	48"x30"	ROAD CLOSED (Mounted on barricade)		12	
R11-2a-48	48"x30"	STREET CLOSED (Mounted on barricade)		12	
R11-3a-60	60"x30"	ROAD CLOSED __ MILES AHEAD LOCAL TRAFFIC ONLY (Mtd on barricade)		15	
R11-3c-60	60"x30"	STREET CLOSED __ MILES AHEAD LOCAL TRAFFIC ONLY (Mtd on barricade)		15	
R11-4a-60	60"x30"	STREET CLOSED TO THRU TRAFFIC (Mounted on barricade)		15	
W1-3-48	48"x48"	REVERSE TURN RIGHT or LEFT		35	
W1-4-48	48"x48"	REVERSE CURVE RIGHT or LEFT		35	
W1-4b-48	48"x48"	TWO LANE REVERSE CURVE RIGHT or LEFT		35	
W1-6-48	48"x24"	ONE DIRECTION LARGE ARROW		26	
W3-1-48	48"x48"	STOP AHEAD		35	
W3-3-48	48"x48"	SIGNAL AHEAD		35	
<b>W3-4-48</b>	<b>48"x48"</b>	<b>BE PREPARED TO STOP</b>	<b>4</b>	<b>35</b>	<b>140</b>
<b>W3-5-48</b>	<b>48"x48"</b>	<b>SPEED REDUCTION AHEAD</b>	<b>4</b>	<b>35</b>	<b>140</b>
W4-2-48	48"x48"	LANE ENDS RIGHT or LEFT		35	
W5-1-48	48"x48"	ROAD NARROWS		35	
W5-8-48	48"x48"	THRU TRAFFIC RIGHT LANE		35	
W5-9-48	48"x48"	ROAD WORK TRAFFIC ONLY DOWN & LT or RT ARROW		35	
W6-3-48	48"x48"	TWO WAY TRAFFIC		35	
<b>W8-1-48</b>	<b>48"x48"</b>	<b>BUMP</b>	<b>10</b>	<b>35</b>	<b>350</b>
W8-3-48	48"x48"	PAVEMENT ENDS		35	
W8-7-48	48"x48"	LOOSE GRAVEL		35	
<b>W8-11-48</b>	<b>48"x48"</b>	<b>UNEVEN LANES</b>	<b>4</b>	<b>35</b>	<b>140</b>
<b>W8-12-48</b>	<b>48"x48"</b>	<b>NO CENTER LINE</b>	<b>4</b>	<b>35</b>	<b>140</b>
W8-17-48	48"x48"	SHOULDER DROP-OFF SYMBOL		35	
W8-53-48	48"x48"	TRUCKS ENTERING HIGHWAY		35	
W8-54-48	48"x48"	TRUCKS ENTERING AHEAD or __ FT or __ MILE	2	35	70
<b>W8-55-48</b>	<b>48"x48"</b>	<b>TRUCKS CROSSING AHEAD or __ FT or __ MILE</b>	<b>2</b>	<b>35</b>	<b>70</b>
W8-56-48	48"x48"	TRUCKS EXITING HIGHWAY		35	
W9-3a-48	48"x48"	CENTER LANE CLOSED SYMBOL		35	
W13-1P-30	30"x30"	__ MPH ADVISORY SPEED PLAQUE (Mounted on warning sign post)		14	
W14-3-64	64"x48"	NO PASSING ZONE		28	
W16-2P-30	30"x24"	__ FEET PLAQUE (Mounted on warning sign post)		10	
<b>W20-1-48</b>	<b>48"x48"</b>	<b>ROAD WORK AHEAD or __ FT or __ MILE</b>	<b>6</b>	<b>35</b>	<b>210</b>
W20-2-48	48"x48"	DETOUR AHEAD or __ FT or __ MILE		35	
W20-3-48	48"x48"	ROAD or STREET CLOSED AHEAD or __ FT or __ MILE		35	
W20-4-48	48"x48"	ONE LANE ROAD AHEAD or __ FT or __ MILE		35	
W20-5-48	48"x48"	RIGHT or CENTER or LEFT LANE CLOSED AHEAD or __ FT or __ MILE		35	
<b>W20-7-48</b>	<b>48"x48"</b>	<b>FLAGGER</b>	<b>6</b>	<b>35</b>	<b>210</b>
<b>W20-8-18</b>	<b>18"x18"</b>	<b>STOP - SLOW PADDLE Back to Back</b>	<b>6</b>	<b>5</b>	<b>30</b>
W20-52P-54	54"x12"	NEXT __ MILES (Mounted on warning sign post)		12	
W21-1-48	48"x48"	WORKERS		35	
<b>W21-2-48</b>	<b>48"x48"</b>	<b>FRESH OIL</b>	<b>2</b>	<b>35</b>	<b>70</b>
W21-3-48	48"x48"	ROAD MACHINERY AHEAD or __ FT or __ MILE		35	
W21-5-48	48"x48"	SHOULDER WORK		35	
W21-5a-48	48"x48"	RIGHT or LEFT SHOULDER CLOSED		35	
W21-5b-48	48"x48"	RIGHT or LEFT SHOULDER CLOSED AHEAD or __ FT or __ MILE		35	

SIGN NUMBER	SIGN SIZE	DESCRIPTION	AMOUNT REQUIRED	UNITS PER AMOUNT	UNITS SUB TOTAL
W21-6-48	48"x48"	SURVEY CREW		35	
W21-50-48	48"x48"	BRIDGE PAINTING AHEAD or __ FT		35	
W21-51-48	48"x48"	MATERIAL ON ROADWAY		35	
W21-52-48	48"x48"	PAVEMENT BREAKS		35	
<b>W21-53-48</b>	<b>48"x48"</b>	<b>RUMBLE STRIPS AHEAD</b>	<b>2</b>	<b>35</b>	<b>70</b>
W22-8-48	48"x48"	FRESH OIL LOOSE ROCK		35	
W24-1-48	48"x48"	DOUBLE REVERSE CURVE		35	
<b>SPECIAL SIGNS</b>					
<b>SPEC &amp; CODE</b>					
<b>704-1000 TRAFFIC CONTROL SIGNS</b>					
<b>TOTAL UNITS</b>					
<b>2572</b>					
<b>SPEC &amp; CODE</b>					
<b>DESCRIPTION</b>					
<b>UNIT QUANTITY</b>					
704-0100	FLAGGING		MHR	648	
704-1048	PORTABLE RUMBLE STRIPS		EACH	3	
704-1050	TYPE I BARRICADES		EACH		
704-1052	TYPE III BARRICADES		EACH		
704-1060	DELINERATOR DRUMS		EACH		
704-1065	TRAFFIC CONES		EACH		
<b>704-1067</b>	<b>TUBULAR MARKERS</b>		EACH	240	
704-1070	DELINERATOR		EACH		
704-1072	FLEXIBLE DELINERATORS		EACH		
<b>704-1080</b>	<b>STACKABLE VERTICAL PANELS</b>		EACH	20	
704-1081	VERTICAL PANELS - BACK TO BACK		EACH		
704-1085	SEQUENCING ARROW PANEL - TYPE A		EACH		
704-1086	SEQUENCING ARROW PANEL - TYPE B		EACH		
704-1087	SEQUENCING ARROW PANEL - TYPE C		EACH		
<b>704-1185</b>	<b>PILOT CAR</b>		HR	180	
704-1500	OBLITERATION OF PVMT MK		SF		
704-3501	PORTABLE PRECAST CONCRETE MED BARRIER		LF		
704-3510	PRECAST CONCRETE MED BARRIER - STATE FURNISHED		EACH		
762-0200	RAISED PAVEMENT MARKERS		EACH		
762-0420	SHORT TERM 4IN LINE - TYPE R		LF		
762-					

	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	SS-6-018(094)198	100	2	



	STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	SS-6-018(094)198	120	1	



Spec	Code	Description	Quantity	Location
762	1106	Pvmt Mk Painted 6IN Line		
		White Edge Line	180 LF	Walsh Co Rd 11 E
			180 LF	Walsh Co Rd 9 E
			180 LF	Walsh Co Rd 9 W
			180 LF	Walsh Co Rd 1B
			180 LF	Walsh Co Rd 1A
762	1124	Pvmt Mk Painted 24IN Line		
		White Stop Bar	12 LF	Walsh Co Rd 11 E
			12 LF	Walsh Co Rd 9 E
			12 LF	Walsh Co Rd 9 W
			12 LF	Walsh Co Rd 1B
			12 LF	Walsh Co Rd 1A

Pavement Marking Details

Milling and HMA  
N JCT 17 to CO LN



## NDDOT ABBREVIATIONS

D-101-1

?	This is a special text character used in the labeling of existing features. It indicates a feature that has an unknown characteristic, potentially based on: lack of description, location accuracy or purpose.	C Gdrl	cable guardrail	Culv	culvert	FOS	factor of safety
		Calc	calculate	C&G	curb & gutter	Fed	Federal
		CIP	cast iron pipe	CI	curb inlet	FP	feed point
		CB	catch basin	CR	curb ramp	Fn	fence
		CRS	cationic rapid setting	C	cut	Fn P	fence post
Abn	abandoned	C Gd	cattle guard	Dd Ld	dead load	FO	fiber optic
Abut	abutment	C To C	center to center	Defl	deflection	FD	field drive
Adj	adjusted	CL or C	centerline	Defm	deformed	F	fill
Aggr	aggregate	Ch	chain	DInt	delineate	FAA	fine aggregate angularity
Ahd	ahead	Chnlk	chain-link	Dlntr	delineator	FH	fire hydrant
ARV	air release valve	Ch Blk	channel block	Depr	depression	Fl	flange
Align	alignment	Ch Ch	channel change	Desc	description	Flrd	flared
Al	alley	Chk	check	Det	detail	FES	flared end section
Alt	alternate	Chsld	chiseled	DWP	detectable warning panel	F Bcn	flashing beacon
Alum	aluminum	Cir	circle	Dtr	detour	FA	flight auger sample
ADA	Americans with Disabilities Act	Cl	class	Dia or ø	diameter	FL	flow line
&	and	CInt	clean-out	Dir	direction	Ftg	footing
Appr	approach	Clr	clear	Dist	distance	FM	force main
Approx	approximate	Cl&gr	clearing & grubbing	DM	disturbed material	Fnd	found
ACP	asbestos cement pipe	Comb.	combination	DB	ditch block	Fdn	foundation
Asph	asphalt	Coml	commercial	DG	ditch grade	Frac	fractional
AC	asphalt cement	Compr	compression	Dbl	double	Frwy	freeway
Assmd	assumed	CADD	computer aided drafting & design	Dn	down	Fr	front
@	at	Conc	concrete	Dwg	drawing	FF	front face
Atten	attenuation	CECB	concrete erosion control blanket	Dr	drive	F Disp	fuel dispenser
ATR	automatic traffic recorder	Cond	conductor	Drwy	driveway	FFP	fuel filler pipes
Ave	Avenue	Const	construction	DI	drop inlet	FLS	fuel leak sensor
Avg	average	Cont	continuous	D	dry density	Furn	furnish/ed
ADT	average daily traffic	CSB	continuous split barrel sample				
		Contr	contraction				
		Contr	contractor				
Bk	back	CP	control point	Ea	each		
BF	back face	Coord	coordinate	Esmt	easement		
Balc	balcony	Cor	corner	E	East		
B Wire	barbed wire	Corr	corrected	EB	Eastbound		
Barr	barricade	CAES	corrugated aluminum end section	Elast	elastomeric		
Btry	battery	CAP	corrugated aluminum pipe	EL	electric locker		
BI	beehive inlet	CMES	corrugated metal end section	E Mtr	electric meter		
Beg	begin	CMP	corrugated metal pipe	EVSE	electric vehicle supply equipment		
BG	below grade	CPVCP	corrugated poly-vinyl chloride pipe	Elec	electric/al		
BM	bench mark	CSES	corrugated steel end section	EDM	electronic distance meter		
Bkwy	bikeway	CSFES	corrugated steel flared end section	Elev or El	elevation		
Bit	bituminous	CSP	corrugated steel pipe	Ellipt	elliptical		
Blk	block	CSTES	corrugated steel traversable end section	Emb	embankment		
BH	bore hole	Co	County	Emuls	emulsion/emulsified		
Bot	bottom	Crse	course	ES	end section		
Blvd	Boulevard	Ct	Court	Engr	engineer		
Bndry	boundary	Xarm	cross arm	ESS	environmental sensor station		
Brkwy	breakaway	Xbuck	cross buck	Eq	equal		
Br	bridge	Xsec	cross sections	Evgr	evergreen		
Bldg	building	Xing	crossing	Exc	excavation		
Bus.	business	Xrd	crossroad	Exst	existing		
BV	butterfly valve	Crn	crown	Exp	expansion		
Byp	bypass			Expy	Expressway		
				E	external of curve		
				Extru	extruded		

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
04-23-18 09-20-18 12-18-20 08-16-22 04-14-25	General Revisions General Revisions General Revisions General Revisions General Revisions

KIRK J. HOFF  
REGISTERED  
PROFESSIONAL  
PE-4683  
04/14/25  
ENGINEER  
NORTH DAKOTA

## NDDOT ABBREVIATIONS

D-101-2

Galv	galvanized	Ln	lane	Obsc	obscure(d)	Qty	quantity
Gar	garage	Lg	large	Ocpd	occupied	Qtr	quarter
Gs L	gas line	Lat	latitude	Ocpy	occupy		
G Reg	gas line regulator	Lt	left	O/s	offset		
GMV	gas main valve	Lens	lenses	OC	on center	Rad or R	radius
G Mtr	gas meter	Lvl	level	C	one dimensional consolidation	RR	railroad
GSV	gas service valve	Lvng	leveling	OC	organic content	Rlw	railway
GVP	gas vent pipe	Lht	light	Orig	original	Rsd	raised
GV	gate valve	LP	light pole	O To O	out to out	RC	rapid curing
Ga	gauge	Ltg	lighting	OD	outside diameter	Rec	record
Gov	government	Liq	liquid	OH	overhead	Rcy	recycle
Grd	graded/grade	LL	liquid limit			RAP	recycled asphalt pavement
Grnd	ground	Loc	location	PMT	pad mounted transformer	RPCC	recycled portland cement concrete
GWM	ground water monitor	Long.	longitude	Pg	pages	Ref	reference
Gdrl	guardrail	Lp	loop	Pntd	painted	R Mkr	reference marker
Gtr	gutter	LD	loop detector	Pr	pair	RM	reference monument
		Lum	luminaire	Pnl	panel	RP	reference point
				Pk	park	Refl	reflectorized
H Plg	H piling			PSD	passing sight distance	RCB	reinforced concrete box
Hdwl	headwall	Mb	mailbox	Pvmt	pavement	RCES	reinforced concrete end section
Ht	height	ML	main line	Ped	pedestal	RCFES	reinforced concrete flared end section
Hel	helical	MH	manhole	Ped	pedestrian	RCP	reinforced concrete pipe
HDPE	high density polyethylene	Mkd	marked	PPP	pedestrian pushbutton post	RCPS	reinforced concrete pipe sewer
HM	high mast	Mkr	marker	Pen.	penetration	RCTES	reinforced concrete traversable end section
HP	high pressure	Mkg	marking	Perf	perforated	Reinf	reinforcement
HPS	high pressure sodium	MA	mast arm	Per.	perimeter	Res	reservation
HTCG	high tension cable guardrail	Matl	material	Perm	permanent	Res	residence
Hwy	highway	Max	maximum	PL	pipeline	Ret	retaining
Hor	horizontal			PI	place	Rev	reverse
HBP	hot bituminous pavement	Meas	measure	P&P	plan & profile	Rt	right
HMA	hot mix asphalt	Mdn	median	PL	plastic limit	R/W	right of way
Hyd	hydrant	MD	median drain	PI or P	plate	Riv	river
Ph	hydrogen ion content	MC	medium curing	Pt	point	Rd	road
		MGS	Midwest Guardrail System	PE	polyethylene	Rdbo	road bed
		MM	mile marker	PVC	polyvinyl chloride	Rdw	roadway
Id	identification	MP	mile post	PCC	Portland Cement concrete	RWIS	roadway weather information system
Incl	inclinometer tube	Min	minimum	PP	power pole	Rk	rock
IMH	inlet manhole	Misc	miscellaneous	Preempt	preemption	Rt	route
ID	inside diameter	Mon	monument	Prefab	prefabricated		
Inst	instrument	Mnd	mound	Prfmd or Pref	preformed		
Intchg	interchange	Mtbl	mountable	Prep	preperation		
Intmdt	intermediate	Mtd	mounted	Press.	pressure		
Intscn	intersection	Mtg	mounting	PRV	pressure relief valve		
Inv	invert	Mk	muck	Prestr	prestressed		
IP	iron pipe			Pvt	private		
				PD	private drive		
Jt	joint			Prod.	production/produce		
Jct	junction	Neop	neoprene	Prog	programmed	07-01-14	
		Ntwk	network	Prop.	property	REVISIONS	
		N	North	Ppsd	proposed	DATE	CHANGE
		NE	Northeast	PB	pull box	08-03-15	General Revisions
		NW	Northwest			04-23-18	General Revisions
		NB	Northbound			12-18-20	General Revisions
		No. or #	number			08-16-22	General Revisions
						04-14-25	General Revisions

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
08-03-15	General Revisions
04-23-18	General Revisions
12-18-20	General Revisions
08-16-22	General Revisions
04-14-25	General Revisions



## NDDOT ABBREVIATIONS

D-101-3

Salv	salvage(d)	Tel	telephone
San	sanitary sewer line	Tel B	Telephone Booth
Sec	section	Tel P	telephone pole
SL	section line	Tv	television
Sep	separation	Temp	temperature
Seq	sequence	Temp	temporary
Serv	service	TBM	temporary bench mark
Sht	sheet	T	thinwall tube sample
Shtng	sheeting	Ts	topsoil
Shldr	shoulder	Traf	traffic
Sw or Sdwk	sidewalk	TSCB	traffic signal control box
SD	sight distance	Tr	trail
SN	sign number	Transf	transformer
Sig	signal	Trans	transition
Sgl	single	TT	transmission tower
SRCP	slotted reinforced concrete pipe	TES	traversable end section
SC	slow curing	Trans	transverse
SS	slow setting	Trtd	treated
Sm	small	Trmt	treatment
S	South	Qc	triaxial compression
SE	Southeast	TERO	tribal employment rights ordinance
SW	Southwest	Tpl	triple
SB	Southbound	Typ	typical
Sp	spaces		
Spcl	special		
SA	special assembly	Qu	unconfined compressive strength
SP	special provisions	Ugrnd	underground
G	specific gravity	Util	utility
Spk	spike		
SB	split barrel sample		
SH	sprinkler head	VG	valley gutter
SV	sprinkler valve	Vap	vapor
Sq	square	Vert	vertical
Stk	stake	VCP	vitrified clay pipe
Std	standard	Vol	volume
N	standard penetration test	VSFS	vehicle speed feedback sign
Std Specs	standard specifications		
Stm L	steam line	Wkwy	walkway
SEC	steel encased concrete	W	water content
SMA	stone matrix asphalt	WGV	water gate valve
SSD	stopping sight distance	WL	water line
SD	storm drain	WM	water main
St	street	WMV	water main valve
SPP	structural plate pipe	W Mtr	water meter
SPPA	structural plate pipe arch	WSV	water service valve
Str	structure	WW	water well
Subd	subdivision	Wrng	wearing
Sub	subgrade	WIM	weigh in motion
Sub Prep	subgrade preperation	W	west
Ss	subsoil	WB	westbound
SS	supplement specification	Wrng	wiring
Supp	supplemental	W/	with
Surf	surfacing	W/o	without
Surv	survey		
Sym	symmetrical		

NORTH DAKOTA	
DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
08-03-15 04-23-18 12-18-20 08-16-22 04-14-25	General Revisions General Revisions General Revisions General Revisions General Revisions



KIRK J. HOFF  
REGISTERED  
PROFESSIONAL  
PE-4683  
04/14/25  
ENGINEER  
NORTH DAKOTA

## NDDOT ABBREVIATIONS

D-101-4

## MEASUREMENTS

ac	acres
A	ampere
Bd Ft	board feet
Cd	candela
cm	centimeter
C	coulomb
CF	cubic feet
m3	cubic meter
m3/s	cubic meters per second
CY	cubic yard
CY/mi	cubic yards per mile
D or Deg	degree
F	Fahrenheit
F	farad
ft	feet/foot
Gal	gallon
G	giga
Ha	hectare
H	henry
Hz	hertz
hr	hour(s)
in.	inch
J	joule
K	kelvin
kN	kilo newton
kPa	kilo pascal
kg	kilogram
kg/m3	kilogram per cubic meter
km	kilometer
K	Kip(s)
LF	linear foot
L	litre
Lm	lumen
L sum	lump sum
Lx	lux
M Hr	man hour
M	mega
m	meter
m/s	meters per second
mi	mile
mL	milliliter
mm	millimeter
mm/hr	millimeters per hour
n	nano
N	newton
Pa	pascal
lb	pounds
sec	seconds
S	siemens
SF	square feet
km2	square kilometer
m2	square meter
SY	square yard
Sta Yd	station yards
SI	Systems International

T	tesla
T/mi	tons per mile
V	volt
W	watt
Wb	weber


## SURVEY DESCRIPTIONS

Az	azimuth
Bs	backsight
Brg	bearing
BP Cap	blue plastic cap
BS	both sides
BC	brass cap
CC	closing corner
CS	curve to spiral
Eq	equation
E	external of curve
FS	far side
FB	field book
Fs	foresight
Geod	geodetic
GIS	Geographical Information System
GPS	Global Positioning System
HI	height of instrument
IM	iron monument
I Pn	iron pin
LS	Land Surveyor (licensed)
LSIT	Land Surveyor In Training
L	length of curve
LC	long chord
LB	level book
MC	meander corner
Mer	meridian
M	mid ordinate of curve
NGS	National Geodetic Survey
NS	near side
Obsn	observation
Off Loc	office location
OP Cap	orange plastic cap
PK	Parker-Kalon nail
P Cap	plastic cap
PP Cap	pink plastic cap
PCC	point of compound curve
PC	point of curve
PI	point of intersection
PRC	point of reverse curvature
PT	point of tangent
POC	point on curve
POT	point on tangent
RTP	random traverse point
Rge	range
RP Cap	red plastic cap
SC	spiral to curve
SC	standard corner
ST	spiral to tangent
Sta	station
SE	superelevation
Tan	tangent
T	tangent (semi)
TS	tangent to spiral
Twp	township
TB	transit book
TP	traverse point
TP	turning point
USC&G	US Coast & Geodetic Survey
USGS	US Geologic Survey
VC	vertical curve
WC	witness corner
WGS	World Geodetic System
YP Cap	yellow plastic cap
Z	zenith

## SOIL TYPES

Cl	clay
Cl F	clay fill
Cl Hvy	clay heavy
Cl Lm	clay loam
Co S	coal slack
C Gr	coarse gravel
CS	coarse sand
FS	fine sand
Gr	gravel
Lig Co	lignite coal
Lig Sl	lignite slack
Lm	loam
Rk	rock
Sd	sand
Sdy Cl	sandy clay
Sdy Cl Lm	sandy clay loam
Sdy Fl	sandy fill
Sdy Lm	sandy loam
Sc	scoria
Sh	shale
Si Cl	silt clay
Si Cl Lm	silty clay loam
Si Lm	silty loam

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
12-18-20 4-14-25	Sheet Added - Continued from D-101-3 General Revisions



## NDDOT UTILITY COMPANY AND ORGANIZATION ABBREVIATIONS

D-101-10

702COM	702 Communications	GTR RAMSEY WD	Greater Ramsey Water District	RED RIV COMM	Red River Communications
ACCENT	Accent Communications	GT PLNS NAT GAS	Great Plains Natural Gas Company	RESVTN TEL	Reservation Telephone
AGASSIZ WU	Agassiz Water Users District	HALS TEL	Halstad Telephone Company	ROBRTS TEL	Roberts Company Telephone
AGC	Associated General Contractors of America	IDEA1	Idea1	R-RIDER ELEC	Roughrider Electric Cooperative
ALL PL	Alliance Pipeline	INT-COMM TEL	Inter-Community Telephone Company	RRVW	Red River Valley & Western Railroad
ALL SEAS WU	All Seasons Water Users District	KANEPL	Kaneb Pipeline Company	S CENT REG WD	South Central Regional Water District
AMOCO PI	Amoco Pipeline Company	KEM ELEC	Kem Electric Cooperative Incorporated	SE WU	Southeast Water Users Incorporated
AMRDA HESS	Amerada Hess Corporation	KOCH GATH SYS	Koch Gathering Systems Incorporated	SCOTT CABLE	Scott Cable Television Dickinson
AT&T	AT&T Corporation	LKHD PL	Lakehead Pipeline Company	SHERDN ELEC	Sheridan Electric Cooperative
B PAW	Bear Paw Energy Incorporated	LWR YELL R ELEC	Lower Yellowstone Rural Electric	SHEYEN VLY ELEC	Sheyenne Valley Electric Cooperative
BAKER ELEC	Baker Electric	LUMEN	Lumen Technologies Incorporated	SKYTECH	Skyland Technologies Incorporated
BASIN ELEC	Basin Electric Cooperative Incorporated	MCKNZ CON	McKenzie Consolidated Telcom	SLOPE ELEC	Slope Electric Cooperative Incorporated
BEK TEL	Bek Communications Cooperative	MCKNZ ELEC	McKenzie Electric Cooperative	SOURIS RIV TELCOM	Souris River Telecommunications
BELLE PL	Belle Fourche Pipeline Company	MCKNZ WRD	McKenzie County Water Resource District	ST WAT COMM	State Water Commission
BLM	Bureau of Land Management	MCLEOD	McLeod USA	STATE LN WATER	State Line Water Cooperative
BNSF	Burlington Northern Santa Fe Railway	MCLN ELEC	McLean Electric Cooperative	STER ENG	Sterling Energy
BOEING	Boeing	MCLN-SHRDN R WAT	McLean-Sheridan Rural Water District	STUT RWD	Stutsman Rural Water District
BRNS RWD	Barnes Rural Water District	MDU	Montana-dakota Utilities	SW PL PRJ	Southwest Pipeline Project
BURK-DIV ELEC	Burke-Divide Electric Cooperative	MIDCO	MidContinent Communications	SWWA	Southwest Water Authority
BURL WRD	Burleigh County Water Resource District	MIDSTATE TEL	Midstate Telephone Company	SUNOCO	Sunoco LP
CABLE ONE	Cable One	MINOT CABLE	Minot Cable Television	T M C	Turtle Mountain Communications
CABLE SERV	Cable Services	MINOT TEL	Minot Telephone Company	TCI	TCI of North Dakota
CAP ELEC	Capital Electric Cooperative Incorporated	MISS VALL COMM	Missouri Valley Communications Incorporated	TESORO HGH PLNS PL	Tesoro High Plains Pipeline
CASS CO ELEC	Cass County Electric Cooperative	MISS W W S	Missouri West Water System	TRI-CNTY WU	Tri-County Water Users Incorporated
CASS RWU	Cass Rural Water Users District	MNKOTA PWR	Minnkota Power	TRL CO WRD	Trall County Water Resource District
CAV ELEC	Cavalier Rural Electric Cooperative	MOR-GRAN-SOU ELEC	Mor-gran-sou Electric Cooperative	UNTD TEL	United Telephone
CBLCOM	Cablecom Of Fargo	MOUNT-WILLIELEC	Mountrail-williams Electric Cooperative	UPPR SOUR WD	Upper Souris Water District
CENEX PL	Cenex Pipeline	MLGC	Moore & Liberty - Griggs County	US SPRINT	U.S. Sprint
CENT PL WATER DIST	Central Pipe Line Water District	MUNICIPAL	City Water And Sewer	USAF MSL CABLE	U.S.A.F. Missile Cable
CENT PWR ELEC	Central Power Electric Cooperative	MUNICIPAL	City Of '.....'	USFWS	US Fish and Wildlife Service
CENTURYLINK	CenturyLink	N CENT ELEC	North Central Electric Cooperative	USW COMM	U.S. West Communications
COE	Corps of Engineers	N PRAIR REG WD	North Prairie Regional Water District	VRNDRY ELEC	Verendrye Electric Cooperative
CONS COMM	Consolidated Communications	ND PKS & REC	North Dakota Parks And Recreation	W RIV TEL	West River Telephone Incorporated
CONS TELCOM	Consolidated Telcom	ND TEL	North Dakota Telephone Company	WAPA	Western Area Power Administration
CONT RES	Continental Resource Inc	NDDDOT	North Dakota Department of Transportation	WAWSA	Western Area Water Supply Authority
CPR	Canadian Pacific Railway	NE REG WD	Northeast Regional Water District	WEB	W. E. B. Water Development Association
D O E	Department Of Energy	NDSU SOIL SCI DEPT	NDSU Soil Science Department	WILLI WRD	Williams County Water Resource District
DAK CARR	Dakota Carrier Network	NEMONT TEL	Nemont Telephone	WILSTN BAS PL	Williston Basin Interstate Pipeline Company
DAK CENT TEL	Dakota Central Telephone	NODAK R ELEC	Nodak Rural Electric Cooperative	WLSH RWD	Walsh Water Rural Water District
DAK RWD	Dakota Rural Water District	NOON FRMS TEL	Noonan Farmers Telephone Company	WOLVRTN TEL	Wolverton Telephone
DGC	Dakota Gasification Company	NPR	Northern Plains Railroad	XLENER	Xcel Energy
DICKEY R NET	Dickey Rural Networks	NSP	Northern States Power	YSVR	Yellowstone Valley Railroad
DICKEY WRD	Dickey County Water Resource District	NTHN BRDR PL	Northern Border Pipeline		
DICKEY TEL	Dickey Telephone	NTHN PLNS ELEC	Northern Plains Electric Cooperative Incorporated		
DNRR	Dakota Northern Railroad	NTHWSTRN REF	Northwestern Refinery Company		
DOME PL	Dome Pipeline Company	NW COMM	Northwest Communication Cooperation		
DVELEC	Dakota Valley Electric Cooperative	NWRWD	Northwest Rural Water District		
DVMW	Dakota, Missouri Valley & Western	ONEOK	Oneok gas		
E CENT REG WD	East Central Water District	OSHA	Occupational Safety and Health Administration		
ENBRDG	Enbridge Pipelines Incorporated	OTTR TL PWR	Otter Tail Power Company		
ENVENTIS	Enventis Telephone	PAAP	Plains All American Pipeline		
EQUINOR	Equinor Pipeline	P L E M	Prairielands Energy Marketing		
FALK MNG	Falkirk Mining Company	POLAR COM	Polar Communications		
FHWA	Federal Highway Administration	PVT ELEC	Private Electric		
G FKS-TRL WD	Grand Forks-trail Water District	QWEST	Qwest Communications		
GETTY TRD & TRAN	Getty Trading & Transportation	R&T REG WD	R & T Water District		
GLDN W ELEC	Golden West Electric Cooperative				

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
04-23-18 09-20-18 12-18-20 08-16-22 04-14-25	General Revisions General Revisions General Revisions General Revisions General Revisions



## LINE STYLES

D-101-20

## Existing Topography

Void — Void — Void — v Existing Ground Void

—+—+— Existing Cemetery Boundary

----- Existing Box Culvert Bridge

----- Existing Concrete Surface

----- Existing Drainage Structure

— Existing Gravel Surface

— Existing Riprap

— Existing Dirt Surface

— Existing Asphalt Surface

— Existing Tie Point Line

— Existing Railroad Centerline

----- Existing Guardrail Cable

— Existing Guardrail Metal

— Existing Edge of Water

- - - -x- - - -x- - Existing Fence

| | | | | Existing Railroad

---- Existing Field Line

— Existing Curb

----- Existing Valley Gutter

----- Existing Driveway Gutter

----- Existing Curb and Gutter

----- Existing Mountable Curb and Gutter

----- Existing 3-Cable w Posts

— Site Boundary

..... Existing Berm, Dike, Pit, or Earth Dam

..... Existing Ditch Block

— Existing Tree Boundary

..... Existing Brush or Shrub Boundary

..... Existing Retaining Wall

— Existing Planter or Wall

— Existing W-Beam Guardrail with Posts

● Existing Railroad Switch

— Existing Wet Area-Vegetation Break

— Existing High Tension Cable Guardrail

— Existing High Tension Cable Guardrail with Posts

## Proposed Topography

— 3-Cable w Posts

— Flow

— Existing Flow

— Existing Curb

— REMOVE REMOVE Remove Line

— Wall

— Retaining Wall (Plan View)

— W-Beam w Posts

— High Tension Cable Guardrail with Posts

## Existing Utilities

— E Existing Electrical

— FO Existing Fiber Optic Line

— FO Existing TV Fiber Optic

— G Existing Gas Pipe

— OH Existing Overhead Utility Line

— P Existing Power

— PL Existing Fuel Pipeline

— PL Existing Undefined Above Ground Pipe Line

— SAN Existing Sanitary Sewer

— SAN FM Existing Sanitary Force Main

— SD Existing Storm Drain

— SD FM Existing Storm Drain Force Main

— Existing Culvert

— T Existing Telephone Line

— TV Existing TV Line

— W Existing Water or Steam Line

— Existing Under Drain

— Existing Slotted Drain

— Existing Conduit

— Existing Conductor

— Existing Down Guy Wire Down Guy

— Existing Underground Vault or Lift Station

## Proposed Utilities

— 24 Inch Pipe

— Reinforced Concrete Pipe

— Under Drain

— Edge Drain

## Traffic Utilities

— Conductor

— Fiber Optic

— Existing Loop Detector

— Existing Double Micro Loop Detector

— Micro Loop Detector Double

— Existing Micro Loop Detector

— Micro Loop Detector

— Signal Head with Mast Arm

— Existing Signal Head with Mast Arm

## Sign Structures

— Existing Overhead Sign Structure

— Existing Overhead Sign Structure Cantilever

— Overhead Sign Structure Cantilever

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
09-23-16 12-18-20	Added and Revised Items, Organized by Functional Groups General Revisions



## LINE STYLES

D-101-21

## Right Of Way

-----	Easement
-----	Existing Easement
-----	Right of Way
-----	Existing Right of Way
-----	Existing Right of Way Railroad
-----	Existing Right of Way Not State Owned
-----	Existing Government Lot Line
.....	Existing Adjacent Block Lines

## Cross Sections and Typicals

-----	Existing Ground
-----	Existing Topsoil (Cross Section View)
void — void — void — v	Existing Ground Void (Not Surveyed)
-----	Existing Concrete
-----	Existing Aggregate (Cross Section View)
-----	Existing Curb and Gutter (Cross Section View)
-----	Existing Asphalt (Cross Section View)
-----	Existing Reinforcement Rebar

## Striping

-----	Centerline Pavement Marking
=====	Barrier with Centerline Pavement Marking
=====	Barrier Pavement Marking
- - - - -	Stripe 4 IN Dotted Extension White
- - - - -	Stripe 8 IN Dotted Extension White
- - - - -	Stripe 8 IN Lane Drop

## Erosion Control

.....	Limits of Const Transition Line
.....	Bale Check
.....	Rock Check
-----	Floating Silt Curtain
-----	Silt Fence
.....	Excavation Limits
-----	Fiber Rolls

## Geotechnical

----- D ----- D -----	Geotextile Fabric Type D
----- Geo ----- Geo -----	Geogrid
----- R ----- R -----	Geotextile Fabric Type R
----- R ----- R -----	Geotextile Fabric Type R1
----- RR ----- RR -----	Geotextile Fabric Type RR

## Pavement Joints

*****	Doweled Joint
+++++	Tie Bar 30 Inch 4 Foot Center to Center
+++++	Tie Bar 18 Inch 3 Foot Center to Center
+++++	Tie Bar at Random Spacing

## Environmental

-----	Wetland Mitigation
-----	Existing Wetland Easement USFWS
-----	Existing Wetland Jurisdictional
-----	Existing Wetland
-----	Tree Row

## Boundary Control

Existing City Corporate Limits or Reservation Boundary

Existing State or International Line

Existing Township

Existing County

Existing Section Line

Existing Quarter Section Line

Existing Sixteenth Section Line

Existing Centerline

Tangent Line

## Contours

Depression Contours

Supplemental Contour

## Profile

Subgrade, Subcut or Ditch Grade

Topsoil Profile

Small Hidden Object

Large Hidden Object

Phantom Object

Existing Conditions Object

Centerline Main

Centerline Secondary

Excavation Limits

Proposed Ground

Sheet Piling

NORTH DAKOTA	
DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
09-23-16 12-18-20	Added and Revised Items, Organized by Functional Groups General Revisions



## SYMBOLS

D-101-30

	North Arrow (Half Scale)
	Alignment Data Point
	Alignment Monument
	Spot Elevation
	Existing Miscellaneous Spot
	Existing Access Control Arrow
	Existing Benchmark
	Reset USGS Marker
	Iron Monument Found
	Iron Pin R/W Monument
	Property Corner
	Iron Pin Reference Monument
	Right of Way Marker (Exst, Ppsd, Reset)
	Existing Federal Reference Corner
	Existing Section Corner (Full, Quarter, Sixteenth, Meander)
	Existing Witness Corner
	Existing Control Point (CP, GPS-RTK, TRI)
	Existing Traverse PI Aerial Panel
	Existing Reference Marker Point NGS
	Existing EFB Misc
	Existing Bush or Shrub
	Existing Large Evergreen Tree
	Existing Small Evergreen Tree
	Existing Large Tree
	Existing Small Tree
	Existing Tree Trunk
	Cairn or Stone Circle
	Existing Artifact
	Existing Satellite Dish
	Existing Weather Station
	Existing Windmill or Tower
	Reinforced Pavement
	Continuous Split Barrel Sample
	Flight Auger Sample
	Split Barrel Sample
	Thinwall Tube Sample
	Standard Penetration Test
	Inclinometer Tube
	Excavation Unit
	Existing Ground Water Well Bore Hole

NORTH DAKOTA	
DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
12-18-20	General Revisions

KIRK J. HOFF  
REGISTERED  
PROFESSIONAL  
PE-4683  
Kirk J Hoff  
NORTH DAKOTA  
ENGINEER  
12 18 2020

## SYMBOLS

D-101-31

■	Flexible Delineator	■	Highway Sign (Exst, Ppsd)
□ □	Flexible Delineator Type A (Exst, Ppsd)	□ □	Mile Post Type A (Exst-Ppsd-Reset)
□ □	Flexible Delineator Type B (Exst, Ppsd)	□ □	Mile Post Type B (Exst, Ppsd)
□ □	Flexible Delineator Type C (Exst, Ppsd)	□ □	Mile Post Type C (Exst, Ppsd)
○ ○	Flexible Delineator Type D (Exst, Ppsd)	○ ○	Object Marker Type I (Exst, Ppsd)
○ ○	Flexible Delineator Type E (Exst, Ppsd)	○ ○	Object Marker Type II (Exst, Ppsd)
└ └ └ └	Delineator Type A (Exst, Ppsd, Diamond Grade-Reset)	└ └	Object Marker Type III (Exst, Ppsd)
└ └ └ └	Delineator Type B (Exst, Ppsd, Diamond Grade-Reset)	○	Existing Reference Marker
└ └ └ └	Delineator Type C (Exst, Ppsd, Diamond Grade)	○—○	Road Closure Gate 18 Ft (Exst, Ppsd)
○ ○ ○	Delineator Type D (Exst, Ppsd, Diamond Grade)	○—○	Road Closure Gate 28 Ft (Exst, Ppsd)
○ ○ ○	Delineator Type E (Exst, Ppsd, Diamond Grade)	○—○	Road Closure Gate 40 Ft (Exst, Ppsd)
└ └ └	Barricade (Type I, Type II, Type III)	□	Existing Railroad Battery Box
○ ○ ○	Arrow Panel (Caution Mode, Double Direction, Left Directional, Right Directional, Sequencing, Truck Mounted)	×	Existing RR Profile Spot
△	Attenuation Device	×	Existing Railroad Crossbuck
☒	Truck Mounted Attenuator	×	Existing Railroad Frog
●	Delineator Drums	—	Existing Mailbox (Private, Federal)
□	Flagger		
←	Tubular Marker		
▲	Traffic Cone		
---	Back to Back Vertical Panel Sign		

NORTH DAKOTA	
DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
12-18-20	General Revisions




KIRK J. HOFF  
REGISTERED  
PROFESSIONAL  
PE-4683  
NORTH DAKOTA  
12 18 2020

## SYMBOLS

D-101-32

	Existing Luminaire			High Mast Light Standard 3 Luminaire (Exst, Ppsd)			Existing Traffic Signal Standard
	Luminaire LED			High Mast Light Standard 4 Luminaire (Exst, Ppsd)			Pull Box (Exst-Ppsd-Undefined)
	Existing Light Standard Luminaire			High Mast Light Standard 5 Luminaire (Exst, Ppsd)			Intelligent Transportation Pull Box (Exst, Ppsd)
	Relocate Light Standard			High Mast Light Standard 6 Luminaire (Exst, Ppsd)			Transformer (Exst, Ppsd)
	Light Standard Light LED Luminaire			High Mast Light Standard 7 Luminaire (Exst, Ppsd)			Power Pole (Exst-Ppsd-with Transformer)
	Light Standard 35 Watt High Pressure Sodium Vapor Luminaire			High Mast Light Standard 8 Luminaire (Exst, Ppsd)			Wood Pole (Exst, Ppsd)
	Light Standard 50 Watt High Pressure Sodium Vapor Luminaire			High Mast Light Standard 9 Luminaire (Exst, Ppsd)			Pedestrian Push Button Post (Exst, Ppsd)
	Light Standard 70 Watt High Pressure Sodium Vapor Luminaire			High Mast Light Standard 10 Luminaire (Exst, Ppsd)			Existing Pole
	Light Standard 100 Watt High Pressure Sodium Vapor Luminaire			Overhead Sign Structure Load Center (Exst, Ppsd)			Existing Telephone Pole
	Light Standard 150 Watt High Pressure Sodium Vapor Luminaire			Traffic Signal Controller (Exst, Ppsd)			Existing Post
	Light Standard 200 Watt High Pressure Sodium Vapor Luminaire			Pad Mounted Traffic Signal Controller (Exst, Ppsd)			Connection Conductor (Ground, Neutral, Phase 1, Phase 2)
	Light Standard 250 Watt High Pressure Sodium Vapor Luminaire			Flashing Beacon (Exst, Ppsd)			
	Light Standard 310 Watt High Pressure Sodium Vapor Luminaire			Concrete Foundation (Exst, Ppsd)			
	Light Standard 400 Watt High Pressure Sodium Vapor Luminaire			Pipe Mounted Flasher (Exst, Ppsd)			
	Light Standard 700 Watt High Pressure Sodium Vapor Luminaire			Pad Mounted Feed Point (Exst, Ppsd)			
	Light Standard 1000 Watt High Pressure Sodium Vapor Luminaire			Pipe Mounted Feed Point with Pad (Exst, Ppsd)			
	Emergency Vehicle Detector			Pole Mounted Feed Point (Exst, Ppsd)			
	Video Detection Camera			Junction Box (Exst, Ppsd)			
				Existing Pedestrian Head with Number			
				Existing Signal Head			
				Pole Mounted Head			
				Existing Lighting Standard Pole			



## SYMBOLS

D-101-33

○ ○ ○	Existing Manhole (Electrical, Gas, Telephone)	Cap or Stub Exst Gas, Exst Sanitary, Exst Storm Drain, Ppsd Storm Drain, Exst Water
○ ○ ○	Water Manhole (Exst, Exst with Valve)	□ □ □ □ □
○ ○ ○	Sanitary Sewer Manhole (Exst, Ppsd, Exst with Valve)	Existing Pedestal Electrical, Telephone, Fiber Optic Telephone, TV, Fiber Optic TV, Undefined
○ ○ ○	Sanitary Force Main Manhole (Exst, Ppsd, Exst with Valve)	□ □ □ □ □ □
○ ○ ○	Storm Drain Manhole (Exst, Ppsd, Exst with Inlet, Ppsd with Inlet)	Existing Pipe Vent Gas, Fuel, Sanitary, Storm Drain, Water, Undefined
○ ○ ○	Force Main Storm Drain Manhole (Exst, Exst with Valve)	□ □ □ □ □ □
○ ○ ○	Manhole (Ppsd, Ppsd 48 Inch, Exst Undefined)	Valve Exst Gas, Exst Water, Ppsd Water, Exst Undefined
○ ○ ○	Existing Water Appurtenance	○ ○ ○ ○
○ ○ ○	Sprinkler Head (Exst, Ppsd)	Pump Sanitary, Storm Drain, Exst Water
○ ○ ○	Fire Hydrant (Exst, Ppsd)	○ ○ ○
○ ○ ○	Cleanout (Exst Sanitary, Underdrain)	Corrugated Metal End Section (18, 24, 30, 36, 42, 48, 54, 60 Inch)
○ ○ ○	Existing Catch Basin Inlet (Round, Square)	□ □ □ □ □ □ □ □
○ ○ ○	Existing Curb Inlet (Round, Square)	Reinforced Concrete End Section (18, 24, 30, 36, 42, 48, 54, 60 Inch)
○ ○ ○	Existing Slotted Reinforced Concrete Pipe	□ □ □ □ □ □ □
○ ○ ○	Catch Basin (Riser 30 Inch, Beehive, Type A)	
○ ○ ○	Inlet Mountable Curb (Type A, Type B)	— Existing Utility Marker
○ ○ ○	Inlet Saddle Base (Type 1, Type 2)	□ Existing Meter
○ ○ ○	Inlet Special (Catch Basin, Type 1, Type A)	□ Existing Fuel Dispensers
○ ○ ○	Inlet (Tee, Type 1, Type 2, Type 2 Double)	□ Existing Fuel Filler Pipes
○ ○ ○	Median Drain	○ Existing Fuel Leak Sensors
○ ○ ○	Headwall (Exst, Ppsd, Ppsd Single with Vegetation Barrier, Ppsd Double with Vegetation Barrier)	



NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
12-18-20	General Revisions Sheet added - Continued from D-101-32



## TRAFFIC CONTROL FOR CORING OF HOT BITUMINOUS PAVEMENT



D-704-2

Two Lane, Two Way Roadways



Typical Protection Vehicle

Multilane Roadways




Typical Protection Vehicle

## Notes:

1. Display a 360 degree rotating, flashing, oscillating or strobe light on the working vehicle.
2. Display a 360 degree rotating, flashing, oscillating or strobe light on the shadow vehicle. Operate a sequencing arrow panel Type C in chevron mode on the shadow vehicle for Multilane Roadway.
3. Use these layouts during daylight hours and in areas of good visibility only.
4. Use flagger to protect the work area and warn oncoming traffic for two lane, two way roadway.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-25-12	
REVISIONS	
DATE	CHANGE
9-27-17 10-03-19 8-01-24	Updated to active voice New Design Engr PE Stamp Electronic Stamp/Signature



## BREAKAWAY SYSTEMS FOR CONSTRUCTION ZONE SIGNS

D-704-7

**Perforated Tube**

Notes:

1. Torque slip base bolts as specified by manufacturer.
2. Use anchor with 43.9 KSI yield strength and 59.3 KSI tensile strength.
3. Provide 4" vertical clearance for anchor or breakaway base. Measure the 4"x60" measurement above and below post location and back and ahead of post.
4. In concrete sidewalk, use same anchor without wings.
5. Provide more than 7' between the first and fourth posts of a four post sign.

**Top Post Receiver**  
Plate - ASTM A572 grade 50  
Angle Receiver -  $2\frac{1}{2}'' \times 2\frac{1}{2}'' \times 3\frac{3}{8}''$  ASTM A36 structural angle

**Telescoping Perforated Tube**

Number of Posts	Post Size in.	Wall Thickness Gauge	Sleeve Size in.	Wall Thickness Gauge	Anchor Size without Slip Base in.
1	2	12			No $2\frac{1}{4}$
1	$2\frac{1}{4}$	12			No $2\frac{1}{2}$
1	$2\frac{1}{2}$	12			(A) 3
1	$2\frac{1}{2}$	10			Yes
1	$2\frac{1}{4}$	12	2	12	Yes
1	$2\frac{1}{2}$	12	$2\frac{1}{4}$	12	Yes
2	2	12			No $2\frac{1}{4}$
2	$2\frac{1}{4}$	12			No $2\frac{1}{2}$
2	$2\frac{1}{2}$	12			Yes
2	$2\frac{1}{4}$	10	2	12	Yes
2	$2\frac{1}{2}$	12	$2\frac{1}{4}$	12	Yes
3 & 4	$2\frac{1}{2}$	12			Yes
3 & 4	$2\frac{1}{2}$	10			Yes
3 & 4	$2\frac{1}{2}$	12	$2\frac{1}{4}$	12	Yes
3 & 4	$2\frac{1}{4}$	12	2	12	Yes
3 & 4	$2\frac{1}{2}$	10	$2\frac{1}{4}$	10	Yes

**Properties of Telescoping Perforated Tube**

Tube Size in.	Wall Thickness in.	U.S. Standard Gauge	Weight per Foot lbs.	Moment of Inertia in. <sup>4</sup>	Cross Sec. Area in. <sup>2</sup>	Section Modulus in. <sup>3</sup>
$1\frac{1}{2} \times 1\frac{1}{2}$	0.105	12	1.702	0.129	0.380	0.172
2 x 2	0.105	12	2.416	0.372	0.590	0.372
$2\frac{1}{4} \times 2\frac{1}{4}$	0.105	12	2.773	0.561	0.695	0.499
$2\frac{3}{16} \times 2\frac{3}{16}$	0.135	10	3.432	0.605	0.841	0.590
$2\frac{1}{2} \times 2\frac{1}{2}$	0.105	12	3.141	0.804	0.803	0.643
$2\frac{1}{2} \times 2\frac{1}{2}$	0.135	10	4.006	0.979	1.010	0.785

**Top Post Receiver Data Table**

Square Post Sizes (B)	A	B	C	D	E	F
$2\frac{3}{16} \times 10$ ga.	$1\frac{1}{64}$	$2\frac{1}{2}$	$3\frac{1}{32}$	$2\frac{5}{32}$	$1\frac{33}{64}$	$1\frac{7}{8}$
$2\frac{1}{2} \times 10$ ga.	$1\frac{1}{32}$	$2\frac{1}{2}$	$3\frac{5}{16}$	$\frac{5}{8}$	$1\frac{21}{32}$	$\frac{1}{4}$

(A) Use breakaway base when support is placed in weak soils. Engineer determines if soils are weak.

(B) For additional wind load, insert the  $2\frac{3}{16} \times 10$  ga. into  $2\frac{1}{2} \times 10$  ga.

**Anchor Unit and Post Assembly**

**Multi-Directional Slip Base Anchor Unit and Post Sleeve Assembly**

**Bolt Retainer for Base Connection**  
Bolt Retainer-  $\frac{1}{32}$ " Reprocessed Teflon


**NORTH DAKOTA DEPARTMENT OF TRANSPORTATION**  
2-28-14  
REVISIONS  
DATE CHANGE  
9-27-17 Updated to active voice  
10-03-19 New Design Engr PE Stamp  
8-01-24 Electronic Stamp/Signature

**KIRK J. HOFF**  
REGISTERED  
PROFESSIONAL  
PE-4683  
ENGINEER  
NORTH DAKOTA  
08/01/24


## BREAKAWAY SYSTEMS FOR CONSTRUCTION ZONE SIGNS

D-704-8

## U-Channel Post



Detail A




Front View

Side View

Back View

Breakaway U-Channel Detail  
Alternate A


Install a maximum of 2 posts within 7'.




Retainer Strap Detail

## Alternate A Steps of Installation:

- a) Drive anchor unit to within 12" of ground level.  
b) Establish proper assembly by lining up bottom hole of retainer strap with 6th hole from the top of the anchor unit.  
c) Assemble strap to back of anchor unit using  $\frac{5}{16}$ "x2" bolt, lock washer and nut.  
d) Rotate strap 90° to left.
- a) Drive anchor unit to 4" above ground.  
b) Rotate strap to vertical position.
- a) Place  $\frac{5}{16}$ "x2" bolt, lock washer and nut in bottom of sign post to facilitate alignment of sign post with proper hole in anchor unit.  
b) Alternately tighten two connector bolts.
- Complete assembly by tightening  $\frac{5}{16}$ "x2" bolt (this fastens sign post to retainer strap).
- Properly nest base post, strap, and sign post. Proper nesting occurs when all flat surfaces of the base post, strap, and sign post at the bolts have full contact across the entire width.


Breakaway U-Channel Splice Detail  
Alternate B  
(2.5 and 3 lb/ft)

Install a maximum of 3 posts within 7'.

Breakaway U-Channel Splice Detail  
Alternate C  
(2.5 and 3 lb/ft)

Install a maximum of 3 posts within 7'.


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
2-28-14	
REVISIONS	
DATE	CHANGE
9-27-17 10-03-19 8-01-24	Updated to active voice New Design Engr PE Stamp Electronic Stamp/Signature




08/01/24

CONSTRUCTION SIGN DETAILS  
TERMINAL AND GUIDE SIGNS


D-704-9



G20-1-60

Legend: black (non-refl)  
Background: orange


G20-50a-72

Legend: black (non-refl)  
Background: orange


G20-1b-60

Legend: black (non-refl)  
Background: orange

G20-52a-72

Legend: black (non-refl)  
Background: orange


G20-2-48

Legend: black (non-refl)  
Background: orange

G20-55-96

Legend: black (non-refl)  
Background: orange


G20-4b-36

Legend: black (non-refl)  
Background: orange


E5-1(L or R)-48

Legend: white  
Background: green (orange optional)


See ARROW DETAILS



M4-8-36


Legend: black (non-refl)  
Background: orange

E5-1-48





G20-50a-72

G20-52a-72




M4-9(L or R)-30

Right or Left

M4-9(L or R)-30  
Advanced Right or Left

M4-9-30

Straight

M4-9(L or R)-30 &  
M4-9-30Legend: black (non-refl)  
Background: orange

See ARROW DETAILS

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-13-13	
REVISIONS	
DATE	CHANGE
08-17-17 10-03-19 08-01-24 06-30-25	Added sign & background color New Design Engineer PE Stamp Electronic Stamp/Signature Legislative Changes

KIRK J. HOFF  
REGISTERED  
PROFESSIONAL  
PE-4683  
06/30/25  
ENGINEER  
NORTH DAKOTA


## NOTES:

(A) Arrow may be right or left of the legend to indicate construction to the right or left.

## ARROW DETAILS


CONSTRUCTION SIGN DETAILS  
REGULATORY SIGNS

D-704-10




R1-50P-24

Legend: black (non-refl)  
Background: white




R11-3c-60

Legend: black (non-refl)  
Background: white




R2-1aP-24

Legend: black (non-refl)  
Background: white



R11-4a-60

Legend: black (non-refl)  
Background: white



R11-2a-48


Legend: black (non-refl)  
Background: white

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-13-13	
REVISIONS	
DATE	CHANGE
08-17-17 10-03-19 08-01-24 06-30-25	Revised sign number New Design Engineer PE Stamp Electronic Stamp/Signature Legislative Changes




D-704-11

CONSTRUCTION SIGN DETAILS  
WARNING SIGNS




W5-8-48

Legend: black (non-refl)  
Background: orange




W8-53-48

Legend: black (non-refl)  
Background: orange




W8-56-48

Legend: black (non-refl)  
Background: orange




W5-9-48

Legend: black (non-refl)  
Background: orange



W8-54-48

Legend: black (non-refl)  
Background: orange




W8-55-48


Legend: black (non-refl)  
Background: orange

WORD	LETTER SPACING
AHEAD	Standard
200 FT	Standard
350 FT	Standard
500 FT	Standard
1000 FT	Reduce 40%
1500 FT	Reduce 40%
1/2 MILE	Reduce 50%
1 MILE	Standard

\* DISTANCE MESSAGES



W5-9-48



W9-3a-48








ARROW DETAILS

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-13-13	
REVISIONS	
DATE	CHANGE
8-17-17 5-31-18 10-03-19 8-01-24	Updated sign number Revised sign and arrow details New Design Engineer PE Stamp Electronic Stamp/Signature




08/01/24

D-704-11A

CONSTRUCTION SIGN DETAILS  
WARNING SIGNSW16-7aP-18  
Legend: black (non-refl)  
Background: orangeW21-50-48  
Legend: black (non-refl)  
Background: orangeW20-51-48  
Legend: black (non-refl)  
Background: orangeW21-51-48  
Legend: black (non-refl)  
Background: orangeW21-53-48  
Legend: black (non-refl)  
Background: orangeW22-8-48  
Legend: black (non-refl)  
Background: orangeW20-52P-54  
Legend: black (non-refl)  
Background: orangeW21-52-48  
Legend: black (non-refl)  
Background: orange

WORD	LETTER SPACING
AHEAD	Standard
200 FT	Standard
350 FT	Standard
500 FT	Standard
1000 FT	Reduce 40%
1500 FT	Reduce 40%
1/2 MILE	Reduce 50%
1 MILE	Standard

\* DISTANCE MESSAGES




NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
5-31-18	
REVISIONS	
DATE	CHANGE
11-01-19 8-01-24	Added details for sign W16-7aP-18. Electronic Stamp/Signature.

KIRK J. HOFF  
REGISTERED  
PROFESSIONAL  
PE-4683  
ENGINEER  
NORTH DAKOTA  
08/01/24

## BARRICADE AND CHANNELIZING DEVICE DETAIL


D-704-13






D-704-15

## ROAD CLOSURE LAYOUTS



## SIGN LAYOUT FOR ONE LANE CLOSURE TWO LANE ROADWAY

D-704-17



## Notes:


1. Place barricades on moveable assemblies and signs on portable assemblies when located on roadway.
2. Remove existing striping as required. Use back to back delineators when inslope is 4:1 or flatter and roadway alignment is visible to approaching vehicles. Place back to back vertical panels when roadways have steep slopes and alignment is not visible to approaching traffic.
3. Re-establish speed limit. Determine exact speed limit in the field, dependent on location and conditions.
4. Determine the reduced speed limit based on the in-place speed limit before construction. Where speed reductions exceed 30 MPH, install a second speed limit sign with the desired speed reduction (not to exceed 30 MPH). Place the second speed limit sign at  $\frac{1}{2}B$ .
5. Install flags on warning signs in urban areas when signs are not portable. Mount 24 inch square flags perpendicular to the edges of the sign, and at such a distance above the edge that the flag does not touch the sign when limp.
6. As an option, use portable sign supports in lieu of post mounted signs in accordance with NDDOT Standard Drawing D-704-14.
7. Cover existing speed limit signs within a reduced speed zone.
8. Sign G20-55-96 is not required if this layout is part of other traffic control that contains this sign, or if work is less than 15 days.
9. Recommend using 40 mph speed limit in vicinity of workers, unless location and conditions dictate otherwise.


ADVANCE WARNING SIGN SPACING			
Road Type	Distance Between Signs Min. (ft)		
	A	B	C
Urban - Low Speed (30 mph or less)	150	150	150
Urban - Low Speed (over 30 to 40 mph)	280	280	280
Urban - High Speed (over 40 mph to 50 mph)	360	360	360
Rural - High Speed (over 50 mph to 65 mph)	720	720	720
Urban Expressway and Freeway (55 mph to 60 mph)	850	1350	2200
Rural Expressway and Freeway (70 mph to 80 mph)	1000	1500	2640
Interstate/4-Lane Divided (Maintenance and Surveying)	750	1000	1500

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-27-13	
REVISIONS	
DATE	CHANGE
08-17-17 11-01-19 12-08-21	Note update & sign numbers Removed signs & revised note Switched order of Road Work XXXX and Spd Limit Enforced 8 added Dollars At Work
11-29-22 08-21-24 06-30-25	Removed Dollars At Work Pvmt Mkg Wldth & Med Barrier Legislative Changes






## TERMINAL AND SEAL COAT SIGN LAYOUTS





D-704-26

## MISCELLANEOUS SIGN LAYOUTS



Notes


1. Re-establish speed limit. Determine exact speed limit in the field, dependent on location and conditions.
2. Determine reduced speed limit based on in-place speed limit before construction. Where speed reductions exceed 30 mph, install a second speed limit sign with the desired speed reduction (not to exceed 30 mph). Place the second speed limit sign at  $\frac{1}{2}B$ .
3. Install flags on warning signs in urban areas when signs are not portable. Mount 24 inch square flags perpendicular to the edges of the sign, and at such a distance above the edge that the flag does not touch when limp.
4. Cover existing speed limit signs within reduced speed zones.
5. As an option, use portable sign supports in lieu of post mounted signs in accordance with NDDOT Standard Drawing D-704-14.
6. Sign G20-55-96 is not required if this standard is part of other traffic control layouts, or work is less than 15 days.
7. When pilot car operation is used, place sign G20-4b-36 "Wait For Pilot Car" at major intersections within pilot car control area.
8. Recommend 40 mph speed limit in vicinity of workers, unless location and conditions dictate otherwise.
9. Layouts shown for one direction only.

ADVANCE WARNING SIGN SPACING			
Road Type	Distance Between Signs		
	Min. (ft)	A	B
Urban - Low Speed (30 mph or less)	150	150	150
Urban - Low Speed (over 30 to 40 mph)	280	280	280
Urban - High Speed (over 40 mph to 50 mph)	360	360	360
Rural - High Speed (over 50 mph to 65 mph)	720	720	720
Urban Expressway and Freeway (55 mph to 60 mph)	850	1350	2200
Rural Expressway and Freeway (70 mph to 80 mph)	1000	1500	2640
Interstate/4-Lane Divided (Maintenance and Surveying)	750	1000	1500

\* Posted speed, off-peak 85th percentile speed prior to work starting, or the anticipated operating speed in mph.

Longitudinal Buffer Space			
Speed (mph)	Length Min (feet)		
	A	B	C
20		115	
25		155	
30		200	
35		250	
40		305	
45		360	
50		425	
55		495	
60		570	
65		645	
70		730	
75		820	
80		910	

NORTH DAKOTA	
DEPARTMENT OF TRANSPORTATION	
	9-27-13
DATE	CHANGE
08-17-17	Added speed limit signs. Updated notes & sign numbers.
11-01-19 02-23-23 06-30-25	Revised note 5 & sign numbers Revised distance & removed signs Legislative Changes





KEY

- Flagger
- Sign
- Cones
- Survey Equipment


S = Numerical value of speed limit or 85th percentile.

MOBILE OPERATION  
(PAVEMENT MARKING)


D-704-27

Typical Shadow Vehicle 1  
Two-Way Roaday


Two-Way Roadway with Paved Shoulders






Two-Way Roadway without Paved Shoulders



Undivided Multi-Lane Roadway



Typical Shadow Vehicle 1 & 2  
Multi-Lane Highways

A = [Left] [Right] [Center]




Divided Multi-Lane Highway

## Sign Details



## Notes

1. Use additional vehicles you choose to be in the convoy with truck mounted attenuators, at your own expense.
2. Display yellow rotating beacons or strobe lights on shadow and work vehicles, unless otherwise stated in the plans.
3. Use Type B or Type C flashing arrow panels controlled from inside the vehicle.
4. Provide each vehicle with two-way electronic communication capability.
5. Move shadow vehicle 1 first to shadow other convoy vehicles when convoy changes lane.
6. Vary vehicle spacing between shadow vehicle 1 and shadow vehicle 2 based on sight distance restrictions. Motorists approaching the work convoy need to see trail vehicle in time to slow down and/or change lanes as they approach shadow vehicle.
7. Sign Colors
  - Letters = Black
  - Border = Black
  - Background = Orange
8. As an option, use shadow vehicle 2 the paint tender vehicle.
9. Use sign CW21-10A only during painting operation.
10. Pull over work and shadow vehicles periodically to allow motor vehicle traffic to pass on two lane - two way roadways.




NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-27-13	
REVISIONS	
DATE	CHANGE
6-18-14	Removed shadow vehicle 2 on two lane roadways
9-27-17 11-08-19 8-02-24	Updated to active voice Changed Standard Heading Electronic Stamp/Signature




## Two-Lane Roadway Portable Rumble Strips





D-704-33



ADVANCE WARNING SIGN SPACING			
Road Type	Distance Between Signs Mln. (ft)		
	A	B	C
Urban - High Speed (over 45 mph to 50 mph)	360	360	360
Rural - High Speed (over 50 mph to 65 mph)	720	720	720



## PORTRABLE RUMBLE STRIPS ARRAY DETAIL



## PORTRABLE RUMBLE STRIPS ARRAY TYPES OF MOVEMENT AND MAXIMUM ALLOWANCES

Notes:


1. Determine speed in the field based on location and conditions.
2. Re-establish the speed limit. Determine the exact speed limit in the field, dependent on location and conditions.
3. Sign R2-1aP-24 is not required when pilot car operation is used.
4. Do not use rumble strips on a non paved surface or in a pre-construction speed zone of 45 mph or less.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
02-22-22	
REVISIONS	
DATE	CHANGE
03-07-23 06-30-25	Use changed to mln 45 mph Legislative Changes



## PORTABLE SIGN SUPPORT ASSEMBLY

D-704-50




NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
11-23-10	
REVISIONS	
DATE	CHANGE
12/02/2020	Updated Note to active voice.




**MOBILE OPERATION**  
Grinding Shoulder Rumble Strips

D-704-56




TWO LANE - TWO WAY ROADWAY




TWO LANE - TWO WAY ROADWAY

Typical Protection Vehicle with  
Flashing Arrow Panel In Caution Mode




INTERSTATE & 4 LANE DIVIDED HIGHWAY




INTERSTATE & 4 LANE DIVIDED HIGHWAY

Typical Protection Vehicle with Flashing Arrow  
Panel In Flashing Arrow Mode




NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
11-15-12	
REVISIONS	
DATE	CHANGE
8-17-17 10-03-19 8-02-24	Updated notes & signs New Design Engineer PE Stamp Electronic Stamp/Signature
KIRK J. HOFF	
REGISTERED PROFESSIONAL PE-4683	
NORTH DAKOTA 08/02/24	




## BITUMINOUS LABORATORY

D-706-1




Provide a laboratory with the following:

1. A 1'x1' shelf at 36" above the regular countertop.
2. Double compartment stainless steel sink, with each compartment a minimum of 16"x14"x10" deep. Provide water service lines made of copper or plastic and a diameter of  $\frac{1}{2}$  inch.
3. An exhaust fan capable of removing inside air at a rate of 400 CFM.
4. Fresh air vent hinged to open or close manually.
5. 24" x 48" table capable of holding a 200 lb masonry saw with a minimum clearance of 36" above the table.
6. A water supply tank with a capacity of 500 gallons and a 20 gallon capacity pressure tank on the pump.
7. Heavy duty type locks, latches, and hinges for doors made to withstand the intense use in service.
8. A wall between the office and the work area properly insulated to prevent the transmission of heat and noise.
9. The steel cable tie downs and ground anchors at each corner of the lab.
10. Electrical service entrance wired for 100 amps and separate circuits for air conditioners. Space convenience outlets in counter areas a minimum of four feet apart.




## SECTION A -




## SECTION B -

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-03-13	
REVISIONS	
DATE	CHANGE
07-30-14	Changed standard's title and revised notes.
01-11-16	Revised notes.
08-27-19	New Design Engineer PE Stamp
08-09-24	Electronic Stamp/Signature.





# RUMBLE STRIPS UNDIVIDED HIGHWAYS (SHOULDERS 4' OR GREATER)


D-760-3




Undivided Highways (Shoulders 4' or Greater)



Inset A - Shoulder Rumble Strip  
(Layout for opposite shoulder reversed)




Inset B - Centerline Rumble Strip




Milling Depths		
Location A (in)	Depth MIL	Depth in
0	62.5	1/16
1 3/4	156	5/32
3 1/2	281	9/32
5 1/4	438	7/16
7	500	1/2
8 3/4	438	7/16
10 1/2	281	9/32
12 1/4	156	5/32
14	62.5	1/16

## NOTES:


- 1) Discontinue shoulder rumble strips through the entire length of right turn lanes and tapers, and at the radius of paved or gravel highways, section line approaches, or private drives.
- 2) Discontinue centerline rumble strips 100' before and after paved or gravel highways, section line approaches, or private drives. Place rumble strips at left turn lanes as shown below.
- 3) No additional quantity provided for centerline rumble strips on left turn tapers. Include all costs for centerline rumble strips on left turn tapers in the price bid for "Sinusoidal Rumble Strip - Asphalt Centerline" or "Sinusoidal Rumble Strip - Concrete Centerline".



Discontinue rumble strip approx. 12" on both sides of PCC transverse joint



Inset C




Inset D

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
12-29-09	
REVISIONS	
DATE	CHANGE
2-25-10 4-19-10 9-08-11 10-25-19 11-16-21 3-07-23 5-26-23	Note 4 was added. Revised Note 5, Note 6, and Turn Lane (Right & Left), Revised Notes and D-760-3. Added missing dimensions. Changed turn lane rumble layouts. Added Note 3. Made rumble strips sinusoidal.




05/26/23


Shoulder Varies  
(2' to < 4')RUMBLE STRIPS  
UNDIVIDED HIGHWAYS (SHOULDERS LESS THAN 4')

Inset A - Edgeline Rumble Strip

(Layout for opposite shoulder reversed)



Inset B - Centerline Rumble Strip





## NOTES:



1) Discontinue shoulder rumble strips through the entire length of right turn lanes and tapers, and at the radius of paved or gravel highways, section line approaches, or private drives.

2) Discontinue centerline rumble strips 100' before and after paved or gravel highways, section line approaches, or private drives. Place rumble strips at left turn lanes as shown below.


3) No additional quantity provided for centerline rumble strips on left turn tapers. Include all costs for centerline rumble strips on left turn tapers in the price bid for "Sinusoidal Rumble Strip - Asphalt Centerline" or "Sinusoidal Rumble Strip - Concrete Centerline".




Milling Depths		
Location A (in)	MIL	in
0	62.5	1/16
1 3/4	156	5/32
3 1/2	281	9/32
5 1/4	438	7/16
7	500	1/2
8 3/4	438	7/16
10 1/2	281	9/32
12 1/4	156	5/32
14	62.5	1/16



Undivided Highways (12' Driving Lanes &amp; Shoulders 2' to &lt; 4')



Undivided Highways (12' Driving Lanes or less &amp; Shoulders Less than 2')



Discontinue rumble strip approx. 12" on both sides of PCC transverse joint


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
12-29-09	
DATE	CHANGE
2-25-10 4-19-10 9-08-11 1-26-12 10-25-19 11-16-21 3-07-23 5-26-23	Note 4 was added. Revised Note 5, Note 6, and Turn Lane (Right & Left), Revised Notes and D-760-4. Revised details for rumble strip widths and dimensions. Added missing dimensions. Revised turn lane rumble layout. Added Note 3. Rumble Strips made Sinusoidal.






## PAVEMENT MARKING


D-762-4




Two Lane Two Way  
RURAL ROADWAY




Two Lane Roadway  
INTERSTATE HIGHWAY  
Concrete Section




Two Lane Divided  
Rural Roadway  
PRIMARY HIGHWAY  
Asphalt Section




RURAL FIVE LANE ROADWAY  
Asphalt Section




Two Lane Divided  
Rural Roadway  
PRIMARY HIGHWAY  
Concrete Section




URBAN FIVE LANE SECTION  
Asphalt Section




Two Lane Roadway  
INTERSTATE HIGHWAY  
Asphalt Section




RURAL FOUR LANE ROADWAY  
Concrete Section




URBAN FOUR LANE SECTION  
Concrete Section




RURAL FIVE LANE ROADWAY  
Concrete Section




URBAN FIVE LANE SECTION  
Concrete Section



RURAL FOUR LANE ROADWAY  
Asphalt Section



URBAN FOUR LANE SECTION  
Asphalt Section



CENTERLINE PAVEMENT MARKING SKIP SPACING DETAIL

## NOTES:

1. Continue edge lines through private drives and field drives. Break edge lines for intersections.

For section lines, county roads, and street approaches, stripe the radii and edge lines of the paved surface within the right of way except where curb and gutter is present.

2. Normal width line - 6 inches wide for freeways, expressways, and ramps; 6 inches for all other roadways with speed limits > 40 mph.

3. Use 4 or 6 inch wide pavement marking for all other roadways with speed limits < 40 mph.


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
12-1-10	
REVISIONS	
DATE	CHANGE
10-17-17 08-27-19 11-22-23 07-09-24	Updated to active voice. New Design Engineer PE Stamp. Revised pavement marking widths. Modified Note 1.



## PAVEMENT MARKING FOR STANDARD 90 DEGREE FLARED INTERSECTION

D-762-5

(No Center Left Turn Lane on Major Road)




## Notes


- At "T" intersections (3-leg), additionally install left turn pavement marking message arrow.
- The barrier lines have variable distances dependent on speed limit. Obtain barrier line length from table below (stopping sight distance.)
- Normal width line - 6 inches wide for freeways, expressways, and ramps; 6 inches for all other roadways with speed limits > 40 mph.
- Use 4 or 6 inch wide pavement marking for all other roadways with speed limits  $\leq$  40.
- Wide line - 8 inches wide if 4 inch normal width lines are used and 12 inches wide if 6 inch normal width lines are used.

Table for Length of Barrier Line


Speed Limit (mph)	30	35	40	45	50	55	60	65	70
Minimum Length	200'	250'	305'	360'	425'	495'	570'	645'	730'



- 6" Marking
- 8" Marking
- 12" Marking
- 24" Marking




NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
3-29-16	
DATE	CHANGE
8-17-17 8-30-18 8-27-19 11-22-23 1-17-24	Updated note & dimensioning. Corrected pmkt mkg placement. New Design Engineer PE Stamp. Revised pavement marking widths. Revised wide pmkt mkg width.




## SHORT-TERM PAVEMENT MARKING

D-762-11




Painted or Tape Lines




Raised Pavement Markers

## TWO-LANE TWO-WAY ROADWAY




Painted or Tape Lines




Raised Pavement Markers

## FOUR LANE ROADWAY




Painted or Tape Lines




Raised Pavement Markers

## FIVE LANE ROADWAY TWO WAY LEFT TURN



Painted or Tape Lines



Raised Pavement Markers

## FIVE LANE ROADWAY WITH MARKED ISLANDS

## NOTES:

1. Place no passing zones on two-lane two-way roadways as shown. In lieu of short term no passing zone pavement markings, place no passing zone signs. Replace no passing zone signs with short term no passing zone pavement marking within three days.
2. Place short term center line stripe (paint) on top lift to match exact placement of permanent stripe.
3. Remove raised markers and tape markings after permanent pavement marking is installed.
4. Normal width line - 6 inches wide for freeways, expressways, and ramps; 6 inches for all other roadways with speed limits > 40 mph.
5. Use 4 or 6 inch wide pavement marking for all other roadways with speed limits ≤ 40 mph.
6. Wide lines - 8 inches wide if 4 inch normal width lines are used and 12 inches wide if 6 inch normal width lines are used.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
12-1-10	
REVISIONS	
DATE	CHANGE
3-29-16	Re-numbered to be D-762-11 (previously was D-762-6)
10-17-17	Updated to active voice.
8-27-19	New Design Engineer PE Stamp.
11-22-23	Revised pavement marking widths.
1-17-24	Revised wide pvtm marking width.

