


# Valley City Landslide Interstate 94



Colter Schwagler, Tyler Peterson, Greg Fischer  
2020 Virtual OPD/Construction Conference  
Bismarck, ND

# Slide Location



# Timeline

- Grade Raise and Realignment completed in 2000
- 2001 North Inslope begins to show distress



# Timeline

- Grade Raise and Realignment completed in 2000
- 2001 North Inslope begins to show distress



# Timeline

- Grade Raise and Realignment completed in 2000
- 2001 North Inslope begins to fail
- 2001 400 feet of sheet piling and longitudinal drain installed



# Timeline

- 2007 Road Shoulder has dropped noticeably, and sheet piling is deflecting



# Timeline

- 2014 Shoulder has continued to drop and pull away from driving lane. New shoulder area further west has noticeably dropped and pulled away.




# Timeline

- 2014 Shoulder has continued to drop and pull away from driving lane. New shoulder area further west has noticeably dropped and pulled away.
- Become concerned about larger failure



# Geologic Map



# 1959 Aerial



# Timeline


- 2016 Inclometers installed through the area of distress North, South and in the Median of the Interstate




# Inclinometers

- Inclinometers are plastic tubes with internal grooves that guide a probe along the length of the tube.
- The inclinometers are placed in a borehole and grouted in place
- The inclinometers move with the surrounding soil and can be read using a portable probe
- Inclinometers can show depth, direction, and rate of movement over time.


# Inclinometer Locations



094 291 0009L042 A





094 291 0009L042 B



094 291 0009L042 A

094 291 0009L042 B





PROJECT NUMBER NH-2-094(151)290 DATE STARTED 10/31/16 COMPLETED 11/1/16

PCN 21765 ELEVATION 1274 ft

LOCATION Barnes County RP+FEET 290+5028 OFFSET 68 DIR L

DRILLED BY Dallan LOGGED BY Jamie DRILLING METHOD Hollow Stem Auger

ENGINEER NOTES Middle North Inslope

ELEVATION (ft)	DEPTH (ft)	MATERIAL DESCRIPTION	GRAPHIC LOG	AASHTO	USCS	SAMPLE TYPE & NUMBER	RECOVERY (%)	SPT N VALUE	MC	LL	TESTS & REMARKS
1274.0	0.0	Topsail	0.3 ft	A-8	SC	SS 1480	40	7	1635	40	
1273.7	0.3	1273.7 ft		A-7.6	CH	SS 1481	40	7	22 57		
1270.0	4.0	Loose Moist Clayey Sand Fill circa 2000	4.0 ft	A-7.6	CH	SS 1482	50	4	22 60		$\gamma = 101.4$ pcf $\gamma = 131.9$ pcf UU=1869 pcf
1263.0	11.0	Medium Stiff to Stiff Moist Brown/Black/Grey Fat Clay and Elastic Silt with Gravel fill circa 2000	11.0 ft	A-7.6	CH	SS 1483	40	10	26 60		
1263.0	11.0	1263.0 ft		A-7.6	CH	3TW 1484	35	8	27 60		
1255.0	19.0	Medium Stiff to Stiff Moist Brown/Black/Grey Fat Clay and Elastic Silt with Gravel fill circa 1955		A-7.6	CH	SS 1485	65	11	21 52		
1255.0	19.0	1255.0 ft		A-7.6	CH	SS 1486	75	11	133		
1249.0	25.0	Medium Stiff to Stiff Moist Brown/Black/Grey Fat Clay and Elastic Silt with Gravel	25.0 ft	A-7.6	CH	SS 1487	25	10	31 78		
1249.0	25.0	1249.0 ft		A-7.6	CH	SS 1488	75	10	37 81		
1244.0	30.0	Coarse Sand	30.0 ft	A-7.6	CH	SS 1489	10	10	43 86		
1244.0	30.0	1244.0 ft		A-7.6	CH	3TW 1490	65	14	36 78		$\gamma = 85.5$ pcf $\gamma = 114.9$ pcf UU=2739 pcf
1243.4	30.6	Stiff Moist Black/Grey Fat Clay Failure Plane at 61'	30.6 ft	A-7.6	CH	SS 1500	50	17	35 73		$\gamma = 99.3$ pcf $\gamma = 126.7$ pcf UU=2791 pcf
1243.4	30.6	1243.4 ft		A-7.6	CH	SS 1501	90	17	28 68		
1240.0	40.0	1240.0 ft		A-7.6	CH	3TW 1502	65	14	26 68		
1230.0	50.0	1230.0 ft		A-7.6	CH	SS 1503	75	11	24 60		
1220.0	60.0	1220.0 ft		A-7.6	CH	SS 1504	85	14	21 48		
1210.0	70.0	1210.0 ft		A-7.6	CH	SS 1505	85	14	23 55		
1200.0	80.0	1200.0 ft		A-7.6	CH	SS 1506	85	14	21 53		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1507	85	22	22 54		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1508	85	14	35 104		$\gamma = 74.8$ pcf $\gamma = 109.4$ pcf $c = 1382.5$ psf $\phi = 5.2^\circ$ $\gamma = 74.9$ pcf $\gamma = 109.4$ pcf UU=2188 pcf
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1509	85	11	33 99		$\gamma = 78.7$ pcf $\gamma = 112.4$ pcf $\gamma = 78.2$ pcf $\gamma = 113.0$ pcf
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1510	85	12	34 107		$\gamma = 76.4$ pcf $\gamma = 114.4$ pcf
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1511	85	11	33 90		$\gamma = 86.3$ pcf $\gamma = 117.5$ pcf UU=3172 pcf
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1512	85	11	32 97		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1513	85	11	36 108		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1514	85	11	28 113		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1515	85	12	31 118		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1516	85	11	30 141		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1517	85	21	24 76		$\gamma = 91.7$ pcf $\gamma = 121.3$ pcf $c = 1272.9$ psf $\phi = 16.0^\circ$ $\gamma = 92.0$ pcf $\gamma = 121.3$ pcf UU=4324 pcf
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1518	85	35	24 76		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1519	85	35	22 84		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1520	85	40	25 84		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1521	85	52	26 88		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1522	85	55	27 105		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1523	85	59	25 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1524	85	59	27 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1525	85	100	25 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1526	85	100	27 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1527	85	100	25 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1528	85	100	27 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1529	85	100	25 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1530	85	100	27 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1531	85	100	25 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1532	85	100	27 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1533	85	100	25 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1534	85	100	27 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1535	85	100	25 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1536	85	100	27 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1537	85	100	25 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1538	85	100	27 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1539	85	100	25 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1540	85	100	27 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1541	85	100	25 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1542	85	100	27 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1543	85	100	25 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1544	85	100	27 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1545	85	100	25 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1546	85	100	27 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1547	85	100	25 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1548	85	100	27 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1549	85	100	25 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1550	85	100	27 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1551	85	100	25 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1552	85	100	27 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1553	85	100	25 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1554	85	100	27 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1555	85	100	25 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1556	85	100	27 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1557	85	100	25 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1558	85	100	27 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1559	85	100	25 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1560	85	100	27 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1561	85	100	25 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1562	85	100	27 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1563	85	100	25 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1564	85	100	27 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1565	85	100	25 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1566	85	100	27 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1567	85	100	25 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1568	85	100	27 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1569	85	100	25 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1570	85	100	27 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1571	85	100	25 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1572	85	100	27 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1573	85	100	25 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1574	85	100	27 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1575	85	100	25 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1576	85	100	27 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1577	85	100	25 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1578	85	100	27 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1579	85	100	25 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1580	85	100	27 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1581	85	100	25 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1582	85	100	27 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1583	85	100	25 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1584	85	100	27 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1585	85	100	25 107		
1195.0	85.0	1195.0 ft		A-7.6	CH	SS 1586	85	100</			



PROJECT NUMBER NH-2-094(151)290 DATE STARTED 10/31/16 COMPLETED 11/1/16  
PCN 21765 ELEVATION 1274 ft  
LOCATION Barnes County RP+FEET 290+5028 OFFSET 68 DIR L  
DRILLED BY Dallon LOGGED BY Jamie DRILLING METHOD Hollow Stem Auger  
ENGINEER

NOTES Middle North Inslope

ELEVATION (ft)	DEPTH (ft)	MATERIAL DESCRIPTION	GRAPHIC LOG	AASHTO	USCS	SAMPLE TYPE & NUMBER	RECOVERY (%)	SPT N VALUE	MC	PL	LL	CLAY FRACTION (%)	TESTS & REMARKS
1274.0	0.0	Topsail	0.3 ft	A-8	EC	SS 1460	40	7	1635	40	80	80	
1273.7	0.3			A-7.6	CH	SS 1461	40	7	22	57			
1270.0	4.0	Loose Moist Clayey Sand Fill circa 2000	4.0 ft	A-7.6	SC	STW 1482	50	4	22	60			$\gamma_s = 101.4$ pcf $\gamma = 131.5$ pcf $UU = 1859$ psf
1263.0	11.0	Medium Stiff to Stiff Moist Brown/Black/Grey Fat Clay and Elastic Silt with Gravel fill circa 2000	11.0 ft	A-7.6	CH	SS 1483	40	8	25	60			
1253.0	12.0			A-7.6	CH	STW 1484	35	8	27	60			
1253.0	12.0	Medium Stiff to Stiff Moist Brown/Black/Grey Fat Clay and Elastic Silt with Gravel fill circa 1958		A-7.6	CH	SS 1485	65	11	21	52			
1249.0	25.0			A-7.6	CH	SS 1486	75	11	133				
1249.0	25.0	Medium Stiff to Stiff Moist Brown/Black/Grey Fat Clay and Elastic Silt with Gravel		A-7.6	CH	STW 1488	75	10	31	78			
1244.0	30.0			A-7.6	CH	SS 1489	10	10	37	81			
1243.4	30.6	Coarse Sand	30.6 ft	A-7.6	SC	STW 1490	65	10	43	86			
1243.4	30.6	Stiff Moist Black/Grey Fat Clay Failure Plane at 61'		A-7.6	CH	SS 1501	25	10	35	78			$\gamma_s = 83.6$ pcf $\gamma = 114.9$ pcf $UU = 2738$ psf
1243.4	30.6			A-7.6	CH	STW 1502	85	14	26	68			
1243.4	30.6			A-7.6	CH	SS 1503	50	17	24	60			$\gamma_s = 98.9$ pcf $\gamma = 125.7$ pcf $UU = 2725$ psf
1243.4	30.6			A-7.6	CH	STW 1504	50	17	21	48			
1243.4	30.6			A-7.6	CH	SS 1505	90	17	23	55			
1243.4	30.6			A-7.6	CH	STW 1506	75	11	21	53			
1243.4	30.6			A-7.6	CH	SS 1507	75	11	22	54			
1243.4	30.6			A-7.6	CH	STW 1508	85	22	35	104			
1243.4	30.6			A-7.6	CH	SS 1509	85	14	33	99			$\gamma_s = 74.8$ pcf $\gamma = 103.4$ pcf $c = 1387.5$ psf $\phi = 5.2^\circ$
1243.4	30.6			A-7.6	CH	STW 1510	85	14	34	107			$\gamma_s = 74.5$ pcf $\gamma = 103.4$ pcf
1243.4	30.6			A-7.6	CH	SS 1511	90	12	33	90			$\gamma_s = 75.7$ pcf $\gamma = 112.4$ pcf $UU = 2186$ psf
1243.4	30.6			A-7.6	CH	STW 1512	75	11	32	97			
1243.4	30.6			A-7.6	CH	SS 1513	85	11	36	108			$\gamma_s = 79.2$ pcf $\gamma = 113.0$ pcf
1243.4	30.6			A-7.6	CH	STW 1514	85	11	28	113			
1243.4	30.6			A-7.6	CH	SS 1515	75	12	31	118			$\gamma_s = 76.4$ pcf $\gamma = 114.4$ pcf
1243.4	30.6			A-7.6	CH	STW 1516	75	12	30	141			$\gamma_s = 83.3$ pcf $\gamma = 117.5$ pcf $UU = 3172$ psf
1243.4	30.6			A-7.6	CH	SS 1517	85	11	24	76			$\gamma_s = 81.7$ pcf $\gamma = 121.3$ pcf $c = 1272.9$ psf $\phi = 18.0^\circ$
1243.4	30.6			A-7.6	CH	STW 1518	85	21	24	76			$\gamma_s = 82.0$ pcf $\gamma = 121.3$ pcf $\gamma = 106.5$ pcf $\gamma = 129.7$ pcf $UU = 4324$ psf
1243.4	30.6			A-7.6	CH	SS 1519	85	40	25	84			
1243.4	30.6			A-7.6	CH	STW 1520	85	40	26	88			
1243.4	30.6			A-7.6	CH	SS 1521	85	52	26	105			
1243.4	30.6			A-7.6	CH	STW 1522	85	52	27	105			
1243.4	30.6			A-7.6	CH	SS 1523	85	55	25	107			
1243.4	30.6			A-7.6	CH	STW 1524	85	55	27	107			
1243.4	30.6			A-7.6	CH	SS 1525	85	59	27	107			
1243.4	30.6			A-7.6	CH	STW 1526	85	59	27	107			
1243.4	30.6			A-7.6	CH	SS 1527	85	59	27	107			
1243.4	30.6			A-7.6	CH	STW 1528	85	59	27	107			
1243.4	30.6			A-7.6	CH	SS 1529	85	59	27	107			
1243.4	30.6			A-7.6	CH	STW 1530	85	59	27	107			
1243.4	30.6			A-7.6	CH	SS 1531	85	59	27	107			
1243.4	30.6			A-7.6	CH	STW 1532	85	59	27	107			
1243.4	30.6			A-7.6	CH	SS 1533	85	59	27	107			
1243.4	30.6			A-7.6	CH	STW 1534	85	59	27	107			
1243.4	30.6			A-7.6	CH	SS 1535	85	59	27	107			
1243.4	30.6			A-7.6	CH	STW 1536	85	59	27	107			
1243.4	30.6			A-7.6	CH	SS 1537	85	59	27	107			
1243.4	30.6			A-7.6	CH	STW 1538	85	59	27	107			
1243.4	30.6			A-7.6	CH	SS 1539	85	59	27	107			
1243.4	30.6			A-7.6	CH	STW 1540	85	59	27	107			
1243.4	30.6			A-7.6	CH	SS 1541	85	59	27	107			
1243.4	30.6			A-7.6	CH	STW 1542	85	59	27	107			
1243.4	30.6			A-7.6	CH	SS 1543	85	59	27	107			
1243.4	30.6			A-7.6	CH	STW 1544	85	59	27	107			
1243.4	30.6			A-7.6	CH	SS 1545	85	59	27	107			
1243.4	30.6			A-7.6	CH	STW 1546	85	59	27	107			
1243.4	30.6			A-7.6	CH	SS 1547	85	59	27	107			
1243.4	30.6			A-7.6	CH	STW 1548	85	59	27	107			
1243.4	30.6			A-7.6	CH	SS 1549	85	59	27	107			
1243.4	30.6			A-7.6	CH	STW 1550	85	59	27	107			
1243.4	30.6			A-7.6	CH	SS 1551	85	59	27	107			
1243.4	30.6			A-7.6	CH	STW 1552	85	59	27	107			
1243.4	30.6			A-7.6	CH	SS 1553	85	59	27	107			
1243.4	30.6			A-7.6	CH	STW 1554	85	59	27	107			
1243.4	30.6			A-7.6	CH	SS 1555	85	59	27	107			
1243.4	30.6			A-7.6	CH	STW 1556	85	59	27	107			
1243.4	30.6			A-7.6	CH	SS 1557	85	59	27	107			
1243.4	30.6			A-7.6	CH	STW 1558	85	59	27	107			
1243.4	30.6			A-7.6	CH	SS 1559	85	59	27	107			
1243.4	30.6			A-7.6	CH	STW 1560	85	59	27	107			
1243.4	30.6			A-7.6	CH	SS 1561	85	59	27	107			
1243.4	30.6			A-7.6	CH	STW 1562	85	59	27	107			
1243.4	30.6			A-7.6	CH	SS 1563	85	59	27	107			
1243.4	30.6			A-7.6	CH	STW 1564	85	59	27	107			
1243.4	30.6			A-7.6	CH	SS 1565	85	59	27	107			
1243.4	30.6			A-7.6	CH	STW 1566	85	59	27	107			
1243.4	30.6			A-7.6	CH	SS 1567	85	59	27	107			
1243.4	30.6			A-7.6	CH	STW 1568	85	59	27	107			
1243.4	30.6			A-7.6	CH	SS 1569	85	59	27	107			
1243.4	30.6			A-7.6	CH	STW 1570	85	59	27	107			
1243.4	30.6			A-7.6	CH	SS 1571	85	59	27	107			
1243.4	30.6			A-7.6	CH	STW 1572	85	59	27	107			
1243.4	30.6			A-7.6	CH	SS 1573	85	59	27	107			
1243.4	30.6			A-7.6	CH	STW 1574	85	59	27	107			
1243.4	30.6			A-7.6	CH	SS 1575	85	59	27	107			
1243.4	30.6			A-7.6	CH	STW 1576	85	59	27	107			
1243.4	30.6			A-7.6	CH	SS 1577	85	59	27	107			
1243.4	30.6			A-7.6	CH	STW 1578	85	59	27	107			
1243.4	30.6			A-7.6	CH	SS 1579	85	59	27	107			
1243.4	30.6			A-7.6	CH	STW 1580	85	59	27	107			
1243.4	30.6			A-7.6	CH	SS 1581	85	59	27	107			
1243.4	30.6			A-7.6	CH	STW 1582	85	59	27	107			
1243.4	30.6			A-7.6	CH	SS 1583	85	59	27	107			
1243.4	30.6			A-7.6	CH	STW 1584	85	59	27	107			
1243.4	30.6			A-7.6	CH	SS 1585	85	59	27	107			
1243.4	30.6			A-7.6	CH	STW 1586	85	59	27	107			
1243.4</													

# Timeline

- 2017 Shannon and Wilson Hired to Peer Review Design Process
- 2017 Distress moves into the driving lane pavement and a project is triggered and design begins




# Peer Review Process

- NDDOT has no experience with structural landslide mitigation alternatives
- NDDOT has had consultants provide structural landslide mitigation alternatives in the past couple years
- Due to project constraints it was likely that this project would require a structural alternative
- RFP process was relatively quick and painless
- Consultant was chosen based on phone interviews and short presentation
- Allowed the NDDOT to rely on Shannon and Wilson's experience designing and constructing structural solutions during the design process


# Options and Design Issues

- 1<sup>st</sup> choice mitigation alternative was a buttress
- Drainage at toe of slope must be accounted for both during construction and permanently
- Buttress option would require an 11' x 9' approximately 1000' long box culvert




# Options and Design Issues

- Excavation required for box culvert option results in very questionable temporary stability
- Buttress option is abandoned, and Ground Anchor Option is pursued




# Ground Anchors

- Ground Anchors are grouted, prestressed structural elements installed in soil or rock that are used to transmit a tensile load into the ground
- Ground Anchors consist of a bond zone, anchorage, and unbonded zone.




# Ground Anchors

- The bond zone is a length of prestressed steel that is bonded to the grout and the soil
- The anchorage transmits the force from the prestressing steel to the ground
- The unbonded zone is a portion of the prestressed steel that is not directly exposed to grout allowing it to elongate elastically and transfer the force from the bond length to the anchorage.




# Ground Anchors

- The bond zone is a length of prestressed steel that is bonded to the grout and the soil
- The anchorage transmits the force from the prestressing steel to the ground
- The unbonded zone is a portion of the prestressed steel that is not directly exposed to grout allowing it to elongate elastically and transfer the force from the bond length to the anchorage.




# Ground Anchors

- The bond zone is a length of prestressed steel that is bonded to the grout and the soil
- The anchorage transmits the force from the prestressing steel to the ground
- The unbonded zone is a portion of the prestressed steel that is not directly exposed to grout allowing it to elongate elastically and transfer the force from the bond length to the anchorage.




# Ground Anchors

- The bond zone is a length of prestressed steel that is bonded to the grout and the soil
- The anchorage transmits the force from the prestressing steel to the ground
- The unbonded zone is a portion of the prestressed steel that is not directly exposed to grout allowing it to elongate elastically and transfer the force from the bond length to the anchorage.




# Options and Design Issues

- Access to Drill Ground Anchors is evaluated
- Cannot avoid impacting the drainage at the toe of the slope
- Requires a 48" diameter Temporary pipe to maintain drainage and temporary grading to provide a construction platform



# Final Design


- Satisfactory Ground Anchor Option is achieved
- 1-3 rows
- 5 strand 193.1 kip Design Load
- 125-140' Long





# Timeline

- 2018 SAA installed
- 2018 Construction Begins



# Construction


- Project Engineering Staff
- Construction Phasing
- Major Project Issues

# Project Engineering Staff


- NDDOT
  - Project Engineer
  - Geotechnical Engineers (M & R)
- KLJ
  - Project Inspectors
  - Materials Tester
  - Surveyor
- Shannon and Wilson
  - Geotechnical Inspector
  - Geotechnical Engineer

# Construction Phasing

- Two Year Project
  - Year 1 – 2018
  - Year 2 - 2019




4/18/2018 12:58:21 PM ghaf R:\project\20094290.15\design\Sheet\004\SW\_001\_Year 1.dgn



4/16/2018 12:50:22 PM gtwf R:\project22094290\_151\design\Sheets\004876\_001\_Year 2.dgn

# Year 1 - 2018

- Place and Remove Temporary Drainage Pipe



STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	IM-2-094(151)290	20	4

SPEC	CODE	BID ITEM	UNIT	QTY
714	4128	PIPE CONDUIT 48IN - APPROACH	LF	1,625
Sta 108+00 to 124+25 (WB I-94)				

This document was originally issued and sealed by Jeffrey R. Renach, Registration Number PE- 8211, on 4/11/18 and the original document is stored at the North Dakota Department of Transportation

Construction Phasing Detail  
 Drainage Ditch & Ground Anchors  
 Valley City I-94

#18/2018 12:30:23 PM ghr R:\project\20094280\_15\design\sheet\0200\_004\_Ground Anchor Phasing.dgn




# Year 1 - 2018

- Place and Remove Temporary Drainage Pipe
- Grading
- Precast and Install Concrete Anchor Blocks
- Drill and Install Ground Anchors

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	IM-2-094(151)290	20	4

SPEC	CODE	BID ITEM	UNIT	QTY
714	4128	PIPE CONDUIT 48IN - APPROACH	LF	1,625
Sta 108+00 to 124+25 (WB I-94)				



This document was originally issued and sealed by Jeffrey R. Rensch, Registration Number PE- 8211, on 4/11/18 and the original document is stored at the North Dakota Department of Transportation

Construction Phasing Detail  
 Drainage Ditch & Ground Anchors  
 Valley City I-94



4/18/2018 12:50:23 PM ghar R:\project\20094290\151\design\Sheets\2000\_04\_Ground Anchor Phasing.dgn







STATE	PROJECT NUMBER	SECTION NO.	SHEET NO.
ND	IM-2-094(151)290	20	1





**DESIGN STRENGTHS:**

$f'_c = 4,000$  psi - Class AAE-3 Concrete  
 $f_y = 60,000$  psi - Reinforcing Steel  
 Load & Resistance Factor Design

BAR LIST - ONE ANCHOR BLOCK			
SIZE	MARK	NO.	LENGTH
7	A100	48	9'-2"
4	C100	4	3'-0"
4	N100	4	6'-4"

MATERIAL QUANTITIES (ONE ANCHOR BLOCK)	
REINFORCING STEEL (LBS)	CONCRETE (CY)
924	6.1
<b>TOTAL ANCHOR BLOCKS</b>	<b>285</b>



**NOTES:**

- The Contractor is to determine the size and thickness of the bearing plate, trumpet, anchor head and end cap. Provide a steel bearing plate and trumpet with a minimum yield strength of 50 ksi. Provide a bearing plate with minimum plan dimensions of 16" x 16".
- Provide a Sch 40 steel pipe meeting ASTM A53 with a minimum yield strength of 30 ksi. Extend the pipe for the full depth of the concrete anchor block. Include the cost of furnishing and placing the steel pipe in the price bid for Class AAE-3 concrete.
- Achieve a minimum 28-day concrete compressive strength of 4,000 psi in the anchor block before the ground anchor is stressed.
- Install the anchor block so that it is in full contact with the soil prior to the application of tendon jacking loads. No voids between the anchor block and soil are permitted.

SPEC	CODE	ITEM DESCRIPTION	UNIT	QUANTITY
602	0130	CLASS AAE-3 CONCRETE	CY	1,738.5
612	0115	REINFORCING STEEL-GRADE 60	LBS	263,340

This document was originally issued and sealed by Brian W. Raschke, Registration Number PE 4361, on 04/09/18 and the original document is stored at the North Dakota Department of Transportation

NORTH DAKOTA  
 DEPARTMENT OF TRANSPORTATION  
**I-94 VALLEY CITY SLIDE REPAIR**  
**CONCRETE ANCHOR BLOCK DETAILS**

PROJECT: IM-2-094(151)290  
 BARNES COUNTY  
 04/09/18 Jon Ketterling














# Year 1 - 2018

- Place and Remove Temporary Drainage Pipe
- Grading
- Precast and Install Concrete Anchor Blocks
- Drill and Install Ground Anchors
- Jack and Bore Pipe Conduit
- Pipe Extensions

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	IM-2-094(151)290	20	5



4/18/2018 12:50:24 PM ghart R:\project\20094\151\design\18\sheet\020\00\_05\_jack-Bore Pipe.dgn



# Year 1 - 2018

- Place and Remove Temporary Drainage Pipe
- Grading
- Precast and Install Concrete Anchor Blocks
- Drill and Install Ground Anchors
- Jack and Bore Pipe Conduit
- Pipe Extensions
- Drill and Install Inclinometers



# Year 1 - 2018


- Place and Remove Temporary Drainage Pipe
- Grading
- Precast and Install Concrete Anchor Blocks
- Drill and Install Ground Anchors
- Jack and Bore Pipe Conduit
- Pipe Extensions
- Drill and Install Inclinometers
- Topsoil, Seeding, & Permanent Erosion Control



# Year 2 - 2018

- Removal of Pavement
- Grading
- PCC Pavement
- Permanent Erosion Control

STATE	PROJECT NO.	SECTION NO.	SHEET NO.
ND	IM-2-094(151)290	100	4



This document was originally issued and sealed by Wayne A. Zacher, Registration Number PE- 6402, on 4/11/18 and the original document is stored at the North Dakota Department of Transportation

Reconstruction Work Zone  
Traffic Control Phasing  
Year 2  
Valley City I-94



# Major Project Issues

- Jack and Bore Pipe Conduit
- Erosion Control

# Jack and Bored Pipe

- Reconstruction of the pavement section triggered a hydraulic study
- Hydraulic study called for an additional 30" diameter pipe to be jack and bored through the slide area
- Original schedule called for this to take 21 days
- Work began on October 28<sup>th</sup>, 2018
- October 30<sup>th</sup> pipe contractor encountered boulders (approx. 140' in)
- No boulders were encountered during geotechnical investigation
- Boulders required microblasting and manual removal for the rest of the 170' of pipe
- 36 ground anchors could not be installed in 2018 due to the bore pit
- Construction completed on May 22<sup>nd</sup>, 161 total days to complete this work
- Contract revision due to differing site conditions

# Jack and Bored Pipe

- All labor, equipment, & material was tracked and accounted for
- Re-Mobilization to finish the ground anchor work













# Erosion Control

- The Original Design was to install seeding class II or Wetland Seed with Turf Reinforcement Mats
- In the Spring of 2019, the ditch experienced high turbulent flows
- The NDDOT and the Contractor evaluated the ditch and noticed excessive amounts of erosion





# Erosion Control

- The Original Design was to install seeding class II or Wetland Seed with Turf Reinforcement Mats
- In the Spring of 2019, the ditch experienced high turbulent flows
- The NDDOT and the Contractor evaluated the ditch and noticed excessive amounts of erosion
- A contract revision was made to line the ditch with Grade II RIP RAP to prevent future erosion from occurring.





# Consultant Role - Review

- Subsurface Information
  - Exploration and instrumentation by NDDOT
  - Review NDDOT landslide characterization
- Proposed Alternatives
  - Preliminary analyses
  - Comparison and selection of stabilization approach
- Design of Selected Alternative
  - Review of NDDOT analyses and Independent analyses
- Plans and Specifications
  - Review and support

# Consultant Role - ~~Review~~

- Independent Analyses
  - Limit Equilibrium
    - Preliminary evaluation of various alternatives
    - Check of NDDOT final design and evaluation of several construction cases (e.g. installation of access benches, culvert)
  - Stress Distribution
- Specialized Analyses
  - FLAC to evaluate A-Frame micropile structure

# Review Schedule

- 2 Weeks of Receiving Deliverable
- Concept – Engagement throughout Design Process to Expedite Review Process
- Coordinated effort to find and evaluate potential fatal flaws
  - Construction access and stability of slide
  - Anchor bond strength

# Add-Ons

- Ground Anchor Specifications
- Instrumentation for stability monitoring
  - Shape Accel Array
  - Real-time remote monitoring with alerts
  - Setting monitoring thresholds and dealing with triggers



# Construction

- Full-time representative during anchor installation
- Review of verification and proof test results
- Stability monitoring and review of SAA data
- Problems during construction?


# Submittal Review



- Anchor Contractor
- Anchor Working Drawing
- Instrumentation Plan
- Sacrificial Tests
- Work Plan to Remove Obstruction

# Inspector

- Interpret and verify the Contractors compliance
- Perform visual field verification of excavated soil/rock material for comparison to the projects boring logs
- Perform required reporting
- Perform inspection of instrumentation installation for compliance to plans and manufacturer recommendations







Apparent Free Length		
Min. Allowable (ft)	$L_{app}$ (ft)	Max. Allowable (ft)
86.4	99.8	128.0

Elongation at 0.60 MUTS	
Elastic, $\delta_e$ (in.)	Residual, $\delta_r$ (in.)
6.245	4.375

Creep at 0.40 MUTS	
1 to 10 min (in.)	6 to 60 min (in.)
0.000	0.008


























# Instrumented Anchors

## Anchor A-19

<u>Strain Gauge</u>	<u>Test Load at 193 kips</u>	<u>18 Days after Lock-off</u>	<u>Readings taken 7/3/19</u>
S1 (10' in bond zone)	Not Functioning	67.8 kips	72.7 kips
S2 (25' in bond zone)	31.2 kips	23.4 kips	27.6 kips
S3 (40' in free length)	151.8 kips	109.8 kips	91.8 kips

## Anchor C-37

<u>Strain Gauge</u>	<u>Lock-off at 193 kips</u>	<u>2 Days after Lock-off</u>	<u>7 Days after Lock-off</u>	<u>Readings taken 7/3/19</u>
S7 (10' in bond zone)	88.8 kips	90.6 kips	93.0 kips	97.8 kips
S8 (25' in bond zone)	28.2 kips	31.2 kips	31.2 kips	30 kips
S9 (40' in free length)	139.2 kips	132 kips	126 kips	140.4 kips

# Summary

- Consultant Review Role Successful
- Useful when Considering New Technology or New Design Approaches without In-House Experience
- Previous Working Relationship Helpful
- Ground Anchor Stabilization Successful
- Don't Forget about the Other Features of a Project

# Questions