

**NORTH DAKOTA
DEPARTMENT OF TRANSPORTATION**

MATERIALS AND RESEARCH DIVISION

Experimental Study NDEP 94-05

Moisture Sensors in a Base and Subbase

Second Annual Report

Project IM-8-094(005)331

April 1997

Prepared by

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION

BISMARCK, NORTH DAKOTA

Website: <http://www.discovernd.com/dot/>

DIRECTOR

Marshall W. Moore

MATERIALS AND RESEARCH DIVISION

Ron Horner

U.S. DEPARTMENT OF TRANSPORTATION FEDERAL HIGHWAY ADMINISTRATION									
EXPERIMENTAL PROJECT REPORT									
EXPERIMENTAL PROJECT	EXPERIMENTAL PROJECT NO.						CONSTRUCTION PROJ NO		LOCATION
	1	STATE ND	YEAR 94	-	NUMBER 05	SURF	8 IM-8-094(005)331		2 Cass County
	EVALUATION FUNDING						NEEP NO. <div style="border: 1px solid black; width: 50px; height: 20px; margin: 5px;"></div>	PROPRIETARY FEATURE?	
	48	1 HP&R	3 DEMONSTRATION				Yes		
		2 CONSTRUCTION	4 IMPLEMENTATION			49	51 No		
SHORT TITLE	TITLE 52 Moisture Sensors in a Base and Subbase								
THIS FORM	DATE 140	MO. 0	4	-	9	7	REPORTING 1 INITIAL 2 X ANNUAL 3 FINAL		
KEY WORDS	KEY WORD 1					KEY WORD 2			
	KEY WORD 3					KEY WORD 4			
	UNIQUE WORD					PROPRIETARY FEATURE NAME			
CHRONOLOGY	Date Work Plan Approved 04-94 277		Date Feature Constructed: 09-94 281		Evaluation Scheduled Until: 08-99 285		Evaluation Extended Until: 289		Date Evaluation Terminated: 293
QUANTITY AND COST	QUANTITY OF UNITS <div style="border: 1px solid black; width: 150px; height: 30px; margin: 5px;"></div> 297			UNITS 1 LIN. FT 5 TON 2 SY 6 LBS 3 SY-IN 7 EACH 4 CY 8 X LUMP SUM 305				UNIT COST (<i>Dollars, Cents</i>) <div style="border: 1px solid black; width: 150px; height: 30px; margin: 5px; text-align: right;">25579.20</div> 306	
AVAILABLE EVALUATION REPORTS	X CONSTRUCTION 315			X PERFORMANCE			FINAL		
EVALUATION	CONSTRUCTION PROBLEMS 1 X NONE 2 SLIGHT 3 MODERATE 4 SIGNIFICANT					PERFORMANCE 1 EXCELLENT 2 GOOD 3 SATISFACTORY 4 MARGINAL			
APPLICATION	1 ADOPTED AS PRIMARY STD. 2 PERMITTED ALTERNATIVE					4 PENDING 5 REJECTED <i>(Explain in remarks if 3, 4, 5, or 6 is checked)</i>			
REMARKS	321 Results inconclusive. It appears that at joint locations the drainable base is not effective or is only marginally effective in reducing the moisture content of the subgrade at the joint locations. The mid-panel locations appear to show the dense graded base is more effective than the drainable base, however, the moisture content in the subgrade shows the drainable base to be more effective. <div style="text-align: right; margin-top: 10px;">700</div>								

EXPERIMENTAL

Moisture Sensors in a Base and Subbase

SECOND ANNUAL REPORT

IM-8-094(005)331

MARCH 1997

Written by
Jeff M. Richter

Disclaimer

The contents of this report reflect the views of the author or authors who are responsible for the facts and the accuracy of the data presented herein. The contents do not reflect the official views of the North Dakota Department of Transportation or the Federal Highway Administration. This report does not constitute a standard, specification, or regulation.

TABLE OF CONTENTS

PURPOSE	1
SCOPE	1
LOCATION	1
DESIGN	1
Figure 1 Drainable base	1
Figure 2 Dense Graded base	2
Figure 3 Sensor Location Joints	3
Figure 4 Sensor Location Mid-Panel	3
CONSTRUCTION	4
EVALUATION	4
Graph 1 Moisture %'s in base under Joints 1995	5
Graph 2 Moisture %'s in base under Joints 1996	6
Graph 3 Moisture %'s in base under Mid-Panel 1995	7
Graph 4 Moisture %'s in base under Mid-Panel 1996	8
Graph 5 Moisture %'s in subgrade 1995	9
Graph 6 Moisture %'s in subgrade 1996	10
SUMMARY	11-14
Figure 5 Average Moisture Drainable Base @ Joint	12
Figure 6 Average Moisture Dense Graded Base @ Joint	12
Figure 7 Average Moisture Drainable Base @ Mid-Panel	13
Figure 8 Average Moisture Dense Graded Base @ Mid-Panel	13
APPENDIX A:	Construction Plans

MOISTURE SENSORS IN A BASE AND SUBBASE

Project IM-8-094(005)331
NDEP94-05

PURPOSE:

The purpose of this study is to determine the effectiveness of a permeable base in reducing the moisture levels in the base and subgrade.

SCOPE:

The scope of this experimental project is to compare the moisture levels in the salvaged base beneath a permeable base, in a dense graded base, and in the subgrade. These sections are beneath a Portland Cement Concrete (PCC) pavement roadway surface.

LOCATION:

This project is located in the eastbound lanes of Interstate 94 in Cass County near Casselton, North Dakota. The moisture sensors are located at station 880+98.4, station 881+35.9, station 891+52.5, and station 891+90. See appendix A.

DESIGN:

The design called for placing three moisture sensors in two different roadway sections. The first section consists of four inches of a drainable base and eight inches of salvaged bituminous base placed on the subgrade as shown in figure 1.





Figure 1

The second section consists of six inches of dense graded base placed on the subgrade as shown in figure 2 below. Each section called for placement of moisture sensors at two locations. The roadway section with a drainable base called for placing two moisture sensors in the salvaged base and one sensor in the subgrade as shown in figure 1. The roadway section without the permeable base called for placing two moisture sensors in the dense graded base and one sensor in the subgrade as shown in figure 2.



Stations: 891+52.5 Rt. and 891+90 Rt.

Figure 2

The sensors were located below a skewed transverse joint and below the midpoint of a concrete panel for each type of base course as shown in figures 3 and 4.

It is anticipated that the joint sealant will eventually lose its sealing capacity and allow moisture to readily enter the base material below the joints. It is then anticipated that the permeable base will remove the excess moisture while the dense graded base will allow the moisture to accumulate causing the base to lose its support capability.

The amount of moisture entering the base course at the midpoint of the PCC panels will be dependent on the lateral movement of the moisture in the base and capillary movement of moisture from the subgrade.




Figure 3




Figure 4

CONSTRUCTION:

Installation of the moisture sensors was performed by Fargo Electric from Fargo, North Dakota in September 1994. The installation was constructed to plan without problem in the following sequence:

- 1) Installation of cabinet concrete footings
- 2) Trenching for conduit and sensors
- 3) Installation of sensors and conduit
- 4) Compaction of trench fill
- 5) Mounting of controlled environment cabinets
- 6) Installation of multiplexer control panel
- 7) Tagging and recording cables from sensors

EVALUATION:

The graphs on the following pages represent the monthly average of the data collected from the moisture sensors. Graph 1 and Graph 2 include data from the sensors in the salvaged base and in the dense graded base located at the transverse joints. Graph 3 and Graph 4 include data from the sensors in the salvaged base and in the dense graded base located at the midpoint of the PCC pavement panels. Graph 5 and Graph 6 represent data from the sensors located in the subgrade for all locations.



There is no data available for the month of June 1995 for any of the sensors. There was erroneous data from the sensors in the subgrade under the mid-panel dense graded base during May, July, August, and September of 1995, which was not included in graph 5. There was also erroneous data from the sensors in the subgrade under the transverse joint dense graded base during May and August of 1995 which was not included in graph 5. The data for 1996 includes only the months of April, May, June, and July. This is due to problems collecting the data between January and April of 1996. It was also decided to change the evaluation parameters of the study to include data from July to July for the next comparisons.

SENSORS LOCATED AT TRANSVERSE JOINT

WITHIN BASE COURSE

1995

%MOISTURE



* Below Permeable
Stabilized Base


Graph 1

SENSORS LOCATED AT TRANSVERSE JOINT


WITHIN BASE COURSE

1996

%MOISTURE



MONTHLY AVERAGE



* Below Permeable
Stabilized Base



Graph 2

SENSORS LOCATED AT MIDPANEL

WITHIN BASE COURSE

1995

%MOISTURE



* Below Permeable
Stabilized Base



Graph 3

SENSORS LOCATED AT MIDPANEL

WITHIN BASE COURSE

1996

%MOISTURE





Graph 4

SENSORS IN SUBGRADE

1995

%MOISTURE





* Below Permeable
Stabilized Base

Graph 5

SENSORS IN SUBGRADE

1996

%MOISTURE



Graph 6

SUMMARY:

A comparison of sensor readings on Graphs 1 and 2 show that since construction, the top of the salvaged base course (Figure 5) averages 22% moisture at the joint location. The bottom of the salvaged base course (Figure 5) at the same location averages 35% moisture. Graphs 1 and 2 also show that the moisture content of the top of the dense graded base course (Figure 6) has an average of 27% moisture while the bottom of the dense course (Figure 6) has an average moisture content of 23%.

A comparison of sensor readings on Graphs 3 and 4, where the sensors are located at mid-panel, indicate that the top of the dense graded base course (Figure 7) has an average moisture of 18% at mid-panel and the bottom of the dense graded base course (Figure 7) has an average of 19% moisture. The graphs also show that the top of the salvage base course (Figure 8) has an average of 27% moisture while the bottom (Figure 8) has an average of 25% moisture.

Graphs 5 and 6 show the moisture contents in the subgrade below a transverse joint (Figure 5) to be 24 % below the salvage base and 31% below the dense graded base (Figure 8). The mid-panel moisture contents are 29% below the salvage base (Figure 6) and 38% below the dense graded base (Figure 7). A comparison of these moisture contents is shown in the following diagrams.

Figure 5




Figure 6




Figure 7





Figure 8



These results are inconclusive at this time. It appears that at joint locations the drainable base is not effective or is only marginally effective in reducing the moisture content in the base material. It is however effective in reducing the moisture content of the subgrade at the joint locations.

The mid-panel locations appear to show that the dense graded base is more effective than the drainable base, however the moisture content in the subgrade shows the drainable base to be more effective.

APPENDIX A

DESIGN DATA				
Traffic	Average Daily			Est Month
Current 1994	Pass. 3,455	Trucks 700	total 4,155	450
Forecast 2014	Pass. 5,000	Trucks 1,050	total 6,130	775
Minimum Sight Dist. for:	Design Speed			70 MPH
Stopping	625 Ft			
Full Control of Access				
No Point of Access Other Than at Interchange Ramps				

JOB# _____ NORTH DAKOTA DEPARTMENT OF TRANSPORTATION

FED. REGION	STATE	PROJECT NO.	SHEET NO.
8	ND	IM-8-094(005)331	1

IN CASS COUNTY

FEDERAL AID PROJECT IM-8-094(005)331

PCC RECYCLING & SPS-2 EXPERIMENTAL SECTIONS

GOVERNING SPECIFICATIONS:

Standard Specifications adopted by the North Dakota Department of Transportation September 1992; Standard Drawings currently in effect; and other Contract Provisions submitted hereto.


LENGTH OF PROJECT

Miles-Cross 7.510
Miles-Net 7.449

0.061 M deducted for bridges.



BEGIN Sta. 855+18.4
Section 12, Twp 139 N,
Rge 52 W




PAVING SECTION	<i>Benjamin</i>
URBAN SECTION	
TRAFFIC SECTION	<i>Acry. S. L. Field</i>
RURAL SECTION	
RECOMMEND APPROVAL	<i>2-1-1994</i>
DESIGN ENGINEER	<i>David H. Lee</i>

U.S. DEPARTMENT OF TRANSPORTATION FEDERAL HIGHWAY ADMINISTRATION	APPROVED DATE <i>2-1-94</i>	
APPROVED	<i>Ray Zink</i> DIRECTOR OF HIGHWAYS AND ENGINEERING	
DIVISION ADMINISTRATOR	DATE	

SCOPE OF WORK

FINVA REGION	STATE	FED. AID PROJ. NO.	SHEET NO.
8	N.D.	1H-8-094(005)331	3

EDUCATION
916+85.7 BK=
914+94.4 ANH



LEGEND
 SPS SECTIONS
 RECYCLED PCC PVMT

A-2

NOTES

FHVA REGION	STATE	FED. AID PROJ. NO.	SHEET NO.
8	N.D.	HM-8-094(005)331	8

990 The contractor shall furnish the Department with a Pearpoint Color
P01 Flexiprobe System consisting of the following:

Quantity	ID #	Description
1 EA	IN2207101	Camera Control Unit
1 EA	HC0504901	5 Meter 16 ft Link Cable
1 EA	HW1321201	T Piece
1 EA	IK1100001	Metal Coller
1 EA	HC0505601	Rod 320'
1 EA	HI2662001	6W 44mm Lighthouse
1 EA	HC2179801	Plastic Sleeve
1 EA	HC2174001	Camera Color
1 EA	PP165101	Spring Centering Device
1 EA	AIQRD40051	Radio Sonde Receiver
1 EA	HI2662201	Lamp Replace PCB Kit
1 EA		4 Head VCR W/Audio & Video-In Capabilities
1 EA		Honda Generator 650 Watt

The specified system shall become the property of the Department.
(NOTE: Northern Water Works Supply is the only licensed dealer of the Pearpoint flexible video system in North Dakota.)

The unit price bid for "Pearpoint Color flexiprobe System" shall include all costs to provide this system.

990 The contractor shall furnish and install a Moisture Sensor System
P02 consisting of the following:

Soilmoisture Equipment Corporation

Quantity	Product No.	Description
2	6050X1	Trace System 1
12	6005L2	Durable Waveguide (2 Meter Cable)
12	6006L20	Extension Cable (20 Meters)
2	6021C16	TDR Switching Board (16 Channel)
1	6022	Multiplexer Control Board

Hennessy Products

Quantity	Product No.	Description
2	LS583017A13R	
2	231633	Shelf Kit
2	240627	Fan Thermostat
2	240625	300 Watt Heat Kit
2		Insulation Adder

The specified system shall become the property of the Department. The contractor shall install the Moisture Sensor System according to the manufacturer's recommendations. A representative from the Soilmoisture Equipment Corporation shall be present during installation of the equipment. The contact person is Richard White (phone number (805)964-3525.)



The contractor shall take the steps necessary to protect the sensors once they are in place. Damaged sensors shall be replaced at the contractor's expense.

The cables running from the sensors to the cabinet shall be placed in 1 inch rigid conduit.

The contractor shall give 48 hours advance notice of installation of sensors to Cliff Kuntz of the WDDOT (phone number (701)221-6910.)


The unit price bid for "Moisture Sensor System" shall include all costs to provide and install this system.

FIPA REG. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.
8	N.D.	IN-8-094(005)331	18




TYPICAL SECTION

FHWA REGION	STATE	FED. AID PROJ. NO.	SHEET NO.
8	N.D.	1H-8-094(005)331	10




WIDTH	QUANTITY	UNIT	APPROXIMATE QUANTITIES
556		N Gal	482 N Gal Water for Dust Palliative and Subgrade Prep + 48 Gal/Ton of Salvaged Base Course
5025'	12696	Ton	Salvaged Base Course
44'	4839	Ton	Permeable Asphalt Stabilized Base
121		Ton	AC 20 Asphalt Cement
10100		LF	Edge Drains
346		LF	Outlet Pipe
38'	21491	SY	10' Non-Reinforced RPCC Pavement
1412		Ton	Portland Cement
332		Ton	Flyash
24'	8136	LF	Beveled Contraction Joint Assembly
385'	13052	LF	Contraction Joint Silicone Seal
44'	4977	Gal	MC-70 or 250 Lq Asph for Prime Coat @ .20 Gal/SY.


CROSS SECTION OF PCC PAVEMENT SLAB
(TANGENT)

UNVELED JUNCTION PLAIN PCC PAVEMENT
 SIDEWALK ROADWAY
 SECTION I
 Sta 002+70.4 to Sta 095+53.4

FED. AID PROJ. NO.	SHEET NO.
0	22
STATE	
N.D.	
IN-094-B(005)330	



ITEM	QUANTITY	UNIT	APPROPRIATE QUANTITIES
42'	1930	Ton	Base Graded Base Course
30'	5303	SY	11' Non-Reinforced PCC Pavement - CLASS AE
30.5'	3272	LF	Contraction Joint Silicone Seal
24'	2040	LF	Beveled Contraction Joint Assembly



CROSS SECTION OF PCC PAVEMENT SLAB
 (TANGENT)

TABLE OF VARIATION FOR SECTION 1 THRU SECTION 12


FINA REGION	STATE	FED. AID PROJ. NO.	SHEET NO.
8	N.D.	HM-8-094(005)331	38

TYPICAL SECTION	PCC PVHI DEPTH (INCHES)	PCC PVHI WIDTH (FEET)	14 DAY FLEXURAL STRENGTH (PSI)	BASE TYPE	JOINT ORIENTATION	TRANSVERSE JOINT SPACING (FEET)	TYPE OF LOAD TRANSFER DEVICE
1	11	38	*	CL 5 AGGR	SKEVED	15	DOVELS
2	11	24	550	CL 5 AGGR	SKEVED	VARIABLE	NONE
3	11	24	550	CL 5 AGGR	90°	15	DOVELS
4	11	28	900	CL 5 AGGR	90°	15	DOVELS
5	8	24	900	CL 5 AGGR	90°	15	DOVELS
6	8	28	550	CL 5 AGGR	90°	15	DOVELS
7	8	28	550	LCB	90°	15	DOVELS
8	8	24	900	LCB	90°	15	DOVELS
9	11	28	900	LCB	90°	15	DOVELS
10	11	28	550	LCB	SKEVED	VARIABLE	NONE
11	11	24	550	LCB	90°	15	DOVELS
12	11	24	550	PASB	90°	15	DOVELS
13	11	24	550	PASB	SKEVED	VARIABLE	NONE
14	11	38	*	PASB	SKEVED	15	NONE
15	11	28	900	PASB	90°	15	DOVELS
16	8	28	550	PASB	90°	15	DOVELS
17	8	24	900	PASB	90°	15	DOVELS

* Class AE as per NDDOT Specifications.

PAYEMENT DETAILS FOR SRP TEST SECTIONS

FIRMA	STATE	FED. AID PROJ. NO.	SHEET
8	N.D.	1H-8-094(005)331	40



LEGEND

PCC- Portland Cement Concrete
 PASB- Penn Asph Stabilized Base
 LCB- Lean Concrete Base
 DGB- Dense Graded Base
 RPCC- Recycled PCC
 SB- Salvaged Base

--- Tied Longitudinal Joint
 Edge of Hot Bit Pmnt
 — Edge of PCC Slab
 [Pattern] Transition

Paid for as 11' PCC Pmnt		
10' RPCC	PCC	11' PCC
4' PASB		
8' SB	DGB	6' DGB

SECT. A-A

JOINT DETAILS

FIRMA	STATE	FED. AID PROJ. NOL	SHEET
8	N.D.	W-0-09(1005)330	40

