## **RESEARCH REPORT DOCUMENTATION PAGE**

1. Report No. MR 2004-01	2. Report Date February, 2005	3. Contract No. N/A		4. Project No. AC-HPP-4-052(045)058
5 Title and Subtitle		6. Report Type	7. Project No.	
Effects of HBP Paver Motion on Ride Quality			Click on link to open report	0. Project No.
			Work Plan	8. Project No.
				9. Project No.
			Final	10. Project No.
11. Author(s)/Principle Investigator(s) Kyle Evert				
12. Performing Organization Name and Address 13. Sponsoring Agency Name and Address				
NDDOT M+R ⊠ NDDOT OTHER* □	North Dakota DO Materials and Res	I search Division	North Dakota DOT	
NDSU	300 Airport Road		Materials and Research Division 300 Airport Road	
	Bismarck ND 58504-6005		Bismarck ND 58504-6005	
OTHER*				
see supplementary notes				
14. Supplementary Notes				
15. Abstract				
Purpose and Need				
HBP paver can result in rough pavements. Variation in paver speed can be the result of plant production rate, truck delivery, hauling distance, or equipment operator expertise. In addition to improving ride quality, research from (NCHRP 1-31 Smoothness Specification for Pavements) has indicated that pavement life may be extended by improving initial smoothness.				
Objective				
The objective of this project is to determine if there is a correlation between paver motion and the ride quality of new hot bituminous pavements.				
Scope				
A lightweight inertial profiler evaluated the new asphalt section. A GPS unit was placed on the paver to record its motion during the paving of the asphalt section. After the project was finished, the lightweight inertial profiler obtained the final profile of the roadway. The paver's motion was then compared to the measured profile of the roadway. Using the captured data from the profiler, GPS unit and the project engineer's comments; conclusions and recommendations for optimizing paving operations will be given.				
Construction				
The widening and re-grading of the roadway and the first lift of the asphalt section was completed in the 2003, as part of project AC-HPP-4- 052(045)058. Project AC-HPP-4-052(045)058 the intermediate and final lifts of HBP was constructed in 2004. Steve Sink from the Minot District the project engineer and Mayo Construction from Cavalier, ND was the prime contractor.				
Conclusion				
Attempting to keep the paver motion constant and limiting the number of paver stops would be recommended as a result this project. It may be impossible to eliminate the paver from stopping, but the number of stops may be reduced by altering paving methods. Also, the length of stops may help reduce the size of the bump. Making the base and first asphalt lift as smooth as possible to reduce the bumps from reflecting there the final lifts is also recommended. Trying to improve aspects of paving may help in improving the ride.				
16. Key Words	17. Distribution Statement No restrictions. Th	is document is availa	able to the public from:	18. No. of Pages 39
Profile Bituminous		inte Deperturent (T		19. File type/Size
Mine and Blend	North Dal Mate	vota Department of I erials and Research I	ransportation Division:	
Roughness	300 Airport Road			Pat / 6.7 mb
	E Office: (701) 32	Зіsmarck ND 58504-6 28-6900 Fa	5005 ix: (701) 328-0310	