

**NORTH DAKOTA DEPARTMENT OF TRANSPORTATION
SUPPLEMENTAL SPECIFICATIONS**

Bid Opening 09-24-04

The following specifications are supplementary to the 2002 Edition of the *Standard Specifications for Road and Bridge Construction* as they apply to this Contract.

101.02 DEFINITIONS.	Page 17	04-16-04
----------------------------	----------------	-----------------

Add “product data sheets,” after “shop drawings,” in the second line of the **Working Drawings** definition.

103.08 ESCROW OF BID DOCUMENTATION.	Page 25	02-20-04
--	----------------	-----------------

Delete the first paragraph of Section 103.08 D. in its entirety and replace with the following:

After award, the Department and the Contractor will jointly deliver the sealed container and affidavit to a banking institution or other bonded document storage facility selected by the Contractor and approved by the Department for placement in a safety deposit box, vault, or other secure accommodation. The document storage facility shall be located in Bismarck, North Dakota unless otherwise approved by the Department. The Contractor will provide escrow instructions to the document storage facility consistent with this Section.

105.03 COOPERATION WITH UTILITIES	Page 36	07-16-04
--	----------------	-----------------

In the third paragraph (beginning “These utilities will be relocated...”), delete the word “owners” and replace it with “owner’s”.

105.03 COOPERATION WITH UTILITIES	Page 36	05-21-04
--	----------------	-----------------

Add the following sentence to the end of the sixth paragraph (beginning “The Contractor shall make arrangements...”):

Unless a pay item is shown on the plans, any and all costs associated with such protections shall be incidental to the prices bid for other items.

105.03 COOPERATION WITH UTILITIES	Page 36	04-16-04
--	----------------	-----------------

Delete the seventh paragraph (beginning “The Contractor shall notify...” in its entirety and insert the following:

Utilities shown on the plans, if any, are for reference purposes only and may not constitute an exhaustive representation of all utilities within the project limits. The Contractor shall notify the North Dakota One Call System (1-800-795-0555) prior to the beginning of construction, so they may locate and mark all utilities in the project area. Separate Plans, if any, showing relocation or adjustment work will be made available to the Contractor, upon request to the Engineer. The Contractor shall be responsible for locating NDDOT-owned, publicly-owned and privately-owned utilities, whether on or off the One Call System. Subcutting or scarifying over utility lines may be eliminated if, in the opinion of the Engineer, a hazardous situation exists.

105.03 COOPERATION WITH UTILITIES

Page 37

05-21-04

Delete the second sentence of the eleventh paragraph (i.e. third paragraph on the page, beginning "The Contractor shall prevent...") and insert the following sentence in its place:

"Damage to underground utilities caused by the Contractor's operations shall be corrected at the Contractor's expense."

105.06 CHARACTER OF WORKERS

Page 38

02-14-03

03-14-03

Delete the first sentence of Section 105.06 C. in its entirety and insert the following:

When the methods and equipment to be used are specified, other methods and equipment shall not be used without authorization of the Engineer.

105.08 PLANS AND WORK DRAWINGS

Page 40

04-16-04

Delete Section 105.08 in its entirety and insert the following:

105.08 PLANS AND WORK DRAWINGS.

- A. **General.** Plans will show the location and details of all structures, lines, grades, and typical cross sections of the roadway. When required by the contract documents, the Plans will be supplemented by work drawings necessary to adequately control the work.
- B. **Work Drawings Submitted By The Contractor.** Work drawings, necessary to complete the work, which are supplied by the Contractor shall be submitted to the Engineer prior to the performance of the work. The drawings shall be submitted on sheets no larger than 11" x 17" unless otherwise allowed by a work item specification.

Each sheet of the work drawings submitted shall be stamped as approved by the contractor performing the work. At a minimum, the stamp will include the signature and title of the person approving the work drawing and the date of the approval.

The Engineer shall review the work drawings as indicated in the plans, proposal, specifications, or other contract documents. Any submittal and review of work drawings by the Engineer shall not constitute approval of nor acceptance of items represented by such drawings and shall not relieve the Contractor of any responsibility under the Contract. Such responsibility includes, but is not limited to:

1. Successful completion of the work.
2. Errors, omissions, or deviations from the contract requirements.
3. Accuracy of dimensions and details.
4. Agreement and conformity with the Contract.
5. Proper and safe design done by the Contractor.
6. Proper and safe construction of the work.

In addition to any time requirements which may be specified for a work item, the Contractor shall allow sufficient time for the Engineer to review and comment on the submittal, and the Contractor to respond to the comments, prior to performance of the work. The Contractor shall not change any requirements as shown in the contract documents without the Engineer's written authorization. A cover letter to be included with each work drawing submittal shall include, at a minimum:

1. The project number.
2. The prime contractor name.
3. The subcontractor name, if applicable.
4. Verification that the work drawings have been reviewed and approved by the contractor performing the work.
5. The items of work covered in the work drawing. Each item shall be identified by the specification, code, and description.
6. An itemized list of any deviations from the contract documents.
7. Any other information as required by the Engineer.

The Contract price will include the cost of furnishing all required work drawings.

106.02 LOCAL MINERAL AGGREGATE SOURCES**Page 45****07-16-04**

Delete the third sentence in paragraph 3 of Section 106.02 B., beginning "(Time will be counted from...)", in its entirety.

**106.06 STOCKPILING AGGREGATE
AND SALVAGED MATERIALS****Page 47****02-20-04**

Delete the last paragraph of Section 106.06 and insert the following:

Equipment will not be permitted on salvaged bituminous material that will remain the property of the Department or that will be used for hot recycled bituminous pavement. When the plans specify the material to be salvaged for these purposes the material shall not be stockpiled higher than 15 feet.

106.09 BUY AMERICAN PRODUCTS.**Page 48****02-14-03**

Delete the heading of Section 106.09 and replace with the following:

106.09 BUY AMERICA PRODUCTS.

107.04 HISTORIC PRESERVATION RESPONSIBILITIES.**Page 50 & 51****06-20-03**

Delete the first paragraph of Section 107.04 A. in its entirety and replace with the following:

- A. **Department Owned or Optioned Areas.** When the Contractor is operating within the right of way, easement areas, or within Department optioned areas and encounters the remains of prehistoric dwelling sites, human burials, or historical or archeological artifacts, operations at that location shall be temporarily discontinued. The Contractor shall inform the Engineer and the Department's Cultural Resource Section of the discovery and shall move construction operations to another part of the project. The Contractor shall not resume construction operations until the Department obtains clearance from the State Historic Preservation Officer (SHPO). The Contractor will make all reasonable efforts to protect the material until the matter has been reviewed by the SHPO. If cultural resources are discovered that are eligible for inclusion in the National Register of Historic Places, compliance with Section 106 of the National Historic Preservation Act of 1966 and the Advisory Council on Historic Preservation "Procedures for the Protection of Historic and Cultural Properties" (36 CFR, Pt. 800) will be required. When directed, the Contractor shall excavate the site to preserve the artifacts encountered. Such excavation shall be paid for as "Extra Work." If the Contractor fails to notify the Engineer of the discovery, the Contractor shall be liable for all standby costs, all damage incurred, and all costs associated with the salvage and preservation activities specified in this section.
-

107.04 HISTORIC PRESERVATION RESPONSIBILITIES.**Page 51****06-20-03
07-18-03**

Delete the second and third paragraph of Section 107.04 B. in their entirety and replace with the following:

The Department shall review the furnished legal description and map to determine if the area has been previously utilized as a material source for a Department project. Within 14 days from the receipt of the legal description and map, the Department shall inform the Contractor of the status of the cultural resources in the proposed material source. If the Department finds that cultural resource work is necessary, the Contractor shall take the necessary action to appropriately satisfy Section 106 of the NHPA. Typically this begins with (but is not necessarily limited to) a Class III Cultural Resource Inventory. Every material source must be subject (minimally) to a Class III Cultural Resource Inventory. If the Department determines that a moderate or higher potential does exist, the Contractor must obtain clearance from the SHPO before any operations can be initiated. The Contractor is responsible for any and all costs associated with the cultural resource work necessary to fulfill Section 106 of the NHPA. The Department will not be responsible for, or share in any costs associated with Section 106 compliance on contractor-optioned material sources. The Contractor will not receive payments or compensation for delays resulting from the Department review.

The Department review and subsequent independent completion of the Section 106 process will not relieve the Contractor of the responsibility of complying with all federal and state laws and regulations which govern the salvage and preservation of any cultural resources that are discovered during pit or borrow operations. In the event of a discovery, the procedures specified in Section 107.04 A shall be followed, except that the Contractor shall be liable for all standby costs, all damages incurred, and all costs associated with the salvage and preservation activities.

107.05 RESPONSIBILITY TO THE PUBLIC.**Page 52****11-21-03**

The following sentence shall be added after the fourth sentence of the second paragraph of Section 107.05 A.1.:

... and farms. Details on location of access points and construction procedures shall be worked out with the Engineer in the field prior to the start of the project. The cost of ...

107.05 RESPONSIBILITY TO THE PUBLIC.**Page 53****05-21-04**

Add the following paragraph to the end of Section 107.05 A.5:

The Contractor shall not use private property to park vehicles or equipment, to store materials, or as a work area without written permission from the property owner. The Contractor, at his sole expense, shall repair, to the property owner's satisfaction, any private-property damages resulting from the Contractor's activities.

107.05 RESPONSIBILITY TO THE PUBLIC.**Page 56****11-21-03**

The following paragraph shall be added to Section 107.05 D.:

The Contractor shall protect the existing pavement outside of the construction limits during the course of construction. Surface repair which is required because of the Contractor's operations, other than designated haul roads, shall be repaired by the Contractor at the Contractor's expense.

107.06 RAILWAY HIGHWAY PROVISIONS.**Page 57****09-24-04**

In Section 107.06 B, add the following to the end of the last sentence of the last paragraph (beginning "If flagging of railroad traffic..."):

and the Contractor will reimburse the Department for these expenses. The costs for this flagging shall be incidental to other items bid.

107.10 INERT WASTE DISPOSAL.**Page 61****04-16-04****05-21-04****06-18-04**

Delete Section 107.10 in its entirety.

Insert the following in its place:

107.10 INERT WASTE DISPOSAL.

- A. This work consists of the proper recycling or disposal of inert material waste on a project. Inert waste includes, but is not limited to; Clearing and Grubbing (as defined in Section 201.02 B), Concrete, Steel, Bituminous Pavements and Pavement Base. For additional information regarding inert waste classification, reference the North Dakota Department of Health – Division of Waste Management’s “GUIDELINE 17 – WASTES EXCLUDED FROM ACCEPTANCE AT LANDFILLS.”

When inert material on a project is designated the property of the contractor, and the contractor chooses to waste the material, the material must be disposed in one of two ways:

1. Disposal of the material at an approved permanent waste management facility.
2. If waste cannot be reasonably recycled, reused or managed at an approved landfill, the North Dakota Department of Health may consider allowing a variance for disposal. An “INERT WASTE DISPOSAL VARIANCE APPLICATION,” SFN 50278, is available from the North Dakota Department of Health – Division of Waste Management. For guidance in filing the application refer to the North Dakota Department of Health – Division of Waste Management’s “GUIDELINE 22A – INERT WASTE DISPOSAL VARIANCE.” Upon approval of the variance, the contractor shall furnish the engineer with an approved copy, before any material is disposed at the approved site.

Locations of permanent waste facilities, and a variance application and guideline can be obtained at the North Dakota Department of Health – Division of Waste Management, 701-328-5166. A list of municipal and Inert waste landfills is available at the North Dakota Department of Health website at: <http://www.health.state.nd.us/ndhd/envIRON/wm/lists.htm>. Guideline 17 and 22A and other North Dakota Department of Health guidance are available at: <http://www.health.state.nd.us/ndhd/envIRON/wm/pubs.htm#swpubs>.

- B. If the Contractor fails to comply with all requirements of Section 107.10, the Department reserves the right to:
1. Suspend progressive estimate payments.
 2. Invoke any other disincentive allowed by the contract.
 3. Request the North Dakota Department of Health to take any and all enforcement actions provided by applicable law.
- C. Nothing in Section 107.10 shall be construed to prevent the beneficial recycling or reuse of waste materials on this project, as allowed in other sections of the specifications/plans, or on other projects of the Contractor’s choice, including stockpiling the material at a Contractor obtained storage facility so long as the materials are restricted to recyclable inert materials, they are not placed in environmentally sensitive areas such as floodplains, steep areas, wetlands, ravines, etc. and the activities are in accordance with any state and local zoning and health requirements.
- D. Unless a bid item is shown on the plans, all costs associated with inert waste disposal shall be incidental to the price bid for other items.

151.03 HAULING EQUIPMENT.

Page 90

04-11-03

Delete Section 151.03 A. in its entirety and insert the following:

- A. **Water-Hauling Equipment.** Water hauling units shall be equipped with a spraying device capable of evenly distributing water over the designated area. The water tank and all connections shall be watertight.

151.07 SCALES.**Page 96****06-20-03**

Insert the following paragraph as paragraph 2 to Section 151.07 E. 1.:

Loader Bucket Scales shall comply with the requirements of items 2 through 4 of this Section. The weight indicated shall be accurate to within 1.0 percent of the true weight.

153.06 ROADBED PLANERS.**Page 106 & 107****04-11-03**

Delete the first sentence of the second paragraph in its entirety and insert the following:

The planer shall be equipped with rotary cutting mechanisms capable of trimming the subgrade and base to the required lines and grades within the tolerances of Section 302.04 F.3 Surface Tolerance Type C.

201.02 CONSTRUCTION REQUIREMENTS.**Page 117****04-16-04**

In Section 201.02 B, delete the last two paragraphs, in their entirety. The first paragraph begins "Materials and debris may be..." and the second paragraph begins "When permitted by the Engineer..." and insert the following:

"Clearing and Grubbing, if wasted, must be disposed according to Section 107.10 – INERT WASTE DISPOSAL."

{Note: modification to Section 107.10, above}

202.02 CONSTRUCTION REQUIREMENTS.**Page 119****09-24-04**

From Section 202.02 A, delete the last sentence (beginning "Copies of all agreements...") from the first paragraph. Also, delete the phrase "and shall be disposed of in a manner satisfactory to the property owners and governing agencies" from the next to last sentence in the first paragraph. Insert the following as a new sentence at the end of the first paragraph:

If the Contractor chooses to waste the removed material, it shall be disposed of according to Section 107.10.

202.02 CONSTRUCTION REQUIREMENTS.**Page 120****09-24-04**

Add the following as a new paragraph to the end of Section 202.02 D (Removal of Pavement, Sidewalks, Curbs, etc.):

Removal of manholes shall consist of removing the casting, rings, barrel and base; plugging or capping the existing lines; and backfilling to grade. All labor, equipment, materials, and disposition of items involved in the removal shall be included in the price bid for "Removal of Manholes."

203.02 CONSTRUCTION REQUIREMENTS.**Page 123****11-21-03**

The following shall be added to Section 203.02 A.:

6. **Coal.** When coal is encountered, it shall be removed to a depth of 6 feet below the final profile grade between the graded shoulders. From the graded shoulders to the top of the backslopes, it shall be removed to a depth of 1 foot below the final profile grade. All coal removed shall be paid for as Common Excavation.

203.02 CONSTRUCTION REQUIREMENTS.**Page 123****11-21-03**

The following two sentences shall be added after the first sentence of Section 203.02 B.:

... grading limits. Salvaged topsoil that is stockpiled within the clear zone must be stockpiled in a manner that is safely traversable. The stockpile must have slopes which are 4:1 or flatter if they are located within the clear zone. Additional areas ...

210.04 METHOD OF MEASUREMENT.**Page 135****11-21-03**

The following paragraph shall be added to Section 210.04 B.:

Excavation shall include Channel Excavation, Class 1 Excavation, and Class 2 Excavation unless these are specified as separate bid items.

230.02 CONSTRUCTION REQUIREMENTS.**Page 138****11-21-03**

The following two sentences shall be added after the first sentence of Section 230.02 A.4.:

... the Engineer. Salvaged topsoil that is stockpiled within the clear zone must be stockpiled in a manner that is safely traversable. The stockpile must have slopes which are 4:1 or flatter if they are located within the clear zone. Topsoil shall ...

230.03 METHOD OF MEASUREMENT.**Page 140****09-24-04**

In the first sentence of Section 230.03 D replace the phrase "Square Yards" with "Stations".

304.04 CONSTRUCTION REQUIREMENTS.**Page 155****02-14-03**

Delete the first sentence in Section 304.04 B.2. and insert the following:

2. **Compaction.** Compaction of the permeable base shall be according to Section 302.04 D. except the roller shall be a 10 ton, double drum, steel wheeled roller.

306.04 CONSTRUCTION REQUIREMENTS.**Page 160****02-14-03**

Delete the second sentence of Section 306.04 H. in its entirety and insert the following:

The surface shall be finished using a Surface Tolerance Type B as specified in Section 302.04 F.

401.05 METHOD OF MEASUREMENT.

Page 173

05-16-03

Delete paragraph C. of Section 401.05 in its entirety.

401.06 BASIS OF PAYMENT.

Page 173

05-16-03

Delete the Pay Item Water in Section 401.06 in its entirety.

408.04 CONSTRUCTION REQUIREMENTS.

Page 192

03-14-03

09-24-04

Section 408.04 B., add the following sentence at the end of the second paragraph (Currently beginning "The Contractor will provide..."):

Regardless of who is preparing the mix design, the Contractor shall provide the Department with the bitumen, aggregate and blend portions for the mix design, a minimum of 7 days before production begins.

408.04 CONSTRUCTION REQUIREMENTS.

Page 192

03-14-03

Delete footnote 3 of the mix design table in Section 408.04 B., in its entirety and insert the following:

The mix design will be approved if the laboratory mix meets one of the three properties, % VMA, Fines/Asphalt Ratio, Film Thickness and all of the other specified properties.

408.06 METHOD OF MEASUREMENT.

Page 203

11-21-03

The following shall be added to Section 408.06:

- D. **Rumble Strips.** When a bid item is included in the plans, the quantity for rumble strips is determined by project length for each shoulder per mile. The quantity paid for will be the quantity shown in the Contract, provided the project is constructed as shown in the plans. A deduction in length will not be made for discontinued rumble strips across road approaches, ramps, etc. as identified in the notes in the standard drawings.

When the bid item for rumble strips is each, payment will be for all rumble strips installed at a stop intersection in one lane.

408.07 BASIS OF PAYMENT.**Page 204****04-11-03**

The following item shall be added to this section:

Pay Item	Pay Unit
Rumble Strips	Each or Mile

409.04 CONSTRUCTION REQUIREMENTS.**Page 206****03-14-03**

Delete the words "Special Provision" in line 11 of the first paragraph under Quality Control Plan in Section 409.04 and insert the word "Specification".

409.04 CONSTRUCTION REQUIREMENTS.**Page 206****09-24-04**

In section 409.04 A, add "106." after the word "section" in the first sentence. The first sentence should read "Stripping of the pit and pit operations shall be conducted according to section 106."

409.04 CONSTRUCTION REQUIREMENTS.**Page 207****03-14-03**

Delete the following sentence in lines 5 and 6 of the second paragraph of Section 409.04 A., in its entirety:

The Department will develop the mix design for the project.

409.04 CONSTRUCTION REQUIREMENTS.**Page 208****03-14-03**

Delete the statement "as revised in October 1998" in lines 3 and 4 in the first paragraph of Section 409.04 B., in there entirety.

409.04 CONSTRUCTION REQUIREMENTS.**Page 210****02-14-03**

Delete the table for the Determination of Surface Area in Section 409.04 B.2.c. and insert the following table:

Determination of Surface Area								
Sieve Analysis % Passing								
Sieve	Maximum Size	No. 4	No. 8	No. 16	No. 30	No. 50	No. 100	No. 200
Combined Grading	***	***	***	***	***	***	***	***
Coefficient	0.02	0.02	0.04	0.08	0.14	0.30	0.60	1.60

410.02 MATERIALS.**Page 222****02-14-03**

Delete Table 1 of Section 410.02 B. and insert the following:

Table 1
Initial Control Points for Superpave Aggregate Blend Gradation

Sieve Size	Nominal Aggregate Size* ½" (12.5 mm) % Passing	
	Min	Max
5/8" (15.9 mm)	100	100
½" (12.5 mm)	90	100
#8 (2.36 mm)	28	58
#200 (75 F)	2.0	7.0

*Nominal aggregate size is defined as one sieve size larger than the first sieve to retain more than 10 percent.

410.04 CONSTRUCTION REQUIREMENTS.

Page 228

02-14-03

Delete the title of Table 5 in Section 410.04 B.1. and insert the following:

TABLE 5
MIX DESIGN

410.04 CONSTRUCTION REQUIREMENTS.

Page 228

02-14-03

Delete the table for the Determination of Surface Area in Section 410.04 B.1. and insert the following table:

Determination of Surface Area

Sieve Analysis % Passing								
Sieve	Maximum Size	No. 4	No. 8	No. 16	No. 30	No. 50	No. 100	No. 200
Combined Grading	***	***	***	***	***	***	***	***
Coefficient	0.02	0.02	0.04	0.08	0.14	0.30	0.60	1.60

410.04 CONSTRUCTION REQUIREMENTS.**Page 229****02-14-03**

Delete Section 410.04 B.2.c and 410.04 B.2.d in their entirety and insert the following:

- c. 1/2% above the optimum AC content determined by the Trial Mix Design.
- d. 1.0% below the optimum AC content determined by the Trial Mix Design.

410.04 CONSTRUCTION REQUIREMENTS.**Page 232****11-21-03**

Delete the Allowable Working Ranges for Fine Aggregate Angularity and Clay Content in Table 8, Section 410.04 P.2. and replace with the following:

Fine Aggregate Angularity	Not less than the minimum specified
Clay Content	Not less than the minimum specified

410.05 ACCEPTANCE.**Page 234****11-21-03
02-20-04**

In the first sentence of the last paragraph of Section 410.05 A.1., delete "2\$" and replace with "2%".

410.05 ACCEPTANCE.**Page 236****02-14-03
03-14-03**

Delete Section 410.05 C.1.b. in its entirety and insert the following:

- b. Compact two gyratory specimens with each sample taken to determine the field gyratory density. The number of gyrations applied to the gyratory specimens shall be as specified in the plans or as specified by the Engineer, and the temperature of the mix shall be 270⁰ F plus or minus 5⁰ F; and

420.04 CONSTRUCTION REQUIREMENTS.**Page 245****02-20-04
04-16-04
09-24-04**

In Section 420.04 E., delete the last sentence (beginning "The flaggers shall provide..."), including the printed notice verbiage, from the first partial paragraph on the page and replace it with the following sentence:

Flaggers and pilot car(s) shall not be bid separately, but shall be included in the price bid for other items.

In Section 420.04 E., delete the phrase "and printed notices" from the fifth full paragraph on the page (beginning "On four-lane highways the additional...").

550.04 CONSTRUCTION REQUIREMENTS.**Page 262****11-21-03**

The following shall be added to Section 550.04 J.:

8. **Rumble Strips.** When a bid item is included in the plans, the quantity for rumble strips is measured by project length for each shoulder per mile, and paid for by plan quantity. No deduction in length will be made for discontinued rumble strips as identified in the notes in the standard drawings.

550.04 CONSTRUCTION REQUIREMENTS.**Page 265****11-21-03**

Delete the last paragraph of Section 550.04 N. in its entirety and insert the following:

When bituminous pavement or any colored concrete is applied adjacent to P.C.C. pavement, the adjacent P.C.C. pavement shall be protected from spills and smears. Discolored P.C.C. pavement shall be cleaned at the Contractor's expense. The P.C.C. pavement shall not be used to stockpile or mix any material unless approved by the Engineer.

550.04 CONSTRUCTION REQUIREMENTS.**Page 265****02-20-04
05-21-04**

Delete Section 550.04 O. in its entirety and insert the following:

- O. Opening to Traffic.** Newly constructed concrete pavement shall not be opened to public traffic until the concrete has attained a flexural strength of 550 psi or a compressive strength of 3000 psi. Specimen beams and cylinders used for testing shall be cured under the same conditions as the concrete pavement or cores may be taken from the pavement. Pavement that has not reached the required flexural and compressive strengths shall not be opened to public traffic or heavy equipment until it has aged at least 14 days. In addition to the strength requirements, the newly constructed concrete pavement shall not be opened to public traffic until all joints have been sealed. Construction traffic may be permitted on the concrete pavement when all of the following conditions have been met:
1. The strength requirements are met
 2. The initial relief cut has been made on all joints and
 3. Joint widening (or the second joint cut) has not been done on any joints, unless the widened joints have been sealed, in conformance with the final plan requirements.

550.05 METHOD OF MEASUREMENT.**Page 271****02-14-03**

Add the following to the first paragraph in Section 550.05 D.:

When separate payment is not made for Doweled Expansion or Contraction Joint Assemblies, the cost to provide and install the assemblies will be incidental to the Concrete Pavement.

550.06 BASIS OF PAYMENT.**Page 272****11-21-03**

The following item shall be added to this section:

Pay Item**Pay Unit**

570.04 CONSTRUCTION REQUIREMENTS.

Page 277

02-14-03

Delete the first paragraph in Section 570.04 A.1. and insert the following:

1. **Restoring the Subgrade.** Concrete in full depth repair areas shall be removed by lifting with adequately sized equipment that will minimize disruption to the existing subgrade. Construction equipment will not be allowed in areas where the concrete has been removed. Voids deeper than one inch beneath the removed concrete shall be filled and compacted with granular fill as directed by the Engineer.

570.04 CONSTRUCTION REQUIREMENTS.

Page 278

07-16-04

In Section 570.04 A.6.b.(2), replace all instances of the word "tiebars" with "tie bars".

570.04 CONSTRUCTION REQUIREMENTS.

Page 278

07-16-04

Add the following sentence to the end of Section 570.04 A.6.b.(2):

The price bid for full-depth repair shall include the costs for all material, equipment and labor required to make the repairs, as specified above.

570.04 CONSTRUCTION REQUIREMENTS.

Page 278

**07-18-03
11-21-03**

Delete the first two sentences of Section 570.04 A.8 and insert the following:

Shape the longitudinal joint reservoir 1/4-inch wide by 3/4-inch deep in areas of full-depth repairs. Clean the joint as directed by the Engineer and seal with a Type 2 Hot Applied Joint Sealant.

570.04 CONSTRUCTION REQUIREMENTS.

Page 281

05-21-04

In Section 570.04 C.1.e, delete Patchroc 10-60 from the first sentence.

570.04 CONSTRUCTION REQUIREMENTS.

Page 282

11-21-03

The following shall be added to Section 570.04 C.2.:

- I. **Opening to traffic.** The dowel bar retrofit portion of the project will not be opened to traffic until the surface has been ground.

570.04 CONSTRUCTION REQUIREMENTS.

Page 284

07-16-04

In Section 570.04 D.4, delete the word "Pavement" from the section title and replace it with "Payment".

602.03 CONSTRUCTION REQUIREMENTS**Page 304****02-20-04
03-26-04**

Delete the last sentence in the first paragraph of Section 602.03 F.2.c. and insert the following:

The geotextile fabric or burlap shall be kept continuously moist for 7 days or covered with a waterproof material such as polyethylene until the end of the 7 day period.

602.03 CONSTRUCTION REQUIREMENTS.**Page 305****11-21-03**

Delete the third sentence of Section 602.03 F.3. and replace with the following:

The wet cure material shall be placed and the wet cure started no later than 30 minutes after the finish of the completed area.

704.02 MATERIALS AND EQUIPMENT**Page 385****03-26-04**

Delete the letter I preceding subsection Tubular Markers and Flexible Delineators and insert the letter H. The new subsection title will be as follows:

H. Tubular Markers and Flexible Delineators.

704.02 MATERIALS AND EQUIPMENT**Page 385****03-26-04**

Delete Subsection 2 of Section 704.02 H. in its entirety and insert the following:

2. **Flexible Delineators.** The flexible delineators shall be installed in the locations shown on the plans. The posts shall be resilient and be orange in color. The delineator posts shall be made of PVC or polyethylene and shall be pre-approved for use by the Design Division. Posts currently approved are Services and Material Co. Inc., Deluxe delineator post and Safety Guide's Traf-Flex Post or Flex Stake.

The post shall have 4-inch wide white bands as shown on the plans. The reflective intensity of the bands shall meet the requirements of Type III B, Type III C, or Wide Angle Prismatic flexible reflective sheeting as provided in Section 894.02

704.03 CONSTRUCTION REQUIREMENTS.**Page 388****03-14-03**

Delete the last sentence of the second paragraph after Section 704.03 A.3 and insert the following:

The Contractor shall provide documentation showing the requirements are being met for any sign supports used that do not comply with NDDOT's Standard Drawings.

Delete Section 704.03 M. in its entirety and insert the following:

- M. Flexible Delineator Application.** The delineator base shall be attached to the pavement as shown on the plans. The contractor shall maintain the delineators until they are removed. The delineators shall be removed as soon as the new roadway is opened to traffic. The flexible delineators shall remain the property of the contractor.

If the contractor uses a two sided delineator such as Safety Guide's Flex Stake, the delineator shall have the wide side towards traffic. If the delineator is to be seen by side traffic, an additional delineator shall have the wide side placed facing the side traffic. The side traffic delineators shall not be paid for, but shall be included to the price bid for "Flexible Delineators."

If the contractor uses the butyl pad for attaching the flexible delineator to concrete roadways, the contractor shall remove the butyl pad down as close as possible to the pavement using a mechanical scraper such as a loader-type machine with a bucket.

All costs for providing, installing, maintaining, and removing the flexible delineators with butyl pad when used shall be included in the unit price bid for "Flexible Delineators."

704.03 CONSTRUCTION REQUIREMENTS.

Page 394

07-18-03
08-15-03

The following shall be added to Section 704.03 U.:

3. **Traffic Signal Maintenance.** On projects where permanent or interim traffic signals are being installed, the Contractor shall designate an experienced person in this area that can troubleshoot any possible problems that may occur with the traffic signal maintenance. This maintenance person shall be in addition to the traffic control supervisor and the watchperson as specified in Sections 704.03 U.1 and 704.03 U.2.

The traffic signal maintenance person, or experienced alternate, must be accessible to the job site within one hour of notification and be "on call" on a 24-hour basis. In the event of emergency control, refer to Section 704.03 V.

The Contractor shall be required to maintain the interim or permanent traffic signals until the project has been accepted by the Engineer.

704.03 CONSTRUCTION REQUIREMENTS.

Page 394

07-18-03
08-15-03

Delete the first sentence of Section 704.03 V. in its entirety and replace with following:

- V. **Emergency Control.** Written notification shall be provided to the Engineer, the State Police, and local law enforcement agencies, of the names, addresses, and the telephone numbers of the Contractor's Superintendent, an alternate for the superintendent, Traffic Control Supervisor, Watchperson, and Traffic Signal Maintenance Person.

704.03 CONSTRUCTION REQUIREMENTS.

Page 394

07-16-04

In Section 704.03 W., modify the first sentence of the second paragraph (currently beginning "At the time of...") to read "Except when devices are to become Department property (as indicated below), at the time

of...” and add the following as paragraph 3 of this section:

When the plans indicate that temporary traffic-control devices are to remain in place at the end of the project and become Department property, these devices shall be new upon delivery to the project and be classified acceptable upon project completion.

708.02 SEEDING, SODDING, AND MULCHING.**Page 404****09-24-04**

In Section 708.02 B.1.d, modify the Class II and Class III seed application rates to the following (varieties, species and units are to remain unchanged):

Western Wheatgrass	8
Switchgrass	4
Green Needlegrass	6
Sideoats Grama	6
Slender Wheatgrass	<u>5</u>
	29

708.02 SEEDING, SODDING, AND MULCHING.**Page 405****09-24-04**

In Section 708.02 B.1.e.(2), delete the last paragraph (beginning “The required fertilizer shall be...” in its entirety.

708.02 SEEDING, SODDING, AND MULCHING.**Page 408****09-24-04**

In Section 708.02 C.1.e.(2), delete the paragraph (the entire section following the title) in its entirety and replace it with the following:

Seed-drilling equipment meeting the requirements for Classes I, II and V seed shall be used, when Class III (Hydro-Mulch) seeding is specified. If drilling equipment cannot physically access an area (in the opinion of the Engineer) or the slope to be seeded is steeper than 3:1 (H:V), hydraulic spraying equipment capable of mixing the specified seed in water for uniform distribution may be used. In all cases, the mulch shall be applied within 24 hours following seed application, using hydraulic spray equipment capable of mixing the specified mulch in water for uniform distribution.

708.02 SEEDING, SODDING, AND MULCHING.**Page 409****09-24-04**

In Section 708.02 C.1.f, delete the last sentence (currently beginning “The fertilizer may be...” in its entirety and replace it with the following:

The fertilizer shall be mixed with the Class III (Hydro-Mulch) mulch mixture, as the mixture is applied. If the seed is applied with hydraulic spraying equipment, the fertilizer may be mixed with the seed mixture. Otherwise, as stated above, the fertilizer may not be mixed with the seed (including under Class III application).

708.02 SEEDING, SODDING, AND MULCHING.**Page 409****08-15-03**

The following shall be added to Section 708.02 C.1.h.:

Hydroseeding completed after October 1 will not be provided Temporary Care. However, hydroseeding

completed after October 1 will not be accepted until it shows evidence of established growth after May 15 of the following year.

708.07 SILT FENCE.

Page 418

**10-24-03
11-21-03
02-20-04
05-21-04**

The following Section shall be added:

708.07 SILT FENCE.

- A. **Description.** This work shall consist of furnishing, installing, maintaining, and removing a geotextile barrier-fence designed to remove suspended particles from storm water runoff. The quantities of silt fence shown on the plans may be increased or decreased as directed by the Engineer based on weather, contractor operations or actual site conditions that occur during construction of the project. Such variations in quantity will not be considered as a change in character of work. A Pre-Fabricated silt fence will not be allowed.
- B. **Materials.**
1. **Posts.** Either wood or steel posts may be used. Wood posts shall be treated (Penta or Green Treated) and shall be a minimum of 6 feet long with minimum dimensions of 2 inches diameter for round posts or 1 ½ inches by 1 ½ inches for rectangular posts. Steel posts shall be a minimum of 5 feet long, weigh a minimum of 1.3 lbs/ft and have projections to aid in fastening the wire or fabric. Steel posts should also have a metal plate welded near the bottom such that when the post is driven to the proper depth, the plate will be below the ground level for added stability.
 2. **Woven Wire.** When backing for a filter fabric silt fence is required, a steel wire fence fabric shall be used. A woven wire fence shall conform to ASTM A 116, Class 1 zinc coating for wire. The woven wire support fence shall be at least 32 inches high and a maximum opening size of 6 inches by 6 inches. The wire shall be a minimum of 14 gage grade 60.
 3. **Filter Fabric.** Silt fence fabric shall conform to AASHTO M 288 silt fence specification. Filter fabric shall be composed of fibers consisting of long chain synthetic polymers composed of at least 95% by weight of polyolefins, polyesters or polyamides. The fibers shall be formed into a network such that the filaments or yarns retain dimensional stability relative to each other. The filter fabric shall be free of any treatment or coating which might adversely alter its physical properties after installation. The fabric shall be free of defects or flaws that significantly affect its physical and/or filtering properties. The fabric shall have a minimum width of 36 inches. The filter fabric shall be furnished with suitable wrapping for protection against moisture and extended ultraviolet exposure prior to placement.
- The filter fabric shall meet the minimum physical requirements contained in Table 1. Unless otherwise indicated, numerical values represent the minimum average roll value. The required numerical value for the AOS is the maximum allowable in SI Units and the minimum allowable in U.S. Standard Sieve Numbers.

Table 1

Property		Test Method	Supported *	Unsupported
Grab Tensile Strength (lbs)		ASTM D-4632		
	Machine		90	123
	Cross Machine		90	101
Permittivity (sec ⁻¹)		ASTM D-4491	0.05	0.05
Water Flow Rate (gpm / ft ²)		ASTM D-4491	4.43	4.43
AOS (US Sieve #) mm Sieve #		ASTM D-4751	0.600 #30	0.600 #30
UV Resistance (%)		ASTM D-4355	70%@500hrs	70%@500hrs

*Silt fence support shall consist of 14 gage steel wire with a mesh maximum spacing of 6 by 6 inches.

C. Construction Requirements.

In addition to the Standard Drawing shown in the plans the following will apply:

1. **Installation.** The geotextile at the bottom of the fence shall be buried in a "J" configuration to a minimum depth of 6 inches in a trench so that no flow can pass under the silt fence. Wire support fence if used shall also be buried a minimum of 2 inches. The trench on the upstream side of the silt fence shall be backfilled and the soil compacted over the geotextile.

Silt fence fabrics shall be spliced together only at support posts with a minimum of 18 inches of overlap and in such manner to prevent silt from passing between the two ends. At the time of installation, the fabric or fence will be rejected if it has any defects, deterioration, or other damage incurred during manufacture, transportation, storage, or installation.

Posts shall be spaced 4 feet apart and driven or placed a minimum of 20 inches into the ground. Depth shall be increased to 24 inches if fence is placed on a slope 3:1 or greater. Geotextiles shall be attached to posts by staples, wire, nails, or in accordance with the manufacturer's recommendations. Wire staples shall be a No. 17 gauge minimum and shall have a minimum 0.75 in. wide crown and 0.5 in. long legs. Staples shall be evenly placed with at least 4 per post. Nails shall be a minimum of 14 gauge, 1 inch long, with 0.75 button heads. Nails shall be evenly spaced with at least 4 per post.

Silt fences should be continuous and transverse to the flow. The silt fence should follow the contours of the site as closely as possible. The fence shall also be placed such that the water cannot flow around the end of the fence.

2. **Maintenance.** Sediment deposits shall be removed when the deposit reaches half of the height of the silt fence at the lowest area or when directed by the Engineer. Silt fence shall be inspected by the Contractor immediately after each rainfall and at least daily during prolonged rainfall. Any deficiencies shall be immediately corrected. Filter fabric shall be removed and replaced whenever it has deteriorated to such extent that it reduces the effectiveness of the silt fence. In addition, the Contractor shall make daily review of the location of silt fences in areas where construction activities have changed the natural contour and drainage runoff to ensure that the silt fences are properly located for effectiveness. Where deficiencies exist,

additional silt fences may be installed as directed by the Engineer.

If a silt fence, or portion of a fence, is located in an area where removing the sediment is not possible, then a second silt fence may be installed at the discretion of the Engineer. In this case, the silt fences or portions involved, will be measured and paid for at the unit price for silt fence.

Silt fence shall remain in place until the vegetative coverage is restored to seventy percent of preexisting vegetation. Fence materials that are removed will be disposed of by the Contractor. Upon removal, the Contractor shall dress the area to give a pleasing appearance, and vegetate all bare areas in accordance with the contract requirements. If the new reshaped area still poses an erosion threat, the Engineer may require the Contractor to erect a new silt fence. If vegetative coverage is not restored to seventy percent of preexisting vegetation prior to project acceptance, the silt fence will remain in place and will be removed by NDDOT.

- D. **Method of Measurement.** Silt fence will be measured to the nearest linear foot of fence actually installed in accordance with the plans or as required by the project Engineer. The measurement for payment excludes the fabric or fence material used for overlapping as well as fabric used for seam overlaps.

Silt fence will be paid for per linear foot in place and shall be full compensation for completing the work specified.

- E. **Basis of Payment.**

Payment will be made at the Contract Unit Price for the following:

Pay Item	Pay Unit
Silt Fence Supported	Linear Foot Installed
Silt Fence Unsupported	Linear Foot Installed

This payment will be full compensation for all materials, equipment and labor to install and remove the silt fence.

Cleaning of the sediment deposits shall be paid at the price listed in the "Price Schedule PS-1."

709.03 CONSTRUCTION REQUIREMENTS.

Page 420

11-21-03

The following paragraph shall be added to Section 709.03 B.:

Geotextile fabric for wrapping the joints of pre-cast box culverts shall meet the specifications of Section 858.01 A., separation fabric Type S2.

714.03 CONSTRUCTION REQUIREMENTS.

Page 424

09-24-04

In Section 714.03, add the following as a general paragraph prior to subpart A:

If the existing drainage facilities become inoperable before the new drainage system is functioning, the contractor shall provide sufficient temporary pumping and/or drainage facilities to keep the roadway drained to the satisfaction of the engineer. The cost of providing sufficient temporary pumping and drainage shall not be bid separately but shall be included in the price bid for other items.

714.03 CONSTRUCTION REQUIREMENTS.**Page 426****09-24-04**

Add the following as 714.03 A.10:

10. **Connection to Manholes and Inlets.** If the proposed pipe or drain is to be connected to a manhole or inlet barrel, the cost of materials, equipment and labor to cut the manhole- or inlet-barrel entrance and to grout the pipe-to-barrel connections shall be incidental to other items.
-

714.04 METHOD OF MEASUREMENT.**Page 429****04-16-04**

Add "If a pay item is shown on the plans," at the beginning of the first sentence of the second paragraph of subsection **C. Underdrains.**, currently beginning "Granular Fill will be..."

714.05 BASIS OF PAYMENT.**Page 429****04-16-04**

Add "If a pay item is not shown on the plans," at the beginning of the last paragraph, currently beginning "Granular fill or trench backfill..."

720.03 CONSTRUCTION REQUIREMENTS.**Page 430****06-20-03**

The following paragraph shall be added to Section 720.03 A.:

All concrete alignment monuments shall be precast. Precast concrete alignment monuments will be furnished and placed by the Contractor on all centerline alignment PI's, section corners, quarter corners, and on section lines crossing the centerline alignment as shown on the Standard Drawings. When centerline alignment PI's are located outside the highway right of way, an iron monument (defined in the Standard Drawings) may be placed in lieu of the precast concrete alignment monuments. The precast concrete alignment monuments shall be placed on all grading projects, and all other projects where existing monuments will be disturbed. A licensed Registered Land Surveyor (including the Contractor's surveyor) must be involved in the placement and recording of all Public Land Corners (section corners and quarter corners), section line crossings, and PI monuments as required by the N.D.C.C. The costs associated with concrete monuments are to be included in the pay item "Monuments". A licensed Registered Land Surveyor is not required to be involved in the placement of the other alignment monuments, right of way markers, and right of way monuments. The price bid for "Monuments" shall include the cost of materials, installation, and the Registered Land Surveyor as required.

722.03 CONSTRUCTION REQUIREMENTS.**Page 432****09-24-04**

Add the following sentence to the end of 722.03 G:

The cost of materials, equipment and labor to make the connections shall be incidental to other items.

722.03 CONSTRUCTION REQUIREMENTS.**Page 433****09-24-04**

Add the following as 722.03 M:

- M. Maintenance of Drainage.** If the existing drainage facilities become inoperable before the new drainage system is functioning, the contractor shall provide sufficient temporary pumping and/or drainage facilities to keep the roadway drained to the satisfaction of the engineer. The cost of providing sufficient temporary pumping and drainage shall not be bid separately but shall be included in the price bid for other items.

724.03 CONSTRUCTION REQUIREMENTS**Page 436****09-24-04**

Insert the following as Section 724.03 C.8.

8. Using a method approved by the Engineer, the Contractor shall provide temporary service to properties whose services will be interrupted for more than eight (8) hours. If the Contractor intends to perform the work without providing temporary services, all affected property occupants shall be notified, in writing, at least 24-hours in advance of the service interruption. At a minimum this notice shall contain the following information:
- a. Contractor contact information
 - b. Engineer contact information (as directed by the Engineer)
 - c. When the service will be interrupted
 - d. Approximately when the service will be restored
 - e. A general description of the work being done (e.g. "a fire hydrant is being installed", "a valve is being installed", "the water main is being replaced", etc.)
- Prior to distribution, the Engineer shall approve the form and language of the notice. At the same time the property occupants are notified, a copy of the final version shall be provided to the Engineer. If any service is interrupted for more than eight (8) hours and temporary service has not been provided, the Contractor shall provide all necessary temporary services prior to continuing any other work. The cost of providing temporary water services and notifying property occupants, if required, shall be incidental to the price bid for "Water Main."

752.03 CONSTRUCTION REQUIREMENTS**Page 448****03-26-04
07-16-04**

Insert the following as Section 752.03 G.

- G. Temporary Safety Fence.** The temporary safety fence shall be four feet high, colored bright orange and constructed of a polyethylene web. The weight of a 4' X 100' roll shall be a minimum of 32 pounds. The fence shall be supported, at a minimum, by a 7-foot, 1.12-pound/foot channel steel post or an approved equal. Fencing placed across asphalt or concrete may be supported by barricades, delineator drums, or by other means approved by the Engineer. All supports used shall be capable of supporting the fence. The fence shall be securely attached to the supports and be maintained in good condition. The temporary fence installation shall be approved by the Engineer.

752.04 METHOD OF MEASUREMENT	Page 448	03-26-04
-------------------------------------	-----------------	-----------------

Delete the first sentence of the first paragraph in Section 752.04 and insert the following:

New, Temporary Safety Fence and reset fence will be measured by the Linear Foot.

752.05 BASIS OF PAYMENT	Page 449	03-26-04
--------------------------------	-----------------	-----------------

Add the following as a Pay Item to Section 752.05:

<u>Pay Item</u>	<u>Pay Unit</u>
Temporary Safety Fence	Linear Foot

754.03 CONSTRUCTION REQUIREMENTS.	Page 454	03-14-03
--	-----------------	-----------------

Remove all references to Flange Channel in Section 754.03 E.3.

754.03 CONSTRUCTION REQUIREMENTS.	Page 454	05-16-03 07-16-04
--	-----------------	------------------------------------

In Section 754.03 E.4. delete, from this section, all occurrences of the word "single".

754.03 CONSTRUCTION REQUIREMENTS.	Page 454	06-20-03
--	-----------------	-----------------

Delete the word "base" in line 3 in Section 754.03 E.4. and insert the word "foundation".

754.03 CONSTRUCTION REQUIREMENTS.	Page 454	05-16-03
--	-----------------	-----------------

Add the following sentence to Section 754.03 E.4:

Welders shall meet the requirements of Section 105.06 D.

754.03 CONSTRUCTION REQUIREMENTS.	Page 457	07-18-03
--	-----------------	-----------------

Delete the last sentence of Section 754.03 E.6.a. in its entirety.

754.03 CONSTRUCTION REQUIREMENTS.	Page 458	06-20-03
--	-----------------	-----------------

Delete Section 754.03 H. in its entirety and replace with the following:

- H. Remove Sign Foundations.** This item consists of removing signs, steel supports, and foundations or H-pile footings and restoring the surface to match the surrounding area. Foundations and H-pile footings shall be removed to a depth of 2 feet below the ground line unless otherwise specified in the plans. The signs, steel supports, H-pile footings and foundations removed shall become property of the Contractor and be disposed of outside the highway right of way.

754.04 METHOD OF MEASUREMENT.	Page 459	03-14-03
--------------------------------------	-----------------	-----------------

Remove all references to Flange Channel in Section 754.04 B.

754.04 METHOD OF MEASUREMENT.	Page 460	05-16-03
--------------------------------------	-----------------	-----------------

Delete the first line of Section 754.04 B.2 in its entirety and insert the following:

2. **Galvanized Steel Posts – Standard Pipe.** Pipe post signs will be

754.04 METHOD OF MEASUREMENT.	Page 460	07-18-03
		08-15-03

Delete the last sentence of Section 754.04 B.3 in its entirety and insert the following:

The post length and the 14 foot pile length as shown in the plans, will be included in the length of the post to be measured and paid for.

754.04 METHOD OF MEASUREMENT.	Page 461	06-20-03
--------------------------------------	-----------------	-----------------

Delete the first sentence in Section 754.04 K. in its entirety and insert the following:

- K. **Remove Sign Foundations.** The item "Remove Sign Foundations" will be measured by the number of foundations and H-piling footings removed.

754.04 METHOD OF MEASUREMENT.	Page 461	05-21-04
--------------------------------------	-----------------	-----------------

Insert the following:

- N. **Reset Mile Post.** The item "Reset Mile Post" will be measured by the number of locations at which a mile post has been reset. The quantities measured will be paid for at the contract price and shall be full compensation for all labor, equipment, and material necessary to complete the work.

754.05 BASIS OF PAYMENT.	Page 461	03-14-03
---------------------------------	-----------------	-----------------

Remove all references to Flange Channel in Section 754.05.

754.05 BASIS OF PAYMENT.	Page 461	05-16-03
---------------------------------	-----------------	-----------------

Delete the Pay Item _____ " Galvanized Steel Post – Standard Pipe (Single Post) in Section 754.05 in its entirety and insert the following:

_____ " Galvanized Steel Post – Standard Pipe

754.05 BASIS OF PAYMENT.**Page 461****05-21-04**

Insert the following item at the end of the Pay Item/Pay Unit table:

Reset Mile Post	Each
-----------------	------

762.02 MATERIALS.**Page 462****04-11-03**

Delete Section 762.02 in its entirety and replace with the following:

Pavement Marking material shall meet the following:

Item	Section
Pavement Marking Paint*	880.01
Glass Beads for Pavement Marking Paint	880.02
Plastic Pavement Marking Film*	880.03
Preformed Plastic Marking Film	880.04
Preformed Patterned Pavement Marking Film	880.05
Short-Term Pavement Marking	
Paint	880.06
Tape	880.06
Construction Zone Marking	880.07
Raised Pavement Markers	880.08
Epoxy Paint Pavement Marking	880.09

*Either "slow," "medium," or "fast dry" paint and either type of Plastic Marking Film may be used.

762.04 CONSTRUCTION REQUIREMENTS.**Page 464****02-20-04**

The following two sentences shall be added to the first paragraph of Section 762.04.C.2.

Two-way traffic shall be maintained on 2-lane roadways, and ½ of the roadway shall be open to traffic on multi-laned roadways at all times. The cost to furnish, erect, and maintain cones, signs, and barricades including the cost for flagging and shadow vehicles, shall be incidental to the cost of pavement marking.

762.04 CONSTRUCTION REQUIREMENTS.**Page 467****03-26-04**

Move Section 762.04 D 2.c. to Section 762.04 D 2.d and insert the following as the new Section 762.04 D 2.c:

- c. **Plastic Pavement Marking Film Rolled in Hot Asphalt.** The plastic pavement marking shall be rolled into the hot asphalt surface. The contractor shall arrange to have the plastic pavement markings placed on the hot asphalt in the position shown on the plans at the time of final asphalt rolling operations. The plastic pavement markings shall receive at least one rolling. The requirements not allowing installation prior to June 1 or after September 1 will not apply. The temperature of the hot asphalt pavement during application shall be as specified by the manufacturer. The cost of placing and rolling the pavement markings into the hot asphalt pavement shall be included in the price bid for the item "Plastic Pavement Marking Film Line or Message."

762.04 CONSTRUCTION REQUIREMENTS.**Page 468****03-26-04**

Delete Section 762.04 D.3 in its entirety and insert the following:

3. Preformed Patterned Pavement Marking Film.

- a. **General.** Preformed Patterned pavement marking film applied as a permanent pavement marking shall not be applied before June 1 nor after September 1 of any year. The permanent marking film shall not be applied when the pavement surface temperature is 50°F. or colder, nor shall the film be placed over painted markings. The pavement surface shall be prepared for installation as required by the manufacturer. The film shall be lap or butt spliced when required to join 2 lengths of film, and the film shall be cut at open joints or cracks in the pavement. The cut ends shall be firmly tamped in place.
- b. **Preformed Patterned Pavement Marking Film Application.** Application of preformed patterned pavement marking film shall be according to the manufacturer's recommendation.
- c. **Preformed Patterned Pavement Marking Film Rolled in Hot Asphalt.** The contractor shall provide Preformed Patterned Pavement Marking Film for longitudinal lines and messages. The preformed patterned pavement marking shall be rolled into the hot asphalt surface. The contractor shall arrange to have the preformed patterned pavement markings placed on the hot asphalt in the position shown on the plans at the time of the final rolling operations. The preformed patterned pavement markings shall be rolled at least twice. The requirements not allowing installation prior to June 1 or after September 1 will not apply. The temperature of the hot asphalt pavement during application shall be as specified by the manufacturer. The cost of placing and rolling the pavement markings into the hot asphalt pavement shall be included in the price bid for the item "Preformed Patterned Pavement Marking Line or Message."

762.04 CONSTRUCTION REQUIREMENTS.**Page 474****02-20-04**

Delete the word "above" in line 11 of Section 762.04.E.4.b.(4) and insert the word "below".

762.05 METHOD OF MEASUREMENT.**Page 475****03-14-03**

In Section 762.05 C.3. and Section 762.05 C.5., delete "Type KNURL" and replace with "Type NR".

762.06 BASIS OF PAYMENT.**Page 476****03-14-03**

Delete the Pay Item Short Term-___-Inch Line, Type KNURL in Section 762.06 and insert the following:

Short Term-___-Inch Line, Type NR

764.03 CONSTRUCTION REQUIREMENTS.**Page 480****04-16-04**

Delete Section 764.03 H in its entirety and insert the following:

- H. **Completion Requirements.** On projects where existing guardrail is to be removed or removed and replaced or reinstalled, and the roadway will be open to traffic during construction, the

guardrail installation at each site shall be completed within 10 working days from the day all other controlling items of work are sufficiently complete to allow guardrail installation to commence. A guardrail installation is defined as each individual run of guardrail (i.e., a typical bridge would have four guardrail installations). Controlling items of work for a guardrail installation include, but are not limited to: structure, structure end block, barrier, paving, guardrail and grading work (all within each individual run of guardrail).

Prior to any guardrail removal, a written construction schedule for work at the guardrail-installation area shall be developed by the Contractor and Subcontractors (if any), and reviewed by the Engineer. At a minimum, the schedule of work will include a sequence of controlling items and the timing of each. If the Contractor removes guardrail prior to the work plan being reviewed by the Engineer, the Engineer may apply the disincentives listed below. Work shall not cease at any individual guardrail installation for more than four (4) working days, between controlling items of work. Additionally, the Contractor shall give each controlling item of work the constant attention necessary to facilitate continuous progress, at each guardrail installation.

Once the existing guardrail is removed from any item of concern (e.g. bridge end, box culvert, bridge column, etc.), the Contractor shall place and maintain drums at 25-foot intervals adjacent to each location of removed guardrail. These devices shall extend 175 feet beyond the item of concern for each direction of traffic. Drums shall remain in place until new guardrail has been installed. Unless otherwise noted on the plans, drums shall be paid according to Section 704.05.

If the Contractor fails to complete the required work, at fixed objects, within the time allowed, the Contractor shall provide the "Short-Term End Treatment for Bridges" shown in the Standard Drawings. The type of treatment shall be at the option of the Contractor. The cost of furnishing and installing the Short-Term End Treatment for Bridges shall be included in the price bid for guardrail installation. If the Contractor chooses to place the guardrail end treatment, the material used for this installation shall not be reused in the final guardrail installation. The Short-Term End Treatment shall remain the property of the Contractor.

Prior to removing the existing guardrail at steep-slope or culvert-extension sites, the Contractor shall essentially complete all work except guardrail installation, if any.

If the Contractor fails to comply with all requirements of Section 764.03 H, the Department reserves the right to:

4. Suspend progressive estimate payments.
5. Apply a contract price reduction of \$300 per day, if the deficiency is not remedied within 24 hours of notification to correct such item.
6. Have the Short-Term End Treatment installed by other forces, with the costs deducted from monies due or that become due the Contractor. Materials from this installation shall become the Prime Contractor's property, upon removal, and shall not be used for the permanent installation.
7. Invoke any other disincentive allowed by the contract.

764.03 CONSTRUCTION REQUIREMENTS.**Page 480****05-21-04**

In the last paragraph of Section 764.03 I, delete the next to last sentence (beginning “The contractor shall furnish...”) and insert the following in its place:

Within fifty (50) days of contract execution by the Department, the Contractor shall furnish to the Engineer, for review, eight (8) sets of shop drawings for crash-attenuating cushion, in accordance with Section 105.08.

{Note the modifications to Section 105.08, above}

770.02 MATERIALS.**Page 7 Vol. 2****Revised 05-21-04**

In Section 770.02 B, in the first sentence (beginning “Required shop drawings...”), delete the word “approval” and insert “review” in its place.

In Section 770.02 B, in the second sentence of the second paragraph (beginning “The Engineer’s review and...”), delete the words “and approval”.

In Section 770.02 B, delete the last sentence of the second paragraph (beginning “The approved shop drawings...”), in its entirety.

770.02 MATERIALS.**Page 8 Vol. 2****05-21-04**

In Section 770.02 E, in the next to last sentence of the first paragraph (beginning “They shall contain...”), delete the word “approved” and insert “reviewed” in its place.

770.03 CONSTRUCTION REQUIREMENTS.**Page 12 Vol. 2****09-24-04**

In Section 770.03 H, add the following as paragraph 3:

The light standards shall be placed to provide the greater minimum horizontal and vertical clearances to power lines required by the National Electric Code (NEC), current addition, or as follows for the indicated power line voltages:

Power Line Voltage (V)	Horizontal Clearance (ft)	Vertical Clearance (ft)
0 - 22,000	5	6
Greater than 22,000	5 + 0.033 per kV greater than 22 kV	6 + 0.033 per kV greater than 22 kV

However, the plan light standard locations shall not be adjusted without the prior approval of the Engineer.

772.02 MATERIALS.**Page 18 Vol. 2****Revised 05-21-04**

In Section 772.02 B, in the first sentence (beginning “Required shop drawings...”), delete the word “approval” and insert “review” in its place.

In Section 772.02 B, in the second sentence of the second paragraph (beginning “The Engineer’s review

and...”), delete the words “and approval”.

In Section 772.02 B, delete the next to last sentence of the second paragraph (beginning “The approved shop drawings...”), in its entirety.

772.03 CONSTRUCTION REQUIREMENTS.**Page 21 Vol. 2****09-24-04**

In Section 772.03 B, add the following as paragraph 2:

The Concrete Foundations shall be placed to provide the greater minimum horizontal and vertical clearances between the signal standards/mast arms/appurtenances and power lines required by the National Electric Code (NEC), current addition, or as follows for the indicated power line voltages:

Power Line Voltage (V)	Horizontal Clearance (ft)	Vertical Clearance (ft)
0 - 22,000	5	6
Greater than 22,000	5 + 0.033 per kV greater than 22 kV	6 + 0.033 per kV greater than 22 kV

However, the plan Concrete Foundation locations shall not be adjusted without the prior approval of the Engineer.

772.03 CONSTRUCTION REQUIREMENTS.**Page 30, Vol. 2.****02-14-03****03-14-03**

Delete Sections 772.03 T.1, 772.03 T.2, and 772.03 T.3., and insert the following:

1. **Initial Inspection.** An initial functional inspection shall be made approximately 15 days after all signals or flashing beacons under the Contract are operational, except when snow or ice conditions are present preventing observation of installed equipment, or when extreme cold conditions prevent proper observation of equipment operations and adjustments.
 - a. When the above conditions exist, the initial inspection will be delayed. The Engineer will determine when conditions have improved so the inspection can be scheduled.
 - b. During the time of delayed inspection, all signals or flashing beacons in operation shall be maintained by the Contractor. When conditions permit initial inspection to be performed, the other inspections will be performed as specified.
2. **Final Inspection.** A final functional inspection will be made 30 or more days after the initial inspection. The Contractor will request the Engineer to schedule the final inspection. The Engineer shall notify the Traffic Operations Engineer to coordinate a time for the final inspection. The final inspection shall not be made until all items noted on the initial inspection have been corrected. Minor finish work items, such as dirt leveling, will not prevent the final inspection. The traffic signals or flashing beacons shall be in operation during this time. When snow, ice or extreme cold conditions are present preventing the proper observation of the installed equipment, the final inspection will be delayed. The Engineer will determine when the conditions have improved so the inspection can be scheduled. The Contractor shall maintain the signals or flashing beacons during the period between the initial inspection and final functional inspection.
3. **Final Acceptance.** Final acceptance will not be made until the system has been operating for 14 consecutive days after the final inspection without interruption due to malfunctions attributable to defective equipment or improper workmanship. The Contractor shall be responsible for the

electrical and communications costs for the system until the traffic signals and/or flashing beacons are accepted by the State.

802.01 DESCRIPTION.

Page 499

05-21-04

Insert the following, at the end of the first paragraph of Section 802.01 C.6:

Fly ash shall meet the requirements of Section 820.

**816.03 AGGREGATES FOR SURFACING, BASE,
ASPHALT MIXES, BLOTTER, AND SEAL COATS**

Page 510

**06-20-03
07-16-04**

Make the following changes to Table I of Section 816.03 B.:

- In Class 7 (Permeable Base), remove No. 16 sieve requirement in its entirety.
- In Class 3 and 3M (Aggregate for Subgrade Repair and for Blended Base, respectively), add a $\frac{3}{4}$ " sieve requirement of 80-100.

**816.03 AGGREGATES FOR SURFACING, BASE,
ASPHALT MIXES, BLOTTER, AND SEAL COATS**

Page 511

07-16-04

Make the following changes to Table II of Section 816.03 B.:

- In Class 27, 29, 31 and 33 (Asphalt Hot Mix Low to High Quality), revise the No. 200 sieve requirements to be 2.0–7.0.

818.02 SPECIFIC REQUIREMENTS.

Page 514

**03-14-03
05-16-03
05-21-04**

Delete Section 818.02 D.2. in its entirety (including test table) and insert the following:

2. **Modified Cationic Emulsified Asphalt.** Emulsified asphalt grades shall meet the requirements of AASHTO M 316.

818.02 SPECIFIC REQUIREMENTS.

Page 516

**05-16-03
06-20-03**

Delete the Ductility requirements from the property table in Section 818.02 E. in its entirety and replace with the following:

Property	ASTM Test	HFMS-2	HFRS-2P	HFRS-2
Ductility, 77° F., 5cm/min., cm, min.	AASHTO T-51		40	40

820.01 General.

Page 518

05-21-04

At the end of the second paragraph (beginning "Sampling and testing..."), insert " , except as described below."

Delete the third paragraph (beginning “The requirement for loss...”) and insert the following in its place:

The chemical composition of fly ash required to meet AASHTO M 295 shall be Class F (as described in Table 1 of AASHTO M 295) with the following modifications:

- The total of silicone dioxide (SiO_2) plus aluminum oxide (Al_2O_3) plus iron oxide (Fe_2O_3) shall be at least 66.0 percent by dry weight of the total fly ash composition.
- The silicon dioxide (SiO_2) shall be at least 40.0 percent by dry weight of the total fly ash composition.
- Loss on Ignition shall be no more than 2.0% maximum.
- The optional requirements of Table 2 shall be required.

In addition to the certificate described below, the Contractor shall supply fly ash test data to the Engineer in the form of a chemical and physical analysis report, prepared by an independent lab, prior to the Department proceeding with the concrete mix design. The Department may retest project samples to verify specification compliance. The Department will select an independent lab to perform verification testing and will be responsible for cost of the testing. When performed, the verification tests will be the basis of acceptance.

822.02 TESTING.

Page 520

03-14-03

The following requirements shall be added to this section:

C. Treatment Penetration.

Test	Minimum Depth	Method
Penetration	0.15 inch	DOT Procedure

D. Vapor Permeability.

Treated concrete shall retain its moisture vapor permeability as determined by the Department's test procedure.

826.02 MATERIALS

Page 523

02-20-04

Delete the Tack-Free Time test requirement in Section 826.02 B 1. Insert the following sentence after the second sentence in the first paragraph:

The silicone sealant material shall be tack free prior to opening the roadway to traffic.

834.04 PERMANENT METAL CONCRETE FORMS.	Page 532	02-14-03
---	-----------------	-----------------

Delete the paragraph in Section 834.04 in its entirety and insert the following:

Permanent metal forms for concrete floor slabs shall be of zinc-coated (galvanized) steel sheets meeting ASTM A924 with coating class of G235 according to ASTM A635.

836.04 DOWEL BARS AND TIE BARS FOR PAVEMENT JOINTS.	Page 533	08-15-03 11-21-03
--	-----------------	------------------------------

Delete the last paragraph in Section 836.04 in its entirety and insert the following:

Tie bars for the centerline joint and adjoining driving lanes in Portland Cement Concrete pavement shall be epoxy coated, meeting the requirements in 836.02 B. All other tie bars shall meet AASHTO M-31, Grade 40 deformed.

880.01 PAVEMENT MARKING PAINT.	Page 548	09-24-04
---------------------------------------	-----------------	-----------------

In Section 880.01 C., change the pigment percentage line to read as follows:

Characteristics	White	Yellow
Pigment (%)	58.0-62.0	57.0-61.0

880.09 EPOXY PAINT PAVEMENT MARKING.	Page 561	05-21-04
---	-----------------	-----------------

In Section 880.09 C., first sentence – delete the word “ASSHTO” and replace it with “AASHTO”.

894.05 POSTS AND HARDWARE FOR SIGNS.	Page 575	02-14-03
---	-----------------	-----------------

In Section 894.05 B.1., second paragraph – “Section 5” should be “Section 6” and “Section 4” should be “Section 5.”

894.05 POSTS AND HARDWARE FOR SIGNS.	Page 577	03-14-03
---	-----------------	-----------------

In Section 894.05 B.4.h.(5) delete “1/6” and insert “1/16”.

894.05 POSTS AND HARDWARE FOR SIGNS.	Page 577	03-14-03
---	-----------------	-----------------

Delete all references to Flange Channel in Section 894.05 B.5. and 894.05 B.5.a.

894.06 DELINEATORS.**Page 579****02-14-03**

Delete the table in Section 894.06 B.2.c. and insert the following:

OBSERVATION ANGLE degrees	ENTRANCE ANGLE degrees	COEFFICIENT OF LUMINOUS INTENSITY cd/lx		
		CRYSTAL	YELLOW	RED
0.1	0	11.0	6.6	2.7
0.1	20	4.4	2.6	1.0

895.03 CONDUCTORS.**Page 44, Vol. 2.****02-14-03**

Delete the last two sentences of Section 895.03 B.2.a.

895.06 LIGHTING STANDARDS.**Page 46, Vol. 2.****11-21-03**

Delete the last sentence of Section 895.06 F. and replace with the following:

The outlet box shall be welded inside of the pole, and the outlet cover shall be a water tight while-in-use cover. The festoon receptacle shall be provided with a single gang while-in-use cover. The body and plates shall be made of gray colored polycarbonate, with a gasket made of closed cell foam, neoprene blend regular density, UL rated HBF. Covers shall be mounted vertically with stainless steel screws. The cover shall comply with NEC requirements for installation in wet locations.

896.07 TRAFFIC CONTROL STANDARDS.**Page 64, Vol. 2.****03-14-03**

In Section 896.07 B.1, first sentence – delete “AASHTO M-183” and replace with “ASTM A-36”.

INDEX.**Page 591.****05-21-04**

Add “Dowel Bar Retrofit.....280”.
