

?

This is a special text character used in the labeling of existing features. It indicates a feature that has an unknown characteristic, potentially based on: lack of description, location accuracy or purpose.

Abn abandoned  
Abut abutment  
Ac acres  
Adj adjusted  
Aggr aggregate  
Ahd ahead  
ARV air release valve  
Align alignment  
Al alley  
Alt alternate  
Alum aluminum  
ADA Americans with Disabilities Act  
A ampere  
& and  
Appr approach  
Approx approximate  
ACP asbestos cement pipe  
Asph asphalt  
AC asphalt cement  
Assmd assumed  
@ at  
Atten attenuation  
ATR automatic traffic recorder  
Ave Avenue  
Avg average  
ADT average daily traffic  
Az azimuth  
Bk back  
BF back face  
Bs backsight  
Balc balcony  
B Wire barbed wire  
Barr barricade  
Btry battery  
Brg bearing  
BI beehive inlet  
Beg begin  
BG below grade  
BM bench mark  
Bkwy bikeway  
Bit bituminous  
Blk block  
Bd Ft board feet  
BH bore hole  
BS both sides  
Bot bottom  
Blvd Boulevard  
Bndry boundary  
BC brass cap  
Brkwy breakaway  
Br bridge

Bldg building  
BV butterfly valve  
Byp bypass  
C Gdrl cable guardrail  
Calc calculate  
Cd candela  
CIP cast iron pipe  
CB catch basin  
CRS cationic rapid setting  
C Gd cattle guard  
C To C center to center  
Cl or  $\text{C}$  centerline  
Cm centimeter  
Ch chain  
Chnlk chain-link  
Ch Blk channel block  
Ch Ch channel change  
Chk check  
Chsld chiseled  
Cir circle  
Cl class  
Cl clay  
Cl F clay fill  
Cl Hvy clay heavy  
Cl Lm clay loam  
CInt clean-out  
Clr clear  
Cl&gr clearing & grubbing  
Co S coal slack  
C Gr coarse gravel  
CS coarse sand  
Comb. combination  
Coml commercial  
Compr compression  
CADD computer aided drafting & design  
Conc concrete  
CECB concrete erosion control blanket  
Cond conductor  
Const construction  
Cont continuous  
CSB continuous split barrel sample  
Contr contraction  
Contr contractor  
CP control point  
Coord coordinate  
Cor corner  
Corr corrected  
CAES corrugated aluminum end section  
CAP corrugated aluminum pipe  
CMES corrugated metal end section  
CMP corrugated metal pipe  
CPVCP corrugated poly-vinyl chloride pipe  
CSES corrugated steel end section  
CSFES corrugated steel flared end section

CSP corrugated steel pipe  
CSTES corrugated steel traversable end section  
C coulomb  
Co County  
Crse course  
Ct Court  
Xarm cross arm  
Xbuck cross buck  
Xsec cross sections  
Xing crossing  
Xrd Crossroad  
Cm crown  
CF cubic feet  
M3 cubic meter  
M3/s cubic meters per second  
CY cubic yard  
Cy/mi cubic yards per mile  
Culv culvert  
C&G curb & gutter  
CI curb inlet  
CR curb ramp  
CS curve to spiral  
C cut  
Dd Ld dead load  
Defl deflection  
Defm deformed  
Deg or D degree  
DInt delineate  
DIntr delineator  
Depr depression  
Desc description  
Det detail  
DWP detectable warning panel  
Dtr detour  
Dia or  $\varnothing$  diameter  
Dir direction  
Dist distance  
DM disturbed material  
DB ditch block  
DG ditch grade  
Dbl double  
Dn down  
Dwg drawing  
Dr drive  
Drwy driveway  
DI drop inlet  
D dry density  
DSDS dynamic speed display sign  
Ea each  
Esmt easement  
E East  
EB Eastbound  
Elast elastomeric  
EL electric locker  
E Mtr electric meter  
Elec electric/al

EDM electronic distance meter  
Elev or El elevation  
Ellipt elliptical  
Emb embankment  
Emuls emulsion/emulsified  
ES end section  
Engr engineer  
ESS environmental sensor station  
Eq equal  
Eq equation  
Evgr evergreen  
Exc excavation  
Exst existing  
Exp expansion  
Expy Expressway  
E external of curve  
Extru extruded  
FOS factor of safety  
F Fahrenheit  
FS far side  
F farad  
Fed Federal  
FP feed point  
Ft feet/foot  
Fn fence  
Fn P fence post  
FO fiber optic  
FB field book  
FD field drive  
F fill  
FAA fine aggregate angularity  
FS fine sand  
FH fire hydrant  
Fl flange  
Flrd flared  
FES flared end section  
F Bcn flashing beacon  
FA flight auger sample  
FL flow line  
Ftg footing  
FM force main  
Fs foresight

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
04-23-18 09-20-18	General Revisions General Revisions

This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930 , on 09/20/18 and the original document is stored at the North Dakota Department of Transportation



NDDOT ABBREVIATIONS

D-101-2

Fnd	found	ID	inside diameter	Mkg	marking	PMT	pad mounted transformer
Fdn	foundation	Inst	instrument	MA	mast arm	Pg	pages
Frac	fractional	Intchg	interchange	Matl	material	Pntd	painted
Frwy	freeway	Intmdt	intermediate	Max	maximum	Pr	pair
Frt	front	Intscn	intersection	MC	meander corner	Pnl	panel
FF	front face	Inv	invert	Meas	measure	Pk	park
F Disp	fuel dispenser	IM	iron monument	Mdn	median	PK	Parker-Kalon nail
FFP	fuel filler pipes	I Pn	Iron Pin	MD	median drain	Pa	pascal
FLS	fuel leak sensor	IP	iron Pipe	MC	medium curing	PSD	passing sight distance
Furn	furnish/ed	Jt	joint	M	mega	Pvmt	pavement
Gal	gallon	J	joule	Mer	meridian	Ped	pedestal
Galv	galvanized	Jct	junction	M	meter	Ped	pedestrian
Gar	garage	K	kelvin	M/s	meters per second	PPP	pedestrian pushbutton post
Gs L	gas line	Kn	kilo newton	M	mid ordinate of curve	Pen.	penetration
G Reg	gas line regulator	Kpa	kilo pascal	MGS	Midwest Guardrail System	Perf	perforated
GMV	gas main valve	Kg	kilogram	Mi	mile	Per.	perimeter
G Mtr	gas meter	Kg/m3	kilogram per cubic meter	MM	mile marker	PL	pipeline
GSV	gas service valve	Km	kilometer	MP	mile post	PI	place
GVP	gas vent pipe	K	Kip(s)	MI	milliliter	P&P	plan & profile
GV	gate valve	LS	Land Surveyor (licensed)	Mm	millimeter	PL	plastic limit
Ga	gauge	LSIT	Land Surveyor In Training	Mm/hr	millimeters per hour	P Cap	plastic cap
Geod	geodetic	Ln	lane	Min	minimum	PI or $\overline{P}$	plate
GIS	Geographical Information System	Lg	large	Misc	miscellaneous	Pt	point
G	giga	Lat	latitude	Mon	monument	PCC	point of compound curve
GPS	Global Positioning System	Lt	left	Mnd	mound	PC	point of curve
Gov	government	L	length of curve	Mtbl	mountable	PI	point of intersection
Grd	graded/grade	Lens	lenses	Mtd	mounted	PRC	point of reverse curvature
Gr	gravel	Lvl	level	Mtg	mounting	PT	point of tangent
Grnd	ground	LB	level book	Mk	muck	POC	point on curve
GWM	ground water monitor	Lvng	leveling	Mun	municipal	POT	point on tangent
Gdrl	guardrail	Lht	light	N	nano	PE	polyethylene
Gtr	gutter	LP	light pole	NGS	National Geodetic Survey	PVC	polyvinyl chloride
H Plg	H piling	Ltg	lighting	NS	near side	PCC	Portland Cement concrete
Hdwl	headwall	Lig Co	lignite coal	Neop	neoprene	Lb or #	pounds
Ha	hectare	Lig Sl	lignite slack	Ntwk	network	PP	power pole
Ht	height	LF	linear foot	N	newton	Preempt	preemption
HI	height of instrument	Liq	liquid	N	North	Prefab	prefabricated
Hel	helical	LL	liquid limit	NE	North East	Prfmd or Pref	preformed
H	henry	L	litre	NW	North West	Prep	preperation
Hz	hertz	Lm	loam	NB	Northbound	Press.	pressure
HDPE	high density polyethylene	Loc	location	No. or #	number		
HM	high mast	LC	long chord	Obsc	obscure(d)		
HP	high pressure	Long.	longitude	Obsn	observation		
HPS	high pressure sodium	Lp	loop	Ocpd	occupied		
Hwy	highway	LD	loop detector	Ocpy	occupy		
Hor	horizontal	Lm	lumen	Off Loc	office location		
HBP	hot bituminous pavement	Lum	luminaire	O/s	offset		
HMA	hot mix asphalt	L Sum	lump sum	OC	on center		
Hr	hour(s)	Lx	lux	C	one dimensional consolidation		
Hyd	hydrant	Mb	mailbox	OC	organic content		
Ph	hydrogen ion content	ML	main line	Orig	original		
Id	identification	M Hr	man hour	O To O	out to out		
In or "	inch	MH	manhole	OD	outside diameter		
Incl	inclinometer tube	Mkd	marked	OH	overhead		
IMH	inlet manhole	Mkr	marker				

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
08-03-15 04-23-18	General Revisions General Revisions

This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930 , on 04/23/18 and the original document is stored at the North Dakota Department of Transportation



NDDOT ABBREVIATIONS

D-101-3

PRV	pressure relief valve	Sc	scoria	St	street	Vert	vertical
Prestr	prestressed	Sec	seconds	SPP	structural plate pipe	VC	vertical curve
Pvt	private	Sec	section	SPPA	structural plate pipe arch	VCP	vitrified clay pipe
PD	private drive	SL	section line	Str	structure	V	volt
Prod.	production/produce	Sep	separation	Subd	subdivision	Vol	volume
Prog	programmed	Seq	sequence	Sub	subgrade	Wkwy	walkway
Prop.	property	Serv	service	Sub Prep	subgrade preperation	W	water content
Prop Ln	property line	Sh	shale	Ss	subsoil	WGV	water gate valve
Ppsd	proposed	Sht	sheet	SE	superelevation	WL	water line
PB	pull box	Shtng	sheeting	SS	supplement specification	WM	water main
Qty	quantity	Shldr	shoulder	Supp	supplemental	WMV	water main valve
Qtr	quarter	Sw or Sdwk	sidewalk	Surf	surfacing	W Mtr	water meter
Rad or R	radius	S	siemens	Surv	survey	WSV	water service valve
RR	railroad	SD	sight distance	Sym	symmetrical	WW	water well
Rlwy	railway	SN	sign number	SI	systems international	W	watt
Rsd	raised	Sig	signal	Tan	tangent	Wrng	wearing
RTP	random traverse point	Si Cl	silt clay	T	tangent (semi)	Wb	weber
Rge or R	range	Si Cl Lm	silty clay loam	TS	tangent to spiral	WIM	weigh in motion
RC	rapid curing	Si Lm	silty loam	Tel	telephone	W	west
Rec	record	Sgl	single	Tel B	Telephone Booth	WB	westbound
Rcy	recycle	SRCP	slotted reinforced concrete pipe	Tel P	telephone pole	Wrng	wiring
RAP	recycled asphalt pavement	SC	slow curing	Tv	television	W/	with
RPCC	recycled portland cement concrete	SS	slow setting	Temp	temperature	W/o	without
Ref	reference	Sm	small	Temp	temporary	WC	witness corner
R Mkr	reference marker	S	South	TBM	temporary bench mark	WGS	world geodetic system
RM	reference monument	SE	South East	T	tesla	Z	zenith
RP	reference point	SW	South West	T	thinwall tube sample		
Refl	reflectorized	SB	Southbound	T/mi	tons per mile		
RCB	reinforced concrete box	Sp	spaces	Ts	topsoil		
RCES	reinforced concrete end section	Spcl	special	Twp or T	township		
RCFES	reinforced concrete flared end section	SA	special assembly	Traf	traffic		
RCTES	reinforced concrete traversable end section	SP	special provisions	TSCB	traffic signal control box		
RCP	reinforced concrete pipe	G	specific gravity	Tr	trail		
RCPS	reinforced concrete pipe sewer	Spk	spike	Transf	transformer		
Reinf	reinforcement	SC	spiral to curve	TB	transit book		
Res	reservation	ST	spiral to tangent	Trans	transition		
Rs	residence	SB	split barrel sample	TT	transmission tower		
Ret	retaining	SH	sprinkler head	TES	traversable end section		
Rev	reverse	SV	sprinkler valve	Trans	transverse		
Rt	right	Sq	square	Trav	traverse		
R/W	right of way	SF	square feet	TP	traverse point		
Riv	river	Km2	square kilometer	Trtd	treated		
Rd	road	M2	square meter	Trmt	treatment		
Rdbd	road bed	SY	square yard	Qc	triaxial compression		
Rdwy	roadway	Stk	stake	TERO	tribal employment rights ordinance		
RWIS	roadway weather information system	Std	standard	Tpl	triple		
Rk	rock	N	standard penetration test	TP	turning point		
Rt	route	Std Specs	standard specifications	Typ	typical		
Salv	salvage(d)	Sta	station	Qu	unconfined compressive strength		
Sd	sand	Sta Yd	station yards	Ugrnd	underground		
Sdy Cl	sandy clay	Stm L	steam line	USC&G	US Coast & Geodetic Survey		
Sdy Cl Lm	sandy clay loam	SEC	steel encased concrete	USGS	US Geologic Survey		
Sdy Fl	sandy fill	SMA	stone matrix asphalt	Util	utility		
Sdy Lm	sandy loam	SSD	stopping sight distance	VG	valley gutter		
San	sanitary sewer line	SD	storm drain	Vap	vapor		

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
08-03-15 04-23-18	General Revisions General Revisions

This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930 , on 04/23/18 and the original document is stored at the North Dakota Department of Transportation



NDDOT UTILITY COMPANY AND ORGANIZATION ABBREVIATIONS

D-101-10

702COM	702 Communications	GT PLNS NAT GAS	Great Plains Natural Gas Company	RED RIV TEL	Red River Rural Telephone
ACCENT	Accent Communications	HALS TEL	Halstad Telephone Company	RESVTN TEL	Reservation Telephone
AGASSIZ WU	Agassiz Water Users Incorporated	IDEA1	Idea1	ROBRTS TEL	Roberts Company Telephone
AGC	Associated General Contractors of America	INT-COMM TEL	Inter-Community Telephone Company	R-RIDER ELEC	Roughrider Electric Cooperative
All PI	Alliance Pipeline	KANEB PL	Kaneb Pipeline Company	RRVW	Red River Valley & Western Railroad
ALL SEAS WU	All Seasons Water Users Association	KEM ELEC	Kem Electric Cooperative Incorporated	S CENT REG WD	South Central Regional Water District
AMOCO PI	Amoco Pipeline Company	KOCH GATH SYS	Koch Gathering Systems Incorporated	S E W U	South East Water Users Incorporated
AMRDA HESS	Amerada Hess Corporation	LKHD PL	Lakehead Pipeline Company	SCOTT CABLE	Scott Cable Television Dickinson
AT&T	AT&T Corporation	LNGDN RWU	Langdon Rural Water Users Incorporated	SHERDN ELEC	Sheridan Electric Cooperative
B PAW	Bear Paw Energy Incorporated	LWR YELL R ELEC	Lower Yellowstone Rural Electric	SHEYN VLY ELEC	Sheyenne Valley Electric Cooperative
BAKER ELEC	Baker Electric	MCKNZ CON	McKenzie Consolidated Telcom	SKYTECH	Skyland Technologies Incorporated
BASIN ELEC	Basin Electric Cooperative Incorporated	MCKNZ ELEC	McKenzie Electric Cooperative	SLOPE ELEC	Slope Electric Cooperative Incorporated
BEK TEL	Bek Communications Cooperative	MCKNZ WRD	McKenzie County Water Resource District	SOURIS RIV TELCOM	Souris River Telecommunications
BELLE PL	Belle Fourche Pipeline Company	MCLEOD	McLeod USA	ST WAT COMM	State Water Commission
BLM	Bureau of Land Management	MCLN ELEC	McLean Electric Cooperative	STATE LN WATER	State Line Water Cooperative
BNSF	Burlington Northern Santa Fe Railway	MCLN-SHRDN R WAT	McLean-Sheridan Rural Water	STER ENG	Sterling Energy
BOEING	Boeing	MDU	Montana-dakota Utilities	STUT RWU	Stutsman Rural Water Users
BRNS RWD	Barnes Rural Water District	MID-CONT CABLE	Mid-Continent Cable	SW PL PRJ	Southwest Pipeline Project
BURK-DIV ELEC	Burke-Divide Electric Cooperative	MIDSTATE TEL	Midstate Telephone Company	T M C	Turtle Mountain Communications
BURL WU	Burleigh Water Users	MINOT CABLE	Minot Cable Television	TCI	TCI of North Dakota
Cable One	Cable One	MINOT TEL	Minot Telephone Company	TESORO HGH PLNS PL	Tesoro High Plains Pipeline
CABLE SERV	Cable Services	MISS VALL COMM	Missouri Valley Communications	TRI-CNTY WU	Tri-County Water Users Incorporated
CAP ELEC	Capital Electric Cooperative Incorporat	MISS W W S	Missouri West Water System	TRL CO RWU	Traill County Rural Water Users
CASS CO ELEC	Cass County Electric Cooperative	MNKOTA PWR	Minnkota Power	UNTD TEL	United Telephone
CASS RWU	Cass Rural Water Users Incorporated	MOR-GRAN-SOU ELEC	Mor-gran-sou Electric Cooperative	UPPR SOUR WUA	Upper Souris Water Users Association
CAV ELEC	Cavalier Rural Electric Cooperative	MOUNT-WILLI ELEC	Mountrail-williams Electric Cooperative	US SPRINT	U.S. Sprint
CBLCOM	Cablecom Of Fargo	MRE LBTY TEL	Moore & Liberty Telephone	USAF MSL CABLE	U.S.A.F. Missile Cable
CENEX PL	Cenex Pipeline	MUNICIPAL	City Water And Sewer	USFWS	US Fish and Wildlife Service
CENT PL WATER DIST	Central Pipe Line Water District	MUNICIPAL	City Of '.....'	USW COMM	U.S. West Communications
CENT PWR ELEC	Central Power Electric Cooperative	N CENT ELEC	North Central Electric Cooperative	VRNDRY ELEC	Verendrye Electric Cooperative
COE	Corps of Engineers	N VALL W DIST	North Valley Water District	W RIV TEL	West River Telephone Incorporated
CONS TEL	Consolidated Telephone	ND PKS & REC	North Dakota Parks And Recreation	WEB	W. E. B. Water Development Association
CONT RES	Continental Resource Inc	ND TEL	North Dakota Telephone Company	WILLI RWA	Williams Rural Water Association
CPR	Canadian Pacific Railway	NDDOT	North Dakota Department of Transportation	WILSTN BAS PL	Williston Basin Interstate Pipeline Company
D O E	Department Of Energy	NDSU SOIL SCI DEPT	NDSU Soil Science Department	WLSH RWD	Walsh Water Rural Water District
DAK CARR	Dakota Carrier Network	NEMONT TEL	Nemont Telephone	WOLVRTN TEL	Wolverton Telephone
DAK CENT TEL	Dakota Central Telephone	NODAK R ELEC	Nodak Rural Electric Cooperative	XLENER	Xcel Energy
DAK RWD	Dakota Rural Water District	NOON FRMS TEL	Noonan Farmers Telephone Company	YSVR	Yellowstone Valley Railroad
DGC	Dakota Gasification Company	NPR	Northern Plains Railroad		
DICKEY R NET	Dickey Rural Networks	NSP	Northern States Power		
DICKEY RWU	Dickey Rural Water Users Association	NTH PRAIR RW	Northern Prairie Rural Water Association		
DICKEY TEL	Dickey Telephone	NTHN BRDR PL	Northern Border Pipeline		
DNRR	Dakota Northern Railroad	NTHN PLNS ELEC	Northern Plains Electric Cooperative Incorporated		
DOME PL	Dome Pipeline Company	NTHWSTRN REF	Northwestern Refinery Company		
DVELEC	Dakota Valley Electric Cooperative	NW COMM	Northwest Communication Cooperation		
DVMW	Dakota, Missouri Valley & Western	NWRWD	Northwest Rural Water District		
ENBRDG	Enbridge Pipelines Incorporated	ONEOK	Oneok gas		
ENVENTIS	Enventis Telephone	OSHA	Occupational Safety and Health Administration		
FALK MNG	Falkirk Mining Company	OTTR TL PWR	Otter Tail Power Company		
FHWA	Federal Highway Administration	P L E M	Prairielands Energy Marketing		
G FKS-TRL WD	Grand Forks-trail Water District	POLAR COM	Polar Communications		
GETTY TRD & TRAN	Getty Trading & Transportation	PVT ELEC	Private Electric		
GLDN W ELEC	Golden West Electric Cooperative	QWEST	Qwest Communications		
GRGS CO TEL	Griggs County Telephone	R&T W SUPPLY	R & T Water Supply Association		
GTR RAMSEY WD	Greater Ramsey Water District				

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
04-23-18 09-20-18	General Revisions General Revisions

This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930 , on 09/20/18 and the original document is stored at the North Dakota Department of Transportation



Existing Topography

	Existing Ground Void
	Existing Cemetary Boundary
	Existing Box Culvert Bridge
	Existing Concrete Surface
	Existing Drainage Structure
	Existing Gravel Surface
	Existing Riprap
	Existing Dirt Surface
	Existing Asphalt Surface
	Existing Tie Point Line
	Existing Railroad Centerline
	Existing Guardrail Cable
	Existing Guardrail Metal
	Existing Edge of Water
	Existing Fence
	Existing Railroad
	Existing Field Line
	Exst Flow
	Existing Curb
	Existing Valley Gutter
	Existing Driveway Gutter
	Existing Curb and Gutter
	Existing Mountable Curb and Gutter

	Existing 3-Cable w Posts
	Site Boundary
	Existing Berm, Dike, Pit, or Earth Dam
	Existing Ditch Block
	Existing Tree Boundary
	Existing Brush or Shrub Boundary
	Existing Retaining Wall
	Existing Planter or Wall
	Existing W-Beam Guardrail with Posts
	Existing Railroad Switch
	Gravel Pit - Borrow Area
	Existing Wet Area-Vegetation Break

Proposed Topography

	3-Cable w Posts
	Flow
	Fence
	Remove Line
	Wall
	Retaining Wall (Plan View)
	W-Beam w Posts

Existing Utilities

	Existing Electrical
	Existing Fiber Optic Line
	Existing TV Fiber Optic
	Existing Gas Pipe
	Existing Overhead Utility Line
	Existing Power
	Existing Fuel Pipeline
	Existing Undefined Above Ground Pipe Line
	Existing Sanitary Sewer
	Existing Sanitary Force Main
	Existing Storm Drain
	Existing Storm Drain Force Main
	Existing Culvert
	Existing Telephone Line
	Existing TV Line
	Existing Water or Steam Line
	Existing Under Drain
	Existing Slotted Drain
	Existing Conduit
	Existing Conductor
	Existing Down Guy Wire Down Guy
	Existing Underground Vault or Lift Station

Proposed Utilities

	24 Inch Pipe
	Reinforced Concrete Pipe
	Under Drain
	Edge Drain

Traffic Utilities

	Conductor
	Fiber Optic
	Existing Loop Detector
	Existing Double Micro Loop Detector
	Micro Loop Detector Double
	Existing Micro Loop Detector
	Micro Loop Detector
	Signal Head with Mast Arm
	Existing Signal Head with Mast Arm

Sign Structures

	Existing Overhead Sign Structure
	Existing Overhead Sign Structure Cantilever
	Overhead Sign Structure Cantilever














NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
09-23-16	Added and Revised Items, Organized by Functional Groups

This document was originally issued and sealed by  
Roger Weigel,  
Registration Number  
PE-2930,  
on 09/23/16 and the original document is stored at the  
North Dakota Department  
of Transportation












Line Styles









Right Of Way

	Easement
	Existing Easement
	Right of Way
	Existing Right of Way
	Existing Right of Way Railroad
	Existing Right of Way Not State Owned
	Existing Government Lot Line
	Existing Adjacent Block Lines
	Existing Adjacent Lot Lines
	Existing Adjacent Property Line
	Existing Adjacent Subdivision Lines
	Sight Distance Triangle Line
	Dimension Leader








Boundary Control

	Existing City Corporate Limits or Reservation Boundary
	Existing State or International Line
	Existing Township
	Existing County
	Existing Section Line
	Existing Quarter Section Line
	Existing Sixteenth Section Line
	Existing Centerline
	Tangent Line



Cross Sections and Typicals

	Existing Ground
	Existing Topsoil (Cross Section View)
	Existing Ground Void (Not Surveyed)
	Existing Concrete
	Existing Aggregate (Cross Section View)
	Existing Curb and Gutter (Cross Section View)
	Existing Asphalt (Cross Section View)
	Existing Reinforcement Rebar



Geotechnical

	Geotextile Fabric Type D
	Geogrid
	Geotextile Fabric Type R
	Geotextile Fabric Type R1
	Geotextile Fabric Type RR
	Geotextile Fabric Type S
	Subgrade Reinforcement







Countours

	Depression Contours
	Supplemental Contour





Profile

	Subgrade, Subcut or Ditch Grade
	Topsoil Profile










Striping

	Centerline Pavement Marking
	Barrier with Centerline Pavement Marking
	Barrier Pavement Marking
	Stripe 4 IN Dotted Extension White
	Stripe 8 IN Dotted Extension White
	Stripe 8 IN Lane Drop








Pavement Joints

	Doweled Joint
	Tie Bar 30 Inch 4 Foot Center to Center
	Tie Bar 18 Inch 3 Foot Center to Center
	Tie Bar at Random Spacing






Bridge Details

	Hidden Object
	Small Hidden Object
	Large Hidden Object
	Phantom Object
	Centerline Main
	Centerline
	Existing Ground (Details)
	Existing Conditions
	Sheet Piling

Erosion Control

	Limits of Const Transition Line
	Bale Check
	Rock Check
	Floating Silt Curtain
	Silt Fence
	Excavation Limits
	Fiber Rolls

Environmental
































































































	Wetland Mitigation
	Existing Wetland Easement USFWS
	Existing Wetland Jurisdictional
	Existing Wetland
	Tree Row

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE
09-23-16	Added and Revised Items, Organized by Functional Groups

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930 , on 09/23/16 and the original document is stored at the North Dakota Department of Transportation























































































Symbols

	North Arrow (Half Scale)		Attenuation Device		Existing Railroad Battery Box		Existing Delineator Type E														
	Truck Mounted Attenuator		Diamond Grade Delineator Type A		Existing Bush or Shrub		Existing EFB Misc														
	Type I Barricade		Diamond Grade Delineator Type B		Existing Gas Cap or Stub		Existing Flashing Beacon														
	Type II Barricade		Diamond Grade Delineator Type C		Existing Sanitary Cap or Stub		Existing Pipe Mounted Flasher														
	Type III Barricade		Diamond Grade Delineator Type D		Existing Storm Drain Cap or Stub		Existing Pad Mounted Feed Point														
	Catch Basin		Diamond Grade Delineator Type E		Existing Water Cap or Stub		Existing Pipe Mounted Feed Point with Pad														
	Caim or Stone Circle		Flexible Delineator		Existing Sanitary Cleanout		Existing Pole Mounted Feed Point														
	Video Detection Camera		Flexible Delineator Type A		Existing Concrete Foundation		Existing Railroad Frog														
	Storm Drain Cap or Stub		Flexible Delineator Type B		Existing Traffic Signal Controller		Existing Snow Gate 18														
	Corrugated Metal End Section 18 Inch		Flexible Delineator Type C		Existing Pad Mounted Signal Controller		Existing Snow Gate 28														
	Corrugated Metal End Section 24 Inch		Flexible Delineator Type D		Existing Sixteenth Section Corner		Existing Snow Gate 40														
	Corrugated Metal End Section 30 Inch		Flexible Delineator Type E		Existing Quarter Section Corner		Existing Headwall														
	Corrugated Metal End Section 36 Inch		Delineator Type A		Existing Section Corner		Existing Pedestrian Head with Number														
	Corrugated Metal End Section 42 Inch		Delineator Type A Reset		Existing Railroad Crossbuck		Existing Signal Head														
	Corrugated Metal End Section 48 Inch		Delineator Type B		Existing Satellite Dish		Existing Sprinkler Head														
	Concrete Foundation		Delineator Type B Reset		Existing Fuel Dispensers		Existing Fire Hydrant														
	Ground Connection Conductor		Delineator Type C		Existing Flexible Delineator Type A		Existing Catch Basin Drop Inlet														
	Neutral Connection Conductor		Delineator Type D		Existing Flexible Delineator Type B		Existing Curb Inlet														
	Phase 1 Connection Conductor		Delineator Type E		Existing Flexible Delineator Type C		Existing Manhole Inlet														
	Phase 2 Connection Conductor		Delineator Drums		Existing Flexible Delineator Type D		Existing Junction Box														
	Traffic Cone		Spot Elevation		Existing Flexible Delineator Type E	<table><tr><th colspan="2">NORTH DAKOTA DEPARTMENT OF TRANSPORTATION</th></tr><tr><th colspan="2">07-01-14</th></tr><tr><th colspan="2">REVISIONS</th></tr><tr><th>DATE</th><th>CHANGE</th></tr><tr><td></td><td></td></tr><tr><td></td><td></td></tr><tr><td></td><td></td></tr></table> <div>This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930 , on 07/01/14 and the original document is stored at the North Dakota Department of Transportation</div>		NORTH DAKOTA DEPARTMENT OF TRANSPORTATION		07-01-14		REVISIONS		DATE	CHANGE						
NORTH DAKOTA DEPARTMENT OF TRANSPORTATION																					
07-01-14																					
REVISIONS																					
DATE	CHANGE																				
	Signal Controller		Existing Access Control Arrow		Existing Delineator Type A																
	Pad Mounted Signal Controller		Existing Artifact		Existing Delineator Type B																
	Alignment Data Point		Existing Flashing Beacon		Existing Delineator Type C																
	Emergency Vehicle Detector		Existing Benchmark		Existing Delineator Type D																



Symbols

D-101-31
































































































	Existing Light Standard		Existing Manhole with Valve Water		Existing Telephone Pole		Existing Undefined Manhole
	Existing High Mast Light Standard 10 Luminaire		Existing Water Manhole		Existing Wood Pole		Existing Undefined Pull Box
	Existing High Mast Light Standard 3 Luminaire		Existing Mile Post Type A		Existing Post		Existing Undefined Pedestal
	Existing High Mast Light Standard 4 Luminaire		Existing Mile Post Type B		Existing Pedestrian Push Button Post		Existing Undefined Valve
	Existing High Mast Light Standard 5 Luminaire		Existing Mile Post Type C		Existing Control Point CP		Existing Undefined Pipe Vent
	Existing High Mast Light Standard 6 Luminaire		Existing Reference Marker		Existing Control Point GPS-RTK		Existing Gas Valve
	Existing High Mast Light Standard 7 Luminaire		Existing RW Marker		Existing Control Point TRI		Existing Water Valve
	Existing High Mast Light Standard 8 Luminaire		Existing Utility Marker		Existing Reference Marker Point NGS		Existing Fuel Pipe Vent
	Existing High Mast Light Standard 9 Luminaire		Iron Monument Found		Existing Pull Box		Existing Gas Pipe Vent
	Existing Overhead Sign Structure Load Center		Iron Pin R/W Monument		Existing Intelligent Transportation Pull Box		Existing Sanitary Pipe Vent
	Existing Luminaire		Existing Object Marker Type I		Existing Water Pump		Existing Storm Drain Pipe Vent
	Existing Light Standard Luminaire		Existing Object Marker Type II		Existing Slotted Reinforced Concrete Pipe		Existing Water Pipe Vent
	Existing Federal Mailbox		Existing Object Marker Type III		Existing RR Profile Spot		Existing Weather Station
	Existing Private Mailbox		Existing Electrical Pedestal		Existing Fuel Leak Sensors		Existing Ground Water Well Bore Hole
	Existing Meander Section Corner		Existing Telephone Pedestal		Existing Highway Sign		Existing Windmill or Tower
	Existing Meter		Existing Fiber Optic Telephone Pedestal		Existing Miscellaneous Spot		Existing Witness Corner
	Existing Electrical Manhole		Existing TV Pedestal		Existing Lighting Standard Pole		Flashing Beacon
	Existing Gas Manhole		Existing Fiber Optic TV Pedestal		Existing Traffic Signal Standard		Flagger
	Existing Sanitary Manhole		Existing Fuel Filler Pipes		Existing Transformer		Pipe Mounted Flasher
	Existing Sanitary Force Main Manhole		Existing Traverse PI Aerial Panel		Existing Large Evergreen Tree		Sanitary Force Main with Valve
	Existing Sanitary Manhole with Valve		Existing Pole		Existing Small Evergreen Tree		
	Existing Storm Drain Manhole		Existing Power Pole		Existing Large Tree		
	Existing Force Main Storm Drain Manhole		Existing Power Pole with Transformer		Existing Small Tree		
	Existing Force Main Storm Drain Manhole with Valve				Existing Tree Trunk		
	Existing Telephone Manhole				Existing Pad Mounted Traffic Signal Control Box		

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-01-14	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 07/01/14 and the original document is stored at the North Dakota Department of Transportation



Symbols

	Pad Mounted Feed Point		Light Standard 1000 Watt High Pressure Sodium Vapor Luminaire		Object Marker Type I		Reinforced Concrete End Section 48 Inch									
	Pipe Mounted Feed Point with Pad		Light Standard 150 Watt High Pressure Sodium Vapor Luminaire		Object Marker Type II		Reinforced Concrete End Section 54 Inch									
	Pole Mounted Feed Point		Light Standard 175 Watt High Pressure Sodium Vapor Luminaire		Object Marker Type III		Reset Right of Way Marker									
	Headwall		Light Standard 200 Watt High Pressure Sodium Vapor Luminaire		Caution Mode Arrow Panel		Reset USGS Marker									
	Double Headwall with Vegetation Barrier		Light Standard 250 Watt High Pressure Sodium Vapor Luminaire		Back to Back Vertical Panel Sign		Right of Way Markers									
	Single Headwall with Vegetation Barrier		Light Standard 310 Watt High Pressure Sodium Vapor Luminaire		Double Direction Arrow Panel		Riser 30 Inch									
	Pole Mounted Head		Light Standard 35 Watt High Pressure Sodium Vapor Luminaire		Left Directional Arrow Panel		Continuous Split Barrel Sample									
	Sprinkler Head		Light Standard 400 Watt High Pressure Sodium Vapor Luminaire		Right Directional Arrow Panel		Flight Auger Sample									
	Fire Hydrant		Light Standard 50 Watt High Pressure Sodium Vapor Luminaire		Sequencing Arrow Panel		Split Barrel Sample									
	Inlet Type 1		Light Standard 70 Watt High Pressure Sodium Vapor Luminaire		Truck Mounted Arrow Panel		Thinwall Tube Sample									
	Inlet Type 2		Light Standard 700 Watt High Pressure Sodium Vapor Luminaire		Power Pole		Highway Sign									
	Double Inlet Type 2		Manhole		Wood Pole		SNOW GATE 18 FT									
	Inlet Grate Type 2		Manhole 48 Inch		Pedestrian Push Button Post		SNOW GATE 28 FT									
	Junction Box		Sanitary Force Main Manhole		Property Corner		SNOW GATE 40 FT									
	High Mast Light Standard 10 Luminaire		Sanitary Sewer Manhole		Pull Box		Standard Penetration Test									
	High Mast Light Standard 3 Luminaire		Storm Drain Manhole		Intelligent Transportation Pull Box		Transformer									
	High Mast Light Standard 4 Luminaire		Storm Drain Manhole with Inlet		Sanitary Pump		Inclinometer Tube									
	High Mast Light Standard 5 Luminaire		Reset Mile Post		Storm Drain Pump		Underdrain Cleanout									
	High Mast Light Standard 6 Luminaire		Mile Post Type A		Reinforced Pavement		Excavation Unit									
	High Mast Light Standard 7 Luminaire		Mile Post Type B		Reinforced Concrete End Section 15 Inch		Water Valve									
	High Mast Light Standard 8 Luminaire		Mile Post Type C		Reinforced Concrete End Section 18 Inch	<table><tr><th colspan="2">NORTH DAKOTA DEPARTMENT OF TRANSPORTATION</th></tr><tr><td colspan="2">07-01-14</td></tr><tr><th colspan="2">REVISIONS</th></tr><tr><th>DATE</th><th>CHANGE</th></tr><tr><td></td><td></td></tr></table>	NORTH DAKOTA DEPARTMENT OF TRANSPORTATION		07-01-14		REVISIONS		DATE	CHANGE		
NORTH DAKOTA DEPARTMENT OF TRANSPORTATION																
07-01-14																
REVISIONS																
DATE	CHANGE															
	High Mast Light Standard 9 Luminaire		Right of Way Marker		Reinforced Concrete End Section 24 Inch											
	Relocate Light Standard		Tubular Marker		Reinforced Concrete End Section 30 Inch											
	Overhead Sign Structure Load Center		Alignment Monument		Reinforced Concrete End Section 36 Inch											
	Light Standard 100 Watt High Pressure Sodium Vapor Luminaire		Iron Pin Reference Monument		Reinforced Concrete End Section 42 Inch											

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION		This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930 , on 07/01/14 and the original document is stored at the North Dakota Department of Transportation
07-01-14		
REVISIONS		
DATE	CHANGE	



Cross Section Legend


Description	Longitudinal Parallel to Roadway	Transverse Perpendicular to Roadway*
Cable Line	● CBL1	● CBL2
Conduit Line	● CDU1	● CDU2
Electric Line	● E1	● E2
Fiber Optic Line	● F1	● F2
Gas Main Line	● GM1	● GM2
Gas Service Line	● GS1	● GS2
Gas Transmission Line	● GT1	● GT2
Fuel Pipeline	● PL1	● PL2
Sanitary Sewer Force Main	● SSF1	● SSF2
Sanitary Sewer	● SS1	● SS2
Steam Line	● STE1	● STE2
Storm Drain (Assumed Depth)	● SD1	● SD2
Telephone Line	● T1	● T2
TV Line	● TV1	● TV2
Water Main Line	● WM1	● WM2
Water Service Line	● WS1	● WS2

Description	Longitudinal Parallel to Roadway	Transverse Perpendicular to Roadway*
Overhead Power Transmission Line	OHT1 ↑	OHT2 ↑
Overhead Line	OH1 ↑	OH2 ↑



When storm drain invert elevations are NOT used to draw pipe, they will appear as shown to the left. When invert elevations are used to draw pipe, they will be a cross section similar to the graphics shown below.

\* Usually the transverse utilities are shown on a cross section with 2 or more symbols. The utility runs from one symbol to the other, but the connection may not be shown.



On the right side of most cross sections there is a earthwork table. The following example (values not related to project) details the earthwork table layout.





Cut Area	CA: 34.34 SF
Fill Area	FA: 0.017 SF
Cut Volume	CV: 64.44 CY
Fill Volume	FV: 0.031 CY
Mass Ordinate	MO: 65.13 CY

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-20-18	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by  
Roger Weigel,  
Registration Number  
PEPE-2930  
on 9/20/18 and the original document is stored at the  
North Dakota Department  
of Transportation



## TIED JOINTS

[illegible]

## JOINT SEALER DETAILS




NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-15-2010	
REVISIONS	
DATE	CHANGE
10/23/2012	Expanded Tie Bar Table
03/16/2016	Updated Jt Details & notes

This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930, on 3/16/2016 and the original document is stored at the North Dakota Department of Transportation



TRANSVERSE CONTRACTION JOINT DETAILS

D-550-3




CONTRACTION JOINT DOWEL ASSEMBLY  
(1/2 roadway shown)


Notes

1. The joint seal details apply to both doweled and non-doweled (plain) transverse joints.
2. T = Thickness of pavement.
3.  $B = T/4 + 1/4$ " for AE or YE for non-dowelled concrete pavement or  
 $B = T/3$  for high early or dowelled concrete pavement

Coat entire dowel bar length with Multipurpose Lithium Grease (NLGI Grade #2), Tectyl 506 or approved equal



SECTION A-A



NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-15-2010	
REVISIONS	
DATE	CHANGE
6/23/2014	Removed dowel size reference
3/16/2016	Revised Joint Details and notes

This document was originally issued and sealed by  
Roger Weigel,  
Registration Number  
PE- 2930,  
on 3/16/16 and the original document is stored at the  
North Dakota Department  
of Transportation







D-550-5





- |  |                                 |
|--|---------------------------------|
| NORTH DAKOTA<br>DEPARTMENT OF TRANSPORTATION |                                 |
| 9-15-2010                                    |                                 |
| REVISIONS                                    |                                 |
| DATE   | CHANGE                          |
| 3-16-16                                      | Revised Joint Details and notes |
|  |                                 |

This document was originally  
issued and sealed by  
Roger Weigel,  
Registration Number  
PE- 2930 ,  
on 3/16/2016 and the original  
document is stored at the  
North Dakota Department  
of Transportation



ATTENUATION DEVICE


D-704-1



Outer Containers




Cones



Typical Assembly

Typical Module Construction Detail




Reflective Sheet Detail


Note:  
Apply Type IV reflective sheeting (as specified in the NDDOT Standard Specifications) directly to the outer container of the last attenuation device facing traffic, following the details above.  
Or apply the sheet to a metallic sheet and attach it to the container with approved fasteners.

(A) Use 3" orange sheeting for temporary installations, and 3" yellow sheeting for permanent installations.

Fill Chart					
	Module Weights (LBS)				
	200	400	700	1400	2100
Distance from top edge	8½"	5"	4"	3"	0"



Note:  
Angle attenuation devices 10 degrees towards traffic when placed at piers offset from roadway.



Section A-A  
(Type B Layout)

Type B Attenuation Device											
Module Number	Dash Number										
	75	70	65	60	55	50	45	40	35	30	25
	Module Weights (LBS)										
B1	2100										
B2	2100										
B3	2100	2100	2100	2100	2100	2100	2100	2100	2100		
B4	2100	2100	2100	2100	2100	2100	2100	2100	2100		
B5	1400	1400	1400	1400	1400	1400	1400	1400	1400	1400	1400
B6	1400	1400	1400	1400	1400	1400	1400	1400	1400	1400	1400
B7	1400	1400	1400	1400	1400	1400	1400	1400	1400	1400	1400
B8	1400	1400	1400	1400	1400	1400	1400	1400	1400	1400	1400
B9	700	700	700	700	700	700	700	700	700	700	700
B10	700	700	700	700	700	700	700	700	700	700	700
B11	700	700	700	700	700	700	700	700	700	700	700
B12	700	700	700	700	700	700	700	700	700	700	700
B13	700	700	700	700	700	700	700	700	700	700	700
B14	400	400	400	400	400	400	400	400	400	400	400
B15	400	400	400	400	400	400	400	400	400	400	400
B16	200	200	200	200	200	200	200	200	200	200	200
Length (L)	34.2'	30.7'	30.7'	30.7'	30.7'	30.7'	30.7'	30.7'	30.7'	27.2'	27.2'
Module Weights (LBS)	Replacement Module										
	1	1	1	1	1	1	1	1	1	1	1
2100	1	1	1	1	1	1	1	1	1	1	1
1400	1	1	1	1	1	1	1	1	1	1	1
700	2	2	2	2	2	2	2	2	2	2	2
400	1	1	1	1	1	1	1	1	1	1	1
200	2	2	2	1	1	1	1	1	1	1	1


Notes:

- Materials
  - Use modules manufactured from frangible polyethylene material which shatters upon impact.
  - Fill modules with class 43 aggregate meeting NDDOT Standard Specifications aggregate requirements. Use fill with a unit weight of at least 100 pounds per cubic foot. Use fill with a moisture content of 2% or less when left over winter.
- Modules
  - Provide three components for 2, 4, 7, 14, or 21 cubic foot module containers:
    - A 14 C.F., yellow outer container.
    - A black lid securely locking over the top lip of the container.
    - A variable cone-shaped supporting insert capable of supporting 200, 400, or 700 pounds of sand mass to allow for three sizes of modules. Place cone inserts inside the 14 cubic foot container.
  - Provide two components for the 14 cubic foot module container:
    - A 14 C.F., yellow outer container.
    - A black lid securely locking over the top lip of the container.
  - Provide two components for the 21 cubic foot module container:
    - A 36" height X 36" width yellow outer container.
    - A black lid which locks securely over the top of the container.
- For temporary installations use Energite or Fitch attenuation barrels manufactured by Energy Absorption Systems of Chicago, IL, TrafFix barrels manufactured by TrafFix Devices, Inc. of San Clemente, CA, or approved equal modules. As an option, place attenuation devices on 3½" maximum thickness pallets to facilitate maintenance.
- For permanent installations use Barrel Attenuation Device consisting of one-piece outer sand container modules with separate detachable lid. Energite attenuation barrels manufactured by Energy Absorption Systems of Chicago, IL, TrafFix barrels manufactured by TrafFix Devices, Inc. of San Clemente, CA, or approved equal meet these requirements.
- The Typical Module Construction Detail and Type B Layout are based on the Energite Crash Cushion manufactured by Energy Absorption. Provide any required layouts and details from other sand filled attenuation module manufacturers which differ from those shown here.


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-25-12	
REVISIONS	
DATE	CHANGE
7-18-14	Revised sheeting in reflective sheet detail
9-27-17	Update to active voice

This document was originally issued and sealed by  
Roger Weigel,  
Registration Number  
PE-2930,  
on 9/27/2017 and the original document is stored at the  
North Dakota Department  
of Transportation








Multi-Directional Slip Base Assembly



Anchor Unit and Post Assembly




Multi-Directional Slip Base Anchor Unit and Post Sleeve Assembly




Top Post Receiver

Plate - ASTM A572 grade 50  
Angle Receiver - 2 1/2"x2 1/2"x3/8" ASTM A36 structural angle



Bottom Soil Stub

Tube - 3"x3"x7 gauge ASTM A500 grade B tube  
Stabilizing Wing - 7 gauge H.R.P.O. ASTM A1011  
Plate - ASTM A572 grade 50



Bolt Retainer for Base Connection  
Bolt Retainer- 1/32" Reprocessed Teflon

- Notes:
1. Torque slip base bolts as specified by manufacturer.
  2. Use anchor with 43.9 KSI yield strength and 59.3 KSI tensile strength.
  3. Provide 4" vertical clearance for anchor or breakaway base. Measure the 4"x60" measurement above and below post location and back and ahead of post.
  4. In concrete sidewalk, use same anchor without wings.
  5. Provide more than 7" between the first and fourth posts of a four post sign.

Telescoping Perforated Tube						
Number of Posts	Post Size in.	Wall Thickness Gauge	Sleeve Size in.	Wall Thickness Gauge	Slip Base	Anchor Size without Slip Base in.
1	2	12			No	2 1/4
1	2 1/4	12			No	2 1/2
1	2 1/2	12			(A)	3
1	2 1/2	10			Yes	
1	2 1/4	12	2	12	Yes	
1	2 1/2	12	2 1/4	12	Yes	
2	2	12			No	2 1/4
2	2 1/4	12			No	2 1/2
2	2 1/2	12			Yes	
2	2 1/2	12			Yes	
2	2 1/4	10	2	12	Yes	
2	2 1/2	12	2 1/4	12	Yes	
3 & 4	2 1/2	12			Yes	
3 & 4	2 1/2	10			Yes	
3 & 4	2 1/2	12	2 1/4	12	Yes	
3 & 4	2 1/4	12	2	12	Yes	
3 & 4	2 1/2	10	2 3/16	10	Yes	

Properties of Telescoping Perforated Tube						
Tube Size in.	Wall Thickness in.	U.S. Standard Gauge	Weight per Foot lbs.	Moment of Inertia in. <sup>4</sup>	Cross Sec. Area in. <sup>2</sup>	Section Modulus in. <sup>3</sup>
1 1/2 x 1 1/2	0.105	12	1.702	0.129	0.380	0.172
2 x 2	0.105	12	2.416	0.372	0.590	0.372
2 1/4 x 2 1/4	0.105	12	2.773	0.561	0.695	0.499
2 3/16 x 2 3/16	0.135	10	3.432	0.605	0.841	0.590
2 1/2 x 2 1/2	0.105	12	3.141	0.804	0.803	0.643
2 1/2 x 2 1/2	0.135	10	4.006	0.979	1.010	0.785

Top Post Receiver Data Table						
Square Post Sizes (B)	A	B	C	D	E	F
2 3/16"x10 ga.	1 9/64"	2 1/2"	3 1/32"	2 5/32"	1 33/64"	1 7/8"
2 1/2"x10 ga.	1 9/32"	2 1/2"	3 5/16"	5/8"	1 21/32"	1 3/4"






- (A) Use breakaway base when support is placed in weak soils. Engineer determines if soils are weak.
- (B) For additional wind load, insert the 2 3/16"x10 ga. into 2 1/2"x10 ga.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
2-28-14	
REVISIONS	
DATE	CHANGE
9-27-17	Updated to active voice

This document was originally issued and sealed by  
Roger Weigel,  
Registration Number  
PE-2930,  
on 9/27/2017 and the original document is stored at the  
North Dakota Department  
of Transportation



U-Channel Post



Alternate A Steps of Installation:

- Drive anchor unit to within 12" of ground level.
  - Establish proper assembly by lining up bottom hole of retainer strap with 6th hole from the top of the anchor unit.
  - Assemble strap to back of anchor unit using  $\frac{5}{16}$ "x2" bolt, lock washer and nut.
  - Rotate strap 90° to left.
- Drive anchor unit to 4" above ground.
  - Rotate strap to vertical position.
- Place  $\frac{5}{16}$ "x2" bolt, lock washer and nut in bottom of sign post to facilitate alignment of sign post with proper hole in anchor unit.
  - Alternately tighten two connector bolts.
- Complete assembly by tightening  $\frac{5}{16}$ "x2" bolt (this fastens sign post to retainer strap).
- Properly nest base post, strap, and sign post. Proper nesting occurs when all flat surfaces of the base post, strap, and sign post at the bolts have full contact across the entire width.


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
2-28-14	
REVISIONS	
DATE	CHANGE
9-27-17	Updated to active voice

This document was originally issued and sealed by  
Roger Weigel,  
Registration Number  
PE-2930,  
on 9/27/2017 and the original document is stored at the  
North Dakota Department  
of Transportation




CONSTRUCTION SIGN DETAILS  
TERMINAL AND GUIDE SIGNS


D-704-9




G20-1-60  
Legend: black (non-refl)  
Background: orange




G20-1b-60  
Legend: black (non-refl)  
Background: orange




G20-2-48  
Legend: black (non-refl)  
Background: orange




G20-4b-36  
Legend: black (non-refl)  
Background: orange




G20-50a-72  
Legend: black (non-refl)  
Background: orange




G20-52a-72  
Legend: black (non-refl)  
Background: orange




G20-55-96  
Legend: black (non-refl)  
Background: orange




E5-1(L or R)-48  
Legend: white  
Background: green (orange optional)




M4-8-36  
Legend: black (non-refl)  
Background: orange




M4-9(L or R)-30 &  
M4-9-30  
Legend: black (non-refl)  
Background: orange




E5-1-48




G20-50a-72  
G20-52a-72



M4-9(L or R)-30  
Right or Left



M4-9(L or R)-30  
Advanced Right or Left



M4-9-30  
Straight

ARROW DETAILS

NOTES:






(A) Arrow may be right or left of the legend to indicate construction to the right or left.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-13-13	
REVISIONS	
DATE	CHANGE
8-17-17	Added sign & background color

This document was originally issued and sealed by  
Roger Weigel,  
Registration Number  
PE-2930,  
on 8/17/17 and the original document is stored at the  
North Dakota Department  
of Transportation



D-704-10


[illegible]

This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930 , on 8/17/17 and the original document is stored at the North Dakota Department of Transportation




CONSTRUCTION SIGN DETAILS  
WARNING SIGNS


D-704-11




W5-8-48  
Legend: black (non-refl)  
Background: orange




W8-53-48  
Legend: black (non-refl)  
Background: orange




W8-56-48  
Legend: black (non-refl)  
Background: orange




W5-9-48  
Legend: black (non-refl)  
Background: orange




W8-54-48  
Legend: black (non-refl)  
Background: orange



W9-3a-48  
Legend: black (non-refl)  
Background: orange





W8-9a-48  
Legend: black (non-refl)  
Background: orange



W8-55-48  
Legend: black (non-refl)  
Background: orange

WORD	LETTER SPACING
AHEAD	Standard
200 FT	Standard
350 FT	Standard
500 FT	Standard
1000 FT	Reduce 40%
1500 FT	Reduce 40%
1/2 MILE	Reduce 50%
1 MILE	Standard

\* DISTANCE MESSAGES



ARROW DETAILS

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-13-13	
REVISIONS	
DATE	CHANGE
8-17-17	Updated sign number
5-31-18	Revised sign and arrow details


This document was originally issued and sealed by  
Roger Weigel,  
Registration Number  
PE- 2930 ,  
on 5/31/18 and the original document is stored at the  
North Dakota Department  
of Transportation




CONSTRUCTION SIGN DETAILS  
WARNING SIGNS

WORD	LETTER SPACING
AHEAD	Standard
200 FT	Standard
350 FT	Standard
500 FT	Standard
1000 FT	Reduce 40%
1500 FT	Reduce 40%
½ MILE	Reduce 50%
1 MILE	Standard


\* DISTANCE MESSAGES




W20-51-48  
Legend: black (non-refl)  
Background: orange




W21-51-48  
Legend: black (non-refl)  
Background: orange




W22-8-48  
Legend: black (non-refl)  
Background: orange




W20-52P-54  
Legend: black (non-refl)  
Background: orange



W21-52-48  
Legend: black (non-refl)  
Background: orange



W21-50-48  
Legend: black (non-refl)  
Background: orange




W21-53-48  
Legend: black (non-refl)  
Background: orange

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
5-31-18	
REVISIONS	
DATE	CHANGE


This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930 , on 5/31/18 and the original document is stored at the North Dakota Department of Transportation






Provide horizontal, circumferential, alternating orange and white retroreflective stripes 4" to 6" wide for drum markings. Use a minimum of two orange and two white stripes with the top stripe being orange for each drum. Do not exceed 3" nonretroreflectitized spaces between the horizontal orange and white stripes. Avoid placement of stripes on drum ribs or indentations. Use closed top drums that will not allow collection of debris. Do not place ballast on the top of drum.


Provide alternating orange and white retroreflective stripes, sloping downward in direction vehicular traffic is to pass. Place retroreflective sheeting on both sides of panel with a minimum of 270 square inches of retroreflective area facing vehicular traffic. Where the height of the retroreflective material on the vertical panel is 36 inches or more, use a stripe width of 6 inches.



Provide retroreflectorization of cones more than 36" in height by alternating orange and white retroreflective stripes. Use a minimum of two orange and two white stripes for each cone with the top stripe being orange. Use maximum 3" nonretroreflectorized space between the orange and white stripes.




Provide retroreflectorization of tubular markers more than 42" in height by alternating four 4" to 6" wide orange and white stripes with the top stripe being orange.




INSTALLATION NOTES:


1. Drill installation holes to diameter and depth required by manufacturer's specifications.
2. For removal, remove anchors and fill installation hole with an epoxy designed to bond to pavement surface.
3. In lieu of bolted down base, use an 8" x 8" butyl pad or hot melt butyl. Remove butyl as close as possible to pavement surface.



### BARRICADE BLADE DETAIL




**SIDE VIEW**




### BARRICADE ASSEMBLY DETAIL (Wood or Plastic Rails)

**SIDE VIEW**




## TYPE I BARRICADE




## TYPE II BARRICADE

## BARRICADE RAIL DETAILS



### TYPE III BARRICADE



## DELINEATORS

MINIMUM BALLAST  
(For each side of barricade support)

Without Sign	4 - 25 lb sandbags
With Sign	6 - 25 lb sandbags

Note: Number of sandbags based on a wind speed of 55 MPH. Sandbags assumed to be placed at or near the ends of the skids.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-3-13	
REVISIONS	
DATE	CHANGE
9-27-17	Updated to active voice


This document was originally  
issued and sealed by  
Roger Weigel,  
Registration Number  
PE- 2930,  
on 9/27/2017 and the original  
document is stored at the  
North Dakota Department  
of Transportation




CONSTRUCTION SIGN PUNCHING AND MOUNTING DETAILS

D-704-14


Note: In curb sections, place signs a minimum horizontal distance of 2' from face of the curb to near edge of the sign.




TYPICAL SECTION  
(48" x 48" diamond warning sign shown)




24" x 24" ROUTE MARKER ASSEMBLY




36" x 36" ROUTE MARKER ASSEMBLY




18" x 18" DIAMOND SIGN




48" x 48" DIAMOND SIGN  
(with 30" x 30" secondary sign)




48" x 48" DIAMOND SIGN  
(with 30" x 24" secondary sign)




R1-2-60 - YIELD SIGN




W14-3-64 - PENNANT SIGN




R1-1-48 - STOP SIGN  
(with R6-1-54 sign as required)




R1-1-48 - STOP SIGN  
(with R1-50P-24 sign as required)




48" x 48" SIGN  
(with R6-1-54 sign as required)




48" x 48" SIGN  
(with R2-1aP-24 sign as required)




24" x 36" SIGN




30" x 24" SIGN




108" x 48" SIGN




96" x 48" SIGN




72" x 36" SIGN




72" x 24" SIGN




60" x 24" SIGN



48" x 24" SIGN



PORTABLE SIGN SUPPORT  
LOW-MOUNTING HEIGHT



PORTABLE SIGN SUPPORT  
HIGH-MOUNTING HEIGHT

NOTES:

1. Sign Supports: Galvanize or paint supports. Minimum post sizes are 2.5 lb/ft u-channel or 2" x 2" x 12 gauge steel perforated tube, except where noted. When installing signs on u-channel, minimum post size for assemblies containing a secondary sign is 3.0 lb/ft. Post sizes based on a wind speed of 55 MPH.

Place signs over 50 square feet on 2 1/2" x 2 1/2" perforated tube supports as a minimum.

Do not attach guy wires to sign supports. Attach wind beams behind sign panels when used with u-posts.

2. Sign Panels: Provide sign panels made of 0.100" aluminum, 1/2" plywood, or other approved material, except where noted. Punch all holes round for 3/8" bolts.

3. Alternate Messages: Install and remove alternate message signs on reflectorized plate (without borders) as required. (i.e. "Left" and "Right" message on lane closure sign)

4. Route Marker Auxiliary Signs: Provide route marker auxiliary signs, such as the cardinal direction and directional arrows, with a background and legend that match the route marker they are used with:

Interstate - white legend on blue background  
Interstate Business Loop - white legend on green background  
US and State - black legend on white background  
County - yellow legend on blue background

5. Vertical Clearance: Install signs with a vertical clearance of 5'-0" (see TYPICAL SECTION.) In areas where parking or pedestrian movements are likely or the view of the sign may be obstructed, install signs with a vertical clearance of 7'-0" from the top of the curb or from the near edge of the driving lane in absence of a curb.

The vertical clearance to secondary signs is 1'-0" less than the vertical clearance stated above.

Provide a minimum clearance of 7'-0" from the ground at the post for signs with an area exceeding 50 square feet.

6. Portable Signs: Provide portable signs that meet the vertical clearance stated above when it is necessary to place signs within the pavement surface.

Use of low-mounting height (minimum 12" vertical clearance) portable signs for 5 days or less, is allowed as long as the view of the sign is not obstructed. Time delays caused by unforeseen circumstances, such as equipment breakdown, rain, subgrade failures, etc., will not accrue towards the 5 day period. Use of R9-8 through R9-11a series, W1-6 through W1-8 series, M4-10, and E5-1 is allowed for longer than 5 days.

Restrict signs mounted on portable sign supports shown in the LOW-MOUNTING HEIGHT and HIGH-MOUNTING HEIGHT details to a maximum surface area of 16 square feet.

MINIMUM BALLAST  
(For each side of sign support base)

Sign Panel Mounting Height (ft)	Number of 25 lb sandbags for 4' x 4' sign panel
1'	6
5'	8
7'	10

Note: The number of sandbags are based on a wind speed of 55 MPH. Place sandbags at or near the ends of skids.


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-4-13	
REVISIONS	
DATE	CHANGE
11-14-13 9-27-17	Revised Note 6. Updated to active voice

This document was originally issued and sealed by  
Roger Weigel,  
Registration Number  
PE-2930,  
on 9/27/2017 and the original document is stored at the  
North Dakota Department  
of Transportation



LANE CLOSURE ON A TWO LANE ROAD USING TRAFFIC CONTROL SIGNALS

D-704-16



- Notes
- Span conductor overhead between poles except on bridges, where it may alternately be attached and supported by the bridge structure. When conductor is supported by the bridge structure, attach conductor to avoid interference with bridge construction. Attach conductor on either side of bridge as determined by field personnel.
  - Locate controller on a wood pole in the cable run between signal heads for through traffic movements.
  - The timing schedule is suggested trial setting. Check signals in operation frequently to obtain the most efficient timing schedule.
  - Place wood poles a minimum of 16 feet from edge of driving lane. Provide a minimum 16 to 19 feet clearance from the center line of the roadway to the bottom of traffic signal heads suspended over the roadway.
  - Place traffic signal heads with 12 inch red, yellow and green lenses and 5 inch louvered backplates.
  - See standard drawing "Span Wire Mounted Traffic Signals" for interim traffic construction details.
  - Re-establish speed limit. Determine exact speed limit in the field, dependent on location and conditions.
  - Determine the reduced speed limit based on the in-place speed limit before construction. Where speed reductions exceed 30 MPH, install a second speed limit sign with the desired speed reduction (not to exceed 30 MPH.) Place the second speed limit sign at 1/2 B.
  - Install flags on warning signs in urban areas when signs are not portable. Mount 24 inch square flags perpendicular to the edges of the sign, and at such a distance above the edge that the flag does not touch the sign when limp.
  - Cover existing speed limit signs within a reduced speed zone.
  - Place barricades on moveable assemblies and signs on portable assemblies when located on roadway.
  - As an option, use portable sign supports in lieu of post mounted signs in accordance with NDDOT Standard Specifications.
  - Continue double yellow centerline thru private drives.
  - Sign G20-55-96 is not required if layout is part of other traffic control or if work is less than 15 days.
  - Recommend using 40 mph speed limit in vicinity of workers, unless location and conditions dictate otherwise.

ADVANCE WARNING SIGN SPACING			
Road Type	Distance Between Signs Min. (ft)		
	A	B	C
Urban - Low Speed (30 mph or less)	150	150	150
Urban - Low Speed (over 30 to 40 mph)	280	280	280
Urban - High Speed (over 40 mph to 50 mph)	360	360	360
Rural - High Speed (over 50 mph to 65 mph)	720	720	720
Urban Expressway and Freeway (55 mph to 60 mph)	850	1350	2200
Rural Expressway and Freeway (70 mph to 75 mph)	1000	1500	2640
Interstate/4-Lane Divided (Maintenance and Surveying)	750	1000	1500

SUGGESTED TIMING AND SIGNAL SEQUENCE						
Heads 1 & 2	Green	Yellow	Red			
Heads 3 & 4		Red	Green	Yellow	Red	
Time						
Cycle = 90 seconds	18.0	4.5	22.5	18.0	4.5	22.5
Percent of Cycle	20	5	25	20	5	25

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-27-13	
REVISIONS	
DATE	CHANGE
11-20-15	Revised Note 6, Renumbered Minimum Fee plaque.
8-17-17	Revised notes & added note


KEY	
	Work Area
	Type III Barricade
	Sign
	Delineator Drum

This document was originally issued and sealed by  
Roger Weigel  
Registration Number  
PE- 2930 ,  
on 08/17/17 and the original document is stored at the  
North Dakota Department  
of Transportation



DETOUR AND ROADWAY DIVERSION SIGN LAYOUTS

D-704-21



- Notes
- Variables  
S=Numerical value of speed limit or 85th percentile. W=The width of taper.  
L=Minimum length of taper, or  $S \times W$  for freeways, expressways, and all other roads with speeds of 45 mph or greater, or  $W \times S^2 / 60$  for urban, residential, and other streets with speeds of 40 mph or less.
  - Place barricades on moveable assemblies and signs on portable assemblies when on roadway.
  - Space delineator drums and vertical panels at dimension "S" for tapering traffic. Space delineator drums, tubular markers and vertical panels at 2 times "S" for tangents.
  - Determine the reduced speed limit based on the in place speed limit before construction. Where speed limits exceed 30 MPH, install a second speed limit sign with the desired speed reduction (not to exceed 30 mph.) Place the second speed limit sign at  $\frac{1}{2} B$ .
  - Install flags on warning signs in urban areas when signs are not portable. Mount 24 inches square flags perpendicular to the edges of the sign, and at such a distance above the edge that the flag does not touch the sign when limp.
  - Cover existing speed limit signs within a reduced speed limit zone.
  - Covered (when approved by engineer) or obliterated pavement marking measured as Obliteration of Pavement Marking.
  - As an option, use portable sign supports in lieu of post mounted signs in accordance with NDDOT Standard Specifications.
  - If the tangent between tapers is less than 600', as an option, use sign W24-1-48 in place of double reverse curve signs.
  - Recommend using 40 mph speed limit in vicinity of workers, unless location and conditions dictate otherwise.
  - Re-establish speed limit. Determine exact speed limit in the field, dependent on location and conditions.

TYPE J  
ROAD CLOSURE WITH A DIVERSION SIGN LAYOUT

2 lane highway with widened section,  
traffic maintained in both directions.  
Use layout when work is less than 5 days or is within a project.

ADVANCE WARNING SIGN SPACING			
Road Type	Distance Between Signs Min. (ft)		
	A	B	C
Urban - Low Speed (30 mph or less)	150	150	150
Urban - Low Speed (over 30 to 40 mph)	280	280	280
Urban - High Speed (over 40 mph to 50 mph)	360	360	360
Rural - High Speed (over 50 mph to 65 mph)	720	720	720
Urban Expressway and Freeway (55 mph to 60 mph)	850	1350	2200
Rural Expressway and Freeway (70 mph to 75 mph)	1000	1500	2640
Interstate/4-Lane Divided (Maintenance and Surveying)	750	1000	1500












NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-27-13	
REVISIONS	
DATE	CHANGE
8-17-17	Updated notes, Added speed limit

This document was originally  
issued and sealed by  
Roger Weigel  
Registration Number  
PE-2930,  
on 08/17/17 and the original  
document is stored at the  
North Dakota Department  
of Transportation



MISCELLANEOUS SIGN LAYOUTS

D-704-26



- Notes
1. Re-establish speed limit. Determine exact speed limit in the field, dependent on location and conditions.
  2. Determine reduced speed limit based on in-place speed limit before construction. Where speed reductions exceed 30 mph, install a second speed limit sign with the desired speed reduction (not to exceed 30 mph.) Place the second speed limit sign at 1/2B.
  3. Install flags on warning signs in urban areas when signs are not portable. Mount 24 inch square flags perpendicular to the edges of the sign, and at such a distance above the edge that the flag does not touch the sign when limp.
  4. Cover existing speed limit signs within reduced speed zones.
  5. As an option, use portable sign supports in lieu of post mounted signs in accordance with NDDOT Standard Specifications.
  6. Sign G20-55-96 is not required if this standard is part of other traffic control layouts, or work is less than 15 days.
  7. When pilot car operation is used, place sign G20-4b-36 "Wait For Pilot Car" at major intersections within pilot car control area.
  8. Recommend 40 mph speed limit in vicinity of workers, unless location and conditions dictate otherwise.

ADVANCE WARNING SIGN SPACING			
Road Type	Distance Between Signs Min. (ft)		
	A	B	C
Urban - Low Speed (30 mph or less)	150	150	150
Urban - Low Speed (over 30 to 40 mph)	280	280	280
Urban - High Speed (over 40 mph to 50 mph)	360	360	360
Rural - High Speed (over 50 mph to 65 mph)	720	720	720
Urban Expressway and Freeway (55 mph to 60 mph)	850	1350	2200
Rural Expressway and Freeway (70 mph to 75 mph)	1000	1500	2640
Interstate/4-Lane Divided (Maintenance and Surveying)	750	1000	1500

Longitudinal Buffer Space	
*Speed (mph)	Length Min (feet)
20	115
25	155
30	200
35	250
40	305
45	360
50	425
55	495
60	570
65	645
70	730
75	820

\* Posted speed, off-peak 85th percentile speed prior to work starting, or the anticipated operating speed in mph.

KEY

Sign      Flagger      Cones

S = Numerical value of speed limit or 85th percentile.


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
9-27-13	
REVISIONS	
DATE	CHANGE
8-17-17	Added speed limit signs. Updated notes & sign numbers

This document was originally issued and sealed by Roger Weigel Registration Number PE- 2930, on 08/17/17 and the original document is stored at the North Dakota Department of Transportation



PORTABLE SIGN SUPPORT ASSEMBLY

D-704-50



Notes:

- ① The maximum weight of the assembly is 250 pounds.
- ② Use a 14" wheel and tire.
- ③ Automotive and equipment axle assemblies may not be used for trailer-mounted sign supports.
- ④ Other NCHRP 350 crash tested assemblies are acceptable.


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
11-23-10	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by  
Roger Weigel  
Registration Number  
PE- 2930 ,  
on 11/23/10 and the original document is stored at the  
North Dakota Department  
of Transportation




PORTABLE PRECAST CONCRETE MEDIAN BARRIER  
(TEMPORARY USAGE)


D-704-51



Plan View




End View




Connecting Bolt Detail

(One per 10 Ft section)




Side View




Barrier Marker Detail


Use same color reflective faces as the edge line along barrier edge. Two way reflective on Surface 1 & 2.




Bolt Connection Detail




Dap Detail




C1 Bar Detail



U3 Bar Detail



U1 Bar Detail



U2 Bar Detail

Notes:

1. Galvanize all exposed hardware as per ASTM A153, except for the loop inserts.
2. Use AAE-3 Concrete.
3. Provide steel in accordance with Section 612 of NDDOT Standard Specifications.
4. Imprint barrier ends A and B as shown with 4 inch letters. Field match A end with B end.
5. Place barrier markers at the center of the barrier at 20' centers.
6. Connect barrier sections with 1 1/4" Dia A-307 double hex connecting bolt. Maintain bottom nut and washer connection for duration of barrier installation.
7. Place barrier to minimize openings between individual sections.

**Marker Body**  
Use high impact, weatherable engineering thermo-plastic material conforming to the following:

Property	Result	ASTM Test Method
Thickness (min)	.090"	—
Tensile strength (min psi) @ yield	5,500	D638
Impact strength @ -20°F (ft-lbs/in of notch)	3.2	D256 Method A
Impact strength @ 73°F (ft-lbs/in of notch)	14.0	D256 Method A
Flexural strength, PSI 1/4" @ 73°F	8,000	D790
Flexural modulus, PSI 1/4" @ 73°F	300,000	D790
Elongation @ yield	30%	D638

**Reflective Tape**  
Use retroreflective, acrylic microprism material with acrylic backing, 3" wide, providing the following minimum optical performance with an observation angle of 0.1° measured in candlepower for the reflector:

Entrance Angle	Specific Intensity
Yellow - 4"	136
White - 4"	200

**Adhesive**  
Use factory applied solid butyl rubber 1/8" thick, 2" wide on 2 1/4" wide release paper on surface 3 to temporarily mount markers to portable concrete barrier.


Bar List				
Mark	Size	No.	Length	Shape
C1	4	6	9'-4"	Straight
U1	4	2	4'-8"	Bent
U2	4	2	4'-10 1/4"	Bent
U3	4	15	5'-4"	Bent

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
07-20-12	
REVISIONS	
DATE	CHANGE
9-27-17	Updated to active voice


This document was originally issued and sealed by  
Roger Weigel  
Registration Number  
PE- 2930 ,  
on 09/27/2017 and the original document is stored at the  
North Dakota Department  
of Transportation




EROSION AND SILTATION CONTROLS  
MEDIAN OR DITCH INLET PROTECTION




FIBER ROLL PROTECTION  
(MEDIAN OR DITCH INLET)




FIBER ROLL PROTECTION  
(INLET OF CULVERT)




SILT FENCE PROTECTION  
(MEDIAN OR DITCH INLET)



GRAVEL INLET PROTECTION  
(MEDIAN OR DITCH INLET)



SANDBAG PROTECTION  
(LOW POINT)




SANDBAG PROTECTION  
(ON SLOPE)

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-03-13	
REVISIONS	
DATE	CHANGE
06-26-14	Updated reference to standard drawing number for fiber roll staking details.
10-01-14	Updated reference to standard drawing number for silt fence.
10-17-17	Updated to active voice.

This document was originally issued and sealed by  
Roger Weigel  
Registration Number  
PE- 2930,  
on 10-17-2017 and the original document is stored at the  
North Dakota Department  
of Transportation




REINFORCED CONCRETE PIPE CULVERTS AND END SECTIONS  
(Round Pipe)



REINFORCED CONCRETE PIPE - FLARED END SECTION  
Reinforcement to be equivalent to Class III RCP


TRAVERSABLE END SECTION							
DIA	B	C	D	E	F	R	S
15"	4"	9"	4'-9"	1'-7½"	2½"	3"	6
18"	5'-9"	9"	6'-6"	1'-11"	2½"	3"	6
24"	6"	1'	7"	2'-6"	3"	3"	4
30"	7'-6"	1'	8'-6"	3'-1"	3½"	3½"	4
36"	7'-3"	15"	8'-6"	3'-8"	4"	3"	4



- NOTES (Traversable End Section):
1. Manufactured in accordance with applicable portions of ASTM C76/AASHTO M170.
  2. Reinforcement per Class III RCP with double reinforcement in the upper 120° of the full barrel portion.

FLARED END SECTION						
TERMINAL DIMENSIONS						
DIA	A	B	C	D	E	U
12	0'-4"	2'-0"	4'-0⅞"	6'-0⅞"	2'-0"	2"
15	0'-6"	2'-3"	3'-10"	6'-1"	2'-6"	2½"
18	0'-9"	2'-3"	3'-10"	6'-1"	3'-0"	2½"
21	0'-9"	3'-0"	3'-1"	6'-1"	3'-6"	2½"
24	0'-9½"	3'-7½"	2'-6"	6'-1½"	4'-0"	3"
27	0'-10½"	4'-0"	2'-1½"	6'-1½"	4'-6"	3½"
30	1'-0"	4'-6"	1'-7¾"	6'-1¾"	5'-0"	3½"
36	1'-3"	5'-3"	2'-9"	8'-0"	6'-0"	4"
42	1'-9"	5'-3"	2'-9"	8'-0"	6'-6"	4½"
48	2'-0"	6'-0"	2'-0"	8'-0"	7'-0"	5"
54	2'-3"	5'-5"	2'-9¼"	8'-2¼"	7'-6"	5½"
60	2'-11"	5'-0"	3'-3"	8'-3"	8'-0"	5"
66	2'-6"	6'-0"	2'-3"	8'-3"	8'-6"	5½"
72	3'-0"	6'-6"	1'-9"	8'-3"	9'-0"	6"
78	3'-0"	7'-6"	1'-9"	9'-3"	9'-6"	6½"
84	3'-0"	7'-6½"	1'-9"	9'-3½"	10'-0"	6½"
90	3'-5"	7'-3½"	2'-0"	9'-3½"	11'-0"	6½"

REINFORCED CONCRETE PIPE - TRAVERSABLE END SECTION  
Reinforcement to be equivalent to Class III RCP



All Classifications of Round Concrete Pipe					
Internal Dia. of Pipe in Inches	Cross-Sectional Water Area	Weight per Lin. Foot of Pipe Std. Wall	Joint J Groove End Min./Max.	Joint K Tongue Min.	Minimum Wall Thickness (T)
Dia	Sq. ft.	Lbs.	In.	In.	In.
12	0.79	92	1⅞-2⅜	¾	2
15	1.23	127	1¾-2¾	⅞	2½
18	1.77	168	1⅞-2⅞	1	2½
21	2.40	214	1⅞-3⅞	1⅞	2¾
24	3.14	265	2¾-3¾	1⅞	3
27	3.98	322	2¾-4	1¼	3¼
30	4.91	384	3¼-4¼	1¼	3½
33	5.94	452	3¼-4¼	1½	3¾
36	7.07	524	3¼-4¼	1½	4
42	9.62	685	3¾-4¾	1¾	4½
48	12.57	685	3¾-4¾	1⅞	5
54	15.90	1070	4½-5½	2	5½
60	19.63	1296	4½-5½	2¼	6
66	23.76	1542	5-6	2⅞	6½
72	28.27	1810	5½-6¾	2⅞	7
78	33.18	2098	6¼-7¼	2⅞	7½
84	38.48	2410	5½-7¾	3⅞	8
90	44.18	2793	6¾-8½	3⅞	8½
96	50.27	3092	7-8¼	3½	9
102	56.75	3466	7-8¼	3½	9½
108	63.62	3864	7¼-8½	3¾	10

- NOTES:
1. All reinforcing steel shall meet AASHTO M170 requirements.
  2. All circular, longitudinal, and elliptical reinforcement shall be assembled and securely fastened in cage fashion so as to maintain reinforcement in exact shape and correct positions within the forms.
  3. Laying length of pipe: 12" to 66" (incl.) = not less than 4 feet 66" to 108" (incl.) = not less than 6 feet
  4. Joints shall be sealed with rubber gaskets or with sealer approved by the engineer whenever pipe are specified for storm drain or sanitary sewers.
  5. For Class IV and Class V reinforced concrete pipe and end section sizes which do not have reinforcement specified by AASHTO M170, shop drawings and design calculations shall be prepared and sealed by a Professional Engineer and submitted for the Engineer's review.

SEE STANDARD DRAWING D-714-22 FOR DETAILS OF CONCRETE PIPE TIES (TIE BOLTS).

NORTH DAKOTA  
DEPARTMENT OF TRANSPORTATION

05-12-14

REVISIONS

DATE	CHANGE
01-21-15	Revised Note 5
11-21-16	Revised End Section Dimensions

This document was originally issued and sealed by

Jon Ketterling




Registration Number PE-4684,

on 11/21/16 and the original document is stored at the North Dakota Department of Transportation



ROUND CORRUGATED STEEL PIPE CULVERTS AND END SECTIONS

D-714-4



PIPE DIA.	GALV. THICK.	END SECTION DIMENSIONS					APPROX. SLOPE RATE	BODY
		A	B	H	L	W		
IN	IN	IN	IN	IN	IN	IN		
15	0.064	7	8	6	26	30	2 1/2:1	1
18	0.064	8	10	6	31	36	2 1/2:1	1
24	0.064	10	13	6	41	48	2 1/2:1	1
30	0.079	12	16	8	51	60	2 1/2:1	1 or 2
36	0.079	14	19	9	60	72	2 1/2:1	2
42	0.109	16	22	11	69	84	2 1/2:1	2
48	0.109	18	27	12	78	90	2 1/2:1	2
54	0.109	18	30	12	84	102	2:1	2
* 60	0.109	18	33	12	87	114	1 1/2:1	3
* 66	0.109	18	36	12	87	120	1 1/2:1	3
* 72	0.109	18	39	12	87	126	1 1/3 :1	3
* 78	0.109	18	42	12	87	132	1 1/4:1	3
* 84	0.109	18	45	12	87	138	1 1/6 :1	3

\* These sizes have 0.109" sides and 0.138" center panels.

\* \* Pipe diameter is equal to dimension "D" of end section.

Manufacturers tolerances of above dimensions will be allowed.




















Splices to be the lap riveted type.

Multiple panel bodies shall have lap seams which are to be tightly joined with 3/8" dia. galv. bolts or rivets. Nuts to be torqued to 25 foot-lbs ±.

NOTES:

- Pipes and connecting bands shall conform to applicable sections of NDDOT Standard Specifications and to AASHTO M-36.
- Top edge of all end sections to have rolled edges for reinforcement (see Section A-A). The reinforced edges are to be supplemented with 2" x 2" x 1/4" galv. angle for 60" through 72" dia. and 2 1/2" x 2 1/2" x 1/4" galv. angle for 78" and 84" dia.. Angles to be attached by galv. 3/8" dia. bolts and nuts. Angles are to extend from pipe to the corner wing bend.
- Elongated pipes shall be factory preformed so that the vertical diameter shall be 5% greater and the horizontal diameter 5% less than a circular pipe.
- Coupling bands shall be two-piece for pipes larger than 36" as shown in Section C-C & D-D details. For pipes 36" and smaller, a one-piece band is acceptable.
- 1/2" x 8" bolts may be used as a substitute for the 1/2" x 6" bolts shown in the details.
- Coupling bands wider than 14" may be used if a minimum of four 1/2" bolts with maximum spacing of 5 1/2" are used for the connection.
- Length of spot welds shall be minimum 1/2".

COUPLING BAND DIMENSIONS				
COUPLING TYPE	CORRUGATION PITCH x DEPTH	PIPE SIZE	COUPLING BAND LENGTH	MIN. BAND THICKNESS
Hat Band	2 2/3" x 1/2"	12" - 48"	2 3/4"	.064"
Annular Band	2 2/3" x 1/2"	12" - 72"	12"	.052"
		78" - 84"	12"	.079"
Hugger Band	2 2/3" x 1/2" Rerolled End	12" - 72"	10 1/2"	.052"
		78" - 84"	10 1/2"	.079"
	3" x 1" Rerolled End	48" - 120"	10 1/2"	.052"
		48" - 120"	12"	.064"




NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
08-06-13	
REVISIONS	
DATE	CHANGE
01-07-14	End Section Plan View
02-27-14	3" x 1" Corrugation Detail

This document was originally issued and sealed by Terrence R. Udland, Registration Number PE- 2674 , on 02/27/2014 and the original document is stored at the North Dakota Department of Transportation




CONCRETE PIPE, CATTLE PASS, OR  
PRECAST CONCRETE BOX CULVERT TIES


D-714-22




EYE BOLT TIE (PIPES ONLY)




ADJUSTABLE TIE (RCB AND PIPES ONLY)




SECTION A-A




U BOLT TIE (RCB, PIPES, OR CATTLE PASSES)




WELDED TIE (RCB AND PIPES ONLY)




DETAIL A




CANOPY TIE (PIPES ONLY)




HIDDEN TIE (RCB ONLY)





DETAIL B



PLAN VIEW



END VIEW



REQUIRED SIZE OF TIE BOLTS		
Pipe Size	Thread $\phi$	XXS Pipe Sleeve Inner $\phi$
18" - 24"	$\frac{5}{8}$ " See note 2	$\frac{3}{4}$ "
30" - 66"	$\frac{3}{4}$ "	1"
72" - 78"	1"	1 $\frac{1}{4}$ "
RCB/Cattle Pass		

- NOTES:
- The pipe size listed is the inside diameter of round pipe or the equivalent diameter of pipe arch.
  - Cattle Pass and Jacked and Bored pipes shall have pipe ties inserted from the inside of the pipes and grouted into place. Jacked and bored pipes with a diameter of 24" or less do not require pipe ties.
  - Nuts and washers are not required on Jacked and Bored pipes or pipes with a 24" diameter or less. Where nuts and washers are not used, the tie bars shall be inserted and grouted into place.
  - Ties are only for holding pipe or RCB sections together, not for pulling sections tight.
  - Tie bolt assembly shall be hot dip galvanized in accordance with AASHTO M232.
  - Holes in pipes to accommodate tie bolts can be precast or drilled. Tapered holes are permitted when precast. Holes shall have a diameter  $\frac{1}{4}$ " larger than the diameter of the thread. Holes in precast RCB's shall contain cast-in bolt sleeves with an inside diameter of 1  $\frac{1}{4}$ ".
  - The contractor has the option of selecting the type of tie bolt used from those shown.
  - The cost of precasting or drilling the required holes and furnishing and installing the tie bolts shall be included in the price bid for the appropriate conduit or RCB pay item.
  - All centerline and approach RCP culvert joints shall be tied. Storm drain systems shall have the first three joints including the end section of all free ends tied. Free ends are defined as any storm drain end which does not terminate at an inlet or manhole. Outfall culverts with end sections which drain adjacent ditches are examples of free ends.
  - Place joint wrap prior to installing ties. Overlap the joint by 12" in both directions.
  - Tie bolts shall conform to ASTM A 36. Nuts shall be heavy hex and conform to ASTM A 563. Washers shall conform to ASTM F 436, Type 1. Welded pipe sleeves and cast-in bolt sleeves shall conform to ASTM A 53, Grade B.
  - RCB tie locations shall be as shown on the plans.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
3-18-14	
REVISIONS	
DATE	CHANGE
7-21-15 6-6-17	Note 8 Notes 2-11, Table, Title, Labels

This document was originally issued and sealed by Jonathan David Ketterling, Registration Number PE-4684, on 6/6/2017 and the original document is stored at the North Dakota Department of Transportation



STANDARD MONUMENTS AND RIGHT OF WAY MARKERS

NOTES:


Construct and install Alignment Monuments, Iron Pin Reference Monuments, Iron Pin R/W Monuments, and Right of Way Markers (witness posts) according to Section 720 of the Standard Specifications.

ALIGNMENT MONUMENTS: Place Iron Pin or Precast Concrete Alignment Monuments with aluminum caps on the centerline alignment PI's, section corners, quarter corners, section line crossings, quarter line crossings, and at curve points (PC's, PT's, TS's, and ST's) on the centerline.


IRON PIN R/W MONUMENT: Place Iron Pins with aluminum caps (No. 5 X 18") at breaks on the Right of Way line, and at curve points (PC's, PT's, TS's and ST's) on the Right of Way line.

IRON PIN REFERENCE MONUMENT: Place Iron Pins without aluminum caps (No. 5 X 18") as reference monuments on the Right of Way line at section corners, quarter corners, section line crossings, and quarter line crossings.

R/W MARKERS (WITNESS POST) WITHIN DRIVEWAYS: If a single iron Pin R/W or Reference Monument is within a driveway, place right of way marker (witness post) 50 feet back, in stationing, from the Iron Pin Monument along the R/W line. If R/W break is within a driveway, place right of way markers (witness posts) 50 feet back, or ahead from respective Iron Pin R/W Monuments along the R/W lines. Maintain Iron Pin R/W or Reference Monument original position within driveway.




MARKING DETAIL



RECYCLED PLASTIC  
RIGHT OF WAY MARKER  
(WITNESS POST) DETAILS

&


IRON PIN REFERENCE AND R/W  
MONUMENT DETAILS




SIGN DETAIL

Black letters on orange high intensity background sheeting meeting ASTM D-4956 Type III or higher on 80 gauge 5052-H38 aluminum. Silk screen graphics. One color print. Attach sign by drilling two holes in the face of the post (side facing the private owner, away from the Department of Transportation right of way). Put inserts into the holes and mount the sign with #4 vandal proof screws. Install sign 2" from top of post.


ALIGNMENT MONUMENT DETAILS




IRON PIN  
(Within Finished Roadway Surface)



IRON PIN  
(Within Finished Roadway Surface) (Outside Finished Roadway Surface)  
(Inside R/W Limits)




PRECAST CONCRETE  
(Outside Finished Roadway Surface)  
(Inside R/W Limits)




IRON PIN  
(Outside Finished Roadway Surface)  
(Outside R/W Limits)


VARIOUS MONUMENT AND MARKER PLACEMENTS




R/W BREAKS  
SECTION LINE CROSSINGS  
QUARTER LINE CROSSINGS




SECTION CORNERS  
QUARTER CORNERS



CURVE POINTS:  
PI  
SPIRAL CURVE (TS, ST)  
SIMPLE CURVE (PC, PT)



INTERSECTION OF HIGHWAYS  
FLARED R/W BREAKS



DIVIDED HIGHWAYS  
SECTION CORNERS  
QUARTER CORNERS

LEGEND

- Iron Pin Reference Monument
- ⊙ R/W Marker (witness post)
- Alignment Monument
- Iron Pin R/W Monument


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-3-2013	
REVISIONS	
DATE	CHANGE
11/12/13	Note for SIGN DETAIL modified to meet ASTM D-4956 Type III or higher on 80 gauge 5052-H38
10/17/17	Updated to active voice.

This document was originally issued and sealed by  
Roger Weigel  
Registration Number  
PE- 2930 ,  
on 10-17-2017 and the original document is stored at the  
North Dakota Department  
of Transportation



INLET - CATCH BASIN

D-722-1A



NOTES:

1. Use of other castings, similar in dimension, is allowed if the casting conforms to the riser section and has a grate style specified in the plans, meeting or exceeds the waterway area listed. Modifications to the inlet to facilitate similar castings are only allowed with written approval from the Engineer.
2. Use castings manufactured in accordance with AASHTO M306-09. Use metal conforming to AASHTO M105 Class 35B in the manufacture of castings.
3. Use class AE concrete precast or cast-in-place bases constructed in accordance with NDDOT Standard Specifications. Use aggregate size approved by the Engineer.
4. Construct precast concrete risers in accordance with AASHTO M199.
5. On projects with PCC pavement, construct inlet risers 4 to 5 inches below final elevation and adjust to final grade with adjusting rings, masonry or cast-in-place concrete after paving. Include all costs for this adjustment in the price bid for the inlet.
6. Use Grade 60 reinforcing steel.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
05-14-13	
REVISIONS	
DATE	CHANGE
6-24-14	Revised Note 3.
10-17-17	Updated to active voice.

This document was originally issued and sealed by  
Roger Weigel,  
Registration Number  
PE-2930,  
on 10-17-2017 and the original document is stored at the  
North Dakota Department  
of Transportation



D-722-1B



## PAY ITEMS

48 in. Riser	[	Inlet Special - Type 1	48 in.	.....	Ea.	
		Inlet Special - Type 2	48 in.	.....	Ea.	
		Inlet Special Mountable - Type A	48 in.	.....	Ea.	
		Inlet Special Mountable - Type B	48 in.	.....	Ea.	
		Inlet Special Catch basin	6 in. beehive 48 in.	.....	Ea.	
		Inlet Special Catch basin	9 in. beehive 48 in.	.....	Ea.	
60 in. Riser	[	Inlet Special - Type 1	60 in.	.....	Ea.	
		Inlet Special - Type 2	60 in.	.....	Ea.	
		Inlet Special Mountable - Type A	60 in.	.....	Ea.	
		Inlet Special Mountable - Type B	60 in.	.....	Ea.	
		Inlet Special Catch basin	6 in. beehive 60 in.	.....	Ea.	
		Inlet Special Catch basin	9 in. beehive 60 in.	.....	Ea.	
72 in. Riser	[	Inlet Special - Type 1	72 in.	.....	Ea.	
		Inlet Special - Type 2	72 in.	.....	Ea.	
		Inlet Special Mountable - Type A	72 in.	.....	Ea.	
		Inlet Special Mountable - Type B	72 in.	.....	Ea.	
		Inlet Special Catch basin	6 in. beehive 72 in.	.....	Ea.	
		Inlet Special Catch basin	9 in. beehive 72 in.	.....	Ea.	
			Inlet Special Catch basin - Type A	72 in.	.....	Ea.

NOTES:

1. For inlet casting details, see Standard Drawings D-722-1, D-722-21A, D-722-2, and D-722-3. Other castings, similar in dimension, may be used provided the casting meets the requirements set forth in the referenced Standard Drawings. The grate style shall be as specified on the plans and included in the price bid for "Inlet Special - (casting type & riser size)".
2. Metal used in the manufacture of castings shall conform to AASHTO M-105, Class 35B.
3. The Class of concrete, aggregate size, and methods of construction for the manhole riser, cover, and base shall be as detailed in Standard Drawing D-722-5.
4. See Standard Drawing D-722-5 for manhole riser, cover, and base details, dimensions, and reinforcement requirements.
5. The distance between the  $\varnothing$  of the cover opening and the  $\varnothing$  of the storm drain shall be noted on the Plan & Profile sheets.
6. Manhole steps, if noted on the Plan and Profile sheets, shall be constructed per Standard Drawing D-722-5.
7. On projects with P.C.C pavement, all risers shall be constructed 4 to 5 inches below final elevation and adjusted to final elevation after paving. Adjustments may be made with adjusting rings or cast-in-place concrete. All costs for this adjustment shall be included in the price bid for "Inlet - Special, (casting type & riser size)".

NORTH DAKOTA	
DEPARTMENT OF TRANSPORTATION	
03-18-14	
REVISIONS	
DATE	CHANGE









This document was originally issued and sealed by Terrence R. Udland Registration Number PE- 2674 , on 03-18-14 and the original document is stored at the North Dakota Department of Transportation



INLET - TYPE 2

D-722-2

Pay Items  
Inlet - Type 2 .....Ea.  
Inlet - Type 2, Double.....Ea.



- Notes:
1. Drainage structure castings shall be manufactured in accordance with AASHTO M306. Metal used in the manufacture of castings shall conform to AASHTO M105 Class 35B.
  2. Other castings, similar in dimension, may be used if the casting conforms to the riser section and has the grate style as specified in the plans. If modifications to the inlet riser are required to accommodate similar castings, the contractor must receive written approval from the engineer.
  3. Precast risers shall be constructed in accordance with ASTM C858.
  4. The contractor shall have the option of using precast or poured in place bases. Cast in place concrete shall be Class AE-3. Construction shall be in accordance with section 722 of the Standard Specifications.
  5. On projects with P.C.C. pavement, all inlet risers or barrels shall be constructed 4 to 5 inches below final elevation and adjusted to final grade after paving. Adjustment may be done with adjusting rings or cast-in-place concrete. All costs for this adjustment shall be included in the price bid for the inlet.
  6. Welded wire reinforcing fabric shall conform to AASHTO M55 Grade 65.
  7. The deformed reinforcing steel shall conform to AASHTO M31.



NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
05-12-14	
REVISIONS	
DATE	CHANGE
07-07-14	Revised Note 4

This document was originally issued and sealed by  
TERRENCE R. UDLAND  
Registration Number  
PE-2674,  
on 07/07/14 and the original document is stored at the  
North Dakota Department  
of Transportation



INLET - SLOTTED DRAIN

D-722-3A



- NOTES:
1. Corrugated steel pipe shall conform with applicable sections of NDDOT Standard Specifications and AASHTO M 36.
  2. Slotted grate assembly, including rebar and steel plate end, shall be a weldable grade of steel complying with the mechanical requirements of AASHTO M 183 and shall be hot dip galvanized in accordance with AASHTO M 111.
  3. All labor, equipment and materials necessary to complete the work, except for the concrete curb and gutter and the inlets, shall be included in the price bid for "Inlet - Slotted Drain (Size)".
  4. The non-slotted corrugated pipe angled fitting (see Table 1) shall not be paid for separately but shall be included in the price bid for the Inlet - Slotted Drain.
  5. Construction shall be in accordance with Sections 714 and 722 of the Standard Specifications.

PAY ITEMS

Inlet - Slotted Drain, 12 In	L.F.
Inlet - Slotted Drain, 15 In	L.F.
Inlet - Slotted Drain, 18 In	L.F.
Inlet - Slotted Drain, 24 In	L.F.
Inlet - Slotted Drain, 30 In	L.F.
Inlet - Slotted Drain, 36 In	L.F.






TABLE 1  
CSP Angled Fitting Dimensions

Slotted Drain Pipe Dia (in.)	A (in.)	B (in.)							
		Inlet		Inlet - Special					
		Type 1	Type 2	Type 1 48"	Type 1 60"	Type 1 72"	Type 2 48"	Type 2 60"	Type 2 72"
12	12	18(A)	18	35	41	42	31	36	37
15	12	18(A)	18	36	42	43	31	37	38
18	12		18	37	42	43	32	38	39
24	24				44	45		39	41
30	24				45	46		41	42
36	24					48			44

(A) 135° min. angle required between CSP and Storm Pipe for Type 1 Inlet - see Type 1 Inlet Connection Detail)



TYPE 1 INLET CONNECTION DETAIL  
For 12" and 15" Slotted Drain Installation



SLOTTED GRATE SECTION


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
03-17-2014	
REVISIONS	
DATE	CHANGE

This document was originally issued and sealed by Terrence R. Udland Registration Number PE- 2674 , on 03-17-2014 and the original document is stored at the North Dakota Department of Transportation




MANHOLE DETAILS


D-722-5




ELEVATION



TOP



LID



FRAME

MANHOLE CAST IRON RING & COVER

PRECAST MANHOLE COVERS

RISER DIAMETER	COVER DIAMETER	WEIGHT OF SECTION	T	K	L	BOTTOM * BARS	TOP * BARS
48"	58"	1,080 Lb	6"	6"	8"	#4 at 6"	—
54"	65"	1,910 Lb	8"	6"	8"	#4 at 6"	—
60"	72"	2,430 Lb	8"	7"	9"	#4 at 6"	#4 at 11"
66"	79"	3,010 Lb	8"	7"	9"	#4 at 6"	#4 at 11"
72"	86"	3,640 Lb	8"	8"	10"	#4 at 6"	#4 at 11"
84"	100"	5,060 Lb	8"	9"	11"	#5 at 6"	#5 at 11"
96"	114"	6,695 Lb	8"	9"	11"	#5 at 6"	#5 at 11"
108"	128"	12,810 Lb	12"	10"	12"	#5 at 6"	#5 at 11"
120"	142"	15,900 Lb	12"	11"	13"	#5 at 6"	#5 at 11"

\* - Place reinforcement listed in each direction.


MANHOLE BASES

RISER DIAMETER	BASE DIAMETER	WEIGHT OF SECTION	A	BARS *
48"	66"	1,785 Lb	6"	#4 at 12"
54"	72"	2,830 Lb	8"	#4 at 12"
60"	78"	3,320 Lb	8"	#4 at 12"
66"	86"	4,035 Lb	8"	#4 at 12"
72"	92"	4,620 Lb	8"	#4 at 12"
84"	107"	6,245 Lb	8"	#4 at 12"
96"	120"	7,855 Lb	8"	#4 at 12"
108"	132"	14,255 Lb	12"	#4 at 8"
120"	148"	17,925 Lb	12"	#4 at 8"


\* - Place reinforcement listed in each direction.

NOTES:


1. Use class AE concrete precast or cast-in-place bases constructed in accordance with NDDOT Standard Specifications. Use aggregate size approved by the engineer.
2. Use precast concrete manholes, risers and steps conforming to AASHTO M199.
3. Reinforce precast concrete bases and covers as shown in the table for the corresponding riser diameter.
4. Use Grade 60 reinforcing steel.
5. Cut or Precast manhole riser bottoms square to fit the manhole base. Grout joint between base and riser with cement mortar.
6. The manhole riser length listed in the plans is based on a 7" manhole casting, plus 2 concrete adjusting rings (5"), plus the "T" dimension shown in the Precast Manhole Covers table.
7. Use corrosion resistant manhole steps with a minimum 800 pound vertical load resistance and a minimum 400 pound horizontal pull-out resistance. Use configuration of steps approved by the Engineer.
8. Precast concrete manhole covers shown are designed for an HS-20 wheel load and maximum fill height of 15'-0". Special design is required for heavier wheel loads and/or greater fill heights.
9. Use of other castings, similar in dimension, is allowed if the casting conforms to the manhole cover and has a lid style specified in the plans. Modifications to the manhole cover to facilitate similar castings are only allowed with written approval from the Engineer.
10. Use castings manufactured in accordance with AASHTO M306-09. Use metal conforming to AASHTO M105 Class 35B in the manufacture of castings.




TOP VIEW




SECTION A-A  
PRECAST MANHOLE BASE




TOP VIEW



SECTION B-B  
PRECAST COVER



TOP VIEW


















STEP DETAIL

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION		This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930 , on 10-17-2017 and the original document is stored at the North Dakota Department of Transportation
05-14-2013		
REVISIONS		
DATE	CHANGE	
6-24-14	Revised notes 1 & 6, added dimensions to Elev. drawing.	
10-17-17	Updated to active voice.	



### Curb & Gutter and Valley Gutter



- NOTES:

1. Use Curb and Gutter Type 1 (Sec. A & B). Use section "A" with (-) pavement slopes and section "B" with (+) pavement slopes.
2. Contraction Joints: Tool the Curb & Gutter 2" as shown on the contraction joint details.
3. Isolation Joints: Use  $\frac{3}{4}$ " expansion joint filler for isolation joint material. Form the backer rod and joint sealant opening with a pre-cut piece of wood or other material approved by the engineer. Dowel supports are not required on the second pour at a cold joint. Install plastic or metal caps and greased dowels in the cold joint for the second pour.
4. Joint Spacing: For hot bituminous pavements use a 10' max joint spacing for the curb and gutter with panels on each side of the inlets. For concrete pavements match the joint spacing for the curb and gutter to the pavement joint on PCC Pavements (approximately 15' spacing.)
5. Joint sealing: Seal contraction and isolation joints as shown in the details. Use joint sealant for contraction joints that conforms to section 826.02B. Use sealant for expansion joints specified in note 3 above. Tool and install sealant in accordance with the manufacturer's recommendations.
6. Face of Gutter Depth: For hot bituminous pavement use 7" gutter depth as shown. For PCC pavements, match the gutter depth to the depth of adjacent PCC pavement or to construct a 7" depth as shown.
7. Tie curb and gutter to abutting PCC pavement with No. 3 bars, 1'-6" in length, spaced at 4' centers.
8. On street returns and other locations where new curb and gutter ends and does not abut existing curb and gutter, taper the last two (2) feet of the curb from 6" in height to 0". Install a 1/2" premolded full depth isolation joint, the same shape as the curb and gutter just ahead of the taper. Install an 18" tie bar across the joint.
9. Valley Gutter Joints: Form, saw, or score  $\frac{1}{8}$ " min. to  $\frac{3}{8}$ " max. width contraction joints (a minimum 2" depth) at approx 10' intervals. Seal the joints with hot poured elastic type joint sealer (Section 826.02A.2 of the Standard Specifications.) Include all costs for the joint and sealant in the price bid for Valley Gutter.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-7-2013	
REVISIONS	
DATE	CHANGE
10-17-17	Updated to active voice.

This document was originally  
issued and sealed by  
Roger Weigel  
Registration Number  
PE- 2930 ,  
on 10-17-2017 and the original  
document is stored at the  
North Dakota Department  
of Transportation



CONCRETE DRIVEWAY - URBAN


D-750-1

NOTES:

- 1. See Standard D-748-1 for curb and gutter isolation joint detail. On PCC roadways, match curb and gutter joints with pavement joints, as much as practical.
- 2. Joint Spacing: Use 1 center contraction joint on driveways 20' width or less, 2 center contraction joints for driveways 20' to 30' width, and 3 center contraction joints for driveways greater than 30' width.  
  
Saw or groove contraction joints a minimum depth of 1/3 the depth of the concrete.  
  
Use isolatoin joints between separately poured concretes, or between old and new concrete.  
  
Seal joints with hot pour bituminous filler or low modulus silicone. Install and tool sealant according to manufacturer's recommendations.  
  
Include all costs for labor, equipment, and material to construct and seal joints in the price bid for the driveway.
- 3. Include all costs for gutter-Type 1 in the unit price bid for "Curb and Gutter-Type 1".
- 4. Use 6" driveway unless otherwise specified.
- 5. Place 4" base material under concrete driveway. Include all costs for labor and materials necessary to place the base material in the price bid for Salvage Base Course or Aggregate Base Course CL 5.
- 6. Construct sidewalk behind a driveway to the same thickness as the driveway. The Engineer will measure it as driveway concrete.




Section A-A




6" Section B-B

Keyed Construction Joint or Tied Joint (#3 x 1'-6" Bars) 4' on center




8" Section B-B

Keyed Construction Joint or Tied Joint (#3 x 1'-6" Bars) 4' on center




Driveway Type 1


Detail A




Sag - Driveway Type 1




Summit - Driveway Type 1




Driveway Type 2A




Sag - Driveway Types 2A & 2B




Summit - Driveway Types 2A & 2B




Driveway Type 2B




Sag - Driveway Type 3



Summit - Driveway Type 3



Driveway Type 3



Typical Isolation Joint Seal (longitudinal and transverse)

Driveway ADT	Grade G1		Dimension (L) ft.		Grade Changes (D)	
	Desirable	Maximum	Desirable	Maximum	Desirable	Maximum
(0-500)	5%	12% or controlled by vehicle clearance	12	6	6%	15% or controlled by vehicle clearance
(500-1500)	3%	8%	20	20	3%	6%
(> 1500)	2%	5%	40	40	0%	3%

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
2-13-2014	
REVISIONS	
DATE	CHANGE
10-17-17	Updated to active voice.

This document was originally issued and sealed by  
Roger Weigel  
Registration Number  
PE- 2930,  
on 10-17-2017 and the original document is stored at the  
North Dakota Department  
of Transportation




SIDEWALK

D-750-2




NOTES:

1. Curb ramp and detectable warning panel layouts for informational purposes only. See Standard Drawing D-750-3 for curb ramp and detectable warning panel details.
2. Joint Spacing: Vary transverse contraction joint spacing from 4' to 6' to create approximate square panels.  
  
Use longitudinal contraction joints when sidewalk width is 8' or greater, and space at half the sidewalk width.  
  
Saw or groove contraction joints to a minimum depth of 1/3 the depth of the concrete.  
  
When sidewalk is adjacent to curb & gutter, vary the sidewalk joint spacing to match curb & gutter joints.  
  
Use isolation joints between separate concrete pours, or between old and new concrete.
3. Include all costs for labor, equipment, and material necessary to construct contraction and isolation joints in the price bid for sidewalk concrete.
4. Use 4" sidewalk concrete thickness unless otherwise specified.
5. Use 4" base material thickness unless otherwise specified. Include all costs for labor and materials necessary to place the base material in the price bid for "Salvage Base Course" or "Aggregate Base Course CL 5."  
  
Modify existing ground slope with landscaping as needed. If not possible, such as adjacent buildings, use a vertical curb as shown in the detail below. The Engineer will measure curb at the unit price bid for "Curb - Type I" per lineal foot.
6. Sidewalk Width & Grade: Provide a continuous 4' min clear width pedestrian access route with max 2% concrete cross slope, excluding flares. The width of the curb cannot be counted as part of the pedestrian access route.

When clear width of pedestrian access routes is less than 5.0', provide passing spaces at a maximum of 200' with a minimum size of 5.0' by 5.0'.




Typical Joint Layouts




Sidewalk Width and Grade



Utility Blockout




Sidewalk with Curb Detail  
(Building face application)




Sidewalk Detail  
(Installed adjacent to curb and gutter)




"L" Bar Detail  
#3 Bar



Sidewalk with Curb Detail  
(Adjacent property application)



Concrete Median Detail



Typical Isolation Joint Seal  
(longitudinal and transverse)






NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
11-26-13	
REVISIONS	
DATE	CHANGE
10-17-17	Updated to active voice.
09-05-18	Added sidewalk details for width and grade and passing lane requirements.




This document was originally issued and sealed by  
Roger Weigel,  
Registration Number  
PE-2930,  
on 09-05-2018 and the original document is stored at the  
North Dakota Department  
of Transportation



D-750-3

1. Ramp width is the useable portion of the ramp, excluding flares. Match curb ramp width to existing sidewalk width (4' minimum or 5' for island ramps). Match ramp width to existing shared use path width. Maximum ramp length is 15'.
2. Desirable turning space size is 5' x 5' or larger with a minimum size of 4' x 4'. The maximum slope for turning spaces is 2% in any direction.
3. Match detectable warning panel width to ramp width. Radial panels are allowed. Place detectable warning panel within the lower turning space.
4. Provide a continuous 4' minimum width pedestrian access route with max 2% concrete cross slope, excluding flares.
5. Modify existing ground slope with landscaping, as needed. If not possible, such as adjacent buildings, use a vertical curb as shown in the detail below. The Engineer will measure curb at the unit price bid for "Curb - Type I" per lineal foot.
6. Islands: If the grade of the island curb ramp is less than 2%, provide a minimum distance of 2' between warning panels. If the grade of the Island curb ramp is steeper than 2%, provide a turning space between the ramps.

 : Detectable Warning Panel  
 : Landscaping  
 : Transitional tie-in segment if needed for retrofits. Max grade slope 8.3%.  
 : Upper Turning Space  
 : Lower Turning Space  
 0", 3", or 6" : Curb Height  
 8.3% : All slopes shown are max grades. Flatter slopes may be used.



4	
NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
11-26-13	
REVISIONS	
DATE	CHANGE
10-17-17	Updated to active voice.
09-05-18	Revised Notes, Revision for Turning Space, Added Passing Space Requirements, Turned Detectable Warning Panel


This document was originally  
issued and sealed by  
Roger Weigel,  
Registration Number  
PE-2930,  
on 09-05-2018 and the original  
document is stored at the  
North Dakota Department  
of Transportation



LETTER AND ARROW DETAILS

D-754-9


NOTE: Measure rotation angle of arrows counterclockwise from positions shown in details.




DETERMINE SIZE OF THE FRACTION AS FOLLOWS:

SYMBOL	TITLE	RATIO TO HEIGHT OF CAPITAL OR UPPER CASE
A	Letter height	1.0 of capital or upper case
B	Fraction height	1.5 X A
C	Fraction width	2.5 X A
D	Fraction width	2 X A
E	Space to next character	1 to 1.5 X A
F(A)	Length of diagonal	1.75 X A

(A) Center diagonal stroke of fraction optically.




TYPE A



TYPE B


DESIGNATION	LETTER SIZE (Upper Case)	A	B	C	D	E	F	G
ND_6IN	6"	12"	9.125"	3"	1"	0.625"	20"	13.5"
ND_8IN	8"	15.125"	11.563"	3.75"	1.313"	0.813"	25"	17"
ND_10IN	10"	18.25"	14"	4.5"	1.5"	0.75"	30"	20"
ND_12IN	12"							
ND_13IN	13.3"							
ND_16IN	16"	22.25"	17"	5.375"	1.75"	1"	35"	25"
ND_20IN	20"							

NOTE: Arrow size on gore signs is based on the letter size of "EXIT".




TYPE D

DESIGNATION	LETTER SIZE (Upper Case)	A	B	C	D	E	F
ND_2IN	2"	2"	1.625"	0.75"	0.125"	0.125"	3"
ND_4IN	4"	4"	3.313"	1.5"	0.25"	0.25"	6"
ND_6IN	6"	6"	4.875"	2.25"	0.375"	0.375"	9"
ND_8IN	8"	8"	6.625"	3"	0.5"	0.5"	12"
ND_10IN	10"	10"	8.375"	3.75"	0.75"	0.75"	15"
ND_12IN	12"	12"	10"	4.5"	0.875"	0.875"	18"




TYPICAL SPACING




ROUNDBOUT

DESIGNATION	LETTER SIZE (Upper Case)	A	B	C	D	E	F	G	H	J	K	L	M
ND_6IN	6"	5.25"	4.688"	2"	0.375"	0.375"	6.5"	10.125"	6.094"	10.75"	1.168"	1.25"	2.625"
ND_8IN	8"	7"	5.75"	2.625"	0.5"	0.5"	8.688"	13.5"	8.166"	14.333"	1.557"	1.667"	3.5"



SPECIAL

DESIGNATION	A	B	C	D	E	F	USES
ND_0.75IN	2"	1.625"	0.75"	0.125"	0.125"	7.75"	Parking Signs (Regulatory)
ND_2.625IN	7"	5.75"	2.625"	0.5"	0.5"	15"	Frontage Road Signs



DOWN ARROW


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-3-11	
REVISIONS	
DATE	CHANGE
7-8-14	Revised gore sign and added 4" D & D arrow
5-4-16	Revised Distance & Destination and Typical Spacing details
4-23-18	Revised arrow details
8-30-18	Updated notes to active voice.

This document was originally issued and sealed by Roger Weigel, Registration Number PE- 2930, on 8-30-2018 and the original document is stored at the North Dakota Department of Transportation




Notes:

- 1. Curbed Roadways: Use a 3' clearance from face of the curb except where right of way or sidewalk width is limited; Use a minimum 2' clearance. Increase the horizontal clearance if required to maintain a minimum sidewalk clear width of 4' from the sign support, not including any attached curb.
- 2. Minimum vertical clearance: Provide at least 5' measured from the bottom of the sign to the edge of the driving lane or auxiliary lane at the side of the road in rural districts. Provide at least 7' clearance to the bottom of the sign, where parking or pedestrian movements occur.  
  
Install signs on expressways a minimum height of 7'.  
  
Install adopt-a-highway signs on Freeways at least 7' above the edge of the driving lane.  
  
Maximum vertical clearance is 6" greater than the minimum vertical clearance.
- 3. Offset signs: Use a vertical clearance of 5' above the edge of the driving lane for signs placed 30 feet or more from the edge of the traveled way.
- 4. Provide a horizontal clearance from edge of shared use path to edge of sign of 3', except where width is limited. Provide a minimum clearance of 2'.




Stop Sign Location  
Wide Throat Intersection  
Use layout for the placement of "Stop" signs.

Radius ft.	Y-max. ft.	Y-min. ft.
40	50	15
45	50	18
50	50	21
55	50	25
60	50	28
65	50	32
70	50	35
75	50	39
80	50	43




Typical Section (without curb)

Horizontal Clearance Table	
Shoulder Width ft	Offset ft
0 to 2	16
>2 to 4	18
>4 to 6	20
>6 to 8	22
>8 to 10	24



Typical Section (with curb)  
Residential or Business District





NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-3-13	
REVISIONS	
DATE	CHANGE
7-8-14 8-30-18	Revised note 2, added note 4, Updated notes to active voice.

This document was originally issued and sealed by  
Roger Weigel  
Registration Number  
PE- 2930 ,  
on 8-30-2018 and the original document is stored at the  
North Dakota Department  
of Transportation



Number of Posts	Telescoping Perforated Tube					
	Post Size In.	Wall Thick-ness Gauge	Sleeve Size In.	Wall Thick-ness Gauge	Slip Base	Anchor Size Without Slip Base In.
1	2	12			No	2 1/4
1	2 1/4	12			No	2 1/2
1	2 1/2	12			(B)	3(C)
1	2 1/2	10			Yes	7
1	2 1/4	12	2 1/2(D)	12	Yes	7
1	2 1/2	12	2 1/4	12	Yes	7
2	2 1/2	10			Yes	7
2	2 1/4	12	2 1/2(D)	12	Yes	7
2	2 1/2	12	2 1/4	12	Yes	7
3 & 4	2 1/2	12			Yes	7
3 & 4	2 1/2	10			Yes	7
3 & 4	2 1/2	12	2 1/4	12	Yes	7
3 & 4	2 1/4	12	2 1/2(D)	12	Yes	7
3 & 4	2 1/2	10	2 1/8	10	Yes	7


(B) - Provide a shim as specified by the manufacturer when placing 2 1/2", 12 gauge posts in standard soils without breakaway bases. Provide breakaway base when placing the support in weak soils. The Engineer will determine if the soils are weak. Weak soils are classified as boggy, wet, or loose soil areas.  
(C) - 3" anchor unit  
(D) - 2 1/2" x 12 ga. x 18" minimum length external sleeve required.




MULTI-DIRECTIONAL SLIP BASE ASSEMBLY:  
Inserting 2 1/2" x 12 ga with 2 1/4" x 12 ga and inserting 2 1/2" 10 ga with 2 3/8" x 10 ga to achieve higher load ability is allowed.

#### SHOULDER BOLT



Shimming agent to reduce tolerance between 3" anchor unit and 2 1/2" post.  
(use standard 3/8" diameter grade 8 bolt with proper shim)



#### Mounting Details Perforated Tube



#### SLIP BASE FOR 2 1/2" POST




Properties of Telescoping Perforated Tubes							
Tube Size In.	Wall Thickness in.	U.S. Standard Gauge	Weight Per Foot Lbs.	Moment of Inertia In. <sup>4</sup>	Cross Sect. Area In. <sup>2</sup>	Section Modulus In. <sup>3</sup>	
1 1/2 x 1 1/2	0.105	12	1.702	0.129	0.380	0.172	
2 x 2	0.105	12	2.416	0.372	0.590	0.372	
2 1/4 x 2 1/4	0.105	12	2.773	0.561	0.695	0.499	
2 3/8 x 2 3/8	0.135	10	3.432	0.605	0.841	0.590	
2 1/2 x 2 1/2	0.105	12	3.141	0.804	0.803	0.643	
2 1/2 x 2 1/2	0.135	10	4.006	0.979	1.010	0.783	

The 2 3/8" size 10 gauge is shown as 2.19" size on the plans;  
The 2 1/2" size is shown as 2.51" size on the plans.

#### NOTE:

- 4" Vertical clearance of anchor or breakaway base. The 4" x 60" measurement is above and below post location and also back and ahead of post.
- Provide 7 gauge HRPO commercial quality ASTM A569 and 3" x 3" x 7" gauge ASTM A500 grade B anchor material with 43.9 KSI yield strength and 59.3 KSI tensile strength. Hot dip galvanize anchor per ASTM A123/153. Tolerances on anchor unit and slip base bottom assembly are +/- 0.005" unless otherwise noted.
- Eliminate wings when anchor is used in concrete sidewalk.
- Provide a minimum 8' distance between the first and fourth post on four post signs.
- Install in accordance with manufacturers recommendation.
- Use a minimum 1/2" diameter x 4" grade 8 concrete fastener for surface mount breakaway base.



NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-8-09	
REVISIONS	
DATE	CHANGE
8-30-18	Updated notes to active voice & corrected max height of base.

This document was originally issued and sealed by  
Roger Weigel,  
Registration Number  
PE- 2930,  
on 8-30-2018 and the original document is stored at the  
North Dakota Department  
of Transportation



Breakaway Coupler System  
for Perforated Tubes



Notes:

- 4" Vertical clearance of anchor or breakaway base. The 4" x 60" measurement is above and below post location and also back and ahead of post.
- Use anchor unit of the same size and specification as the post.
- Provide a minimum 8' distance between the first and fourth post on four post signs.
- Use the breakaway base system on standard D-754-24 or the breakaway coupling system manufactured from material meeting the requirements of ASTM A325 fasteners with the special requirements specified by DENT BREAKAWAY IND., INC. which meets the test requirements of NCHRP Report 350.

Number of Posts	Telescoping Perforated Tube						
	Post Size In.	Wall Thick-ness Gauge	Sleeve Size In.	Wall Thick-ness Gauge	Slip Base	Anchor Size Without Slip Base In.	Anchor Wall Thickness Gauge
1	2	12			No	2¼	12
1	2¼	12			No	2½	12
1	2½	12			(B)	3(C)	7
1	2½	10			Yes		7
1	2¼	12	2	12	Yes		7
1	2½	12	2¼	12	Yes		7
2	2½	10			Yes		7
2	2¼	12	2	12	Yes		7
2	2½	12	2¼	12	Yes		7
3 & 4	2½	12			Yes		7
3 & 4	2½	10			Yes		7
3 & 4	2½	12	2¼	12	Yes		7
3 & 4	2¼	12	2	12	Yes		7
3 & 4	2½	10	2¾	10	Yes		7



(B) - 2½" 12 gauge posts do not need breakaway bases unless support is placed in boggy, wet, or loose soil areas.

(C) - 3" anchor unit



Section C-C

Max protection of the stub post is 4" above a 60" chord aligned radially to the center line of the highway and connecting any point, within the length of the chord, on the ground surface on one side of the support to a point in the ground surface on the other side.




NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-3-2013	
REVISIONS	
DATE	CHANGE
8-30-18	Updated notes to active voice.


This document was originally issued and sealed by  
Roger Weigel  
Registration Number  
PE-2930,  
on 8-30-2018 and the original document is stored at the  
North Dakota Department  
of Transportation



Mounting Details Perforated Tube




Side View




Top View

STRINGER MOUNTING  
(WITH STRINGER IN FRONT OF POST)




Side View




Top View


STRAP DETAIL




STREET NAME SIGNS AND ONE WAY SIGNS  
SINGLE POST ASSEMBLY  
ONE STRINGER OR BACK TO BACK MOUNTING



ANCHOR UNIT AND POST ASSEMBLY




BOLT MOUNTING



Top View

BACK TO BACK MOUNTING



Properties of Telescoping Perforated Tubes							
Tube Size In.	Wall Thickness In.	U.S. Standard Gauge	Weight Per Foot Lbs.	Moment of Inertia In. <sup>4</sup>	Cross Sect. area In. <sup>2</sup>	Section Modulus In. <sup>3</sup>	
1 1/2 x 1 1/2	0.105	12	1.702	0.129	0.380	0.172	
2 x 2	0.105	12	2.416	0.372	0.590	0.372	
2 1/4 x 2 1/4	0.105	12	2.773	0.561	0.695	0.499	
2 3/16 x 2 3/16	0.135	10	3.432	0.605	0.841	0.590	
2 1/2 x 2 1/2	0.105	12	3.141	0.804	0.803	0.643	
2 1/2 x 2 1/2	0.135	10	4.006	0.979	1.010	0.783	

The 2 3/16" size 10 gauge is shown as 2.19" size on the plans.  
The 2 1/2" size is shown as 2.51" size on the plans.

Note:

- Horizontal stringers - Use perforated tubes or 1 3/4" x 3/16" thick, 1.08 lbs./ft aluminum or 3.16 lbs./ft steel z bar stringers.
- Use minimum outside diameter 15/16" ± 1/16" and 10 gauge thick metal washers on sign face.
- Place No Parking signs with directional arrows at a 30 to 45 degree angle with the line of traffic flow. Turning the support to the correct angle for No Parking signs requiring the above angles is allowed. If the No Parking sign is placed with another sign that requires placement at a 90 degree angle with the line of traffic flow, use the detailed angle strap to mount the No Parking sign. Use flat washers and lock washers with all nylon washers.
- Punching the sign backing and placing the bolt through the sign, the stringer and the post is allowed in lieu of using the bent bolt to attach the post to the stringer.
- 4" vertical clearance of anchor or breakaway base. The 4" x 60" measurement is above and below post location and also back and ahead of post.

Number of Posts	Telescoping Perforated Tube						
	Post Size In.	Wall Thick-ness Gauge	Sleeve Size In.	Wall Thick-ness Gauge	Slip Base	Anchor Size Without Slip Base In.	Anchor Wall Thick-ness Gauge
1	2	12			No	2 1/4	12
1	2 1/4	12			No	2 1/2	12
1	2 1/2	12			(B)	3(C)	7
1	2 1/2	10			Yes		7
1	2 1/4	12	2 1/2(D)	12	Yes		7
1	2 1/2	12	2 1/4	12	Yes		7
2	2 1/2	10			Yes		7
2	2 1/4	12	2 1/2(D)	12	Yes		7
2	2 1/2	12	2 1/4	12	Yes		7
3 & 4	2 1/2	12			Yes		7
3 & 4	2 1/2	10			Yes		7
3 & 4	2 1/2	12	2 1/4	12	Yes		7
3 & 4	2 1/4	12	2 1/2(D)	12	Yes		7
3 & 4	2 1/2	10	2 3/16	10	Yes		7




(B) - When placing 2 1/2", 12 gauge posts in standard soils without breakaway bases, provide a shim as specified by the manufacturer. Provide breakaway base when placing the support in weak soils. Engineer will determine if soils are weak. Weak soils are classified as boggy, wet, or loose soil areas.  
(C) - 3" anchor unit  
(D) - 2 1/2" x 12 ga. x 18" minimum length external sleeve required.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
8-8-09	
REVISIONS	
DATE	CHANGE
7-8-14 8-30-18	Revised Note 3, Updated notes to active voice.

This document was originally issued and sealed by  
Roger Weigel,  
Registration Number  
PE- 2930 ,  
on 8-30-2018 and the original document is stored at the  
North Dakota Department  
of Transportation




SIGN PUNCHING, STRINGER AND SUPPORT LOCATION  
DETAILS REGULATORY, WARNING AND GUIDE SIGNS




Assembly No. 6



- Notes:
1. Use 0.100 inch minimum thickness sign backing material.
  2. Use 1½" x 1½" perforated square tube stringers.
  3. Punch holes round for ⅜" bolt.






Assembly No. 7






Assembly No. 8



Assembly No. 9



Assembly No. 10






Assembly No. 11

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
12-1-10	
REVISIONS	
DATE	CHANGE
8-30-18	Updated notes to active voice.


This document was originally issued and sealed by  
Roger Weigel,  
Registration Number  
PE- 2930,  
on 8-30-2018 and the original document is stored at the  
North Dakota Department  
of Transportation




LIGHT STANDARD, SIGNAL STANDARD,  
AND SPAN WIRE MOUNTED SIGN  
ASSEMBLY DETAIL




Section B-B  
Span Wire Mounted Sign Detail




Section A-A




Vertical Mounting  
(Use 2 clamps per sign)




Horizontal Mounting  
alternate clamp mounting  
(Use 2 clamps per sign)




Light Standard Mounted Sign Bracket Detail  
Max. 24"x30" signs (D)




Plan




Elevation




Sign Mounted Beyond End of Mast Arm Detail




Side View



Detail A




Clamp Detail




Detail B  
Steel Channel

Post Size dia.	Clamp Gauge min.
3 1/2" to 5"	11
6" to 12"	10

Clamp	
Post Size dia. in.	D in.
3 1/2	3
4	3 3/16
5	5 1/8
6	7 7/16
8	13 1/16
10	20 3/4
12	29 5/8




Plan



Elevation

Mast Arm Mounted Street Name Sign Detail



Signal Standard Mounted Sign Attachment Detail

- Notes:
- (A) Use 1 1/4"x3/16" thick 1.08 lb/ft aluminum alloy Z-bar. In place of Z-bar, use two 1 3/4"x1 3/4"x3/16" angles bolted together or a 1 1/4"x2"x.188" channel.
- (B) 3/8" U-bolt, hex. nut, lock washer, and bracket (U-bolt length depends on dia. of mast arm.)
- (C) 3/8" U-bolt, hex. nut, lock washer, and bracket (U-bolt length depends on dia. of mast arm.)
- Maximum perforated tube lengths for mounting signs beyond end of mast arm:  
2"x2" maximum support length 9.9'  
2 1/4"x2 1/2" maximum support length 12.6'  
2 1/2"x2 1/2" maximum support length 15.7'
- (D) Use galv. steel strap and sign attachment bracket similar to the one shown in the detail. Include all costs of bracket assembly in the price bid for flat sheet signs. Punch as shown on Standard Drawings. Provide a 7' minimum vertical clearance to the bottom of signs mounted on light standards.
- (E) Use metal washers and nylon washers with a minimum outside dia. of 1 5/16" ± 1/16" and 10 gauge thickness on sign face.


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-3-13	
REVISIONS	
DATE	CHANGE
8-30-18	Updated notes to active voice.

This document was originally issued and sealed by  
Roger Weigel  
Registration Number  
PE-2930,  
on 8-30-2018 and the original document is stored at the  
North Dakota Department  
of Transportation




Pavement Marking Message Details


D-762-1




22 S. F.




29 S. F.




12 S. F.



16 S. F.




27 S. F.




41 S. F.


Note: Rotate merge arrow 20° from edge of roadway.




4 S. F.



22 S. F.




34.5 S. F.



46 S. F.


Speed Limit	Chevron Width	Chevron Spacing 45° to Traffic
0-25 mph	8"	5'
30-40 mph	8"	15'
45 mph and above	12"	25'

Chevron Crosshatching Table



Centerline Pavement Marking Skip Spacing Detail


Advance Placement Distance for Railroad Warning Signs	
Posted or 85th Percentile Speed	Advance Distance
20 mph	min. 100 ft
25 mph	min. 100 ft
30 mph	min. 100 ft
35 mph	min. 100 ft
40 mph	125 ft
45 mph	175 ft
50 mph	250 ft
55 mph	325 ft
60 mph	400 ft
65 mph	475 ft
70 mph	550 ft



See Standard Drawing D-754-81


Notes:  
Mark a three lane roadway with a centerline for two-lane approach operation on the approach to a crossing. On multi-lane roads, extend the transverse bands across all approach lanes, and use individual R X R symbols in each approach lane.

See plans for correct message. Use white pavement markings unless noted otherwise.



R15-1

Railroad cross & 2 R's 3 Bands (12' lane) 60.5 S.F. 72 S.F.



Continental Crosswalk Detail

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
12-6-11	
REVISIONS	
DATE	CHANGE
10-17-17	Updated to active voice.

This document was originally issued and sealed by  
Roger Weigel,  
Registration Number  
PE-2930,  
on 10-17-2017 and the original document is stored at the  
North Dakota Department  
of Transportation



CONCRETE FOUNDATIONS  
(TRAFFIC SIGNALS & HIGHWAY LIGHTING)

NOTES:

**LIGHT & SIGNAL STANDARD FOUNDATIONS:**  
See plans for conduit size, number of bends and correct position for each foundation. When conduit does not continue beyond the foundation, conduit with a 105° bend and bushings on both ends may be substituted for the 90° bends shown. See plans for correct size & location of foundations. The grade and exact location shall be established by the Engineer in the field. All reinforcing shall be Grade 60. Tie bars shall have a minimum of a 12" lap. Reinforcing may be omitted for Type I, II, V, VI & VII signal standard foundations if the anchor bolts extend to within 3" to 6" above the bottom of the foundation. A minimum of 6 anchor bolts shall be used for cantilevered structures.

**CONTROLLER CABINET FOUNDATION PAD MOUNT**  
FOUNDATION: See plans for the number of 90° bends per foundation and correct positioning. The foundation for Pad Mounted Controller Cabinet shall be of sufficient size so that there is a minimum of 3" of clearance from the outside edge of cabinet to the outside edge of the foundation on any side. The contractor shall ensure a water-tight seal between the controller cabinet and the foundation by caulking, except for V-groove.


**WORKING AREA SLAB:** The materials and preparation of this slab shall be as approved by the Engineer in the field.

**TRANSFORMER & FEED POINT CABINET FOUNDATION PAD MOUNTED:** The foundation shall have a wood float finish. All conduits shown shall be installed. Conduit that is not used at this time shall be plugged with an expandable plug.

**FEED POINT CABINET FOUNDATION PAD MOUNTED:** The foundation shall have a wood float finish. All conduits shown shall be installed. Conduit that is not used at this time shall be plugged with an expandable plug.


LIGHT & SIGNAL FOUNDATION TABLE	
FOOTING DEPTH (ft)	LONGITUDINAL REINFORCING
≤ 12	8 - #5
13 - 14	8 - #6
15 - 16	8 - #7
17 - 19	8 - #8

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION		This document was originally issued and sealed by Terrence R. Udland Registration Number PE- 2674 , on 6/15/10 and the original document is stored at the North Dakota Department of Transportation
6-15-10		
REVISIONS		
DATE	CHANGE	




CONTROLLER CABINET FOUNDATION PAD MOUNT

The Controller Cabinet Foundation shall be bid as Concrete Foundation - Traffic Signals.




TRANSFORMER & FEED POINT  
CABINET FOUNDATION PAD MOUNT

The Transformer & Feed Point Cabinet Foundation Pad Mount shall be bid as Concrete Foundation ~ Feed Point ~ Type A.




The Working Area Slab shall be installed where shown on the plans and shall not be bid separately but shall be included in the price bid for Concrete Foundation - Traffic Signals.




FEED POINT CABINET  
FOUNDATION PAD MOUNT

The Feed Point Cabinet Foundation Pad Mount shall be bid as Concrete Foundation ~ Feed Point ~ Type B.



ANCHOR BOLT DETAIL





LIGHT & SIGNAL STANDARD FOUNDATION


An anchor bolt cage shall be shop fabricated from #6 bar circle or 3/4" square stock or approved equal welded to the inside of anchor bolt to hold alignment.




FEED POINTS  
(ROADWAY LIGHTING)



Plan  
Transformer and Feed Point Cabinet Pad Mounted



Plan  
Elevation  
Feed Point Cabinet Pad Mounted




Feed Point Type IV

Provide Type I feed point similar to Type IV, except with one electrical circuit, one 50 Amp - 2 pole breakers, and one lighting relay, normally open.

Provide Type II feed point similar to Type IV, except with two electrical circuit, two 50 Amp - 2 pole breakers, and two lighting relays, normally open.



Provide Type III feed point similar to Type IV, except with three electrical circuits, three 50 Amp - 2 pole breakers, and three lighting relays, normally open.

(A) Install when festoon circuit is required.



Feed Point Pole Mounted

- Notes:
1. Photo Cell: Furnish and install the photoelectric cell. Face photo lens north.
  2. Meter Socket: Install meter socket and trim if the meter is required by local Utility Company. Meter furnished and installed by Utility Company.
  3. Pole Mounted Cabinet: Provide cabinet with lock drip shield, factory installed steel backing, stainless steel hardware, and side hinge door. Shop coat cabinet with one coat of primer and two coats of exterior gray enamel.
  4. Wood Pole: Provide minimum 20' Class VII full length penta pressure treated wood pole. (if required, see layout sheets)
  5. Pad Mounted Cabinet: Provide 56" high x 26" wide x 14" deep weatherproof cabinet. Minimum 12 gauge steel or aluminum with provisions for padlock. Provide steel cabinet with one coat of primer and two coats of exterior dark green enamel.
  6. Grounding Grid: Provide grounding grid with a maximum ground resistance of 25 ohms, using one or more 5/8"x10' copperweld ground rods in parallel or series at two corners. Provide a minimum distance between ground unit assemblies of 6'0".
  7. Meter Location: Do not mount the meter (if required) on the same side of the cabinet as the photo cell.









Conduit Standoff Bracket  
Omission of conduit standoff brackets allowed when not required by local utility company.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-8-13	
REVISIONS	
DATE	CHANGE
7-8-14	Revised note 3.
10-17-17	Updated to active voice.



This document was originally issued and sealed by  
Roger Weigel,  
Registration Number  
PE- 2930,  
on 10-17-2017 and the original document is stored at the  
North Dakota Department  
of Transportation





PULL BOX DETAILS



Cast Iron Frame and Cover





Section Cover



Polymer Concrete Pull Box

Note: Polymer concrete reinforced by a heavy weave fiberglass




Polymer Concrete Pull Box Notes:

1. Place top of pull box flush with surfaced area and approximately one inch above earth or sodded areas on level surfaces.
2. Provide at least one knockout per side in pull box.
3. Provide Polymer Concrete pull box meeting Tier 22 as per ANSI / SCTE 77.

PVC Pull Box Notes:

1. Attach split 24" nominal diameter PVC cover support ring with four 3/8" dia. x 2" long stainless steel hex head bolts with nuts at 90 degrees apart.
2. Two type 2 shoulder eye bolts, 3/8" dia. x 1 1/4" shank length with hex nuts 180 degrees apart (for lifting pull box and supporting electric cable).
3. Four 1/4" x 1 1/4" long galvanized lag screws. Screw assembly together.
4. Attach split 24" nominal diameter PVC cover support extension ring with four 3/8" dia. x 2" long stainless steel hex head bolts with nuts at 90 degrees apart.
5. Bolt assembly together.
6. Size conduit holes in barrel section a maximum of 1" larger than size of conduit being used.
7. After pull box and conduit installation, make inside walls and cover water tight to the satisfaction of the Engineer.
8. PVC pipe to meet requirements of ASTM F679T-1 or equal.
9. Use austenitic stainless steel hex head bolts and nuts. Galvanize other fasteners as per AASHTO M-232.
10. Coat concrete cover on top and sides with an approved epoxy coating. Apply light gray, clear, or neutral color epoxy protective coating as recommended by the manufacturer. Clean the surfaces of concrete receiving the epoxy protective coating by wire brush and dry before application.
11. Cast Iron Cover castings shall be gray iron as per AASHTO M 105, Class 35B.



Typical Pull Box in Rural Section


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-8-13	
REVISIONS	
DATE	CHANGE
7-8-14 10-17-17	Added Note 3 Updated to active voice.

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 10-17-2017 and the original document is stored at the North Dakota Department of Transportation




LIGHTING AND SIGNAL DETAILS

D-770-4




Surface Patch Details

Note: Saw cut trenches. Use PCC pavement for replacement concrete with the coarse aggregate gradation, maximum size and method of curing as approved by the Engineer. Immediately prior to pouring replacement concrete, paint all surfaces with an approved epoxy compound.




Light Standard Numbering

Note: On the roadway side of each light standard, stencil the pole number using black paint or an adhesive coated plastic such as Scotchcal by 3M or as approved by the Engineer. See layout sheets for pole numbers.




Emergency Vehicle Detector Detail




Alternate Emergency Vehicle Detector Detail (adjustable)


- Notes:
1. Use Type X Unilet with two Par lamp holders and lamps for Two-way Detectors. (one in each direction).
  2. Plug unused end of One-way Detector with metal pipe plug.
  3. Rotate detector lens to face direction of travel on Two-way Detectors.



Bridge Mounted Conduit Hanger




Curb Mounted Conduit




Cable Trench


Note: Sod entire area disturbed by trenching, unless directed otherwise by the Engineer.



Terminal Block Detail




Terminal Block (rigid mounted)




Revise Concrete Foundation

Note: Jackhammer or drill to remove material and provide a location for conduit. Make opening no larger than necessary. Place conduit, fill with concrete and finish foundation to original appearance.



Plan View




Conduit Placement under Railroad Tracks



NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-8-13	
REVISIONS	
DATE	CHANGE
10-17-17	Updated to active voice.

This document was originally issued and sealed by  
Roger Weigel,  
Registration Number  
PE-2930,  
on 10-17-2017 and the original document is stored at the  
North Dakota Department  
of Transportation







Light Standard Details




Truss Mast Arm



Top View




Steel Base Detail




Keeper Plate Detail (A)

(A) ASTM A446 Grade "A" 28 gauge keeper plate on top of middle flat washer. Galvanize Keeper plate after fabrication.




Slip Base Placement Detail



Anchor Bolt Detail

Multi-Directional Slip Base



Pole Wiring Diagram

Receptacle Mounting Detail (B)

(B) Mount receptacle on side of pole that faces the street. Install Festoon Receptacle only when specified in the plans.

Notes:

Light Standard Locations: The minimum offset distance from the curb face is 3 feet. Offset light standards at least 3 feet in urban areas and where speeds are less than 30 mph. Where speeds are 30 mph or more, place light standards at least 16 feet from the driving lane.

Steel Standards: Touch up marred or scratched areas after erection.

Luminaire: Use internal ballast-constant wattage 120x240 voltage. See layout sheets for type of luminaire, wattage, I.E.S. distribution, and operating system.



Fusing: Fusing in base, see specifications.

Slip Base Bolt Torque Procedure:  
1. Tighten all bolts the maximum possible with 12" to 15" wrench to bed washers and to clean bolt threads, then loosen.  
2. Retighten bolts with a systematic order to prescribed torque.  
3. Loosen each bolt and retighten to prescribed torque in the same order as initial retightening.  
4. Burr threads of junction with nut using center punch to prevent nut loosening.





NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
10-8-13	
REVISIONS	
DATE	CHANGE
10-17-17	Updated to active voice.

This document was originally issued and sealed by  
Roger Weigel,  
Registration Number  
PE-2930,  
on 10-17-2017 and the original document is stored at the  
North Dakota Department  
of Transportation





Alternate Signal Standard Base  
For use only with Type V, VI, and VII signal standards.



- (A) Use positioning of the sign, pushbutton, and direction of arrow to clearly indicate which crosswalk is actuated by the push button. Place type of sign based on the jurisdiction in which placed.
- (B) Attach sign to post using rust resistant 0.081 aluminum bracket and banding. See Standard Signs book for dimensions and legend series. See plans for type of sign.


Notes:

Signal Heads: See traffic signal layout for correct mounting position, number, size, and arrangement of lenses.

Steel Standards: Place signal standard a minimum of 3 ft. from the face of the curb to center of signal standard, unless shown otherwise on layout sheets.

Paint: See note sheet for required color of paint.

Transformer Base: In lieu of transformer base use alternate signal standard base.




NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
11-14-13	
REVISIONS	
DATE	CHANGE
10-17-17	Updated to active voice.


This document was originally issued and sealed by  
Roger Weigel,  
Registration Number  
PE-2930,  
on 10-17-2017 and the original document is stored at the  
North Dakota Department  
of Transportation




TRAFFIC SIGNAL STANDARDS  
(MAST ARM TYPE)




Anchor Bolt Detail




Twin Mast Arm



Truss Type Mast Arm



3/4" Top Plate



3/4" Bottom Plate

Detail A


Note: In lieu of the plate type connection, use a telescoping clamp type extension.

Combination Signal and Light Standard			
Signal Standard Type	Luminaire Mounting height (ft)	Install Light Standard Extension and Luminaire	Luminaire Mast Arm
A	30	yes	single
B	30	(A)	single
C	40	yes	single
D	40	(A)	single
E	30	yes	twin
F	30	(A)	twin
G	40	yes	twin
H	40	(A)	twin
I	50	yes	single
J	50	yes	twin

(A) Install the light standard extension for these signal standards at a later date under a separate contract.

Notes:

- Light standard extension: Mast arm is 6 ft. unless otherwise noted on the plans. Use light standard extension galvanized in accordance with ASTM A 123.
- Luminaire: Use internal ballast - constant wattage 120 x 240 voltage luminaires. See layout sheets for type of luminaire, wattage, and I.E.S. distribution.
- Signal head: See Traffic Signal Layout for correct mounting position, number, size, and arrangement of lenses. Place mast arm mounted signal heads with a clearance between 17 ft. and 19 ft. from the centerline of the roadway to the bottom of signal heads.
- Multi-sided poles: Provide a means, other than friction, that will not allow the mast arm to be rotated by wind forces. Fabricate the pole so the mast arm is rotatable. This feature to be as approved by the Engineer.
- Transformer base: In lieu of the transformer base, use the alternate signal standard base.




Section A-A

Section B-B

Alternate Signal Standard Base

Note: For use with Type IV and combination signal standards only



Signal Standard Minimum Clearance Detail

Type IV Signal Standard


(B) On combination signal and light standards Type B, D, F, and H, and on all Type IV signal standards install a suitable pole cap as per manufacturer's specifications.

NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
11-14-13	
REVISIONS	
DATE	CHANGE
10-17-17	Updated to active voice.

This document was originally issued and sealed by  
Roger Weigel,  
Registration Number  
PE-2930,  
on 10-17-2017 and the original document is stored at the  
North Dakota Department  
of Transportation




TRAFFIC SIGNAL HEAD MOUNTING




Light Standard Mounted  
Pedestrian Signal Head (A)




Type II  
Pedestal Mounted - Pedestrian (A)




Type IV  
Post Mounted - Vehicular  
Post Mounted - Pedestrian (A)




Type V  
Post Mounted - Vehicular  
Post Mounted - Pedestrian (A)




Type VI  
Post Mounted - Vehicular  
Post Mounted - Pedestrian (A)




Type VII  
Post Mounted - Vehicular  
Post Mounted - Pedestrian (A)




Side View  
Mid-Span Mounted and  
Mast Arm Rigid Mounted  
Signal Heads




Mast Arm Signal  
Head Bracket



Plan Layout  
(typical)  
  
Note: Place signal heads behind the face of the curb.




Front View




Isometric View

End Mounted and Mast Arm Rigid Mounted  
Signal Heads



Front View



Isometric View

- Notes:
- Reinforcing Plates:** Install reinforcing plates where mounting hardware attaches to signal heads when using polycarbonate signal heads. Where a plumbizer is used, place reinforcing plates on each side of the plumbizer.
- Clearance:** Place the bottom of post or pedestal mounted vehicular signal heads a minimum of 10 ft. and pedestrian signal heads a minimum of 8 ft. above the ground line or sidewalk.
- Signal Heads:** See traffic signal layout for correct mounting position, numbers, size, and arrangement of lenses.
- Pole Clamps:** A pole plate with suitable banding material, as approved by the Engineer, is allowed in place of pole clamps. Where traffic signal heads and pedestrian signal heads are mounted one above the other, one pole clamp assembly is allowed.
- Paint:** Paint signal housing yellow and backplates dull black. Paint pole clamps and signal head mounting hardware the same color as the signal standard shaft.
- When pedestrian heads are light standard mounted, paint the lower 12 ft. the same color as the other traffic signal standards.
- Mounting Details:** All signal heads shown viewed from direction of travel.


NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
11-14-13	
REVISIONS	
DATE	CHANGE
7-8-14 10-17-17	Added reinforcing plate note Updated to active voice.

This document was originally  
issued and sealed by  
Roger Weigel,  
Registration Number  
PE-2930,  
on 10-17-2017 and the original  
document is stored at the  
North Dakota Department  
of Transportation



FLASHING BEACON

D-772-7



NORTH DAKOTA DEPARTMENT OF TRANSPORTATION	
2-28-14	
REVISIONS	
DATE	CHANGE
7-8-14	Span wire size and sag.
10-17-17	Updated to active voice.

This document was originally issued and sealed by Roger Weigel, Registration Number PE-2930, on 10-17-2017 and the original document is stored at the North Dakota Department of Transportation