

1. Report No. ND 94-05	2. Report Date April 1997	3. Contract No. N/A	4. Project No. IM-8-094(005)331
5. Title and Subtitle  Moisture Sensors in a Base and Subbase		6. Report Type <i>Click on link to open report</i>  Work Plan <input type="checkbox"/> Construction <input type="checkbox"/> <b>Evaluation</b> <input checked="" type="checkbox"/> Final <input type="checkbox"/>	7. Project No.  8. Project No.  9. Project No.  10. Project No.
11. Author(s)/Principle Investigator(s) Jeff M. Richter			
12. Performing Organization Name and Address NDDOT M+R <input checked="" type="checkbox"/> North Dakota DOT NDDOT OTHER* <input type="checkbox"/> Materials and Research Division NDSU <input type="checkbox"/> 300 Airport Road UND <input type="checkbox"/> Bismarck ND 58504-6005 UGPTI <input type="checkbox"/> OTHER* <input type="checkbox"/> *see supplementary notes		13. Sponsoring Agency Name and Address  North Dakota DOT Materials and Research Division 300 Airport Road Bismarck ND 58504-6005	
14. Supplementary Notes			
15. Abstract <b><u>Purpose and Need</u></b> Historically, bases and subgrade that have high moisture contents reduce the overall life of the pavement structure leading to increased costs associated with increased maintenance. There is a need to determine if the moisture content in the base and subgrade can be reduced by using permeable base with edge drains.  <b><u>Objective</u></b> The objective of this study is to determine the effectiveness of a permeable base in reducing the moisture levels in the base and subgrade.  <b><u>Scope</u></b> The scope of this experimental project is to compare the moisture levels in the salvaged base beneath a permeable base, in a dense graded base, and in the subgrade. These sections are beneath a Portland Cement Concrete (PCC) pavement roadway surface. The project location is on Interstate 94 in the eastbound lane near Casselton, ND. The project will evaluate the moisture levels at the sensor locations. The project will be evaluate for a period of five-years on an annual basis.  <b><u>Summary</u></b> These results are inconclusive at this time. It appears that at joint locations the drainable base is not effective or is only marginally effective in reducing the moisture content in the base material. It is however effective in reducing the moisture content of the subgrade at the joint locations. The mid-panel locations appear to show that the dense graded base is more effective than the drainable base, however the moisture content in the subgrade shows the drainable base to be more effective. The project was terminated due to a traffic accident which damaged one of the multiplexer enclosures.			
16. Key Words  Base Subbase Moisture Sensors Permeable Base	17. Distribution Statement No restrictions. This document is available to the public from:  North Dakota Department of Transportation Materials and Research Division: 300 Airport Road Bismarck ND 58504-6005  Office: (701) 328-6900		18. No. of Pages 29  19. File type/Size  Pdf / 1.0 MB

**NORTH DAKOTA  
DEPARTMENT OF TRANSPORTATION**

# **MATERIALS AND RESEARCH DIVISION**

**Experimental Study NDEP 94-05**

**Moisture Sensors in a Base and Subbase**

**Second Annual Report**

**Project IM-8-094(005)331**

**April 1997**

**Prepared by**

**NORTH DAKOTA DEPARTMENT OF TRANSPORTATION**

**BISMARCK, NORTH DAKOTA**

**Website: <http://www.discovernd.com/dot/>**

**DIRECTOR**

**Marshall W. Moore**

**MATERIALS AND RESEARCH DIVISION**

**Ron Horner**

EXPERIMENTAL PROJECT REPORT

EXPERIMENTAL PROJECT	EXPERIMENTAL PROJECT NO.					CONSTRUCTION PROJ NO		LOCATION	
	1	STATE ND	YEAR 94	-	NUMBER 05	SURF	8	IM-8-094(005)331	2 Cass County
	EVALUATION FUNDING						NEEP NO.	PROPRIETARY FEATURE?	
	48	1	HP&R		3	DEMONSTRATION		Yes	
		2	CONSTRUCTION		4	IMPLEMENTATION	49	51 No	
SHORT TITLE	TITLE 52 Moisture Sensors in a Base and Subbase								
THIS FORM	DATE	MO.	YR.	REPORTING					
	140	0	4	-	9	7	1	INITIAL	2 X ANNUAL
KEY WORDS	KEY WORD 1				KEY WORD 2				
	KEY WORD 3				KEY WORD 4				
	UNIQUE WORD				PROPRIETARY FEATURE NAME				
CHRONOLOGY	Date Work Plan Approved		Date Feature Constructed:		Evaluation Scheduled Until:		Evaluation Extended Until:		Date Evaluation Terminated:
	04-94		09-94		08-99				
	277		281		285		289		293
QUANTITY AND COST	QUANTITY OF UNITS			UNITS				UNIT COST ( <i>Dollars, Cents</i> )	
	297			305				306	
	1 LIN. FT			5 TON		25579.20			
	2 SY			6 LBS					
	3 SY-IN			7 EACH					
	4 CY			8 X LUMP SUM					
AVAILABLE EVALUATION REPORTS	X CONSTRUCTION			X PERFORMANCE			FINAL		
	315								
EVALUATION	CONSTRUCTION PROBLEMS				PERFORMANCE				
	1	X	NONE		1	EXCELLENT			
	2		SLIGHT		2	GOOD			
	3		MODERATE		3	SATISFACTORY			
	4		SIGNIFICANT		4	MARGINAL			
APPLICATION	1	ADOPTED AS PRIMARY STD.			4	PENDING	<i>(Explain in remarks if 3, 4, 5, or 6 is checked)</i>		
	2	PERMITTED ALTERNATIVE			5	REJECTED			
REMARKS	321 Results inconclusive. It appears that at joint locations the drainable base is not effective or is only marginally effective in reducing the moisture content of the subgrade at the joint locations. The mid-panel locations appear to show the dense graded base is more effective than the drainable base, however, the moisture content in the subgrade shows the drainable base to be more effective.								
									700

EXPERIMENTAL

**Moisture Sensors in a Base and Subbase**

**SECOND ANNUAL REPORT**

IM-8-094(005)331

MARCH 1997

Written by  
Jeff M. Richter

## **Disclaimer**

The contents of this report reflect the views of the author or authors who are responsible for the facts and the accuracy of the data presented herein. The contents do not reflect the official views of the North Dakota Department of Transportation or the Federal Highway Administration. This report does not constitute a standard, specification, or regulation.

## TABLE OF CONTENTS

<b>PURPOSE</b> .....	1
<b>SCOPE</b> .....	1
<b>LOCATION</b> .....	1
<b>DESIGN</b> .....	1
Figure 1 Drainable base .....	1
Figure 2 Dense Graded base .....	2
Figure 3 Sensor Location Joints .....	3
Figure 4 Sensor Location Mid-Panel .....	3
<b>CONSTRUCTION</b> .....	4
<b>EVALUATION</b> .....	4
Graph 1 Moisture %'s in base under Joints 1995 .....	5
Graph 2 Moisture %'s in base under Joints 1996 .....	6
Graph 3 Moisture %'s in base under Mid-Panel 1995 .....	7
Graph 4 Moisture %'s in base under Mid-Panel 1996 .....	8
Graph 5 Moisture %'s in subgrade 1995 .....	9
Graph 6 Moisture %'s in subgrade 1996 .....	10
<b>SUMMARY</b> .....	11-14
Figure 5 Average Moisture Drainable Base @ Joint .....	12
Figure 6 Average Moisture Dense Graded Base @ Joint .....	12
Figure 7 Average Moisture Drainable Base @ Mid-Panel .....	13
Figure 8 Average Moisture Dense Graded Base @ Mid-Panel .....	13
<b>APPENDIX A:</b> .....	Construction Plans

# MOISTURE SENSORS IN A BASE AND SUBBASE

Project IM-8-094(005)331  
NDEP94-05

## PURPOSE:

The purpose of this study is to determine the effectiveness of a permeable base in reducing the moisture levels in the base and subgrade.

## SCOPE:

The scope of this experimental project is to compare the moisture levels in the salvaged base beneath a permeable base, in a dense graded base, and in the subgrade. These sections are beneath a Portland Cement Concrete (PCC) pavement roadway surface.

## LOCATION:

This project is located in the eastbound lanes of Interstate 94 in Cass County near Casselton, North Dakota. The moisture sensors are located at station 880+98.4, station 881+35.9, station 891+52.5, and station 891+90. See appendix A.

## DESIGN:

The design called for placing three moisture sensors in two different roadway sections. The first section consists of four inches of a drainable base and eight inches of salvaged bituminous base placed on the subgrade as shown in figure 1.





Figure 1

The second section consists of six inches of dense graded base placed on the subgrade as shown in figure 2 below. Each section called for placement of moisture sensors at two locations. The roadway section with a drainable base called for placing two moisture sensors in the salvaged base and one sensor in the subgrade as shown in figure 1. The roadway section without the permeable base called for placing two moisture sensors in the dense graded base and one sensor in the subgrade as shown in figure 2.



*Stations: 891+52.5 Rt. and 891+90 Rt.*

**Figure 2**

The sensors were located below a skewed transverse joint and below the midpoint of a concrete panel for each type of base course as shown in figures 3 and 4.

It is anticipated that the joint sealant will eventually lose its sealing capacity and allow moisture to readily enter the base material below the joints. It is then anticipated that the permeable base will remove the excess moisture while the dense graded base will allow the moisture to accumulate causing the base to lose its support capability.

The amount of moisture entering the base course at the midpoint of the PCC panels will be dependent on the lateral movement of the moisture in the base and capillary movement of moisture from the subgrade.




Figure 3




Figure 4

## **CONSTRUCTION:**

Installation of the moisture sensors was performed by Fargo Electric from Fargo, North Dakota in September 1994. The installation was constructed to plan without problem in the following sequence:

- 1) Installation of cabinet concrete footings
- 2) Trenching for conduit and sensors
- 3) Installation of sensors and conduit
- 4) Compaction of trench fill
- 5) Mounting of controlled environment cabinets
- 6) Installation of multiplexer control panel
- 7) Tagging and recording cables from sensors

## **EVALUATION:**

The graphs on the following pages represent the monthly average of the data collected from the moisture sensors. Graph 1 and Graph 2 include data from the sensors in the salvaged base and in the dense graded base located at the transverse joints. Graph 3 and Graph 4 include data from the sensors in the salvaged base and in the dense graded base located at the midpoint of the PCC pavement panels. Graph 5 and Graph 6 represent data from the sensors located in the subgrade for all locations.



There is no data available for the month of June 1995 for any of the sensors. There was erroneous data from the sensors in the subgrade under the mid-panel dense graded base during May, July, August, and September of 1995, which was not included in graph 5. There was also erroneous data from the sensors in the subgrade under the transverse joint dense graded base during May and August of 1995 which was not included in graph 5. The data for 1996 includes only the months of April, May, June, and July. This is due to problems collecting the data between January and April of 1996. It was also decided to change the evaluation parameters of the study to include data from July to July for the next comparisons.

# SENSORS LOCATED AT TRANSVERSE JOINT

WITHIN BASE COURSE

1995

%MOISTURE



\* Below Permeable Stabilized Base



Graph 1

# SENSORS LOCATED AT TRANSVERSE JOINT

WITHIN BASE COURSE

1996

%MOISTURE



\* Below Permeable  
Stabilized Base



Graph 2

# SENSORS LOCATED AT MIDPANEL

WITHIN BASE COURSE

1995

%MOISTURE



\* Below Permeable  
Stabilized Base



Graph 3

# SENSORS LOCATED AT MIDPANEL

WITHIN BASE COURSE

1996

%MOISTURE





Graph 4

# SENSORS IN SUBGRADE

1995

%MOISTURE





\* Below Permeable Stabilized Base

Graph 5

# SENSORS IN SUBGRADE

1996

%MOISTURE



Graph 6

## **SUMMARY:**

**A comparison of sensor readings on Graphs 1 and 2 show that since construction, the top of the salvaged base course (Figure 5) averages 22% moisture at the joint location. The bottom of the salvaged base course (Figure 5) at the same location averages 35% moisture. Graphs 1 and 2 also show that the moisture content of the top of the dense graded base course (Figure 6) has an average of 27% moisture while the bottom of the dense course (Figure 6) has an average moisture content of 23%.**

**A comparison of sensor readings on Graphs 3 and 4, where the sensors are located at mid-panel, indicate that the top of the dense graded base course (Figure 7) has an average moisture of 18% at mid-panel and the bottom of the dense graded base course (Figure 7) has an average of 19% moisture. The graphs also show that the top of the salvage base course (Figure 8) has an average of 27% moisture while the bottom (Figure 8) has an average of 25% moisture.**

**Graphs 5 and 6 show the moisture contents in the subgrade below a transverse joint (Figure 5) to be 24 % below the salvage base and 31% below the dense graded base (Figure 8). The mid-panel moisture contents are 29% below the salvage base (Figure 6) and 38% below the dense graded base (Figure 7). A comparison of these moisture contents is shown in the following diagrams.**

Figure 5




Figure 6




Figure 7





Figure 8



**These results are inconclusive at this time. It appears that at joint locations the drainable base is not effective or is only marginally effective in reducing the moisture content in the base material. It is however effective in reducing the moisture content of the subgrade at the joint locations.**

**The mid-panel locations appear to show that the dense graded base is more effective than the drainable base, however the moisture content in the subgrade shows the drainable base to be more effective.**

## **APPENDIX A**

DESIGN DATA			
Traffic	Average Daily		Est Month
Current 1994	Pass. 3,455	Trucks 700	total 4,155
Forecast 2014	Pass. 5,000	Trucks 1,050	total 6,130
Minimum Sight Dist. for:	Stopping	625 FT	Design Speed
			70 MPH
Full Control of Access			
No Point of Access Other than at Interchange Ramps			

JOB# \_\_\_\_\_

FEDERAL REGION	STATE	PROJECT NO.	SHEET NO.
8	ND	IM-8-094(005)331	1

# NORTH DAKOTA DEPARTMENT OF TRANSPORTATION

IN CASS COUNTY  
FEDERAL AID PROJECT IM-8-094(005)331  
PCC RECYCLING & SPS-2 EXPERIMENTAL SECTIONS


**GOVERNING SPECIFICATIONS:**  
Standard Specifications adopted by the North Dakota Department of Transportation September 1992. Standard Drawings currently in effect and other Contract Provisions submitted herein.

LENGTH OF PROJECT  
Miles-Cross 7.510      Miles-Net 7.449

0.061 M deducted for bridges.



BEGIN Sta. 855+48.4  
Section 11, Twp 139 N,  
Rge 52 W




A-1

PAVING SECTION	<i>Benjamin P. ...</i>
URBAN SECTION	
TRAFFIC SECTION	<i>Acroy, St. ...</i>
RURAL SECTION	
RECOMMEND APPROVAL	<i>2-1-1994</i>
DESIGN ENGINEER	<i>[Signature]</i>

U.S. DEPARTMENT OF TRANSPORTATION FEDERAL HIGHWAY ADMINISTRATION	APPROVED DATE <i>2-1-94</i>	
	APPROVED <i>Ray Zink</i> DIRECTOR OF HIGHWAYS AND ENGINEERING	
DIVISION ADMINISTRATOR	DATE	NORTH DAKOTA DEPARTMENT OF TRANSPORTATION

SCOPE OF WORK

FINVA REGION 8	STATE N.D.	FED. AID PROJ. NO. 1H-8-094(005)331	SHEET NO. 3
-------------------	---------------	--	----------------



**LEGEND**  
 SPS SECTIONS  
 RECYCLED PCC PAVI

A-2

**NOTES**

990 The contractor shall furnish the Department with a Pearpoint Color  
 P01 Flexiprobe System consisting of the following:

Quantity	ID #	Description
1 EA	IKU2207101	Camera Control Unit
1 EA	IKC0504901	5 Meter 16 ft Link Cable
1 EA	IKU1321201	T Piece
1 EA	IKI100001	Metal Coller
1 EA	IKC0505601	Rod 320'
1 EA	HI2662001	6W 44mm Lighthouse
1 EA	IKC2179801	Plastic Sleeve
1 EA	IKC2174001	Camera Color
1 EA	PP165101	Spring Centering Device
1 EA	AIQRD40051	Radio Sonde Receiver
1 EA	HI2662201	Lamp Replace PCB Kit
1 EA		4-Head VCR W/Audio & Video-In Capabilities
1 EA		Honda Generator 650 Watt

The specified system shall become the property of the Department.  
 (NOTE: Northern Water Works Supply is the only licensed dealer of the Pearpoint flexible video system in North Dakota.)

The unit price bid for "Pearpoint Color flexiprobe System" shall include all costs to provide this system.

990 The contractor shall furnish and install a Moisture Sensor System  
 P02 consisting of the following:

Soilmoisture Equipment Corporation		
Quantity	Product No.	Description
2	6050X1	Trace System 1
12	6005L2	Durable Waveguide (2 Meter Cable)
12	6006L20	Extension Cable (20 Meters)
2	6021C16	TDR Switching Board (16 Channel)
1	6022	Multiplexer Control Board

Hennessy Products		
Quantity	Product No.	Description
2	L5583017A13R	
2	231633	Shelf Kit
2	240627	Fan Thermostat
2	240625	300 Watt Heat Kit
2		Insulation Adder

The specified system shall become the property of the Department. The contractor shall install the Moisture Sensor System according to the manufacturer's recommendations. A representative from the Soilmoisture Equipment Corporation shall be present during installation of the equipment. The contact person is Richard White (phone number (805)964-3525.)

The contractor shall take the steps necessary to protect the sensors once they are in place. Damaged sensors shall be replaced at the contractor's expense.



The cables running from the sensors to the cabinet shall be placed in 1 inch rigid conduit.

The contractor shall give 48 hours advance notice of installation of sensors to Cliff Kuntz of the WDDOT (phone number (701)221-6910.)

The unit price bid for "Moisture Sensor System" shall include all costs to provide and install this system.


# RESHAPING ROADWAY

FED. AID PROJ. NO.	STATE	FED. AID PROJ. NO.	SHEET NO.
8	N.D.	14-8-894(005)331	18




A-4

TYPICAL SECTION



A-5


WIDTH	QUANTITY	UNIT	APPROXIMATE QUANTITIES
556'		N Gal	482 N Gal. Water for Dust Palliative and Subgrade Prep + 48 Gal/Ton of Salvaged Base Course
5025'	12696	ton	Salvaged Base Course
44'	4839	ton	Permeable Asphalt Stabilized Base
	121	ton	AC 20 Asphalt Cement
	18180	LF	Edge Drains
	546	LF	Ductile Pipe
38'	21491	SY	10' Non-Reinforced RPCC Pavement
	1412	ton	Portland Cement
	332	ton	Flyash
24'	8136	LF	Beveled Contraction Joint Assembly
385'	13852	LF	Contraction Joint Silicone Seal
44'	4977	Gal	MC-70 or 250 Lq. Asph for Prime Coat @ .20 Gal/SY.



CROSS SECTION OF PCC PAYEMENT SLAB (TANGENT)

LEVELER, JIMMIE PLAIN, PCC, PVM1  
 SIBBIE ROADWAY  
 SECTION 1  
 Sta 002+70.4 to Sta 095+53.4

FYVA BLG 0	STATE N.D.	FED. AID PROJ. NO. W-094-01005330	SHEET 22
---------------	---------------	--------------------------------------	-------------



A-6

DEPTH	QUANTITY	UNIT	APPROPRIATE QUANTITIES
			121 M Gal. Water for Best Practice and Subgrade Prep. + 20 Gal/Ton of Dense Graded Base Course
42'	1930	Ton	Dense Graded Base Course
30'	5303	SY	11" Non-Reinforced PCC Pavement - CLASS AE
30.5'	3272	LF	Contraction Joint Silicone Seal
24'	2040	LF	Doweled Contraction Joint Assembly




TABLE OF VARIATION FOR SECTION 1 THRU SECTION 17


TYPICAL SECTION	PCC PVHI DEPTH (INCHES)	PCC PVHI WIDTH (FEET)	14 DAY FLEXURAL STRENGTH (PSI)	BASE TYPE	JOINT ORIENTATION	TRANSVERSE JOINT SPACING (FEET)	TYPE OF LOAD TRANSFER DEVICE
1	11	38	*	CL 5 AGGR	SKEVED	15	DOVELS
2	11	24	550	CL 5 AGGR	SKEVED	VARIABLE	NONE
3	11	24	550	CL 5 AGGR	90°	15	DOVELS
4	11	28	900	CL 5 AGGR	90°	15	DOVELS
5	8	24	900	CL 5 AGGR	90°	15	DOVELS
6	8	28	550	CL 5 AGGR	90°	15	DOVELS
7	8	28	550	LCB	90°	15	DOVELS
8	8	24	900	LCB	90°	15	DOVELS
9	11	28	900	LCB	90°	15	DOVELS
10	11	28	550	LCB	SKEVED	VARIABLE	NONE
11	11	24	550	LCB	90°	15	DOVELS
12	11	24	550	PASB	90°	15	DOVELS
13	11	24	550	PASB	SKEVED	VARIABLE	NONE
14	11	38	*	PASB	SKEVED	15	NONE
15	11	28	900	PASB	90°	15	DOVELS
16	8	28	550	PASB	90°	15	DOVELS
17	8	24	900	PASB	90°	15	DOVELS

\* Class AE as per NDDOT Specifications.

A-7

PAYMENT DETAILS FOR SURF TEST SECTIONS

FIRMA REGION	STATE	FED. AID PROJ. NO.	SHEET NO.
8	N.D.	1H-8-094(005)331	40



8-A

LEGEND

- PCC- Portland Cement Concrete
- PASB- Perm Asph Stabilized Base
- LCB- Lean Concrete Base
- DGB- Dense Graded Base
- RPCC- Recycled PCC
- SB- Salvaged Base










- Tied Longitudinal Joint
- Edge of Hot Bit Pmnt
- Edge of PCC Slab
- Transition

	Paid for as 11' PCC Pmnt	
10' RPCC	PCC	11' PCC
4' PASB		6' DGB
8' SB	DGB	

SECT. A-A

# JOINT DETAILS

FVMA REGION	STATE	FED. AID PROJ. N.O.	SHEET NO.
8	N.D.	N-0-09(1005)330	40



A-9